

	£	s	d	£	s	d
Brought forward, £	67	7	2	14	0	0
<i>Carpenter Work—</i>						
Retort house, roof of iron						
Apparatus, shed roof, 371 square yards	64	18	6			
at 3s 6d						
Manager's and counting house roof	115	10	0			
660 square yards						
Gas holder roof, bound work, 848 do	296	16	0			
at 7s						
346 running feet of gas holder beams	25	19	0			
12 ins. x 8 ins. at 1s 6d	12	10	0	515	13	6
10 sky lights						
This item rated at Glasgow prices.						
Inside finishing of manager's house						
and counting house						
Furniture for counting house						
Workmen's Tools, main gate						
Doors and Windows about the prop'ty				215	16	0
This item rated at Glasgow prices						
<i>Freight—</i> Iron work, say 500 tons						
Bricks, lime, &c. 200 "						
700 tns. at 12s				420	0	0
<i>Superintendent</i> from Britain to look						
after the work getting made and for-						
warded from Britain, and afterwards						
seeing its erection in Halifax and						
superintending the work for say 3						
months after the Gas has been made						
and distributed through the mains,						
say 12 or 15 months—say				280	0	0
	£	8204	3	6		

The Committee having received, per steamer Britannia, the foregoing Report and Estimate, beg leave to state for the information of the present Stockholders, and those persons who are favourable to the project of lighting the Town with Gas, that they have carefully examined the documents sub-