

road crossings at all times, a safe crossing is in good order; that the contractor takes all reasonable precaution to protect the public from injury due to his operations, and will hold the contractor to a strict account in this particular matter.

CLEARING.

68. The specifications must be closely observed; dead or leaning trees within the limits called for in the specifications must be cut down and removed, the right of way must be left clear. Great care must be taken in burning brush to see that all the Provincial Fire Regulations are observed, and every precaution must be insisted upon to insure the protection of the forest from fires.

GRUBBING.

69. See that all grubbing is burned up and that the specifications are strictly adhered to. Grubbing will not be estimated in cuttings over four feet in depth (see Clause 11 of specifications).

CENTRES.

70. Resident Engineer will give centres in all cuttings from time to time to insure the contractor excavating to the required lines and slopes, and will see that the slopes are left clean and true. Projecting or dangerous rocks on slopes must be removed. Slides of rock loose or solid must be carefully guarded against.

BACKFILLING ROCK CUTS.

71. Backfilling in rock cuts must not be done until the required excavation one foot below