

CLOAK ROOM:

Cloak room will have a 12" quarry tile floor with a 12" grey Missisquoi marble border.

The floors of the stair halls will also be finished in red quarry tile, grey marble border, and marble dado as mentioned for stairway.

GENERAL TOILET:

The floor of the Toilet Room will be finished in 3" square vitreous glazed tile. The walls will have a 5' dado of grey marble with plaster above. The toilet partitions will also be of grey marble.

ELEVATOR:

It is proposed to install an automatic push button control elevator to serve all floors. The elevator to have a carrying capacity of 2 tons and a speed of 100 feet per minute. It will be a combination freight and passenger elevator and will be operated only by a master key in the possession of those authorized to use it.

I am enclosing herewith copies of two letters from Messrs Thomson & Jamieson, the Engineers, one of which explains our reason for carrying the main walls on the steel frame and the other giving the floor loads provided for in the different parts of the building. This latter I would suggest that you refer to your Engineers in order that there may be a clear understanding of the weights provided for.

We will now proceed with the specification and hope to be ready to call for tenders in about two weeks time.

Yours respectfully,

Encls.