

the services, in one and which can be assembled on-site with a minimum of field labour.

A second hut is planned to be built of a material which may ultimately permit foaming in place.

If these are successful it is hoped to encourage further development along these lines.

If successfully developed such a method of construction would be particularly useful for northern construction. If the experiment is successful, it is possible to envisage two cans of liquid shipped to a site and then foamed in light weight molds up to 20 or 30 times its volume. Transport by air would be eased very much. Further, unskilled on-site labour could erect such houses easily.