

A complete fan system of ventilation has been provided, the fresh air being drawn in over heating coils and ejected into every ward, and the foul air ejected above roof. Pullman automatic sash ventilators have also been provided. The building will be heated by a low pressure steam system with two return tubular units and the Powers automatic system of temperature regulation by thermostats and compressed air.

The contract calls for the building to be finished by December, 1910, and the walls are now at ground floor level.