

(Copy.)

INTERCOLONIAL RAILWAY.

Contract No. 5. Division of the Line C.

Quantities.	Description of Work.	Rate.	Amount.
		\$ cts.	\$ cts.
100.2	Acres clearing and close cutting, &c.....	16 00	1,603 20
272,200	Lineal Feet Fencing	7 70	20,959 40
94,994	Cubic yards Rock Excavation.....	1 00	94,994 00
338,800	} Cubic yards Earth Excavation.....	0 28	223,166 36
443,937			
34,450	Lineal Feet under Drains (per 100 feet)	11 00	3,789 50
1,200	Cubic yards Rip Rap.....	2 00	2,400 00
800	" " Concrete	4 00	3,200 00
4,550	" " 1st class Masonry.....	13 00	59,150 00
7,147	" " 2nd " "	9 50	67,896 50
1,198	" " Paving	5 00	5,990 00
	Foundations		3,551 04
	Bridge Superstructure		17,600 00
	Road Crossing and Diversions.....		8,800 00
	Special Works		9,900 00
	Contract sum		\$533,000 00

INTERCOLONIAL RAILWAY,

OFFICE OF THE CHIEF ENGINEER,

Ottawa, March 25th, 1871.

S. Hazlewood, Esq., Rimouski.

MY DEAR SIR,—Enclosed find approximate Estimates for Sections 1 and 5, based on Revised Quantities received in your letters of March 6th and 15th. The prices are very similar to those used by you; the figures are, however, more even, and will be found much easier for calculations.

Yours very truly,

(Signed)

SANDFORD FLEMING!