

CANADIAN PACIFIC RAILWAY.

BILL OF WORKS 100 Miles West of the Province of Manitoba.—North-western Line.

nt. cts. 00 00	Description of Work.	Approximate Quantities.		Rates.		Amount.
				\$ cts.		\$ cts.
65 00	Clearing, very light, mostly brush	Acres.	190	16 00	per acre . . .	3,040 00
00 00	Close cutting	"	10	30 00	" . . .	300 00
00 00	Grubbing	"	9	60 00	" . . .	540 00
00 00	Fencing, 100 miles	Lineal feet	1,056,000	05	per lin. ft..	52,800 00
50 00	Earth excavation, including borrowing, surface drains, foundations, &c.	Cubic feet.	1,600,000	25	per cub. yd	400,000 00
50 00	Under drains	Lineal feet.	1,000	35	per lin. ft..	350 00
80 00	Crib work on abutments of bridges, in- cluding stone filling	Cubic yds.	920	4 00	per cub. yd	3,680 00
00 00	Bridge superstructures, Howe truss	1 span.	100			4,000 00
00 00	" " " "	1 "	80			2,600 00
704 00	Piles driven	Lineal feet.	1,780	40	per lin. ft .	712 00
075 00	Square timber in trestle bridges and culverts, &c.	Cubic feet.	170,000	35	per cub. ft.	59,500 00
337 50	Spruce plank	F. b. m.	16,000	25 00	M.	400 00
90 00	Oak "	"	2,000	50 00	" ..	100 00
250 00	Wrought iron	Lbs.	70,000	10	per lb.	7,000 00
640 00	Cast "	"	21,500	08	"	1,720 00
90 00	Spikes	"	1,300	08	" ..	104 00
500 00	Public road crossings	No.	50	150 00	each	7,500 00
000 00	Private " "	"	200	15 00	"	3,000 00
000 00	Ties, 104 miles, 2,400 per mile		250,000	30	"	75,000 00
320 00	Carriage of rails from beginning of con- tract, average 50 miles	Tons.	10,400	80	p. ton p. m.	8,320 00
400 00	Track-laying	Miles.	104	250 00	per mile . .	26,000 00
500 00	Ballast, 104 miles, 2,000 c. yd. per mile		208,000	30	per cub. yd	62,400 00
000 00	Points and crossings	Sets.	30	50 00	each	1,500 00
001 50	Station buildings	No.	12	2500 00	"	30,000 00
						\$750,566 00