The Paterson Mfg Co. Ltd.	Beauvais Frères	J. H. Wilson	Lockerby & McComb	Caverhill Learmont & Co.	Frothingham & Workman	SUNDRY MATERIALS
7c	8½c	15c	6½c			Coal Tar, per gallon.
42c	70c	55c	42c			Pitch, per 100 lbs.
	8c	11c	Barrels will be charged on Invoice for tar delivery and credit note will be allowed when returned.	8¾c	9c	Cotton Waste, "white", per pound
		5c		4.75 pr. 100 lbs		Oakum, "English Navy" " "
	2c					Rosin " "
	3¾c	3½c		5 75 per gross		Axle Grease " "
						Hose Leather " "
				60c		Lace " " "
					13c	Bass, for Brooms and Sweepers "
	19c					Dualine 40% per "
	21c					" 50% " "
	7.50					Detonators " 100 lbs.
	5.50	5.75		Anchor 4.25	4.00	Fuse "Gutta percha", per 1000 feet.
	¾-7.29-1 9.72	¾"/3 plis 9c 1" 3 plis 12c		2 ply x ¾" 6c per foot, 2 ply x ½" 4¾ foot	¾" x 3 ply 8c 1" x 3 ply 14½c	Rubber Hand Hose, ¾ in. and 1 in per foot.

TROTTOIRS EN COMPOSITION ——— COMPOSITION SIDEWALKS

La Compagnie de Construction et de Pavages Modernes de Montréal

1o—6½ of cinders, gravel or broken stone for drainage purposes;
2o—4" of concrete foundation, one part cement, 3 parts sand, six parts broken stone;
3o—1½" of top finish, one part Portland cement, 1½ part sand, thoroughly mixed together in the form of a stiff mortar and immediately laid on the foundation, lamp black shall be added to soften the color of the finish surface;
Expansion joints to be cut in the concrete foundation, to extend entirely through the said and to be filled with dry sand before the top finish is placed $2.22
Hassonite Cement Curb.—One part of cement, 3 parts of sand and 6 parts of stone, cinders or gravel. Price 80c per lineal ft.
Extra for rock excavations $3.00 per curb yd.
5 inches of concrete and 1½ top finish $1.95

The Barber Asphalt Paving Co.

Bermudez Lake Asphalt sidewalk having a wearing surface of 1½ inches of asphalt surface of a quality, and laid according to the specifications of the City of Montreal for asphalt street paving on 5 inches of portland cement concrete foundation, per sq. yd $2.03

The Sicily Asphaltum Paving Co. Ltd

Cement Sidewalks

5" concrete 1, 3 and 6 proportions, per sq. yd $2.06
1" finish 1, 1½ and 1½ " " 2.06
5" concrete 1, 3 and 6 " " 2.26
1½" finish 1, ½ and 1½ " " 2.26

M. Néolet

Pavés céramiques de Pont Ste Maxime, Oise France.

Pour surface 100 à 300 verges carrées, le pied carré, tout posé 0.34
Pour surface 300 à 1000 verges carrées, le pied carré, tout posé 0.33
Pour surface 1000 verges et au-dessus, le pied carré, tout posé 0.32

Laurin & Leitch

Trottoirs en béton fait comme suit, savoir :

D'abord fondation (après creusage) de 10 pouces de cendre ou 10 pouces de pierres aveuglées avec cendres et par dessus 4 pouces de béton de 1.3.5 et le tout fini avec 1 pouce de "finishing" et formant des blocs de longueurs convenables avec joints de sable pour parer aux changements de température $2.50

The Sicily Asphaltum Paving Co.

Supply concrete flags, 1½ gravel, 1½ sand 1 stone size :

3' x 2' x 3" thick per sq. yd $1.40
4' x 2' x 3" " " 1.45
5' x 2' x 3" " " 1.45
6' x 3' x 3" " " 1.50
del on streets.

E. D. Hofeller

Cement Sidewalks

Excavation :
1½ inches.

Drainage foundation :
5 inches stone.

Concrete foundation :
5 inches viz.
1 part Portland cement.
3 parts sharp sand.
6 parts stone cubes (not larger than 2").

Finishing or Wearing Coat :
1 part Portland cement.
2 parts sharp grit per sample.
1½ inches thick.

Expansion Joints :
To be cut through finishing and concrete courses cut to foundation to form seperate slabs.

Top Finishing Surface :
To be neatly blocked and worked with Roller, per square yard $1.86