

SPECIFICATIONS FOR MAIN BARN—*Concluded.*

Brought forward..... \$86 00

Doors—*Concluded*—

3 roller doors, 10 ft. by 7 ft. 6 in. (batt'd), complete	15 00
2 " 8 " 4 " " "	8 00
2 hinged doors, 7 ft. by 3 ft. 6 in.	8 00
2 double doors for gables, 8 ft. by 6 ft.	16 00
Two dormer windows on roof	25 00
Three ventilators on ridge	50 00
Eight kegs of nails	30 00
Twenty-eight concrete piers (8 bbls. cement).	25 00
Feed carrier (complete)	50 00
Hay carrier (with track)	25 00
Cost of labour for building (estimate)	200 00
	\$538 00.

Specifications for Cow Stable

(60 BY 32 FEET).

Sills—10 pieces, 32 ft. by 10 in. by 8 in.	2,000 ft.
Joists—56 pieces, 24 ft. by 2 in. by 10 in.	2,200 "
Studding for sides—53 pieces, 10 ft. by 2 in. by 6 in. .	500 "
Studding for ends—20 pieces, 20 ft. by 2 in. by 6 in. .	400 "
Tie beams—26 pieces, 30 ft. by 2 in. by 6 in.	800 "
Rafters—52 pieces, 24 ft. by 2 in. by 6 in.	1,250 "
Stays for rafters—52 pieces, 9 ft. by 2 in. by 6 in.	450 "
Flooring—Planks, 2 in. by 12 in.	4,000 "
Roof sheeting (open)—1 in. by 6 in.	2,000 "
Rustic—1 in. by 6 in.	2,600 "
Shiplap for inside sheeting	3,500 "
Lumber for 35 cow-stalls—Dressed lumber, 1 in. by 6 in. .	1,000 "
" studding, 1 in. by 5 in.	600 "
" " 1 in. by 4 in.	300 "
" planking, 2 in. by 12 in.	800 "
Shingles for roof	22,400 ft.
Litter carrier (complete)	30,000
Windows—17, 4 lights, 12 in. by 14 in. (estim'd. cost)	\$55 00
Two ventilators on ridge	60 00
Nails	30 00
Four doors (roller), 7 ft. 6 in. by 5 ft.	15 00
Two " " 7 ft. 6 in. by 6 ft.	20 00
Eighteen concrete piers (5 bbls. cement)	10 00
Labour for building stable	16 00
	100 00
	\$306 00