

were satisfied from past successes that this was a possible and practicable scheme. Temporary wooden staging was built across the river upon which were laid the skidding or rolling track rails. These were laid at such a height that between their bases and the top of the pedestals of 8 there was just room for an ordinary railroad tie and an inch or two of blocking, Fig. 5. On top of these rails were then built the posts of bent 8. The base of bent 7 being 6 ft. higher than bent 8, this amount of timber blocking was built upon the rails 40 ft. west of bent 8 and upon this small timber tower bent 7 was erected. When the bracing and 40-ft. girders of this tower had been completed a stiff-leg derrick was built on top of the tower by the erection derrick on tower 9-10, Fig. 6.

Between the shoe plates of bent 7 and the blocking upon which they rested was placed another set of rails, so that when the tower had been rolled westward until blocking under bent 7, having passed pedestal 8, was about 8 ft. from pedestal 7 they would project over pedestal 7 and when staged or blocked, would form a track upon which




Fig. 8.—Method of Hoisting and Erecting Trusses.

the shoes of bent 7 could slide the last few feet of their travel, the shoes of bent 8, of course, still rolling. Thus for the first 135 ft. or so the two bents of the tower rolled on the lower tiers and afterwards the higher shoes slid on the upper tiers. The rollers were 2 ins. in diameter and about 4 ft. in length. In this manner the tower was rolled to position and then jacked down onto its anchor bolts which were already in place on the pedestals. The rolling was effected by the winding engine of the stiff-legged derrick on top of the tower rolled. Lines from its spools to a hitch west of pedestal 7 passed back to the tackles, which were placed around posts at gussets and around the blocking under 7. The derrick up above thus pulled the tower carrying it into place. The movement was very easily accomplished and without any trouble or hindrance.

The next problem was the erecting of the truss span. The two bottom chords were lowered piece by piece to the staging already referred to, a few feet only from the ground, and there they were bolted up and trussed as shown in Fig. 7, by temporary eye bars and short struts. By this means they were made strong enough to carry themselves and a part of their respective trusses as spans of 145 ft. 6 ins. length. The end vertical posts of the trusses had, of course, been already erected as part of the towers and the bottom chord and splices were arranged to permit of the trussed chord being hoisted vertically and immediately bolted to the short end sections, which were shop riveted to the gusset plates at the foot of the vertical posts incorporated into the towers. By this means the two bottom chords were hoisted into place and connected, the stiff-legged derrick on 7-8 taking hold of about 40-ft. out and the main traveller taking hold of about 50 ft. out. The bottom lateral bracing was then put in place and the chords thus stayed horizontally.

The next process (Fig. 7) was the erecting on the low staging of the web members of the two panels at each end of each truss; that is, the main compression diagonal, the first vertical and the main tension diagonal. These were then hoisted into place and immediately braced by the placing of the first floor-beam and sway-bracing. The second verticals being added, the remaining central portion of each truss was assembled down below with the four panels of top chord and then similarly hoisted up to position and bolted on. The intermediate floor-beams, sway-bracing and top lateral bracing followed and the addition of end sections of top chords and stringer girders completed the span. When sufficient riveting had been done the temporary eye bar trussing was removed and everything was ready for the laying of track and the passage of the erection derrick. The stiff-legged derrick was dismantled and the erection of the remaining towers was proceeded with on the same plan as above described for the eastern shore. The photograph of the placing of the last girder is interesting in that it shows the device whereby a brace frame is hoisted above the second girder of a span, so that immediately both girders are correctly placed they can be braced together.

The main erection derrick had an interesting feature in its telescopic booms. They were built of steel sections in two lengths each, and so arranged that the outer half could enter the inner half and the effective boom thus shortened. Holes and pins were provided in the webs of each position of each boom whereby various lengths could be obtained and retained. The capacity of the booms was 15 tons per boom when shortened down to about 40 ft., and 10 tons each when acting at their full extension of 62 ft.

The greatest weight lifted in this viaduct was about 20 tons, divided between the derrick and the stiff-leg erected on tower 7-8. This weight comprised the centre portion of the 150-ft. span, was 394,185 lbs., and the total in the viaduct 913 tons.

The steelwork was manufactured and erected by the Dominion Bridge Co., Limited, of Montreal, under the supervision of R. F. Uniacke, bridge engineer to the N.T.C.R. Mr. F. P. Shearwood is the designing engineer of the company, and Mr. J. Finley the erection superintendent, while the author as assistant designing engineer was in responsible charge of the designing of the work above described.

The year 1910 has stood the record year for the production of coal in British Columbia, with a total of 3,139,235 tons (2,240 lbs.). The production in 1912 amounted to 3,025,709 tons, which is the second highest annual production, labor troubles being responsible for the lesser output than that of 1910.

Engineers and contractors from many sections of the country are to gather at Cleveland, Ohio, September 17 and 18, on the occasion of the tenth annual meeting of the National Paving Brick Manufacturers' Association. In former years the association has held its annual meetings during winter months, but at the last yearly assemblage of the paving brick manufacturers, it was decided to hold future conventions during an "open season." This will afford, besides the usual programme of written papers, discussion and criticism of brick street and brick road construction methods while work on the highways is in actual progress. The large amount of construction work in the district, will afford splendid opportunity for investigation in a most practical way.