

## ANNEX NO. (3)

It has been agreed that the Government of Iraq shall compensate for the areas appropriated from the cemetery with an equivalent area of approximately 3075m<sup>2</sup> and shall carry out all necessary work connected with the relocation of the cemetery maintaining the same architectural, structural and horticultural style as the existing site.

The work required is as detailed below:

1. Clear the area of the new site, including the walls marked = = = on drawing IRAQ/MOS/11A and the existing toolshed in the south-east corner of the site. Break up all concrete foundations and floors and remove from site.
2. Make up levels to match existing gradients using selected fill in well compacted 300mm layers. Finish to existing gradients with a minimum of 300mm topsoil over the site, increasing to 2 metres of topsoil in areas where trees are to be planted.
3. Carefully take down the existing Cross of Sacrifice and seat feature and re-erect in new positions as shown on drawing IRAQ/MOS/11A and particularly in accordance with drawings IRAQ/MOS/13 and IRAQ/MOS/15.
4. Carefully take down the existing Hindu Memorial and re-erect in the new position as shown on drawing IRAQ/MOS/11A and particularly in accordance with drawing IRAQ/MOS/14.
5. Carefully take down the existing entrance feature and rebuild to the amended design detailed on drawing IRAQ/MOS/12 in the position as shown on drawing IRAQ/MOS/11A.