

## GOVERNMENT HOUSE, NEW WESTMINSTER.

The foundations having settled, new sills have been laid on brick piers, the old studs rescarfed and the necessary repairs executed. (Appendix 13, page 64.)

## POWDER MAGAZINE, NEW WESTMINSTER.

This building has been repaired and the lightning conductor lengthened and improved. (Appendix 13, page 64.)

## CUSTOM HOUSE, VICTORIA.

In the attic story of the building, an office has been provided for the Inspector of Fisheries. (Appendix 13, page 64.)

---

HARBOURS AND PIERS.

---

ATLANTIC COAST.

## COLVILLE BAY.

In King's County, P.E.I., on the east coast, 15 miles from the eastern point of the Island.

The restoration of that portion of the breakwater carried away in January, 1878, has been commenced. About one half had been completed at the close of the fiscal year. (Appendix 4, page 20.)

## ST. PETER'S BAY.

In King's Co., P.E.I., on the northern shore, 40 miles from the eastern point of the Island.

The breakwater completed in Aug. 1878, has had the effect of deepening the water at the entrance of the harbour. (Appendix 4, page 20.)

## GRAND RIVER.

In King's Co., P.E.I., on the eastern shore, 25 miles from eastern point of the Island.

The flats in the harbour and the outer bay have been dredged and the channel at the public wharf deepened. (Appendix 4, page 20.)