

299028

Specifications for the repairs of
Bridge No. 3. over McConzie creek.
Inuvik.

Materials
vs.

The Contractor shall furnish all materials, tools, labor etc. for carrying on and completing the work mentioned in the following specification.

Piles.

Provide 6 piles of live, straight and sound white or swamp oak 21 ft long, and must have at least 16 in. in diameter at the cut off to receive the caps, and at least 9 in. in diameter at the small ends, and all barks must be peeled off, and the piles shall be driven to a depth of at least 10 ft or to hard bottom. The piles are for the new bents as shown on plan.

Caps.

Provide 4 pieces of 6 in. x 12 in. - 14 ft. of sound white pine timber free from warps, and the caps to be bolted on the tenons of the piles with 2. 3/4" - 15" under heads nuts and washers complete to each pile as shown on plan.

Joists
✓

Provide and lay in places 24 pieces of 3 in. x 12 in. - 14 ft. of good quality of white pine joists, and placed at 24 in. centres