

TABLE OF MINE COSTS

FOR TWELVE MONTHS ENDING SEPT. 30, 1899.

	DEVELOPMENT WORK.				ORE EXTRAC- TION.
	SINKING. Main Shaft.	SINKING. Small Shaft.	RAISING.	DRIFTING.	
Total advance, feet	122½	7	417	1884½	
Ore stoped, tons					45,810
COST PER FOOT.					COST PER TON.
Drilling	\$52 55	\$21 00	\$14 01	\$8 45	\$1 53
Tramming and Shoveling ..	4 22	5 00	4 06	3 10	53
Timbering	23 22	4 86	3 16	07	29
Hoisting	9 72	1 10	15	20	13
Smithing	5 18	2 11	1 88	1 21	15
Ore Sorting	74		14		01
General Labor	10 04	3 10	3 36	2 39	30
Air	7 32	2 44	2 76	1 55	21
Candles and Ill. Oil	95	54	40	27	03
Lubricating Oils and Waste	75	19	22	14	02
Explosives	5 25	3 49	3 22	1 87	25
Drills and Fittings	1 71	83	52	26	05
Mine Supplies	1 61	46	49	35	04
Lumber Expense	74	38	45	32	03
Stable and Teaming	1 19	45	42	28	04
Assaying	54	80	40	19	05
Surveying	90	09	28	18	02
Electric Lighting	74		40	28	03
Salaries	4 07	2 35	1 76	1 21	18
Office Expense	38	42	14	08	01
General Expense	1 10	38	56	38	05
Total	\$132 92	\$49 99	\$38 78	\$22 78	\$3 95

ORE SOLD.

Stoped	45,810 tons.
Dumps	3,762 "
Met in development	1,671 "
Total	51,243 tons.