PERSONAL.

Ross & Macdonald, architects, have moved their offices from 908 Royal Bank Building to 61 Front Street West, Toronto.

G. Jacques & Co., architects and engineers, of Windsor. On-tario, have moved their offices in that city from 5 Sandwich street west, to the Peninsular Security Building, Chatham street west, and would be pleased to receive manufacturers' samples and catalogues.

and catalogues. Mr. Frank A. Spaugenberg, who has been associate of Mr. C. S. Cobb for the past three and a halt years, is leaving for Buffalo, N.Y., where he will be located with Messrs. Lansing, Bley, & Lyman. Mr. Spangenberg's architectural experience has been gained through association with some of America's fore-most firms, covering a period of thirteen years. In the year of 1909 to 1913 he studied architectural design in Ateller Prevot, New York City, and Columbia University. In 1913 Mr. Spangen-berg was chief designer and chief draupthsman for Austin W. Lord, architect, Isthmian Canal Commission (of Lord & Hewlett. architects, New York City). His work in Toronto has been par-ticularly devoted to the National Sanitarium Office Building, the new Registry of Deeds and Land Titles, the W. J. Gage resi-dence, and the C. S. Blackwell residence.

CHANGE IN MANAGEMENT.

Changes in the management of MacKinnon, Holmes & Co., Limited, of Sherbrooke, Que., have recently taken place, caused by the retirement from the company of Mr. A. R. Holmes, who in the past has occupied the position of director and secretarytreasurer

In the plasma becomend the plasma of the pla

INVESTIGATIONS OF GRAVITY AND ISOSTASY.

Recent investigations of gravity and isostasy are discussed and summarized in Special Publication No. 40 of the United States Coast and Geodetic Survey, a quarto volume of one hun-dred and ninety-six pages illustrated by numerous plates and obarts.

Area and ninety-six pages illustrated by numerous plates and charts. The survey for a number of years has been carrying on geo-detic investigations of isostasy with special reference to the effect of isostatic compensation upon the deflection of the ver-tical and the intensity of gravity. Four previous reports on these investigations have appeared, the first one in 1909 and the last in 1912. The present volume gives the results of further study of the relation between gravity and isostasy. In it are embodied the gravity data resulting from the previous work. The conclusions which may be drawn from the investigation reported in this volume substantiate to a great extent the con-clusions arrived at from previous investigations. This is con-sidered important because seventy per cent. more gravity sta-tions in the United States were used at this time than in the preceding gravity investigation, and many stations in Canada. India, and Europe for which data were available were also used. Copies of the volume may be obtained at sixty cents each from the Superintendent of Documents, Government Printing Office, Washington, D.C.

CONTRACT AWARDED.

The British Cordite Co., Ltd., have recently executed a con-tract for ten 400 h.p. Murphy furnaces to be installed in their new plant at Nobel, Ont.

INSTRUCTIONS TO STEEL INSPECTORS IN THE FIELD. By Elwyn E. Seelye.

INSTRUCTIONS TO STEEL INSPECTORS IN THE FIELD. By Elwyn E. Seelye. The purpose of this article is to bring out the essential points to look for when inspecting a steel frame. It is assumed that the structure has been properly designed and that the shop work has been properly executed. It should be emphasized at this point that shop inspection and mill inspec-tion are very important. The reasons for that are numerous. Some of the most important of them are as follows: Where steel is being rolled and some orders are being inspected the rejected material is apt to be unloaded on the purchaser who does not have inspection. In fabricating, if there is no inspection, the plans may not be followed accurately, causing delay and expen-sive field changes at the site, also, as will be noted later in the article, certain errors of fabrication are not apparent after the fabrication is complete. Where supposing the steel has been shipped in perfect order for damages, due to shipment. These will generally appear as bent plates or members. All these damages is serious an expert should be called in to pass on it. Where no shop inspection has been made, the field inspector should go over the riveting and see made, the field inspector should go over the riveting and see that surfaces in direct bearing are milled and in contact. The important thing in the erection of bases, either grillages, this can best be done by pouring the grout into a funnel raised high enough to produce a hydraulic pressure. The space between the concrete foundation and the iron should also be rodded to eliminate voids. It is very important that the bases be set level, faced on the top and that the column be faced to provide a full and even bearing between the bottom of the column and the base. In unimportant columns a discrepancy may be wedged

<text><text><text><text><text><text><text><text>

snould be taken to see that it is amply supported by the masonry and anchored thereto. Painting is a very important matter in the preservation of steel work, and all portions where paint has been removed by shipment should be repainted before erection. The field coat should be of different color than the shop coat. Cast iron members should be carefully inspected for visible defects. All cast iron columns charts

Cast from members should be carefully inspected for visible defects. All cast iron columns should have at least two holes drilled in the column for the purpose of checking the thickness of the column. Often the core is displaced in pouring, rendering the column thinner on one side than the other. A discrepancy of more than twenty-five per cent. should be cause for rejection. All bearing surfaces in cast iron should be milled. Columns which are crooked should be rejected. The cast iron beam seats should slope down outwards to make the beam bear as close as possible to the column and eliminate flexure in the seat. A double lug generally engages the web of a beam through which a single bolt is passed. On one job these bolts held the beams up off the seat and necessitated field changes. All steel should be marked for identification in the field and the shop inspector's mark should also appear. The most intelli-gent field inspection can be made by a representative from the designer's office, as he will be able to follow the designer's in-tent.

addigner's office, as he will be able to follow the designer's intent.
The inspector should co-operate with the erector in safe-guarding the structure from accidents during erection. He should see that the derrick base is secured from the horizontal kick of the boom in any direction. The steel carrying the derrick should be strong enough and have sufficient connections for the erection stresses involved. He should exert a check on dangerous practices, such as lifting too heavy a load for the strength or counter-ties of the derrick, booming out too far or the splicing of booms.
Guying and bracing of steel in the process of erection against wind-bracing is important. In this case it is well to remember that serious accidents have occurred through the shrinkage of guy ropes when wet. To sum up:
1. See that your steel is inspected by a competent bureau in the mill and shop.
2. See that your bases have a proper masonry contact.
3. See that columns bear directly on bases with full bearing; that columns bear directly on columns with full bearing and that all stiffeners are milled to bear.
4. See that the steel is repaired and straightened where injured during shipment.
5. See that no rivets are in tension.
6. See that no rivets are in tension.
7. Look out for a good two-coat paint job.
8. Be sure that beams have proper wall bearing.
9. Inspect cast iron for workmanship and flaws.
10. Safeguard the erection against accidents.