

The total cubic contents amount to some 775,000 ft., and can be built for \$300,000.00, provided the cost of construction can be kept down to 39 cents per cubic foot.

In addition, there is an item of \$8,000.00 for Tunnel connection to the Royal Victoria Hospital, and a small sum of \$3,000.00 might be allowed as a charge for excavation against the future University tunnel passing through the basement of the building.

The equipment of a Pathological Building is of a peculiarly complex and expensive nature. How much should be installed at once is a matter of policy.

It is to be understood that the bulk of the equipment of the building will not figure in the general contract, and should be separately dealt with after report from the Consulting Architects, which will take some time.

8. Time.

From the time of approving the sketch plans we estimate that fully ten weeks will be consumed in the preparation of working drawings sufficient for estimates and tenders; but if there is great urgency a contract for the excavation (and for the plain rubble work also, perhaps) might be advantageously let in one month's time.

(Signed) Percy E. Nobbs
for the Architects.

(Signed) William Carless
for the Associate Architects.

Concurred in,

(Signed) Frederick C. Lee
for the Consulting Architects.