

BILL OF MATERIAL, CONTINUED.

Sand 75 cu. yds. }
 Gravel 110 " " } For 148 cu. yds. concrete @ 1 : 2 : 3 mix.
 Cement 220 bbls. }

Gate Valves, iron body, inside screw, hub ends.

5 only 6", two for main inlet lines to septic tanks
 5 only 4", three for septic tanks and three for draining contact beds.
 Three of these valves to be fitted with 8" stems, one with
 11" stem, and one with 18" stem. All eight valves to be
 complete with hand wheel.

100 - linear feet of 6" vitrified tile sewer pipe hub and spl. got
 standard.

3 - only, ring and cast iron plug for 6" sludge outlets from bottom
 of septic tanks with ring in top as specified on plan

2 - five foot lengths of 6" Galv. soil pipe extra heavy, single hub.

1 - single hub return bend, 6" K.H. soil pipe extra heavy

1 - Tee branch, 6" soil pipe, extra heavy.

1 - Three foot length of 6" soil pipe extra heavy both ends without
 hub.

6 - Manhole frames and covers, 18" diameter, cover to be without
 perforations.

FOR CHLORINATED RUBBER

Coast Ply No. 1 Common Galv. L.P.K.

1 - 2" x 8" x 14'	"	"	"
1 - 1" x 8" x 12'	"	"	"
8 - 8" x 4" x 14'	"	"	"
8 - 8" x 4" x 10'	"	"	"
8 - 8" x 6" x 10'	"	"	"
1 - 8" x 6" x 12'	"	"	"
210 F.B.M.	"	"	"
of single holes	6" shingles	Roof Spruce	"

1 - 0.5" door frame 1 1/2" x 4 1/2" and sill

1 - Door 2 1/2" x 6 1/2" x 1 1/2/8" S X

1 - Window 24" x 24" x 2 lights S.D.

5" x 6" rebated frame and 5" x 10" sill.

1 - Cash fastener

1 - Pair 4" brass butts

1 - Horrible lock

1 1/2" x 5" shingles

REINFORCING STEEL

Round Rods	Round Rods
36 - 3/8 x 3'	40 - 1/2" x 6'
11 - 3/8 x 5'	225 - 1/2 x 7'
56 - 3/8 x 8 1/4'	15 - 1/2 x 7 1/2'
5 - 3/8 x 6'	55 - 1/2 x 8 1/2'
10 - 3/8 x 7'	50 - 1/2 x 10'
11 - 3/8 x 8'	70 - 1/2 x 11'
56 - 3/8 x 9'	45 - 1/2 x 14 1/2'
100 - 3/8 x 12'	15 - 1/2 x 16 1/2'
6 - 3/8 x 15 1/2'	5 - 1/2 x 20'
7 - 3/8 x 19'	55 - 1/2 x 20 1/2'
22 - 3/8 x 21'	8 - 1/2 x 22'
7 - 3/8 x 22'	
22 - 3/8 x 23'	
5 - 3/8 x 26'	

1007 Lin Ft. 3/8"

Total

5505 Ft. - 1070.04 lbs.

5505 Ft. - 2604.04 lb