

80 brick wells (man holes) 7'0 x 3'6'

NEW FIRE HYDRANTS.

142 hydrants of 2 jets.

4 " 3 "

---

Total 146

NEW MAINS FOR HOUSES.

650 mains of 1-2 inch.

18 " 3-4 "

8 " 1 "

9 " 1 1-2 "

8 " 2 "

11 " 4 " for fire purposes

10 " 6 "

---

Total 714

WATERWORKS, Limolou.

Water cast iron pipes.

106 feet of water pipe of 4 ins.

15078 " " 6 "

11899 " " 8 "

15000 " " 14 "

---

42083

DRAINAGE PIPES IN VITRIFIED CLAY.

2640 feet of drainage pipe of 6 feet

8570 " " 9 "

6576 " " 12 "

2666 " " 15 "

278 " " 18 "

3541 " " 24 "

597 " " 27 "

828 drainage of... 42 "

---

36906