

Ottawa, August 24, 1917.

Sir,-

I beg to acknowledge the receipt of your letter dated the 8th ultim. in reference to water supply and repairs at Cape Croker agency, and in reply to inform you that it has been decided to provide the necessary earthtroughing (5") around untroughed portion of the house, and connect to and repair earthtrough now on and to provide 2" of conductor connecting troughing with an new cistern in basement through rear outside wall.

To provide a new concrete cistern having an inner dimension of 5' x 7 by 5' in height with walls and floor not less than 10" in thickness. The concrete used to be in proportion of 1 cement, 2 of clean sharp sand, and 4 parts fine clean gravel mixed thoroughly and well tamped in forms to ensure density and satisfactorily hold water, for which a guarantee must be given.

To also provide an 18 x 30 channelled cast iron earthtrough complete with brackets, 1 1/2" trap and galv. iron waste pipe connected and connected to drain, also cisterns form pipe of good quality erected on platform at sink having 1 1/2" pipe connected to cistern, for the price of sum of \$125.00 as quoted by D.J. Hunter, Esq., of Winton.

The Department also approves of a well being drilled for hard water in a suitable position near the buildings.

Yours Lennox, Esq.,
Indian Agent,
Cape Croker,
Ont.

Indian Affairs. Letterbook,
9 August 1917 - 24 August 1917, (R.G. 10, Volume 5683)

Copy.

PUBLIC ARCHIVES
ARCHIVES PUBLIQUES
CANADA