

and is built complete for the inspection of the

public the same as the rest of the building.

watt & BLACKWELL, ARCHITECTS; w. c. MURRAY, ASSOCIATED. foot over the ordinary type of school construction. The building was also completed with a deduction of thirty-five dollars from the contract. Watt &

Off the main entrance is situated the library, principal's and teachers' offices; in the principal's office, which is in direct connection with the principal's classroom, situated the switchboard for the intercommunicating telephone system.

The exterior of the Ryerson School, which is of classic design and presa_partients cularly effective facade, wals originally signed with tapestry brick face, but owing to the extreme economy exercised by/ the trustees, was afterwardschanged to stucco, which gives a very pleasing effect, and will improve with time, when the terracing is finished and the vines grow up on this trellis work.

The cost of this school was fifty-three thousand dollars, cost per cubic foot nine and one-half cents, a saving of at least six cents per cubic foot over the