

2.

Adjusting of all windows and doors where required,
painting of exterior wood work.

INTERIOR OF BUILDING,-

A radiator having a capacity of 24 square feet of radiation should be installed in the bath-room on ground floor with the necessary connections, valves, etc.

New ceiling in cellar made of 7/8" T. & G. lumber and a new hardwood floor 7/8" T. & G. lumber placed on top of present floor with a thickness of insulating paper between

The ceiling joists of the kitchen should be sheathed on top with 7/8" T. & G. boarding and entirely covered with one thickness of heavy building or tar paper well applied and secured to sheathing.

The whole stable and shed may be demolished and reconstructed using as much of the old material as possible. The main building to have a compartment for wood and coal, a small stable for one horse and one cow and sufficient space for the vehicles.

It is expected that you will employ yourself diligently on the works as per instructions, and you should apply to the Agent for any necessary additional labour and materials which will have to be purchased through his office in the usual manner.

Your salary while employed on this work will be at the rate of \$4.00 per day, which price includes your travelling and board expenses.

Kindly acknowledge the receipt of this letter, and oblige

Your obedient servant,

Asst. Deputy and Secretary.

Indian Affairs. Letterbook
24 August 1917 - 12 September 1917. (R.G. 10, Volume 5685)

Poor
Copy.

PUBLIC ARCHIVES
ARCHIVES PUBLIQUES
CANADA