

Specifications for raising the grade
at the new concrete arch on the
sideline between lots 24 & 25, Con. 2, Div.

Furnish
Tools, &c.

The Contractor shall furnish all Tools,
Labor, and everything necessary for
carrying on and completing the contract.

Plan.

Level stakes being planted every 50 ft.
apart on the west side of the track
having marked on them in feet and
inches the height to be raised as shown
on the accompanying profile sketch
of the present grade, and the raised
grade as proposed, and the track
shall be at least 16 ft. wide with a
crown of 8 inches, and the side slopes
shall be one and half to one ($1\frac{1}{2}$ to 1.)

Earth
&c.

The earth to be employed for raising
the grade shall be from the hills
immediate south and north side of
the McKenzie creek. No side ditches
shall be excavated, and the track
shall be uniformly surface level
from stake one to stake eight, and
from stake nine to stake thirteen.

Cuttings

The hills where cuttings are made
for the earth shall be left with
side