

pools, temporary drains for carrying off or diverting existing drains or runs of water, during the progress of the works; the removal of all superfluous earth or material, not required for re-making the ground, and depositing the same in such places within the City limits, as may be pointed out by the officer or person in charge of the work. The re-making the ground; after the masons and bricklayers have completed their work, and leaving the road or street in all respects in a state of perfect and good repair. The providing and fixing all boarding, fences, and bars required in securing the public from accident; the forming good and sufficient bridging across the excavation to accommodate the traffic during the progress of the work, at the intersection of such streets or highways as may be directed. The providing, fixing, and maintaining all lanterns or lamps that may be required to indicate obstruction in the way as well as proper watchmen by night. The timber and shoring all places where the excavation is confined to narrow limits, that is, where, from the depth of cutting required, no slope can be given for the sides thereof. The pumping out or removing all accumulation of water in the cuts, and keeping the same free therefrom, until the masonry or brickwork is completed, with its filling in and backing.

Such timbering as may be deemed necessary by the Superintendent, to be retained for the security of the work, to be measured and paid for at the market price.