

ESTIMATE.

3,357 M Bricks, at \$12.00.....	\$40,284.00
Labour and Cement, per M \$8.00.....	26,856.00
82,000 yards Excavation :	
27,333 yards rock, at \$1.50.....	42,000.00
54,666 " earth, at \$0.20.....	10,933.00
60,200 " re-filling, at \$0.05.....	3,010.00
21,800 " carting away, at \$0.25.....	5,450.00
Inlet Pipes to Sewers :	
3,000 pieces 6 inch, at \$0.33 each.....	990.00
1,000 " 9 " 0.66 ".....	660.00
1,000 " 12 " 1.00 ".....	1,000.00
100 " 15 " 1.90 ".....	190.00
Laying Pipes from 400 Catch Pits, with cement, each \$2.50.....	1,000.00
Pipes from 400 Catch Pits, each 25 feet 9 inch., at \$0.33.....	3,300.00
Excavating 400 Catch Pits, 2½ yards each, at \$0.50.....	500.00
Excavating for Pipes from Catch Pits, 4,000 yards, at \$0.50.....	2,000.00
Granite Fittings for 400 Gratings, at \$4.00.....	1,600.00
100 Man Holes, each \$10.00.....	1,000.00
Outlet at Collins's Wharf :	
450 yards ballast, at \$1.00.....	\$450.00
160 " masonry, at \$12.00.....	1,920.00
150 " concrete, at \$4.00.....	600.00
Outlet at City Wharf.....	2,000.00
Outlet at Queen's Wharf.....	1,000.00
Additional 10 per cent. of above.....	14,674.00
	<u>\$161,417.00</u>

REDUCED ESTIMATE.

3,357 M Brick, at \$9.00.....	\$30,213.00
Labour and Cement, at \$7.00.....	23,499.00
82,000 yards Excavation :	
27,333 yards rock, at \$1.10.....	30,066.00
54,666 " earth, at \$0.17.....	9,273.00
Re-filling 60,200 yards, at \$0.05.....	3,010.00
Carting away 21,800 yards, at \$0.20.....	4,360.00
Inlet Pipes to Sewers :	
3,000 pieces 6 inch, each at \$0.26.....	780.00
1,000 " 9 " " 0.50.....	500.00
1,000 " 12 " " 0.80.....	800.00
100 " 15 " " 1.60.....	160.00
Pipes from 400 Catch Pits, each 25 ft. 9 in., at \$0.25.....	2,500.00
Excavating 400 Catch Pits, each 2½ yards, at \$0.40.....	400.00
Excavation for Pipe, 4,000 yards, at \$0.40.....	1,600.00
Granite Fittings for 400 Gratings, at \$4.00.....	1,600.00
100 Man Holes, each \$10.00.....	1,000.00
Laying Pipes from 400 Catch Pits, with Cement, at \$1.75.....	700.00
Outlet at Collins's Wharf :	
450 yards ballast, at \$0.75.....	\$337.00
160 " masonry, 12.00.....	1,920.00
150 " concrete, 3.50.....	525.00
Outlet at City Wharf.....	2,782.00
Outlet at Queen's Wharf.....	2,000.00
Additional 10 per cent of above.....	1,000.00
	<u>11,626.00</u>
	<u>\$127,889.00</u>