all the sashes and fans with box glass, well puttied, spriged and back puttied leaving the whole in a clear and perfect state at the rendering up of the buildings.

Also for a Hospital Privy at the same post.

To excavate for and form a soil pit 14X6 feet and ten feet deep clear dimensions—and build the sides in good sound rubble masonry to the surface of the ground of the same description of workmanship and material as described for the foundation walls of the Hospital. To fix a cedar frame round the sawpit, of scantling 8X6 well secured at the angles with dragon ties, introducing three beams across of the same scantling, dovetailed and pinned down to external sills. To build a Privy 17 feet long, 6 feet wide; sills 8X4, angle studs 4X4, intermediate studs 4X3, and two feet apart, braces 4X3, plate 4X3, joists 7X3, rafters 4X2—the roof to be covered with pine shingles four inches to the weather, one inch grooved and tongued boarding. The whole to be properly framed and braced and covered with inch wrought and rebated clapboarding, 7 inches wide and lined on the inside with inch boarding wrought one side, grooved and tongued. The floor to be 2 inch deal grooved and tongued and wrought one side; the partition divisions of the Privy to be also of two inch deal, wrought both sides and beaded in addition. Fit up the seats with seat and riser and form the seat openings [illegible] as implies. The doors to be [illegible] and board, grooved, tongued and [illegible], hung with strong hooks and ribs and fitted with [illegible] hinges, [illegible] latches [illegible]. The remaining part of the Privy to be as [illegible] of two inch deal, let into a frame [illegible]—bolted to the floor with [illegible]. A door to be inserted over the [illegible] each Privy to be fixed from the [illegible] to cover the cesspool in rear of the [illegible] grooved and tongued, and provided with a [illegible] shingled. Also for access to ditto, hung with strong hooks and ribs and fitted with rings and staples. The clapboarding, including shingles on the door and screen, to receive three good coats in oil.

All the workmanship and materials to be of first quality, and in compliance with the foregoing specification, and the whole completed by the 30th October, subject to