COMMUNICATIONS DIVISION (Cont'd)

FUNCTION	STAFF	AREA	REMARKS
Communications Centre	•		•
Signal Master	1	120	S.P. with Line Room
Duplicating Room	20	800	G.O. Top security area.
Cypher Room #1	20	750	G.O. Top security area. Sound proofing required.
Cypher Room #2	2	240	G.O. Top security area.
Cypher Room #3	1	240	G.O. Top security area.
Cypher Room #4	4	300	G.O. Top security area
Tape and Teletype Store		200	G.O.
Vault		100	G.O.
Lunch Room	,	240	G.O. Kitchen counter and sink required.
Locker Room		100	G.O.
Bag Room	12	1,600	G.O. Top security area.
Mail Room	8	500	G.O.
Storage	•	150	
Maintenance Section	9	900	G.O.
Janitor's Closet	1	40	
Total	139	8,680	

Within the Communications Centre area, there should be an area of 500 sq.ft. for a telephone line room which will house the incoming telephone cables and switchboard.

Also within the comcentre area will be the special room '77' shown under the DL2 division and the Duty Officer and Emergency Operations Room shown under DL1 division.

All electrical installations within the comcentre area for equipment will be carried out by their own staff. All that will be required of the general contractor will be the provision of ducts and panel boards in each room where special equipment is located. This information will be provided at final sketch plan stage.

Although no final decision has been taken, there is the possibility of installing a mail tube service between the comcentre and the local file room on each floor of the building for the transmittal and reception of important messages.