

EGAT's Thermal Power Plant Project

1. Project name : Ao Phai 1-2
2. Type of generation : coal-fired steam plant
3. Description and scope of project
  - a) Location : Ao Phai District,  
Chon Buri Province
  - b) Rated capacity : 2x600 MW
  - c) Annual energy generation : 2x3950 GWh
  - d) Fuel : imported coal
  - e) Fuel consumption : 2x1.546 million tons per year

| 4. Project cost (Million Baht) of each unit of 600 MW | ---FC--- | ---LC--- | ---Total--- |
|---|----------|----------|-------------|
| -Turbine generator & auxiliary                        | 1698.03  | -        | 1698.03     |
| -Steam generator & auxiliary                          | 2764.26  | -        | 2764.26     |
| -Coal handling  | 353.70   | -        | 353.70      |
| -Ash handling   | 288.90   | -        | 288.90      |
| -Structural steel                                     | 285.39   | -        | 285.39      |
| -Intake and C.W. pipe                                 | 45.90    | -        | 45.90       |
| -Electrical equipment                                 | 833.49   | -        | 833.49      |
| -Instrumentation & control                            | 216.54   | -        | 216.54      |
| -Water treatment                                      | 166.86   | -        | 166.86      |
| -Building super structure                             | 210.87   | -        | 210.87      |
| -Plant miscellaneous                                  | 54.81    | -        | 54.81       |
| -Air conditioning                                     | 30.24    | -        | 30.24       |
| -Construction equipment                               | 49.14    | -        | 49.14       |
| -Civil works  | 73.71    | 2082.24  | 2155.95     |
| -Mechanical construction                              | -        | 1699.11  | 1699.11     |
| -Electrical & control construction                    | -        | 787.05   | 787.05      |
| -Inspection service                                   | 14.04    | -        | 14.04       |
| -Local transport                                      | -        | 70.74    | 70.74       |
|   | -----    | -----    | -----       |
| Total   | 7,085.88 | 4,632.14 | 11,725.02   |

5. Tentative schedule
  - a) Feasibility study and approval : October 1992
  - b) Engineering : October 1993 (Ao Phai # 1)  
October 1994 (Ao Phai # 2)
  - c) Preliminary, manufacturing, construction and installation works : October 1994 (Ao Phai # 1)  
October 1995 (Ao Phai # 2)
  - d) Commissioning : October 1999 - October 2000