

13. Take down existing headstones and monuments to the Consular Graves Section and re-erect in the positions shown on drawing IRAQ/MOS/11A.
14. Carefully excavate and exhume remains to the whole area of the existing Protestant Plot and rebury sequentially in the new Protestant Plot shown on drawing IRAQ/MOS/11A.
15. Take down all existing headstones and monuments to the Protestant Plot and re-erect in the new Protestant Plot.
16. Provide and fix a new mains water supply in the position shown on drawing IRAQ/MOS/11A.
17. Provide and lay, at a depth of 500mm, a 50mm diameter PN10 polyethylene reticulation system as shown on drawing IRAQ/MOS/11A.
18. On completion of the work the site should be left clean and level and free of all debris.
19. it is agreed that:
 - a. all this work and the necessary horticultural treatment which follows shall be under the supervision of an official of the Commonwealth War Graves Commission;
 - b. if import of materials is necessary for the completion of the work or the horticultural treatment, this shall be facilitated by the Government of Iraq.