

copy
171

DEPARTMENT OF THE INTERIOR
2 OCT 78
CANADA

Specifications for the Construction
of a School House for the Western
School Section, Mohawk Reserve.

Foundation

Trenches to be dug two and a half
feet deep and one and a half feet
wide, six by twenty by thirty feet, also
two holes to be dug three by three
feet for a butress for underpinning,
the central timber two feet apart
the stone wall to be built two feet
above the highest part of the ground
laid in with perfect mortar of lime
and sand

Carpenter Work.

Building twenty by thirty feet, ten
feet posts, rafters fifteen feet long
besides the projection, the shingles
to lay close, lime mortar to be laid
under the shingles, the shingles
to lay five inches to the weather
the cornice to be made in pro-
portion to the building, say one foot
the body of the building to be sided
up with one inch dressed lumber
(common siding) and sealed up on the
inside and outside with cull lumber
one inch thick between the posts
leaving a space of four inches
and

RG 10, B-3-a, vol. 2027
File/dossier 8799 1/2

INDIAN AFFAIRS
AFFAIRES INDIENNES

National Archives of Canada
Archives nationales du Canada

000010