

ble and practicable into this system, and preparation will be made for the same in the work.

Flood or stop gates will be provided for the mouth of the Culvert, as well as for the sewer at Barrack Street, should it be found desirable to have a discharge at that point, above or below which, there will be no communication whatever with the River, and all existing openings will be shut up and closed, so as to prevent the possibility of water entering the drains, at least by those means:

All open drains of water will be taken up, and the courses diverted into the proposed sewers. No drainage or waste water will be allowed to enter the sewers, except in such manner or quantity, and at such times as may be decided upon by the person who has charge of the sewerage, to prevent accident from flooding the sewers when already full.

The contract to be founded on the following specification, embraces—the removal of the metal or paving with which the street or road is covered, to be relayed where required; the excavation for all drains, sewers, or cess-pools, where pointed out or laid down on the plan of the City which is appended hereto, or herein referred to, marked A and signed by the contracting parties; the providing of materials, tools, and labor of their respective kinds, as described more fully hereafter; and generally, the true and faithful execution of the works contracted for, according to the intent of the plan or specification. Under this heading, is comprised—the excavation for all drains, cess-