

Technical and Bibliographic Notes / Notes techniques et bibliographiques

The Institute has attempted to obtain the best original copy available for filming. Features of this copy which may be bibliographically unique, which may alter any of the images in the reproduction, or which may significantly change the usual method of filming, are checked below.

L'Institut a microfilmé le meilleur exemplaire qu'il lui a été possible de se procurer. Les détails de cet exemplaire qui sont peut-être uniques du point de vue bibliographique, qui peuvent modifier une image reproduite, ou qui peuvent exiger une modification dans la méthode normale de filmage sont indiqués ci-dessous.

- Coloured covers/  
Couverture de couleur
- Covers damaged/  
Couverture endommagée
- Covers restored and/or laminated/  
Couverture restaurée et/ou pelliculée
- Cover title missing/  
Le titre de couverture manque
- Coloured maps/  
Cartes géographiques en couleur
- Coloured ink (i.e. other than blue or black)/  
Encre de couleur (i.e. autre que bleue ou noire)
- Coloured plates and/or illustrations/  
Planches et/ou illustrations en couleur
- Bound with other material/  
Relié avec d'autres documents
- Tight binding may cause shadows or distortion  
along interior margin/  
La reliure serrée peut causer de l'ombre ou de la  
distorsion le long de la marge intérieure
- Blank leaves added during restoration may appear  
within the text. Whenever possible, these have  
been omitted from filming/  
Il se peut que certaines pages blanches ajoutées  
lors d'une restauration apparaissent dans le texte,  
mais, lorsque cela était possible, ces pages n'ont  
pas été filmées.
- Additional comments:/  
Commentaires supplémentaires:

- Coloured pages/  
Pages de couleur
  - Pages damaged/  
Pages endommagées
  - Pages restored and/or laminated/  
Pages restaurées et/ou pelliculées
  - Pages discoloured, stained or foxed/  
Pages décolorées, tachetées ou piquées
  - Pages detached/  
Pages détachées
  - Showthrough/  
Transparence
  - Quality of print varies/  
Qualité inégale de l'impression
  - Continuous pagination/  
Pagination continue
  - Includes index(es)/  
Comprend un (des) index
- Title on header taken from:/  
Le titre de l'en-tête provient:
- Title page of issue/  
Page de titre de la livraison
  - Caption of issue/  
Titre de départ de la livraison
  - Masthead/  
Générique (périodiques) de la livraison

This item is filmed at the reduction ratio checked below/  
Ce document est filmé au taux de réduction indiqué ci-dessous.

10X	12X	14X	16X	18X	20X	22X	24X	26X	28X	30X	32X
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

# CANADIAN CONTRACT RECORD

A WEEKLY JOURNAL OF PUBLIC WORKS, TENDERS, ADVANCE INFORMATION AND MUNICIPAL PROGRESS

EVERY THURSDAY

THIS PAPER REACHES EVERY WEEK THE TOWN AND CITY CLERKS, TOWN AND CITY ENGINEERS, COUNTY CLERKS AND COUNTY ENGINEERS THROUGHOUT CANADA.

Vol. 4. DECEMBER 7, 1893 No. 42

## THE CANADIAN CONTRACT RECORD,

PUBLISHED EVERY THURSDAY

As an Intermediate Edition of the "Canadian Architect and Builder."

Subscription price of "Canadian Architect and Builder" (including "Canadian Contract Record") \$2 per annum, payable in advance.

C. H. MORTIMER, Publisher,

CONFEDERATION LIFE BUILDING, TORONTO.  
Telephone 1362.

64 Temple Building Montreal.  
Bell Telephone 2199.

Information solicited from any part of the Dominion regarding contracts open to tender.

ADVERTISING RATES ON APPLICATION.

At its Convention held in Toronto, Nov. 30 and 31, 1889, the Ontario Association of Architects signed its approval of the CANADIAN CONTRACT RECORD, and pledged its members to use this journal as their medium of communication with contractors with respect to advertisements for Tenders.

The following resolution was unanimously adopted at the First Annual Meeting of the Province of Quebec Association of Architects, held in Montreal, Oct. 10th and 11th, 1890: "Moved by M. Perrault, seconded by A. F. Dunlop, that we the Architects of the Province of Quebec now assembled in Convention being satisfied that the CANADIAN CONTRACT RECORD affords us a direct communication with the Contractors,—Resolved, that we pledge our support to it by using its columns when calling for Tenders."

Subscribers who may change their address should give prompt notice of same. In doing so, give both old and new address. Notify the publisher of any irregularity in delivery of paper.



## Notice to Contractors

### TENDERS FOR ANNUAL SUPPLIES.

Tenders will be received by registered post, addressed to the City Engineer, Toronto, up to 11 o'clock a. m. on SATURDAY, DECEMBER 9TH, 1893, for the following supplies for the year ending 31st December, 1894:

Sewer Pipe, Iron Work, Lumber, Cedar Posts, Horse Feed, etc., Wire Nails, Hardware, etc., Gravel and Sand.

Specifications may be seen and forms of tender obtained on and after Saturday, December 2nd, 1893, at the office of the City Engineer.

A deposit in the form of a marked cheque, payable to the order of the City Treasurer, for the sum of 5 per cent. on the value of the material tendered for under \$1,000, and 2½ per cent. on the value of the material tendered for over that amount, must accompany each and every tender, otherwise it will not be entertained.

All tenders must bear the bona fide signatures of the contractor and his sureties (see specifications) or they will be ruled out as informal.

The Committee do not bind themselves to accept the lowest or any tender.

DANIEL LAMB,

Chairman Committee on Works,

Committee Room, Toronto, Nov. 27, 1893.

## TO CONTRACTORS

Sealed tenders will be received by the undersigned until noon on WEDNESDAY, THE 20TH DAY OF DECEMBER, 1893, for building an

### IRON OR STEEL BRIDGE

over Kettle Creek, in the village of Port Stanley, in the County of Elgin. Specifications and information can be obtained by application to the undersigned.

At the same time will also be received tenders for the construction of the substructure for the said bridge, consisting of two stone abutments and one stone pier, with a certain amount of piling and timber work.

Plans and specifications of this work can be seen, and blank forms of tender obtained at the office of the undersigned.

The lowest nor any tender necessarily accepted.

JAMES A. BELL,

Engineer County of Elgin,  
St. Thomas, Ont.

## WINDSOR WATER WORKS

### NOTICE TO MANUFACTURERS OF CAST IRON WATER PIPE.

Sealed Tenders will be received by the Secretary of the Board of Water Commissioners, Windsor, until 6 p. m. on the 10TH DAY OF DECEMBER, 1893, to be endorsed "Tender for Cast Iron Pipe," for furnishing, approximately 1,300 Tons of 30-inch Cast Iron Pipe and Necessary Specials.

Specifications may be seen at the office of the Board at Windsor, and at the office of the Engineer at Toronto.

For blank forms of tender and other information apply to the Secretary of the Board.

C. J. REID,

Sec., Board of Water Commissioners,  
Windsor, Ont.

WILLIS CHIPMAN,  
Engineer, 103 Bay, street, Toronto.

November 22nd, 1893.



## NOTICE TO CONTRACTORS

Tenders will be received by registered post, addressed to the City Engineer, Toronto, up to 11 o'clock a. m. on SATURDAY, DECEMBER 9TH, 1893, for the following work:

### A Brick Sewer on Moutray Street.

Plans and specifications may be seen and forms of tender obtained on and after December 4th, 1893, at the office of the City Engineer.

A deposit in the form of a marked cheque, payable to the order of the City Treasurer, for the sum of 5 per cent. on the value of the work tendered for under \$1,000, and 2½ per cent. on the value of the work tendered for over that amount, must accompany each and every tender, otherwise it will not be entertained. All tenders must bear the bona fide signatures of the contractor and his sureties (see specifications), or they will be ruled out as informal.

The Committee do not bind themselves to accept the lowest or any tender.

DANIEL LAMB,

Chairman Committee on Works,

Committee Room, Toronto, Nov. 24, 1893.

## Notice to Contractors

### CANADIAN CONTRACTORS' HAND-BOOK

A new and thoroughly revised edition of the *Canadian Contractors' Hand-Book*, consisting of 150 pages of the most carefully selected material, is now ready, and will be sent post-paid to any address in Canada on receipt of price. This book should be in the hands of every architect, builder and contractor who desires to have readily accessible and properly authenticated information on a wide variety of subjects adapted to his daily requirements.

Price, \$1.50; to subscribers of the CANADIAN ARCHITECT AND BUILDER, \$1.00. Address

C. H. MORTIMER, Publisher,

Confederation Life Building, TORONTO.

Montreal Office:  
64 Temple Building.

### LEGAL DECISIONS.

**CHENIER vs. THE CORPORATION OF HULL.**—In the Superior Court of Almer, Que., recently, Judge Galt gave his decision in this case, the particulars of which are as follows: The plaintiff who is a contractor, was given the contract by the corporation to construct certain water services. After the work had been partially completed the city took the contract out of Mr. Chenier's hands, and employed, another contractor to finish the work. Mr. Chenier having on hand a large stock of materials to be used in his contract took the matter into the courts. For over four years the case has been going on, witnesses being heard at almost every session of the court. The judge rendered his decision in favor of the plaintiff for the amount of \$1,087.

### A NEW CHEAP WHITE ENAMELED BRICK.

A recent patent covers a process for manufacturing a cheap white enameled brick for warehouse purposes, tunnels, dark passages, etc. The enamel, after being reduced to powder, is scattered or sieved in equal portions over the flat surface of the brick while the latter is at a bright red heat. The bricks are heated in a muffle kiln on an inclined plane, and a constant supply of red-hot bricks pass under the powdering sieve, all excess of enamel being used again. The powdered enamel immediately melts over the side of the bricks, adhering and forming a sound coating without soiling or running over the end. Any color of enamel powder may be used in conjunction with an enamel made to suit the quality of the clay, which may range from almost a silicate of alumina to a pure silica. The inventor of this process does not claim to be able to compete with a highly finished article, turned out for the best class of work, but the new brick is spoken of as filling the want now existing for a cheap white enameled brick, which is damp-proof, and a non-absorbent of dirt.

### CONTRACTS OPEN.

**BEDFORD, QUE.**—A scheme to light the streets by electricity is being considered.

**HALIFAX, N. S.**—The Dominion Government has selected the site for the new drill shed.

**HEMMINGFORD, QUE.**—The Roman Catholic congregation are preparing to build a new church.

**BERLIN, ONT.**—J. D. Bowman, County Clerk, will receive tenders until the 14th inst. for the purchase of \$20,000 worth of debentures.

**SELKIRK, MAN.**—Capt. Robinson is said to be about to erect a large saw mill here.—Mr. H. B. Mitchell, will also build a saw mill here.

**PETERBORO, ONT.**—The Town Engineer has been instructed to prepare plans for a new bridge to span the river a short distance above the old railway bridge.

**WATERLOO, ONT.**—Messrs. Lippert, Schaeffer & Co. have decided to erect a furniture factory here, to be four stories in height, with engine and boiler room attached.

**VICTORIA, B. C.**—It is reported that the proposed site for the contemplated Canada Western hotel has been purchased for a new post-office, customs house and inland revenue building.

**GEORGETOWN, ONT.**—A movement has been commenced to build and equip a factory for the manufacture of blankets. Messrs. Wm. McLeod and John Newton are interested in the project.

**KINGSTON, ONT.**—The Kingston, Napanee and Western Railway Company proposes to build a branch line of railway from a point in the township of Loughborough to Lake Sydenham.

**ORANGEVILLE, ONT.**—Engineer Chipman has recommended the construction of a system of waterworks for this town, at a cost of about \$50,000. The source of supply is to be from a well.

**DRUMMONDVILLE, QUE.**—The Drummondville Hydraulic and Manufacturing Co. has just been incorporated for the purpose of constructing certain dams on the River St. Francis. W. J. Watts, of this place is one of the promoters of the Company.

**STE. SCHOLASTIQUE, QUE.**—A bill has just passed the Quebec Legislature authorizing the cure and church wardens of l'Œuvre et Fabrique of the parish of Ste. Scholastique, in the district of Terrebonne, to grant aid towards the rebuilding of the convent in this village.

**PETROLEA, ONT.** G. S. McPherson, Town Clerk, will receive tenders until Wednesday, the 14th inst., for the construction of a tile drain on Eureka street in this town. Plans may be seen at the office of the Town Clerk and at the office of Messrs. Moore & Henry, architects, London.

**HAMILTON, ONT.**—T. Beasley, City Clerk, invites tenders until Saturday, the 20th of January, 1894, for the supply of

boards, plank, scantling, crossing timbers and cedar posts required by the corporation during the year 1894. Specifications may be seen at the office of the City Engineer.—It is said that Ald. Magill will erect a block of stores next year.

CHARLOTTETOWN, P. E. I.—J. W. Morrison, Secretary of Public Works, will receive tenders until Wednesday, January 17, 1894, for the repairing and extension of Murray River Wharf. Plans may be seen at the office of the Secretary and at the store of Mr. Cartney McClure, Murray River.—Tenders will also be received at Public Works Department until the 9th of January for building a new bridge across Martin's Creek, near Eldon.

MONCTON, N. B.—Mr. D. Pottinger, General Manager Intercolonial Railway, invites proposals until Thursday, the 28th inst., for the construction of a steel through bridge of five spans over the Narrows, Halifax Harbor, Nova Scotia, including piers and abutments containing about 6000 yards of ashlar masonry and 1000 yards of concrete. Plans may be seen at the Chief Engineer's office, Moncton, and at the office of the Station-Master, North street station, Halifax.

GALT, ONT.—Mr. F. W. Mellish, architect, is preparing plans for a two-story, nine room residence for Mr. J. McKenzie, to cost \$2,000. The same architect is preparing plans for a store and office block for Mr. R. G. Struthers. The building will be three stories in height, the first story to be fitted for stores, and the second and third floors as offices. The materials used will be brown pressed brick and Portage Entry stone trimmings.—Mr. W. Hallman is building four dwelling houses for Dr. Lowry, at a cost of about \$1,500 each from plans made by Mr. F. W. Mellish, architect.

OTTAWA, ONT.—The congregation of New Edinburgh Presbyterian church will meet shortly to consider the question of an enlargement of the Sunday school.—A meeting of the property owners of Gloucester township was held at Clarkston village last week to discuss the question of draining the large swamps in that neighborhood. The Government has offered to loan the necessary funds for twenty years to carry out the work. The matter will again be taken up at the next Township Council meeting.—A joint committee composed of members of Hull and Gatineau Point Councils recently waited on the Chief Engineer of the Public Works Department in regard to the erection of a bridge over Pond Creek. It was agreed that plans should be prepared at once for submission to the authorities.

LONDON, ONT.—Mr. J. F. Wood, of Ingersoll, proposes to erect a mammoth cold storage warehouse in this city, near the C. P. R. track.—The City Engineer has prepared the following estimate of the cost of carrying out the proposed improvements to the waterworks system, in accordance with Mr. Keefer's plans: steam pumping machinery, alterations and additions to pump house and connections, \$25,000; hydraulic pumping machinery, alterations to house and connections, \$30,000; additional springs, with connections, \$15,000; purchase of Byron dam and improving power, \$18,000; duplicate main of steel, 28-inch, \$68,000; main extensions, \$25,000; main extensions for London West, \$15,000; house services for next five years, \$15,000. The Council will apply to the Legislature for leave to borrow \$125,000 of this amount, and the ratepayers will be asked to vote on a by-law in January sanctioning the expenditure of \$58,000 for the new steel main.

MONTEAL, QUE.—Mr. Clement, of the firm of Clement & Pagnuelo, has written to the health Committee offering a piece of land situated between the two cemeteries as a site for the proposed contagious diseases hospital.—At the request of the Superintendent of waterworks, the Finance Committee of the City Council last week voted the sum of \$22,000 to replace the old breast wheel at the pumping station. The sum of \$16,000 was also

granted for sundry improvements to the pumping station.—The special Committee appointed to report on the extension of the Dalhousie Square Station by the C. P. R. Company, has recommended to Council (1) that the City should expropriate the square, bounded by Craig, Berri, Notre Dame and Lacroix streets, to turn it over to the company for the erection of the depot; (2) to bridge Notre Dame street over the railway tracks; (3) to subscribe \$150,000 towards the cost of the station, which should have a frontage of 300 feet on Craig street, be 66 feet deep, four stories high, and cost not less than \$350,000; and that in turn the company will turn over to the city, Bellerive Park, the military stores property, the Macdonald property, and the lot on the corner of Berri and Francois streets, the company to construct and maintain an overhead passage from Notre Dame st. to the station on Craig st., for foot passengers.

TORONTO, ONT.—The City Engineer is preparing plans for the widening of the Queen street subway.—The City Council has given notice of its intention to construct a sewer on May street, between the north side of Hill street and its north end, at an estimated cost of \$775.—A petition is being circulated among vessel owners and lake captains, for presentation to the Minister of Marine and Fisheries, requesting the erection of a lighthouse at Missis-sauga Point, at the mouth of the Niagara river.—Improvements are to be made to the building, No. 44 King St. East.—New plans for the improvement of the water front have been prepared, which locate the Ferry wharf first west of Yonge street, the Niagara beats wharf, between Yonge and Bay streets, and the Montreal and Hamilton boat wharves west of Lorne st. It is said that a local firm is ready to build a cold storage warehouse and fruit market on the block adjoining the Niagara wharf, provided they can start operations at an early date.—Building permits have been granted as follows: Guinane Bros., alterations and 2 story addition, 214 Yonge st., cost \$12,500; Mrs. Gillespie, 193 Church st., three att. 3 story bk. dwellings, n. e. cor. Shuter and Dalhousie sts., cost \$3,500.

#### FIRES.

Remillard's confectionery establishment at 110 McGill street, Montreal, was damaged by fire recently to the extent of \$3,000.—The Riendeau hotel at Longueuil, Que., was burned to the ground on the 1st inst. The building belonged to Edmond Guenn, of Montreal, and was insured for \$3,000.—J. W. Ross' general store at Sundridge, Ont., was burned last week. Loss, \$2,500.—The old Colcutt brewery on University avenue, Cobourg, Ont., now used as bolting works by F. F. Meehan, was destroyed by fire on Friday of last week. Mr. Meehan's plant was valued at \$3,000.—Messrs. Stanley & Dight's storehouse at Lucan, Ont., was burned on the first inst., with all its contents. Loss, \$10,000; partially covered by insurance.—The furniture factory of H. A. Wilder & Co., at 29 William street, Montreal, was damaged by fire to the extent of \$25,000 recently.—Fletcher's grist and saw mills at Flesherton, Ont., have been destroyed by fire.—The City Hotel at Jarvis, Ont., was burned to the ground recently.—The residence of Mr. James Murphy at Whitby, Ont., was destroyed by fire on Tuesday last. Loss, \$2,500; no insurance.

#### CONTRACTS AWARDED.

TORONTO, ONT.—The Property Committee of the Public School Board have awarded contracts as follows for the completion of the Leslie street school: carpenter work, Kain & Wilson, \$1,625; plastering, T. Gander, \$351; plumbing, Keith & Fitzsimmons, \$99; painting, J. A. Ber-ridge, \$184; heating, Smead, Dowd & Co.

MONTEAL, QUE.—The contract for the foundation for the new Worthington engine has been awarded by the Water Committee to Messrs. R. E. Edwards &

Sons, at \$1,185.50.—The Harbor Commissioners have awarded contracts as follows for the supply of timber and deals for 1894: W. H. Kelly, Montreal, round hemlock timber, pine deals and hemlock deals; Pembroke Lumber Co., Pembroke, Ont., hemlock face timber; J. & W. D. Brown, Quebec, pine face timber; William Mason & Sons, Ottawa, flat pine timber; Robert McIntyre, Calumet, round pine timber; W. M. Platt, Brighton, Ont., coping pine timber.

#### BUSINESS NOTES.

J. H. Larkin, builder, Hamilton, has assigned to F. H. Lamb.

Wm. S. Dockrill, plumber, Montreal, has assigned with liabilities estimated at \$3,000.

The partnership existing between Johcoeur and Apollinaires Gendreau, contractors, Montreal, has been dissolved.

Jos. Lebrun and Alfred Dumonier will carry on business in Montreal as contractors under the style of J. Lebrun & Co.

S. Swanton, contractor, 52 Victor ave., Toronto, has made an assignment to Geo. H. May. It is thought the assets and liabilities are about equal.

The Legal and Commercial Exchange report the following: S. Salloit & Co., contractors, Montreal, have dissolved.—Foisy & Leclair have formed a partnership as bricklayers and contractors in Montreal.—A partnership has been registered between Guisophe, Leonard & Co., builders, Montreal.—Wm. Loundes, builder, Halifax, N. S., has made an assignment.—Hall & Secord, builders, Brantford, Ont., has assigned to C. E. Oles.—Lessard & Lafleur will carry on business in Montreal as contractors.—Caron & Fils, contractors, Nicolet, Que., have assigned.

#### MOSAIC.

In order to reproduce a painting in mosaic the artists, or artisans, take a flat sheet of iron of the same size as the painting, surrounded by a border about an inch high. This receptacle is then filled with plaster, so as to obtain a perfectly flat surface. On this the outlines of the figures are drawn. The plaster is then cut up into small squares, which are removed and gradually replaced by as many squares of mosaic of the same size. In the holes left empty when the plaster is taken away, a new plaster made of travertine dust, lime and linseed oil is poured.

After three days this new plaster acquires the necessary consistency, and in this the artist sticks the little colored squares. When all the surface of the plaster is covered with these colored pieces of mosaic, the whole is washed with sand and water until it becomes quite smooth. The colored pieces are made of mixtures of different minerals, like arsenic, lead, glass, etc. These minerals are placed in an oven, and the different colors are obtained by the different degrees of heat, and as many as 28,000 various colors can be obtained.—Harper's Weekly.

As is well known, it is somewhat difficult to get vermilion surface to keep its brilliancy of colour. The following method gives good results: First give a priming coat of Venetian red, ground in oil; then apply a coat of vermilion and red lead, ground in oil and mixed with sufficient turpentine to produce a flat tint. On this apply an exactly similar coat, and finish by applying a free coat of good coach varnish.

There may be some of our readers who do not know the way in which zinc and lead may be used in interior painting. Of course, these pigments may never be mixed together for inside work, or even one coat applied on top of the other, because the result is sure to be a yellow appearance that will appear very soon after the painting is finished. If, however, a coat of alcoholic shellac is applied between the coats, lead and zinc may be used alternately without any disadvantage.

## MUNICIPAL DEPARTMENT.

### THE MANUFACTURE AND USE OF PAVING BRICK.

(Continued.)

There are two methods used for burning brick. The ordinary way in which common building brick are burned is in the updraft or clamp kiln. This furnishes good ordinary brick, but it is almost impossible to get a uniform product, not over 40 per cent. of the brick in a kiln being available for "pavers." The downdraft kiln secures a uniform and much higher temperature, a large percentage of the brick, from 80 to 90 per cent. in a well-designed and well-constructed kiln, being suitable for paving purposes.

In burning brick the fires must be started slowly in order to "water smoke" the brick without cracking them. In the brick, as they come from the machine, there is from 20 to 30 per cent. of water. About 50 per cent. of this water is the water of the pores, and is removed at a temperature of 212 deg. Fahr. in the drying. The balance is lost at a temperature of about 1,400 deg. Fahr. in the burning. The loss of the physical and chemical water of the brick is accompanied by a corresponding loss in weight, and a considerable shrinkage in the dimensions of the brick, as may be seen from the following table:—

	On leaving machine.	On leaving dryer.	Bred., not vitrified.	Vitrified.
Weight..	6.46 lbs.	5.79 lbs.	5.08 lbs.	5.08 lbs.
Length..	8 1/2 ins.	8 ins.	7 7/8 ins.	7 3/4 ins.
Breadth..	4 7/16 ins.	4 1/16 ins.	3 7/8 ins.	3 3/4 ins.
Thickness	2 1/2 ins.	2 1/4 ins.	2 1/8 ins.	2 ins.

Average of twelve samples.

Slow firing is continued until the smoke passing off shows no further signs of the water smoke (steam), after which the fires are gradually raised until the temperature throughout the kiln is sufficient to vitrify the brick, at which point it is held until they reach the proper point of vitrification, which is shown by the trial pieces or whole brick taken out through inspection holes in the top and sides of the kiln. After this the kiln is gradually cooled down and the brick removed. Too rapid cooling is detrimental, as the brick are rendered very brittle. By slow cooling the brick are annealed and rendered tough. The burning occupies from two to four days for water-smoking, from four to six days for burning proper and from three to five days for cooling.

In all lines of practical work experience with a given material is the only satisfactory method of determining the value of its various qualities. As in the case of cement, stone and wood, paving brick must be selected with due reference to the uses to which they are to be put; that is to say, to the nature and extent of the traffic they are to encounter and the character of the climate they are to withstand. A large percentage of clays are undoubtedly capable of producing brick suitable for country roads, light suburban travel and residence streets of towns or cities. From many can be made brick which will withstand the moderate traffic of the smaller cities of from 30,000 to 50,000 inhabitants. It is the writer's belief that clays can be found which, if properly manufactured and properly placed in the pavement, will outrival granite under the heaviest traffic, and some brick are now made which it is believed would prove economical under such traffic.

The colour in brick is no criterion of its value as a paving brick when comparing brick of various makes, but in inspecting brick from a single factory the colour will usually furnish a fairly safe guide as to the relative hardness, when the inspector is thoroughly acquainted with the particular manufacturer. Another criterion as to the character of any single make of brick is the comparative size. As the harder the brick is burned the smaller it becomes up to a certain limit, which must be determined for each make of brick; the unduly large brick may be unhesitatingly rejected as too soft. In general a brick for paving purposes must be homogeneous, free from uncushbed or lumpy material, especially if such material is not united by vitrification with the balance of the material of the brick. Vitrification is desirable, but not essential.

The disintegrating effects of frost are the most severe test a paving brick must stand, especially in streets of moderate traffic. Hence one of the first requisites of such a brick must be that it will not absorb a large percentage of water. The permissible ratio of absorption cannot be definitely fixed at any given percentage, for it is found that this ratio varies with different classes of brick. One class of brick, which seems to be uniformly made from clays which approach near to fireclays in character will admit 4 per cent. or 5 per cent. of water, and still not crumble through the action of frost, while others, if not burned hard enough to render them impervious to more than 2 1/2 to 3 per cent., will be rapidly disintegrated by the frost. A core of lamination affords a seam where the frost may enter, and is inadmissible in paving brick. Fire cracks should be limited in number and extent. The presence of lime, in itself, is not detrimental in limited quantities, yet this must not exist as lime pebbles, or it will render the product entirely unfit for use by disintegrating and crumbling it.

The specific gravity of a brick is somewhat of an index of its comparative value, as the more material contained in it the greater the density and other things being equal, the greater its resistance to abrasion, crushing, &c. A certain

**MUNICIPAL ENGINEERS, CONTRACTORS, AND MATERIALS.**

amount of toughness is desirable in a paving brick to prevent the splintering and breaking under traffic. This, quality, the writer believes, is at present over-estimated, as when laid in the street a brick can splinter only to a limited extent at the corners, after which the shape assumed is such as to greatly resist abrasion. The brick must be of sufficient transverse and crushing strength to resist all the demands of traffic with a sufficient factor of safety. Further than this these qualities are of little material value.

(To be Continued).

**DEBENTURES WANTED.**

Municipalities issuing debentures, no matter for what purpose, will find a ready purchaser by applying to **G. A. STIMSON, 9 Toronto Street, Toronto.** N.B.—Money to loan at lowest rates on first mortgage.

Municipal Officers, Contractors and others are requested to mention the **CONTRACT RECORD** when corresponding with advertisers.

Established 1841.

**THOROLD CEMENT**

MANUFACTURED BY  
**ESTATE OF JOHN BATTLE,**  
Thorold, Ontario.

GRAND TRUNK RAILWAY CO. OF CANADA.  
CHIEF ENGINEER'S OFFICE,  
HAMILTON, ONT., Oct. 17, 1893.

REPRESENTATIVES OF THE  
**ESTATE OF JOHN BATTLE,**  
THOROLD, ONT.

Gentlemen: In reply to yours of September 19th last as to the cement manufactured at the John Battle Works, Thorold, Ontario, we have been using it on this Division of the Grand Trunk Railway for many years, and have found it to be of good quality.

Yours truly,

**JOSEPH HOBSON,**  
Chief Engineer.

**Drummond McCall Pipe Foundry Company,**

**MONTREAL**

MANUFACTURERS OF

**CAST IRON WATER AND GAS PIPES**

WORKS: LACHINE, QUE.

PRICES ON APPLICATION.

**Ontario Water Meter Co., Ltd.**

MANUFACTURERS OF

**WATER METERS**

Meter Supports, Dial Extensions, Fixture Locks, Water Cart Registers, Strainers, Coupling Seals and Reservoir Indicators.


Send for Price Lists and Testimonials. Our meters are adopted and in use in over 500 cities and towns in Canada and the United States. Highly endorsed by leading Engineers. A guarantee for five years given with all Meters. All information furnished on application to

**A. C. WINTON, Secretary-Treas.**

Office: No. 23 Toronto Street, Toronto, Ont.

**MUNICIPAL OFFICIALS** should see to it that in the erection of town and city **PUBLIC BUILDINGS,** the installation of water works plant, etc., the advantages of . . .

**MINERAL WOOL**



are made use of for deadening sound in floors and partitions, insulation of heat and cold, fireproofing, etc., also **SECTIONAL MINERAL WOOL COVERING** for steam pipes, boilers, exposed water pipes, etc.

**CANADIAN MINERAL WOOL CO., Limited, 122 Bay Street, Toronto.**

Montreal Agent:

**GEO. A. COWAN, Room 23, 204 St. James St.**

**GEO. R. THOMPSON & CO.,**  
Agents, Winnipeg, Man.

**WILLIS CHIPMAN, B.A.Sc.,**

M. Can. Soc. C.E.; M. Am. Soc. C.E.;  
M. Am. W. W. Ass'n.

**CIVIL AND SANITARY ENGINEER**

Water Works - Sewerage  
Storage Disposal

103 BAY STREET TORONTO.

**J. McDOUGALL, C. E.,**

ENGINEER COUNTY OF YORK,

Consulting Engineer for Municipal Work.

Electric Railways and Bridges.

COURT HOUSE, TORONTO.

**JOHN GALT**

C. E. AND M. E. M. CAN. SOC. C. E.,

Consulting Engineer.

20 Years' Practical Experience in England, United States and Canada in Civil, Sanitary, Hydraulic, and Mechanical Engineering.

SPECIALTIES:

WATERWORKS, SEWERAGE, ELECTRIC RAILWAYS.

Office: Rooms 99 and 100,  
CANADA LIFE BUILDING, TORONTO.

**Fire Bricks and Cement**

DRAIN AND WATER PIPES

SANITARY EARTHENWARE

LONDON PORTLAND CEMENT

GUARANTEED GENUINE.

Paving and Scoria Bricks for Stables, Sidewalks, Yards, etc.

Large quantities on hand and to arrive. We handle only the best quality. Prices lower than ever.

**F. HYDE & CO.**

31 Wellington Street, - MONTREAL,

Sole Agents for

THE "GRAHTRYX" SMOKE TEST AND DISINFECTING MACHINE.

**PORTLAND CEMENT**

BEST AND CHEAPEST IN TORONTO.

JOSSON, PETERS and BURHAM Brands for highest class work.

WHITE HORSE, R. W., IMPERIAL, &c. FROM \$2.00 PER BARREL.

Nichols, Smythe & Co., - 25 George St., Toronto.

CEMENT CONTRACTORS TO THE CITY OF TORONTO.

Telephone 1948 or call and see us.

**CANADA PIPE AND FOUNDRY CO. . . . .**

MANUFACTURERS OF

**. . . . . Cast Iron Pipes and Special Castings**

Works: MONTREAL AND ST. HENRI, QUE.

CORRESPONDENCE SOLICITED.

**THE STANDARD DRAIN PIPE CO.**

OF ST. JOHNS, P. Q., (LIM.)

Manufacturers of

Salt-Glazed,

Vitrified

**SEWER**


**PIPES**

Double Strength

Railway Cul-

vert Pipes,

Inverts, Vents,



AND ALL KINDS OF FIRE CLAY GOODS.

**STEVENS & BURNS**

London, Ont.

To Municipal Corporations and Contractors:

. . . WE MANUFACTURE . . .


**Hydrants, Valves, Valve Boxes**

and Water Works Supplies generally,

INCLUDING

Tools for tapping mains under pressure

and Service Brass Work of all descriptions.



THE

**ENGLE CREMATING CLOSET**

A SUBSTITUTE FOR PRIVY VAULTS AND CESS POOLS.

A PERFECT SANITARY TRIUMPH,

Applicable to the uses of schools, colleges, hospitals, factories, asylums and dwellings.

This closet is invaluable where sewer and water privileges are not obtainable, possessing all the convenience of the modern water closet.

Manufactured and erected in sizes suitable to any number of persons, by

**TORONTO FURNACE & CREMATORY CO., LTD.**

8 & 10 Queen St. East, TORONTO.



WRITE FOR CATALOGUE CONTAINING FULLEST INFORMATION AND EXPLANATION.

**THE G. & J. BROWN MFG. CO.**

Railway and Contractors' Plant.

**BRIDGE BUILDERS**

BELLEVILLE, ONT.

CENTRAL BRIDGE AND - - ENGINEERING COMPANY, (LIMITED) Peterborough, Ont. WM. H. LAW, Manager and Engineer. MANUFACTURER OF

RAILWAY AND HIGHWAY BRIDGES Viaducts, Piers, Roofs, Turntables and Girders in Steel and Iron. Tension members forged without welds. Riveting done by hydraulic or compressed air machines. Specialties: Good workmanship and strict adherence to specifications and drawings. CAPACITY: 2,000 TONS PER ANNUM.

ISAAC USHER & SON, THOROLD, ONT. Manufacturers of

QUEENSTON CEMENT Proved by Government tests to be the best Canadian natural cement. Write for prices, &c.

OUR SALES OF "BURHAM" Portland Cement ..

for the past 8 months have been 25,499 CASKS. "Burham" Brand outranks all others. Try it and be convinced.

Sole Consignees for Canada: McRAE & CO., OTTAWA

Prices of Building Materials. CONDITION OF THE MARKET. The market for builders' supplies remains unchanged, no particular lines being in very brisk demand. The cement trade is quieter than for some time past, and prices are about the same. Hardware is also quieter, shelf goods only meeting with a fair demand.

LUMBER. CAR OR CARGO LOTS.

Table with columns for Toronto and Montreal prices for various lumber items like planks, flooring, and shingles.

Table with columns for Toronto and Montreal prices for various construction materials like cutting planks, cedar, and shingles.

Table with columns for Toronto and Montreal prices for various types of brick, including common walling and sewer.

Table with columns for Toronto and Montreal prices for various types of brick, including pressed brick and ornamental.

SAND. Per Load of 1 1/2 Cubic Yards

STONE. Common Rubble, per cubic delivered

Table with columns for Toronto and Montreal prices for various stone items like rubble, granite, and limestone.

SLATE. Roofing (\$ square).

Table with columns for Toronto and Montreal prices for various paint items like white lead and red lead.

Table with columns for Toronto and Montreal prices for various lamp and oil items.

CEMENT, LIME, etc.

Table with columns for Toronto and Montreal prices for various types of cement and lime.

HARDWARE.

Table with columns for Toronto and Montreal prices for various hardware items like nails, steel, and wire.

Table with columns for Toronto and Montreal prices for various types of nails.

Table with columns for Toronto and Montreal prices for various types of finishing nails.

Table with columns for Toronto and Montreal prices for various types of slating nails.

Table with columns for Toronto and Montreal prices for various types of common barrel nails.

Table with columns for Toronto and Montreal prices for various types of clinch nails.

Table with columns for Toronto and Montreal prices for various types of sharp and flat pressed nails.

Table with columns for Toronto and Montreal prices for various types of structural iron.

Table with columns for Toronto and Montreal prices for various types of iron pipe.

INDEX TO ADVERTISEMENTS In the "Canadian Architect and Builder."

Large index table listing various professional services and suppliers like Architects, Church and School Furniture, Grates and Tiles, Plumbing Supplies, etc.