









IMAGE EVALUATION TEST TARGET (MT-3)



Photographic Sciences Corporation

**23 WEST MAIN STREET
WEBSTER, N.Y. 14580
(716) 872-4503**

**CIHM/ICMH
Microfiche
Series.**

**CIHM/ICMH
Collection de
microfiches.**



Canadian Institute for Historical Microreproductions / Institut canadien de microreproductions historiques

© 1986

Technical and Bibliographic Notes/Notes techniques et bibliographiques

The Institute has attempted to obtain the best original copy available for filming. Features of this copy which may be bibliographically unique, which may alter any of the images in the reproduction, or which may significantly change the usual method of filming, are checked below.

L'Institut a microfilmé le meilleur exemplaire qu'il lui a été possible de se procurer. Les détails de cet exemplaire qui sont peut-être uniques du point de vue bibliographique, qui peuvent modifier une image reproduite, ou qui peuvent exiger une modification dans la méthode normale de filmage sont indiqués ci-dessous.

- ☐ Coloured covers/
Couverture de couleur
- ☐ Covers damaged/
Couverture endommagée
- ☐ Covers restored and/or laminated/
Couverture restaurée et/ou pelliculée
- ☐ Cover title missing/
Le titre de couverture manque
- ☐ Coloured maps/
Cartes géographiques en couleur
- ☐ Coloured ink (i.e. other than blue or black)/
Encre de couleur (i.e. autre que bleue ou noire)
- ☐ Coloured plates and/or illustrations/
Planches et/ou illustrations en couleur
- ☐ Bound with other material/
Relié avec d'autres documents
- ☐ Tight binding may cause shadows or distortion along interior margin/
La reliure serrée peut causer de l'ombre ou de la distorsion le long de la marge intérieure
- ☐ Blank leaves added during restoration may appear within the text. Whenever possible, these have been omitted from filming/
Il se peut que certaines pages blanches ajoutées lors d'une restauration apparaissent dans le texte, mais, lorsque cela était possible, ces pages n'ont pas été filmées.

- ☐ Coloured pages/
Pages de couleur
- ☐ Pages damaged/
Pages endommagées
- ☐ Pages restored and/or laminated/
Pages restaurées et/ou pelliculées
- ☒ Pages discoloured, stained or foxed/
Pages décolorées, tachetées ou piquées
- ☐ Pages detached/
Pages détachées
- ☒ Showthrough/
Transparence
- ☐ Quality of print varies/
Qualité inégale de l'impression
- ☐ Includes supplementary material/
Comprend du matériel supplémentaire
- ☐ Only edition available/
Seule édition disponible

- ☒ Additional comments: [Printed ephemera] 1 sheet (verso blank)
Commentaires supplémentaires:

This item is filmed at the reduction ratio checked below/
Ce document est filmé au taux de réduction indiqué ci-dessous.

10X	12X	14X	16X	18X	20X	22X	24X	26X	28X	30X	32X
						☒					

The copy filmed here has been reproduced thanks to the generosity of:



New Brunswick Museum
Saint John

The images appearing here are the best quality possible considering the condition and legibility of the original copy and in keeping with the filming contract specifications.

Original copies in printed paper covers are filmed beginning with the front cover and ending on the last page with a printed or illustrated impression, or the back cover when appropriate. All other original copies are filmed beginning on the first page with a printed or illustrated impression, and ending on the last page with a printed or illustrated impression.

The last recorded frame on each microfiche shall contain the symbol ➡ (meaning "CONTINUED"), or the symbol ▼ (meaning "END"), whichever applies.

Maps, plates, charts, etc., may be filmed at different reduction ratios. Those too large to be entirely included in one exposure are filmed beginning in the upper left hand corner, left to right and top to bottom, as many frames as required. The following diagram illustrates the method:



L'exemplaire filmé fut reproduit grâce à la générosité de:

New Brunswick Museum
Saint John

Les images suivantes ont été reproduites avec le plus grand soin, compte tenu de la condition et de la netteté de l'exemplaire filmé, et en conformité avec les conditions du contrat de filmage.

Les exemplaires originaux dont la couverture en papier est imprimée sont filmés en commençant par le premier plat et en terminant soit par la dernière page qui comporte une empreinte d'impression ou d'illustration, soit par le second plat, selon le cas. Tous les autres exemplaires originaux sont filmés en commençant par la première page qui comporte une empreinte d'impression ou d'illustration et en terminant par la dernière page qui comporte une telle empreinte.

Un des symboles suivants apparaîtra sur la dernière image de chaque microfiche, selon le cas: le symbole ➡ signifie "A SUIVRE", le symbole ▼ signifie "FIN".

Les cartes, planches, tableaux, etc., peuvent être filmés à des taux de réduction différents. Lorsque le document est trop grand pour être reproduit en un seul cliché, il est filmé à partir de l'angle supérieur gauche, de gauche à droite, et de haut en bas, en prenant le nombre d'images nécessaire. Les diagrammes suivants illustrent la méthode.

PROSPECTUS

OF

THE SAINT JOHN SUSPENSION BRIDGE COMPANY.

At the last Session of the General Assembly of this Province, an Act was passed to Incorporate the undersigned, his associates, and assigns, by the name of "THE SAINT JOHN SUSPENSION BRIDGE COMPANY," for the purpose of constructing a Suspension Bridge, of Iron Wire, across the Falls of the River Saint John, at Split Rock, near the City of Saint John; the Capital of the Company to be £20,000, divided into four thousand shares of £5 each, with power to increase the Stock to £40,000, when necessary.

The Act contains the usual provisions for the organization and management of the Company, and for the annual election of five Directors, each holding not less than twenty shares of Stock; each share of Stock to give one vote in the choice of Directors, and on all other questions affecting the business of the Company. Power is given to enter upon lands on both sides of the River, to make and complete the necessary erections for the Bridge, and to survey and lay out roads and approaches to it, as also to set up turnpike gates and toll houses at either end of the Bridge, and to demand and receive tolls, not exceeding the following rates: For every foot passenger two-pence; for every horse, one shilling; every carriage drawn by one horse, with one person, two shillings; each additional horse, sixpence; each additional person in the carriage, two-pence; neat cattle, four-pence each; sheep, calves and hogs, half-penny each.

The Bridge to be completed in three years after the passing of the Act, otherwise the operation of the Act to cease.

The Act further provides, that the Bridge shall be constructed of iron wire or chains, in all respects of sufficient strength and quality to render it safe for life and property; and that it shall not be opened for public use until it is certified to the Lieutenant Governor by a competent engineer to be appointed by him, that the Bridge is in all respects of sufficient strength and materials for the purpose for which it is intended.

This Act is not to come into effect until Her Majesty's Royal Assent is thereunto had and declared.

So soon as the Royal Assent is declared, it is the intention of the Undersigned, under the powers and privileges granted by the Act, to commence the construction of the Suspension Bridge therein mentioned, and complete the same as soon as possible, of the following dimensions, or as near thereto as circumstances will admit.

The length of roadway between the towers of suspension will be about five hundred feet; this roadway, as provided by the Act, will be at least seventy feet above high water level in the River below. At each end of this roadway, there will be an approach of about one hundred feet, making the whole length of the Bridge about seven hundred feet; the width of the roadway will be about twenty-three feet, with a carriage way of fifteen feet in the centre, and a foot way on each side, four feet wide. The Bridge will be supported by four iron wire cables of not less than five and a half inches in diameter, to be carried over a granite tower at each end, such towers to be not less than thirty-five feet in height above the roadway, resting on sufficient foundations, and of proportionable size.

All the wood work of the Bridge to be of hachmatac, or other wood of the first quality in the country, and all other materials to be of the best quality. The whole wood work to be well painted as far as necessary, and the wire cables and iron work to be well prepared and coated to prevent corrosion.

The Undersigned proposes to construct the whole Bridge and its approaches, with toll houses, gates, and every other requisite for its use, and to the satisfaction of the Engineer to be appointed by the Lieutenant Governor, for the sum of Twenty Thousand Pounds New Brunswick currency, including compensation for land occupied or damaged. This sum of £20,000 to be divided into 4000 shares of £5 each, as provided by the Act, payable as follows: One half the amount subscribed by each Shareholder to be paid on the completion of the said Bridge, and on its being certified as ready for public use; and the remaining half of the subscriptions in three, six, nine, and twelve months thereafter, with interest until paid. The Bridge and all its appurtenances and privileges to be then delivered to the shareholders, free of all claims, demands and incumbrances whatsoever; and all tolls received or earned in the meantime to be then accounted for to the Shareholders.

Saint John, N. B., 18th May, 1849.

WILLIAM K. REYNOLDS.

