




**IMAGE EVALUATION
TEST TARGET (MT-3)**



**Photographic
Sciences
Corporation**

23 WEST MAIN STREET
WEBSTER, N.Y. 14580
(716) 872-4503 8

18
20
22
25

**CIHM
Microfiche
Series
(Monographs)**

**ICMH
Collection de
microfiches
(monographies)**



Canadian Institute for Historical Microreproductions / Institut canadien de microreproductions historiques

10
01

© 1991

The Institute has attempted to obtain the best original copy available for filming. Features of this copy which may be bibliographically unique, which may alter any of the images in the reproduction, or which may significantly change the usual method of filming, are checked below.

- Coloured covers/
Couverture de couleur
- Covers damaged/
Couverture endommagée
- Covers restored and/or laminated/
Couverture restaurée et/ou pelliculée
- Cover title missing/
Le titre de couverture manque
- Coloured maps/
Cartes géographiques en couleur
- Coloured ink (i.e. other than blue or black)/
Encre de couleur (i.e. autre que bleue ou noire)
- Coloured plates and/or illustrations/
Planches et/ou illustrations en couleur
- Bound with other material/
Relié avec d'autres documents
- Tight binding may cause shadows or distortion
along interior margin/
La reliure serrée peut causer de l'ombre ou de la
distorsion le long de la marge intérieure
- Blank leaves added during restoration may appear
within the text. Whenever possible, these have
been omitted from filming/
Il se peut que certaines pages blanches ajoutées
lors d'une restauration apparaissent dans le texte,
mais, lorsque cela était possible, ces pages n'ont
pas été filmées.
- Additional comments: /
Commentaires supplémentaires:

This item is filmed at the reduction ratio checked below/
Ce document est filmé au taux de réduction indiqué ci-dessous.

				10X					12X					14X					16X					18X					20X					22X

Bibliographic Notes / Notes techniques et bibliographiques

st original
copy which
alter any
may
ing, are

L'Institut a microfilmé le meilleur exemplaire qu'il lui a été possible de se procurer. Les détails de cet exemplaire qui sont peut-être uniques du point de vue bibliographique, qui peuvent modifier une image reproduite, ou qui peuvent exiger une modification dans la méthode normale de filmage sont indiqués ci-dessous.

- Coloured pages/
Pages de couleur
- Pages damaged/
Pages endommagées
- Pages restored and/or laminated/
Pages restaurées et/ou pelliculées
- Pages discoloured, stained or foxed/
Pages décolorées, tachetées ou piquées
- Pages detached/
Pages détachées
- Showthrough/
Transparence
- Quality of print varies/
Qualité inégale de l'impression
- Continuous pagination/
Pagination continue
- Includes index(es)/
Comprend un (des) index

Title on header taken from: /
Le titre de l'en-tête provient:

- Title page of issue/
Page de titre de la livraison
- Caption of issue/
Titre de départ de la livraison
- Masthead/
Générique (périodiques) de la livraison

ack)/
ou noire)

stortion

e ou de la

may appear
ese have

ajoutées
ns le texte,
ges n'ont

cked below /
indiqué ci-dessous.

18X	20X	22X	24X	26X	28X	30X	32X
					✓		

The copy filmed here has been reproduced thanks to the generosity of:



Library of the National Archives of Canada

The images appearing here are the best quality possible considering the condition and legibility of the original copy and in keeping with the filming contract specifications.

Original copies in printed paper covers are filmed beginning with the front cover and ending on the last page with a printed or illustrated impression, or the back cover when appropriate. All other original copies are filmed beginning on the first page with a printed or illustrated impression, and ending on the last page with a printed or illustrated impression.

The last recorded frame on each microfiche shall contain the symbol \rightarrow (meaning "CONTINUED"), or the symbol ∇ (meaning "END"), whichever applies:

Maps, plates, charts, etc., may be filmed at different reduction ratios. Those too large to be entirely included in one exposure are filmed beginning in the upper left hand corner, left to right and top to bottom, as many frames as required. The following diagrams illustrate the method:



L'ex
géné

Les
plus
de la
confé
filma

Les
papie
par le
derni
d'imp
plat,
origin
prem
d'imp
la de
empr

Un d
derni
cas: f
symb

Les
filmé
Lors
repro
de l'a
et de
d'ima
illust

I thanks

L'exemplaire filmé fut reproduit grâce à la
générosité de:

La bibliothèque des Archives
nationales du Canada

ality
ibility
e

Les images suivantes ont été reproduites avec le
plus grand soin, compte tenu de la condition et
de la netteté de l'exemplaire filmé, et en
conformité avec les conditions du contrat de
filimage.

filmed
on
mpres-
All
on the
re-
rinted



Les exemplaires originaux dont la couverture en
papier est imprimée sont filmés en commençant
par le premier plat et en terminant soit par la
dernière page qui comporte une empreinte
d'impression ou d'illustration, soit par le second
plat, selon le cas. Tous les autres exemplaires
originaux sont filmés en commençant par la
première page qui comporte une empreinte
d'impression ou d'illustration et en terminant par
la dernière page qui comporte une telle
empreinte.

e
ON-
D"),

Un des symboles suivants apparaîtra sur la
dernière image de chaque microfiche, selon le
cas: le symbole \rightarrow signifie "A SUIVRE", le
symbole ∇ signifie "FIN".

at
to be
d
ft to
is
the

Les cartes, planches, tableaux, etc., peuvent être
filmés à des taux de réduction différents.
Lorsque le document est trop grand pour être
reproduit en un seul cliché, il est filmé à partir
de l'angle supérieur gauche, de gauche à droite,
et de haut en bas, en prenant le nombre
d'images nécessaire. Les diagrammes suivants
illustrent la méthode.



(All rights reserved.)

ADVANCE PROOF—(Subject to revision).

This Proof is sent to you for discussion only, and on the express understanding that it is not to be used for any other purpose whatsoever.—(See Sec. 39 of the Constitution.)

Canadian Society of Civil Engineers.

INCORPORATED 1867

TRANSACTIONS.

N.B.—This Society, as a body, does not hold itself responsible for the facts and opinions stated in any of its publications.

DESIGN AND CONSTRUCTION OF THE AVON BRIDGE.

By R. F. UNIAKER, M. Can. Soc. C.E.

To be read 24th October.

The problem of renewing the old toll bridge at Windsor, known as the Avon Bridge, has for years been looked upon as a perplexing and costly undertaking, and it was not until the early part of 1886 that actual steps were taken by the Government of Nova Scotia to take over the old bridge, open it free to the public, and make provision for its renewal, when in the interests of the public safety this should become necessary.

The old bridge was built in the year 1836, and consisted of five spans, varying in length from 147 to 162 feet in clear, supported by piers and abutments of close faced cribwork with cribwork approaches. The height of piers was from 45 to 50 feet. Ordinary tides rise 27 feet, spring tides 34 feet. The trusses were T-ways wooden lattice, double, with double chords top and bottom. The whole of the trusses were built of 2" planking, and housed in. They had been supplemented by wooden arches springing from about 6 feet below the floor; an additional pier had also been built under the centre of one of the spans. The structure had settled and warped considerably, in some places as much as four feet, and all indications pointed to the fact that it would soon become necessary to take steps for its renewal.

The structure had been purchased by the Provincial Government from the stock Company who had hitherto owned it, and it was at once declared free of toll to the public for ordinary traffic. Some repairs were put upon it, extra vigilance being exercised to prevent heavy and continuous traffic, and with those precautions the public were allowed the use of it, until such a time as the progress of the new work would render it necessary to close it altogether.

The question of renewing the bridge having been decided on, it was next to be determined what style of structure should be erected.

Besides the plan selected, two designs were submitted. One was for four spans of iron 200 feet each between end piers, supported by piers and abutments of close faced cribwork filled with concrete; roadway 18 feet in clear with two footways 5 feet each; estimated cost \$56,000. The second design was for four spans of Howe Truss of wood 160 feet each, and two smaller spans of wood 120 feet and 50 feet respectively; piers to be of close faced cribwork filled with stone, estimated cost \$36,000.

The first would have made a strong and handsome structure, but the cost was considered excessive. The plan for a structure altogether of wood was strongly advocated by adherents of the old system, who argued

that since the old wooden bridge had stood so long, a similar structure would answer all requirements. This view at first sight seemed reasonable enough, but when we consider the fact that the bridge had in its lifetime undergone a series of repairs and additions, and that such costly repairs together with the first cost of the bridge would go for naught in considering its reconstruction, it was not thought desirable in view of the experience of the past to project a similar experience into the future.

Before taking up and describing the supplementary and adopted plan, it may be as well to state some of the reasons why a masonry substructure did not enter into our calculations. The experience gained in this Province, from bridges built across tidal estuaries of the Bay of Fundy, goes to show that masonry structures built in these places have invariably proved failures, whereas old bridges that have been built of cribwork, as far as the piers are concerned, have stood firm and sound, without appearance of decay below high water mark for half a century. A most striking example of the failure of masonry is close to this bridge in the Windsor and Annapolis Railway Bridge, crossing the Avon River a few hundred feet upstream. This is a rivetted iron lattice bridge of the English type, with river spans 166 feet centre to centre of piers. The piers were completed in the year 1869, and are of regular coursed ashlar masonry. Since that time several thousand dollars have been expended on them in repairs. The face stones had been connected by iron dogs or clamps, which has not prevented the destructive process which was threatening the stability of the structure; the effect of tides and frost became each year more apparent, the piers became cracked, these cracks seeming to extend completely through them so much that they were considered unsafe, and condemned by the Provincial Government. The Railway Company have surrounded these piers with close-laced cribwork, leaving a clear space of about 3 feet all around which space was filled with concrete, and iron rods passed through the piers outside to outside, making a permanent and substantial job, though somewhat detracting from the dignity of the structure.

Precisely the same course was adopted on the Intercolonial Railway Bridge at Sackville, N.B., and extensive repairs and renewals have been made to the piers of the Railway bridge across the Shubenacadie, both tidal rivers of the Bay of Fundy.

These and other examples, together with the excessive cost, precluded the adoption of masonry.

The form of the structure as adopted and built may be described as follows: Beginning at the Windsor side was a small span of iron 50 feet centre to centre of end pins, then four spans of 150 feet each, and a shore span on the Falmouth side of 110 feet. There were five piers placed 162 feet apart centres, each pier consisting of two cylindrical columns each 5 feet inside diameter 19' 1" apart centre to centre, built of steel plates $\frac{3}{4}$ " in thickness, the joints both vertical and horizontal butted together and connected by steel bands $4\frac{1}{2}$ " x $3\frac{1}{2}$ " rivetted on the outside. The bottom of each column was provided with a flange turning outwards, formed by bending a 3" x 4" angle iron and riveting it on. This bottom flange in each instance rested upon the bed rock. The distance from a little above low water to the underside of the cap was divided into three spaces by four horizontal struts, each strut consisting of two laced channels butting against the columns, and secured by connecting plates. Pins were placed in the ends of each strut, and all connected with $1\frac{1}{2}$ " round iron rods with turnbuckle adjustment. Each pair of columns was enclosed up to 2 feet above low water with a cribwork of square timber 20' x 40' outside measurement. Spaces 8' x 8' were left in the cribwork, where the columns would come, and these spaces together with the cylinders themselves were filled to the top with concrete; the remaining voids in the cribs were filled with stone. Each column was capped by a circular plate and an ornamental casting *cyano recta*. Two 12" rolled beams, 60 lbs. per foot each, extended across the columns secured to the caps, and upon these beams rested the bed plates of the trusses.

To protect the sway bracing against the heavy ice floes, a system of sheathing was built between the columns, enclosing the rods and struts on each side from high water down with 1" plank, placed vertically, and bolted through and through, wooden struts being placed at intervals between them to keep the planking the right distance apart. As a further precaution, extra cribwork with stone filling was built up the same section as before to the second horizontal strut, or 26 feet below the floor of the bridge.

The height of each pair of columns from finished floor of bridge to surface of rock foundation as built was —

Pier No. 1.....	47.36
" 2.....	59.84
" 3.....	49.65
" 4.....	53.44
" 5.....	55.63

The columns varied slightly in height, that given is the average height of each pair.

The cribs were built on shore, and sufficient ballast placed in them to partially submerge them. They were then towed to their place, and all the voids except those reserved for the columns were filled with stone at time of low water.

The bed rock extends across the stream; in some places it is bare, at others it is covered with from two to six feet of mud and silt. Means had been provided for removing this deposit from within the cribs, but this was not found necessary, for when the cribs were once placed in position, the increased tidal current caused by contracting the water-way completely scoured this loose material out, leaving the rock bare, and any loose stones or detached boulders were removed by grappels.

As an additional precaution against any tendency of the cylinders to slide on the rock, it was determined to secure them by iron dowels. Nine of these were used in each column. A rough floor was placed across the crib, and the exact position of each cylinder marked upon it; auger holes were bored as guides, and the rods of two inch round iron tempered at the end, and fashioned to a rock drill point, were jammed into place. No difficulty was found in thus drilling three feet into the rock, leaving about five feet projecting.

At this stage preparations were made for lowering the bottom sections into place. The lengths of these sections as shipped vary from 9½ to 23½ feet. The roof and side covering had by this time been removed from the old bridge, and overhead braces were secured strong enough to take the weight of sections, which were lowered into place through the floor by block and tackle. A wooden cross head was fixed to the top of each section, the centre marked on it, and the cylinder accurately centred by means of a suspended plumb bob. The section was secured by wooden shores against the inside of the crib, and everything was now ready for the concrete filling. The materials for this were brought alongside in a scow. The mode of laying the concrete as practised here, in from five to twelve feet of running water, is a somewhat novel experiment, and the success which attended it in this case will lead to its adoption in other instances in this province.

This point has been referred to by Mr. Murphy in his paper on Concrete Structures, read before this Society; * but a more detailed account of it will perhaps be in keeping with the subject of this paper. Coarse brown paper bags, well stiffened with glucose, of a capacity of two cubic feet, were employed. A small wooden tray, suspended on trunions at the end of a pole, was used, and could be tipped at any position by the workman guiding the pole by a cord attached to the back of the tray. The bag was placed upon the tray, and about one cubic foot of concrete placed in it, the superfluous paper being roughly fiddled down. The whole was raised from above by a rope attached to the handle, guided into place by a

* Concrete as a Substitute for Masonry in Bridge Work, by M. Murphy, Trans. Vol. II., Page 79, Feby., 1888.

man standing on a plank placed across the top of section, and tipped at the proper time. This operation was repeated very quickly, the paper dissolving and breaking up almost as soon as the bottom was reached, allowing the concrete to flow into any cavities or irregularities in the rock under the cylinder, and forming a cover bed of concrete. This operation was continued until the cylinders were filled to within a foot or two of the bottom, and then the voids around them filled to the top of ribs.

As soon as a pair of bottom sections were secured in place, levels were taken on the top of them, and the exact height from the top of each to finished floor was at once sent to the Dominion Bridge Co., contractor for the new work, thus enabling them to send the proper length of sections to comply with the column. The same operation was performed for each of the foundations, the concrete gang being on hand as soon as the ground had placed the bottom sections in position.

Before the cribs were erected, the Falmouth span at the shore end caught fire and soon dropped into the river, the trusses breaking off at the pier, and the barge mass floating downstream with the tide. Up to this time the public had seen none of the old bridge. Our located points for pier No. 5 were of course gone, and a quick and ready means had to be adopted for setting the cylinders in proper position. This was effectually done by means of steel wire fixed in position over centre of each cylinder. Two plus points were provided as far as convenient on the old floor, the distance between them was about 160 feet, and we had 54 feet to centre of axis over. These distances were first carefully laid out on the old floor, and the points fixed on the wire which was stretched clear off the floor with a plummet attached at this point, and giving the wire the same curve it would have in its proper position. The wires were next drawn across the opening, with plummet attached, brought to the same line, and made fast. This was done on a calm night, and proved a very accurate means of setting these columns.

The cribs for piers Nos. 4 and 5 were built larger than the rest, being 51 x 50 feet outside measurement. Shear-heads were erected on the last crib for handling the sections. Through some accidental cause some of the ballast had fallen into the voids of this crib reserved for the columns, and it became necessary to employ a diving crew to remove them. With this exception the operation of setting the bottom sections as previously described was performed for each of the piers.

The time of setting these sections was as follows:

Pier No. 1 July 19th, 1887.

"	2	"	25th	"
"	3	"	28th	"
"	4	Aug. 30th	"	"
"	5	"	19th	"

Two periods of low tide were generally sufficient for setting these sections. The first tide was sufficient for a pair of them to be lowered, and they were grouted and cemented at the next.

The foundations by this time were all ready for the iron men to proceed with their work of completing the columns and connecting the sway bracing; but owing to unfortunate delays caused by unforeseen difficulties, the remainder of the foundation did not arrive on the ground until late in the fall. The process of handling on the sections proceeded with energy, the sway bracing was connected, and concrete filling followed on as fast as each section was riveted. Cold weather suddenly came, and with it a run of ice in the river. Piers Nos. 1, 2 and 3 had been completed and filled with concrete up to high water, pier No. 4 partially finished, and pier No. 5 had to be abandoned without any bracing or concrete filling above low water. Urgent efforts were made to get these finished, but with the river now almost blocked with floating ice, the men's lives were in danger, and the work had to be left, not however till the 50 feet span had been swung, and two sets of false work for the next span had been carried away. Attempts to get the sheathing in place failed, but some additional protection of round timber had been built around the cylinders.

The columns were now left in a seemingly precarious condition, with out the trusses to stiffen them longitudinally, the cross bracing exposed to heavy ice floes, which could strike them obliquely with the force of the rushing tide, and some of them only partially filled with concrete, or not at all.

The winter months passed, and the proverbial oldest inhabitant failed to recollect larger or more continuous flows of heavy ice than the Ayon river experienced during that time. When spring came it was found that pier No. 4 had experienced some dents above the concrete filling, and one of the beams was broken. Pier No. 5 which had no bracing or concrete filling was partially demolished, the rest stood firm and perfectly true. The night fairly be considered a pretty severe test, and a sufficient answer to much adverse criticism on the adaptability of such a structure for the Ayon River.

Operations were resumed in the month of May and prosecuted to completion. The injuries to the columns had been repaired, the missing plates replaced and filled to the top with concrete. The work proceeded with rapidity, and the last span was swung in the first week in July. Soon afterwards the bridge was opened for traffic.

The superstructure is the ordinary type of American pin, connected Pratt truss with an ornamental iron lattice hand railing on each side. The specifications were the same as generally adopted under the Nova Scotia Bridge Act for non-ferrous, with special clauses and modifications to suit this particular case, and as they would present nothing new it will not be necessary to reproduce them here, beyond a few of the principal requirements.

One span 50 feet between end pins.

Number of panels, 5.

Depth of truss, 8 feet.

Four spans, 130 feet each between end pins.

Number of panels, 10.

Depth of trusses, 22 feet.

One span 110 feet between end pins.

Number of panels, 7.

Depth of truss, 22 feet.

Roadway throughout 18 feet in clear.

No footways.

Rolling load 1,350 lbs. per lined foot, or 75 lbs. per square foot of roadway.

Ultimate tensile strength of iron at least 50,000 lbs. per square inch, an elastic limit not less than 26,000 lbs. per square inch, and a minimum elongation of 20 per cent. in 8 inches. Tensile strain produced in any member not to exceed 10,000 lbs. per square inch. Working strain reduced on girders, hip verticals and beam hangers. Working compressive strain not to exceed 8,000 lbs. per square inch reduced by formula.

The cylinders were to be put together in sections of not greater length than 8 feet of $\frac{3}{4}$ boiler plate hot rivetted, no screw bolts to be allowed in connecting the sections. On top of each pair of cylinders there were to be two rolled I beams, 12 inches in depth, 60 lbs. per foot each, with plates and stiffening T's to support trusses.

Considerable work was done on the approaches. The old abutment on the Windsor side was cut down to the foundation, and rebuilt. The floor in the approaches is supported by trestles resting on the old work at about high water level, and has a grade of 1 in 20.

The iron superstructure, complete together with the columns, was contract work, and built by the Dominion Bridge Co., Engineers and Contractors, Montreal. The preparation of the foundations, cribwork, concrete filling, together with the work on approaches, was all performed by day's work, under Government superintendence.

Supplying material, such as sand, gravel, stone and timber, was generally let by contract, the contractor delivering the material at bridge site as required.

A contract was also let for building additional cribwork around the cylinders up to within 26 feet of floor

COST OF WHOLE WORK.

Erection of iron superstructure and column.....	\$32190
Sub-structure (days work).....	22300
Shanting cribs and removing old piers (contract).....	1760
	<hr/>
	\$56315

In looking at the cost of this work, it must be remembered that the circumstances here were anything but favorable to making a good showing with a crew of men in a short time. Men were at their post night and day, whenever the tide permitted, and could not work more than three hours at the most before having to make everything fast and get ashore when the flood tide came. High wages had to be paid, as otherwise men could not be induced to work broken time in the wet and mud. Experienced foremen were employed, who even kept a sharp lookout for the safety of the men, as well as to see that each performed his full share of the work in a skillful and workmanlike manner, and it is a happy feature that although the work was prosecuted at all hours of the day and night, in a dangerous locality, especially when the cold weather set in, not an accident or fatality occurred.

The bridge as now completed in general appearance is such as to satisfy the most sceptical, and is to the casual observer the most elegant structure of the kind in this province. To the eye of the engineer it is bold and strong, each detail being designed to add strength where it is most needed. The columns have a graceful and finished appearance, the workmanship is all that can be desired, and standing side by side with the English lattice railway bridge the two bridges present striking examples of the European and American practice.

