

PAGES

MISSING

INDEX TO ADVERTISEMENTS

In the "Canadian Architect and Builder."

Architects. Ontario Directory..... 111 Quebec Directory..... 111	Cements. Owen Sound Portland Cement Co..... 111 The Rathburn Co..... 111 Sun Portland Cement Co..... 111 Crescent Portland Cement Co..... 65 Cabot, Samuel..... 65 Canada Paint Co..... xv	Manilla, Grates, and Tiles. Holbrook & Mollington i Rice Lewis & Son..... IV Wall Tiles. The Cutler Mfg. Co. xi Mouldings. Decorative Supply Co..... xv Co..... xv Monter Colors and Stencil Stains. Cabot, Samuel..... 65 Muirhead, Andrew..... i	Revolving Doors Revolving Door Co... v Sash Cord. Samson Cordage Works..... xv Slate Steinberger, Hendry Co..... vii Cannon, Thos. Wm... xii Stained and Decorative Glass Bloomfield & Son. Henry..... v Horwood & Sons, H. v Cannon, Thos. Wm... xii Mackay Stained Glass Co..... xv McKenzie's Stained Glass Works..... v Queen City Plate Glass Co..... v St. George, H. E. v Robert McLaughlin & Co. v Stained Glass Co... v Sanitary Supplies James Morrison Brass Mfg. Co..... xi Johns & Co, Edward xi i Shingles and Metal Roofing Metallic Roofing Co. 65 Ormsby & Co., A. B. i Roofers Supply Co... II
Architects' Tools Thornton & Co, A. G. xv Blue Print Paper. Hughes Owens Co. xv Pells and Clocks Meneely & C..... 65 Warner & S. ns, John xii	Doors and Windows Colledge & Hirden. xii Dawling Inks Wagner, Gun Her... xii Electricity Fenlon, John..... i Oth Elevator Co..... IV all ch & Co..... IV Parkin Elevator Co... i Jurnhill & Russell Col V Williams & Wilson... II Engines Can. Photo-Eng. Bussard..... ii Fire-Proof Doors, Etc. Canad an Fire-Proof Door and Scutter Co..... y Smith-Warren Co... i Vokes Hardware Co. 65 Folding Partitions. Springer, O. T..... II	Ornamental Plaster Hynes, W. J..... xv Fredk Walton..... xiii Painters. Montreal Directory. xv Toronto Directory. xv Patent Store Fronts I. W. C. Wilson & Co. x Plaster. Toronto Plate Glass v Paints & Varnishes Bridgeport Wood Finishing Co..... xvii Canada Paint Co... xv Japanese Paint Co... vi Muirhead, Andrew... i Parquet Floors Elliott & Son Co..... viii	Receiving Doors Revolving Door Co... v Sash Cord. Samson Cordage Works..... xv Slate Steinberger, Hendry Co..... vii Cannon, Thos. Wm... xii Stained and Decorative Glass Bloomfield & Son. Henry..... v Horwood & Sons, H. v Cannon, Thos. Wm... xii Mackay Stained Glass Co..... xv McKenzie's Stained Glass Works..... v Queen City Plate Glass Co..... v St. George, H. E. v Robert McLaughlin & Co. v Stained Glass Co... v Sanitary Supplies James Morrison Brass Mfg. Co..... xi Johns & Co, Edward xi i Shingles and Metal Roofing Metallic Roofing Co. 65 Ormsby & Co., A. B. i Roofers Supply Co... II
Architects' Tools Thornton & Co, A. G. xv Blue Print Paper. Hughes Owens Co. xv Pells and Clocks Meneely & C..... 65 Warner & S. ns, John xii	Doors and Windows Colledge & Hirden. xii Dawling Inks Wagner, Gun Her... xii Electricity Fenlon, John..... i Oth Elevator Co..... IV all ch & Co..... IV Parkin Elevator Co... i Jurnhill & Russell Col V Williams & Wilson... II Engines Can. Photo-Eng. Bussard..... ii Fire-Proof Doors, Etc. Canad an Fire-Proof Door and Scutter Co..... y Smith-Warren Co... i Vokes Hardware Co. 65 Folding Partitions. Springer, O. T..... II	Ornamental Plaster Hynes, W. J..... xv Fredk Walton..... xiii Painters. Montreal Directory. xv Toronto Directory. xv Patent Store Fronts I. W. C. Wilson & Co. x Plaster. Toronto Plate Glass v Paints & Varnishes Bridgeport Wood Finishing Co..... xvii Canada Paint Co... xv Japanese Paint Co... vi Muirhead, Andrew... i Parquet Floors Elliott & Son Co..... viii	Receiving Doors Revolving Door Co... v Sash Cord. Samson Cordage Works..... xv Slate Steinberger, Hendry Co..... vii Cannon, Thos. Wm... xii Stained and Decorative Glass Bloomfield & Son. Henry..... v Horwood & Sons, H. v Cannon, Thos. Wm... xii Mackay Stained Glass Co..... xv McKenzie's Stained Glass Works..... v Queen City Plate Glass Co..... v St. George, H. E. v Robert McLaughlin & Co. v Stained Glass Co... v Sanitary Supplies James Morrison Brass Mfg. Co..... xi Johns & Co, Edward xi i Shingles and Metal Roofing Metallic Roofing Co. 65 Ormsby & Co., A. B. i Roofers Supply Co... II

Architectural Sculptors..

Holbrook & Mollington

Dealers in Maw & Co.'s and Minton & Co.'s Artistic and Plain Tiles for Cabinet Hearths, Floors, Etc

No. 308 King St. West
TORONTO
TELEPHONE MAIN 2490

Established 1880.

GREATEST DURABILITY
SMALLEST COST
SUPERIOR EFFECT

MUIRHEAD'S METAL WHITE

This article, as its name implies, is a White Metallic Paint, ground in Pure Linseed Oil. IT DOES NOT injure the Linseed Oil as all grades of White Lead do. IT WILL NOT chalk nor flake off. IT HAS greater spreading capacity than White Lead. IT IS non-poisonous, being a perfect sanitary paint. IT IS more easily applied than White Lead. IT IS invaluable for painting the inside and outside of houses, farm implements, boats, greenhouses, or any thing requiring paint. BY ACTUAL TEST it has worn six times as long as pure White Lead on a floor—it is equally good for dove steps and decks of vessels. IT MAY be tinted to any shade. IT IS the most important article introduced for painting in recent years.

MANUFACTURED BY...

Andrew Muirhead

Office, No. 82 Bay Street
Warehouse, Mining Lane
Factory, St. Lawrence St.

TORONTO

Please Mention the CANADIAN ARCHITECT AND BUILDER when corresponding with Advertisers.

ENAMELED BRICK

List of Contracts Furnished in Canada:

PUBLIC BUILDINGS:	PRIVATE STABLES:
Bank of Montreal..... 150,000	F. W. Moleson..... 8,000
Royal Victoria Hospital..... 20,000	C. R. Nosmer..... 10,000
Banque de Hochelaga..... 3,000	
POWER HOUSE:	OFFICE BUILDING:
Montreal Street Railway Power House..... 17,000	Henry Berk's Jewelry Store..... 11,000 and quality

ONE YEAR'S BUSINESS

Local Agents in Montreal, Toronto and Ottawa

ENAMELED INTERLOCKING TILE (Substitute for Brick)

American Enameled Brick & Tile Co.

1 Madison Avenue, NEW YORK.

J. D. MACDONELL & CO., Toronto Agents, Toronto. (SEND FOR CATALOGUES) HUGH CAMERON, Montreal Agent, Canada Life Building, Montreal.

GEORGE E. GREEN
Limited
28 Wellington Street West,
TORONTO ONTARIO.

Importers and Dealers in
HIGH CLASS WALL PAPERS
HANGINGS and FABRICS

English, French and German.
Correspondence solicited.


Smith's Patents

Automatic Closing, Sliding and Revolving Sashes


FIREPROOF METAL WINDOWS

SMITH-WARREN CO.,
253 Broadway, New York.

Hamilton Radiators



★
For
Hot Water
and
Steam



Are the production of the best mechanical skill to be procured.

Unexcelled in QUALITY, DURABILITY, and EFFICIENCY.

Made with all iron to iron joints—no packing of any kind.

Used in hundreds of the best and most expensive buildings in Canada

Manufactured by ...

Correspond with us before deciding on your method of heating.

THE GURNEY, TILDEN COMPANY
Hamilton, - Canada. LIMITED

TORONTO OFFICE: 134 Bay Street.

EASTERN AGENTS: H. R. Ives, Montreal, Que., and The Star Iron Co., Montreal.


WESTERN AGENTS: The Gurney Stove & Range Co., Limited, Winnipeg, Man

CATALOGUE FOR THE ASKING

H. R. IVES & CO.

MONTREAL, QUE.

General
Founders
and
Manufacturers



Architectural
Iron Work
Stable Fittings
etc., etc.

THE ROYAL-BUFFALO HOT WATER HEATER

write for Catalogues

THE RICHMONDT CONDUIT & MFG. CO., LIMITED
 SOLE MANUFACTURERS OF
RICHMONDT ELECTRO-CALVANIZED CONDUIT TUBING AND FITTINGS



Contractors use it because—It Saves Time and Money. Supply Dealers carry it because—It Sells Itself.
 Architects specify it because—It fills the Underwriters' requirements.

FACTORY AND OFFICE : 15, 17 and 19 Jarvis Street, TORONTO, CANADA.

ALBERT MANUFACTURING CO.

MANUFACTURERS OF **PATENT ROCK WALL PLASTER**

MANUFACTURERS OF **"HAMMER BRAND" CALCINED PLASTER**

HILLSBOROUGH, N. B., CANADA

Cable Address : GILMOUR, TRENTON

Established 1820

MAIN OFFICES: TRENTON, ONTARIO

Established 1820

GILMOUR & CO., LTD.

TRENTON CANADA

BRANCH OFFICES IN: London, Eng., New York, Capetown, S. Africa, Chicago, Sydney, Australia, Glasgow

DOORS **LUMBER**

SECTION SHOWING PROCESS

SECTION PATENT LUMBER

STILE SECTION

CAPACITY OF MILLS & FACTORIES 25,000,000 FEET PER YEAR

OUTPUT; 300,000 DOORS PER YEAR

SAW MILLS, PATENT LUMBER, DOOR, SASH, BOX AND VENEER FACTORIES

MANUFACTURERS OF SASH, DOOR AND BOX FACTORY GOODS, LATH, SHINGLES, RAILROAD TIES, TELEGRAPH POLES AND POSTS, JOINERY, FINE INTERIOR FINISH, HARDWOOD FLOORING, ETC. EGG CASES, EGG FILLERS

WRITE OR WIRE FOR SAMPLES AND PRICE LISTS

Responsible Agents Wanted in All Parts of the World

Gilmour & Company, Limited ©

TRENTON, CANADA

ORDERS PROMPTLY FILLED

Luxfer Decorative Glass



PRICES—(Per square foot)—104 75c 118 60c 123 \$1.50 128a \$1.60 150 \$1.60 163 \$1.25 171 \$1.70 175 \$1.50 206 \$1.00 210 65c 218 \$1.75 221B \$1.00
224 \$1.50 235 \$2.75 238a \$2.00 247 \$1.10 313 \$1.50 317 \$1.50 32 \$3.50 323 \$3.50 324 \$1.25.

Copper Electroglazed in bright, antique or black finish.

LEADED WORK of all kinds.

Write for designs and prices.

Luxfer Prism Co., Limited

98-100 KING STREET WEST, TORONTO

...Glass Painting...
Memorial Windows
McKENZIE'S STAINED GLASS WORKS
8 AND 10 MAIN STREET EAST
Church and Domestic
Ornamental Glass. **Hamilton, Ont.**
Original Designs made to suit all classes of work.

ROBERT McCausland, Limited
88 Wellington St. W., TORONTO
Memorial Stained Glass
Decorative Leaded Glass
Superior Metallic Glazing

ART GLASS WORKS
ESTABLISHED 1876.
Memorial Church Windows,
Geometrical and Quarrie Windows,
Art Glass for Residences, etc.
Send for designs and prices to

H. HORWOOD & SONS PRESCOTT, ONT
and Ogdensburg, N. Y.
100 and 402 Bank Street, - OTTAWA.




HENRY BLOOMFIELD & SONS
ARTISTS IN STAINED AND LEADED GLASS
Mount Pleasant, Vancouver, B. C.
SEETCHES AND PRICES ON APPLICATION.

HIGH-CLASS
FIGURE
WINDOWS
ART GLASS
Original Designs.
H. E. St. George
180 Dundas St.
LONDON, ONT.

Please mention this paper when corresponding with advertisers.

MEMORIALS AND DOMESTIC ART GLASS
DOMINION STAINED GLASS
EQUI CO. LTD.
34 RICHMOND ST. E. TORONTO
of Fishery & South Front



SEVERELY TESTED BY FIRE.

SAVES PROPERTY, SAVES INSURANCE.

The Canadian Automatic Fire-Proof Door and Shutter Co.
MANUFACTURERS OF
Barber's Patents for Absolute Self-Acting Fire Proof Doors, Shutters, Vault Linings Fittings, etc., Safes, Document Boxes and Jewel Cases.
Everything guaranteed.
For booklet and quotations, apply to
C. A. BARBER, MANAGER,
41 Bleury Street - - - MONTREAL Qu

LATEST MODEL, CLOSED

REVOLVING DOORS



"ALWAYS CLOSED"


Made and Sold Under
VAN KANNEL PATENTS and IFE PATENTS
Keep out all Snow, Wind, Rain and Dust, cannot be Left Open, Blown Open or Slammed.
USED IN
Office and Public Buildings, Banks, Hotels, Churches, Clubs, Libraries, Etc
SEND FOR CATALOGUE
CANADIAN REVOLVING DOOR CO.
Limited
165 QUEEN ST. EAST, TORONTO

The Queen City Plate Glass and Mirror Co., Limited.
243, 245 & 247 Victoria Street, TORONTO, ONT.


EXTENSIVE DEALERS IN
Plate Glass, Window Glass, Bent Glass, Plain and Ornamental Bolted Glass, Skylight Glass and all other Glass required for Buildings, also Glaziers' Points and Putty in Bladders or Bulk.
MANUFACTURERS OF
Plain and Ornamental Chipped Glass, Sand-Cut Glass and Art Lead Work, Beil'sh, German and Shock Mirror Plates.
BEVELLERS. MIRROR MAKERS.

The Globe Furniture Co., Limited
MANUFACTURERS OF . . .
OFFICE FITTINGS
Church and School Furniture
WALKERVILLE, ONTARIO

RHODES, CURRY & COMPANY, LIMITED



BANK AND OFFICE FITTINGS SCHOOL DESKS A SPECIALTY
We manufacture all kinds of building materials, including cast iron columns, creating, sash weights, etc.
In addition to our large stock of native lumber we are now carrying about one million feet of foreign lumber, including oak, walnut, ebony, whitewood, basswood, red cedar, douglas fir, mahogany, etc.
RHODES, CURRY & CO.
Amherst, N. S.
BRANCH AT
HALIFAX SYDNEY




**LIGHT BROWN
or RED STONE** *Sackville Freestone Co., Limited*
Sack , New Brunswick.
—**LARGE BLOCK, DIMENSION, SHODDY.**—
State your requirements and ask for prices before contracting.
C. PICKARD, Managing Director.

Amherst Red Stone Quarry Co.
AMHERST, N. S.
Amherst Red Stone
*Samples Sent Free Hardens with Age
Correspondence Requested*

STONE.
Contractors can be supplied with all kinds of stones—Rubble, Coursers, all thicknesses, Footing Stone, Flagging, Crushed Stone, as d Grey lime, at Horse Shoe Quarry, St. Marys, Ont., at reasonable prices, in quarry or f.o.b. cars at St. Marys, or destination. Also an analysis of their stone for refining purposes of a box. Geo. D. LAWRIE, Sec.-Treas. ALEX. DOUGLAS, Pres.

JOHN KLINE
—DEALER IN—
ROUGH AND DRESSED GRANITE
Heavy blocks a specialty. Street paving and curbing. Also granite for monumental and building purposes. Estimates and samples on application. JOHN KLINE, Granite Dealer, HALIFAX, N.S.

GRANIZE
Red and Rose Pink
Fine Rich Colours for
BUILDING and MONUMENTAL PURPOSES
and **GRANITE PAVING**
can be had at low figures from the
St. Philippe d'Argenteuil Quarries.
Send for quotations and samples to
JOS. BRUNET
Cote des Neiges, Montreal, Que.



JAMES BRODIE & CO.
Quarries and Manufacturers of . . .
*Canadian Quinsy, Ebony
and Stanstead Granite*
Monumenta Building, Curbing, Paving, etc. - Rough work a Specialty.
Mount Johnston, Que.

**BROWN AND OLIVE
FREE STONE**
Any dimensions and finest quality, for BUILDING PURPOSES, from our New Brunswick quarries.
Pulp Stones
SAMPLES ON APPLICATION
WM. HOOD & SON
10 Richmond Sq., MONTREAL

D. ROBERTSON & CO.
LIME AND STONE
Credit Valley Sandstone, Sills, Heads, Coursing and Dimension Stone our Specialties, either dressed or in the rough.
Lime Works at Milton, Omcos, Toronto and Milton.

THE AMHERSTBURG STONE QUARRY
T. W. BELLHOUSE, MANAGER.
AMHERSTBURG, . . . ONT.
Apply for prices on
BUILDING STONE
COURSING. FOOTING CRUSHED.

**TO CONTRACTORS
AND BUILDERS**
Cheapest and best stone on the market for footing, bridge work, dimension of all sizes, sawed blocks, slabs and kerbing.
Silex Stone Quarries Co.
SHELburne, ONT.

CROOKSTON QUARRIES, Crookston, Hastings Co., Ontario.
LIMESTONE adapted for all kinds of heavy Masonry.
Also Sills, Monument Bases, Rubble and Stone for crushing purposes.
Grand Trunk & C. P. R. Sidings.
QUINLAN & ROBERTSON.

CREDIT FORKS STONE CO.


23 Toronto Street - TORONTO

Brown Stone Quarries, Supply the **BROWN STONE** IN . . CANADA
✠ ✠ ✠ **Credit Forks, Ont** Best . . .

DIMENSION	COURSING	BRIDGE STONE
RANDOM	SHODDY	
HEADS, SILLS	RUBBLE	

OFFICE:
23 Toronto Street
TORONTO
Telephone Main 208

For Prices of Unoccupied Spaces in above Directory, address the CANADIAN ARCHITECT AND BUILDER, Toronto.



GRAND TRUNK OFFICE BUILDING.

The largest and most modern Office Buildings, Hotels and Factories are equipped with the

Webster System . . of Steam Circulation

Our 1902 Illustrated Catalogue gives a full description of this System, and will be mailed on application.

DARLING BROS.

"Reliance Works," Montreal.

JAPANOL An Enamel Paint A Flat Paint


A Paint of Unsurpassed Durability.
Will Stand Any Climate and is Suitable for Every Purpose.

Made in over 100 Shades of Colour.
No Paint Equal in Quality or Value to Japanol.

The JAPANOL PAINT COMPANY

Agents: Geo. Rogers, Son & Co., 22 Great St. Helen's, London, E. C.

DO YOU USE ENGRAVINGS?



The leading Newspapers and the leading Advertisers in Canada use those made by

THE ALEXANDER ENGRAVING CO.,

Successors to Moore & Alexander

Engravers, Designers and Commercial Photographers

Write for Prices.....

16 Adelaide St. West, TORONTO.

WHEELER'S WOOD FILLER

Brings out the full life and beauty of the wood. Permanently sustains the finish over same. More economical to use by reason of greater covering properties and saving of labor and material.

PAINT THAT LASTS

Pure Lead Chalks; Lead and Zinc Seales; Lead, Zinc and Silix; the base of Breinig's Lithogen Silicate Paint and Lithogen + hite Lead, is the most perfect paint compound known. This is admitted by many eminent chemists and painters. This paint is as much superior to others as Wheeler's Filler to other fillers.

THE BRIDGEPORT WOOD FINISHING CO.

NEW YORK, 55 FULTON ST. CHICAGO, 70 W. LAKE ST.
McARTHUR & CO., MONTREAL.

PHILADELPHIA, 231 DOCK ST. NEW MILFORD, CT
STEWART & WOOD, TORONTO.

BENT GLASS

MANUFACTURERS

FOR { Shop Fronts
House Windows
Show Cases


FINE BENT GLASS FOR CABINETS AND ART FURNITURE.

Toronto Plate Glass Importing Co.

ALL KINDS OF WINDOW GLASS.

135 to 143 Victoria St. TORONTO

Refractory Glass TRANSONS for LIGHT DIAGNOSIS.



CAREY'S Magnesia Flexible

Cement ROOFING

Adapted to Flat or Steep Roofs. Always flexible. Fire-proof. Anyone can apply it. Durable as slate and costs less.

Correspondence promptly attended to. Catalogue and sample free.

PHILIP CAREY M'FG. CO.,
94 Adelaide St. W., Toronto.

ROOFING

Felt and Gravel
Slate
Spanish Tile
our specialties.

County work given special attention.

W. D. HUTSON & SONS

(Established 1864.) 21 QUEEN STREET E., TORONTO.
ROOFERS AND SHEET METAL WORKERS.

Our forty years experience in the roofing and sheet metal business throughout Canada ought to be sufficient inducement to you to consult us as to what class of roofing is most adapted to your building before letting contract for same. Information and estimates cheerfully furnished. Remember we have experimented with numbers of different roofs and are now in a position to give you the benefit of that experience free of charge.

OUR WOOD FLOORS

are made in our own factory and are now to be found all over Canada from Halifax to Vancouver. They are superior to the cheap American floors imported here and carry with them our guarantee. In addition to our catalogue design (free on request) we make any other design required at low prices.

The ELLIOTT & SON CO., Limited
79 KING ST. WEST, TORONTO



Use Rock Wall Plaster



LONDON, ONT.

#85ND FOR CATALOGUE.

School and Church **Bells**

Floor and Urinal **Slate**

Slate and Hyloplate **Blackboards**

THE STEINBERGER, HENDRY CO.
Limited

37 RICHMOND STREET W., TORONTO

The Canadian Architect and Builder

VOL. XVI.—NO. 184.

APRIL, 1903.

ILLUSTRATIONS ON SHEETS.

C. A. & B. Students' Competition for a Town or Suburban House.—Design submitted by "T Square, Jr." (Mr. Clarence Thetford), Awarded Honorable mention.
House in Park Road, Toronto.—Burke & Horwood, Architects.
Entrance Gateway, Upper Canada College, Toronto—Symons & Rae, Architects.

ADDITIONAL ILLUSTRATIONS IN ARCHITECTS' EDITION.

Detail, Certosa di Pavia, Italy.
Old Building at Chinon, France.

ILLUSTRATIONS IN TEXT.

Buildings under construction for the Louisiana Purchase Exposition, St. Louis, Mo.
Decorative Panel for a Dining Room.

CONTENTS

Editorial	61-62	Methods of Construction in Relation to Insurance	68-69-70-71-72
High Building	63	The Nova Scotia Freestones	73
By the Way	64	Men Who Build a Sky-Scraper	75
Street Architecture in Paris	66	Advertising Value	76
Aspect and Prospect as Factors in House Planning	66	British Brick Standards	ix
Sixth International Congress of Architects	67	Portland Cement Affected by Time	x
A Transparent Tracing Table	67	Legal	
Greek Details	67		

SPECIAL CONTRIBUTORS.

- PROF. S. H. CAPPER, R.C.A., Department of Architecture, McGill University, Montreal
MR. W. A. LANGTON, Architect, Toronto.
" EDMUND BURKE, " "
" S. H. TOWNSEND, " "
" FREDERICK G. TODD, Landscape Architect, Montreal
" W. H. ELLIOTT, Toronto.
" J. C. B. HORWOOD, Architect, Toronto.
" A. F. DUNLOP, R.C.A., Architect, Montreal.
" FRED. T. HODGSON, Architect, Collingwood, Ont.

Putting in Foundations in Winter.

For several years in Toronto there has been but a very short gap between one building season and another. In fact, if account is taken of the new structures on which inside work is in progress throughout the winter, there may be said to be no gap at all. The present winter, which has been a favorable one for architects and builders, witnessed the putting in of foundations for new buildings during January and the early part of February. The method adopted to prevent frost from getting in below the foundations is to cover the work when not in process of construction, with manure. It is admitted, however, that there is considerable risk attending the practice—the success of which largely depends on securing a week or ten days of favorable weather. We have been told of instances in which frost having got below the footings of a cellar pier, caused the architect trouble from settlement throughout the whole progress of the work.

Building Failures.

The Montreal papers have already recorded this year several instances in which buildings in that city have collapsed. Such cases have been altogether too frequent in Montreal during the last three or four years. In some instances, as in the case of a bis-

cuit factory on Delorimer Avenue last month, the collapse came while the building was in process of construction. In others, the buildings had been standing for years, and probably succumbed to strains imposed on them which they were never intended to bear. In the case of the uncompleted buildings the explanation is not so clear. Their collapse would seem to be due either to faulty materials or construction or to carelessness on the part of contractors in failing to properly support the unfinished walls. Whatever the cause, greater care should be exercised lest human life be sacrificed, which through good fortune rather than good management, has not yet occurred.

An inspection of a batch of tenders, even for an ordinary house, will show the necessity for a better all-round education and in particular a better business training, for contractors. It is evident that many contractors do not study and grasp the meaning of the specifications on which their tenders are based. The specifications may in the most explicit manner require the contractor to state what deductions in price he will make if certain parts of the work are omitted, but as a rule he pays no attention whatever to the requirement and it is impossible for the architect to know whether his tender is designed to

clude the whole work or not. Then there is the wide variation in tenders to which previous reference has been made. Tenders for the carpentry work of a house of moderate price are found to be as much as one thousand dollars apart, and even in so small an item as the electric wiring, there is a difference of fifty dollars between one offer and another. There would seem to be something radically wrong either with the methods or morals of contractors when such wide differences as these occur, and in view of such apparently hap-hazard figuring it is surprising that the percentage of failures among contractors is not greater than it is.

The Designing of Commercial Buildings.

The Confederation Life Building, Toronto, is serving as an example of the unsuitability of gothic design for commercial buildings. In order to secure an adequate revenue the owners were compelled two or three years ago to have remodelled the western front, to serve as banking premises. With the same end in view it is now proposed to redesign and reconstruct the upper part of the Yonge and Richmond street fronts as far back as the main tower and to add three stories to the height. When this is done the revenue from this part of the building will probably be more than double what could have been obtained before. The alterations will represent a large expenditure, the greater part of which might have been saved if the purpose of the building and its revenue producing value had received proper consideration by the designer and those responsible for the selection of this particular design from among a large number submitted by architects in competition. Architects, owners and judges in architectural competitions should alike be impressed by the lesson which the history of this building teaches—that a plan for a building is successful in so far as the requirements are properly considered and provided for. Following this in order of importance should come the effort to make the building pleasing in appearance, which with a skilled designer is always possible.

Assisted by a grant of \$50,000 from the Federal Government, it has been decided to hold a Dominion Exhibition in Toronto this year. For some time we have advocated this project, and are therefore gratified to learn that it has assumed definite form. The question arises however, whether four or five months is sufficient time for the preparations to be made on a sufficiently ample and complete scale. It is stated that the Industrial Exhibition Association have already been at work on the enterprise for several months. If this is the case, no doubt many of the arrangements are already well under way. Every patriotic Canadian should lend his assistance to make this Exhibition truly representative of the resources of the entire Dominion. The hearty co-operation of the local governments, commercial bodies and leading men of the various provinces forming the Confederation, is essential to success. The railway and steamboat companies can also greatly assist by granting such low transportation rates as will encourage visitors to attend from every part of the country. It is to be hoped that means will be found and steps taken to bring before the visitors to this Exhibition the im-

provements in design, materials and methods which have marked the progress of the building industry in this country, especially during the last decade.

An Important Decision

Consternation has been caused in the ranks of the labor unions in England by the recent decision of the Superior Courts, condemning the Amalgamated Society of Railway Servants to pay \$115,000 to the Taff Vale Railway Co. as compensation for damage sustained by the company by reason of the intimidation of their employees by the Society during a strike. In this case, as in that of the journeymen plumbers in Toronto last year, the strikers did not hesitate when it suited their purpose to violate their agreement with their employers by quitting work without giving fourteen days notice as required by the terms of their engagement. The secretary of the Society has admitted that had the Society lived up to its agreement, the strike could not have succeeded, as the company would have been able to get the required help. When the company were granted an injunction preventing interference by the strikers with their workmen, the society capitulated. Then the company took the aggressive and sued the society for \$150,000 damages, and as stated, were awarded \$115,000. The situation in England now is that men still have the right to organize, but they may not strike until they have given the legal notice, and when they have quit their employment they must not interfere with the men who take their places. If they do they are liable in damages, and as the present decision shows, substantial ones at that. An effort is now being made to have the law changed in such a way as to relieve the Unions of the responsibility placed on them by the courts.

Wired Glass.

The Chief Engineer of the New York Fire Department has recently expressed high appreciation of wired glass as an efficient protection from fire. The fire-resisting qualities of this material are now generally recognized. According to the American Architect, however, except when fire is present, it has undesirable, even dangerous qualities. This journal cites as proof the South Terminal Station in Boston. In the windows that face east, south, and west, and in the thousands of feet of pent-roof over the street sidewalks, there is said to be hardly a sheet of the glass that is not cracked and shivered into a dozen or a hundred different pieces of glass, just now held in place by the embedded wire and the unequal planes of fracture of the glass itself. But where cracks are, there moisture and acid-gases can penetrate, and when corrosion has done its work on the wire there is likely to be many a repetition, less innocent, too, of the incident which attended President Roosevelt's reception in Boston a few weeks ago, when a sizable piece of this shattered wire-glass fell onto the platform not far from the President. Meanwhile before the time comes when falls of heavy pieces may be looked for, much of this shattering of the glass is already accompanied by the flying of fine splinters of glass. As fracture occurs least often on the side, and most frequently where the windows face the rising sun, it is evident that the manufacturers must give further study to the qualities of radiant heat before wire-glass can be held to be a perfectly safe material to use.



TOM MOORE HOUSE AT STE. ANNE, NEAR MONTREAL.

HIGH BUILDING.

It is satisfactory for the rest of the world that New York should proceed as fast as it can to the logical extreme in high building. What the rest of the world wants to know is, what will it come to? What is the limit; and what are going to be the consequences of building up to the limit?

The limit in height is practically in sight. Passenger elevators, which were the generating factor in these buildings, are also fixing their limitations. Accessibility to the street level is what is required for an office; and, when buildings are so high that time is wasted in going and coming in the elevator, the offices in the highest floors will not rent sufficiently well. The device of express elevators gets over the difficulty to some extent, but in the first place there is a limit to the percentage of floor space that can be given up to the elevator shafts, if the building is to pay; and in the second place there is a speed limit in elevators. What is known as a "nausea limit" is recognized; anything above this rate of speed is found to be uncomfortable—at least for landsmen. For men this rate is said to be 720 feet a minute; for women not more than 600 feet; and the descent must be much less rapid than this. Anything faster than 400 feet a minute going down, is distressing; so that about 600 feet per minute up and 400 feet per minute down is the maximum for an express elevator. The floor to floor elevator is still further reduced in speed, to enable the operator to make a prompt stop. If, with higher speed he bobs up and down at every floor—a consequence partly of human weakness and partly of the elasticity of steel rope—there is no ultimate gain in speed and considerable waste of power. Limiting calculations are often upset by new inventions; but, where the human body is the measure, there is a standard which may be relied on not to change. It is difficult to conceive of more rapid motion up or down for human beings than the present nausea limit, or of more abrupt stops at this rate of speed without great discomfort to the occupants of the car; and we may therefore accept as a scientific datum the present opinion of engineers in New York, that the limit of business buildings due to the limited speed of elevators, is between twenty-five and thirty storeys.

This may be the limit of height, but how to fix the limit of continuity. A sky scraper at intervals is a gain in every way; it gives well lighted, airy, and quiet offices; and it makes the street picturesque. A row of sky scrapers converts the street into a box canyon of unwholesome gloom; but it is not to be com-

pared to the gloom and unwholesomeness within the buildings themselves. This condition of affairs is rapidly approaching in New York. There is what almost amounts to a skyscraper war going on. The early tall buildings in which, with more confidence than judgment, the party walls were filled with windows, are now in an awkward position. Skyscrapers are rising beside skyscrapers and blocking up whole walls of windows. Rooms which, when the buildings were erected, had the winter sun and the summer breeze, are now sealed up in darkness forever; and the sanitary consequences are beginning to cause alarm. In the lower rooms, in a street of continuous sky-scrapers, there is no light anyway; and, if darkness is to invade the upper storeys too, the unwholesomeness of the overcrowding in these expensive offices is going to be as bad as that in the poor tenements, which so much effort has been made to stop. At a recent meeting of the Municipal Art Society, a prominent speaker said:

"I read in my newspaper to-day of the benevolent project to build a great hospital for consumptives, the victims of tuberculosis; where they may have air and sunlight. And in the same paper I read of plans for a thirty story building. What are we trying to do? What do we mean by putting up these horrible structures, to the lower floors of which no light can ever penetrate? . . . We build hospitals for the poor consumptive, and then we turn around and erect skyscraping structures where consumption may breed, so that we shall not lack for patients."

It is not merely the darkness, but the crowding of the streets and buildings which is a menace to health and safety. This same speaker calculates that "when Broadway is lined with these structures, there won't be room for the tenants, unless they are packed horizontally thirty feet thick." It is not hard to believe that this calculation, if checked, will be found to be not far from the truth. It was calculated at the beginning of the year that the buildings of nine storeys or more in the lower part of Manhattan Island, below Leonard street—that is to say only in the tall building district proper—have added the floor area above their fifth storeys, 180 acres of area to the island. The estimated cost of these buildings was \$33,000,000. There is said to be \$10,000,000 worth of buildings of the same sort in process of erection now, so that, as area may be presumed to compare consistently with price, when these are completed, which will not be long at the rate these buildings go up now, there will be added to this small district 240 acres of standing room above the streets; but there will be only the same old streets to walk in, and these more than ever filled with vehicles from other parts. The Broad Exchange Building has a floor area of 12½ acres and a normal population of 4,000 persons. Apply this rate of population to the 60 acres or so of floor area (above the fifth storey) which are now being constructed and it will appear that this portion of New York is about to receive an increase in daily population of at least 20,000 souls. If they only were souls; if, "in going from place to place," they need not "pass through the intermediate space," it would be all right; but 20,000 hustling bodies in streets where one has already, in going to keep an appointment, to allow time for hindered progress—it is nearing the limit.

The cure is exhibited in a trio of buildings on Broadway; a two-storey bank between two sky-scrapers. This is, at any rate, the solution of the light and air problem. It would also solve the problem in design. The two storeys of the bank run with the two storeys

which constitute the base of the tall building; the bank's cornice with the top member of this base; their columns and arcades are fairly comparable. Here is dignity without monotony, picturesqueness without extravagance, height without gloom; every gain without any loss except loss of space, and loss of space is gain in this case.

What other cities have to learn from New York is to put the limit out of the question by taking precautions in time. The limit is not practical. It is not worth while to shut numbers of people in darkness, for the sake of getting them all together, only to find that it would be better if there were not quite so many together. The limit of elevators, and the limit of traffic and transit in the streets, seem to point to the same moderation in close building which is indicated by the requirements of planning for light. It is no extreme to advocate the attainment of this moderation by municipal regulation, requiring that every tall building shall be isolated above such height as usually forms the base storeys of a sky-scraper. This allows for such an arrangement as is suggested by the bank on Broadway between two such buildings. It would make a satisfactory street effect if the cornice at this height were continuous and the sky line above broken at intervals, more or less regular, by buildings more or less tall.

A way to bring this about would be to require every high builder to isolate his upper storeys by the purchase of land sufficient for the purpose. This would not be tyrannical legislation. If any criticism is to be made of it, it might be called grandmotherly legislation; for it is looking after the interests of the high builder himself to guard the value of his building in this way. It is not however entirely grandmotherly, for the interests of the public are also guarded in matters for which it is certainly within the province of the City Fathers to care, viz., light and air and reasonable density of population. There is also plenty of precedent, in cities which owe part of their success to regulations of this kind, for requiring that the low part of the building shall have for æsthetic considerations, a cornice line of a fixed height.

W. A. LANGTON.

Messrs. King and Bannigan, of Boston, are reported to have purchased a large plaster quarry at Hillsboro, Albert county, N. B., and to be making arrangements to open up the work and to prosecute it in a vigorous manner.

The Lake Manitoba Quarry and Transportation Co. has been formed to develop extensive deposits of excellent building stone at the Lake Manitoba Narrows.

BY THE WAY.

There are said to be within the limits of the city of New York two hundred thousand inner rooms unprovided with means of ventilation. To this cause is largely attributed the increase in the number of consumptives.

× × ×

The inconvenience arising from lack of uniformity in size of bricks is evidently not confined to Canada. A petition has been presented to the legislature of Massachusetts praying that the standard for face bricks shall be fixed at $8\frac{3}{8}$ by $4\frac{1}{4}$ by $2\frac{1}{4}$ inches and for common brick at $8\frac{1}{4}$ by 4 by $2\frac{1}{4}$ inches.

× × ×

Recent excavations in the far east have revealed the fact that the Jerry builder had to be reckoned with one thousand years before the time of Moses. The following has been found among other enactments of a Babylonian ruler of that period:—"If a builder build a house and finish it, but does not make it solid, and if then the house fall and kill the owner, that builder shall be

put to death. If it strikes the owner's son dead, then the son of the builder shall be put to death".

× × ×

The Deputy Chairman of the Liverpool Corporation Housing Committee thinks he has solved the problem of the cheap and substantial construction of dwellings for the dispossessed slum population. He proposes to use very large slabs of concrete made from refuse-destroyer and clinker cement,

hoisted into position and bolted together. A quicker and therefore cheaper method than this would be the plan attributed to Thomas A. Edison of pouring the concrete into a mould of the desired form.

GLASS-FACED BRICK.



The Cleveland Leader says that a new company has been organized lately to manufacture glass-faced brick. A number of prominent Cleveland men are financially interested in the project and the concern is looking for a factory site of from three to five acres.

The new brick is another of the great variety of concrete building material now being manufactured. A glass plate is laid in the bottom of a mold, and the concrete mixture is poured in on top of the glass. The concrete hardens on the glass, thus forming a brick or building block with a very brilliant exterior.

This kind of brick is for use in such places as courts and light wells in large buildings, where the glass becomes a reflector, and on account of its smooth surface does not become soiled easily, and is readily washed. The new process will yield a product similar to enamel brick.



DECORATIVE PANEL FOR A DINING ROOM—G. A. REID, R. C. A.



BUILDINGS UNDER CONSTRUCTION FOR THE LOUISIANA PURCHASE EXPOSITION, ST. LOUIS, MO.
No. 1. TRAVELLERS' PROTECTIVE ASSOCIATION BUILDING. No. 2. LIBERAL ARTS BUILDING. No. 3. FRATERNAL BUILDING.

STREET ARCHITECTURE IN PARIS.

New regulations concerning the erection of buildings in Paris have just been issued by the municipal surveyors, as the decrees hitherto in force (though they dated no further back than 1882 or 1884) did not satisfy modern requirements in the matter of hygiene, comfort and luxury.

The height of buildings is thus fixed: If the road is less than 12 meters (39 feet) wide, the height of the building must not exceed the width of the street by more than 6 meters (19½ feet). On a roadway 12 meters wide, the house may therefore be 18 meters (59 feet) high, and for every additional meter in the breadth of the road a quarter of a meter (about ten inches) may be added to the height of the house until the limit of 20 meters (nearly 66 feet) to the eaves is reached; but no building may exceed that.

In all dwellings, whether situated on a public or private road or in a courtyard, the height of the ceiling of the ground-floor apartment, and also that of the entresol, shall not be less than 9 feet 2 inches.

Projections—bases of columns, balconies, corbels, bow windows, etc.—are subject to certain general regulations, which may be modified in special cases. Thus if a roadway is 52 feet or more wide, the regulation width of the balconies may be increased by one-fourth.

A new and useful clause in the decree provides that any shutter, blind or sunshade placed not more than 10 feet above the pavement must either be within the body of the wall or must not open outwards.

There are also minute regulations concerning verandahs, awnings, sunblinds, outside lamps, cornices and signs.

ASPECT AND PROSPECT AS FACTORS IN HOUSE PLANNING.

BY G. A. T. MIDDLETON, A.R.I.B.A.

Few problems are more frequently brought to an architect for solution than that of designing a small house. It is consequently a problem to which it is worth while to devote a considerable amount of attention, for, though apparently simple in most cases, its very simplicity may then lead to carelessness over some of those minor details which go so far towards comfort and consequent success; while in other cases a cramped site may introduce difficulties requiring skill of no mean order to successfully overcome. Perhaps the detail most commonly overlooked is that of aspect, yet it is one which can scarcely have enough attention paid to it. Primarily, it may be taken as an axiom that as much sunlight should be admitted into a house as possible if the inhabitants are to live in health. This means that the rooms which are most used should have windows opening towards the position of the sun at the hours when they would be most probably in use. Thus the ideal position for a breakfast room would be towards the south-east, while a dining room, used largely in the evening, might have a westerly aspect, and the drawing-room face towards the south. On the other hand, a billiard room or a studio would be better without direct sunlight, and might be on the north or north-east, or even the east, for the billiard room, at any rate, would not often be used early in the day. Kitchens, on account of their being largely used by the servants, and often by the ladies of the household also, need to be bright and well lit, but they become un-

bearably hot if much direct sunlight be admitted. It is better, therefore, that they should have large windows looking out on to a sun-lit yard, but themselves facing north, a small window being, perhaps, contrived in a side-wall to admit a ray of sunlight in the evening. Larders should also face north or north-east.

Sculleries, w-c.'s, and boot-rooms, instead of being "anywhere," ought to be amongst the best lit and sunniest, for in them impurities are most likely to lurk, and the bacteriologist has proved that sunlight is the greatest enemy of the bacillæ of infection. So, too, with bedrooms; they need all the sunlight they can get, so that if the exigencies of a plan necessitate the principal (or only) window of a bedroom facing north, a secondary window towards east and west should be introduced, or a bay or oriel thrown out.

It is wonderful how much the cheerfulness of a room is enhanced by the introduction of a bay window with canted sides, admitting a ray of sunlight across the floor, which would otherwise have passed outside.

While upon the question of light, it may be remarked that there ought to be no dark corners in a house whatever. Their avoidance generally calls for a certain amount of skill in planning, it being by no means easy for a novice to see whether passages and cupboards will be well or ill-lit, but this perception is well worth cultivating. Dark corners are common lodgements for dust, and the happy home of the spider and the black beetle.

Very little less important is aspect than prospect. Many an architect will sit down happily and plan a house, without a knowledge of the compass-bearings of the site; many more without having studied the directions from which the best views are to be obtained. To take a personal instance: I live in the last house of a terrace facing east. My house is planned, like all others in the terrace, with windows facing east and west, not a single window opening towards the side road on the south. Thus the house is, through carelessness, deprived of much obtainable sunshine, and also, from the upper rooms, of a prospect of waving tree-tops, which would be most acceptable in a great city.

It is always worth while to introduce a subsidiary window, or to throw out a bay, in order to secure a pretty view, or even the sight of sun-lit field or sea. Such a prospect will often, indeed, largely compensate for a necessarily unsatisfactory aspect, the sight of sunlight being almost as refreshing as its possession. Now and again a prospect can be made by careful planning of a garden, but more often the house has to be planned to fit its natural surroundings, and the arrangement should, where possible, be such that the best and brightest views can be seen from the most generally occupied portions of a room. Thus, in the breakfast room the view should be visible from the table, and in the principal sitting-room from the circle round the fire-place; while from a bedroom it should be seen from the most probable position of the bed-head.

It is rarely, indeed, that attention to these points does not add to the comfort of a house, and incidentally to its letting and selling value, while giving it an individuality in plan—which is the architect's opportunity.—The Irish Builder.

SIXTH INTERNATIONAL CONGRESS OF ARCHITECTS.

The Sixth International Congress of Architects, will be held next year in Madrid under the auspices of the Spanish Government, on April 6th to 13th, in the Royal Academy of Fine Arts of San Fernando, Alcala street, No. 11.

The membership fee for "protectors" will be 100 francs and 30 francs for adhering (or associate) members. Each member will receive an identification card, a membership card, a copy of the programme and regulations and a badge.

The proceedings will be in French, Spanish and English.

The questions to be discussed are the following:—

1. "Art Nouveau," the so-called modern art in architecture.
2. The preservation and restoration of architectural monuments.
3. Influence of modern processes of building on the artistic form.
4. The scientific studies in the general study of Architecture.
5. The artistic ownership of architectural works.
6. The education of workmen in building trades.
7. The influence of municipal by-laws and regulations on private modern architecture.
8. The expropriation of architectural works of art.
9. Is it necessary to have the architect as arbiter in the regulating of the connection between the workmen and masters, or to settle conflicts that may arise between them?

The second, fifth and seventh questions are the same as discussed in the last congress, held in Paris, France, in 1900.

All correspondence should be addressed as follows: Senor Don Luis-Maria-Cabello-y-Lapiedra, Secretario del Comision Ejecutiva, del Sexto Congreso Internacional de Arquitectos, Columela, 5, tercero izquierda, Madrid, Espana.

Mr. Alcide Chausse, City Hall, Montreal, Que., who is a corresponding member of the Sociedad Centrale de Arquitectos de Madrid, is a member of one of the committees of the congress. He will be pleased to receive the cards of all his Canadian confreres to whom he will send copies of the programme.

A TRANSPARENT TRACING TABLE.

In the drafting rooms of the Metropolitan Water-Works, Boston, there is in use an illuminated tracing table, for making tracings on thick paper or of drawings having weak lines. The following description is reprinted from the Engineering Record:—An ordinary large drafting table with a thick white pine top, having a large drawer sliding across the whole width of the table was adapted for this special purpose. A rectangular hole was cut in the middle of the top of the table and a large piece of $\frac{1}{4}$ -inch plate glass set in so as to be flush with the surface of the table. The drawer was painted white on the inside and in it was set a 6-light cluster of incandescent lamps mounted on a base block. The lights have a white porcelain reflector beneath them and are fitted with independent keys. Lamps of any usual candle-power may be put into the

sockets, but 8-candle-power lamps have been found sufficiently strong for most purposes and stronger ones are very trying to the eyes. Flexible leads are taken from a large wall switch to the cluster of lights so that the whole cluster may be lighted or shut off at one operation, but by means of the independent keys one or more lamps may be cut out separately. A number of vent holes were bored in the sides of the drawer to prevent overheating. The illumination is not quite uniform over the whole area of the glass, but by sliding the drawer or moving the block carrying the lamps in the drawer the most brilliant illumination can be obtained under that part of the work where it is most needed. A great variety of uses have been found for the table, such as comparison of alternative studies for a structure, comparison of contours of proposed surfaces with original contours, and the tracing of additions directly on to brown paper drawings and prints.

GREEK DETAILS.

Mr. T. Spence, in a paper on "Homer and Architecture and the Crafts," presented recently before the London Architectural Association had a great deal to say regarding Greek architectural details. From what I have seen in Greece, remarked Mr. Spence, the perfection of the workmanship of every detail in the architectural remains is very patent—from the perfect arrises of fillets and flutes of the immense Doric columns, the soft and accurate curves of the volutes in the Ionic caps, the daintiness, finish, and shape of the egg and tongue and other details of acanthus leafage on horizontal mouldings; the fine, sinuous, uniting curves, and relief of the acanthus when used in larger and detached forms; the true and delicate contours of their mouldings and the juxtaposition of larger flat curves with smaller incised and sharply cut members; the sense of decoration they get in soft horizontal lines of shadow being picked up and accentuated by the sharp incisive darks below. The evidence of reserve in the disposition of ornament—if their ornament was full of nice detail, it was laid on a quiet field, and thus lost none of its value. This vignetting of the sculptor's jewels is a most commendable feature in architecture. The satisfactory way in which their bas-relief panels filled up the space they were to adorn—the subject filled the space fully and with dignity, the heads not slipping far below the top moulding.

NOTES.

The London County Council have granted permission to the Royal Institute of British Architects to examine the designs prepared by an engineer, for the proposed new Vauxhall Bridge, in London. The Council has been petitioned by the Institute to appoint an architect as collaborateur with the engineer, in order that so important a structure may be artistic in character.

A resolution is said to have been adopted by the French Society of Architects which declares that architects should be given copyright privileges, not only as regards their plans and designs but also photographs of their completed buildings. Under the terms of this resolution the architect could claim a royalty on all sales of photographs or prints of his buildings. We agree with the opinion expressed by British architectural journals that this resolution goes too far—that architects should be satisfied with having their names attached to all prints of their buildings. "When the building is erected," says the Architectural Record, "it is no longer the architect's special property; it becomes public, for good or ill; and as such we fail to see why the architect should be given power to object to any photograph being taken of it, and to demand a royalty on the sale of prints."



TOWERS IN THE GROUNDS OF MONTREAL COLLEGE, SHERBROOKE STREET, PROBABLY THE OLDEST STRUCTURES IN MONTREAL, DATING BACK SOME 250 YEARS.

METHODS OF CONSTRUCTION IN RELATION TO INSURANCE.*

BY JOHN B. LAIDLAW.

The construction of buildings has ever been, and doubtless will ever be, a very important matter to the companies insuring property against loss by fire, and it affords me much pleasure to spend a few moments with the Architects' Association in discussing the standard of building construction adopted by the C.F.U.A. It is possible that in the past there has not been sufficient co-operation between those who supervise the construction of buildings and those who fix the insurance rate based upon the details of such construction, but whatever may have been the policy of the underwriters in the past, there is no question that to-day they stand ready to welcome any improvement in building construction and to assist that movement by means of discriminating rates as between buildings constructed according to their standard, and those in disregard of them.

The Underwriters have always recognized some of the essential features of good construction, such as that the walls of the building should be of brick or stone; that roofs should be of incombustible material—but they have only to a limited extent given attention to the interior construction, except as regards buildings to be used as manufactories. For the latter there has been for years a fairly strict standard, which while not requiring a building to be of what is now called mill construction, demanded strong bearing walls; limited the height and the area of the building; imposed serious extras in rate if there was a mansard roof; also required elevators to be in brick shafts outside a building, or be properly trapped at each floor; required stairways to be enclosed and have self-closing doors at each floor; also called for double floors and of sufficient thickness to carry the machinery in the building.

In accordance with this standard there was to be no inside sheathing of walls. The ceilings and joists were to be left open, and, speaking generally, an effort was made to avoid any concealed spaces in which dirt could accumulate, and fire not only originate, but be difficult to locate and extinguish.

The standard required the heating and the lighting to be as non-hazardous as possible; also the boilers for generating steam were to be in an outside separate building.

These were the general requirements, in addition to which there were other special requirements for each individual class of manufactory, such as requiring dry rooms in laundries to be of safe construction; shaving vaults and dry kilns in connection with woodworking

risks to be outside the building; painting and varnishing and upholstering in furniture factories to be in a separate section, and so on throughout the different classes of manufacturing risks.

These requirements have had a marked effect during the last few years in alterations made to old factories and in the erection of new buildings. It is now intended to adopt a stricter standard for manufacturing risks in accordance with the most up to date requirements of what is called mill construction, the main difference between the new and the old being that under the new the floors are to be without joists and made of solid planking laid on edge, resting on wooden beams supported on strong wooden posts, with 10 foot bays as a standard; this solid plank floor to be covered by a wearing floor of at least one inch in thickness. Such a floor interposes several inches of solid timber between the stories of a factory and leaves on the under side an almost absolutely smooth surface in which, or upon which a fire has difficulty to secure a lodgment. If these floors are left absolutely intact, a fire can, with comparative ease, be confined to the floor in which it originates, and such is the purpose of mill construction, but it is well to bear in mind that everything depends upon that "if"—if the floors are left absolutely intact. I have in mind a factory not 50 miles from Toronto of such construction, where the floor was cut to bring up a stairway. They might just about as well have saved their money and put in an ordinary floor for all the benefit gained.

Tonight however, it is proposed to ask your attention to the possibly more difficult subject of the construction of buildings intended for ordinary mercantile purposes in cities and towns.

When building a factory the first consideration is the business or purpose to which it is to be put. There is usually plenty of ground. The factory can be of any size, or height, or shape that the business requires, and the question of external appearance is but a minor one; when however one comes to consider the construction of a building for mercantile purposes in the heart of a city, say on King, or Yonge, or Queen streets in the centre of Toronto, there are a number of matters which cannot be overlooked, and it is well if any safeguards whatever against fire are introduced. The shape of the lot, the question of light, the business to be carried on, the question of access to the upper floors, must all be considered, and frequently the architect is forced to design a sort of general utility building when the tenant may not have been secured before the work commenced. These conditions have been recognized by the insurance companies and a standard has not been imposed which is too hard, but if anything rather lenient. It does not in any sense call for a fire-proof building, but rather for a well constructed building of joist construction with lath and plaster finish. In such however, there are many hazardous features which the architect can prevent being introduced, which if placed in the building will either induce a fire, or assist to spread it, and so must be charged for by the insurance companies. The standard reads as follows:—

CANADIAN FIRE UNDERWRITERS' ASSOCIATION.

MERCANTILE SCHEDULES.

BUILDING STANDARD.

A standard building is one having walls of brick or stone (brick preferred), not less than twelve inches thick at top storey (16 inches if stone), extending through and 36 inches above roof in parapet and coped, and increasing four inches in thickness for each storey below to the ground—the increased thickness of each storey to be utilized for beam ledges. Ground floor area not over 2,500 square feet (say 25 by 100); height not over three stories, or 40 feet; floors of 2 inch plank, (three inches better) covered by $\frac{7}{8}$ or one-inch flooring, crossing diagonally, with waterproof paper or approved fire resisting material between (if tin or sheet iron between, see deductions); wooden beams, girders, and wooden storey posts or pillars twelve inches thick, or protected

* Paper read before the Toronto Chapter of the Ontario Association of Architects.

iron columns; elevators, stairways, etc., cut off by brick walls or by plaster on metallic studs and lathing; communications at each floor protected with approved tin-covered doors and fire-proof sills; windows and doors on exposed sides protected by approved tin-covered doors and shutters, or wired glass in metallic frame or a water curtain; walls of flues not less than eight inches in thickness to be lined with fire-brick, well burned clay or cast-iron, and throat capacity not less than 96 square inches if steam boilers are used; all floor timbers to be trimmed at least four inches from outside of flue; heated by hot water or steam; lighted by gas; cornices of incombustible materials; roof of slate, metal, or tile; if partitions are hollow or walls are furred off there must be fire-stops at each floor.

For differences from above the following charges and deductions are made to and from the Key Rate of a town which is determined by the Fire Protection Appliances provided:

WALLS.

INDEPENDENT—Charge for each 4 inches deficiency in average from standard (if building over 4 stories high, double the charge)... .01
 On buildings over 3 stories high if average thickness less than 12 inches, add not less than... .05
 If two independent walls adjoin, 4 inches may be deducted from average of these requirements. Charge for one wall only—the most deficient.

A standard independent wall should be 12 inches the top story and increase 4 inches for each story to the bottom. This would require if 3 stories, an average of 16 inches; 4 stories, 18 inches; 5 stories, 20 inches; 6 stories, 22 inches; 7 stories, 24 inches.

PARTY—Charge for each inch deficiency in average from standard (if building over four stories high, double the charge)... .01
 If party wall less than 12 inches thick in any portion, add not less than... .05
 A standard party wall should be 16 inches at the top storey, increasing 4 inches for each storey below. Average required for three storey building, 20 inches; 4 storey, 22 inches; 5 storey, 24 inches; 6 storey, 26 inches; 7 storey, 28 inches, etc.

PARAPET.

Walls not Parapet, each exposed side... .01
 Parapet walls exceeding one foot above roof on all exposed sides, deduct for each foot in excess of one (not exceeding a total of .03)... .01
 Poor bricks or poor quality mortar... .10
 Glass and wood or iron fronts, for each not backed up with bricks and mortar... .03
 Glass and wood for each backed up... .01
 “ “ for each adjoining in row, in addition to above... .01

HEIGHT—For fourth story, add... .05
 Fifth story... .10
 Sixth story... .25
 For each story over six, add... .40
 These charges cumulative; for example a six story building would have 40 cents added.
 If any story double height, charge for two.

HEIGHT—Two story building, deduct... .02
 One story building, deduct... .05

STREET.

If street on which building fronts is inaccessible, unpaved, etc., not less than... .10
 (No charge if no fire department, and no charge for side or rear streets).
 If less than 60 feet wide, but over 50... .01
 If under 50 feet add for each 5 feet less... .01

STREET WIRES.

If to interfere with fire department... .01 to .03

WOODEN CORNICES, CUPOLAS, Dormer Windows or Verandahs... .01
 Not less than... .01

CEILING OR SHEATHING.

Wood (natural or painted) or Strawboard Ceiling, 1 story, .03; each additional story charge... .02
 Wood or strawboard siding, 1 story, .03; each additional story charge... .02
 Double each charge if wood be varnished.
 If side walls furred and plastered, half charge for wood sheathing.
 Cloth or paper ceiling or siding on wooden studs, each story charge... .10
 Metallic studs and lathing throughout, deduct... .05
 Metallic lathing on wooden studs, deduct... .02

FLOORS.

Tin or sheet-iron between floors, deduct... .02
 Water-proof paper or cement between floors, deduct... .01
 Floors water-proof and also inclined with scuppers to carry off surplus water to sewer, deduct... .02
 If floors exceed two inches in thickness, deduct .01 for each excess inch (in addition to above)... .01
 If grade floor fire-proof... .10
 Each fire-proof floor above grade (not exceeding a total of 25c.)... .05
 No cellar or basement, deduct... .05

AREA (GROUND FLOOR).

2,500 to 5,000, sq. ft. charge for each 1,000 in excess of 2,500 sq. ft... .01
 5,000 to 10,000, sq. ft. 3 stories, 1,000 in excess of 2,500 sq. ft... .02
 5,000 to 10,000, sq. ft., over 3 stories, 1,000 in excess of 2,500 sq. ft... .03
 10,000 sq. ft. or more, 3 stories, 1,000 in excess of 2,500 sq. ft... .02½
 10,000 sq. feet or more, over 3 stories, not over 6, in excess of 2,500 sq. ft... .04
 (Not exceeding a total of 200 cents).
 10,000 sq. ft. and over 6 stories, double the area charge.
 (Not exceeding a total of 300 cents).
 If building is of standard fire resisting construction throughout, halve the area charge.
 On-estory building, one-half the charge for 3 story.
 Two-story building, two-thirds the charge for 3 story.

If curtain, cross or division walls, sub-dividing and strengthening the building, even though with arched openings, deduct 10% of area charge for each wall so dividing the risk, not exceeding a total deduction of 40% of the area charge. Communications with adjoining buildings unprotected, charge for area both buildings, and rate as one (allowing for division wall). If fire-doors on communications are not standard, rate as if standard and make an additional charge under “Exposures” for defective doors.

Single Occupancy—If only one tenant outside of dwelling and office tenants twenty per cent. (20%) of the area charge may be deducted.

Small Risks under 1,500 sq. ft. ground floor area and not over 3 stories high, deduct... .05

FRAME REARS—Extensions for each 100 feet wall area, (not more in all than 15c.) charge... .01

If brick veneered, metal clad, or with openings protected with approved metal covering half charge.

STAIRWAYS.

Enclosed in lath and plaster hallway or provided with automatic trap-doors in floors... .03
 Similar to above with traps closed only at night... .05
 Fire-proof enclosure, but defective doors, etc... .02
 Enclosed in wood... .07
 Enclosed in wood with self-closing doors each floor... .05
 Open... .10

If more than one stairway, charge for worst and add one fourth charge for each additional.

One half charge for stairway if charge for elevator—halve the smaller charge.

If elevator and stairway are contained in the same shaft or opening, only one charge for the two.

No charge for stairways in buildings occupied exclusively for offices and dwellings above first story when stairway does not open into store.

ELEVATORS.

Enclosed in lath and plaster shaft or hallway, or if provided with approved automatic trap doors at floors. .05

Fire-proof shaft, but defective doors, or walls not through roof. .03

Open. .10

Wooden shaft without approved automatic traps. .15

One-half above charges for elevators in buildings otherwise standard, or in office building.

If more than one elevator, charge for worst and add one-fourth charge for each additional.

WELL HOLES.

If open, add for each (half charge for approved traps) from. .03 .05

CHUTES, VENTS AND DUMB WAITERS.

(Unless fire-proof shaft), and small floor openings—Add for each, (if trapped half charge). .01

SKYLIGHTS.

If of thin glass (less than $\frac{1}{4}$ inch), in any kind of frame, charge for first 25 feet of total area .02, and for each additional 25 feet of area .0 $\frac{1}{2}$. If more than one small sky-light charge for each (not more in all than 25c.). .02

If skylight is monitor style, charge for square feet in sides as well as top.

If $\frac{1}{4}$ inch glass in wooden frames, half charge.

If $\frac{1}{4}$ inch glass in metal or protected frames, one-fourth charge.

If protected above and below by wire netting, halve the charge.

If wired glass in metal or protected frames, free.

Same charges for floor-lights less than $\frac{3}{4}$ inch thick.

IRON COLUMNS UNPROTECTED.

Cast Iron .03; steel or wrought. .05

LIGHTING.

Electricity, approved. .02

Any other system for lighting must be subject to approval of Local Board of Underwriters and charged for by rule.

Kerosene (no charge if charged for electricity), not less than. .02

Kerosene lighting in hazardous risks, such as paint shops or carpenter shops, not less than. .10

HEATING.

If by hot air furnace, not less than. .03

Furnace with metallic cold air box, and all vertical hot air pipes, through brick walls and one register fastened open, add. .02

Stove (for each additional stove .01). (Must have metal under). .02

Stove in wood working establishments. .25

Natural gas or oil fuel, approved pressure regulating appliances. .05

CHIMNEYS.

Not built from ground, but on brackets, charge for each. .05

If inadequate for service required, or walls of flues less than 8 inches thick, unless lined with pipe, not less than. .05

If resting on attic floor beams or roof joists, add. .25

Poor bricks or mortar. .20

Terra-cotta or cement. .50

STEAM BOILERS.

(Other than heating). Charge if in basement

.05; above basement .10; wood shavings for fuel 1.00 additional. .01

If boiler in fire-proof room cut off in approved manner, no charge.

POWER.

Charge according to hazard. .01

ROOF.

Composition and gravel, if not well covered. .02

Shingles (if laid in mortar 5c.). .10

Mansard with wooden frame, 4 story or lower building, for each lineal five feet, but not more than 10c. for one side or 15c. in all. .01

Mansard on building 5 stories or more in height, $\frac{1}{4}$ c. additional for each lineal five feet, for each story over four. .01

BLIND ATTIC, ROOF SPACE, COCK LOFT.

Take maximum height if slanting roof, and charge for each vertical foot .01, not less than .03 or more than. .05

AGE OF BUILDING.

Over twenty years charge. .02

OCCUPANCY.

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

PROTECTION.

Charge if not within 300 feet of hydrant on 4 in. main circulating or 6 in. main dead end. .05

Iron fire escapes outside of building, with landings at each floor, deduct. .02

Casks of water or filled pails on each floor (6 filled pails to each 2,500 square feet of floor area), deduct. .05

(One-half number may be filled with sand. One cask may be considered the equivalent of three pails.)

Standpipe, internal with tank supply, deduct. .02

“ “ without tank supply, deduct. .01

Standpipe, external, with siamese connection for use of fire department, deduct. .01

Each side or rear accessible to fire department (no deduction for front), deduct. .02

Fire department house, engine, hose or hook and ladder, within 300 feet .01; if next door or on opposite side of street deduct. .02

Basement and sub-cellar perforated pipe sprinklers, deduct. .02

Automatic sprinklers in basement, (no deduction if allowance has been made for sprinklers throughout building). .05

Roof hydrants if protected from freezing. .02

Floor beams and girders self-releasing. .01

Auxiliary private fire plant, force pump, etc. .05
 Watchman, with portable clock. .05
 " with electric detector. .10
 EXPOSURES. To be charged by inspectors according to circumstances.
 CONFLAGRATION HAZARD. Charge for such when conditions require.
 ADD FOR FAULTS OF MANAGEMENT, EASILY CORRECTED.
 140 If stovepipes through floors or partition, not protected, .50; through window, roof or wall, with double metal chimney, .50; not protected, 1.00; entering bottom of flue vertically, .25; entering flue in attic or unused room, etc. .25
 140a Floor beneath stove not protected. .05
 141 Bottom of elevator shaft used for closets, etc., or waste. .50
 142 Swinging gas brackets or bracket lamps unprotected, for one .05, each additional one. .01
 143 Untidiness, rubbish, ashes, etc., especially in cellar or attic, .25; packing material not in bins. .15
 144 Cracked or bulged walls, thin and worn floors, broken plastering, broken windows, etc. .10 to .25
 145 Empty boxes, rubbish, etc., in rear yard, alleys, window recesses, under sidewalk, gratings, etc. .10
 146 Open lights in show windows or electric bulbs covered with tissue paper or paper shades. .25
 147 Sawdust on floors, sawdust spittoons, etc. .25
 148 Kerosene used to sprinkle floors. .25
 149 Ash and waste cans, not metal. .10
 150 Furnace top within 4 inches of wooden beams or ceilings, if brick; or within 12 inches if portable, with metallic shield .10 to .25
 151 Fire-places, hearths on wooden beams, or floors within 16 inches of fire-place; or wooden fire-boards, or summer pieces, or unprotected wooden mantels, or open stovepipe holes. .05 to .25
 152 Steampipes in contact with wood, not less than. .01
 153 Elevator or other shafts communicating with roof space. .25
 154 Electric lighting or other system, with installation not in compliance with underwriters' rules; or arc lights unprotected by tight globes or metal screens. .25
 154a Crowded merchandise without proper aisles, opposite or too near windows, overloading, not less than. .25

Now if you will allow me I will take up each feature in detail.

First—the walls. It is necessary to have a solid wall, not only to sustain whatever weight the building may, during changes of occupancy, be called upon to bear, but also to stand firm and keep out a fire which may burn the neighboring premises. We therefore ask that the side walls shall rise above the roof three feet, as a parapet over which the flames will have difficulty in leaping. We sometimes find that a wall is carried up three feet above the roof but the cornice is run continuously along the front from one building to another. The cornice should be cut as well as the roof.

We call for increasing thickness of walls as the building increases in height, and that the ledges formed by the increase in thickness shall bear the floor joists. This is very important as we are constantly finding that the practice of inserting joists in the walls by leaving out a couple of bricks, not only conveys fire through the walls should the adjoining building burn, but also when a serious fire occurs in the supposed building under consideration, the falling of the floors brings the walls down, causing a total loss to it and to its contents, and also lets the fire through into the next building.

Party walls require to be four inches thicker than in-

dependent walls, the reason for which I am sure will be apparent to every architect. There are many party walls erected in which the joists have only four inches of brick between their ends, and in some cases the joists actually meet and overlap. Such walls are hardly worthy of the name.

The schedule imposes an extra charge on the building if a large amount of the front is of glass or wood, and the charges for exposure to a building so constructed, are also increased.

Our standard calls for a building of moderate height; if that height is increased, extra charges are imposed.

There is a small charge for wooden cornices on building, but such increase the charge for exposure from the adjacent buildings and should be avoided as much possible.

The standard ceiling is plaster upon wooden lath, or a ceiling of metal. There is of course no objection if an old ceiling of plaster upon lath, is covered with metal.

Wood for sheathing of walls or ceilings is decidedly objected to, and still more so if the wood be varnished, the charges in that case being doubled. With wood at its present price there is no economy in using such inflammable material for partitions or ceilings, and the insurance companies hope that such will soon be a thing of the past. If metallic lath is used throughout the building instead of the ordinary wooden laths, a reduction is allowed.

The standard calls for floors to be three inches in thickness. If they are thicker than that, an increased deduction is allowed for each inch in excess. It is recognized that there are very few floors that exceed two inches in thickness, and so in applying the charges, there is a deduction allowed for every inch in excess of two inches.

Then again, if the floors are double and if they have metal between, or if the floors are made water-proof, and drained to carry off any water thrown upon them, or if the floors are made fire-proof, that is, of steel and concrete construction, with the steel properly protected by metal lath and plaster, or porous tile, deductions are allowed.

If the area exceeds the standard, there are extra charges, but even in this case if there are numerous brick walls sub-dividing the building, the area charge is reduced. It is very difficult to locate a fire which may originate in a building of large area, as the smoke at once fills the whole building and when the firemen arrive they waste a large amount of precious time in endeavoring to get at the exact spot where the stock or building is burning.

When the Murray store burned, the building was filled with smoke and the firemen could not see what they were doing; they found after they had been working for two hours that they were throwing the water against a brick wall, the fire being on the other side of it. This does not happen in a small store, or one which is divided into sections.

Now let us suppose that a building has been constructed with solid walls, with double floors, that metallic lathing has been used throughout the building, and what has been gained if numerous openings from floor are introduced?

I would like to draw your attention to Robert Simpson's building on the corner of Queen and Yonge streets, one of the best examples of fire proof construction in the city. In it there is an immense light well from cellar to roof. There are also openings from floor to floor for stairways and elevators. A fire starting in that building would have every opportunity to spread from cellar to roof in an incredibly short time, and if such did happen it would be found that the fire-proof building was nothing more than an immense stove in which the contents would be speedily and completely consumed, although the building itself might remain comparatively unharmed. Were it not for the introduction of automatic sprinklers such a risk would probably not be insured for less than 5% per annum,

and even at that rate the insurance secured would in all probability be but a fraction of the value.

The insurance companies recognize the difficulty of providing an absolute cut-off between floors in a mercantile building, but such is possible, either by having a fire-proof elevator and stairway annex cut off from each floor by fire-proof revolving doors, or if the elevators and stairways must be in the building, then in a shaft walled in by metallic lath and plaster, and (or) wired glass. Well holes or light wells can also be closed by wired glass either perpendicularly around the shaft, or horizontally at the floor line, or better still, construct the building so as not to require such at all. If elevators and stairways are introduced, the companies must charge for them, the charges being so fixed that even if the owner cannot entirely remove the hazard, that the companies will make some allowance for a partial protection.

In this connection let me give you an illustration. If a property owner were to erect six stores alongside of one another, each, one story high, with a brick wall in rear and in front and at each end, but with only lath and plaster partitions between each store, everyone passing would say; that is a shell; that is no better than a frame building; that is a fire trap. But if we can imagine the supposed property owner turning the supposed block of stores upon end so that the first store to the left is the first storey of the new building which is six stories high, and if the supposed property owner immediately starts to make openings between each of the lath and plaster partitions, inserting stairways from floor to floor, and also introducing an elevator from cellar to garret, the passer-by looks and says, that is a splendid building.

We require that skylights be of wired glass in metal frame, and where so built there is no charge. A skylight of thin glass in wooden frame is a conflagration breeder. It not only assists a fire inside but invites the outsider to come in.

Heating by hot air furnaces and by stoves has cost the companies a tidy sum and such is charged for.

Chimneys should not be placed on brackets. Such is a dangerous expedient; if it must be resorted to, a charge must be imposed.

The mansard roof is an undesirable style which is rapidly disappearing. Where such is constructed it necessarily means that a large amount of wooden material is placed in the most dangerous position in the building—hardest to reach should a fire occur, and the point to which all flames naturally go whenever a fire breaks out. Such a roof either entails the destruction of the building or a very serious loss, owing to the amount of water required to extinguish a fire in it.

Many buildings are constructed with blind attics. Such should be avoided wherever possible; particularly should great care be taken that there is no opening from an elevator shaft into a blind attic. Such condition is frequently found and is exceedingly careless and dangerous.

A good many buildings are still roofed with shingles. It is hoped that the architects of Toronto will use their influence to discontinue the use of this most dangerous roof covering. Numerous conflagrations can be traced to the fact that the buildings had shingle roofs. Such not only burn rapidly themselves, but set fire to others, and after a fire has been burning a short time, the shingles will rise from the roof and fly like birds to a considerable distance.

If internal protection against fire is provided, there is an allowance made, particularly for casks and pails, which any workman or even child, knows how to use, but the companies place their chief reliance on the speedy arrival of the fire brigade, and also that the construction of the building is such that the fire will not have been able to gain undue headway before the brigade arrives. If the building is constructed with open elevators, open stairways, or open well holes, a fire will spread with great rapidity from cellar to roof, and by the time the brigade will have reached the scene, the flames will probably be breaking out of every window and cannot be stopped by any brigade short of almost

a total loss. If the elevator had been trapped, the stairway or well hole closed, the fire would probably be still burning upon the floor in which it originated, and the firemen would have a fair chance to extinguish it.

It may be of interest to the architects to know that the Mercantile Schedule which we are to discuss this evening, is based on a schedule compiled a few years ago by a large committee composed of the leading underwriters in the Eastern States, who after more than two years of conference and committee work, published the Universal Mercantile Schedule. I have a copy of this schedule here and can procure others if your members desire to have them for reference.

This work is the basis of the schedule we have adopted in Canada. It will I think repay any time an architect may devote to its study, and I take the liberty of commending it to you to-night.

I may also point out that the schedule referred to has not as yet been put in force in Toronto, and may not be for a few months or even a year. Anyone however, who is about to build would be wise to comply with the requirements of the standard.

The schedule recognizes that a building may be well constructed and still be used in a careless and dangerous manner, and so there are charges for "Faults of Management," such as unprotected stove pipes through floors or partitions—unprotected floors under stoves—bottom of elevator shaft used as a waste dump—swinging gas brackets—badly placed heating furnaces, and dangerous fire places.

The last charge for crowding and overloading the building will, I am sure, appeal to all here as a direct incentive to tear down and build greater.

I am afraid you are all weary of this subject, which I regret I am not able to make as interesting as a critical dissertation on the colonial style or some other one equally fashionable, but I am nearly through now and merely wish to direct your attention to some features of our charges for exposures.

A study of conflagrations in cities shows that they are generally caused by unprotected openings in adjacent walls, a fire being enabled by such to spread quickly to several adjacent buildings and soon provide the brigade with a job quite too large for their fire-fighting equipment. Care should therefore be taken by the architect to guard against this danger, and when there must be numerous window openings in a wall facing another similar wall a few feet distant, that such are protected by outside shutters of wood covered on both sides with metal, or have a metallic frame and wired glass in each exposed window, or provide a water curtain. Also if possible, avoid having the windows in one wall directly opposite the windows of the other. This can often be easily arranged.

Do not cut off a one storey section by a solid wall on the ground floor and leave several windows in the higher building looking down upon the roof of the lower one. Avoid heavy wooden cornices, and if there must be an overhanging eave, see that it is covered with metal. In Montreal a very popular form of roof is centre drained, such not requiring any projecting eave. Also avoid breaking division walls between buildings. It is astonishing to what an extent this practice has grown, until we sometimes find that in as many as ten adjoining buildings there is not one party wall absolutely intact.

If party or division walls must be cut, then be careful to leave no wood about the opening, which should be arched and provided with a sill of stone or concrete, while the door to close the opening should be really and truly standard—such, properly hung on an incline are less in the way, and less unsightly than the old hinged door.

The insurance companies in adopting this standard, hope that it will induce more careful planning, more solid construction, fewer fires, and lower rates. The standard should be of service to the up-to-date architect and we hope it will be freely used by you all in persuading the property owner that good construction and good returns go hand in hand.

THE NOVA SCOTIA FREESTONES.

The changing fashions in stone used for building purposes in all the large cities of America have called out many comments, not alone from practical stone men, but also from general writers who are impressed by the varying effects of city architecture. The brownstone fronts of New York, which formerly lined street after street, with their stately, if sombre facades, figure in every description of the city. As the brownstone yielded place to other materials, every visitor to the city felt called upon to record the change. About a generation ago one stone, although in several colors, was largely used in New York and in all of the leading eastern cities. It has everything to commend it; beauty of color, fineness of texture, ease of working and durability. But its reign was comparatively brief. After a few years of high favor, it passed almost wholly out of the market and now scarcely a foot of it is used in New York and but very little in any of the American cities. Perhaps one reason for this is that it was not an American stone and that our architects and builders thought that they should give the preference to a native product. This was the Nova Scotia freestone. The buildings in which it was used that are still standing afford striking testimony of its excellent quality. About 1865 Mr. Charles D. Archibald furnished the Nova Scotia sandstone in what is known as the olive color for the wall around Central Park. This stone came from the Mary's Point quarry in New Brunswick. Stone in a wall like this in such an exposed position does not have the protection from the weather that is afforded by a building, but this has lasted admirably and few freestones would have endured as well.

About three or four years later one of the first building jobs in the Nova Scotia stone was the Dry Dock Savings Bank on Fourth Avenue, which is still standing. This stone was furnished by the late G. P. Sherwood from the "Budro" quarry on the Petit-Codiac river in New Brunswick. Mr. Sherwood also furnished the stone for the old Hanover bank building, on the corner of Pine and Nassau streets, recently torn down to make room for the new twenty-two story structure of pink Milford granite. When the old building was destroyed it was seen that the stone had weathered perfectly, that every arris was as sharp as when originally cut and that the carved work still bore the mark of the chisel. Many other important buildings were erected of this stone, among them being the block at the corner of Forty-fifth street and Sixth avenue, from the Sherwood quarries, and the Sloane building on Broadway, of brownstone from Mary's Point.

In the New England cities the Nova Scotia freestone was held in still higher favor and its general use by the architects and builders continued for an even longer time. Among the notable structures in Boston which made use of either the russet or olive stone were the

Fifty Associates building on New Washington street, the Harvard buildings on Arch street, the Boylston Bank building, the Young Men's Christian Union on Boylston street, the Columbus Hotel, Parker Memorial Hotel, Hotel Commonwealth, Dr. Lothrop's church, Providence and Lowell depots, the Catholic Cathedral on Washington street, and Prof. Agassiz's Museum, besides many imposing blocks of dwellings and business houses.

Although there has ceased to be any considerable market for this stone in the States, it is in good demand throughout Canada. There is every reason for this aside from mere local pride. Some of the quarries have been worked for a great many years, but the amount of high-grade stone that is still available is unlimited. In a few places quarrying is conducted at a disadvantage. On the River John and the River Philip, most of the quarries are below the river level. The method of working them is to build a dyke or dam along the shore, pump out the water within and then open a quarry. The objection to this method is that it is impossible to keep the water out at all times and it is well known that salt water has a very deleterious effect on sandstone. It frequently causes it to scale or chip and at the best it almost certainly leads to efflorescence. So general is this fact recognized that when the stone used to be shipped to the States on barges the dealers insisted upon its being stowed in the hold and would not purchase it if it made the sea voyage on the decks. At Wallace Harbor the quarries are admirable, having level beds capable of furnishing fine platforms. The stone is overlaid with from 12 to 20 feet of stiff clay. This is a peculiar formation and has almost a leathery toughness. It has to be removed with a pick. At Kennetcook is found a dark brown and an olive and a blue grit, the latter of which is used for grindstones. A cargo of this grit was sent a number of years ago to the water shops at Manchester and other place in Great Britain, and the workmen declared it made the finest grindstones they had ever used. For some reason no great industry was ever built up at this place. Manuidie was also another place that was famous for its grindstones and scythe stones. These deposits were worked for many years by the Seaman Brothers, whose name was known throughout the world.—Stone.

THE BUILDERS' FOREMAN AND CLERK OF WORKS.

At a recent annual dinner of the Provident Institution of Builders' Foremen and Clerks of Works of Great Britain, the chairman, Mr. F. Higgs, thus described the qualifications of a successful builders' foreman and clerk of works—"Every good foreman should be careful, accurate and shrewd, and should have patience, forbearance and tact, personal magnetism, organizing power, fidelity to duty—in fact, character. The Clerk of Works should be honest in purpose and action, disinterested, fair and unbiased in judgment, open-minded for new methods and ideas, not wanting in a due sense of proportion and able to see two sides to a question. The ideal foreman and clerk of works did not quarrel, but pulled together, for though there might be two ways of looking at a work, it must not be forgotten that there was only that one work."

Cold Water Paint for Outside and Inside Use.

Weather Proof.
Fire Proof.

Standard ; Matchless Quality.



WHITE AND COLORS.

COLOR CARDS AND PARTICULARS FROM

Durable.

W. A. FLEMING & CO.,

771 Craig st., Montreal.

—THE—

CANADIAN ARCHITECT AND BUILDER

A Monthly Journal of Modern Constructive Methods,

(With a Weekly Intermediate Edition—The CANADIAN CONTRACT RECORD).

PUBLISHED ON THE THIRD WEDNESDAY IN EACH MONTH IN THE INTEREST OF

ARCHITECTS, CIVIL AND SANITARY ENGINEERS, PLUMBERS
DECORATORS, BUILDERS, CONTRACTORS, MANUFACTURERS OF AND DEALERS IN BUILDING
MATERIALS AND APPLIANCES.

The C. H. MORTIMER PUBLISHING CO. of Toronto, Limited,

Publishers,

Confederation Life Building, - TORONTO, CANADA.

Telephone Main, 2362.

Branch Offices:

IMPERIAL LIFE INSURANCE BUILDING, MONTREAL.
Bell Telephone 2299.

22 GREAT ST. HELEN'S, LONDON, E.C.

SUBSCRIPTIONS.

THE CANADIAN ARCHITECT AND BUILDER will be mailed to any address in Canada or the United States on the following terms: Architects' Edition, \$3.00 per year; Regular Edition, \$2.00 per year. The price to foreign subscribers is: Architects' Edition, 16 shillings; Regular Edition, 12 shillings. Subscriptions are payable in advance. The Journal will be discontinued at expiration of term paid for, if so stipulated by the subscriber; but where no such understanding exists, will be continued until instructions to discontinue are received and all arrears of subscription paid.

ADVERTISEMENTS.

Prices for advertisements sent promptly on application. Orders for advertisements should reach the office of publication not later than the 12th, and change of advertisements not later than the 5th day of the month.

EDITOR'S ANNOUNCEMENTS.

Contributions of value to the persons in whose interest this journal is published are cordially invited. Subscribers are also requested to forward newspaper clippings or written items of interest from their respective localities.

Subscribers who may change their address should give prompt notice of same. In doing so, give both old and new address. Notify the publishers of any irregularity in delivery.

ONTARIO ASSOCIATION OF ARCHITECTS.

OFFICERS FOR 1903.

PRESIDENT - W. L. SYMONS, Toronto
1ST VICE-PRESIDENT - GEO. W. GOINLOCK, Toronto
2ND VICE-PRESIDENT - PROF. C. H. C. WRIGHT, "
TREASURER - A. R. DENISON, "
REGISTRAR - W. R. GREGG, 94 King St., Toronto.

COUNCIL:

EDMUND BURKE - Toronto
LAWRENCE MUNRO - Hamilton
JOHN GEMMELL - Toronto
HENRY SIMPSON - "
J. W. SIDDALL - "

PROVINCE OF QUEBEC ASSOCIATION OF ARCHITECTS.

OFFICERS FOR 1902.

PRESIDENT - J. VENNE, Montreal.
1ST VICE-PRESIDENT - W. E. DORAN, Montreal.
2ND VICE-PRESIDENT - R. P. LEMAY, Quebec.
SECRETARY - PROF. S. H. CAPPER, Montreal.
TREASURER - J. S. ARCHIBALD, Montreal.

COUNCIL.

G. E. TANGUAY - Quebec.
A. RAZA - Montreal.
A. C. HUTCHISON - Montreal.
D. R. BROWN - Montreal.
A. A. COX - Montreal.
S. LESAGE - Montreal.
AUDITORS—C. DUFORT, Montreal; J. H. LEBRON, Quebec.

TORONTO BUILDERS' EXCHANGE.

BOARD OF DIRECTORS:

JOSEPH RUSSELL, President.
R. G. KIRBY, 1st Vice-President.
JOHN H. RIDGE, 2nd Vice-President.
DAVID WILLIAMS, Treasurer.
MESSRS. CLAY AND HOLMES, Auditors.
JOHN SCOTT.
JOHN M. GANDER, Representative on Technical School Board.
JAMES B. THOMSON, Representative on Exhibition Board.

MESSRS. NELSON
WELLER.
CRANG
MARTIN
SMALLWOOD.
LOGAN.

LONDON BUILDERS' EXCHANGE

BOARD OF DIRECTORS:

J. C. SIMPSON, President.
JOHN NUTKINS, 1st Vice-President.
JOHN WHITTAKER, 2nd Vice-President.
GEO. S. GOULD, Secretary-Treasurer.

WM. TYTLER.
THOS. JONES.
ED. MARTYN.
GEO. YOUNG
S. STEVELY.

VANCOUVER BUILDERS' EXCHANGE.

BOARD OF DIRECTORS

E. COOK, President.
A. E. CARTER, Secretary.
H. A. BULL, Treasurer.
T. BRADBERRY

C. P. SHINDLER
K. M. FRASER.
E. G. BAYNES.
D. SAUL

WINNIPEG MASTER CARPENTERS' ASSOCIATION

BOARD OF DIRECTORS

A. MACDONALD, President. A. McCORMICK, Secretary.
A. G. AKIN, 1st Vice-President. J. G. LATIMER, Treasurer.
A. SUTHERLAND, 2nd Vice-President.

MASON BUILDERS' EXCHANGE.

BOARD OF DIRECTORS:

D. D. WOOD, President. A. N. McCUTCHEON, 1st Vice-President
W. F. LEE, 2nd Vice-President. A. T. DAVIDSON, Secretary.
EDWARD CASS, Treasurer WILLIAM ALSIP.
D. T. JACKSON. ANGUS BROWN.
J. MALCOM.

MONTREAL BUILDERS' EXCHANGE.

BOARD OF DIRECTORS:

C. T. WILLIAMS, President. H. R. IVE.
C. W. HUGHES, Vice-President. JAMES PATON.
G. J. SHEPARD, Secretary-Treasurer. N. T. GAGNON.
JOHN WIGHTON. JOSEPH LAMARCHE

CHAMBRE SYNDICATE DE LA CONSTRUCTION.
(French Builders' Exchange.)

8, St. James Street, Montreal.

BOARD OF DIRECTORS.

J. B. GRATTON, President. FELIX SAURAGEAN.
G. MENARD, 1st Vice-President. L. Z. MATHIE.
T. CHARPENTIER, JR., 2nd Vice-President. H. CONTANT.
ALCIDE CHAUSSE, Treasurer. E. Z. COTE.
N. T. GAGNON, Secretary. LOUIS PAVETTE.

VICTORIA BUILDERS' EXCHANGE, VICTORIA, B. C.

BOARD OF DIRECTORS:

W. D. MCKILLICAN - Chairman
E. W. WHITTINGTON - Secretary
THOS. CATTERALL - Treasurer

NOTES.

It is stated that during one month recently, nearly 100,000 tons of iron and steel material were imported through the three ports of New York, Philadelphia and Baltimore. The shipment included pig iron, steel billets, steel and iron rails, structural steel and wire rods, and plate bars. The immediate demand for such products is so great that the domestic plants, extensive as they are, cannot meet it.

DON VALLEY BRICK WORKS
TORONTO

ROBERT DAVIES, PROP.
MANUFACTURER OF
FINE GRADE PRESSED BRICKS,
IN ALL COLORS & DESIGNS.
ENAMELLED BRICKS,
VITRIFIED PAVING BRICKS,
ARCHITECTURAL & POROUS TERRA-COTTA.

MEN WHO BUILD A SKY-SCRAPER.

According to the Architects' and Builders' Journal the following staff is employed in the erection of a modern sky scraper :—

Laborers.....	300
Carpenters.....	100
Concrete layers.....	30
Riggers and riveters.....	150
Stone-masons.....	15
Tile layers.....	30
Electricians.....	30
Plumbers.....	20
Bricklayers.....	20
Plasterers.....	50
Marble workers.....	20
Housesmiths.....	25
Painters.....	25
Steam-fitters.....	25
Roofers.....	30
Sheet-metal workers.....	20
Elevator workers.....	30
Boiler and engine erectors.....	30
Mail-chute workers.....	10
Stationary engineers and firemen.....	10
Total.....	970

PERSONAL.

A partnership has recently been formed between Messrs. G. W. Grant and A. E. Henderson, architects, of Vancouver, B. C.

Mr. L. Feystore, builder, and a resident of Toronto for thirty years, died in that city recently following an operation for appendicitis.

Mr. Silas E. Hoidge, a well-known and highly respected builder of Toronto, died in that city last month as the result of a fall from a building on which he was working at Toronto Junction.

Acknowledgement should have been made in our March issue to the publishers of La Presse, Montreal, to whose courtesy we are indebted for the use of the plate from which was printed the illustration of the Polytechnic School.

The Building Contractors' Council, of Chicago, have determined to sign no agreements with Unions that do not contain a clause prohibiting sympathetic strikes, limitation of amount of

work a workman may perform in a day, or that do not permit the unlimited use of machinery, the employment of apprentices, and the right to employ or discharge any workman at pleasure.



The most artistic and durable color effects on shingles are produced with Shingletint, which is a scientific combination of linseed oil, coloring matter, creosote, and the necessary drying agents.

Among the many shingles stains offered Shingletint is conspicuous not only for its superiority but because it can be called for by its distinctive name, thus offering the consumer protection against inferior goods offered for the same purpose.

When buying Shingle Stains it will be worth while to ignore the "just as good" argument and insist upon Shingletint.

Stained woods and descriptive literature sent free upon request.

Berry Brothers, Limited

Varnish Manufacturers,
New York Philadelphia Chicago St. Louis
Boston Baltimore Cincinnati San Francisco
Factory and Main Office, DETROIT

The Canadian Bridge Co., Limited
Walkerville, Ontario.

... MANUFACTURERS OF

STEEL BUILDINGS, ROOF TRUSSES

Railway and Highway Bridges and Structural Steel and Iron Work of all descriptions
Estimates furnished upon application.

TERRA COTTA FIREPROOF BUILDING MATERIAL

POROUS TERRA COTTA among underwriters is classed as preferred risk, and the schedule of rates now enforced in the city of New York shows a difference, often great, which, computed means an annuity on large sums of money.

This indisputable fact appeals to architects as representing clients who may soon be exposed to the same classification in Canada. An apparent saving in selecting cheaper fireproof material may be more than lost through increased insurance cost.

POROUS TERRA COTTA FIREPROOFING is a credit to the buildings in which it is used and increases their selling value.

The **Montreal Terra Cotta Lumber Company, Limited,**
N. T. Gagnon, Selling Agent, 204 St. James St., Montreal, Canada.

ADVERTISING VALUE.

It is very well for some men to say they believe in advertising, and to expect a liberal return from their investment merely as a reward for their faith in the value of publicity. It is quite another thing to get value out of the space used. The belief in advertising is natural since advertising has done much for many establishments and individuals, but it will not do much unless much is put into the advertising. The real secret about business is business, and the real worth of advertising depends on business also. It is necessary to put common or uncommon business judgment into the space used for the benefit of the business and to make the establishment, the goods and the methods stand out before the possible customer in a light which will be pleasing and help the public in general to understand the worth of the stock. There are those who talk ethical advertising and ideal publicity to an extent that they really believe in it themselves, but will be disappointed in results unless they get something into that advertising which will give it vitality. It is useless to expect to impress a public with the standing of a firm as an up-to-date business combination unless there be life in the advertisement. The message must show the strength of the merchant behind it and must demonstrate the merits of the place. The point is the life and character of the announcement. Make it stand out in every line and make it so conspicuous that any possible buyer will see it and appreciate it.—Advertising World.

NOTES.

At Upleatham, North Yorkshire, is said to be the smallest church in England. Its size is 17' 9" x 13'. The building which is 900 years old, is now used as a cemetery chapel.

An International exhibition of building materials and methods has been arranged

or at Paris this year. The date of opening has not yet been announced. Great Britain, Germany and Belgium will be well represented. A leading feature of the British and Belgian exhibits will be plans for low cost dwellings.

Upwards of twenty committees and sub-committees composed of persons prominently identified with the iron and steel industries of Great Britain have been engaged for a considerable time on the work of standardizing structural iron and steel sections, equal, unequal, and bulb angles, bulb tees and plates, H beams, Z and T bars, channels and beams. Thirty sections of H beams are given, varying from 3in. by 1½in. to 24in. by 7½in., and weighing respectively from 4 lbs. to 100 lbs. per ft. The Engineering Standards Committee states that beams ordered to the standard thickness shall be practically accurate in profile; but if the thickness of the web is less or greater than these standards, the width of the section will be decreased or increased by the same amount; and it is suggested that beams be ordered by depth of section, width of flanges, and weight per foot. It is claimed that the standardization of sections will effect a saving of several million pounds annually.

William Clendenning writes in "Fire-proof" on the subject of "Misplaced Fire Escapes." He states that hundreds of fire escapes in our principal cities follow window lines vertically, from top to bottom, thus exposing them directly to the action of fire when it bursts from the windows at each floor, rendering the escapes unsafe and unfit for the exit of any human being, because they become red-hot in many cases, thus making them death-traps rather than fire escapes. In the course of a single street car ride in Chicago the author says he counted on one side of the street sixty-five fire escapes so located as to be utterly useless in cases of fire on either side of the lower

stories. The remedy for this alarming state of affairs is to place the fire escapes at or near a corner, or at least removed from immediate proximity to windows, with platforms communicating at each floor, and so give the tenant a chance for his life. This subject is probably new to most people and should be looked into by building inspectors. A fire escape placed in front of a row of windows should be condemned and the owner required to remove it to a comparatively safe position.

John Mackay & Coy., of The Canadian Bank of Commerce Building, Toronto, would like to be placed in communication with a firm of architects of the highest professional standing, and of special experience in the erection of modern Bakeries. Communications will be held in the strictest confidence.

LIGHT

The "Best" Light

Brighter than Electricity or Acetylene
and Cheaper than Kerosene

Makes and burns its own gas. It is portable. Requires no pipes, wires or gas machine. A safe, pure white, powerful steady light. 100 candle power costs 2 cents for fifteen hours. Permitted by Fire Insurance Underwriters. No wicks to trim, no smoke or smell. Saving effected by its use quickly pays for it. Over 100 styles for indoor and outdoor use. This is the Pioneer Incandescent Vapor Gas Lamp. It is perfect. Beware of imitations. Agents wanted everywhere. Every lamp warranted. **THE BEST LIGHT CO.,** 225 East Fifth Street, Canton, Ohio.



LIGHT

Desirable that you mention THE CANADIAN ARCHITECT AND BUILDER.

The Sun Portland Cement Company, Limited, Owen Sound

MANUFACTURERS OF

The Sun Brand A High Grade Portland Cement

ASK US FOR QUOTATIONS

Suitable For All Purposes

JAS. A. CLINE, Managing Director

ROMAN THE PERFECT BUILDING STONE

Cheaper than natural Stone.

Absolutely fire proof material.

No limit to its possibilities of application.

Contracts executed for anything in Stone or Concrete

Correspondence and Inspection of our plant solicited.

Manufactured by the most modern process from select building stone.



**STRENGTH
AND
BEAUTY**


Has the exact appearance of natural Stone and is stronger and more durable.

Made in any color or texture for exterior or interior finish,

STONE


THE ROMAN STONE CO., LIMITED, MARLBOROUGH AVE., TORONTO.





THE ALEXANDER ENGINE

HOUSE IN PARK ROAD, TORONTO.
BURKE & HORWOOD, ARCHITECTS.




ENTRANCE GATEWAY
UPPER CANADA COLLEGE

TORONTO.


*Symons & Rae, Architects
Toronto, March, 1903.*

SCALE - 1" = 10'




ENTRANCE GATEWAY, UPPER CANADA COLLEGE, TORONTO.

SYMONS & RAE, ARCHITECTS.



DETAIL, CERTOSA DI PAVIA, ITALY.



OLD BUILDING AT CHINON, FRANCE.

1101, Chinon, France.

THE ALEXANDER ENGL.

BRITISH BRICK STANDARDS.

As a result of many conferences between committees of the Royal Institute of British Architects and the British Institute of Clayworkers, the following standards for bricks and brickwork have been agreed upon :

1. The length of the brick should be double the width plus the thickness of one vertical joint.

2. Brickwork should measure four courses of bricks and four joints to a foot.

Joints should be $\frac{1}{4}$ in. thick and an extra $\frac{1}{8}$, making $\frac{3}{8}$ for the bed joints to cover irregularities in the bricks. This gives a standard length of $9\frac{1}{4}$ in. centre to centre of joints.

The bricks to be measured in the following manner :

(a) Eight stretchers laid square end and splay end in contact in a straight line to measure 72 in.

(b) Eight headers laid side to side frog upwards in a straight line to measure 35 in.

(c) Eight bricks, the first brick frog downwards and then alternately frog to frog and back to back, to measure 21 in.


A margin of one inch less to be allowed as to (a), and $\frac{1}{4}$ in. less as to (b) and (c).

This is to apply to all classes of walling bricks both machine and hand-made.

Ten pictures, the gift of the Industrial Exhibition Association, have recently been added to the nucleus of a collection which in the future will adorn the walls of the Municipal Buildings at Toronto.

CANADA FOUNDRY COMPANY LIMITED

Head Office and Works: TORONTO, ONT.



Artistic Elevator Cages
Elevator Enclosures
Office Railings
Tellers' Cages, Etc.

IN ALL FINISHES

BRANCH OFFICES


Montreal Halifax Ottawa Winnipeg Vancouver Victoria Rossland

Patent Store Fronts

Coulson Patent Corner Posts
and Transom Bars - - - -
for new or remodel'ed store fronts.

Greatest strength for holding costly glass safely.

Strongly recommended by the Plate Glass Insurance Companies and all architects.



The above is a correct representation of our full size No. 13 corner.

J. W. GOULSON & CO.,

96-98 N. 3rd Street,

Columbus, Ohio.

PORTLAND CEMENT AFFECTED BY TIME.

A correspondent signing himself "Architect" writes as follows to the London Building News:—Have you or any of your readers found that Portland cement in course of time occasionally acts curiously and in a manner which I do not pretend to account for? It will remain dormant for say, five, ten, or even twenty years, and then become active to this extent, that mosaic flooring and the like will come away from its screeding,

and plastering will lose its key from walls built in cement, so that when you tap the surface of the walling the plaster sounds hollow, just as the flooring does. I do not refer to blowing of cement improperly mixed. The action I speak of does not refer to any changed or fresh conditions. The cement gradually appears to become deteriorated till at last it becomes sufficiently disintegrated to have lost its rigid cohesive strength. This condition is to be observed in high-class work. How is this, and what steps can be taken to obviate?

Wm. H. Sumbling
LAUNDRY MACHINERY

25 years' experience in best companies in U. S. General and Special Machinery Manufactured and Repaired. Send for Plans and Estimates. 643 Yonge Street, Toronto.

FAVORABLY KNOWN SINCE 1826. BELLS. HAVE FURNISHED 25,000. CHURCH, SCHOOL & OTHER. PUREST BEST. G. MENEELY & CO. GENUINE WEST-TROY, N. Y. BELL-METAL CHIMES. Etc. CATALOGUE & PRICES FREE. Bells Mounted in any Style. GREAT CLOCK BELLS FOR CITY HALLS; FIRE ALARM AND TOWER CLOCK BELLS. Westminster & Cambridge Clock Chimes. Inquiries from Architects solicited.



CABOT'S
CREOSOTE SHINGLE STAINS

The Original and Standard Shingle Stains are made only by SAMUEL CABOT, of Boston, Mass. Every package bears his trade mark, and every gallon is guaranteed. Used and proved in every climate for nearly twenty years. Also

CABOT'S
Sheathing and Deafening "Quilt"
the most perfect insulator of heat and deadener of sound on the market. Decay moth and vermin-proof, and uninflamable

Samples, Catalogue and full information upon application to the manufacturer or his CANADIAN AGENTS: ANDREW MITCHELL, 24 Bay St., Toronto. SEYMOUR & CO., Montreal. C. G. HENSHAW, Vancouver. F. H. BRYDGES, Winnipeg. W. H. THORNE & CO., St. John. E. D. ADAMS Halifax.

Practical Capability

ISN'T THAT THE NECESSITY IN BUILDING MATERIALS?

Most experienced builders all over the country use our

Sheet Metal Building Materials

Because they are honest, capable goods, unstinted in quality, that give the acme of artistic effect as well as sterling endurance.

We make every conceivable need in Ceilings, Shingles, Sidings, Lathing, Finials and Architectural Adornments.

Familiarity with our Catalog is a liberal education in the subject of building requirements.


METALLIC ROOFING CO.,

Limited

TORONTO

MONTREAL

WINNIPEG



RUBEROID

ROOFING

FOR

HOUSE, FACTORY, BARN, WAREHOUSE, FOUNDRY, ETC.

PROOF AGAINST

Water, Steam, Fumes, Acid, Alkali, Gas and Vermin. . .

AIR TIGHT AND ODORLESS
FIRE-RESISTING
WILL NOT MELT OR RUN

The Elasticity of Ruberoid permits of Expansion and Contraction without Opening the Seams. SEAMS ALWAYS TIGHT. Therefore NO leaks.

PRACTICALLY INDESTRUCTIBLE

TORONTO

The VOKES HARDWARE CO., Limited Sales Agents

BUSINESS NOTE.

Architects, builders, painters and others who may require information about any kind of glass will find much to interest and instruct them in the comprehensive new catalogue issued by the Toronto Plate Glass Importing Company. Each of the ten sections into which the catalogue is divided refers to one particular kind of glass, and in addition there is a general index. Besides prices and particulars of the many varieties of glass kept in stock by the company, the catalogue contains much useful data relating to methods of manufacture, the principles of the diffusion of light.

etc. The book is bound in strong, flexible linen covers, and will be sent free to any of our readers who may write for a copy mentioning the CANADIAN ARCHITECT AND BUILDER.

The announcement has been made that Professor S.H. Capper, M.A., who for several years has been at the head of the Department of Architecture of McGill University at Montreal, has accepted the position of Professor for the newly constituted Chair of Architecture, Manchester. It is expected that Professor Capper will return to England and begin the duties connected with the Manchester Chair of Architecture next autumn.

Milton

DR. ROBERTSON, PRESIDENT.

J. S. McCANNELL, MANAGING DIRECTOR.

ARCHITECTURAL TERRA COTTA

We make a Specialty of Ornamental Brick and Terra Cotta Mantels

High-Grade Pressed and Ornamental Bricks in red, buff, yellow, salmon, brown, and special shades. : : :

Pressed

Our products have a wide reputation and are specified by leading architects

THE MILTON PRESSED BRICK CO., LIMITED

Bricks

Works and Head Office: MILTON, ONT.

Montreal Agents: T. A. MORRISON & CO., 204 St. James Street.

For Information About

MAIL CHUTES

WHICH ARE

A Necessity in Office Buildings and Hotels,

Write to the sole makers

THE CUTLER MFG. CO., ROCHESTER, N. Y.,
PATENTED AUTHORIZED U. S. A.

TENDERS WANTED

A Weekly Journal of advance information and public works.

The recognized medium for advertisements for "Tenders."

CANADIAN CONTRACT RECORD
TORONTO.

Richter Mfg. Co.
Manufacturers of
Tapestry and Treatments of
BURLAP
CANVASES, ETC.
A VARIETY OF TEXTILES FOR ARTISAN DECORATIVE PURPOSES.
N.Y. WARE ROOM, 20 E 21st STREET
TENAFLY, N. J.

TENAFLY, N. J.

Architects and Decorators are invited to send for our book of samples.

THE BATTY STOVE & HARDWARE CO.

wholesale Only.


—DEALERS IN—

Mantels, Grates, and Tiles,
Gas Grates, Gas Logs, Andirons, etc.

ALSO A COMPLETE LINE OF

THE JEWEL STOVES AND RANGES,
Hot Air Furnaces, Registers, Etc.

76 York Street TORONTO.



MODERN ARCHITECTURE NOW-A-DAYS DEMANDS LOW TANK CLOSET COMBINATIONS.

The low tank is acknowledged to be most desirable from the standpoint of space economy, artistic appearance and ease of access for repairs.

The Morrison Low Tank is 1/2 smaller than ordinary makes, because its exclusive flush valve requires less water to secure a perfect flush.

It is fitted with our famous emptying valve which operates noiselessly (a feature which no other low tank possesses.)

Made of selected woodwork, and gracefully designed earthenware, of simple construction, without mechanical complications, neat and compact, the Morrison Low Tank Combination is as near perfection as intelligence and ingenuity can conceive, and skilled labor execute from perfect material.

Close prices and prompt shipment are added attractions of this line.

THE JAMES MORRISON BRASS MFG. CO., LIMITED, TORONTO, ONT.



British Trade Supplement

The Publishers of "The Canadian Architect and Builder" have arranged to furnish information respecting British Exporters of Building Materials and their goods advertised in this paper, and will keep on file at their Offices, Imperial Building, Montreal, and Confederation Life Building, Toronto, Catalogues, Price Lists, Etc.

Catalogues will be forwarded to Architects and Building Supply Houses in Canada on application.

British Office: 22 Great St. Helen's, LONDON, E. C.



Colledge & Bridgen

Midland Lock Works,
Wolverhampton, England.

Sole Makers of the

"PERFECT"

Patent Door Spring

Over 10,000 in Use.



GÜNTHER WAGNER'S CHIN-CHIN AND PELICAN WATERPROOF DRAWING INKS

FOR SALE BY ALL DEALERS.

Inventor and Manufacturer:

Günther Wagner

10 LONDON WALL

LONDON, E. C., ENG.

THE MALKIN TILE WORKS CO. LTD

ESTABLISHED 1866
BURSLEM ENGLAND
SPECIALITIES IN FLOOR WALL & HEARTH TILES
ARCHITECTS & BUILDERS PLEASE WRITE FOR NEW CATALOGUE

For Prices for Advertisements
in this Supplement write

The G. H. Mortimer Publishing
Co., of Toronto, Limited

22 Great St. Helens,
London, E. C., Eng.



GEORGE WOOLLISCROFT & SON, LIMITED

Harley, Staffs, England

Will be pleased to receive enquiries from Canadian friends for their numerous manufactures, which include:

Tiling Roof, Floor and Wall.
Mosaics Floor and Wall.
Faience and Terra Cotta For Internal or External Decoration
Faience and Briquette Fireplaces—Sanitary Goods.
Red and Blue Staffordshire Goods of Every Description.

CHURCH DECORATION done in all its branches, Stained Glass, Wood Carving, Marble and Iron Work, Fresco Painting, Della Robbia, &c. Venetian and Ceramic Mosaics for Walls or Floors.

Write for Catalogue &c. While waiting for catalogues from England friends may inspect some at the office of this paper, viz: The G. H. Mortimer Publishing Co., Imperial Building, Montreal, and Confederation Life Building, Toronto.

Our London Office and Showrooms are at
76a Great Portland Street Oxford Circus W.



FLORITE · OPAL · TILING

THE PERMANENT DECORATIVE GLASS CO. LTD

LONDON · MANCHESTER & LANCASTER.

THE NEW ENAMEL WALL DECORATION SUPERSEDING ORDINARY TILES AND OTHER GLAZED SURFACES

SANITARY · WASHABLE · PERMANENT · MODERATE COST

Wall Decorations · DADOS · FRIEZES · BORDERS · PATTERN TILES · PANELS · PICTURES
PLAIN WHITE & COLORS · MARBLE · GRANITE · MOTTLED LACE & OTHER PATTERNS

EASILY FIXED WITH PLASTER ON ANY ORDINARY WALL SURFACE
CABLE - FLORITE · LANCASTER · ENGLAND · POSTAL ADDRESS - LANCASTER · ENGLAND.

British Trade Supplement
JOHN WARNER & SONS, Limited

BELL AND BRASS FOUNDERS TO HIS MAJESTY THE KING, BY SPECIAL APPOINTMENT.
 2 JEWIN CRESCENT, GRIPPLEGATE, LONDON, ENGLAND

CHURCH BELLS, SINGLY OR IN RINGS
 WESTMINSTER CHIMES
 TURRET CLOCKS
 CHAPEL
 SCHOOL
 COLLEGE BELLS



TELEGRAPHIC ADDRESS

BIG BEN, LONDON.

CLOCK, RAILWAY AND
 LIGHTHOUSE BELLS
 CONTRACTORS TO THE ADMIRALTY
 AND WAR OFFICE
 THE INDIAN, JAPANESE, SPANISH,
 RUSSIAN, SOUTH AUSTRALIAN
 AND OTHER GOVERNMENTS

Illustrated Catalogue, POST FREE.

This Space Reserved for

MESSRS MARMOR LIMITED

Marble and Granite Manufacturers

18 Finsbury Square

LONDON, E.C., ENGLAND

THE HENRY RICHARDS TILE CO.
 LONGPORT STAFFS, ENGLAND.

Manufacturers
 of all kinds of

Manufacturers of all kinds of White Glazed, Printed,
 Coloured and Majolica Tiles for Walls, Hearths,
 Stoves, Etc., also all kinds of Flooring and
 Mosaic Tiles.

SANITARY EARTHENWARE,
 CLOSETS, LAVATORIES,
 URINALS, ETC., ETC.

—D—D—

Write for Prices
 Etc.

EDWARD JONES & CO.
 ARMITAGE, NEAR RUGELEY, STAFFS, ENGLAND.

Telegraph Address: "Foenhantas, London."

Geo. Rogers, Son & Co.

ENGLISH, CANADIAN,
 COLONIAL AND : :
 CONTINENTAL AGENTS.

22 Great St. Helen's, LONDON, ENG.

Purchasing and selling business on
 commission solicited. Agencies obtained
 for clients. Correspondence invited.

STANLEY BROS., LIMITED

NUNEATON, ENG.

White and Colored Glazed Bricks

Brown and Cane Glazed Sinks

Patent Tiles for Drying Pulp

Quarries, Roofing and Ridge Tiles

Patent Malt Kiln Tiles, Etc.

Illustrated Lists on Application

Enriched Ceilings, Cornices,
 Friezes, Box Fronts, Capitals,
 Columns, Trusses, Mouldings
 and Centre Flowers for Ceilings

—MADE IN

FIBROUS PLASTER AND GARTON PIERRE

Drawings made and estimates given for every
 style of relief decoration for Theatres, Public
 Buildings, Private Houses, etc.


Geo. Jackson & Sons,

49 Rathbone Place, LONDON W, ENGLAND

British Trade Supplement DRAWING AND SURVEYING INSTRUMENTS, &C.

ENGLISH MAKE, THE LATEST, THE BEST AND THE CHEAPEST
New Edition of Illustrated Catalogue Just Published, Post Free

THE "DESIDERATUM" LEVEL No. 3637




Surveying Instruments of every description Supplied and made to order

English make, 12 in. Telescope, Bronzed, with Case and Tripod, as illustrated, complete.
No. 4462. The "Grosvenor" Level, 14 in. Telescope, Bronzed, 2 Eye-Pieces, Polished Mahogany Case, and Tripod complete.

The above are best value ever offered by any firm.

ENGLISH ELECTRUM INSTRUMENTS




No. 3562. As Illustrated, 6 in. Compass (other instruments in proportionate sizes) Needle Points, Steel Joints, in the Morocco Packet Case..... 33s 6d
Unequaled at the price for the quality. For particulars and prices of the best, most complete, original and cheapest Cases of English Instruments ever offered, see New Edition of Catalogue, post free.

By His Majesty's Royal Letters Patent

THE "NERITE" ADJUSTABLE DRAWING BOARD AND SQUARE

No drawing office should be without this apparatus, combining Utility with Economy.



Full particulars with prices on application. Supplied any size.

Can be quickly and easily adjusted to whatever position best lends itself to perfect execution, or ministers most to the worker's comfort and convenience.

HALF THE PRICE of the similar apparatus in use in America, Germany and elsewhere.


JUST PUBLISHED

NEW EDITION OF ILLUSTRATED CATALOGUE

By far the best and most complete issued.
Contains prices and particulars of all improvements to date.
Post Free.

THORNTON'S PARALLEL SPRING BOW PEN

Quite new. Registered No. 314223.
Will draw circles of any diameter within its range, holding the instrument in a horizontal position.



No. 6002. Parallel Spring Bow Pen, as above, extra quality, Electrum Bolt and Nut, Needle Point... 9s 6d
No. 6003. Above Pen, with Pencil and Divider, Electrum Bolt and Nut, Needle Point. Set of three in Morocco Case..... 22s 6d

THORNTON'S IMPROVED ENGLISH NAPIER COMPASS

with Bolt and Nut, Needle Points.



No. 3502 1/2. In Electrum, extra quality..... 25s
No. 3504a. In Aluminium, extra quality..... 35s
This latter weighs under 1/2 oz., and forms a set of Drawing Instruments in a single tool.

THORNTON'S TRANSPARENT SKIN DRAWING

The cheapest and most useful Paper that has been introduced for Drawing Office requirements.

	20	23	30	40	43
No. 6000.	2s 3d	2s 9d	4s 3d	5s 9d	6s 9d

Free from Preparation, can be used as a Drawing, Detail or Tracing Paper; also for originals to copy from by Photography. Drawing and Tracing Papers and Cloths of every description. In sheets or continuous rolls. Samples and Prices post free. Photo Materials and Papers for Copying Tracings.

CONTRACTOR TO HIS MAJESTY'S GOVERNMENT

Telegrams: "Drawing, Manchester."

A. G. THORNTON

PRACTICAL MANUFACTURER
ST. MARY STREET, MANCHESTER

TELEPHONE



NO. 3273.

AGENTS FOR CANADA:

THE C. H. MORTIMER PUBLISHING COMPANY, Limited, Imperial Building, Montreal, and Confederation Life Building, Toronto

BUILDERS' HARDWARE AND CONTRACTORS' SUPPLIES.

AIKENHEAD HARDWARE LIMITED
PHONE MAIN 3900. 6 Adelaide St. E. Toronto

Samson Spot Cord



Distinguished by our trade-mark the Colored Spot. Warranted to be of pure Cotton, Smooth Finish and Perfect Braid. Samples Free. Carried in stock by *The Fokes Hardware Co. Limited, Toronto, Ont.* *The James Walker Hardware Co., Limited Montreal, Que.*

The Hughes Owens Co., Ltd.

MONTREAL. —Manufacturers of—
MOUNT ROYAL AND IRIS BRAND BLUE PRINT PAPER

Importers of all draughting office supplies. Our goods should be had from all dealers; if not, write direct.

WILLIAM J. HYNES,
16 Guld Street, Toronto.
CONTRACTOR AND PLASTERER

Relief Decorations in Stucco, Fibrous Plaster, Cement, Etc.
Large and varied stock of Centers, Caps, Cornices, Friezes, Etc.
Modelling and Designing.
TELEPHONE MAIN 1600.

THE CANADA PAINT CO. LTD.
MONTREAL AND TORONTO

CAR ROOF BRIDGE STATION

PAINT

VARNISH FOR ALL PURPOSES

FOR BEST RESULTS SPECIFY THE **"Elephant" White Lead**

Troy Laundry Machinery Co., LTD.

OUR LINE IS THE LARGEST, BEST AND MOST COMPLETE
WRITE US FOR CATALOGUE AND LAUNDRY GUIDE.
Troy Chicago New York San Francisco

The Canadian Portland Cement Company, Limited

Manufacture **"RATHBUN'S STAR"** Brand

The Leading Canadian Portland Cement.


Capacity of Works: 500,000 Barrels per Year.

The RATHBUN CO.
310-312 Front Street West, TORONTO, ONT.

SALES AGENTS

St. Lawrence Portland Cement Co.
101-102 Board of Trade Building, Montreal, Que.

CAPITALS



Copyright, 1899, Decorators' Supply Co.

The Decorators' Supply Co.

209-215 South Clinton St., CHICAGO, ILLS.

Manufacturers of . . .

Composition Capitals
For Interior and Exterior,
Interior Plastic Relief,
Exterior and Interior
Composition Ornaments,
Fine Grille Work.


Send for Catalogues.

GRILLES



Please mention this paper when corresponding with advertisers.

PATENT INTERLOCKING RUBBER TILING



THE IDEAL FLOOR COVERING

NOISELESS NON SLIPPERY WATERPROOF SANITARY.

The interlocking feature unites the Tiles into a smooth unbroken sheet of Rubber unlimited in area. The Tiles do not pull apart or come up, and each being distinct any color scheme can be secured. The most durable floor that can be laid.

Manufactured solely by

The GUTTA PERGHA and RUBBER MFG. CO. of Toronto, Limited

Branches Montreal and Winnipeg.

Head Office and Warerooms
45-47-49 West Front St.

TORONTO, CANADA

Classified Directory of Montreal Contractors and Dealers in Builders' Supplies

BUILDING MATERIALS

E. F. DARTNELL.

Stone Pressed and Common Bricks, Mineral Wool, etc.
Telephone 2387. 180 St. James Street.

T. A. MORRISON & CO.,

Milton Pressed Bricks, Limestone and Sandstones, Contractors' Plant, Crushed Stone for Concrete, etc.
204 St. James St., Montreal.

JAS. W. PYKE & CO.

Importers Structural Material—Iron and Steel
Telephone 312. Merchants Bank Bldg.

Subscribe for the ARCHITECT AND BUILDER.

ROOFERS

D. NICHOLSON & CO., Roofers, 679 St. Paul Street, Montreal. Gravel Roofing a Specialty. Repairs of all kinds promptly attended to. Bell Telephone 1665.

Advertise in the ARCHITECT AND BUILDER

Classified Directory of Toronto Contractors and Dealers in Builders' Supplies

BUILDING MATERIALS

GEORGE HATHBONE, 1 Northcote Ave. Pine, Hemlock and Hardwood Lumber; Lath, Shingles and Cedar Posts; Sawn Veneers. Re-sawing up to 30 inches wide a specialty.

Ontario Lime Association

Manufacturers and Dealers in Grey Lime, Guelph White Lime, Ontario Cement, Portland Cements, Plaster Paris, Hair, Fire Brick, Fire Clay, Sewer Pipe, etc.
Telephone 020. 118 Esplanade St. E., Toronto

BUILDERS and CONTRACTORS

FREDERIC HOLMES, Contractor

Telephone North 503. 111 Yonge St., Toronto. Estimates given for Cut Stone, Brickwork, Etc.

JAMES ISAAC

Cut Stone Contractor,
20 Dupont Street, Toronto.

MANTELS, GRATES and TILES

Toronto Hardware Mfg. Co.
1100 Queen St. W.
ALSO PLUMBER'S SUPPLIES.

ROOFERS

ROBT. RENNIE & SON,
Terra Cotta Tile,
SLATE AND GRAVEL ROOFERS, & C.

Every description of Roofing Slate always on hand. Galvanized Iron Ridges, Valleys and Flashings supplied. Telephone 2344. 378 Berkeley St., TORONTO.

H. WILLIAMS & CO., TORONTO.
23 Toronto St.

ROOFERS
With Slate, Felt and Gravel; also Williams' Flat Slate Roof—the best. We lay ROCK ASPHALT on cellar bottoms, floors and walks—the best material for this work. Telephone No. 511.

W. T. STEWART & CO.
Felt and Slate Roofers,
Dealers in Felt, Pitch, Tar, Sheathing Paper, Carpet Paper, and all kinds of Building Paper.
Office: Cor. Adelaide and Bay Sts., TORONTO.
Estimates furnished. Telephone No. 698.

G. DUTHIE & SONS.
Terra Cotta Tile, Slate and Felt Roofers,
Cor. Widmer and Adelaide Sts., TORONTO.
GALVANIZED IRON FURNISHINGS SUPPLIED.
Telephone 1936.

ESTABLISHED 1856
Slate and Felt Roofing.
FORBES ROOFING CO. 153 Bay St

DOUGLAS BROS.

SLATE, TILE AND METAL ROOFERS.
Sheet Metal Work, Metallic Ceilings, Skylights, etc.
24 Adelaide Street West, TORONTO.
Telephone Main 300.

PIONEER GALVANIZED IRON WORKS
ESTABLISHED 1855.

GEORGE RINGHAM TORONTO
23 and 25 Edward Street,
Copper and Galvanized Iron Cornices,
Skylights, Etc., Metal Ceilings
Felt and Slate Roofing. Phone Main 2572.


MOVERS

J. WARDELL & SON
450 Spadina Avenue,
Move Frame and Brick Houses and Machinery.

Send for 3rd edition of the Canadian Contractors' Handbook. Price \$1.50; \$1.00 to subscribers of the Canadian Architect and Builder.

THE C. H. MORTIMER PUBLISHING CO.
OF TORONTO, LIMITED.

Send for a copy of the Third Edition of the Canadian Contractor's Hand-Book and Estimator. Price \$1 to subscribers of the Architect and Builder, \$1.50 to non-subscribers.



Special Designs in IRON FENCING

**BANK RAILINGS
WROUGHT IRONS
WIRE WORK**

THE GEO. B. MEADOWS, Toronto, Wire, Iron and Brass Works Company, Limited
TORONTO, CANADA

PAGES

MISSING