AMERICAN GAZETTEE

EXHIBITING,

In alphabetical Order, a much more full and accurate Account than has been given, of the

STATES,	TOWNS,	HARBOURS,	MOUNTAINS,
PROVINCES,	VILLAGES,	GULFS,	FORTS,
COUNTIES,	RIVERS,	SOUNDS,	INDIAN TRIBES, AND
CITIES,	BAYS,	CAPES,	NEW DISCOVERIES,

THE AMERICAN CONTINENT,

ALSO OF THE

WEST INDIA ISLANDS,

And other Iflands appendant to the Continent, and those newly discovered IN THE PACIFIC OCEAN:

DESCRIBING

The Extent, Boundaries, Population, Government, Productions, Commerce, Manufactures, Curiofities, &c. of the feveral Countries, and of their important Civil Divitions—and the Longitude and Latitude, the Bearings and Diftances, from noted Places, of the Cities, Towns, and Villages:

WITH A PARTICULAR DESCRIPTION OF THE GEORGIA WESTERN TERRITORY.

The Whole comprising upwards of SEVEN THOUSAND DISTINCT ARTICLES.

Collected and compiled from the beft Authorities, and arranged with great Care, by, and under the Direction of,

JEDIDIAH MORSE, D. D.

Author of the American Universal Geography-Fellow of the American Academy of Arts and Sciences-and Member of the Malfachusfiette Historical Society.

THE SECOND EDITION, CORRECTED,

ILLUSTRATED WITH SEVEN NEW AND IMPROVED MAPS.

To which are added, Facts and Calculations respecting the Population and Territory of the UNITED STATES OF AMERICA.

Dublished according to Ad of Congrets.

PRINTED IN BOSTON, NEW ENGLAND.

London :

TEPRINTED FOR J. STOCKDALE, PICCADILLY; C. DILLY, POULTRY; AND T. N. LONGMAN, PATERNOSTER ROW.

1798.

A.A.A. In giateboliesi Ceire, a mach more full and society A that has been dison, of the Torresto inductions, stoned STATES. THE VILLADS, OTLM. 20077034 · All the called a ZERATINA CALES AND CONTRACT AN FREE CLEE. 23217ADE 3 is confine. MENA DINGO FE LATER CARES, ledged an 10.0012122 reader, u informati AMARIAN Syftem or Stable I'd an 2 and the face comment of the A greateft a RATIN but, as w with provide the part of the first sector and the bary sty the many imp V THE ENCINO OCEAN Y It is p to perfon. when it their dif when the other and the same of the same state of the wealth, a the second states have lati ANT POTTON A PARTICULAR TAXOLOGICAL TO STATISTIC GEORGES N'ES what has and, efp Contraction of the group of the state of the second of the fifter king grations choice or en al fai Leirannia Christen Aberlande des eur en se belennas Car Loibein J. the most and Barrens of Manufale Loss articles which th. hefitation NO DO REACH HARDERS WAS apple & within a war is meridian to make of the house of the sector and the modate fi spirit summary and a sector which one is formally bare sector is block to be and the sector of fmall tra and the second state of the second states and the second states and the second states and the second states and man who A THE THE TOURD EDITION COMMENCES containin to Ameri TETORIAL TELE REPAIRS NOT AND THE REPAIRS MATCH All Delegation The same and the second of the Ast The pr of Superi mentary 2.4 20 ment ; th a supro of the as propagate of the second second the Amer the second second second second second AND A DER WER AND A CONTON PIRATE veral rel : nontro la A SU TAN DE THE STANDARD S . 30

ADVERTISEMENT.

THE utility of that species of geographical dictionary, schully called a Gazetteer, whether it extends to the science in general, or is confined to some particular branch of it, is sufficiently acknowledged and obvious; since it may be occasionally consulted by the reader, who can immediately turn to the subject on which he wishes information, which might cost him much time to find in a regular system or continued narrative. The present velocities, in fact, of the American Geography of DOCTOR Money, a work of the greatest accuracy and merit, digested into the form of a Gazetteer, but, as will appear from the Presace of the judicious Author, with many important additions and improvements.

It is prefumed that fuch a work cannot but be highly acceptable to perfons of fcience in this country, and to the public in general, when it is confidered that the American States, notwithstanding their distance from Europe, have so increased in population and wealth, as to become of no little importance to its interefts; and have latterly appeared, in some degree, to extend their influence to what has been termed its balance. Political opinions and difputes, and, especially, the violent commotions which have convulsed the fifter kingdom, have also confiderably increased the number of emigrations to that country; and those who engage, whether from choice or neceffity, in fuch undertakings, will naturally with to obtain the most correct information relative to the part of the world in which they mean to take up their residence. This, it may without hesitation be afferted, they will here find. And still more to accommodate fuch perfons, it has been thought not improper to fubjoin a fmall tract, entitled, Facts and Calculations, written by a gentleman who holds an important station in the American States, and containing ufeful hints and information to fuch as intend to remove to America. the system will be be

The prefent Edition of this Gazetteer may very justly claim a degree of superiority to that published in America; as in it all the supplementary matter is incorporated in a proper alphabetic arrangement; the plates are complete, which, in some of the earlier copies of the American edition they were not; and they are, likewise, in several respects, very greatly improved.

PREFACE.

PREFACE.

THE defign of compiling and publishing an AMERICAN GAZETTEER, was conceived, by the Author of the following Work, as early as the year 1786, while he was travelling through the United States, for the purpose of collecting materials for his American Geography. This defign, perfectly coinciding in its subject with his other work, has never fince been relinquished: opportunities have been carefully improved to procure information necessary to its accomplishment.

The Author's profeffional duties, however—the delicate flate of his health; and the attention he has found it neceffary to pay to the revifion, correction and enlargement of the feveral editions of his Geographical Work, have delayed the completion of the *Gazetteer* much longer than was at first contemplated: but the delay has enabled him to render the Work much more accurate and perfect, than it otherwife must have been, by availing himfelf of a large mass of information, contained in the numerous maps, pamphlets, and larger works, which have been brought into public view, in the course of a few years past.

Soon after the plan of this Work was conceived, and fome. little progrefs made in collecting materials for its accomplifiment, the Author was informed that Capt. THOMAS HUTCHINS, then Geographer General of the United States, contemplated a Work of the fame kind: to him, as being, from the nature of his office, far more competent to the tafk, he cheerfully refigned his pretensions, and made him a tender of all the materials he had collected. But, with a kindnefs and generofity which flowed naturally from his amiable and noble mind, Capt. Hutchins declined the offer, relinquished his defign, and put into the hands of the Author all the collections he had made, together with his maps and explanatory pamphlets, which have contributed not a little to enrich this Work.

The fame kind of liberality was received from the Rev. Dr. BELKNAP, of Bofton, who had also meditated a Work of this fort. From his manuscript minutes, especially from the third volume of his valuable History of New-Hampshire, and also from his entertaining volume of American Biography, very confiderable affistance has been derived.

Edwards's Hiftory of the Weft-Indics-Saint Mery's topographical and political defcription of the Spanifh part of St. Domingo-Raynal's Indies-Robertson's America-Malham's Naval Gazetteer-A compendious Geographical Dictionary-Great Hiftorical

Hiftoric Collect and ma Hiftorio Muleun Sullivar -Whit Gazette by Gut Anfon's voix's Fleurie of man Works, afforded Adde tion to its islan ing the -Des Whitel of Con Pennfyl of Virg the cou others of the The tribes, t tions fro which t Heads letter an Map of the N. feveral. liberty fully be After able pa alphabe rican U In-th must ev unwilli

> * From derived m not been

Hiftorical Dictionary—Furlong's American Coaft Pilot—The Collections of the Maffachufetts Hiftorical Society, both printed and manufcript—Bartram's Travels—Jefferfon's Notes—Hazard's Hiftorical Collections—Imlay's Kentucky—Carey's American Mufeum—Gordon's and Ramfay's Hiftories of the Revolution— Sullivan's Hiftory of Maine—Williams's Hiftory of Vermont— —Whitney's Hiftory of the county of Worcefter—An American Gazetteer, 3 vols. (anonymous)—Brookes's Gazetteer, improved by Guthrie—Scott's Gazetteer of the United States—Cook's, Anfon's, Ulloa's, and Portlock's and Dixon's Voyages—Charlevoix's Hiftory of Paraguay—Clavigero's Hiftory of Mexico— Fleurieu's Difcoveries of the French in 1768-9—Acts and Laws of many of the States—thefe, and many other lefs important Works, have been carefully confulted, and fome of them have afforded much matter to increafe the value of this volume.

n

te

ay

ns

he

he

ite

n-

US

tht

me

h-

VS.

i a

his

his

ad

na-

ned

the

aps

ttle

Dr.

this

hird

alfo

on-

po-Do-

Na-

reat

ical

Added to thefe, the Author has availed himfelf of the information to be derived from all the valuable maps of America, and its islands, particularly 'Arrowsfmith's late excellent map, exhibiting the New Discoveries in the interior parts of North-America —Des Barres' Charts—Holland's Map of New-Hampshire— Whitelaw's of Vermont—Harris's of Rhode-Island—Blodget's of Connecticut—De Witt's of part of New-York—Howell's of Pennsylvania—Griffith's of Maryland and Delaware—Jefferfon's of Virginia—Hutchins's, Imlay's, Lewis's, and Williamsfon's of the country weft of the Alleghany Mountains—Purcell's, and others of the other Southern States—Edwards's and St. Mery's, of the West-Indies, and many others of less note.

The various Treaties with foreign nations and with the Indian tribes, the newspapers, and the publications of various defcriptions from the feveral branches of the Federal Government, with which the Author has been obligingly furnished by fome of the Heads of Departments—many manuscript communications by letter and otherwife; particularly the valuable M. S. Journal and Map of Capt. JOSEPH INGRAHAM, a confiderable difcoverer on the N. W. coast of America,—and the manuscript Journals of feveral other voyagers and travellers, whose names I am not at liberty to mention—these fources of information have also faithfully been improved to enrich this Work.

After all, it is but proper here to observe, that a very confiderable part of the matter of this volume has been selected, and alphabetically arranged, under the proper heads, from The American Universal Geography *.

In the compilation of this Work, which, an infpection of it must evince, has cost much application and labour, the Author, unwilling to divert his attention more than was absolutely neces-

* From this Work, Mr. Scott, Author of the Gazetteer of the United States, derived no finall part of the information contained in his Book, though he has not been candid enough to acknowledge it in his preface.

PREFACE.

fary, from his more important profeffional duties, has employed Mr. JOHN LENDRUM, Author of a ufeful compendious Hiftory of the American Revolution, to felect, arrange, and copy the materials for the Work, from the large collection of books, maps, and other printed and manufcript papers, enumerated above, with which the Author furnished him. In this arduous bufinels, Mr. Lendrum has been constantly employed, under the direction, and at the expense of the Author, for more than two years pail, and has executed it with fatisfactory care, fidelity, and judgment. The whole of the manufcript, however, has undergone the most careful and critical inspection and correction of the Author, who has also corrected all the proof sheets from the prefs.

After all the pains which have been taken, and the expense beftowed upon the Work, it muft not be expected, for it is not pretended, that the Work is free from errors. Its nature, and the circumftance of its being the first work of the kind in this country, upon fo large a fcale, render its prefent perfection next to an impossibility. The Author, conficious of having done his utmost to render it complete, accurate and useful, folicits the candor of his readers, and particularly a correction of every error, however fmall, which falls under their observation. It is hoped that no very important or offensive error will be found in the Work.

In explanation of the Work, it is proper to obferve, that the number of inhabitants in the feveral flates, counties and towns, except in the flates of New-York and Teneffee, where there has been a later enumeration, is taken from an official copy of the general cenfus of 1790.

The diftances and bearings of places are taken, in moft inftances, either from the Lift of Poft-Offices ; the Tables in Regifters and Almanacks, the Journals of Travellers, the records or Journals of Legiflatures, manufcript furveys, or from maps. In this part of the work, where the diftances have been meafured on maps, which, in too many inftances, are not to be depended on, the Author is apprehensive that fome errors will be found. The diffances are generally reckoned as the roads run. When it is confidered how liable transcribers and printers are to miftakes, in a work where figures and fingle letters flanding for words, make fo great a part of it; how great confusion the multitude of places of the fame name in different flates, and many times in the fame flate, mult create, and how difficult it is for an Author to correct a work of this complex kind, an apology will readily be found by a candid mind for a confiderable number of miftakes, fhould they be found, in respect to the distances, bearings, latitudes and longitudes of places.

The table of Poft-Offices, &c. obligingly furnished by the Author, Mr. ABRAHAM BRADLEY, jun. who has in other ways contributed

contributed formation c Longitude or Greenwie The diffe Indian deriv fioned no fi different fpr left equivoc places. The civil the ftates. Jerfey, and thips; and r into parifies ftates South ties. The Le into parifie counties in (neceffarily ftates ; any denominate New-York. are all incon Any Cap New, Eaft. der thefe gi name; as I The artic annexed to and care, an doubt, be i the late pur lency of th fituation fo which it wi attention, a the United blifhments, Indians, and at this time the flates. As the pl dominions i and French an English 1 nexed:

Aixo or 2 north coaft

-1

contributed to increase the value of this Work, furnishes correct information concerning the Post-towns throughout the United States. Longitude is reckoned uniformly from the meridian of London

or Greenwich, except where the reader has notice to the contrary.

The different fpelling of the fame names, effectively those of Indian derivation, among Authors and Map-makers, has occafioned no fmall difficulty to the Author. In many inflances, the different fpellings have been given; in others, the fpelling has been left equivocal, the fame word being fpelt differently in different places.

The civil divisions of the United States are not uniform in all the flates. The five New-England flates, and New-York, New-Jerfey, and Pennsylvania, are subdivided into counties and townships; and most of the townships in New-England are subdivided into parifles and precinets. Parifle is an ecclessifical division. The flates South of Pennsylvania are divided generally only into counties. The Lower Country, in S. Carolina, retains its original division into parifles, which are districts answering, in many respects, to counties in other flates. A town, in the Southern states, does not necessarily imply an incorporated district, as in the northern states; any number of compact houses, few or many, is there denominated a town. Town and township, in New-England and New-York, are generally used as of fynonymous fignification, and are all incorporated by law.

Any Cape, Fort, Point, Lake, Bay, &c. or any place that has New, Eaft, Weft, North, or South, prefixed to it, if not found under these general terms, is to be lought for under its distinctive name; as Fort Schuyler, for instance, look for Schuyler, Fort, &c.

The article GEORGIA WESTERN TERRITORY, with what is annexed to it at the end of the Work, compiled with great labour and care, and with a fluich regard to truth and impartiality, will, no doubt, be interefting to all who are, or may be concerned in the late purchafe of a confiderable portion of it. The excellency of the foil and climate of this country, its advantageous fituation for agriculture and commerce, and the rapidity with which it will probably be fettled, render it a fit object of public attention, and very important as a *frontier*, in an exposed part of the United States. Its fettlement, upon regular and proper eftablithments, by a people friendly to the rights and interefts of the Indians, and under the government of the United States, would, at this time, be of immenfe utility to the union and properity of the flates.

As the plan of this Work embraces the Spanish and French dominions in South America and the West-Indies, some Spanish and French names and terms are made use of, which require, to an English reader, some explanation; the few following are annexed:

Aixo or Aixos, a general term for Flats or Shallows, on the north coaft of South America. Anfe, a Cove.

Barcaderes,

vil

r the ooks. rated luous r the i two elity, s unon of m the penfe is not e, and n this n next ne his its the every It is und in hat the towns, ere has of the oft inin Reords or os. In eafured pended found. When to mil-

oved

ftory

ling for the muld many s for an ogy will mber of es, bear-

by the er ways atributed

PREFACE.

Barcaderes, a term fignifying landing places. Baxos, on the coaft of Brazil, in South America, is a name for Shoals.

Becca, a term used on the north coast of South America, or the Spanish main, for a Month or Channel.

Cayes or Cays, in the West-Indies, are little Islands and Rocks, difperfed among those islands.

Chico, on the west coast of New Mexico, in the Pacific Ocean, fignifies Little.

Forta leza, a term for Fort, on the coaft of Brazil.

Gut, in the Weft-Indies, is a term for the opening of a river or brook.

. Morro, is a term for Head land or Promontory, on the coafts of Chili and Peru in South America.

Sierra, a word used for Hill, on the coafts of Chili and Peru. Sierrillo, means a little hill on the fame coaft. S. OF STRUCT Trou Le, fignifies The Hole. is all the and a state of the second and

CHARLESTOWN, June 1, 1797.

The following articles were received too late to be inferted in the body of the Work.

ADDISON, a township of the Diftrict of Maine, in Walhington county, 10 miles fouth of weit of Machias; on the fea board, between Englishmen's bay and Pleafant river. It was called No. 6, until it was incorporated in February, 1797.

ALABAHA, a confiderable river of Georgia, which purfues a foutherly courie to the Gulf of Mexico, 100 miles weft of the head of St. Mary's river." Its banks are low, and a triffing rain fwells it to more than a mile in width. In a freshet the current is rapid, and those who pass are in danger of being entangled in vines and briars, and drowned; they are also in real danger from great numbers of hungry alligators. The country for nearly 100 miles on each fide of this river, that is to fay, from the head of St. Mary's to Flint river, which is 90 miles weft of the Alabaha, is a continued foft, miry, pine barren, affording neither water nor 1 25. an Lagilla reader, fonce sciebuation's

北部 的日

day or a gradual total for the endander of the

ant coalt of South Sanciss. Asks. A Cover.

The state party of

Bargadores

food for men or beafts; and is fo poor indeed as that the common game of the woods are not found here. The country on the weft of Alabaha is rather preferable to that on the eaft.

The second states and the second seco

Partie Allerations

ALABAMOUS, an old French fort, in the western part of Georgia; fituated between Coofa and Tallapoofe rivers, and not far from their confluence.

ALBANY, a British fortreis in New South Wales, North-America. N. lat.

52. 14. 40. W. long. 81. 59. 58. AMUSKEAG Falls. For " a bridge acrois the falls," &c. read " a bridge a little below the falls," &c.

AUGUSTA, a town of Upper Canada.

BAHIA Hondu, a bay on the northern fide of the island of Cuba. The bay has 15 and 10 fathoms water, the entrance into the harbour 8, and anchorage in 4 and 5 fathoms. The entrance lies in N. lat. 23. 26. W. long. 83.

IN BACHLE

A ARONS county, Penn wefterly from by N. from S ABACCO, Bahama iflanc fubject to Gn W. long. 77. ABACOOC ver rifing in th fing into Geory into the Creek with the Oal Alibama. ABBEVILL diffrict, S. C: N. E. by the by the Savann and 21 in bre habitants, inc. ABERCORN nah river, in from Ebenezer vannah. ABINEAU . Lake Erie, is a

OCTATION DE L Einerer sols 1

includ and may

1 7 21 203 00 1

requilizing with T

from Fort Erie ABINGDON the tide waters county, Maryl from Havre-de from Baltimor inftituted by t is in this town. ABINGDON, ington county, about to houf upwards of 1 50 from Campbell

VIII

me for

ica, or

Rocks,

Dcean,

iver or 医原素 的

pafts of

10123103 eru.

E STORE St. Arris

á asai (children)

18.16

20449C

e Work.

s fo poor te of the he counis rather

h fort, in fituated fe rivers, ce. 's in New

N. lat. a bridge i bridge a

Canada.

he north-The bay , the enanchorentrance ong. 83. 1588 an Lac i maxaa Airo

THE

A second and a second s rungs sela serate standar us carre a seration

ACO

AMERICAN GAZETTEER. to minimum suit

concernent in californianos als ended are i file mentioned and bei will a construction. Des of a court

the by a mineral definition, that was well or mineral the

in a more come and reaction and more in

a historia di rabitati ti tata di

a list the second shirt with an

A ARONSBURGH, lies at the head of Penn's Creek, Northumberland county, Pennsylvania, about 30 miles westerly from Lewisburgh, and 40 W. by N. from Sunbury. ABACCO, or Providence, one of the

Bahama iflands, in the Atlantic ocean, fubject to Great-Britain. N. lat. 24. W. long. 77. See Providence.

ABACOOCHEE, or Coofee, a large ri-ver rifing in the S. W. Territory, paffing into Georgia, through the Cherokee into the Creek country, where it unites with the Oakfuskee, and forms the Alibama.

ABBEVILLE County, in Ninety-Six diffrict, S. Carolina, bounded on the N. E. by the Saluda, and on the S. W. by the Savannah, is 35 miles in length and 21 in breadth; contains 9197 inhabitants, including 1665 flaves.

ABERCORN, a fmall town on Savannah river, in Georgia, about 5 miles from Ebenezer, and 13 N. W. of Savannah.

ABINEAU Port, on the N. fide of Lake Erie, is about 13 miles W. S. W. from Fort Erie.

ABINGDON, a town at the head of the tide waters of Bufh river, Harford county, Maryland; 12 miles S. W. from Havre-de-Grace, and 20 N. E. from Baltimore.—Cokefbury College, inftituted by the Methodists, in 1785, is in this town.

ABINGDON, the chief town of Wafhington county, Virginia, contained but about zo houses in 1788, now (1796)

260 from Richmond, in Virginia, in a direct line, and 310 as the road runs, bearing a little to the 6. of W. Lat. 36. 30. N.

the state and a line I will be brought at a

and der in an ten ster at at air air a

ULSE THE STOCKED WITH

ABINGTON, a township in Plymouth county, Maffachufetts ; 23 miles foutheafterly from Bofton, and contains 1453 inhabitants.

ABINGTON, a parifh in the town of Pomfret, in Connecticut.

ABINGTON, a village in Pennfylva-nia, 12 miles N. of Philadelphia.

ABIPONES, an Indian nation in Paraguay, S. America.

ABITIBBI, a finall lake in Upper Canada; on the S. fide of which is a fettlement called Frederick, which laft lies in N. lat. 49. W. long. 79: 40: Alfo the name of a river which runs N. and joins Moofe river, near, its mouth at James's bay.

ABITIEIS, a lake N. of Nipiffing lake, the N. E. boundary of Canada, in New South Wales; it has communication with James's bay, near Moofe Fort. N. lat. 59. 3. W. long. 78. 5. ABRAM's Creek, falls into Hudfon's river, near the city of Hudson.

ABROJOS, or Baxos de Babuca, a bank, with feveral finall rocks and ifles, E. of Turk's ifland, in N. lat. 21. 5. W. long. 69. 40. Between this bank and Turk's ifland is a deep channel, for fhips of any burden, 3 leagues wide. ABROLHOS, dangerous thoals, about

50 miles from the coaft of Brazil, and near the ifland of St. Barbe.

ABSECON Beach, on the coaft of upwards of 1 50. It is about 145 miles New-Jerfey, 16 miles S. W. from Little from Campbell's flation, near Holfton; Egg Harbour.

ACADIA.

ACABIA, the name by which Nova-Scotia was called, when it belonged to the French. Its limits, as fettled by the treaty of Utrecht, in 1713, were St. Lawrence river on the N. Penobfcot W. and the gulf of St. Lawrence on the E. This name was first applied to a tract, from the 40th to the 46th degrees of N. lat. granted to De Mons, Nov. 8, 1603, by Henry IV. of France.

ACAPALA, or Acapula, a town in the province of Chiapa, New Spain. It is fituated on the Tobafco river, near the city of Chiapa, and not far from a bay in the South Sea, called Teguantipac.

ACAPULCO, a city in New Spain, on a bay of the pacific ocean, 2no miles S. E. of Mexico ; the chief port in this fea, and the principal mart on the whole coaft. Its harbour is fo fpacious that feveral hundred fhips may ride in it without inconvenience. The mouth, which is defended by a low ifland, about a mile and a half long, and half a mile broad, having a wide and deep channel at each end; the westernmost channel is the narroweft, but fo deep that there is no anchoring; and the Manilla fhips pais in that way; but thole from Lima enter through the S. W. channel. This harbour runs N. about three miles ; then growing very narrow, turns fhort to the W. and a mile farther it terminates. The town flands at the mouth of this paffage, on the N. W. fide, close by the fea, and at the end of the town is a platform mounted with guns. Oppolite to the town; on the E. fide, is a high and frong caftle, with guns of a large fize. Ships commonly ride near the bottom of the harbour, under the command of the caftle and platform. The town furrounded by very high mountains, is fo unhealthy, fo defiitute of good water, and fo difagreeable, that except when the Manilla galeon is there, and while the confequent fair continues, it is almost deferted by the inhabitants. When the arrives in this port, the is generally moored on its weftern fide; and her cargo, confifting of fpices, all forts of Chinefe filks and manufactures, filk flockings, Indian fluffs, calicoes, chintz, together with other fmall articles, as goldimiths work, &c. are delivered with all expedition; when the town of Acapulco, from almost folitude, is thronged with merchants from all North America, fituated on a high

ACO

parts of Mexico and Peru. The cargo being landed, the filver and the goods intended for Manilla are taken on board, and the fhip prepares to put to fea with the utmost expedition. The galeon takes in here, in return for the goods which the brings, at leaft ten millions of dollars, a part of which pays the Span-ifh garrifons in the Philippine iflands. The commerce of this place with Peru is not, as many writers have miftaken, confined only to the annual thip from Lima; for at all other feafons of the year, except that wherein the Acapulco fhip arrives, the trade is open, and fhips from Peru, come hither frequently to exchange the commodities of that country for those of Mexico. From the end of November to the end of May, they have no rain here, and it is fo hot in January, when the fair generally begins, that merchants are obliged to do their bufinefs chiefly in the morning. When the fair is over, almost every body leaves the place but a few blacks and mulattoes. The town is governed by a chief juffice, who has 20,000 pieces of eight per annum; and the curate, though al-lowed but 180 pieces of eight, makes his place worth 14,000 by the burial fees of strangers who die here, or on board the ships in the harbour. There is an hospital maintained here, by deductions from the pay of the foldiers, and the alms of the merchants. Within a league of the E. of Acapulco, is PortMarquis, a very good harbour, where the thips from Peru generally run in contraband goods. Lat. 17. 22. N. long. 102. 20. W.

ACARAI, a town in Paraguay, S. America, built by the Jefuits, in 1624. N. lat. 26. W. long. 51. 5.

ACASABASTIAN, a river in the province of Vera Paz, in Mexico. It runs into the Golfo Dulce, and has a town fituated on its banks, of the fame name. The fource of this river is not far from the South Sea.

ACASATHULA, a fea port, fituated on a point of land, in the province of Guatimala proper, in Mexico, on a bay of the South bea, about four leagues from Trinidad. It receives the greateft part of the treasures from Peru and Mexico. In its neighbourhood are three volcanoes.

ACOMA, a town in New Mexico, mountain,

mountain, wi the capital of W. long. 104 ACCOMAC fituated on a p Maryland, E. W. by Chef 13,959 inhal flaves.

ACKLIN'S S. E. from L of the Bahan Key 12 miles fouth eaftward rocks. N. lat. ACHIACHI See Angelos.

ACOUEZ,a ACQUACKI town on the W in Effex count N. of Newarl New-York.

ACTON, a county, Maffac inhabitants ; 2. AGWORTH county, New-8 miles E. by I 73 N. W. by ADAMS, a county, Maffac inhabitants, is of Botton. In this town, is a A pretty mill Brook, which falls into the n river, has, for very deep chan feet deep, thro marble. Over deepeft, fome of form a natural of this bridge t its length is al breadth about bridge, and abo it, is another, v fo long; for at one body of roc! and under this rocks here are other places cle marble common in other towns i

ADAMSTOW county, Pennfyh the capital of the province. N. lat. 35. W. long. 104. 15.

ACCOMACK County, in Virginia, is fituated on a peninfula, bounded N. by Maryland, E. by the ocean, and on the W. by Chefapeak bay, and contains 13,959 inhabitants, including 4262 flaves.

ACKLIN's Key, lies about fifty miles S. E. from Long-Ifland, or Yuma, one of the Bahama iflands. It has Long Key 12 miles to the N. W. Upon the fouth eaftward fide is an entire chain of rocks. N. lat. 22, 10. W. long. 73. 30. ACHIACHICA, a town in Mexico.

See Angelos.

ACOUEZ, an Indian nation in Canada. ACQUACKNACK, or Acquakinunk, a town on the W. fide of Paffaic river, in Effex county, New-Jerfey, 10 miles N. of Newark, and 17 N. W. from New-York.

ACTON, a township in Middlefex county, Maffachufetts, containing \$53 inhabitants ; 24 miles N. W. of Bofton. AGWORTH, a township in Cheshire county, New-Hampfhire, incorporated in 1766, and contains 704 inhabitants; 8 miles E. by N. from Charlestown, and 73 N. W. by W. from Portfmouth.

ADAMS, a township in Berkshire county, Maffachusetts, containing 2040 inhabitants, is about 140 miles N. W. of Botton. In the northern part of this town, is a great natural curiofity. A pretty mill ftream, called Hudfon's Brook, which rifes in Vermont, and falls into the north branch of Heofuck river, has, for 30 or 40 rods, formed a very deep channel, in fome places 60 feet deep, through a quarry of white marble. Over this channel, where deepeft, fome of the rocks remain, and form a natural bridge. From the top of this bridge to the water, is 62 feet; its length is about 12 or 15, and its breadth about 10. Partly under this bridge, and about 10 or 12 feet below it, is another, which is wider, but not fo long; for at the east end they form one body of rock, 12 or 14 feet thick, and under this the water flows. The rocks here are mostly white, and in other places clouded, like the coarfe marble common at Lanefborough, and in other towns in Berkshire county.

ADAMSTOWN, a town in Lancaster county, Pennfylvania, containing about ADA

mountain, with a ftrong caffle, and is [40 houfes ; 20 miles N. E. of Lancafter. ADAYES. See Mexicano River.

> ADDISON County, in Vermont, is on the east fide of Lake Champlain, and is divided nearly into equal parts by Otter creek; has Chittenden county on the N. and Rutland county on the S. and contains 6449 inhabitants, difperfed in 21 townships. It is about 30 miles by 27: a range of the green mountains passes through it. Chief town Middlebury, granted Nov. 1761.

> ADDISON, a town of the above county, containing 401 inhabitants. It lies on Lake Champlain, and is feparated from Newhaven, on the E. by Otter creek. Snake Mountains on the S. E. lie partly in this township, granted 1761.

ADEQUATANGIE Creek, in New-York state, is the eastern head water of Sufquehannah river.

ADMIRALTY Bay, and Port Mulgrave, on the N. W. coaft of America, lie in N. lat. 59. 31. W. long. 140. 18. ADSON's Town, lies near the N. E. line of New-Jerfey, and S. E. of the Drowned Lands; 27 miles N. of Mor-riftown, and 24 N. W. of Patterson.

AFFUERA, one of the iflands of Juan Fernandes, on the South Sea coaft, in the kingdom of Chili. Long. from the meridian of Callao, 30. 20. about 400 leagues to the N. of Cape Horn. This coaft fwarms with fea lions and wolves.

AGAMENTIGUS, a mountain of confiderable elevation in the diffrict of Maine, diftant about fix miles from Bald Head, and eight from York harbour. Lat 43. 16. N. and 70. 39. W. long. from Greenwich. It is a noted landmark for feamen, and is a good directory for the entry of Pafcataqua harbour. as it lies very nearly in the fame meridian with it, and with Pigeon Hill, on Cape Ann. The mountain is covered with wood and fhrubs, and affords pafture up to its fummit, where there is an enchanting profpect. The cultivated parts of the country, especially on the S. and S. W. appear as a beautiful gar-den, interfected by the majeftic river Pafcataqua, its bays and branches. The immenfe ranges of mountains on the N. and N. W. afford a fublime spectacle; and on the fea fide, the various indentings of the coaft, from Cape Ann to Cape Elizabeth, are plainly in view in a clear day; and the Atlantic ft etches to the E. as far as the power of vision extends. A 2

cargo goods board, 1 with galeon goods ions of Spanlands. Peru taken, p from of the apulco d thips itly to counthe end , they hot in begins, o their When / leaves mulata chief of eight igh almakes burial or on There by deoldiers. Withilco, is r, where run in N. long. 1ay, S. 1 1624. the pro-It runs a town e name. ar from

fituated

vince .of

on a bay

leagues

greateft

eru and

are three

Mexico,

a high

ountain,

extends. At this foot the hearings of his 70 or 80 rods wide at its head, and the following objects were taken, with good furveying inftrument, October 11 1780.

ALA

Summit of the White Mountains, N. 15. W.

Cape Porpoife, N. 61. E.

Rochefter Hill, N. 64. W.

Tuckaway South Peak, S. 86. W. Froft's Hill, Kittery, S. 57. W.

Saddle of Bonabeag, N. 14. W. Ifle of Shoals Meeting-houle, S. 6. E. Varney's Hill, in Dover, diftant 101

miles by menturation, N. 89. W. Variation of the Needle, 6. W.

AGAMENTICUS, a river in the centre of York county, district of Maine. It is indebted to the ocean for its waters, through Pascataqua Bay; having no confiderable aid from freams of frefh water. Its mouth is about four miles foutherly from Cape Neddic river. Small vefiels can enter here.

AGAMUNTIC, or Amaguntic Pond, in the diffrict of Maine, fends its waters northward to the Chaudiere, through the weft branch of that river.

AGOMISO, an ifland in James's Bay, near its weltern coaft, N. N. E. from Albany Fort.

AGUGA Cape, on the coaft of Peru, S. America, lies fouthward of Puira, in the 6oth deg. of S. lat. and in the 82d of W. long.

ALABAHA, a confiderable river in E. Florida. Also faid to be the name of a branch of St. Mary's river.

ALABAMA, an Indian village, delightfully fituated on the banks of the Miffiftippi, on feveral fwelling green hills, gradually afcending from the verge of the river. Thefe Indians are the remains of the ancient Alabama nation, who inhabited the east arm of the Great Mobile river, which still hears their name, now poffeffed by the Creaks, or Mufcogulges, who conquered the former.

ALABAMA River, is formed by the junction of the Coofa or Coofee, or High Town river, and Tallapoolie river, at Little Tallatee, and runs in a S. W. direction, until it meets Toinhighee river from the N. W. at the great ifland which it there forms, go miles from the mouth of Mobile bay, in the gulph of Mexico. This beautiful river has a gentle current, pure waters, and excellent fifh. It runs about 2 miles an hour,

ALA

from rs to 18 feet deep, in the drieft feafon. The banks are about so feet high, and feldom, if ever, overflowed. Travellers have gone down in large boats, in the month of May, in 9 days from Little Tallafee to Mobile hav. which is about 350 miles by water. Its banks abound with valuable productions in the vegetable and mineral kingdoms. .

ALABASTER, or Eleuthera, one of the Bahama or Lucayo illands, on which is a fmall fort and garrifon. It is on the Great Bahama Bank. The foil of this ifland, and Harbour Ifland. which lies at the north end of it, is better than Providence Ifland, and produces the greateft part of the pine-apples that are exported ; the climate is very healthy. N. lat. 25. to 26. W. long. 75. to 76. 5.

ALACHUA SAVANNAH, is a level green plain, in the country of the Indians of that name, in E. Florida, fituated about 75 miles weft from St. Auguftine. It is about 15 miles over, and 50 in circumference; and scarcely a tree or bush of any kind to be seen on it. It is encircled with high floping hills, covered with waving forefts, and fragrant orange groves, rifing from an exuberantly fertile foil. The ancient Alachua town flood on the borders of this Savannah; but the Indians removed to Cufcowilla, z miles diftant, on account of the unhealthine's of the former fcite, occasioned by the stench of the purid fifh and reptiles, in the fummer and autumn, driven on thore by the alligators, and the noxious exhalations from the marshes of the favannah. Though the horned cattle and horfes bred in these meadows are large, fleek, fprightly, and fat, yet they are fubject to mortal difeafes; fuch as the water rot, or fcald, occasioned by the warm water of the favannah; while those which range in the high forefts are clear of this diforder.

ALACRANES, LOS, a long range of thoals, banks, and rocks, on the fouth ide of the gulph of Mexico, opposite the peninfula of Yucatan, east from Stone Bank, and weft from Capo St. Antonio; within the 23d deg. of N. lat, and between the Soth and gift degrees of W. long.

ALASKE, a long peninfula on the N. W. coaft

N. W. coaft Briftol bay an and N. and b ters of Cook' At its extrem the chief of w ward, are. (Ocumnak, wh or clufter of i ern Archipela return in 17 channel eaft N. W. Conft of ALATAMA Georgia. It mountains, ne branch of Sau gulo. In i mountains it Areams ; then fiderably rapic country 250. throws it felf in by the name after meanderin joined by the C its fource in the junction, it affi maha, when it river; and flow rent through miles, difcharge by feveral mou glides by the h o miles above turnings, enter pelo and Wo channel, which and deepeft, ai the north, defe courfe between ton iflands; a coaft of St. Sim fouth end of th and the north er its confluence w 500 yards wide. ALBAN'S, ST county, Vermon oppofite N. Hero ALBANY Co

ver, in the fate tween Ulfter and 46 miles by 28. Jan. 20, 1796, 1 in this county w ber of towns 11. ALBANY, the county; is fituate

N. W. coaft of America, formed by Briftol bay and the ocean on the N. W. and N. and by the ocean and the waters of Cook's river on the S. and S. E. At its extremity are a number of iflands, the chief of which, in their order weftward, are, Oonemak, Oonalasha, and Ocumnak, which form part of the chain or clufter of iflands called the Northern Archipelage. Capt. Cook, on his return in 1779, paffed through the channel east of Oonemak island. See N. W. Goaf of America.

ALATAMAHA, a navigable river of Georgia. It rifes in the Cherokee mountains, near the head of a weltern branch of Savannah river, called Tugulo. In its defcent through the mountains it receives feveral auxiliary streams; thence it winds, with confiderably rapidity, through the hilly country 250. miles, from whence it throws itfelf into the open, flat country, by the name of Oakmulgee. Thence, after meandering for 150 miles, it is joined by the Oconre, which likewife has its fource in the mountains. After this junction, it affumes the name of Alatamaha, when it becomes a large majeftic river; and flowing with a gentle current through forefts and plains 100 miles, discharges itself into the Atlantic by feveral mouths. The north channel glides by the heights of Darien, about so miles above the bar, and after feveral turnings, enters the ocean between Sapelo and Wolf illands. The fouth channel, which is effected the largeft and deepeft, after its feparation from the north, defcends gently, taking its courfe between M'Intolh and Broughton iflands; and at laft by the weft coaft of St. Simon's Sound, between the fouth end of the ifland of that name, and the north end of Jekyl island. At its confluence with the Atlantic, it is goo yards wide.

ALBAN's, ST. a township in Franklin county, Vermont, on Lake Champlain, oppofite N. Hero ifland, 2 56 inhabitants.

ALBANY County, on Hudion's river, in the fate of New-York, lies between Uister and Saratoga; its extent 46 miles by 28. By the ftate cenfus, Jan. 20, 1796, the number of electors in this county were 6087, and the number of towns 11.

ALBANY, the chief town of the above

ALB

Hudion's river, 160 miles north of the city of New-York, to which it is next in rank, and 340 S. of Quebec. N. lar. 42. 39. W. long. 73. 30. This city and fuburbs, by enumeration in 1797, contained 1263 buildings, of which 863 were dwelling-houfes, and 6021 inhabitants. Many of them are in the Gothic flyle, with the gable end to the fireet, which cuttom the first fettlers brought from Holland ; the new houles are built in the modern file. Its inhabitants are collected from various parts of the world, and speak a great variety of languages, but the English predominates; and the use of every other is gradually leffening: Albany is unrivalled for fituation, being nearly at the head of floop navigation, on one of the nobleft rivers in the world. It enjoys a falubrious air, and is the natural emporium of the increasing trade of a large extent of country W. and N .- a country of an excellent foil, abounding in every article for the W. India market; plentifully watered with navigable lakes, creeks and rivers, fettling with almost unexampled rapidity, and capable of affording lubliftence to millions of inhabitants : and when the contemplated locks and canals are completed, and convenient roads opened into every part of the country, all which will, it is expected, be accomplished in the course of a few years, Albany will probably encrease and flourish beyond almost any other city or town in the United States. The public buildings are, a Low Dutch church, of ancient and very curious construction, one for pilcopalians, two for Prefbyterians, one for Germans, or High Dutch, and one for Methodifts; an hospital, city hall, and a handfome brick jail. The corporation confilts of a mayor, recorder, fix aldermen, and as many affiltants. In the year 1609, Henry Hudfon, whole name the river bears, alcended it in his boat to Aurania, the fpot on which Albany now ftands.

The improvements in this city, within 5 or 6 years paft, have been very great in almost all respects. Wharves have been built on the river, the ftreets have been paved, a bank initituted, a new and handfome ftyle of building introduced. and now excellent water (an article in which this city has hitherto been extremely deficient, having been obliged sounty, is fituated on the weft bank of to use the dirty water of the river) is about A₃

about to be conducted into the various parts of the city, from a fine fpring 5 miles weft of the city. For these improvements the inhabitants are indebted to the patriotic exertions of a very few gentlemen.

One mile north of this city, in its fuburbs, near the manor house of lieutenant governor Van Renffalaer, are very ingenioufly conftructed, extensive and ufetul works, for the manufacture of Scotch and rappet fnuff, roll and cut tobacco of different kinds, chocolate, mustard, starch, hair-powder, split pease, and hulled barley. These valuable works are the property of Mr. James Caldwell, who unfortunately loft a complete fet of fimilar works by fire. in July, 1794, with the flock, valued at 37, 500 dollars. It is a circumftance worthy of remark, and is evincive of the industry and enterprize of the proprietor, that the whole of the prefent buildings and machinery were begun and completed in the fhort fpace of eleven months. These works are decidedly fuperior to any of the kind in America. All the articles above enumerated, even to the fpinning of tobacco, are manufactured by the aid of water machinery. For the invention of this machinery the proprietor has obtained a patent. Thefe works give employment and fubfiftence to 40 poor boys, and a number of work-men. Men who make fuch efforts to advance American manufactures, deferve well of their country. ALBANY, a British fortres in New

ALBANY, a Britifh fortrefs in New South Wales, in N. America, fituated on the river of the fame name. N. lat. 53. 10. W. long. 87. 20.

ALBANY River, falls into James's bay, in N. America, in N. lat. 51. 30. W: long. 84. 30. This river runs in a N. E. direction, and has communication with a vaft chain of finall lakes, in a line S. W. to the S. end of Winnipeg lake, a body of water next in fize to Lake Superior.

ALBEMARLE County, in Virginia, lies between the Blue sudge and the tide waters, and contains 12,585 inhabitants, including 5579 flaves. Its extent about 35 miles fquare.

ALBEMARLE SOUND, on the coaft of North Carolina, is a kind of inland fea, 60 miles in length, and from 8 to s2 in breadth. It lies north of Pamplico Sound, and communicates with it; as it likewife does with Currituck Inlet. It receives Roanoke and Meherrin rivers, and the paffage into it from the fea is called Roanoke Inlet. ALBION, NEW, the name given by

Sir Francis Drake to California, and part of the N. W. coaft of America, when he took poffeffion of it. A large tract of the N. W. coaft is thus called. Capt. Cook landed on a part of this coait on the 7th of March, 1778, in N. lat. 74. 33. E. long. 235. 10. which he thus defcribes: " The land is full of mountains, the tops of which are covered with fnow; while the vallies between them, and the grounds on the fea-coaft, high as well as low, are covered with trees, which form a beautiful prospect, as of one valt foreft. At first the natives feemed to prefer iron to every other article of commerce; at last they preferred brafs. They were more tenacious of their property than any of the favage nations that had hitherto been met with; fo that they would not part with wood, water, grafs, nor the most trifling article without a compensation, and were sometimes very unreafonable in their demands."

ALDEN, FORT, in Cherry Valley, in the flate of New-York.

ALEMPICON, a fmall lake northward of Lake Superior.

ALEXANDRIA, a township in Grafton county, New Hampshire, containing 298 inhabitants ; incorporated in 1782.

298 inhabitants; incorporated in 1782. ALEXANDRIA, a township in Hunterdon county, New-Jersey, containing 1503 inhabitants, inclusive of 40 slaves.

ALEXANDRIA, a fmall town in Huntingdon county, Pennfylvania, on the Frankftown branch of Juniatta river; 192 miles N. W. of Philadelphia.

ALEXANDRIA, formerly called Belbaven, a city in Virginia, fituated on the fouthern bank of the Patowmac river, in Fairfax county, about 5 miles S. W. from the Federal City, 60 S. W. from Baltimore, 60 N. from Frederickfburgh, 168 N. of Williamfourgh, and 290 from the fea; 38, 45. N. lat. and 77. 10. W. long. Its fituation is elevated and pleafant. The foil is clayey. The original fettlers, anticipating its future growth and importance, laid out the fireets on the plan of Philadelphia. It contains about 400 houfes, many of which are handfomely built, and 2748 inhabitants. This city, upon opening the navigation in confequence future feat of bids fair to be commercial pl ALFORD, a county, Maffa inhabitants ; a Bofton.

ALFORDST Moor county, ALGONQUI Upper Canada Lake Huron.

ALKANSAS nation in Louid Miffifippi river fame name, in fas River.

ALLBURG. county, Vermor tants; fituated ALLEGHAN the Atlantic oc and the lakes, range of mount number of ridg erly and fouthto the fea coaff length, and fre miles in breadtl with respect to I tains which he the back parts fcarcely one ac culture. This, being the cafe in Numerous trad grazing land i ridges. The diff pole this immer have different z flates, viz. the Mountain, or N Back-bone, Lau Mountains, and which fee under ridges, except the through by river forced their way This principal r ately called Alle tively named the States. From tl ceed innumerable

The general na taken collectively been determined. the Endlefs Mo the navigation of Patowmac river, and in confequence of its vicinity to the future feat of the federal government, bids fair to be one of the moft thriving commercial places on the continent.

ALFORD, a township in Berkshire county, Massachusetts, containing 577 infabitants ; 145 miles westward from Boston.

ALFORDSTOWN, a fmall town in Moor county, North-Carolina.

ALCONQUINS, an Indian nation in Upper Canada, on the north fide of Lake Huron.

ALKANSAS, or Arkanfas, an Indian nation in Louifiana, on the weft fide of Miffifippi river, near the river of the fame name, in N dat. 34. See Arkanfas River.

ALLBURG, a township in Franklin county, Vermont, containing 446 inhabitants; fituated on Miffique Bay. ALLEGHANY Mountains, between

the Atlantic ocean, the Miffifippi river, and the lakes, are a long and broad range of mountains, made up of a great number of ridges, extending north-eafterly and fouth-wefterly, nearly parrallel to the fea coaft, about 900 miles in length, and from 60 to 150 and 200 miles in breadth. Mr. Evans obferves. with respect to that part of these mountains which he travelled over, viz. in the back parts of Pennfylvania, that fcarcely one acre in ten is capable of culture. This, however, is far from being the cafe in all parts of this range. Numerous tracts of fine arable and grazing land intervene between the ridges. The different ridges which compole this immense range of mountains, have different names in the different flates, viz. the Blue Ridge, the North Mountain, or North Ridge, or Devil's Back-bone, Laurel Ridge, 'jackfon's Mountains, and Kittatinny Mountains; which fee under these names. All these ridges, except the Allegbany, are broken through by rivers, which appear to have forced their way through folid rocks. This principal ridge is more immediately called Alleghany, and is defcrip-tively named the Back-bone of the United States. From these several ridges proceed innumerable branches, or fpurs.

The general name of the wholerange, taken collectively, feems not yet to have been determined. Mr. Evans calls them the Endlefs Mountains; others have from Princeton.

called them the Appaler ian Mountains, from a tribe of Indians who live on a river which proceeds from this mountain, called the Appalachicola; but the moft common name is the Allegbany Mountains, fo called, probably, from the principal ridge of the range. Thefe mountains are not confudedly feattered, rifing here and there into high peaks, overtopping each other; but run along in uniform ridges, fearcely half a mile high. They fpread as you proceed fouth, and fome of them terminate in high perpendicular bluffs: others gradually fubfice into a level country, giving rife to the rivers which run foutherly into the Gulph of Mexico.

ALL

ALLEGHANY River, in Pennfylvania, rifes on the weftern fide of the Alleghany Mountain, and after running about 200 miles in a S. W. direction, meets the Monongahela at Pittfburg, and both united, form the Ohio. The lands on each fide of this river, for 250 miles above Pittfburg, confift of white oak and chefnut ridges; and in many places of poor pitch pines, interfperfed with tracks of good land, and low meadows. This river, and the Ohio likewife, from its head waters until it enters the Mifflippi, are known and called by the name of Alleghany River, by the Seneca, and other tribes of the Six Nations, who once inhabited it.

ALLEGHANY County, in Pennfylvania, extends from the junction of the river of that name with the Ohio, where its chief town, Pittfburg, is fituated, to the New-York line. It contains 10,309 inhabitants, including 159 flaves.

ALLEGHANY, is the most western county in Maryland, and has Pennsylvania on the north. The windings of the Patowmac River separate it from Virginia on the south, and Sideling-hill Creek divides it from Washington county on the east. It contains 4809 inhabitants, including 258 flaves. Cumberland is its chief town.

ALLEMAENGEL, a fmall Moravian fettlement on Swetara River, in Pennfylvania.

ALLEMAND, a river which falls into the Miffilippi from the S. E. about 43 miles S. of the Natches.

ALLENSTOWN, a town in New-Jerfey, in Moffmouth county, 15 miles N. E. from Burlington, and 13 S. by E. from Princeton.

A 4

ALLENSTOWN;

Thief.

ven by

ia, and

merica,

A large called. of this 778, in . which is full ich are vallies on the are coeautiful At firit iron to rce; at ney were rty than nat had hat they r, grafs, ithout a mes very

alley, in

orthward

in Grafintaining in 1782. in Hunontaining o flaves. in Hunt-, on the ta river; hia. alled Beluated on Patowmac 60 S. W. rederickflat. and on is eleis clayey. pating its laid out ladelphia. many of and 2748 n opening

the

ALLENSTOWN, a township in Rockingham county, New-Hampshire, concausing 254 inhabitants; fituated on the E. fide of Merrimack river, 25 miles N. W. of Exeter, and 40 from Portfmouth.

ALS

ALLEN - TOWN, in Pennfylvania, Northampton county, on the point of land formed by Jordan's creek, and the Little Leheigh. It contains about 90 houfes, and an academy.

ALLOWAY Creek, in Salem county, New-Jerfey, empties into the Delaware. It is navigable 16 miles, interrupted, however, by feveral draw-bridges.

ALL-SAINTS, iflands near Guadaloupe ifland, in the Weft-Indies.

ALL-SAINTS, a parifh in Georgetown diffrict, South-Carolina, containing 2225 inhabitants, of whom 229 are whites, and 1795 flaves. It fends a member to each house of the flate legiflature.

ALL-SAINTS Bay, a captainfhip in the middle division of Brazil, so called from a large bay of that name, bounded N. by the Ria Real; on the S. by that of Las Ilheos; on the E. by the ocean; and on the W, by three unconguered nations of Indians. It is reckoned one of the richeft and most fertile captainfhips in all Brazil, producing great quantities of cotton and sugar. The bay itself is about a leagues over, interspersed with a number of small, but pleasant islands, and is of prodigious advantage to the whole country. It has several cities and towns, particularly St. Salvador, which is its capital. All-Saints Bay lies in lat. 12, 3. S. long. 40. 20. W. See Salvador.

ALMARIA. See Villa Rica.

ALMIRA, a town in Mexico. See Angelos.

AMESBURY, a flourishing town in Effex county, Maffachusets, on the north waftern bank of Merrimack riyer, about four miles N. W. of Newburyport, containing 1801 inhabitants. Powaws river divides the township from Salisbury, over which a handsome bridge has lately been erected. A number of mills lie on this river round the lower falls. See Powaws river.

ALSTEAD, a township in Cheshire county, New-Hampshire, containing y111 iphabitants; \$ miles S, from Charlestown.

1. 19 2 2 1 2 2 3

ALTON, a tract of land in Strafford county, New-Hampshire, N. E. from Barnstead.

AMA

ALVARADO, a river in New Spain, which rifes in the mountains of the Zapotecas, and, after making a circuit through the province of Mazaltan, and receiving feveral fmaller rivers and freams, empties into the Gulf of Mexico, at 30 miles diftance from Vera-Cruz.

AMANIBO, a town on the coaft of Guiana, between Paramaribo, and Cayenne.


AMAPALLA, a feaport town in the province of Guatimala, in North-America, on a gulf of the fame name, 220 miles S. E. of the town of Guatimala. N. lat. 12. 30, W. long, 86, 40.

AMARISCOGGIN River. See Androfcoggin.

AMATIQUES, a feaport town at the mouth of Guanacos river, which empties into the Amatique gulf, or gulf of Honduras, in the province of Vera Pas, Mexico. The inhabitants are chiefly logwood-cutters, and on the S. of the gulf is a tract of land called Amatique land, Lat. 15, 23, long. 89.

AMAZONIA, a large country in S. America, 1400 miles in length, and 900 in breadth; fituated between the equator and 20 S. lat. and bounded N. by Terra Firma and Guiana; E. by Bra-zil; S. by Paraguay, and W. by Peru; but has never yet been thoroughly explored. The river Amazon, called alfo Maragnon, the largest in the known world, gives name to this country., A great number of rivers which rush down with amazing impetuofity from the eaftern declivity of the Andes, unite in a fpacious plain, and form this immenfe river. In its progrefs it runs 3300 miles from W, to E. acrofs South-America. Some of the rivers which fall into it are very broad and deep. The chief of thefe, from the S. and S. W. proceeding from the mouth westward, are Araguaya, Paratinaa, Madeira, Purus, Yulay, Yulacina, and Ucayai rivers. From the N. and N. W. progreffing from its mouth, are Parma, Negro, Yupura, Iffa and Napo, which last rifes near the town of Archidona, about 1 50 miles eastward of Quito. The Amazon is interspersed with a great number of islands, which are too often overflowed to admit of culture. It falls into the Atlantic ocean under the equator, and

i chi





there 150 miles broad. It received its prefent name from Francis d'Orillana, who faid he faw armed women on its banks. 'He was deputed, in 1516, to penetrate into the courses of this river, which he did with an armed fhip, and fought feveral nations of Indians, till he came to that place where he faw the armed women, who, with bows and arrows, opposed his passage.

ANNUE

The air is cooler in this country than could be expected, confidering it is fituated in the middle of the torrid zone. This is partly owing to the heavy rains which occation the rivers to overflow their banks one half of the year, and partly to the cloudiness of the weather, which obscures the fun a great part of the time it is above the horizon. During the rainy leafon, the country is fubject to dreadful ftorms of thunder and lightning.

The foil is extremely fertile, producing a great variety of the tropical fruits; likewife a variety of timber, as cedar, red-wood, pak, ebony, log-wood, and many other forts of dying wood; together with tohacco, fugar-canes, cotton, potatoes, balfam, honey, &c. The woods abound with tigers, wild boars, buffaloes, deer, and game of various kinds. The rivers and lakes abound with fifh. Here are also fea cows and turtles; but the alligators and water ferpents render fishing a dangerous employment.

The natives of this country are of a good stature, have handfome features, long black hair, and are of a copper colour. They are faid to have a tafte for the imitative arts, especially painting and fculpture, and turn out good mechanics. They fpin and weave cot-ton cloth. Their houfes are built with wood and clay, and thatched with reeds. Their arms in general, are darts and javelins, bows and arrows, with targets of cane or fifh fkins. The feveral nations are governed by chiefs or caciques; it being observable that the monarchical form of government has prevailed almost universally, both among ancient and modern nations, in a rude flate of fociety. The regalia which diffinguifh the chiefs, are a crown of parrot's feathers, a chain of tiger's teeth or claws, which hang round the waift, and a wooden fword.

AMBER Bay, on the peninfula of

into the

ator, and

Yucaten, in the bay of Honduras, lies N. of Afcention bay, which fee.

AMBERGREESE Key, an ifland in Hanover bay, on the east fide of the peninfula of Yucaten, in the bay of Honduras. It runs along the mouth of the bay, is 70 miles long, but very narrow. See Afcention bay. AMBOY. See Perib Amboy.

AMBROSE, St. an ifland in the S. Pacific ocean, on the coaft of Chili, 4 or 5 leagues due W. from St. Felix illand. At first view, it appears like two fmall iflands, but after a nearer approach, it is found they are joined by a reef. It lies in 26. 13. S. lat. and 80. 55. W. long. from Greenwich. There is a large rock 4 miles to the northward of the ifland, called, from its appearance, Sail rock. Capt. Roberts, who was here in 1792, found St. Felix ifland inacceffible. On St. Ambrofe ifland, his crew killed and cured 13,000 feal fkins of the best quality, in feven weeks. The ifland has little elfe to recommend it. Fifth and crawfifth abound. The beft featon for fealing is from the rft of April to the 1st of August. The island has the appearance of having had volcanic eruptions.

AMELIA, a county in Virginia, fituated between the Blue-ridge and the tide waters, having Cumberland county N. Prince George county E. and Lunenburg county S. and W. Amelia, including Nottaway, a new county, contains 18,097 inhabitants, of whom 11,037 are flaves.

AMELIA Me, on the coaft of E. Florida, lies about 7 leagues N. of St. Augustine, and very near Talbot island on the S. at the mouth of St. John's river. It is 13 miles long and 2 broad, is very fertile, and has an excellent harbour. Its N. end lies opposite Cumberland ifland, between which and Amelia Ifle is the entry into St. Mary's river, in N. lat. 30. 52. W. long. 67. 23.

AMELINS, Ecor a, is a fouth eaftern head branch of Wabash river, whose mouth is 9 miles N. E. from the mouth of Salamanie river, and 45 miles S. W. from the Miami village and fort.

AMOENIA, a thriving township in Dutchels county, New-York, 6 miles diftant from Sharon, in Connecticut. It contains 3078 inhabitants, of whom 383 are electors.

AMERICA, is one of the four quarters

AME

ters of the world, probably the largeft of the whole, and is, from its late difrovery, frequently denominated the New World, or New Hemifphere. This was country extends from the 56th de-gree of S. lat. to the north pole, and from the 55th to the 165th degree of W. long. from Greenwich. It is nearly 10,000 miles in length. Its average breadth may be about 1800 or 2000 miles. It has two fummers, and a double winter, and enjoys almost all the variety of climates which the earth affords. It is washed by two great oceans. To the eastward it has the Atlantic, which divides it from Europe and Africa. To the W. it has the Pacific, or Great South Sea, by which it is leparated from Afia. By thefe it carries on a direct commerce with the other three parts of the world. America is divided into two great continents, called North and South America, by an ifthmus about 500 miles long; and which, at Darien, about lat. 9. N. is only 60 miles over; other writers fay 4 miles. This ifthmus, with the northern and fouthern continents, forms the Gulph of Mexico, in and near which lie a great number of iflands, called the Wefl-Indies, in contradiffinction to the eaftern parts of Afia, which are called the Eaft-Indies.

In America nature feems to have carried on her operations upon a larger fcale, and with a bolder hand, and to have distinguished the features of this country by a peculiar magnificence. The mountains of America are much fuperior in height to those in the other divisions of the globe. Even the plain of Quito, which may be confidered as the base of the Andes, is elevated farther above the level of the fea than the top of the Pyrenees in Europe; and Chimborazo, the most elevated point of the Andes, is 20,280 feet high, which is at least 7102 feet above the peak of Teneriffe. From the lofty and extenfive mountains of America, descend rivers, with which the freams of Europe, of Afia, or of Africa, are not to be compared, either for length of courfe, or for the valt body of water which they convey to the ocean. The Danube, the Indus, the Ganges, or the Nile, in the eastern hemisphere, are not of equal magnitude even with the St. Lawrence, the Miffouri, or the Miffilippi, in North America; and fall far short of the Amazon, and the La Plata, in South-America.

The lakes of the New World are no lefs confpicuous for grandeur than its mountains and rivers. There is nothing in other parts of the globe which refembles the prodigious chain of lakes in North-America, viz. Superior, Michigan, Huron, Erie, and Ontario. They may be properly termed inland feas of frefh water. And even those of the fecond or third clafs, are of greater circuit, (the Caspian sea excepted) than the greatest lake of the ancient continent.

The luxuriance of the vegetable creation in the New World is extremely great. In the fouthern provinces, where the moifture of the climate is aided by the warmth of the fun, the woods are almost impervious, and the furface of the ground is hid from the eye under a thick covering of fhrubs, of herbs, and weeds. In the northern provinces, although the forefts are not incumbered with the fame wild luxuriance of vegetation, the trees of various species are generally more lofty, and often much larger, than are to be feen in any other parts of the world.

This vaft country produces most of the metals, minerals, plants, fruits, &cc. to be met with in the other parts of the world, and many of them in greater quantities, and in high perfection. The gold and filver of America have fupplied Europe with those precious metals. The gold and filver of Europe now bear little proportion to the high price fet upon them before the difcovery of America. It also produces dia-monds, pearls, emeralds, amethyfts, and other valuable stones. To thefe, which are chiefly the productions of South-America, may be added a great number of other commodities, which, though of lefs price, are of much greater ule. Of these are the plentiful fupplies of cochineal, indigo, anatto, logwood, brazil, fuffic, pimenta, lignumvitæ, rice, ginger, cocoa, or the chocolate-nut, fugar, cotton, tobacco, banillas, red-wood, the balfams of Tolu, Peru, and Chili, that valuable article in medicine, the Jefuit's bark, mechoacan, Mras, farfaparilla, caffia, tamarinds, fides, furs, ambergrife, and a great variety of woods, roots, and plants, to which,

which, before ! the Europeans gers, or which at an extravag Africa, through netians and groffed the trad On this cor variety of exc pine-apples, c pomegranates, riety of culina herbs, roots an otic productic to as great per toil. Notwithftan ments of the 1 nent, great p ftill unknown. nent contains t viz. 3. Upper mada, to which gin, and the 3. New-Brun to which is an Befides thefe foundland, an STATES. It territories of Louisiana, Nez Mexico. Befi menfe unexple and N. W. lie the Spani Firma, Guian Chili; togethe belonging to 1 country of Sui Dutch. Vaft inland parts, a prehended und Amazonia, to A large diftri ftraits of Mag Paraguay, ca known. America, fc claimed and d three European British, and J iards, as they the largest and ing from Loui in North-Am Magellan, in t the large pro belongs to Po

French and Du

which, before the diffeovery of America, the Europeans were either entire firangers, or which they were forced to buy at an extravagant rate from Afia and Africa, through the hands of the Venetians and Genoefe, who then engroffed the trade of the eaftern world.

On this continent there grows alfo a variety of excellent native fruits; as pine-apples, citrons, lemons, oranges, pomegranates, figs, grapes, a great variety of culinary, medicinal, and other herbs, roots and plants, with many exotic productions, which are brought to as great perfection as in their native foil.

Notwithstanding the many fettlements of the Europeans on this continent, great part of America remains still unknown. The northern continent contains the four British provinces, viz. 3. Upper Canada; 2. Lower Canada, to which are annexed New-Britgin, and the island of Cape-Breton ; 3. New-Brunfwick; 4. Nova Scotia, to which is annexed St. John's ifland. Befides these are the island of Newfoundland, and the fixteen UNITED STATES. It contains also the Spanish territories of East and West Florida, Louisiana, New Mexico, California, and Mexico. Befide thefe, there are immenfe unexplored regions to the W. and N. W. In the fouthern continent, lie the Spanish provinces of Terra Firma, Guiana, Peru, Paraguay, and Chili; together with that of Brazil, belonging to the Portuguefe, and the country of Surinam, belonging to the Dutch. Vaft tracts, however, in the inland parts, are unknown, being comprehended under the general name of Amazonia, formerly called Maragnon. A large district also lies between the firaits of Magellan and the province of Paraguay, called Patagonia, little known.

America, fo far as known, is chiefly claimed and divided into colonies, by three European nations, the Spaniards, Britifh, and Portuguele. The Spaniards, as they first discovered it, have the largest and richest portion, extending from Louisiana and New Mexico, in North-America, to the straits of Magellan, in the South Sea, excepting the large province of Brazil, which belongs to Portugal, for, though the French and Dutch have fome forts upon

Swinam and Guiana, they fearcely deferve to be confidered as proprietors of any part of the fouthern continent.

Next to Spain the most confiderable proprietor of America was Great Britain, who derived her claim to North-America from the first discovery of that continent, by Sebastian Cabot, in the name of Henry VII. of England, in the year 1497, about 6 years after the difcovery of South - America by Columbus, in the name of the king of Spain. The country was in general called Newfoundland, a name which is now appropriated folely to an ifland on its coaft. It was a long time before the English made any attempt to fettle in this country. Sir Walter Raleigh, an uncommon genius, and a brave commander, first shewed the way, by planting a colony in the fouthern part, which he called Virginia, in honour of queen Elizabeth, who was unmarried.

The French, indeed, from this period until the conclusion of the war of 1756, laid a claim to, and actually poffeffed, Canada and Louifiana, but, in that war, they were not only driven from Canada, and its dependencies, but obliged to relinquish all that part of Louifiana lying on the E. fide of the Miffifippi; and the British colonies, at the peace of 1763, extended fo far as to render it difficult to afcertain the precife bounds of the empire of Great-Britain in North-America. To the northward, Britain might have extended her claims quite to the pole. From that extremity, the had a territory extending fouthward to Cape Florida, in the Gulph of Mexico, in N. lat. 25. and, confequently, near 4000 miles in a direct line. And to the weftward, the boundaries were unknown; but having entered into impolitic difputes with her colonies, the brought on a war, of which fhe felt the ruinous effects, by the difmemberment of her empire in North-America : and Britifh America, at the peace in 1783, was circumfcribed within the narrow limits already mentioned.

America was very probably peopled early after the flood. Who were the first people of America? And whence did they come? are questions concerning which much has been faid and written. Dr. Robertion and the Abbe Clavigero have attempted a folution of them.

fall fan La Pla-

are no

than its

is noth-

which

of lakes

Michi-

They

feas of

of the

reater

d) than t conti-15.58 ble cres stremely ovinces, imate is fun, the and the from the fhrubs, northern are not luxurivarious ity, and be feen most of nits, &cc. parts of in greatica have precious f Europe the high difcoveuces diamethyfts, To' thefe, ctions of d a great , which, ch great-tiful fupitto, loglignumhe chococo, banil-of Tolu, article in echoacan, amarinds, great va-plants, to

which,

them. A fammary of their opinions may be found in the American Univerfal Geography, p. 78. 85.

It has been common, in estimating the population of the whole world, to allow 150 millions to America. But this is probably three times their real number. For if we suppose every part of the whole continent of America to he as populaus as the United States, (which is not the cafe) the whole number will be but about 60 millions. The exact number is probably confiderably lefs. The prefent Americans may be divided into two general classes. First, the proper Americans, commonly called Indians, fometimes Aborigines, or those who are descended from the first inhabitants of the new world, and who have not mixed their blood with the inhabitants of the old continent. Secondly, those who have migrated, or have been transported to America, fince its difeovery by Columbus, and their defcendants. The former may be fubdivided linto three claffes. Firft, the South-American Indians, who probably came over from the northern and western parts of Africa, and the fouthern parts of Afia and Europe. Secondly, the Mexicans, and all the Indians fouth of the lakes and weft of the Miffifippi. Thirdly, the inhabitants of Elquimeaux, Labrador, and the countries around them. The latter may alfo be diffinguished into three claffes. Firft, Europeans of many difference nations, who have migrated to America, and their descendants, of unmixed blood. In this c'als we include the Spaniards, English, Scotch, Irish, French, Portuguele, Germans, Dutch, Swedes, &c. both in North and South America. Secondly, Africans, who have been transported to America and its islands, and their de'cendants. Thirdly, the mixed breeds called by the Spaniards, Caflas, by the English Mulattoes, that is, these who are descended from an European and an American, or from an European and African, or from an African and American.

AMEWELL, is the most populous town in Hunterdown county, New-Jerfey. It contains 5202 inhabitants, including 283 flaves.

AMHERST, a township in Cumberland county, Nova Scotia, fituated on Chignecto Bason, on the S, fide of La Planch River, and on the rivers Napan and Macon. The navigation of the two laft is difficult on account of fhoals. The town was fettled by North Irifh, Yorkfure and New-England people.

AMHERST, the fhire-town of Hil'fborough county, New-Hampthire, 1s a town of fome note, formerly Soubegan West, and was originally granted from Maffachufetts. It has 2369 inhabitants, and was incorporated in 1762. The Aur an Academy was founded here in 1790. A few years ago, the townfhip being much infelted with wolves, the people, on a day appointed; furrounded a large fwamp which they frequented, and kept up an inceffant firing of guns and heating of drums the whole day; which mulic forced the wolves to decamp the following night, with difinal howlings; and they have never done any mitchief in the town fince. Amherit lies on a northern branch of Souhegan River, which falls into Merrimack River, and is 60 miles W. of Portimouth, and 53 N. W. of Bofton. N. lat. 42. 54. W. long. 71. 33.

AMHERST, a township in Hampshire county, Massachuletts, containing 1233 inhabitants; 91 miles westerly from Boston, and about eight north-easterly from Northampton.

AMHERST County, in Virginia, lies between the Blue Ridge and the tide waters, and contains 13,703 inhabitants, including 5196 flaves. It lies on the north of James River.

AMICU, a lake in the province of Cumana, South-America, whole waters run fouthwardly through Parima River into the Amazon.

AMILPAS, two volcanoes in the province of Guatimals, in N. Spain, near the mountains of Socianuco.

AMONOOSUCK, an Indian name given to two rivers in New-Hampfhire a the one is called Upper Amonooluck, paffing through a track of excellent meadow. It rifes near the north end of the White Hills, runs northerly about 15 miles, where is a carrying place of about three miles to Amarifcoggin River. From thence the river runs S. W. and W. nearly 18 miles, and empties into the Connecticut at Northumberland, near the Upper Coos. The other is called Great or Lower Amonoofuck, which rifes on the weft fide

fide of the W into the Co town of Have a mouth 100 miles from i Amonoofuck, a conia and Li or three hours this last men and occasion to put in mot ameter, but i AMOTAPE lying near the in the empire river of fine try is highly in AMPALLA Ampalia, a c mala Gulf, miles S. E. o and carries or neal, cocoa, h AMPARES, archbilliop of city, in the en in grain and c AMSTERD. originally giv city of Newin the South Friendly Islan from them.

AMSTERD Montgomery contains 235 in tors.

AMUSKEAG thire, are on M miles below C Hookfet Falls pitches, one h the water fall courfe of half pitch, which m on the W. fide the middle of 1 is a high rock which are a nu actly round, li fome of which feveral tons; motion of final force of the da is a bridge acro length, and 20 2000 tons of th for travellers 5 gun. N. lat.

13

ers Napan on of the t of thoals. orth Irifh, people. n of Hil'fthire, 1s a 7 Soubegan nted from habitants, 62. The led here in the townth wolves, nted, furh they freeflant fir-Irums the orced the ing night, they have the town northern which falls 60 miles N. W. of long. 71.

Hampfhire sing 1233 erly from th-cafterly

ginia, lies the tide is inhabi-It lies on

vovince of vhole wah Parima

n the propain, near ampfhire i oncofuck, excellent north end northerly carrying

carrying Amarifthe river 18 miles, efficut at per Coos. or Lower the weft

fide

AMU

fide of the White Mountains. It falls into the Connecticut juft above the town of Haverhill, in Lower Coos, by a mouth 100 yards wide. About two miles from its mouth it receives Wild Amonoofuck, 40 yards wide, from Franconia and Lincoln Mountains. Two or three hours rain raifes the water in this fast mentioned river feveral feet, and occafions a current fo furious as to put in motion flones of a foot in diameter, but its violence foon fubfides.

AMOTAPE, a town near Tumbez, lying near the fhore of the South Sea, in the empire of Peru. Being near a river of fine water, the adjacent country is highly improved. Lat. 4. 15.43. S. AMPALLA, by fome authors called Ampalia, a city and feaport in Guatimala Gulf, in that of Mexico, 350 miles S. E. of the city of Guatimala, and earries on a brifk trade in cochineal, cocoa, hides, indigo, &c.

AMPARES, a jurifdiction under the archbifliop of Plata, eaflward of that city, in the empire of Peru. It abounds in grain and cattle.

AMSTERDAM, NEW, was the name originally given by the Dutch to the city of New-York. Alfo, an Island in the South-Sea, S. S. W. of the Friendly Islands, and not far distant from them.

AMSTERDAM, a new township in Montgomery county, New-York. It contains 235 inhabitants, who are electors.

AMUSKEAG Falls, in New-Hampthire, are on Merrimack River, fixteen miles below Concord, and feven below Hookfet Falls. It confilts of three pitches, one below the other, fo that the water falls about 80 feet in the courfe of half a mile. The fecond pitch, which may be leen from the road, on the W. fide, is truly majeffic. In the middle of the upper part of the fail is a high rocky ifland, on the top of which are a number of pits, made ex.actly round, like barrels or hogfheads, fome of which are capable of holding feveral tons; formed by the circular motion of finall ftones, impelled by the force of the descending water. There is a bridge acrois the falls 556 feet in length, and 20 in breadth, confifting of 2000 tons of timber, and made paffable for travellers 57 days after it was begun. N. lat. 42. 59.

ANAHUAC, the ancient Indian name of New-Spain, or Mexico.

ANASTATIA, ST. a finall ifland clofe to the coaft of Eaft-Florida, fituated S. of Maftances Inlet, where the river Maftances forms two idlands of the fame name at its month. St. Anaftatia ifland is bounded on the N. by St. Auguiline's bar. Here is a quarry of fine from for building.

ANCLOTE Point, on the peninfula of California, and coaft of the North Pacific Ocean, lies in the 30th deg. of N. lat. and 116th of W. long. loutherly from the town of Velicata, and N. E. from the imall ifland of Guadaloupe.

ANCOCUS Creek, in New-Jerley, a water of the Delaware, 6 miles S. W. from Burlington. It is navigable 16 miles; and confiderable quantities of lumber are exported from it.

ANCO, a finall town of South-America, 3 leagues from the city of Guamanga.

ANDAGUAYLAS, a jurifdiction in South-America, in the empire of Peru, subject to the archbishop of Lima; lying E. by S. of the city of Guamanga. It abounds in sugar plantations, grain of most forts, and fruits.

ANDALUSIA, NEW, a province of Terra Firma, on the coaft of the Atlantic, opposite the Leeward Islands.

ANDASTES, an Indian nation in Canada.

ANDES. The principal mountains on this weftern continent are the Cordillera de los Andes, or Great Chain of Andes, in South-America. They ftretch along the Pacific Ocean from the firaits of Magellan to the ifthmus of Darien or Panama, upwards of 4000 miles; thence they run through the extensive kingdom of New-Spain, till they lofe themfelves in the unexplored countries of the North. In New-Spain, the most confiderable part of this chain is called Sierra Madre, particularly in Cinaloa and Tarahumery, provinces 1200 miles diflant from the capital. Further N. they have been called, from their bright appearance, the Shining Mountains. The height of Chimborazo, the most elevated point of this vast chain, is 20,280 feet above the level of the fea; which is 7102 feet higher than any other mountain in the known world. The Andes commonly form two ridges as they run, the one higher and

and

and barren, and covered with fnow, although in the torrid zone; the other fruitful in woods, groves, &c. The latter abounds with wild hogs; and fheep called guanacos, refembling a camel in fhape, but of a fmaller fize, whofe hair for foftnefs, finenefs, and colour is preferred to filk. The Andes have 16 volcances, which break out in various places, and by melting the fnow, occafion fuch torrents of water, that numbers of men and cattle have perifhed. They are only pafiable in fummer, and require 3 or 4 days to reach the top of any one of the higheft.

ANDOVER, a large, fertile and thriving town in Effex county, Maffachufetts. It contains 2863 inhabitants, in two parifles. In the South parifle are a paper mill and powder mill, from the latter of which the army received large fapplies of gun-powder in the late war. There is an excellent academy in this town, called "Phillips Academy," which owes its exiftence to the liberal benefactions of the family whole name it bears. Andover is under excellent cultivation, particularly that part which is watered by Shawtheen River. It lies about 20 miles W. from Newburyport, and about 22 N. from Boffon.

ANDOVER, in Hillfborough, New-Hampfhire, contains 645 inhabitants, and was incorporated 1779.

ANDOVER, is the fouth-westernmost township in Windsor county, Vermont, has Chetter on the E. lies 32 miles N. E. of Bennington, and contains 275 inhabitants.

ANDOVER, a place in Suffex county, New-Jerfey, near the fource of Pequeft River, 5 miles S. S. E. from New-Town, and 16 in the fame direction from Walpack.

ANDRE, ST. a town in the kingdom of Leon, in North-America, near the mouth of Naffas River, which falls into the Gulf of Mexico.

ANDREANOFFSKI Ifles, a crefcent of ifles between Afia and America, difcovered in 1760. See Bebring's Straits, and Northern Archipelago.

ANDRES, ST. or Andreas, an ifland on the Muíquito fhore, off the Pearl Keys. N. lat. 12. 30. W. long. 82. 30.

ANDREW'S, ST. a fmall town in the contefled country between New Brunfwick and the United States; fituated in the rear of an ifland of the fame

ANG

name, on the E. fide of the arm of the inner bay of Paffamaquoddy, called Scoodick. The 'town is regularly laid out in the form of an oblong fquare. The few inhabitants are chiefly employed in the lumber trade. The common tides rife here about 18 feet.

ANDRÉW's, ST. a township in Caledonia county, Vermont, 100 miles N. E. from Bennington.

ANDREW's, ST. a parifh in Charleft ton diffrict, South-Carolina, containing 2947 inhabitants, of whom 370 are whites, and 2546 flaves.

ANDREW'S SOUND, ST. lies S. of Jekyl's Ifland, and is formed by it and a finall ifland at the mouth of Great Sagilla River. The finall river opposite this Sound feparates Camden from Glynn county, in Georgia.

ANDROS, iflands on the S. W. of Providence, in the Bahama iflands, called by the Spaniards, Ylles del Efpiritu Santo. They take up a fpace of 30 leagues long and 4 or 5 broad, interfected by a number of very narrow paffages.

ANDROSCOGGIN, or Amarifcoggin River, in the diffrict of Maine, may be called the main weftern branch of the Kennebeck. Its fources are N. of Lake Umbagog. Its course is foutherly till it approaches near to the White Mountains, from which it receives Moofe and Peabody rivers. It then turns to the E. and then to the S. E. in which courfe it paffes within two miles of the fea-coaft, and then turning N. runs over Pejepskaeg falls into Merry-Meeting-Bay, where it forms a junction with the Kennebeck, 20 miles from the fea. Formerly, from this bay to the fea, the confluent fream was called Sagadahock. The lands on this river are very good.

ANEGADA, one of the Virgin Isles in the Weft-Indies, and dependent on Virgin Gorda. It is about 6 leagues long, is low, and almost covered by water at high tides. On the S. fide is Treasure Point. Lat. 18. 35. N. long. 63 W.

ANGARAEZ, a province in South-America, in the empire of Peru, fubject to the archbish p of Lima, 20 leagues N. W. by W. of the city of Guamanga. It abounds in all kinds of grain and fruits, befides vast droves of cattle for labour and fustenance. ANGELO,

ANGELLO, j the South Sea tween St. Pe broad open bay, but bad landin

reckon it as goo ANGELOS, C of Mexico, exte and South Seas, former which i Mexico on the axaca on the S. on the S. the pro on the W. and N. from which river or Cavones other it is one] 80 along the G upon the South S mate, and produ with Mexico Pre is a chain of me well cultivated ridge of mounts neighbourhood a fhocking temper and frequent im allowed to be th try of New-Spai cribed to its ha Cortez, in the co obtained a grant V. then also king is to this day exe duty whatfoever only pays the kin of maize per hear ment, which inco moft 60 years as 3,000 bufhels; of that Indian con had the name of ' of bread, which principal town. towns and village Its principal tov Achiachica, Tufj Naftla, or Almira Delganda, Sampu Tepeafa, Cordov: Vera Cruz, &c. if tongue, and are perfectly reco customs, and gra nance and defere above their fellow anciently governe wars arifing in i themfelves into an

14

m of the y, called larly laid g fquare. r employcommon

ip in Ca+ oo miles 1 Charlef4

370 are

by it and of Great er oppolite den from

S. W. of ands, call Efpiritu ice of 30 ad, interarrow paf-

ariscoggin e, may be ich of the . of Lake atherly till ite Moun-Moofe and rns to the in which iles of the N. runs rry-Meetfion with m the fea. he fea, the d Sagadaer are very

irgin Ifles pendent on t 6 leagues covered by t S. fide is 5. N. long.

in South-Peru, fub-Lima, 20 the city of all kinds of ft droves of nce. ANGELO, ANG

ANGELLO, port of, is an harbour on the South Sea coaft, in the middle between St. Pedro and Capolita; a broad open bay, with good anchorage, but bad landing; and the Spaniards reckon it as good a harbour as Guatulis.

ANGELOS, or Tlascala, a province of Mexico, extending both to the North and South Seas, having that part of the former which is called the Gulf of Mexico on the E. the province of Guaxaca on the S. E. the Pacific Ocean on the S. the province of Mexico Proper on the W. and that of Penuco on the N. from which it is divided by Tufpa river or Cavones. From one fea to the other it is one hundred leagues, about 80 along the Gulf of Mexico, and 20 upon the South Sea coaft. Its foil, climate, and produce; are much the fame with Mexico Proper. On the W. fide is a chain of mountains of 18 leagues, well cultivated; and another great ridge of mountains on the N. W. the neighbourhood of which fubjects it to thocking tempefts, horrid hurricanes, and frequent inundations; yet this is allowed to be the most populous coun-try of New-Spain, which is partly afcribed to its having been an ally to Cortez, in the conquest of Mexico, who obtained a grant of the emperor Charles V. then also king of Spain, by which it is to this day exempt from all fervice or duty whatfoever to that crown; and only pays the king of Spain an handful of maize per head, as an acknowledgement, which inconfiderable parcels, almost 60 years ago, amounted to near 13,000 bushels; for it produces fo much of that Indian corn, that from thence it had the name of Tlascala, i. c. the land of bread, which name it gives to its principal town. By this means the towns and villages fwarm with Indians. Its principal towns are Acafuchithau, Achiachica, Tuípa, Zacatlan, Cazeres, Naftla, or Almira, Torre Blanca, Punta Delganda, Samputa, Xalappa, Puebla, Tepeafa, Cordova, Punta Brava, New Vera Cruz, &c. They fpeak the Span-ifa tongue, and fearcely any other; are perfectly reconciled to the Spanifh cuttoms, and grateful for the counte-nance and deference shewed to them above their fellow-provinces. It was anciently governed by kings, till civil wars arifing in it, the people formed themfelves into an arithocracy of many

princes, to get rid of one. They divided the towns into different diffricts, each of which named one of their chiefs to refide in the court of Tlafcala, where they formed a fenate, whole refolutions were a law to the whole. Under this form of government, they maintained themfelves against the rulers of Mexico; and continued their aristocracy till their reception of the Spaniards under Cortez, whom they affilted with their numerous forces, and accomplished the ruin of that empire in 1521. See Mexico.

ANGOL, a town in the province of . Chili, South-America, 125 miles N. of Baldivia, S. lat. 27, 26. W. long. 72, 59

Baldivia. S. lat. 37. 36. W. long. 72. 59-ANGRA DE LOS REYES, a town in the captainfhip of Rio de Janeiro, in Brazil, South-America, fubject to the Portuguefe, about 36 miles from Rio de Janeiro. It is fituated upon the coaft in a fmall bay, from whence it has its name; being in English King's Bay. It has 2 churches, a monastery, and 2 finall guard-house of about 20 foldiers. Its chief produce is fifth. Lat. 22. 28. S. long. 41. 10. W.

ANGUILLA, or Snake Ifland, fo called from its windings and irregular form, being 10 leagues in length, and 3 in breadth; 25 leagues N. W. of Barbuda, and 15 from St. Christopher's. It is the moft northerly of all the Caribbee iflands poffeffed by the Britifh. It was fettled in 1650. The inhabitants fubfift moftly by farming, planting Indian corn, and other kinds of hubbandry. The climate is very healthy, and the inhabitants ftrong and vigorous. The exports in 1770, amounted, in fugar, rum, and cotton, to near 60001. Long. 62. 10. W. lat. 18. 4. N.

ANGUILLA, a bank and island E. of the Great Bahama Bank, and N. of the island of Cuba. Long. 78. 10. to 79¹/₂. lat. 23¹/₂. to 24. 10. N.

ANGUILLE, CAPE, a point of land in Newfoundland ifland, on the W. fide, in the Gulf of St. Lawrence, 6 leagues N. from Cape-Ray, the S. W. extremity of the ifland, in lat. 47, 57 N

extremity of the ifland, in lat. 47. 57. N. ANGUILLE, a bay on the N. N. E. fide of the ifland of St. John's, in the Gulf of St. Lawrence, opposite Magdalen Ifles; and having St. Peter's harbour on the S. E. and Port Chimene on the N. W.

ANNAPOLIS River, in Nova-Scotia,

is

is of fmall fize. It rifes in the E. near the head waters of the fmall rivers which fall into the bafon of Minas. Annapolis river paffes into the bay of Fundy through the bafon of its own mane, on the S. fide of which, at the mouth of the river, ftands the town and fort of Annapolis Royal. It is navigable for fhips of any burden 10 miles, for those of 100 tons, 15 miles; and is paffable for boats within 20 miles of Horton. The tide flows up 30 miles.

16

ANNAPOLIS, a county on the above river, adjoining to King's county, having 5 townships, viz. Wilmot, Granville, Annapolis, the chief towns, Clare, and Monckton. It is chiefly inhabited by Acadians, Irish, and New-Englanders.

ANNAPOLIS ROYAL, called Port Royal, by the French, when M. de Ponts fettled a colony here in 1605. This town, the chief town in the county of this name, ftands on the S. fide of the river and bay of Annapolis. Nature has fcarcely omitted one thing to render this the finest harbour in the world. It is two leagues in length, and one in breadth, having a fmall ifland, called Goat ifland, almost in the middle of the bason, which is faid to be large enough to contain feveral hundred thips. Its depth of water is no where lefs than 4 or 5 fathoms; it being 6 or 7 on one fide of the ifland, and on the other 16 or 18. / The bottom is every where very good, and thips may be fecure in it from all winds. The entrance of the harbour is difficult, fays Charlevoix, befides the inconvenience of great fogs; fo that only one fhip can pais in or out at a time, and that with the greatest precaution, the ship being obliged to go ftern foremult by reason of the ftrong currents and tides here. The town is not large, but has fome very handfome buildings. It is fortified; nor can it be cafily attacked, but by a bombardment. The fort is capable of containing about 100 men in its prefent ftate. N. lat. 45. 10. W. long. 64. 5. ANNAPOLIS, is the chief town of Ann Arundel county, and the capital of the fate of Maryland. It ftands at the mouth of the Severn, 30 miles S. of Baltimore; 32 E. by N. from the Federal city; 72 S. W. from Wilmington, in Delaware flate, and 132 S. W. from Philadelphia. It was formerly called

Severn, and in 1694, it was made a port town. It is fituated on a peninfula formed by the river and two small creeks; and affords a beautiful prospect of Chefapeak Bay and the E. fhore beyond it. This city is of little note in the commercial world; but is the wealthielt town of its fize in the United States. The houfes, about 300 in number, are spacious and elegant, indicative of great wealth. The flate-house is the nobleft building of the kind in the union. It ftands in the centre of the city, from which point the freets diverge in every direction, like radii. N. lat. 38. 56. 15. long. 75. 8. W.

ANNATOM, one of the new Hebrides clufter of iflands.

ANNARUNDEL County, in Maryland, lies between Patapíco and Patuxent Rivers, and has Chefapeak Bay S. E. Annapolis is the chief town. This county contains 22,598 inhabitants, of whom 10,131 are flaves.

ANN, CAPE, is the point of land in the town of that name, or Gloucefter, which-forms the N. fide of Maffachufetts Bay, as Cape Cod does the S. fide. N. lat. 42. 45. long. 70. 17. W. See *Gloucefter*. This Cape was fo named in honour of Ann, confort of King James I.

ANN, ST. a lake in Upper Canada, northerly from Lake Superior, which fends its waters north eafterly into James's Bay, through Albany River. Its north-eaftern-point lies in N. lat. 50. W. long. 88.

ANN, ST. is the chief town of the province of Parana, in the E. division of Paraguay, South-America.

ANN, FORT, in the flate of New-York, lies at the head of batteaux navi+ gation, on Wood Creek, which falls into South Bay, Lake Champlain, near Skenefborough. It lies 62 miles S. W. by S. from Skenefborough Fort; 10 E. S. E. from Fort George, and 12 N. E. by N. from Fort Edward, on Hudfon River. Such was the favage ftate of this part of the country, and the layers of trees laid lengthwife and acrofs, and fo broken with creeks and marfhes, that General Burgoyne's army, in July, 1777, could fcarcely advance above a' mile in a day, on the road to Fort Edward. They had no fewer than 40 bridges to conftruct, one of which was of log work 2 miles in length ; circumftances

flances which i hardly credible ANN's, ST. Cape Breton I fels often put i fide of the entry W. long. 60. ANN's, ST. River St. John Brunfwick, ak John's. It is government.

ANSON, an Carolina, in I Mecklinburgh and Cumberlan contains 5133 828 flaves.

ANTHONY'S Miffifippi, lie a the mouth of s joins the Miffi are fituated in a were fo named pin, who travel the year 1680, pean ever feen The whole rive perpendicularly forms a most p rapids below, in render the defce fo that when vie appear to be really are. In is a fmall ifland and fomewhat l a few hemlock about half way the eaftern fliore, very edge of th polition, 5 or 6 h long. These fa ated, as they an the least obstrue ing hill or precip faid, perhaps, of fall in the world. exceedingly beau interrupted plain no relief, but con afcents, which, mer, are covered teciperied with li pleafing variety t

At a little dift a finall ifland, ab grow a great nur the branches of w as made a port a peninfula nd two fimali atiful prospect e E. fhore bef little note in but is the in the United t 300 in numant, indicative te-houfe is the kind in the centre of the the ftreets diike radii. N. . 8. W. new Hebrides

, in Maryland, and Patusent eak Bay S. E. town. This nhabitants, of

bint of land in or Gloucefter, of Maffachutes the S. fide. 17. W. See was fo named fort of King

Jpper Canada, perior, which eafterly into Albany River, ies in N. lat.

f town of the ne E. division erica. state of Newbatteaux navi+ , which falls amplain, near i miles S. W. igh Fort; 10 ge, and 12 N. ard, on Hudhe favage ftate ntry, and the vife and acrofs, s and marshes, army, in July, rance above a' d to Fort Edewer than 49 of which was ngth; circumftances

ANT

ftances which in after ages will appear weight, are, in the proper feason of the hardly credible. Weight, are, in the proper feason of the

ANN'S, ST. a port on the E. fide of Cape Breton Ifland, where fifting veffels often put in. It lies on the N. W. fide of the entrance into Labrador Lake. W. long, 60, N. lat. 47.

W. long. 60. N. lat. 47. ANN'S, ST. is a fmall town on the River St. John's, province of New-Brunfwick, about 80 miles from St. John's. It is at prefent the feat of government.

ANSON, an interior county of N. Carolina, in Fayette diffrict, having Mecklinburgh county N. and Bladen and Cumberland counties on the E. It contains 5133 inhabitants, including 828 flaves.

ANTHONY's FALLS, ST. in the River Miffifippi, lie about 10 miles N. W. of the mouth of St. Pierre River, which joins the Miffilippi from the W. and are fituated in about lat. 44. 50. N. and were fo named by father Louis Henni-pin, who travelled into these parts about the year 1680, and was the first European ever feen by the natives there. The whole river, 250 yards wide, falls perpendicularly above 30 feet, and forms a most pleasing cataract. The rapids below, in the fpace of 300 yards, render the descent confiderably greater; fo that when viewed at a distance, they appear to be much higher than they really are. In the middle of the falls is a fmall ifland, about 40 feet broad, and fomewhat longer, on which grow a few hemlock and fpruce trees; and about half way between this island and the eaftern fliore, is a rock, lying at the very edge of the fall, in an oblique polition, 5 or 6 feet broad, and 30 or 40 long. These falls are peculiarly fituated, as they are approachable without the least obstruction from any intervening hill or precipice; which cannot be faid, perhaps, of any other confiderable fall in the world. The scene around is exceedingly beautiful. It is not an uninterrupted plain, where the eye finds no relief, but composed of many gentle afcents, which, in the fpring and fummer, are covered with verdure, and inteciperied with little groves, that give a pleafing variety to the profpect.

At a little diffance below the falls is a fmall ifland, about 14 acre, on which grow a great number of oak trees, all the branches of which, able to bear the ANT

weight, are, in the proper feafon of the year, loaded with eagle's nefts. Their infinctive wildom has taught them to choose this place, as it is secure, on account of the rapids above, from the attacks either of man or beaft.

ANTHONY'S Kill, a weftern water of Hudfon River. Its mouth is 7 miles above that of Mohawk River, with which likewife it communicates at the E. end of Long Lake.

E. end of Long Lake. ANTHONY'S Nole, a point of land in the Highlands, on Hudfon River, in the flate of New-York, from which to Fort Montgomery on the opposite fide, a. large boom and chain was extended in the late war, which cost not lefs than 70,000l. fterling. It was partly deftroyed and partly carried away by General Sir Henry Clinton, in October, 1777. Allo, the name given to the point of a mountain on the N. bank of Mohawk River, about 30 miles above Schenectady. Around this point runs the flage road.

ANTICOSTI, a barren, uninhabited ifland, in the mouth of St. Lawrence River.

ANTIETAM Creek, in Maryland, rifes by feveral branches in Pennfylvania, and empties into Potowmack River, 3 miles S. S. E. from Sharpfburgh. Elizabeth and Funk's towns ftand on this creek. It has a number of mills and forges.

ANTIGUA, or Antego, one of the Caribbee Hands in the Weft-Indies, belonging to Great-Britain, is fituated 60 miles to the eaftward of Nevis and St. Chriftopher's. It is almost circular; being about 15 miles long and 10 broad, containing 59,838 acres of land, of which about 34,000 are appropriated to the growth of fugar and pafturage annexed : Its other ftaples are cotton and tohacco. The foil is naturally rich, and when not checked by excelfive droughts, to which Antigua is particularly fubject, is very productive. Columbus, who discovered this island, named it from a church in Seville, Santa Maria de la Antigua; and his fone Ferdinand, fays that its Indian name was Jamaica. It is a fingular circumftance, that this word, which in the language of the larger islands fignified a country abounding with fprings, fhould, in the dialect of the Caribbees, have been applied to an island that has not a fingle

a fingle fpring or rivulet of fresh water The inhabitants make ufe of in it. rain water, which, when preferved in cifterns, is light, pure and wholefome. From drought and other circumftances, it is difficult to furnish an average return of the crops, which vary to fuch a degree, that the quantity of fugar exported in fome years, is five times greater than in others'; thus in 1779, were fhipped 3382 hogfheads, and 579 tierces; in 1782, the crop was 15,382 hogfheads, and 1603 tierces; and in the years 1770, 1773, and 1778, there were no crops at all; the canes being deftroyed by a long drought, and the whole body of negroes must have perifhed, for want of food, if American veffels had not fupplied them with corn and flour. On an average, 17,000 hogfheads of fugar, of 16 cwt. each, are reckoned a good faving crop. Antigua exported in one year, ending the 5th of January, 1778, to the value of 592, 5961. 158. 8d. fterling, in 233 veffels: the cargoes were 284,526 cwt. 1 gr. 18 lbs. fugar; 719,546 gal. molaffes; 26 lbs. indigo; dying woods and other finall articles. The value exported to the United States, included in the above, was f. 11,031 15 4. The island abounds in black cattle, hogs, fowls, and moft of the animals in common with the other islands. The number of inhabitants, both white and black, feem to have decreafed progreffively. In 1774, the white inhabitants amounted to 2590, and the flaves to 37,808. The ifland is divided into 6 parifhes and 11 diffricts. The parifhes are St. John's, St. Mary's, St. George, St. Peter, St. Paul, and St. Philip. It has 6 towns and villages. St. John's, (the capital) Parham, Falmouth, Willoughby-Bay, Old-Bay, Old-Road, and James Fort; the two first of which are legal ports of entry. No island in this part of the West-Indies can boast of so many excellent harbours; of these the principal are Englifh Harbour, and St. John's, both well fortified; and at the former are a royal navy yard, and arfenal, with conveniences for careening fhips of war. The military eftablishment generally confifts of z regiments of infantry, and z of foot militia. There are likewife a fquadron of dragoons, and a battalion of artillery, both raifed in the ifland; and the regulars receive additional pay

as in Jamaica. The governor or cap-tain-general of the Leeward Caribbean Islands, generally refides in Antigua, but visits occasionally each island within his government; and, in hearing and determining caufes from the other iflands, prefides alone: He is chancellor of each ifland by his office ; but in caules arifing in Antigua, he is affifted by his council, after the practice of Barbadoes; and the prefident, together with a certain number of the council. may determine chancery caufes during the absence of the governor-general. The other courts of this island are a court of king's bench, a court of common pleas, and a court of exchequer. The church of the United Brethren has been very fuccefsful in converting to chriftianity many of the negro flaves of this and the other iflands. The climate here is hotter than at Barbadoes, and like that ifland fubject to hurricanes. The first grant of Antigua was made by Charles II. about 1663, to William Lord Willoughby of Parham, and three years after, a colony was planted. was furprifed the fame year by the French. It made no figure in commerce, till Col. Chriftopher Codrington, lieut. governor of Barbadoes, came and fettled here in 1690. There happened a most terrible hurricane here in 1707, that did vaft damage to this ifland and Nevis, more than to any of the Carribbee iflands. In October, 1736, was the plot of Court, Tombay and Hercules, three Indians who had conveyed gun-powder under the ball-room, where the governor was to give a hall ; but it was happily difcovered, and they were all executed. Antigua lies between 17. 71. and 17. 17. 45. N. lat. and between 61. 22. 15. and 61. 36. 12. W. long.

ANTILLES, a clufter of iflands in the Weft-Indics, diffinguifhed into Great and Small. They lie from 18 to 24 degrees of N. lat. are diffinguifhed into Windward and Leeward Iflands, and lie in the form of a bow, ftretching from the coaft of Florida N. to that of Brazil S. The moft remarkable of them are Cuba, Jamaica, Hifpaniola or Domingo, and Porto Rico. See each under its proper head.

ANTIQUERA, a feaport town in the province of Guaxaqua, in Mexico.

ANTIQUIERA, or Antequiera, a town

75 miles S. of ANTRIVEN Terra Firmas Carthagena: ANTONIO I town in Mexic coaft of the Pai W. long: 93. 5 ANTONIO, province of Ap ANTONIO, Navarre, in No which runs S. California. ANTONIO, C tern point of th ing on the N. and rocks, call tween which an nel of Guanigu W. long. 8 51. ANTONIO D Brazil, in South St. Augustine, guefe. Here th quantity of fuga long. 35. 22.

in New-Spain,

ANTONIO, ST co, on the W. field below St. Grego of a town on the falls into the Gu Rio de Brava; of the river, S. by ANTERIM, a rough county, Nu 528 inhabitants, 75 miles W. of the fame diffance

ANVILLE, or J phine county, Per of Tulphehocker canal between th Schuylkill, along pleted, this town fome confequence. E. by E. from Ha W. from Philadel

ANZERMA, is Popayan, in Sou mines of gold. In Coca. N. lat. 4. APACHIERA,

vince of New-Me St. Fe, in N. lat. APALACHES, or the country of the E, Florida, in N. la

or cap aribbean Antigua, id within ring and e other chancel-; but in is affifted e of Bartogether : council, s during -general, ind are a of comcchequer. thren has erting to) flaves of ne climate does, and urricanes. was made) William and three inted. It ir by the : \in com-Codringloes, came There hapcane here ge to this to any of ber, 1736, mbay and had conball-room, ive a ball ; I, and they ia lies be-45. N. lat. 61. 36. 12.

> lands in the into Great 8 to 24 deuished into flands, and tching from hat of Brable of them iola or Doice each un-

town in the Mexico. iera, a town ìn APA

In New-Spain, province of Guazaqua, 75 miles S. of the city of Guazaqua.

ANTRIVENTRIA, a fubdivision of Terra Firma, lying to the South of Carthagena:

ANTONIO DE SUCHITEPEC, ST. a town in Mexico or New Spain, on the coaft of the Pacific Ocean. N. lat. 15. W. long: 93. 5.

ANTONIO, ST. the capital of the province of Apachiera, in New-Mexico.

ANTONIO, a town in the province of Navarre, in North-America, on a river which runs S. W. into the Gulf of California.

ANTONIO, CAPE, ST. the most weftern point of the island of Cuba; having on the N. W. a number of iflots and rocks, called Los Colorados, between which and the cape is the channel of Guaniguanica. N. lat. 22. 15. W. long. 8 51

ANTONIO DE CABO, ST. a town in Brazil, in South-America, near Cape St. Augustine, fubject to the Portuguefe. Here they make a confiderable quantity of fugar. S. lat. 8. 34. W. long. 35. 22.

ANTONIO, ST. a town in New-Mexico, on the W. fide of Rio Bravo River, below St. Gregoria. Alfo, the name of a town on the river Hondo, which falls into the Gulf of Mexico, N. E. of Rio de Brava; and on the eastern fide of the river, S. by W. from Texas.

ANTERIM, a township in Hillsborough county, New-Hampfhire, having 528 inhabitants, incorporated in 1777; 75 miles W. of Portimouth, and about the fame diftance N. W. of Bofton.

ANVILLE, or Miller's Town, in Dauphine county, Pennfylvania, at the head of Tulphehocken Creek. When the canal between the Sufquehannah and Schuylkill, along thefe creeks, is completed, this town will probably rife to fome confequence. It lies 18 miles N. E. by E. from Harrifburgh, and 65. N. W. from Philadelphia.

ANZERMA, is a town and province of Popayan, in South-America, having mines of gold. It is feated on the river Coca. N. lat. 4. 58.

APACHIERA, an audience and province of New-Mexico, whole capital is St. Fe, in N. lat. 36. 30. W. long. 104.

APALACHES, or St. Mark's R. rifes in the country of the Seminole Indians, in E. Florida, in N. lat. 31. 30. near the N. Florida, having the Seminole country

APA

W. fource of Great Satilla River ; runs S. W. through the Apalachy country, into the bay of Apalachy, in the Gulf of Mexico, about 15 miles below St. Mark's. It runs about 135 miles, and falls into the Bay near the mouth of Apalachicola River.

APALACHICOLA, a river between E. and W. Florida, having its fource in the Apalachian Mountains, in the Cherokee country, within ten miles of Tuguloo, the upper branch of Savannah River. From its fource to the mouth of Flint River, a diftance of 300 miles, it is called Chata-Uche, or Chatahooche River. Flint River falls into it from the N. E. below the Lower Creek Towns, in N. lat. 31. From thence it runs near 80 miles and falls into the Bay of Apalachy, or Apalachicola, in the Gulf of Mexico, at Cape Blaize. From its fource to the 33d deg. of N. lat. its courfe is S. W. from thence to its mouth it runs nearly S. See Chata-Ucha and Flint Rivers

APALACHICOLA, is likewife the name of the mother town or capital of the Creek or Muscogulge confederacy, called Apalachucla by Bertram. It is, fays he, facred to peace; no captives are put to death or human blood fpilt here : and when a general peace is proposed, deputies from all the towns in the confederacy meet here to deliberate. On the other hand, the great Coweta Town, 12 miles higher up the Chata-Uche River, is called the Bloody Town, where the Micos chiefs and warriors affemble when a general war is proposed; and there captives and state malefactors are put to death. Apalachicola is fituated a mile and an half above the ancient town of that name, which was fituated on a penin-. fula formed by the doubling of the river, but deferted on account of inundations. The town is about 3 days journey from Tallaffee, a town on the Tallapoofe River, a branch of the Mobile River. See Coweta, and Tallaffee.

APALACHIAN Mountains, a part of the range called fometimes by this name, but generally Allegbany Mountains. In this part of the great chain of moun-tains, in the Cherokee country, the river Apalachicola has its fource.

APALACHY Country, extends acrofs Fline and Apalaches Rivers, in Eaft-

on the N. E. Apalachy, or Apalachya, is by fome writers, applied to a town and harbour in Florida, 90 miles E. of Penfacola, and the fame diftance W. from Del Spiritu Santo River. The tribes of the Apalachian Indians lie around it.

APOQUENEMY Creek, falls into Delaware Bay from Middletown, in Newcaffle county, Delaware, a mile and an half below Reedy Ifland. A canal is proposed to extend from the southern branch of this creek, at about 4 miles from Middletown, to the head of Bohemia River, nearly 8 miles distant; which will form a water communication between Delaware Bay, and that of Chefapeak, through Elk River.

APPLE Island, a finall uninhabited island in St. Lawrence River, in Canada, on the S. fide of the river, between Basque and Green Islands. It is furrounded by rocks, which renders the navigation dangerous.

APPLE Town, an Indian village on the E. fide of Seneca Lake, in New-York, between the townships of Ovid on the S. and Romulus on the N.

APPOMATOX, is the name of a fouthern branch of James River, in Virginia. It may be navigated as far as Broadways, 8 or 10 miles from Bermuda Hundred, by any vefiel which has croffed Harrifon's Bar, in James River. It has 8 or 9 feet water a mile or two farther up to Fifher's Bar, and 4 feet on that and upwards to Peterfiburg, where all navigation ceafes.

APOLO-BAMA, a jurifdiction confifing of miffions belonging to the Francifcans, fubject to the bilhop of Cufco, 60 leagues from that city, in the empire of Peru. These confist of 7 towns of converted Indians. To protect these from the infults of the other Indians, and to give credit to the Miffionaries, a militia is kept here, under a major-general, formed by the inhabitants.

APURIMA, or Aporamac, a very rapid river in Peru, South-America, 30 miles from the river Abanzai.

AQUAFORT, a fettlement on the E. fide of the fouth-eastern extremity of Newfoundland Island, lat. 47. 10. N.

AQUEDOCHTON, the outlet of lake Winnipifeogee, in New-Hampfhire, N. lat. 43. 40. whofe waters pais through feveral finaller ones in a S. W, courie, and empty into Merrimack River, be-

tween the towns of Sanburn and Canterbury.

AQUIDNECK, the ancient Indian name of Rhode-Island, in the state of Rhode-Island.

ARAGUAYA, a branch of Para River, in Brazil. See Para.

ARARAT, Mount, or the Stone Head, a flort range of mountains on the N. frontier of North-Carolina, in a N. E. direction from Ararat River, 2 N. W. branch of Yadkin River.

ARATHAPESCOW, an Indian tribe inhabiting the fhores of the lake and river of that name, in the N. W. part of North-America, between the latitudes of 57. and 59. N. North of this nation's abode, and near the Arctic Circle, is Lake Edlande, around which live the Dog Ribbed Indians.

ARAUCO, a fortrefs and town of Chili, in South-America; fituated in a fine valley, on a river of the fame name, N. by W. from Baldivia. The native Indians are fo brave, that they drove the Spaniards out of their country, though defitute of fire-arms. S. lat. 37. 30. W. long. 73. 20.

ARIZIBO, one of the principal places in Porto Rico Island, in the West-Indies. It has few inhabitants, and little trade but fmuggling.

ARCAS, an ifland in the Gulf of Mexico, in the Bay of Campeachy, Lat. 20, long. 92, 50.

Lat. 20. long. 92. 50. ARCH Spring. See Bald Eagle Valley.

ARCHIPELAGO, Dangerous, the name given by Bougainville, in Feb. 1768, to a cluster of islands in the Pacific Ocean, in the neighbourhood of Otaheite, fituated between 10. and 18. degrees S. lat. and between 142. and 145. degrees: W. long. from Paris. The iflands which compose this Archipelan go, he named Quatre Facardins, the Lanciers, and La Harpe, and other iflands, forming two groups, to which he gave no names. In April, 1769, Capt. Cook fell in with these same iflands, and named them Lagoon Ifland, Thrum Cap, Bow Ifland, and the Two Groups.

ARCHIPELAGO of the Great Cyclades, a clufter of iflands in the Pacific Ocean, lying between 14 and 20 deg. S. lat. and between 164 and 168 deg. E. long. from Paris, difcovered by Bougainville, a2d of May, 1768. This is the fame clufter elufter of islam In 1606, and b *frat del Effiri* Capt. Cook pal and called them ARDOIS, a tia, between W miles N. W. deemed the hig tia, and affords all the higb and for and Falmou try bordering th

AREQUIPA, in Peru, South-1 ed by Don I 1539. It ftand about 20 league tile country. N cano. The air the beft in the ce four times laid in It is very popu contains a conve and had a colleg bishoprick in Li S. by E. from th S. long. 75. 30. ARGYLE, a t county, New-Yo Hudson River, habitants, inclusi state census of 1 be 404 electors.

ARGYLE, a t county, Nova-Sc dians and Scotch.

ARICA, a juri rick of Arequips along the coaft of produces little elf pepper; and in olives, of which pickles; but, alt otherwife barren, per amounts annu 60,000 dollars val

ARICA, a town vince of Los Cha the port-town to n that country. It trade, and very without a great de but badly fortified injured by earth alfo hurt its trade. here; the houses a roofs. The valley for little elfe than t and Can-

nt Indian he ftate of

ara River,

m the N. m a N. E. a N. W.

in tribe ine and river 7. part of a latitudes f this nareftic Cirnd which

n of Chili, in a fine name, N. native Indrove the y, though t. 37. 30.

weft-In-

e Gulf of ampeachy,

Eagle Val-

rous, the , in Feb. in the Paurhood of b, and 18. 142. and Paris. The Archipelardins, the and other to which ril, 1769, hefe fame son Island, the Two

> t Cyclades, fic Ocean, eg. S. lat. . E. long. Igainville, a the fame clufter

ARI

eluster of islands discovered by Quiros in 1606, and by him called Tierra Aufiral del Espiritu Santo, which see.— Capt. Cook passed these islands in 1774, and called them New Hebrides.

ARDOIS, a mountain in Nova-Scotia, between Windfor and Halifax; 13 miles N. W. from the latter. It is deemed the higheft land in Nova-Scotia, and affords an extensive prospect of all the high and low lands about Windfor and Falmouth, and the diftant country bordering the Bason of Minas.

AREQUIPA, is one of the largeft cities in Peru, South-America, and was founded by Don Francifquo Pizarro, in 1539. It ftands in the valley of Quilca, about 20 leagues from the fea, in a fertile country. Near it is a dreadful volcano. The air is very temperate; and the beft in the country; but it has been four times laid in ruins by earthquakes. It is very populous, and well built; contains a convent, and two nunneries, and had a college of Jefuits. It has a bifhoprick in Lima, and lies 290 miles S. by E. from that city. Lat. 16. 40. S. long. 75. 30. W.

ARGYLE, a township in Washington county, New-York, on the E. bank of Hudson River, containing 2341 inhabitants, inclusive of 14 flaves. In the state census of 1796, there appears to be 404 electors.

ARGYLE, a township in Shelburne county, Nova-Scotia, fettled by Acadians and Scotch.

ARICA, a jurifdiction in the bifhoprick of Arequipa, in Peru, extending along the coaft of the South Sea. It produces little elie than agi, or Guinea pepper; and in fome places large olives, of which they make oil and pickles: but, although the country is otherwife barren, the produce of pepper amounts annually to no lefs than 60,000 dollars value.

ARICA, a town and port in the province of Los Charcos, in Peru; being the port-town to most of the mines in that country. It is a place of valt trade, and very populous; feldom without a great deal of fhipping. It is but badly fortified, and has been much injured by earthquakes, which have also hurt its trade. No rain ever falls here; the houses are therefore without roofs. The valley of Arica is famous for little elfe than the culture of Guinea

pepper, which the Spaniards planted, and of this they raife annually to the value of 80,000 crowns. It is 550 miles S. E. of Lima. S. lat. 18. 27. W. long. 71. 6.

ARICHAT, a town in Cape Breton island.

ARIES Kill, a fmall creek which runs northerly into Mohawk River, 24 miles W. from Schoharie River, in New-York.

ARKANSAS, a N. W. branch of Miffifippi River, of a very lengthy courfe, which falls in by two mouths, and forms an ifland, whole north-weftern point lies in N. lat. 33. 35. W. long. 91. Its length 35 miles ; its breadth 10. The branch on the north-eaftern fide of the ifland, receives White River, about 24 miles from its mouth.

ARLINGTON, a township in Bennington county, Vermont, 12 miles N. from Bennington. It has 991 inhabitants.

ARMOUCHIQUOIS, a nation of Indians in Canada.

ARNEDO, a town in Peru, on the South-Sea, 25 miles N. of Lima.

ARRACIFFE, a port-town of Brazil, in the captainfhip of Pernambaco; efteemed the ftrongeft in all Brazil. The port confifts of a fuburb, in which are ione large houfes, and repolitories for flores; and is built upon a narrow paffage, with a caftle to defend the entrance. Notwithftanding which, James Lancafter entered the harbour in 1595, with 7 Englift veffels, and made himfelf mafter of the town and caftle, where he continued a month, and carried off immenfe plunder; but fince that time, the Portuguefe have rendered it almoft inacceflible to enemies. Lat. 8, 20, 8, long, 16, 10. W.

Lat. 8. 20. 8. long. 36. 10. W. ARRAYAL DE PORATE, a town in Brazil, fituated on the W. fide of Para River, below the junction of its two great branches. See Para River.

great branches. See Para River. ARROWSIKE, an illand in the diftrict of Maine, parted from Parker's Ifland by a fmall ftrait. It is within the limits of George-Town, and contains nearly $\frac{1}{2}$ of its inhabitants, and has a church. It contains about 20,000 acres of land, including a large quantity of falt marfh. See George-Town and Parker's Ifland.

here; the houses are therefore without roofs. The valley of Arica is famous for little elfe than the culture of Guinea for little elfe than the culture of Guinea to Solomon's Iflands on account of B 3 the barbarous character of their inhabitants, particularly at Port Prailin. Thefe illands were visited by Mr. Shortland in 1788, and by him called New-Georgia. See Solomon's Ifles and Port Prafin.

ARTHUR KULL, of Newark Bay, on the coaft of New-Jerfey, is formed by the union of Paffaic and Hackinfack Rivers.

ARUBA, one of the Little Antille Iflands, in the Weft-Indies, is fubject to the Dutch. It is uninhabited, lies near Terra Firma, 14 leagues W. of Curacoa, and produces little elfe befides corn and wood. N. lat. 13. 30. W. long. 67. 35.

ARUNDEL, a township in York county, district of Maine, containing 1458 inhabitants. It lies between Cape Porpoife, and Biddeford on the N. E. on Saco River, at miles N. E. from York, and 96 N. E. from Boston.

ASANGARO, a jurifdiction under the bishop of Cufco, in Peru, South America, 50 leagues from that city: numbers of cattle are bred here. There are fome filver mines in the N. E. part of it; and it produces papas, quinoas, and canaguas. Of the two laft they make chicha, as others do from maize.

ASCENSION Bay, lies on the F. fide of the peninfula of Yucatan, in the Bay of Honduras, having Amber Bay on the N. and the northern point of Ambergreefe Key on the S. which forms a paffage into Hanover Bay, S. from Afcention Bay.

This is also the name of a bay in the N. part of the Gulf of Mexico, fituated between Cape Balize at the mouth of the Millifippi, and the Bay of Fresh Water on the W, in the 30th degree of N. lat. and 92d of W. long.

N. lat. and 92d of W. long. ASHBURNHAM, formerly Dorchefler Canada, lies in Worcefter county, Maffachufetts, 30 miles N. of Worcefter, and 54 from Bolton, was incorporated in 1765, and contains 951 inhabitants. It flands upon the height of land E. of Connecticut River, and W. of Merrimack, on the banks of Little Naukheag. In this townfhip, is a white fand, equal in finenefs to that at Cape Ann, and which, it is judged, would make fine glafs.

ASHBY, a township in Middlefex county, Maffachufetts, 50 miles N. W. from Boston, containing 751 inhabitants.

ASHCUTNEY, or Afacutacy, a mountain in Vermont, being partly in the townfhips of Windfor and Weatherffield, and oppofite Claremont on Sugar River, in New-Hampfhire state. It is 2034 feet above the sca, and 2732, above high water in Connecticut River, which glides by its E. fide.

ASHFIELD, a township in Hampshire county, Maffachusetts, about 15 miles N. W. of Northampton, and 117 W. from Boston, containing 1459 inhabitants.

ASHFORD, a township in Windham county, Connecticut, settled from Marlborough in Massachusetts, and was incorporated in 1710. It lies about 38 miles north-easterly from Hartford, and 76 south-westerly from Boston.

76 fouth-wefterly from Boston. ASHFORD, NEW, a township in Berkshire county, Massachusetts, 155 miles W. from Boston, containing 460 inhabitants.

ASHMOT, the principal harbour in Ifle Madame, which is dependent on Cape Breton. See Breton Cape.

ASHUELOT, or Abwillet, a fmall river, having a number of branches, whole most diftant fource is at the N, end of the Sunapee Mountains, in New-Hampshire. It runs fouth-wefterly through part of Cheshire county. Below Winchester it runs W. hy N. and empties into Connecticut River, at Hinsdale.

ASPOTAGOEN Mountain. This high land lies on the promontary that feparates Mahone from Margaret's Bay, on the coaft of Nova-Scotia. It is feen at a great diftance from the offing, and is the land generally made by the fhipe bound from Europe and the Weft-Indies to Halifax. The fummit is about goo feet above the level of the fea.

ASSABET, a rivulet which rifes in Grafton, Worcefter county, Maflachufetts, and runs N. E. into Merrimack River.

ASSENEPOWALS, a lake weltward of Chriftianaux Lake, and through which its waters run into Albany River, in New South Wales.

Assiniboils, or Afiniboels, a river and lake in the N. W. part of North-America. The river is faid to rife in the Mountains of Bright Stones, runs N. E. into Lake Guinipique in N. lat. 51 W. long. 106.

The lake is placed in fome maps in the

the gad deg. long. It h Chriftianaux which fends i Near thefe l Chriftianaux, Killiftins.

Assinois, iting the foreft ASSUMPTI the province of vision of Parag America. It of a river of its place where the having Villa Plata on the S. ern, than the far from the mi continent. It iards in 1538, 1 healthy fituatio number of its in and fruitful terri which produces tive and exotic perfection. He Spanish familie flower of the gen place; while the trymen removed are likewife a nt Mulattoes. Th leagues above Paraguay and F mer begins to be la Plata. Near for having in th which fhoots up. like an obelifk. 40. W.

Assumption falls in from the . after a N. W. an as miles, 5 miles §

ASTCHIKOUN Britain, aboundin fuppofed to con Northern Sea.

ATACAMA, of harbour, province Peru in S. Ameri-La Plata; fertile, the fifh called Tole ries on a great tr provinces. This kingdom of Peru There is a great name, and a chain

a mouny in the Veatherfm Sugar c. It is 31, above er, which

lampfhire 15 miles 117 W. inhabit-

Windham om Marld was inabout 38 tford, and mihip in fetts, 155 ining 460 arbour in indent on pe. , a fmall branches, at the N. , in Newh-wefterly nty. Behy N. and River, at

This high that fepa-'s Bay, on ; is feen at ig, and is the fhips Weft-Init is about e fea. ch rifes in Maflachu-Merrimack

; weftward d through Jbany Ri-

4, a river of Northto rife in ones, runs in N. lat.

ie maps in the

ATA

the sad deg. of N. lat. and 96th of W. long. It has communication with Chriftianaux Lake, on the eaftward, which fends its waters to James Bay. Near these lie the countries of the Chriftianaux, and Kiris, called alfo Killiftins.

Assinors, a nation of Indians inhabiting the forefts of Canada.

Assumption, an epifcopal city, in the province of Paraguay, in the E. di-vision of Paraguay or La Plata in S. America. It fands on the eaftern bank of a river of its name, a little above the place where the Picolmaga falls into it : having Villa Rica on the N. and La Plata on the S. and is nearer the fouthern, than the Pacific ocean : but not far from the middle of that part of the continent. It was built by the Spanhards in 1538, and is remarkable for its healthy fituation, as well as for the number of its inhabitants, and the rich and fruitful territory in which it ftands ; which produces a great variety of na-tive and exotic fruits, in the higheft perfection. Here are feveral hundred Spanish families, descendants of the flower of the gentry who fettled in this place; while the dregs of their countrymen removed to other parts. There are likewife a number of Meftizos and Mulattoes. The city lies about 50 leagues above the confluence of the Paraguay and Parana, where the former begins to be called, the River de la Plata. Near the city is a lake, noted for having in the middle of it a rock, which fhoots up to a prodigious height like an obelifk. Lat. 26. S. long. 57. 40. W.

Assumption River, in New-York, falls in from the E. into Lake Ontario, after a N. W. and W. course of about 28 miles, 5 miles S. E. from Pl. Gaverfe.

ASTCHIKOUNIPI, a vaft lake in New-Britain, abounding with whales, and fuppofed to communicate with the Northern Sea.

ATACAMA, or Attacama, a town, harbour, province, and jurifdiction in Peru in S. America, 120 leagues from La Plata; fertile, and remarkable for the fifth called Tolo, with which it carries on a great trade with the inland provinces. This province divides the kingdom of Peru from that of Chili. There is a great defert of the fame name, and a chain of mountains which feparate Peru on the N. from the province of Quito. On these mountains the cold is fo violent, that paffengers are fometimes frozen to death. Lat. 22. S. long. 80. 20. W.

ATCHI KOUNIPI, a lake in Labrador, which fends its waters foutherly into St. Lawrence R. through a connected chain of fmall lakes.

ATHAPESCOW Lake. See Ara-thapefcow, and Slave Lakes. ATHENS, a township in Windham co. Vermont, 32 miles N. E. from Ben-nington, and about 6 W. from Con-necticut R. having 450 inhabitants. Sextons R. which rifes in Londonderry, paffes S. E. by Athens, into the townthip of Westminster to Conn. R.

ATHOL, a township in Worcester co. Maffachufetts, containing 16,000 acres of land, very rocky and uneven, but well watered with rivers and ftreams : On these stand 4 grift-mills, 6 faw-mills, a fulling-mill and a trip hammer. It contains 848 inhabitants, is 35 miles N. W. from Worcefter, and 72 from Bofton. A medicinal (pring famed for its many virtues, iffues out of a high bank on Miller's River, 20 feet above the furface of the river.

ATKINSON, a township in Rockingham co. N. Hampfhire, which was incorporated in 1767, and in 1775 contained 575 inhahitants, in 1790 only 479. It is diftant 30 miles from Portfmouth, and has an academy which was founded in 1789, by the Hon. N. Peabody, who endowed it with 1000 acres of land.

In this township is a large meadow wherein is an ifland of 6 or 7 acres, which was formerly loaded with valuable pine timber and other foreft wood. When the meadow is overflowed, by means of an artificial dam, this ifland rifes with the water, which is fometimes 6 feet. In a pond, in the middle of the ifland, there have been fifh, which, when the meadow has been overflowed have appeared there, when the water has been drawn off, and the island fettled to its ufual place. The pond is now almost covered with verdure. In it a pole 50 feet long has disappeared, without finding bottom.

ATLANTIC Ocean, The, feparates America from Europe and Africa.

ATOYAQUE, a deep and large river in Mexico, or New Spain. On it is B 4 the

the famous natural bridge, called Ponti di Dio, 100 miles S. E. of Mexico, over which coaches and carriages conveni-

ently pais. ATRATO, a confiderable river which runs into the Gulf of Mexico, near Carthagena.

TTLEBOROUGH, a township in Briftol co. Maffachusetts, 32 miles foutherly from Bolton, and 9 N. from Providence.

ATWOOD's Key, a fmall ifland furrounded by rocks, 12 miles N. E. from Crooked I. and 50 eastward from Yuma,

or Long. I. one of the Bahamas. N. lat. 23. 28. W. long. 73. AUGUSTA Co. in Virginia, has Albe-marle co. on the E. Part of it lies E. and part W. of the North Mt. a ridge of the Alleghany. The foil is fertile, and the county contains 10,886 inhabi-terest isolution 2556 forms

tants, including 1567 flaves. Here is a remarkable cafcade, called the *Falling Spring*. It is a branch of the James, where it is called Jackfon's R. rifing in the mountains 20 miles S. W. from the Warm Spring, or Hot Spring, which lies in N. lat. 38.9. W. long. 80. 6. At the Falling Spring, the water falls 200 feet; which is about 50 feet higher than the fall of Niagara. Between the fheet of water and the rock below, a man may walk across dry. The fheet of water is only 12 or 15 feet wide above and fomewhat wider below, _ It is broken in its breadth in two or three places, but not at all in its height.

AUGUSTA, in the Upper Diftrict of Georgia, was till lately the feat of go-vernment. It is fituated on a fine plain in Richmond co. on the S. W. bank of Savannah R. where it is near 500 yards broad, at a bend of the river, 127 miles N. W. from Savannah; from Wafhington S. E. by E. and from Louisville, S. wefterly, 50 miles ; and 934 miles S. W. from Philadelphia.

At the first fettlement of the colony, Gen. Oglethorpe erected a fort here, for protecting the Indian trade, and holding treaties with the natives. In 1739, about 600 people feparated them-felves from the maritime fettlements, and removed to its neighbourhood to carry on a peltry trade with the In-dians. There were, however, but 3 or 4 houses in the town of Augusta in AUR

The country round it has an excellent foil, which with its central fituation, between the upper and lower countries, will bring it fast into importance. N,

lat. 33. 19. W. long. 80. 46. AUGUSTINES, ST. a port and river on the coaft of Labrador, near the ftraits of Bellisse and opposite St. John's Bay, Newfoundland. There are two fmall iflands in the harbour, and about 2 miles S. W. runs a chain of little iflands, called St. Auguffine's Chain; the out-ermoft of which is a remarkable fimooth rock. It is about 25 miles from Great Mecatina I. N. lat. 51. 10. W. long. 58. 50.

AUGUSTINES SQUARE, ST. a number of finall iflands on the coaft of Labrador, in the gulf of St. Lawrence, the largest of which are from Shecatica Bayon the N. E. to Outer I. S. W. viz. Large, Sandy, and Outer islands. Thefe are near the mouth of the St. Lawrence.

AUGUSTINE ST. the capital of E. Florida, is fituated on the fea-coaft, about 80 leagues from the mouth of the gulf of Florida, 180 miles E. from St. Mark's, and 316 S.W. from Charlefton in S. Carolina. It is of an oblong figure, and interfected by 4 streets, which cut each other at right angles. The town is well fortified, has been under different masters, and now belongs to the Spanish king. It has a church and monastery of the order of its name. The breakers at the entrance of the harbour, have formed two channels, whofe bars have 8 feet of water cach. N. lat. 30. W. long. 81. 30.

AUGUSTINE, CAPE ST. on the coaft of Brazil, on the Atlantic Ocean, 300 miles N. E. from the bay of all Souls.

lat. 8. 30. S. long 35. 40. W. AURBAN Academy, a respectable fe-minary of learning in Amherit, New-Hampfhire, which fee.

AURELIUS, a military township in New-York, in Onondago co. on Owafco L. having the Cayuaga Refervation Lands W. and Marcellus E. and 9 miles E. of the ferry on Cayuaga L. By the flate centos of 1796, 213 of the inhabitants are electors. See Military Town/bips.

AURORA, an island belonging to the Archipelago of the Great Cyclades, 15. 8. S. lat. and 165. 58. E. long. from Paris, difcovered by Bougainville, 1780, and in 1787 it contained 200. May 22d, 1768. It is about 20 leagues

long and two h is steep, and co AVALON, corner of the which is joine row neck of] Bay on the S. N. The E. p encompassed b has, befides th bay of Concep bay of St. Mar the S. It co harbours, bays are St. Mary's Francis, &c. AVANCY,

the bishop of C N. E. of that gar canes, fruit AVERIL, a Vermont, form It joins Hamilt on the N. E. a Canada line.

AVES, or Bi Indies, fituated long. 63. 15.1 number of bird is without a tr to lay their egg runs from hence St. Eustatius, which is about from to to 20 fa There is ano

among the Littl coaft of St. Ja Firma, and the AVINO LA western part of

in North-Ameri head branches o Avon, a rive empties into the

eaftward of Hall far as fort Edw tons, and for vel higher. A rive into the Avon, and fprings, abo trance, where it on the road leading navigable for vet

and for large bos AxAs, a town New Albion, in 114. 30. See 5 AYENNIS, an

excellent fituation. countries, ance. N.

and river the ftraits hn's Bay, two finall about 2 tle iflands, the outw. long.

r. a numcoaft of Lawrence, Shecatica .W.viz. s. Thefe Lawrence. ital of E. fea-coaft. mouth of s E. from n Charlefan oblong 4 Itreets, ht angles. has been now be-It has a order of e entrance wo chanof water 81. 30. n the coaft cean, 300 all Souls,

Stable ferft, New-

wnship in on Owalco efervation E. and 9 yuaga L. e Military

ing to the Cyclades, . E. long. gainville, o leagues long

AYE long and two broad. Its eaftern fhore is fleep, and covered with wood.

AVALON, a peninfula at the S. E. corner of the ifland of Newfoundland, which is joined to the island by a narrow neck of land, that has Placentia Bay on the S. and Trinity Bay on the N. The E. part of this peninfula is encompafied by the Great Bank, and has, befides the two former bays, the bay of Conception on the N. and the bay of St. Mary and Trepaffy bay on the S. It contains feveral excellent harbours, bays and capes, among which are St. Mary's, Pine, Race, Ballard, St. Francis, &c.

AVANCY, a jurifdiction fubject to the bishop of Cuico, and lies 4 leagues N. E. of that city. It abounds in fu-gar canes, fruits and corn.

AVERIL, a township in Effex county, Vermont, formerly in that of Orange, It joins Hamilton on the N. W. Canaan on the N. E. and its N. corner is the Canada line.

AVES, or Bird's Island, in the West-Indies, fituated in N. lat. 1 c. 20. W. long. 63. 15. named fo from the great number of birds that breed there, yet is without a tree, which obliges them to lay their eggs in the fand. A fhoal runs from hence to the ifland of Saba, St. Euftatius, and St. Chriftopher's ; which is about 2 leagues broad, and from 10 to 20 fathom foundings.

There is another island of this name among the Little Antilles, between the coaft of St. Jago de Leon, in Terra Firma, and the ifland of Bonaire.

AVINO LA PANEA, a town in the western part of the kingdom of Leon, in North-America, between two of the head branches of Naffas river.

AVON, a river of Nova-Scotia, which empties into the Atlantic Ocean a little eastward of Halifax. It is navigable as far as fort Edward for veffels of 400 tons, and for veffels of 60 tons 2 miles higher. A river called St. Croix runs into the Avon, whole fource is in lakes and fprings, about 7 miles from its entrance, where it is croffed by a bridge on the road leading to Windfor. It is navigable for veffels of 60 tons 3 miles, and for large boats 7 miles.

AXAS, a town in the interior part of New Albion, in N. lat. 39. 5. W. long. 114. 30. See Quivira.

BAF AYERSTOWN, or Ayrflown, in Bur-

lington co. New- Jerfey, lies on the middle branch of Ancocus Creek, 16 miles from the mouth of the creek in the Delaware, and 13 S. eafterly from Burlington.

AYMARAES, a jurifdiction in the em-pire of Peru; fubject to the bifhop of Cufco, 40 leagues S. W. of that city. It abounds in fugars, cattle, corn, and mines of gold and filver ; which laft are for the most part neglected, as it is but thinly inhabited.

AZUCA, or Azua, a little town in the ifland of St. Domingo, in the W. Indies, on the fouthern fide, at the bottom of a deep bay. Before the French revolution it belonged to the Spaniards.

. B

BAAL's River and Bay, in Weft Greenland, lie between Bear Sound on the S. E. and Delft's Point on the N. W. and opposite the mouth of Hudfon's Strait.

BABAHOYO, a village and cuftom houfe on Guayaquil River, in Peru, being the landing place from the city of Guayaquil. Here the merchandize from Peru and Terra Firma, and their. respective provinces, are landed.

BABOPAS, a town in the interior part, of New Albion, eaftward of the long range of mountains which 'extend northward from the head of the peninfula of California. N. lat. 37. 45. W. long. 114. 25. See Quivira.

BACK River. See Baltimore County.

BEAZA, the chief town of the diffrict of Quixos, in the province of Quito, in Peru, and the refidence of the governor. It was built in 1559 by Don Rameiro d'Avilos. The chief manufacture here is cotton cloth.

BAFFIN's Bay, is the largest and most northern gulf or bay, that has yet been discovered in N. America; and lies between the 70th and 80th degrees of N. lat. It opens into the Atlantic ocean through Baffin's and Davis's straits, between Cape Chidley on the Labrador coaft, and Cape Farewell on that of Weft Greenland ; both of which are in about the 60th degree of N. lat. It abounds with whales; and on the S. W. fide of Davis's ftraits has a com-AYENNIS, an Indian tribe in Florida. | munication with Hudson's Bay, through a clufter

a clufter of iflands. It was discovered [by the navigator whole name it bears, in the year 1662. Some maps fliew a communication with Hudson's Bay, in the 70th degree of N. lat. and in the 70th of W. long.

BAGADUCE Point, a head land within Penobicot Bay, in the District of Maine. BAHAMA Channel. See Gulf of Flo-

rida and Bahama Mands.

BAHAMA Islands, in the W. Indies, called by the Spaniards Lucayos, combrehend under this denomination all the iflands, in general, which are to the N. of Cuba and St. Domingo. The first discovery of the New, World, by Columbus, began October 11, 1792, at Guanahani, or Cats Ifland, one of the Bahamas. They were then full of people; who were fimple, mild, and lived happy in the midft of plenty. These unfortunate people were transported to the mines of St. Domingo, after the crucl Spaniards had exterminated the numerous inhabitants of that large ifland ; 14 years after the discovery of these islands, not one perfon remained in any of the Bahamas. At this time Charles II. granted the Bahamas to the proprietors of Carolina. They fent feveral governors, and built the town of Naffau, which is now the feat of government in the I. of Providence. The ifland of Providence afterwards became an harbour for pirates, who, for a long time, infefted the American navigation. In 1718, Capt. Woods Rogers was fent out to diflodge the This pirates, and form a fettlement. the captain effected; and the iflands have been improving fince by a flow progrefs. In time of war the people gain confiderably by the prizes con-demned there; and in the course of the pr-fent war between Great Britain and France, numbers of American velfels, carrying provisions and flores to French ports, have been carried in and condemned; and at all times they profit by the wrecks which are frequent in this labyrinth of rocks and fhoals. The Spaniards and Americans captured these islands during the last war; but they were retaken April 7, 1783. The Bahamas are faid to be 500 in number ; fome of them only rocks, others very low and narrow, or little fpots of land on a level with the water's edge; but az of them are large and fertile, fome It formerly produced great quantities

indeed rocky and barren. Five of them only are inhabited, viz. Providence, Harbour, Eluthera, Cat, and Exuma; Turk's islands have about 500 men in the falt feafon, but at other times half of them return to Bermuda.

The principal island which has given its name to the whole clufter is Great Babama, in the Northern Bank, called the Little Bank of Babama, who fe fituation is E. and W. about 20 leagues from the coaft of Florida. At a little diffance to the E. is I.ucayoneque, of nearly the fame fize, whole fituation is N. and S. To the N. of both is Lucayo, which lies E. and W. A channel of 8 or 10 leagues feparates the Little Bank from the Great Bank, in which is Providence I, with the great island of Alabaster, which has Harbour I. on the N. Cape. Andros iflands are on the S. W. of Providence, which take up a fpace of 30 leagues long and 5 broad. Towards the S. E. are Stocking, Exuma, and Yuma, or Long Ifland. Guanahani, or Cats I. the first discovered in America, lies E. of the Great Bank, and is feparated from it by Exuma Sound.

The climate of these islands is temperate and the air healthy. On the coaft is found ambergrife; and the inhabitants catch great quantities of green turtle. The only article cultivated for exportation is cotton; of which the medium export is 1,500 bags of 2 cwt. each. In 1787, there were 4,500 acres in cotton. In 1785, 1786, and 1787, which were favourable years, each acre produced about 112lbs. It is very lia-ble to be deftroyed by the worms; between Sept. and March, 1788, no lefs than 280 tons were deftroyed. Thefe iflands also produce a great quantity of dying woods, and some lignumvite and mahogany; and lie between 12. and 27. N. lat. and 73. and 81. W. long. In 1773, there were 2052 white, and 2241 black, inhabitants; but of late years there has been a confiderable emigration from North America, fo that the precife number cannot be given.

BAHAMA, the chief of the Bahama islands, is about 20 leagues from the coaft of Florida, and about 10 W. from the island of Lucayo. It is about 28 leagues long and 3 broad, is very fruitful, has a ferene air, and is watered with multitudes of fprings and brooks of faffafras, fa which were all iards. Its chi ton, Indian whe lar kind of rabl of other provifu Their chief co nishing with p are driven in he is fituated on Little Babama northward 601 Babama, or Gi tween the coal ifland. The ! Havannah hom wait an opport and the strait is 45 long.

BAHIA, or] to St. Salvador and to the Bay captainship it is BAHIA DE C

British Hanover of the peninfula Honduras, and R. It has the the S. At its iflands and a r largeft ifland is . runs along the i

70 miles long. BAIRDSTOW Nelfon co. Kei town, of 216 i the head waters S. E. from Lo fame diftance S. BAKERSFIE1 thip in Franklin in Chittenden c 13 inhabitants. BAKERSTON Diffrict of Main tants ; 162 mile

BALCDUTH/ eafternmost part W. fide of Big Clay Lick, and Vancouver's Fo formed by the f BALD EAGLI lie about 200 m

in Bedford co. 1 the western bo Valley. Bald Eagle is

river which run

ive of them Providence, d Exuma; oo men in times half

i has given r is Great ank, called rh fe fituazo leagues. At a little voneque, of lituation is oth is Lu-A channel the Little in which it ifland of I. on the re on the take up a 5 broad. g, Exuma, uanabani, in Ameik, and is bound. s is tem-On the d the ins of green ivated for which the s of 2 cwt. 500 acres nd 1787, each acre very liaworms ; 1788, no I. Thefe antity of numvitæ ween 22. 81. W. 52 white, ; but of inderable 1, fo that given. Bahama from the W. from about 28 ry fruitwatered brooks: uantities

of

BAL

of faffafras, farfaparilla and redwood, which were all deftroyed by the Spaniards. Its chief produce, now, is cotton, Indian wheat, fowls, and a particular kind of rabbits: they have fupplies of other provisions from the continent. Their chief commerce confifts in furnifhing with provisions, fuch thips as are driven in here by bad weather. It is figuated on the fand bank, called Little Babama Bank, which extends northward 60 miles. The Straits of Babama, or Gulf of Florida, lies between the coaft of Florida and this island. The Spanish ships from the Havannah homeward, are obliged to wait an opportunity to pais this firait; and the strait is 16 leagues broad, and 45 long.

BAHIA, or Bay, fometimes applied to St. Salvadore, the capital of Brazil, and to the Bay of All-Saints, in which captainship it is fituated.

BAHIA DE CHETUMEL, called by the British Hanover Bay, lies on the E. fide of the peninfula of Yucatan in the fea of Honduras, and into which falls Honde R. It has the Logwood Country on the S. At its mouth are two large islands and a number of islots. The largeft ifland is Ambergrife Key, which runs along the mouth of the bay, and is 70 miles long.

BAIRDSTOWN, or Beardforwn, in Nelfon co. Kentucky, is a flourishing town, of 216 inhabitants, fituated on the head waters of Salt river, 50 miles S. E. from Louisville, and nearly the fame diftance S. W. from Danville.

BAKERSFIELD, a newly fettled townthip in Franklin co. Vermont, formerly in Chittenden co. In 1790 it had only 13 inhabitants.

BAKERSTOWN, in Cumberland co. Diffrict of Maine, contains 1276 inhabi tants ; 162 miles N. E. from Boston.

BALCDUTHA, a fettlement in the easternmost part of Kentucky, on the W. fide of Big Sandy R. Near this is Clay Lick, and about a mile S. E. ftands Vancouver's Fort, on the point of land formed by the fork of the Big Sandy.

BALD EAGLE, or Warrior Mountains, lie about 200 miles W. of Philadelphia, in Bedford co. Pennfylvania, and forms the western boundary of Bald Eagle Valley.

Bald Eagle is likewife the name of a

and falls into the W. branch of Sufquehanna R. The head water of Huron R. which falls into Lake Erie, is called Bald Eagle Creek.

BALD EAGLE VALLEY, or, as it is commonly called, Sinking Spring Valley, lies upon the frontiers of Bedford co. in Pennfylvania, about 200 miles W. from Philadelphia. It has on the E. a chain of high, rugged mountains, called the Canoe Ridge, and on the W. the Bald Eagle, or Warrior Mts. This is a pleafant vale of limeftone bottom, 5 miles in extent where wideft; and in the vicinity are great quantities of lead ore. It contained, in 1779, about 60 or 70 families, living in log-houses, who formed, in the space of 7 or 8 years, feveral valuable plantations, fome of which are remarkably agreeable on account of their fituation.

During the late war with Great Bri-tain, lead was much wanted, and very difficult to be procured, which induced a company, under the promifes of the ftate, to fettle here; and eftablish a regular let of works. A fort of logs was erected for the protection of the miners ; and a confiderable quantity of ore was produced, from which lead enough was made, to give a competent idea of the real value of the mines in general. The danger of the fituation, however, while an Indian war continued, occafioned the failure of the undertaking. The lead ore was of many kinds;

fome in broad flakes, and others of the fteely texture. Several regular fhafts were funk to a confiderable depth; one of which was on the hill, upon which the fort was erected, and from which many large maffes of ore were procured; but, not forming a regular vein, it was difcontinued, and another opened about a mile from the fort, nearer to Frank's Town. Here the miners continued until they finally relinquished the bufinefs. When they first began, they found in the upper furface or vegetable earth, feveral hundred weight of cubic lead ore, clean and unmixed with any fubstance whatever, which continued as a clue, leading them down thro' the different ftrata of earth, marl, &c. until they came to the rock, which is here in general of the limeftone kind.

Among other curiofities of this place, is that called the S-wallows, which abriver which runs a N. E. course 44 miles | forb feveral of the largest fircams of the valley

valley, and after conveying them feveral miles under ground, in a fubterraneous courfe, return them again upon the fur face. These subterraneous passages have given rife to the name, Sinking Spring Valley. Of these the most re-markable is called the Arch Springs, and run close upon the road from the town to the fort. It is a deep hollow, formed in the limeftone rock, about 30 feet wide, with a rude natural stone arch hanging over it, forming a paffige for the water, which it throws out with some degree of violence, and in fuch enty as to form a fine ftream, which at length buries itfelf again in the bowels of the earth. Some of these pits are near 300 feet deep; the water at the bottom feems in rapid motion ; and is apparently as black as ink ; though it is as pure as the fineft fprings can produce. Many of these pits are placed along the course of this subteraneous river, which foon after takes an opportunity of an opening at a declivity of the ground, and keeps along the furface among the rocky hills for a few rods, then enters the mouth of a large cave, whole exterior aperture would be fufficient to admit a shallop with her fails full ip tad. In the infide it keeps from 18 to 20 feet wide. The roof declines as you advance, and a ledge of loofe, rugged rocks, keeps in tolerable order, on one fiele, affording means to fcramhle along. In the midft of this cave is much timber, bodies of trees, branches, &c. which being lodged up to the roof of this paffage, fnews that the water is fwelled up to the very top during frefhets. This opening in the hill continues about 400 yards, when the cave widens, after you have got round a fudden turning (which prevents its being dif. covered till you are within it) into a fpacious room, at the bottom of which is a vortex, the water that falls into it whirling round with amazing force; flicks, or even pieces of timber, are immediately abforbed, and carried out of fight, the water boiling up with ex-ceffive violence, which fublides by degrees, until the experiment is renewed.

From the top of the Bald Eagle. Mountains is a fine prospect of those of the Alleghany, firetching along until they feem to meet the clouds. Much flate is found here, with firong figns of pit coal. Such as wish these parts muft

crofs the Juniata river 3 or 4 times, from Standing Stone or Huntingdon, to the fort; from which it is computed to be about 22 miles diftance.

BALD Mountains. See Teneffee.

BALD HEAD, at the mouth of Cape Fear River, N. Carolina, is at the S. W. end of Smith's I. and with Oak I. forms the main entrance into the river. The light-house, which was erected here in Dec. 1794, bears miles N. N. W. from the point of Cape Fear, and 24 miles N. W. by N. from the extremity of the Frying Pan shoal.

BALD HEAD, makes the S. We part of what is called Wells Bay, in the Diftrict of Maine. Between Cape Neddick harbour on the S. S. W. and Wells Bay are feveral coves, where finall veffels in a fmooth time, and with a wefterly wind, haul afhore, and are loaded with wood in the courfe of a tide, with eafe and fafety.

BALDIVIA, or Valdivia, a feaport town in the province of Chili Proper, in the kingdom of Chili, S. America. It was built by the Spanish general Baldivia about the year 1551, and stands between the rivers Callacalles and Portero, where they fall into the S. Sea. In the year 1559, the Chilefe chafed the Spaniards from this fettlement, burned the town, and put the inhabitants to the fword ; pouring melted gold down the governor's throat when alive, and afterwards ufed' his skull for a cup to drink in. There are many gold mines here, and the Spaniards have fortified the place ftrongly, as it is supposed to be the key of the S. Seas. The whites of Peru and Chili, banifhed for their crimes, are fent hither to support the fortifications. The Dutch made themselves masters of it in 1643; but were forced to abandon it, leaving all their cannon, 30 or 40 pieces, baggage and ftores; on advice that fuccours were arriving to oppole them from Peru. The viceroy fends. 30,000 crowns a year to support the garrifon. There are great rains here during 3 months of the year. S. lat. 32. 38. W. long. 73. 20.

Baldivia is also the name of a river in Chili.

BALIZE, a fort at the mouth of Miffilippi River.

BALLEZE, Ballize, or Wallis, a river in the peninfula of Yucatan, New-Spain, which runs N. cafterly above

200 miles, and Honduras, opp neff Island. B 1783, it is agi fhall have the r rying away log ing between thi Honde, on the] over Bay. Th to be the unalte BALLTOWN, co. New-York, and contained tants, including cenfus in 179 266 electors in 36 miles N. of terian meeting-1 ing state.

The medicina Springs, from t the limits of thi lebrity, hoth on ing virtue, and dation found nea rians. They a miles W. of Stil part of the bank for the victory of Burgoyne; 36 h Lake George, an New-York. T the bottom of a forming a kind o acres in extent. lofty pines, whi others, and rife a tance above the The woods are] the fprings, Th entertainment, wi and shower baths invalids. Thefe part of the valle nent merchant largeft fpring, ho public. Sir Will observation, when land to private inc the hiftory of the I could only lear difcovered them t in the early par the English. Bu thefe very fprings at 10 miles diftan Saratoga Springs, foil for half a de place, is poor a

25

4 times, ngdon, to mputed to

neffee. n of Cape the S. W. c I. forms er. The ed here in N. W. , and 24 extremity

We part n the Dife Neddick nd Wells mall vefth a wefture loaded ide, with

a feaport i Proper, nerica. It I Baldivia s between ro, where the year Spaniards town,and rd; pourovernor's rards used . There and the he place be the key of Peru rimes, are ifications. nafters of) abandon 30 or 40 on advice to oppole roy fends pport the ains here . S. lat. a river in h of Mifullis, a rian, New-

rly above

200

BAL

soo miles, and empties into the bay of Honduras, opposite the N. end of Turneff Illand. By the treaty of peace in 1783, it is agreed that British subjects shall have the right of cutting and carrying away logwood in the district lying between this river and that of Rio Honde, on the N. which falls into Hanover Bay. The course of the rivers are to be the unalterable boundaries.

BALLTOWN, a township in Saratoga co. New-York, formerly in Albany co. and contained in 1790, 7333 inhabitants, including 69 flaves. By the flate census in 1796, there appears to be 266 electors in this township. It lies 36 miles N. of Albany, has a Presbyterian meeting-house, and is in a thriving flate.

The medicinal waters called Balltown Springs, from their being found within the limits of this town, are of great celebrity, hoth on account of their healing virtue, and the fuperior accommodation found near them for valetudinarians. They are fituated about 12 miles W. of Still Water; 14 from that part of the banks of the Hudfon famous for the victory of Gen. Gates over Gen. Burgoyne; 36 N. of Albany; 30 S. of Lake George, and 196 above the city of New-York. The fprings are found in the bottom of a valley, or excavation, forming a kind of balon, of about fifty acres in extent. In this hollow grow lofty pines, which are overtopped by others, and rife at a greater or lefs diftance above the brim of this bafon. The woods are pretty well cleared near the fprings, There is a large house for entertainment, with neat bathing houfes, and shower baths for the convenience of invalids. Thefe, as also the greatest part of the valley, belong to an emi-nent merchant of New-York; the largeft fpring, however, belongs to the public. Sir William Johnson made this observation, when he fold this tract of land to private individuals : " In tracing the hiftory of these medicinal fprings, I could only learn that an Indian chief difcovered them to a fick French officer in the early part of their wars with the English. But whether they were these very springs in this bason, or those at 10 miles distance, properly called the Saratoga Springs, I know not." The foil for half a dozen miles round this place, is poor and fandy, producing

little elfe than pine trees, fhrub-oaks. fern, and mullen. In the hills in th vicinity, ores have been accidentally found, efpecially iron and copper, or rather what the mineralogists call ferruginous and capreous pyrites. The valley of Balltown and its environs may be made an enchanting fpot, equal, nay, fuperior in fome refpects, to any of the watering places in Europe. The Kayaderafforas river, which is about 10 yards wide, gives feveral hints to the man of tafte, to turn its waters to the use and beauty of the future town, which thefe medicinal fprings will one day raife in this place.

The medicinal waters which have made this fpot fo famous of late, are remarkably limpid, confidering they contain iron, a mineral alkali, common falt, and lime. They are brifk and foarkling like champaigne. In drinking they affect the nofe and palate like bottled beer, and flightly affect the head of fome people, by their inebri-ating quality. They derive this exhilerating quality from what Dr. Prieftly calls fixed air, and is that animating fomething which gives activity to yeaft, and life to malt liquors. It is used in the neighbourhood of the fprings inftead of yeaft in making bread; and makes it rife more speedily and effectually than any other ferment in ordinary ufe. Horfes drink thefe waters with avidity. The ignorant country people fee, with aftonifhment, that a candle will not burn near the furface of thefe waters. Fifh and frogs are killed in a few minutes, and geefe and ducks can only fwim in them a few Thefe minutes, before they expire. waters are apt to burft bottles, when corked in very warm weather, especially during a thunder ftorm; but with care may be transported in bottles to any diffance. They boil with a very moderate degree of heat; they are neverthele's, remarkably cold; for when the mercury in Fahrenheit's thermometer flood at \$6. in the open air, and 79. in the brook running near the fpring, it flood in one of these mineral fprings at 49. and in the other at 51. The first was constantly excluded from the rays of the fun; the last always expoled without a covering.

Phyficians feldom direct their patients to drink more than three quarts

of

of these waters in twelve hours; but | fome drink the enormous quantity of three gallons, and even more, in a day. Cold as they are, they may be drunken with fafety in the hotteft weather. They increase every natural evacuation ; nay, they are cathartic, diuretic, and fudorific, at the fame time. On the first trial they are apt to difagree with many people, they create uneafinefs in the ftomach and bowels, and caufe a heat in the glands of the throat, until they begin to pais off freely by the kidneys. They then become pleafant and operate agreeably. They blacken the teeth and also the alvine fæces. They are deemed a fpecific in lofs of appetite and indigeftion. They are highly ferviceable in hypochondriac cafes, in obftructions, and in the ftone and gravel, and cutaneous diforders. Their credit is not fo well established in the gout or rheumatifm. They are hurtful in inflammatory diforders and confumptions. Their use occasions heat in the glands of the throat, and ftiffnels of the neck, and in fuch as are fubject to the toothache, an aggravation of the pain. They are a powerful and precious remedy in the hands of the judicious, but ought never to be used without the advice of a skilfal physician.

BALLSTOWN, or Balltorun, a townthip in Lincoln co. District of Maine, containing 1072 inhabitants; 195 miles N. E. from Bolton.

BALTIMORE Co. in Maryland, lies between Patapico and Gunpowder rivers, the former dividing it from Ann Arundel co. on the S. and S. W. Gunpowder and Little Gunpowder feparating it from Harford co. on the E. and N. E. It has Frederick co. on the W. and N. W. Pennfylvania on the N. and Chefapeak Bay on the S. E. Befides the rivers which bound it, and their branches, this county has Back and Middle rivers, between the two former, but they are rather arms of Cheiapeak bay, than rivers. Back R. 4 or 5 miles E. of Patapico, receives two fmall ftreams; the N. wefternmoft is called Herring Run. Middle R. has little or no supply of fresh water. There are numerous iron works in this county; and it contains 25,434 inhabitants, including 5,877 flayes. Its chief town is Baltimore.

above county, is the largeft in the flate of Maryland. In fize it is the fourth, and in commerce the fifth in rank in the United States. It is fituated on the N. fide of Patapico R. at a fmall diffance from its junction with the Chefapeak. The entrance of the harbour is defended by Whetstone Fort; hardly a pistol thot acrofs, and of courfe may eafily be defended against naval force. From the head of Elk R. at the head of the bay to Baltimore, is about 60 miles. The town is built around what is called the balon, reckoned one of the fineft harbours in America. The water rifes 5 or 6 feet at common tides. It is divided into what is called the town and Fell's Point, by a creek ; over which are two bridges: but the houfes extend in an irregular manner, from the one to the other. At Fell's Point the water is deep enough for thips of burden, but fmall veffels only go up to the town.

The fituation is low, and was formerly thought unhealthy, but, by its rapid increase, improvements have taken place, which have corrected the dampness of the air, and it is now judged to be tolerably healthy. In 1787, it contained 1955 dwelling houses; of which 1200 were in the town, and the reft at Fell's Point. It then contained 152 ftores. The number of the inhabitants of the town and precincts, in 1791, were 13,503, including 1,255 flaves. The number of houses and inhabitants have been greatly increased fince.

Before the emigration of the French people from Cape François, and other iflands, the houfes had increased to 2,300. Those unfortunate people, flying from their mercilefs countrymen, who had burned and pillaged their cities and towns, and murdered their relations and friends, found here an hospitable asylum, after sufferings hardly paralleled in the annals of hiftory.

Here are 9 places of public worthip, which belong to Roman Catholics, German Calvinifts and Lutherans, Epifcopalians, Prefbyterians, Baptifts, Methodifts, Quakers, and Nicolites, or New Quakers, who all live together in peace. It is inhabited by people from molt parts of Europe. The principal freet is Market Street, which runs nearly E. and W. a mile in length, parallel with BALTIMORE, the chief town in the the water. This is croffed by a number

ber of other ft the water; a nu larly Calvert an built. N. and rifes, and prei the town and ba owned 27 flips, 34 schooners, an tonnage 13,564 fame year amou the imports to 1 exports in July, 1790, amounted lars; but in thef amounted to 1, affairs of the to board of town of of fpecial comm of wardens; the vacancies, and last are appoint every 5th year 53 miles S. W. E. from Richmo E. from the cit 103 S. W. from 39. 21. W. long

BANGOR, a to Diffrict of Main of Penoblcot R mouth at Belfaf W. from Machia lowell, and 280 1

BANKS, Port, W: coaft of Ame Cape Edgecombe Sea Otter Sound. BANN, a town

fylvania. BARACOA, a E. part of the i W. Indies; 50 m de Cuba. N. lat.

BRANCO DE N the province of a Firma, S. Ameri great trade, and Magdalen, 75 mi and is a bifhop's harbour. N. lat. 1

BARAQUICIMI Firma, S. Ameri Caracas, and in Oroonoco R. abo Valencia, and 175 za. N. lat. 8. 5 BARBADOES, illands, belonging

to Jamaica for in

30

in the flate the fourth, rank in the ed on the all diffance Chefapeak. is defended ly a piftol iy eafily be From the of the bay iles. The i called the fineft harrrifes 5 or is divided and Fell's ch are two tend in an one to the e water is arden, but e town. I was forut, by its ents have rected the now judg-In 1787, houfes; of 1, and the 1 contained the inhaecincts, in ling 1,255 fes and inr increased he French and other icreafed to

people, flyuntrymen, iged their lered their d here an ings hardhiftory. ic worfhip, olics, Gers, Epifcofts, Methes, or New r in peace. from moft cipal ftreet s nearly E. raflel with by a number

ber of other ftreets, which run from | Indies. It is about 21 miles in length the water; a number of which, particularly Calvert and Gay ftreets, are well built. N. and E. of the town the land rifes, and prefents a noble view of the town and bay. In 1790, this city owned 27 fhips, 1 fnow, 31 brigantines, 34 fchooners, and 9 floops-Total 102; tonnage 13,564. The exports in the fame year amounted to 2,027,770, and the imports to 1,949,899 dollars. The exports in July, August, and Sept. in 1790, amounted only to 343,584 dollars; but in these months in 1795, they amounted to 1,675,748 dollars. The affairs of the town are managed by a board of town commissioners, a board of fpecial commiffioners, and a board of wardens; the first board fills its own vacancies, and is perpetual; the two laft are appointed by electors, chofen every 5th year by the citizens. It is 53 miles S. W. from Elktown, 176 N. E, from Richmond in Virginia; 50 N. E. from the city of Washington, and 103 S. W. from Philadelphia. N. lat. 39. 21. W. long. 77. 48. BANGOR, a township in Hancock co.

BAR

Diftrict of Maine, on the western fide of Penoblcot R. 25 miles from its mouth at Belfaft Bay; 65 N. W. by W. from Machias; 63 N.E. from Hallowell, and 280 N. E. from Bofton.

BANKS, Port, a harbour on the N. W. coaft of America, S. eafterly from Cape Edgecombe, and N. wefterly from Sea Otter Sound.

BANN, a township in York co. Pennfylvania.

BARACOA, a feaport town in the N. E. part of the island of Cuba, in the W. Indies; 50 miles N. E. of St. Jago de Cuba. N. lat. 21. W. long. 76.10.

BRANCO DE MALAMBO, a town in the province of St. Martha, in Terra Firma, S. America. It is a place of great trade, and feated on the river Magdalen, 75 miles N. of Carthagena, and is a bifhop's fee. It has a good harbour. N. lat. 11. 40. W. long. 75.30.

BARAQUICIMITO, a town in Terra Firma, S. America, in the province of Caracas, and in the head waters of Oroonoco R. about 80 miles S. from Valencia, and 175 N. W. from Calabeza. N. lat. 8. 55. W. long. 66. 55.

BARBADOES, one of the Caribbee illands, belonging to Britain, and next to Jamaica for importance in the W. from High Point, its northern extremity, to South Point; and 14 in breadth, from the Chair near Kitridge Bay E. to Valiant Royalist Fort, W. and contains 106,470 acres of land, most of which is under cultivation. It lies 20 leagues E. from St. Vincent, which may be feen in a clear day; 25 from St. Lucia; 28 S. E. from Martinico; 60 N. E. from Trinidad, and 100 S. E. from St. Christopher's. It is divided into 5 districts, and 11 parishes; and contains 4 towns, viz. Bridgetown, the capital; Oftins, or Charlestown; St. James, formerly called the Hole; and Speight's Town. The names of the parifhes are St. Lucy's, St. Peter's, St. James's, St. Andrew's, St. Thomas's, St. Joseph's, St. John's, St. George's, St. Michael's, St. Philip's, and Chrift Church.

Its foil must be allowed to be highly fertile, if it be true, that it contained in 1670, 50,000 whites, and 100,000 blacks; whole labours employed 60,000 tons of shipping. This is thought to be exaggerated; but it is certain that its population has decreafed rapidly. In 1786 the numbers were 16,167 whites; 838 free people of colour, and 62,115 negroes. The exports, on an average, of 1784, 1785, and 1786, had fallen to 9,554 hhds. of fugar; 5448 puncheons of rum; 6320 bags of ginger; 8331 bags of cotton, exclusive of fmall articles, as aloes, fweet meats, &c. In the year ending the 5th of January, 1788, 243 veffels cleared outwards; and the London market price of their cargoes in fter. money, amounted to 6.539,605 14 10; of which the value exported to the United States, was 6.23,217 13 4. That the dreadful fucceffion of hurricanes, with which this, and the other W. India iflands have been vifited, for many years paft, has contributed to this great defalcation, cannot be doubted. Bridgetown was fcarcely rifen from the affres to which two dreadful fires had reduced it, when it was torn from its foundations, and the whole country made a fcene of defolation, by the ftorm of the 10th of Oct. 1780, in which no lefs than 4326 of the inhabitants, blacks and whites, miferably perifhed; and the damage done to the property was computed at 6.1,320,564 15. fter. The force of the wind

wind was at one place fo great as to lift fome pieces of cannon, with their carriages, feveral paces from the ram-parts. The trade of this and fome others of the iflands, fuffers confiderably by a duty of $4\frac{1}{2}$ per cent. on exported produce; out of which, however, the governor's falary, £.2000 a-year, is paid. The crown acquired this revenue in the reign of Charles II. which the planters agreed to, in order to fecure poffifions to which they had uncertain titles.

Barbadoes was probably difcovered first by the Portuguefe. It is ufually ranked among the Windward division of the Caribbees, being a day or two's fail from Surinam. From its being the first difcovered of any of these islands, it is called Mother of the Sugar Colomes. The first of the English who are known to have landed here, were the crew of the Olive Bloffom, fitted out by Sir Olive Leigh, in 1605. It was found abfolutely defolate; nor had it the appearance of having been peopled even by the most barbarous Indians. The ifland is fortified by nature, all along the windward fhore, by rocks and fhoals, to as to be almost inacceffible; on the leeward fide it has good harbours; but the whole coaft is protected by a good line, of feveral miles in length, and feveral forts to defend it, at the most material places. The military, civil, and religious effablishments are well provided for. Here is a college founded by Col. Codrington ; the only inftitution of the kind in the W. Indies; but it has not answered the intention of the founder. The houses of the planters are very thickly fown all along the country, which, with the luxu-riant productions of the foil, and the gently fwelling hills, form a delightful fcene.

The earlieft planters of Barbadoes were fometimes reproached with the guilt of forcing or decoying into flavery, the Indians of the neighbouring continent. The hiftory of Inkle and Tarico, which the Spectator has recorded for the deteftation of mankind, took its rife in this ifland ; but happily this fpecies of flavery was foon abolifhed. The Barbadoes tar is a particular production of this ifland. It rifes out of the earth, and fwims on the furface of the water. It is of great use in the dry belly-ache, and in difeafes of the breatt.

The capital, Bridgetown, lies in N.

lat. 13. 10. W. long. 59. BARBARA, ST. an ifland on the coaft of Brazil. Alfo the chief town of New-Bifcay, audience of Galicia, New Spain, N. America.

BARBE, ST. a town of Mexico, in New Bifcay, in the vicinity of which are very rich filver mines. It lies 500 miles N. W. of the city of Mexico. N. lat. 26. 10. W. long. 110. 5. BARBUDA, or Barbouthes, one of the

Caribbee iflands, 35 miles N. of An-tigua, and 53 N. E. of St. Christopher's, and is 20 miles long and 12 broad. The natives apply themfelves chiefly to the breeding of cattle, and furnishing the neighbouring iflands with provisions. It is fertile, abounding in the natural productions of the other W. India iflands; and has a good road for fhipping, but no direct trade to Britain. It belongs to the Codrington family, to whom it produces above f. 5000 a. year. The inhabitants amount to about 1 500. N. lat. 18. 30. W. long. 61. 50.

BARBUE, Riviere a la, empties inte Lake Machigan, from E.S. E. between Raifin and Marame rivers. Its mouth, 60 yards wide, lies 72 miles N. by W. from Fort St. Joseph.

Alfo, the name of a river which empties into Lake Erie, from the N. by E. 40 miles W. N. W. from the extremity of Long Point in that lake, and 22 E. by S. from Tonty R.

BARKADARES, the name of a part of the Logwood Country, on the E. fide of the peninfula of Yucaten, thro' which the river Balize runs into the Sea of Honduras. It has Hicks Keys on the S. and South Lagoon on the N. Lat. 17. 45. N. long. 89. W.

BARKHAMSTEAD, a township in the northern part of Connecticut, in Litchfield co. having Hartland on the N. and Granby E. About 25 miles W. of Hartford.

BARNARD, a township in Windsor co. Vermont, containing 673 inhabitants. It has Stockbridge wefterly, and gives rife to the northern branch of Waterqueche R. and is 65 miles N. E. of Bennington.

BARNAVELDT, an island of S. Ame-rica, to the S. of Terra del Fuego, difcovered in 1616, S. lat. 55. 49. W. leng. 66. 58.

BARNEGAT.

BARNEGAT maps, New-Inl the Sea into Flat eastern coast of N. E. from Ca 471 W. long. 7 lies below this In tle Egg Harbour,

BARNEGAT, lage of 8 or 10 h of Hudfon river, keepfie, and 75 fole business of t this place, is be valt quantities of found here. Th N. York, whith quantities annual

BARNET, a 1 co. Vermont, fo containing 477 miles N. E. from lower har of the neclicut R. is fit ner of this town! it fends Stephen Peachum, the adje BARNSTABLE ninfula, the poir Cod, the S. eaft

chufetts Bay, opp Cod lies in N. lat Greenwich 70. 14 the whole peninfu cd by water on all where it is bound It is 65 miles lon from the ifthmus and Buzzard's B and its breadth fo than 3, and above from 6 to 9 miles. faips and the plan having 2343 houfe

itants. Barnstable

1685. See Cape (BARNSTABLE. Mattacheeset of th a port of entry an the fhire town of B tends acrois the per ed by the fea on the Sandwich, and the pee or Mashpee on miles broad, and easterly from Bofto the N. fhore, runs of the town, and for bosoming a large

lies in N.

in the coaft in of New-New Spain,

Mexico, in f which are 500 miles b. N. lat.

one of the N. of Anriftopher's, 12 broad. ves chiefly nd furnifhwith proding in the other W. od road for to Britain. ton family, £.5000 aamount to W. long.

E. between Its mouth, N. by W.

which empe N. by E. t extremity and 22 E.

e of a part on the E. aten, thro' is into the licks Keys i on the N.

the N. and les W. of

n Windfor 73 inhabiefferly, and branch of niles N. E.

of S. Ame-Fuego, difis. 49. W.

ARNEGAT.

BAR

BARNEGAT Inlet, called in fome maps, New-Inlet, is the paffage from the Sea into Flat-Bay-Sound, on the S. eaftern coaft of New-Jerfey, 68 miles N. E. from Cape May. N. lat. 39. 47¹/₂ W. long. 74. 13. Barnegat Beach lies below this Inlet, between it and Little Egg Harbour, 16 miles diftant, S.W.

BARNEGAT, the name of a finall village of 8 or 10 houfes, on the eaft bank of Hudfon river, 5 miles S. of Poughkeepfie, and 75 N. of N. York. The fole bufinefs of the few inhabitants of this place, is burning lime, from the vaft quantities of lime ftone which are found here. Their lime is marketed in N. York, whither they carry it in great quantities annually.

BARNET, a township in Caledonia co. Vermont, formerly in Orange co. containing 477 inhabitants, and 112 miles N. E. from Bennington. The lower har of the 15 mile falls in Connecticut R. is fituated at the N. E. corner of this township. Into that river it fends Stephens R. which rifes in Peachum, the adjoining town on the W.

BARNSTABLE Co. lies upon the peninfula, the point of which is Cape Cod, the S. eaftward point of Maffachufetts Bay, opposite Cape Ann. Cape Cod lies in N. lat. 42. 4. W. long. from Greenwich 70. 14. and gives name to the whole peninfula, which is furrounded by water on all fides, except the W. where it is bounded by Plymouth co. It is 65 miles long, as the road runs, from the ifthmus between Barnstable and Buzzard's Bays to Race Point; and its breadth for 30 miles not more than 3, and above half the remainder from 6 to 9 miles. It contains 11 townships and the plantation of Marshpee; having 2343 houfes, and 17,354 inhabitants. Barnstable was made a shire in 1685. See Cape Cod.

BARNSTABLE, the Mattacheefe, or Mattacheefet of the ancient Indians, is a port of entry and post town, and is the fhire town of Barnstable co. It extends across the peninfula, and is washed by the fea on the N, and S. having Sandwich, and the district called Marshpee or Mashpee on the W. is about 5 miles broad, and 9 long; 67 miles S. easterly from Boston. Sandy Neck, on the N. shore, runs E. almoss the length of the town, and forms the harbour, embosoning a large body of falt marsh. The harbour is about a mile wide, and 4 long; in which the tide rifes from 8 to 14 feet. It has a bar running off N. E. from the Neck feveral miles, which prevents the entrance of large fhips; but fmall vefiels may pafs any part of it at high water; and where it is commonly croffed, it feldom has lefs than 6 or 7 feet at low water.

There is another harbour on the S. called *Lewis's Bay*. Its entrance is within Barniftable, and it extends almost 2 miles into Yarmouth. It is commodious and fafe, and is completely land locked; and has 5 feet water at a middling tide.

A mile or two to the weftward, and near the entrance of Lewis's Bay, lies *Hyanis Road.* It is formed principally by an ifland, joined by a beach to Yarmouth, which together, make the outfide of the bay before mentioned. The S. head of this ifland is called Point Gammon. Oyfter Bay, near the S. W. limit of the town, admits fmall veffels; and which, with Lewis's Bay, has in years paft produced excellent oyfters, in great quantities; though they are now much reduced.

There are about 20 or 30 ponds in Barnstable. The land here produces about 25 hushels of Indian corn to an acre, and rye and other grain in proportion. Wheat and flax are cultivated; the latter with fuccefs. From 12 to 18,000 bufhels of onions are raifed for the fupply of the neighbouring towns. Upwards of 100 men are employed in the fifhery, which is yearly increasing. Whales feldom come into Maffachufetts Bay now, and that fiftery is difcontinued. No quarrels with the ancient natives of the country are recorded in the accounts of this town, where the English settlers of New-England first landed, Nov. 11, 1620. The people, 2610 in number, are generally healthy; and many inftances of longevity are to be met with. Numbers of the farmers are occasionally feamen; and this town has afforded, and continues to furnish many masters of vefiels and mariners who fail from other ports. N. lat. 41. 43.

BARNSTEAD, a township in Strafford co. New-Hampshire, containing 807 inhabitants; 32 miles N. W. of Portsmouth, and 16 E. by S. from Canterbury, on Connecticut R.

BARRE',

BARRE', a townfhip in Worcefter cd. Maffachufetts, containing r613 inhabitants; 24 miles N. W. of Worcefter, and 66 W. of Bolton, deriving its name from Col. Barre, a Britifh fenator, who, on the eve of the late war, plead the caufe of America, in the Britifh houfe of Commons, with great, but unfuccefsful energy. This town has good paftures, and here are fatted multitudes of cattle; and it is fuppofed, more butter and cheefe is carried from hence to the market, annually, than any other town of the fame fize in the flate.

BARRE', a township in Huntingdon co. Pennsylvania.

BARRELL's Sound, on the N. W. Coaft of America, called by the natives Conget-boi-toi, is fituated about 6 leagues from the fouthern extremity of Wafhington, or Charlotte Iflands, in a N. W. direction, about N. lat. 52. W. long. 131. from Greenwich. It has two inlets ; one on the E. the other on the W. fide of the island; the latter is the beft, the other is dangerous. The fhores are of a craggy black rock ; the banks lined with trees of various kinds, as pines, fpruce, hemlock, alder, &c. Mr. Hofkins, in the fummer of 1791, meafured one of these trees, which was ten fathoms in circumference. On one fide of it a hole had been cut, large enough to admit a man; within was a fpacious and convenient room, which had apparently been dug and burnt out with much labour. Mr. Hofkins concluded that it must have been occasionally inhabited by the natives; as he found in it a box, fireworks, dried wood, and feveral domeftic utenfils. This found was named after Joseph Barrell, Eiq. of Charleftown, (Maff.) and was first visited by Capt. Gray, in the Washington, in 1789.

BARREN Creek, rifes in the N. W. corner of Delaware flate, runs about 9 miles S. wefterly, and empties into Nanticoke R. A trangular tract of land in the N. part of Somerfet co. Maryland, is enclosed between this creek on the S. Delaware flate E and Nantitoke R. on the W, and N. W.

BARREN R. Both Big and Little Barren rivers, are S. E. branches of G een R. in Kentucky. Blue Spring lies between thefe rivers, which ice.

BARREN I. a imall ifle in Chefapeak Bay, N. E. from the mouth of Patuxent R. which is feparated from Hooper's I. by a narrow channel on the E.

BARRETSTOWN, a plantation in Hancock co. Diffrict of Maine, having 173 inhabitants.

BARRINGTON, a township, inQueen's co. Nova-Scotia, on the S. fide of the bay of Fundy; fettled by Quakers from Nantucket illand.

BARRINGTON, a township in Strafford co. N. Hampshire, about 22 miles N. W. from Portsmouth, incorporated in 1722, containing 2470 inhabitants. Allum is found here; and the first ridge of the Frost Hills, one of the three inferior fummits of Agamenticus, is continued through this town. Its situation is very healthy; e. g. 14 of the first settlers in 1732, were alive in 1785, who were between 80 and 90 years old.

BARRINGTON, a township in Briftol co. Rhode-Island, on the S. western fide of the N. W. branch of Warren R. little more than 21 miles N. W. of Warren, and about 7 S. E. from Fox Point, in the town of Providence. It contains 683 inhabitants, including 12 slaves.

BARRINGTON, GREAT, is the fecond township in rank in Berkshire co. Massachusetts. It contains 1373 inhabitants, and lies 140 miles W. from Boston, and fouth of Stockbridge, adjoining.

BARROW Harbour, is an extensive bay in that of Bonavista, Newfoundland ifland, divided by Keel's Head on the E. from the port of Bonavista, and from Bloody Bay on the W. by a large peninfula, joined to the island by a narrow ifthmus, which forms Newman's Sound; which, as well as Clode Sound, are within Barrow Harbour.

BART, a port on the fouthern coaft of Nova-Scotia.

BART, a township in Lancaster co. Pennsylvania.

BARTHOLOMEW, ST. a parifh in Charlefton diffrieft, S. Carolina, containing 2,138 white perfons. By the centus of 1790, it contained 12,606 inhabitants, of whom 10,338 were flaves. It fends 3 reprefentatives and 1 fenator to the flate legiflature. Amount of taxes £1,566 105.4d. fterling.

BARTHOLOMEW, CAPE, ST. is the fouthernmost point of Staten Land, in Le Maire straits, at the S. end of S. America; and far suppasses Terra del Fuego in its horrible appearance. BARTHOLOMEW, BARTHOLOI clufter of Ifland which fee.

BARTHOLO Caribbee ifland miles N. of St. E. of Saba. I circumference. for mahuring. caffava, and abo trees most in eff tree, or aloes t 3. The canapia cellent catharti whole boughs root again, and and ftrong defe All along the fh Sea Trees, who plaited togethe were glazed. I of birds, and a ftone, which the the adjacent ifla wife plenty of wood. Its fhor the approaching pilot; but it ha in which thips o from all winds. are Irifh Roman deceffors fettled | are French, to v belonged. It w the crown of Se depend on the they keep in cifb privateers when French ; and at prizes in its harb long. 63. 10.

BARTLET, a rough co. New-I inhabitants.

BARTON, a to Vermont, former lies S. W. of Bry W. by W. fron and 140 N. eafter

BASIN OF MI of confiderable e form, fituated in end of the Bay of ed with its N. E. marrow firait. TJ is generally a ricl by many finall riv rife here 40 feet. BASKINRIDGE

4

BAS

clufter of Iflands, called New Hebrides, which fee.

BARTHOLOMEW, ST. one of the Caribbee islands, in the W. Indies, 25 miles N. of St. Chriftopher's, and 30 N. E. of Saba. It is reckoned 5 leagues in circumference, but has little ground fit for manuring. It produces tobacco, caffava, and abounds with woods. The trees most in efteem are, 1. The foap tree, or aloes tree. 2. The caleback. 3. The canapia, whole gum is an ex-cellent cathartic. 4. The parotane, whole boughs grow downward, take root again, and form a kind of bulwark and ftrong defence in time of attack. All along the fhore are those trees called Sea Trees, whofe boughs are curioufly plaited together, and look as if they were glazed. Here is an infinite variety of birds, and a peculiar kind of lime ftone, which the inhabitants export to the adjacent iflands. They have likewife plenty of lignum vitæ and iron wood. Its fhores are dangerous, and the approaching them requires a good pilot; but it has an excellent harbour, in which thips of any fize are theltered. from all winds. Half its inhabitants are Irifh Roman Catholics, whofe predeceffors fettled here in 1666; the others are French, to whom the island lately belonged. It was ceded by France to the crown of Sweden in 1785. They depend on the fkies for water, which they keep in cifterns. It was a neft for privateers when in the hands of the French; and at one time had 50 British prizes in its harbour. N.lat. 17. 56. W. long. 63. 10.

BARTLET, a plantation in Hillfborough co. New-Hampshire, having 248 inhabitants.

BARTON, a township in Orleans co. Vermont, formerly in that of Orange, lies S. W. of Brownington; 6 miles S. W. by W. from Willoughby Lake, and 140 N. eafterly from Bennington.

BASIN OF MINAS, is a body of water of confiderable extent, and irregular form, fituated in Nova-Scotia, at the E. end of the Bay of Fundy; and connected with its N. E. branch by a fhort and narrow frait, The country on its banks is generally a rich foil, and is watered by many fmall rivers. The fpring tides rife here 40 feet.

BASKINRIDGE, in Somerfet co. New-14.63

BARTHOLOMEW, ST. one of the Jerfey, lies on the W, fide of a N. W. ulter of Islands, called New Hebrides, branch of Paffaie R. nearly 6 miles N. E. from Pluckemin, and 7 S. S. W. from Morriftown. It was here that Col. Harcourt furprifed and made a prifoner of Gen. Lee, Dec. 13, 1776. Bason Harbour, lies on the E. fide of

Lake Champlain, in the township of Ferrifburgh, Vermont, 44 miles S. wef-terly from the mouth of Otter Creek.

BASSE TERRE, the chief town i the island of St. Christopher's, in the W. Indies. fituated at the S. E. end of the I. It confifts of a long freet along the fea fhore ; is a place of confiderable trade, the feat of government, and is defended by 3 batteries. N. lat. 17. 24. W. long. 62. 36. 56.

This is also the name of a part of the I. of Guadaloupe, in the W. Indies between a point of which called Groffe Morne, to that of Antigua in the Grande Terre, the balon called the Great Cal de Sac, is 5 or 6 leagues in length ; wherein is fafe riding for fbips of all rates.

Bass Harbour, Diftrict of Maine, a harbour of Mt. Defert Ifland, 7 miles from Soil Cove.

BASTIMENTOS, fmall iflands, near the Ifthmus of Darien, and fomewhat W. of the Samballoes iflands, at the mouth of the bay of Nombre de Dios, very near the fhore. Here admiral Hofier lay with a British fquadron many years ago, when having loft many of his men, and his thips being almost rotten in an inactive state, he died of a broken heart. Lat. 9. 30. W. long. 79. 45.

BATABANO, a town on the S. fide of the island of Cuba, in the W. Indies ; fituated on the fide of a large bay, oppolite Pinos Ifles, and about 50 miles S. W. from the Havannah.

BATAVIA, a fettlement in N. York, at the head of Schoharie Creek, about 39 miles from its mouth, and 38 S. W. from Albany, and as far N. W. of Elopus.

BATH, a township of Lincoln ca. District of Maine, containing 949 inhabitants. It lies on the W. fide of Kenneheck R. about 13 miles from Wifcaffet, 60 N. E. from Portland, 32 from Hallowell, 13 from Pownalboro', and 165 N. E. from Bofton. N. lat. 43. 49.

35.

BATH, a county of Virginia, about C a 60 miles

inQueen's ide of the akers from p in Straft 22 miles corporated habitants. : first ridge three infe-, is contis fituation he first fetv785, who old. p in Briftol weftern fide Warren R. V. of War-Fox Point, It contains 2 flaves. is the ferkfhire co. 1373 inha-

Hooper's EE.

on in Han-

aving 173

n extensive Newfound-'s Head on avifta, and by a large d by a nar-Newman's lode Sound,

W. from

bridge, ad-

thern coaft

ncaster co.

a parish in dina, cons. By the 12,606 inwere flaves. i i fenator Amount of ng. ST. is the n Land, in end of S. s Terra del ance.

IOLOMEW,

60 miles in length, and 50 in breadth; bounded E. by the county of Augusta. It is noted for its medicinal springs, called the *Hot* and *Warm* springs, near the foot of Jackson's Mountain, which see.

BATH, a thriving town in Berkley co. Virginia, fituated at the foot of the Warm/Spring Mountain. The fprings in the neighbourhood of this town, although lefs efficacious than the Warm Springs in Bath co. draw upwards of 1000 people here, during fummer, from various parts of the United States. The water is little more than milkwarm, and weakly impregnated with minerals. The country in the environs is agreeably diversified with hills and valleys; the foil rich, and in good cultivation; 25 miles from Martinfburg, and 269 miles 8. W. from Philadelphia. BATH, a township in Grafton co. N. Hampshire, containing 493 inhabitants. It lies on the E, bank of Connecticut R. 35 miles N. E. by N. from Dartmouth College, and 97 N. W. from Portfmouth.

BATH, or Port Bath, an ancient town in Hyde co. N. Carolina, on the N. fide of Tar R. about 24 miles from Pamplico Sound, 61 S. by W. of Edenton, and in the port of entry on Tar R. It contains about 12 houfes, and is rather declining. N. lat. 35.31. W.long. 77.15. BATH, a village in the eaftern parifh of St. Thomas, in the I. of Jamaica, in the W. Indies. It has its rife and name from a famous hot fpring in its vicinity, faid to be highly efficacious in curing the dry-belly ache. The water is fulphureous, and flows out of a rocky mountain about a mile diftant ; and is too hot to admit'a hand being held in it. BATH, a village in the co. of Renffalaer, New-York, pleafantly fituated on the east bank of Hudson river, nearly opposite the city of Albany, at the head of floop navigation. A mineral fpring has been difcovered here, faid to poffets valuable qualities; and a commodious bathing-house has been erected, at a confiderable expence, containing hot, cold, and shower baths.

BATH, a thriving post-town in New-York, Steuben co. of about 50 houses, fituated on the N. bank of Conhoston Creek, a northern headwater of Tioga R.; 42 miles S.E. from Williamsburg, on Chenesser R.; 12 N. W. from the

Painted Poft; 120 from Niagara; 59 westerly from Geneva, and 221 W. of Hudson city. N. lat. 42. 15. W. long. 77. 10.

BATTEN Kill, a fmall river which, rifes in Vermont, and after running N. and N. Wefterly about 30 miles, falls into Hudfon, near Saratoga.

BATTLE R. in New South Wales, runs N. E. into Safkahawen R. S. E. from Manchefter Houfe. Its courfe is, thort.

BAULEM's Kill, a weftern water of Hudson R. SI miles below Albahy.

BAXOS DE BABUCA. See Abrojos. BAY OF FRESH WATER, in the N. part of the Gulf of Mexico, lies S. of Afcention Bay. N. lat. 30. W. long. 93.

BAYAMO, a town in the eaftern part of the ifland of Cuba, having the town of Almo W. and St. Barbara on the S. It lies on the E. fide of Effero R. about 20 miles from the fea.

BAYAMO, Channel del, in the ifland of Cuba, runs between the numerous finall iflands and rocks called Jardin de la Reyna, on the N. W. and the fhoals and rocks which line the coaft on the S. E. fide of it, from the hold point called Cabo de Cruz. This channel ieads to the bay of Eftero, which receives two rivers; the fouthernmost of which leads to the town of Bayamo.

BAY OF FUNDY, washes the shores of the British Provinces of New-Brunswick on the N. and Nova-Scotia on the E. and S. This bay is 12 leagues across, from the Gut of Annapolis to St. John's, the principal town of New-Brunswick. The tides are very rapid in this bay, and rife at Annapolis Basin about 30 feet; at the Basin of Minas, which may be termed the N. arm of this bay, 40 feet; and at the head of Chignetto Channel, an arm of this bay, the spring tides rife 60 feet.

BAY DE ROCHE FENDE, lies on the W. fide of Lake Champlain, and in the flate of New-York, 17 miles above Crown Point.

BAY OF ISLANDS, hies on the W. fide of Newfoundland I. in the gulf of St. Lawrence. This bay is very extentive, having 3 arms, by which feveral rivers empty into it. It has feveral iflands; the chief of which are called Harbour, Pearl, and Tweed. The centre of the Bay lies in about 49. 5. N. lat. and 58. 15. W. long. from Greenwich. BAY BAY OF ST. dor coaft, has (and Cape Char many finall iflan is Battle I. in The middle of 52. 23. W. lor BAYNET, a fide of the iflan leagues from Per of the ifland. I of Jackmel. N

BEACH Fork, which rifes in A fine clay is fo might, it is thou into good porcel BEALSBURG,

fon co. Kentuci Rolling Fork, w as alfo a tobacc miles W. S. W W. of Frankfor delphia. N. lat. BEARDSTOW

BEAR Cove, the S. eaftern co I. at the head o ment of Formofe, rocks lie between Water Bay on th from Cape Race

BEAR Grafs C the eaftern fide c dred yards N. of in Kentucky. T the intended cana to the upper fide the mouth of the fide of the rapids This would rend Ohio fafe and ea the fides of this c and Kentucky R See Rapids of the

BEAR LAKE, (part of N. Ameri-Circle, and fends courfe.

BEAR LAKE, Wales, lics in N 1071. It lies N. House.

BEAR LAKE, from another fin Lake, both in N W. long. of the f are faid to give ri BEAR Town,

and

igara; 59 221 W. of . W. long.

ver which unning N. niles, falls

R. S. E. s courfe is

water of Ibany. Abrojos. in the N. lies S. of . long. 93. aftern part the town 1 on the S. p R. about the ifland numerous I Jardin de the fhoals aft on the hold point is channel which reernmolt of yamo. the fhores lew-Brunfotia on the 12 leagues nnapolis to m of New-

very rapid polis Bafin of Minas, urm of this d of Chigis bay, the

lies on the and in the illes above

n the W. he gulf of very extenich feveral are called The cen-. 5. N. lat. Steenwich. BAY BEA

BAY OF ST. LOUIS, on the Labrador coaft, has Cape St. Louis on the N. and Cape Charles on the S. It has many finall iflands; the largeft of which is Battle I. in the mouth of the bay. The middle of the bay lies in N. lat. 52. 23. W. long. 55. 23.

BAYNET, a town and bay on the S. fide of the island of St. Domingo, 41 leagues from Petit Goave, on the N. fide of the island. It is about 8 leagues W. of Jackmel, N. lat. 18. 17.

BEACH Fork, a branch of Salt R. which rifes in Nelfon co. Kentucky. A fine clay is found on this river, which might, it is thought, be manufactured into good porcelain.

BEALSBURG, a fmall town in Nelfon co. Kentucky, on the E. bank of Rolling Fork, which contains 20 houfes, as alfo a tobacco warehoufe. It is 15 miles W. S. W. of Bairdflown, 50 S. W. of Frankfort, and 890 from Philadelphia. N. lat. 37.42. W. long, 85.50. BEARDSTOWN. See Bairdflown.

BEAR Cove, lies on the E. fide of the S. eaftern corner of Newfoundland I. at the head of which is the fettlement of *Formofe*, which fee. Reneau's rocks lie hetween Bear Cove and Frefh Water Bay on the S. 32 miles northerly from Cape Race.

BEAR Grafs Creek, a finall Creek on the eaftern fide of Ohio R. a few hundred yards N. of the town of Louisville, in Kentucky. This is the fpot where the intended canal is proposed to be cut to the upper fide of the *Rapids*. From the mouth of the creek, to the upper fide of the rapids, is not quite z miles. This would render the navigation of the Ohio fafe and eafy. The country on the fides of this creek, between Salt R. and Kentucky R. is beautiful and rich. See *Rapids of the Ohio*.

BEAR LAKE, GREAT, in the N. W. part of N. America, lies near the Arctic Circle, and fends a river a W. S. W. courfe.

BEAR LAKE, BLACK, in New South Wales, lies in N. lat. 537. W. long. 1071. It lies N. W. from Cumberland House.

BEAR LAKE, WHITE, lies due W. from another finall lake called Bear Lake, both in N. lat. 48. 15. and the W. long. of the former is 984. These are faid to give rife to Miffifippi R.

BEAR Town, in Caroline co, Mary-

land, lies about 7 miles N. from Greenfburg, and about 25 S. E. from Cheftertown.

BEAR Creek, a water of Tenneffee river. See Occochappo.

BEAUFORT, a feaport town in Carteret co. on the N. E. fide of Core Sound, and diffrict of Newbern, N. Carolina. It contains about 20 houfes, a courthoufe and gaol, and the county courts are held here. It is 55 miles S. by E. of Newbern, and about 27 from Cape Lookout. N. lat 34. 47.

BEAUFORT, the chief town of Beaufort district, S. Carolina, is fituated on the ifland of Port Royal, at the mouth of Coolawhatchie R. The courts which were formerly held here, are now removed to the town of Coofawhatchie, on the above small river. Beaufort is a little pleafant town, of about 60 houfes, and 200 inhabitants; who are diftinguished for their hospitality and politeness. It has a fine harbour, and bids fair to become a confiderable town. It used to be a ftation for the British squadron when in their poffeffion. Beaufort is fituated 26 miles from Purifburg, and 73 from. Charlefton, to the S. W. noted for its healthy fituation. N. lat. 32. 26. W. long. 80. 55.

BEAUFORT Diffriet, in the lower country of S. Carolina, lies on the fea coaft, between Combahee and Savannah rivers. It is 69 miles in length, and 37 in breadth, and is divided into parifhes, viz. St. Helena, St. Luke, Prince William, and St. Peter, which contain 18,753 inhabitants; of whom only 4346 are whites. The northern part of this diffrict abounds with large forefts of cyprefs; the lands, however, are fit for raifing rice, indigo, &c. It fends 12 reprefentatives and 4 fenators to the ftate legiflature; each parish fending an equal number. Amount of taxes £ 3,022 28. 11d. fter.

BEAVER Creek, runs into Lake Erie, at its E. end ; about 7 miles S. E. from, Fort Erie.

BEAVER CREEK, BIO, falls into the Allegany river, after having received feveral branches from the N. E. about 28 miles N. W. from Pittfburg.—It riles in the S. runs N. about 6 m les, thence N. E. 12 more to the Salt Lick Town; then, pait the Mahoning Town, and Salt Springs, 34 miles S. eafterly to the Kifhkuth Town, from which to its C 3 mouth

mouth is 22 miles foutherly : In all | cenfus of 1796, there appears to be 302 about 74 miles.

BEAVER Dam, a township in Penn-Tylvania, on the W. fide of Sufquehannah R. See Northumberlund co.

BEAVER Kill, is a S.E. arm of the Popachton Branch of the Delaware. Its mouth is 171 miles E. from the Cook Houfe, and 24 N. W. from Kufhichtun Falls.

BEAVER Lake, in New South Wales, lies in about 52. 45. N. lat. and 101.30. W. long. A little N. E. from it is the fource of Churchill R. S. E. from it is Cumberland Houfe, on Grafs R. which has communication by lakes with Nelfon R. S. W. of it is Safkashawen R. on which, towards its head, are a number of houses belonging to the Hudson's Bay Company.

BEAVERS Town, at Tufkarawas, lies between Margaret's Creek, an upper N. W. branch of Muskingum R. and the N. branch of that river ; at the head of which N. branch there is only a mile's portage to Cayahoga R. Beavers Town lies about 85 miles N. W. from Pittsburg. A little below this a fort was crected in 1764.

BECKET, a township in Berkshire co. Maffachufetts, containing 751 inhabit-ants. It is 10 miles E. of Stockbridge, 17 from Lenox, and 130 W. from Bofton.

BEDE Point, is the eaftern cape at the mouth of Cook's R. on the N. W. coaft of N. America.

BEDFORD, a township in Hillsborough co. New-Hampshire, which was incorporated in 1750, and contains 898 inhabitants. It lies on the W. bank of Merrimack R. 56 miles W. of Portfmouth.

BEBFORD, a township in Middlefex co. Maffachusetts, containing 523 inhabitants ; 13 miles northerly from Bofton.

BEDFORD, NEW, is a flourishing town in Briftol co. in the fame ftate, containing 3313 inhabitants; 58 miles fouthward of Bofton. It lies at the head of navigation on Accushnet R. Lat. 40. 41. N. long. 70. 52. W. from Greenwich. BEDFORD, a township in W. Chefter co. New-York, containing 2470 inhabitants, including 38 flaves. It lies contiguous to Connecticut, 12 miles N. from Long-Hand Sound, and 35 from the city of New-York. In the flate

electors.

BEDFORD, a town on the W. end of Long I. New-York, 4 miles N.W. from Jamaica Bay, and 6 E. from the city of New-York.

BEDFORD, a village near the Georgia fide of Savannah river 4 miles above Augusta:

BEDFORD Co. in Pennfylvania, lies on Juniatta R.; has part of the state of Maryland on the S. and Huntingdon co. N. and N. E. It contains 13,124 inhabitants, including 46 flaves; and has 1 of its lands fettled, and is divided into 9 townships.

Its chief town, Bedford, lies on the S. fide of Rayflown branch of the fame river ; 25 miles eaftward of Berlin, and 210 W. of Philadelphia. It is regularly laid out; and the inhabitants who live in 41 log houses and 9 of ftone, have water 'conveyed in wooden pipes to a refervoir in the middle of the town. They have a ftone gaol; the market-house, court-house, and record office, are built of brick. Bedford was incorporated in 1795, and their charter is fimilar to that of Chefter. N. lat. 40. W. long. 78. 50.

BEDFORD Co. in Virginia, is feparated from that of Amherft on the N. by James R.; has Campbell E. Botetourt W. and Franklin co. on the S. It is 34 miles long, 25 broad, and contains 10,531 inhabitants, including 2,754 flaves. It has a good foil and is agreeably diversified with hills and vallies. In fome parts chalk and gypfum have been difcovered. Its chief town is New London.

BEDMINSTER, in Somerfet co. New-Jerfey, is a township containing 1197

inhabitants, including 169 flaves. BEEF Ifland, one of the finaller Virgin iflands, in the W. Indies, fituated between Dog I. on the W. and Tortu-la on the E. It is about 5 miles long and I broad, in Sir Francis Drake's Bay. N. lat. 18. 23. W. long. 63. 2.

BEEKMAN, a confiderable township in Duchels co. New-York, containing 3597 inhabitants, including 106 flaves. In the flate cenfus of 1796, there appears to be 502 electors in this town-

BEHRING's Bay, on the N. W. coaft of N. America, is feparated from 'Admiralty Bay, on the northward, by a point

point of land; Crofs Sound. BEHRING'S from America Ruffian naviga with Thirikos chatka, in Sibe in queft of the ter where it ha approached. land within a f coaft of Ameri difeoveries of (ceffor, Clarke, approximation Cape Prince of terly point of hitherto knowr lat. 65. 46. E. 39 miles diftan Afia.

The fea, fre Straits, to the Afia and Amer deepens from t tifh feas do fro are loft in the does not take p Mes. Between an increase from cept only off St there is a chi From the volu been judged 1 there was a fer at these straits from the ifles t once been dry l the watery eler fire, had, in v verted and ove left the iflands fragments.

The famou fome iflands ftraits, on whi of Ya Zue, or th This gives fon America was 1 nefe; and that ed by Kæmpfe voyages of dif to the laft, act continent, whe the Efquimaux rifon of themfi guifh them by BEKIA, OF

British Island

s to be 302

W. end of N.W. from the city of

the Georgia niles above

Ivania, lies the flate of tingdon co. 13,124 ines; and has divided into

lies on the of the fame Berlin, and t is regularitants who ftone, have ipes to a repown. They inket-houfe, ise, are built oporated in fimilar to . W. long.

a, is feparathe N. by . Botetourt he S. It is nd contains ling 2,754 nd is agreeand vallies. ypfum have own is New

et co. Newining 1197 laves. maller Vires, fituated and Tortumiles long cis Drake's ong. 63, 2. le townfhip containing 106 flaves. , there apthis town-

V. W. coaft from 'Adward, by a point

coint of land; and lies N. W. from Crofs Sound. See Admiralty Bay. BEHRING's Straits, feparate Afia from America; are fo called from the Ruffian navigator, Capt. Behring, who, with Thirikow, failed from Kamptfchatka, in Siberia, on the Afiatic coaft, in queft of the New World, in a quarter where it had, perhaps, never been approached. They both difcovered land within a few degrees of the N. W. coaft of America. But the more recent discoveries of Capt. Cook, and his fucceffor, Clarke, have confirmed the near approximation of the two continents. Cape Prince of Wales is the most wefterly point of the American continent, hitherto known. It is fituated in N. lat. 65. 46. E. long. 191. 45. and is 30 miles diftant from the eaftern coaft of Afia.

BEK

The fea, from the S. of Behring's Straits, to the crefcent of ifles between Afia and America, is very fhallow. It deepens from these straits (as the British feas do from Dover) till foundings are loft in the Pacific Ocean; but that does not take place but to the S. of the files. Between them and the ftraits is an increase from 12 to 54 fathoms, except only off St. Thaddeus Nofs, where there is a channel of greater depth. From the volcanic difpolition, it has been judged probable, not only that there was a feparation of the continents at these straits, but that the whole space from the ifles to that finall opening had once been dry land; and that the fury of the watery element, actuated by that of fire, had, in very remote times, fubverted and overwhelmed the tract, and left the islands to ferve as monumental tragments.

The famous Japanele map places fome iflands feemingly within thefe ftraits, on which is befowed the title of Ya Zue, or the kingdom of the dwarfs. This gives fome reaton to fuppofe that America was not unknown to the Japanefe; and that they had, as is mentioned by Kæmpfer, and Charlevoix, made voyages of difcovery; and, according to the laft, actually wintered upon the continent, where probably meeting with the Efquimaux, they might, in comparifon of themfelves, and juftly, diftinguift them by the name of dwarfs.

BEKIA, or Becouya, or Boquio, a finall British Island among the Granadillas;

55 miles N. E. of Granada, and 65 leagues from Barbadoes. It was called Little Martinico by the French, and has a fafe harbour from all winds; but no frefh water. It is only frequented by thole who catch turtle. The foil produces wild cotton, and plenty of water melons.

BELCHER, a township in Hampshire co. Maffachusetts, containing 1485 inhabitants, who subsist chiefly by farming. It lies 12 miles E. of Hadley, and 85 W. of Boston.

BELEZ, a city of New Grenada, Terra Firma, S. America.

BELFAST, a township and bay in Hancock co. Diffrict of Maine, both fituated in what is called the Waldo Patent, at the mouth of Penobscot R. and on its western fide; 38 miles N. E. by E. from Hallowell, and 246 N. E. from Boston. The town contains 245 inhabitants. The Bay, on the N. western part of which the town flands, runs up into the land by 3 short arms. Islessorough I. lies in the middle of it, and forms two channels leading to the mouth of Penobscot R.

BELGRADE, a township in Lincoln co. District of Maine, incorporated in Feb. 1796. It was formerly called Washington Plantation. It lies W. of Sidney, and between Androscoggin and Kennebeck rivers.

BELHAVEN, the former name of Alexandria, in Fairfax co. Virginia, which fee. It lies 14 miles N. E. of Colchefter, 86 S. W. of Winchefter, 30 W. of Annapolis, and 214 S. W. of Philadelphia.

BELIM, or Para, a town in Brazil. See Para.

BELL Ifle, an Island on the E. fide of the northern part of Newfoundland I. E. of Canada head; between 50. 42. and 50. 50. N. lat. and between W. long. 55. 39. and 55. 46.

BELLAIRE, a post-town near the centre of Harford co. Maryland, and the chief of the county. It contains a courthouse and gaol, and is thinly inhabited; diftant from Harford, 6 miles, N. W.; 22 N. E. from Baltimore, and 86 W. S. W. from Philadelphia.

BELLE I_{le} , an ifland at the mouth of the fraits of this name, between the country of the Efquimaux, or New Britain, and the N. end of Newfoundland I. which fraits leads into the gulf C 4 of

of St. Lawrence from the N. E .--The ifland is about 7 leagues in circumference ; and lies 16 miles from the nearest land on the coast of Labrador, or New Britain. On the N. W. fide it has a harbour for fifting veffels, or finall craft; and on the E. point it has a cove which will admit fhallops. Lat. 51. 55. N. long. 55. 30. W. BELLE Dune, La, or Handfome Down,

a long, projecting, barren point, on the fouthern fide of Chaleur Bay, about 8 leagues N. N. W. of Nipiliguit, where temporary cod and herring fiftheries are carried on by different people; there being no eftablished trader at the place.

BELLGROVE, in Bergen co. N. Jerfey, on the road to Albany, lies within half a mile of the line which feparates New York from New Jerfey, which extends from Delaware R. to that of Hudfon. It is 3 miles northerly from Brabant, and 24 N. by W. from New-York city.

BELLINGHAM, a fmall farming townthip in Norfolk co. Maffachuletts, containing 735 inhabitants, 20 miles northerly from Providence, and 34 foutherly from Bofton.

BELLS Mill, a fettlement in N. Carolina, near the Moravian fettlements, at the fource of Deep R. the N. wefternmost branch of the N. W. branch of Cape Fear, and about 50 miles W. of Hillfborough.

BELFRE, a post-town and finall fettlement in the territory N. W. of the Ohio, on the N. W. bank of Ohio R. between the Hockhocking & Mulkingum Rs. and opposite the month of the Little Kanhaway; about 14 miles below Marietta, and 480 S.W.by W.from Philadel.

BELVIDERE, a new township in Frank-Jin co. Vermont.----Alfo a village in New-Jerfey, in Suffex co. fituated on Delaware R. at the mouth of Pequeft R. and 11 miles above Eafton, in Pennfylvania.

BENEDICT, a town in Charles co. Maryland, on Patuxent R.; opposite Mackall's Ferry; W. from Port Tobacco 16 miles, as the road runs thro' Byrantown ; 30. S. E. from the Federal City, and 20 from Drums Point, at the mouth of the river.

BENNINGTON, a county in the S. W. corner of Vermont, having Windham co. on the E. and the flate of N.

fends Batten Kill and Hoofack rivers. which both rife here, and fall into Hudfon R. 14 miles apart : Rutland co. lies on the N. and the flate of Maffachufetts on the S. It contains 19 townships, of which Bennington and Manchester are the chief. It has 12,154 inhabitants, including 16 flaves. The mountains here furnish iron ore in abundance, and employ already, a furnace and two

forges. BENNINGTON, the fhire town of the above county, and the largest town in the ftate of Vermont, having about 160 houses, in the compact part of the town, is fituated at the foot of the Great Mountain, near the S. W. corner of the flate, 24 miles eafterly from the junction of Hudson and Mohawk rivers, and about 52 from the S. end of Lake Champlain, at the confluence of the E. and S. bays; and lies 55 miles from Rutland; 202 miles N. eafterly from New-York; and 300 in the fame direction from Philadelphia. N. lat. 42. 42. W. long. 74. 10. Bennington has feveral elegant buildings. Its public edifices are a congregational church, state house and gaol. It is the oldest town in the ftate, having been first fettled in 1764, and is in a flourishing condition, containing 2,400 inhabitants. Within the township is mount Anthony, which rifes very high in a conical form.

Two famous battles were fought in or near this town, in one day, Aug. 16, 1777, in which Col. Stark gained great fame. The British loft 4 brais field pieces, and other military ftores; and befides those flain, 700 were taken prifoners. The killed and wounded of the Americans were about 100 men. This defeat contributed in a great measure, to the fublequent furrender of General Burgoyne's army.

BENSON, the N. westernmost townthip in Rutland co. Vermont, is fituated on the E. fide of Lake Champlain; 57 miles N. N. W. of Bennington, and has 658 inhabitants. Hubberton R. paffes through Benfon in its way to Eaft Bay. Cockburne's Creek, which feeds the fame bay, rifes here.

BERABZAN, is a long lake in New North Wales, lying N. and S. and narrows gradually from its N. end, till it mixes with the waters of Shechary York on the W.; into which fate it Lake at the S. end, where thefe waters form

form Seal R. w fon's Bay at C end of Berabzan lat. and in '93. chary L. and Ch BERBICE, a river of the fai which fee. Tl other adjoining Effequibo, furre 1796.

BERBICE, or nam, or Dutch which is a quart two fathoms dee lat. 6. 30. Th low and woody, and cotton. BERGEN Co.

fon R. lies oppo E. and was first from New-York thips, of which and Hackinfack tants, including 7 Dutch Calvin Dutch Lutheran mine here, whi the Schuylers (was confiderably been neglected fo It is a mounta

county, 30 mile It forms part o end of the state tremity meets the co.; fo that the fom Morris and on the S. W. breadth of the ft:

BERGEN, the co. New-Jerfey, water, except c Hudfon feparates city, 3 miles dift row channel lies I.; and on the W The inhabitants from the Dutch fi BERGEN Neck tremity of the abo

BERKHEMSTE a township in L cut, having Har Hartford S.

BERKLEY, at Maffachofetts, co tants ; so miles f BERKLEY, the

ck rivers, into Hudnd co. lies flachufetts nfhips, of hefter are habitants, nountains ance, and and two

wn of the town in bout 160 the town, he Great corner of from the hawk ri-S. end of luence of 55 miles eafterly the fame N. lan nnington Its pub-I church, the oldeft first fething conabitants. t Antho-• conical ought in Aug. 16, hed great field pie-id befides rifoners. Ameri-This deifure, to ral Burft town-

s fituatmplain; ton, and rton R. to Eaft ch feeds

in New and nar-, till it hechary ; waters form BER

form Seal R. which empties into Hudfon's Bay at Churchill fort. The N. end of Berabzan lies in about 60. 30. N. lat. and in 93. 50. W. long. See Shechary L. and Churchill R.

BERBICE, a Dutch fettlement on a river of the fatne name, in Surinam, which fee. This fettlement with the other adjoining ones of Surinam and Effequibo, furrendered to the British in 1796.

BERBICE, or Berbeu, a river in Suri nam, or Dutch Guiana, in S. America, which is a quarter of a mile broad, and two fathoms deep at its mouth, in N. lat. 6. 30. The land on both fides is low and woody, has plenty of logwood and cotton.

BERGEN Co. in New-Jerfey, on Hudfon R. lies opposite New-York, on the E. and was first planted by the Dutch, from New-York. It contains 6 townfhips, of which the chief are Bergen and Håckinfack, and 12,601 inhabitants, including 2301 flaves. Here are 7 Dutch Calvinist churches, and 2 of Dutch Lutherans. There is a copper mine here, which, when worked by the Schuylers (to whom it belorged) was confiderably productive; but it has been neglected for many years.

It is a mountainous, rough, and hilly county, 30 miles long, and 25 broad. It forms part of the E. and northern end of the ftate; and its N. W. extremity meets the N. E. part of Suffex co.; io that thefe two counties embofom Morris and Effex counties, except on the S. W. and form the whole breadth of the ftate in that quarter.

BERGEN, the thire town of Bergen co. New-Jerfey, lies furrounded by water, except on the N.; the river Hudfon feparates it from New-York city, 3 miles diffant; on the S. a narrow channel lies between it and Staten I.; and on the W. it has Hackinfack R. The inhabitants are moftly defcendants from the Dutch fettlers.

BERGEN Neck, is the fouthern extremity of the above township.

BERKHEMSTEAD, or Barkhemstead, a township in Litchfield co. Connecticut, having Hartland N. and New-Hartford S.

BERKLEY, a township in Bristol co. Massachusetts, containing \$50 inhabitants; 50 miles southward of Boston.

BERKLEY, the name both of a coun-

ty and town, in Charleston District, S. Carolina, lying near Cooper and Ashley Rivers. In the census of 1791, it was called St. John's Parish, in Berkley co. and contained 752 free persons, and 5170 flaves.

BBRKLEY Co. in Virginia, lies W. of the Blue Ridge, N. of Frederick co. and feparated from the flate of Maryland, on the N. and E. by Potowmack R. This fertile county, about 40 miles long and 20 broad, has 16,781 free inhabitants, and 2932 flaves. Martinfburg is its chief town.

BERKLEY'S Sound, on the N. W. coaff of N. America, lies on the eaftern fide of Quadras Ifles. The land on its eaftern fide is opposite Cape Flattery, and forms the N. fide of the Straits de Fuca.

BERK'S Co. in Pennfylvania, has Northampton to. on the N. E.; Northumberland on the N. W.; part of Luzern on the N.; Dauphin and Lancafter counties S. W. and Chefter and Montgomery S. E. It is watered by Schuylkill R. and is 53 miles long and near 29 broad, containing 1,030,400 acres. Here iron ore and coal are found in plenty, which fupply feveral iron works. The northern parts are rough and hilly. Berks contains 30,179 inhabitants, of whom 65 only are flaves. It has 29 townfhips, of which Reading is the chief.

BERKSHIRE Co. in Maffachufetts, is bounded W. by New-York ftate; S. by the ftate of Connecticut; E. by Hampfhire co. and N. by the ftate of Vermont. It thus runs the whole extent of the ftate from N. to S. and contains twenty-fix townfhips; the chief of which are Stockbridge, Lenox, Great Barrington, Williamftown, and Pittsfield; and the number of inhabitants 30, 291. White and clouded marble is found in feveral towns, in the rough and hilly parts of this country.

In February, 1796, the legiflature paffed an act to establish a college in Williamstown, by the name of Williams College.

BERKSHIRE, a newly fettled townfhip, in Franklin co. Vermont.

BERLIN, a neat and flourishing town of York co. Pennfylvania, containing about 100 houfes. It is regularly laid out, on the S. W. fide of Conewago Creek, 13 miles westerly of Yorktown,

and

and 101 W. of Philadelphia. N. lat. this name from the difcoverer, John 39. 56. Bermudas, a Spaniard; and were called

BERLIN, a township in Orange co. Vermont, on Dog R. a branch of Onion R. from the S.; which last separates Berlin from Montpelier, on the N. N. W. Berlin contains 134 inhabitants, and is about 94 miles N. casterly from Bennington.

BERLIN, a township in Hartford co. Connecticut, 12 miles S. S. W. of Hartford, 42 N. W. of New-London; and 26 N. N. E. of New-Haven.

BERLIN, a township in Worcester co. Maffachusetts, containing 512 inhabitants; 34 miles W. of Boston, and 45 N. E. of Worcester. Hops have been cultivated here lately, and promise to be a valuable article of hushandry.

BERLIN, in Somerfet co. formerly in that of Bedford Pennfylvania, lies on a branch of Stoney Creek, a S. water of Conemaugh R. on the W. fide of the Alleghany Mountain; 25 miles weft-ward of Bedford; 23 N. W. of Fort Cumberland, in Virginia, and 200 W. of Philadelphia. Stone Creek, the chief fource of Kifkeminitas R. rifes N. N. E. of Berlin. N. lat. 39. 54. BERMUDA HUNDRED, or City Point, as it is fometimes called, is a port of entry and post town, in Chefterfield co. Virginia, fituated on the point of the peninfula, formed by the confluence of the Appamattox with James River, 36 miles wefterly from Williamfburg, 64 from Point Comfort, in Chefapeak Bay, and 315 S. W. by S. from Philadelphia. City Point, from which it is named, lies on the fouthern bank of James R. 4 miles S. S. W. from this town. The exports from this place, chiefly collected at Richmond, 20 miles above it, amounted in 1794, to the value of 773,549 dollars; and from the 1ft of October, to 1ft December, 1795, were as follows: 15 kegs of butter, 578 bbls. S. fine flour, 101 half do. 789 fine do. 393 lbs. indigo, 10 tons pig iron, 100 Ibs. faffafras, 80, 320 hbd. Itaves, 66, 300 bbl. ftaves, 1,819 hhds. tubacco, and 3 kegs manufactured do .- Total exports, 90,859 dollars, 45 cents. There are about 40 houfes here, including fome warehouses. It trades chiefly with the W. Indies, and the different flates. City Point, in James R. lies in N. lat. 37. 16.W. long. 77. 311. See Richmond. BERMUDA Iflands. Thefe received

13

BER

Bermudas, a Spaniard; and were called Sommer's Ifles, from Sir George Sommers, who was thipwrecked on their rocks in 1609, in his paffage to Virginia: The number of this cluffer, in the form of a shepherd's crook, has been computed to be about 400, diffant from the Land's End in England, 1 500 leagues, from the Madeiras 1200, from Hispaniola 400, and 200 from Cape Hatteras in Carolina, which last is the nearest land to them. The islands are walled with rocks; and by reafon of thefe, together with fhoals, are difficult to approach. The entrances into the harbours and channels are narrow as well as fhoaly, and are more dangerous by reason of the firong current which fets to the N. E. from the gulf of Florida. They contain from 12 to 13,000 acres of poor land, of which 9 parts in 10 are either uncultivated, or referved in woods, which confift chiefly of cedars for the fupply of fhip-building. There are about 200 acres laid out in cotton. The main island is about 16 miles longs and from one to two in breadth. The parifh of St. George's, is an I. to the eastward of the main land, in which ftands the town of St. George's, containing about 500 houfes. Contiguous to that is St. David's I. which fupplies the town with provisions. The air is healthy, and a continual fpring prevails; and moft of the productions of the W. Indies might be cultivated here. The houses are built of a foft stone, which is fawn like timber, but being washed with lime, it becomes hard; these ftones are greatly in request throughout the W. Indies, for filtrating water. The houfes are white as fnow; which, beheld from an eminence, contrafted with the greennels of the cedars, and pafture ground, and the multitude of iflands full in view, realize what the poets have feigned of the Elylian Fields .-Some accounts fay that thefe iflands contain from 15 to 20,000 inhabitants ; but Mr. Edwards fays the number of white people is 5462, of blacks 4919. Old writers observe that there were 3000 English in these islands, in 1623. 300 or 400 go annually to Turks I. to rake falt, which is carried to America for provisions, or fold, to fuch as may call for it there, for cash. The Bermudians are chiefly feafaring men, and the negroes

groes are very e late war, there tween 15 and 1 from hence, v negro flaves, wi bly; and fuch here, and fo m their mafters, t ed always retur power; a fing occurred in the The thip Regu carried into Bo on board: 60 flag of truce, New-York; on died. The go under a gover tifh crown, a c fembly. Ther which 3 clerg and there is one In the prefen merous cruizers unwarrantably American veffe fions or naval ft and other ports quitoufly conde BERNARD'S fide of the gult fage into it, b called Pafco de BERNARDST New-Jerfey, co including 93 fl Alfo the n Hampfhire co. ing 691 inhabi weftward from BERNE, a 1 New-York. 7 1796, it appea inhabitants wh BERRY IAA illes on the N. Bahama Bank, vidence. N. lat. BERTIE, at lina, in Edento noke its S. be Sound on the 1 ancient Indian contains 12,60 ber 5141 are fl BERWICK, town in York head of Conews ward of York,

ward of Yo

trer, John were called orge Somi on their ge to Vir-cluffer, in crook, has oo, diftant land, 1 500 1200, from Cape Hatlaft is the iflands are reafon of re difficult s into the narrow as dangerous ent which ilf of Floto 13,000 parts in 10 cferved in of cedars g. There in cotton. miles long, lth. The 1 I. to the in which 'ge's, conitiguous to upplies the is healthy, ails; and he W. Inere. The ne,' which ng washed rd; thefe hroughout ater. The which, beafted with nd pafture of iflands the poets Fields .fe iflands habitants; number of cks 4919. were 3000 123. 300 I. to rake ca for proay call for ermudians d the negroes

BER

groes are very expert mariners. In the late war, there were at one time between 15 and 20 privateers fitted out from hence, which were manned by negro flaves, who behaved irreproachably; and fuch is the ftate of flavery here, and fo much are they attached to their mafters, that fuch as were captured always returned when it was in their power; a fingular inftance of which occurred in the ftate of Maffachufetts. The fhip Regulator, a privateer, was carried into Bofton, and had 70 flaves on board: 60 of them returned in a flag of truce, 9 returned by way of New-York ; one only was miffing, who died. The government is conducted under a governor, named by the Britifh crown, a council, and a general affembly. There are 9 churches, of which 3 clergymen have the charge; and there is one Prefbyterian church.

In the prefent European war, the numerous cruizers from Bermudas, have unwarrantably captured numbers of American veffels, loaded with provifions or naval flores, bound for French, and other ports, which have been iniquitoufly condemned.

BERNARD's Bay, lies on the N. W. fide of the gulf of Mexico. The paffage into it, between feveral illands, is called Pafco de Cavallo.

BERNARDSTOWN, in Somerfet co. New-Jerfey, contains 2377 inhabitants, including 93 flaves.

Also the name of a township in Hampshire co. Massachusetts, containing 691 inhabitants; distant 110 miles westward from Boston.

BERNE, a township in Albany co. New-York. By the state census of 1796, it appears there are 477 of the inhabitants who are electors.

BERRY Iflands, a finall clufter of ifles on the N. W. point of the Great Bahama Bank, in the channel of Providence. N. lat. 25. 30. W. long. 75. 40. BERTIE, a maritime co. in N. Carolina, in Edenton diffrict, with the Roanoke its S. boundary, and Albemarle Sound on the E. In it is fituated the ancient Indian tower of Tufcarora. It contains 12,606 fouls, of which number 5141 are flaves.

BERWICK, or Abbotflowm, a neat town in York co. Penniylvania, at the head of Conewago Creek, 13 miles weffward of York, 26 S. S. W. of Harrif-

burgh, and 103 W. by S. of Philadelphia. The town is regularly laid out, and contains about 100 houfes, a German Lutheran, and Calvinist church. N. lat. 39. 54.

BERWICK, or New-Berwick, a fmall town of Northumberland co. Pennfylvania, on the N. weilern fide of the E. branch of Suiquehannah R. oppofite Nefcopeck Falls, and Nefcopeck Creek, 32¹/₂ miles N. E. from Northumberland and Sunbury, at the junction of the E. with the W. branch of Suiquehannah, and r60 N. W. of Philadelphis. N. lat. 41. 3.

BERWICK, a township in York co. District of Maine, containing 3894 inhabitants. It has an incorporated academy, and lies on the E. fide of Salmon Fall R. 7 miles N. W. of York, and 86 E. of N. from Boston.

BETHABARA, the first fettlement of the Moravians in the lands of Wachovia, in N. Carolina, begun in 1753; 6 miles N. of Salem, and 183 W. of Halifax, in N. lat. 36. 9. It is fituated on the W. fide of Graffy Creek, which unites with the Gargales, and feveral others, and falls into the Yadkip. It contains a church of the United Brethren, and about go dwelling houfes.

BETHANY, or Bethania, a Moravian, fettlement and poft town, in the lands of Wachovia, in N. Carolina, begun in 1760; 9 miles N. W. of Salem, 4 N. W. of Bethabara, and 568 S. W. by S. of Philadelphia. It contains about 60 houfes, and a church, built on a regular plan. See Wachovia.

BETHEL, a finall Moravian fettlement on Swetara R. in Pennfylvania, 12 miles from Mt. Joy.—A township in Dauphin county.

BETHEL, a township in Windsor co. Vermont, containing 473 inhabitants; N. N. W. of, and bounded by Stockbridge, and about 67 miles N. N. easterly of Bennington. It gives rife to a finall branch of White River.

BETHEL, a township in Delaware co. Pennsylvania.

BETHLEHEM, a town in Albany co. New-York, very fruitful in pattures, and has large quantities of excellent butter. By the flate cenfus of 1796, 388 of the inhabitants are electors.

BETHLEHEM, a township in Berkshire co. Massachusetts, having 261 inhabitants. It lies about 10 miles S. of

E.

E. from Stockbridge, 10 from Lenox, and 130 from Bofton. It borders on Tyringham and Loudon. which, belongs to the fociety. There is allo a flore, with a general affortment of poods, an apothecary's flop,

BETHLEHEM, a township in Hunterdon co. New-Jersey, situated at the head of the S. branch & Rariton River. It contains 1335 inhabitants, including 31 flaves. Turf for firing is found here. BETHLEHEM, a township in Litchfield co. Connecticut, joins Litchfield on the N. and Woodbury on the S.

BETHLEHEM, a post town in North-ampton co. Pennsylvania, is a celebrated fettlement of the Moravians, or United Brethren, of the Protestant Epifcopal church, as they term themfelves. It is fituated on Lehigh R. a weftern branch of the Delaware, 53 miles northerly from Philadelphia, and 18 foutherly from the Wind Gap. The town flands partly on the lower banks of the Manakes, a fine creek, which affords trout and other fifth. The fituation is healthful and pleafant, and in fummer is frequented by gentry from different parts. In 1787, there were 60 dwelling houses of stone, well built, and 600 inhabitants. Befides the meeting house, are t other public buildings, large and fpacious : one for the fingle brethren, one for the fingle fifters, and the other for the widows. The literary eftablishments, as well as the religious regulations, here, deferve notice .- In a houfe adjoining to the church, is a school for females; and fince 1787, a boarding school for young ladies, who are fent here from different parts, and are infructed in reading and writing (in the English and German tongues) grammar, arithmetic, geography, needle, work, mufic, &c. The minister of the work, mufic, &cc. place has the direction of this as well as of the boys' ichool, which is kept in a feparate house, where they are initiated in the fundamental branches of literature. Theie fchools, efpecially that for the young ladies, are defervedly in very high repute; and fcholars, more than can be accommodated, are offered from all parts of the United States.

There is at the lower part of the town a machine, of fimple construction, which raifes the water, from a fpring, into a refervoir, to the height of 100 feet; whence it is conducted by pipes into the feveral flreets of the town.

There is a genteel tavern dt the N. from Porto Rico, 6 leagues long, and end of the town, the profit arjung from a broad. The English settled here

which, belongs to the fociety. There is also a flore, with a general affortment of goods, an apothecary's fhop, a large tan-yard, a currier's, and a dyer's fhop, a grift-mill, a fulling-mill, an oil-mill, and a faw-mill, and on the banks of the Lehigh, a brewery. N. lat. 40. 37. W. long. 75. 14.

BEUF, Riviere au, empties eaftwardly into Miffifippi R. in N. lat. 39: 4. 3 about 48 miles, by the course of the river, above the mouth of the Illinois, and 7 miles S. from Riviere Oahaha.

BEUF, SMALL LE. See Le Boeuf. BEVERLY, a township and post town in Effex co. Maffachufetts, containing 3290 inhabitants, is feparated from Salem by a handfome bridge, and is about 20 miles E. of N. of Bofton, and 22 S. W. of Newburyport. It has two parifhes. In the parifh next the harbour, are a number of handlome houses, exhibiting the cheering rewards of enterprife and industry, and the inhabitants are devoted to the fifthery and other branches of navigation. In the other part of the town, which is chiefly agricultural, is a cotton manufactory. The bridge, mentioned before, is 1500 feet in length, erected in 1788, and connects this town with Salem. It has a draw for veffels.

BEVERLY'S Manor, or Irif Tract, in Virginia, is a tract of land, in N. lat. 38. ro. at the head of Maffanuten's R. a weftern branch of the Shenandoah, which rifes here by three branches, viz. Middle R. Lewis and Chriftian Creeks. It lies between the Blue, and the North Ridge. The road from Yadkin River, through Virginia to Philadelphia, paffes through here.

BIDDLES, a fettlement on a branch of Licking R. in Bourbon co. Kentucky; about 6 miles N. W. from Millers, on the N. E. fide of the fame branch, and 32 miles N. N. E. from Lexington.

BIDDEFORD, a port of entry and poft town in York co. Diffrict of Maine, on the S. W. fide of Saco R. on the fea coaft, 14 miles S. W. from Portland, 24 N. E. from York, and 105 from Bofton. It contains 1018 inhabitants; and here the county courts are held, as likewife at York. N. lat. 43, 26.

BIEQUE Ifland, or Boriquen, or Crabs Ifle, one of the Virgin Ifles, 2 leagues from Porto Rico, 6 leagues long, and 2 broad. The English settled here twice twice, and have the Spaniards, w it remain defola and a good roa 18. 2. N. Long BIG BONE C Kentucky, falls E. in about N. la 54. It is very branches; the locks with Ban falls into Lickin able for the larg near it.

BIG BONE L fide of the abc little below the eaftern branches the mouth of t alfo the other fal ern country, are the earth about in a most curiou falces and deer on account of th which it is impr brackifh water r the foil of whic large bones for other places near foft grounds, th mammoth, ftill naturalifts to de they have belo found here by fured forty-nine tooth of this Yale College. N to have examin of these animal tion, fays, that an animal five volume of an el has admitted. tives have no tra fabulous, that aided by it, exce carnivorous; at opinion, and wa Dr. Hunter, of mination of the BIG HILL Cr kafkias R. 25 mi 17 above Blind (from the mouth BIGGIN Swa BIG Rock, al bank of Au V N. E. from its r twice, and have been driven away by the Spaniards, whofe intereft it is to let it remain defolate. It has a rich foil, and a good road on its S. fide. Lat. 18. 2. N. Long. 64. 30. W.

al affort-

y's fhop,

and a dyg-mill, an

d on the

ery. N.

eastward-

· 39. 4. ;

: Illinois,

e Boeuf

ontaining

from Sa-

is about

two pa-

harbour,

ules, ex-

of enter-

habitants

nd other

efly agriry. The

500 feet connects

1 a draw

h Traat,

n N. lat.

ten's R.

nandoah,

hes, viz.

Creeks.

he North

n River,

a, paffes

1 branch

intucky; llers, on

ich, and

and poft

aine, on

the fea

ortland,

om Bof-

bitants ;

held, as

or Crabs

leagues

ng, and

ed here

twice

26.

gton.

poft town

ahaha.

BIG BONE Creek, in Woodford co. Kentucky, falls into the Ohio from the E. in about N. lat. 39, 17. W. long. 85. 54. It is very finall in fize, and has 3 branches; the N. wefternmoft interlocks with Bank Lick Creek, which falls into Licking R. It is only noticeable for the large bones, and falt licks

near it. BIG BONE LICKS, THE, lie on each fide of the above mentioned creek, a little below the junction of the two eastern branches, about 8 miles from the mouth of the creek. Thefe, as alfo the other falt fprings, in the wetcern country, are called Licks, because the earth about them is furrowed up in a most curious manner, by the buffaloes and deer which lick the earth, on account of the faline particles with which it is impregnated. A ftream of brackish water runs through these licks, the foil of which is a foft clay .- The large bones found here, and in feveral other places near falt licks, and in low foft grounds, thought to belong to the mammoth, still puzzle the most learned naturalists to determine to what animal they have belonged. A thigh bone found here by General Parfons, meafured forty-nine inches in length. A tooth of this animal is deposited in Yale College. Mr. Jefferson, who seems to have examined the fkeleton of one of these animals with curious atten tion, fays, that " The bones befoeak an animal five or fix times the cubic volume of an elephant," as M. Buffon has admitted. Of this animal the natives have no tradition, but what is fo fabulous, that no conjecture can be aided by it, except that the animal was carnivorous; and this is the general opinion, and was admitted by the late Dr. Hunter, of London, from an examination of the tufks, &cc.

BIG HILL Creek, runs W. into Kafkafkias R. 25 miles below Beaver Creek, 17 above Blind Creek, and 26 northerly from the mouth of Kafkafkias.

BIGGIN Swamp. See Santee River. BIG Rock, a large rock on the S. E. bank of Au Vaze R.; about 3 miles N. E. from its mouth in the Millippi,

and about 8 miles S. E. from Cape St. Antonio, on that river.

BIG ROCK Branch, the N. eaftern head branch of Alleghany R. The branch called Big Hole Town joins it, and forms the Alleghany, 85 miles N. E. from, and above, Venango, Fort.

BIG SALT Lick, a garrifon in the ftate of Teneffee, near the Salt Lick, on Cumberland R.; 115 miles from Knoxville; 80 from South Weft Point, on Clinch R.; 32 from Bledfoe Lick, and 68 from Nafhville.

BIG SANDY River, or Totterwy, has its fource near that of Cumberland R.; and, feparating Virginia from Kentucky, empties into the Ohio, opposite the French Purchase of Galiopolis, in about N. lat. 38. 30. Vancouver's and Harmar's forts stand on this river. On its banks are several falt licks and springs, *Little Sandy*, is a short, small river, which falls into the Ohio, about 20 miles W. of Big Sandy R. in Mason co. Kentucky.

BILLERICA, a township in Middlefex co. Massachusetts, incorporated in 1655. It has 1200 inhabitants; not has there been much variation in the number for half a century. It lies 20 miles northward of Boston, and is watered by Concord and Shawsheen rivers, which run N. easterly into Merrimack Rive?.

BILLINGSPORT, on Delaware River, lies 12 miles below Philadelphia, was fortified in the late war, for the defence of the channel. Opposite this fort, feveral large frames of timber, headed with iron fpikes, called *chevaux de frizci*, were funk to prevent the British thips from passing. Since the peace, a curious machine has been invented in Philadelphia, to raife them.

BILLET. See Hatborough.

BILLYMEAD, in Caledonia co. in Vermont.

BIMINI I/e, one of the Bahama iflands, near the channel of Bahama, and E. of Cape Florida. It is about 8 miles in length, and as much in breadth; covered with trees, and inhabited by the aborigines of America. It is very difficult of accefs, on account of the shoals; but it is a pleasant place, and is faid to have a good harbour. N. lat. 25. W. long. 79. 30.

BIOBIO, or Biophio, a river in Chili, the largest in that kingdom. It rifes

ir

in the Andes, enters the S. Sea near the city of Conception, opposite the isle of Avequirina, in lat. 37. S.; running through veins of gold and fields of far-faparilla. It is the boundary between the Spaniards and feveral Indian nations, their enemies; which obliges them to keep ftrong garrifons upon it. BIRD Fort, on Monongahela R. 40

miles S. of Fort Pitt.

BIRDS Keys, a rock or island among the Virgin isles in the W. Indies. It is round, and lies about 2 leagues S. of St. John's. It has its name from the guantities of birds which refort there. N. lat. 17. 55. W. long. 63. 20. BIRU, a town to leagues from Trux-illa, in the S. Sea, in the empire of Peru, inhabited by about 80 Indians, Spaniards, Mulattoes, and Meftees. It is very fertile, and well watered by canals cut from the river, and fo conveyed to great diffances; as at Trux-illa. S. lat. 8. 24. W. long. 69. 17.

BISCAY Bay, is in the N. eaftern corner of Trepaffey Bay in the island of Newfoundland; which lies in the S. eastern part of the island.

BASCAY, a province of Mexico, bounding in filver mines, having New-Mexico on the N. and Florida on the W. The river de la Nafias runs thro' a great part of it.

BLACK Lick, lies in Wellmoreland co. Pennfylvania, about 36 miles E. of Pittfburgh.

BLACK Point, and Blue Point, are capes, within those of Elizabeth and Porpoife, in the diffrict of Maine.

BLACK R. There are two fmall rivers of this name in Vermont, one falls into Connecticut R. at Springfield, the other runs N. into Lake Memphre-

magog. BLACK R. in N. York, interlocks with Canada Creek, and runs N. W. into Iroquois river, boatable 60 miles. Alfo a long river which rifes in Vir-ginia, and paffes fouth eafterly into Nottaway R. in N. Carolina.

BLACK River, a British fettlement at the mouth of Tinto R. 20 leagues to the E. of Cape Honduras, the only harbour on the coaft of Terra Firma, from the island of Rattan to Cape Gracias a Dios, and was for more than 60 years the refuge of the logwood cutters, when the Spaniards drove them from the forefts of East Yucatan, which oc-

caffoned adventurers of different kinds to fettle here, where the coaft is fandy. low and fwampy; higher up near the rivers and lagoons, which are full of fifli, the foil is more fertile, and produces plantanes, cocoa-trees, maize, yams, potatoes, and a variety of vegetables; and the paffion for drinking fpirits, made them plant fugar canes. The forefts are full of deer, Mexican, fwine and game. The flores abound with turtle, and the woods with mahogany, zebra-wood, farfaparilla, &c. and indeed the whole fettlement flourifhes fpontaneoully without cultivation. BLACK R. in the island of Jamaica, passes through a level country, is the deepeft and largest in the island, and will admit flat bottomed boats and canoes for about 30 miles.

BLACKSTONE, a fmall R, which has its fource is Ramfhorn pond, in Sut-ton, Maffachufetts, and after paffing through Providence, empties into Narraganfet Bay at Briftol, receiving in its courfe a number of tributary threams.

BLADEN, a county of N. Carolina. in Wilmington diffrict. It has 5084 inhabitants, including 1676 flaves.

BLADENSBURG, a post town in Prince George co. Maryland, on the eaftern bank of the eastern branch of Potowmack R. at the confluence of the N. W. and N. E. branches; 9 miles from its mouth at the Federal City; 38 S. W. from Baltimore, and 12 N. E. from Alexandria, in Virginia. It contains about 150 houfes, and a ware-houfe for the infpection of tobacco.

BLAIZE, Cape, on the coaft of W. Florida, in the gulf of Mexico, is a promontory which feparates the bay of Apalache on the E. from that of St. Joseph; into which last it turns in the thape of a thepherd's crook.

BLANCA, a river in the province of Chiapa, in the audience of Mexico, in New-Spain, North America. Its water is faid to have a petrifying quality, yet is clear, and does no harm to man or beaft that drinks of it.

BLANCO Capes. There are many capes of this name, as follow. 1. The N. western point of the bay of Salinas, in the 10th degree of N. latitude; and on the coaft of Terra Firma ; and, in other maps, is called the N. weftern point of the gulf of Nicoya .--- 2. On the coaft of California, at the broadeft part

part of the penin of N. latitude .of America, in M of the mouth of the River of the gree of N, latitu of Peru, in S. I the S. Sea, 120 quil, S. lat. 3. 4 cape in the fout fide of Patagoni Bay, in the 47th 8 leagues W. of BLANCO, or leagues from T Margarita I. in Andalufia, It habited havin grafs; is dry Ee. of guanas, and vitæ. N. lat. BLANCO, an part of the pen New-Spain. N, BLANDFORD burg co. on Ma fettled by a few BLANDFORD fhire co. Maffaci ticut R.; abou Northampton, a It has 235 house BLANDFORD George co. Virg E. from Peterfb jurifdiction. I and 1200 inhabi fituated on a , branch of App many large ftore houses, which 7000 hhds. It the marshes in drained, the air of Petersburgh,

BLAS ST. a the North Pacif to the S. E. ftan postella, in the New-Spain.

BLEDSOE Lid peffee, lies 32 m garrifon, and 30 BLENHEIM, York, in Schoha

BLOCK Ifan Manifies, hes al of Newport, an

part

BLO

part of the peninfula, in the 32d degree of N. latitude.-3. On the N. W. coaft of America, in New-Albion, fouthward of the mouth of what has been called the *River of the Weft*, in the 44th degree of N. latitude.-4. A promontary of Peru, in S. America, on the coaft of the S. Sea, 120 miles S. W. of Guayaquil, S. lat. 3. 45. W. long. 83,-5. A cape in the fouthern ocean, on the E. fide of Patagonia, S. eaftward of Julian Bay, in the 47th degree of S. latitude, 8 leagues W. of Pepys's Ifland.

BLANCO, or Blanca, an island 35 leagues from Terra Firma. and N. of Margarita I. in the province of New-Andalufia. It is flat, low, and uninhabited having favannahs of long grafs; is dry and healthy; has plenty of guanas, and fome trees of lignumvite. N. lat. 11. 50. W. long. 64. 50.

BLANCO, an ifland on the S. eaftern part of the peninfula of Yucatan, in New-Spain. N, lat. 21. W. long. 88. 5.

BLANDFORD, a township in Lunenburg co. on Mahon Bay, Nova-Scotia, fettled by a few families.

BLANDFORD, a township in Hampfhire co. Massachuletts, W. of Connecticut R.; about 25 miles S. W. of Northampton, and 116 W. of Boston. It has 235 houses, and 1416 inhabitants.

BLANDFORD, a town in Prince George co. Virginia, about 4 miles N. E. from Peterfburgh, and is within its jurifdiction. It contains 200 houfes and 1200 inhabitants, and is pleafantly fituated on a plain, on the eaftern branch of Appamattox R. Here are many large flores, and 2 tobacco warehoufes, which receive annually 6 or 7000 hhds. It is a thriving place; and the marfhes in its vicinity being now drained, the air of this town, and that of Peterfburgh, is much meliorated.

BLAS ST. a cape on the coaft of the North Pacific Ocean, near which, to the S. E. flands the town of Compoftella, in the province of Zalifca, in New-Spain.

BLEDSOE Lick, in the flate of Tepeffce, lics 32 miles from Big Salt Lick garrifon, and 36 from Nafhville.

BLENHEIM, a new town of New-York, in Schoharie co. incorporated in 1797.

BLOCK Ifland, called by the Indians Manifies, hes about 21 miles S. S. W. of Newport, and is in Newport co.

fate of Rhode-Ifland. It was erected into a townfhip, named New-Shorebars, in 1672. This ifland is 46 miles in length, and its extreme breadth is 38 miles. It has 682 inhabitants, including 47 flaves. It is famous for cattle and fheep, butter and cheefer round the edges of the ifland confiderable quanties of cod fifth are caught. The fouthern part of it is in N. lat. 41. 8.

BLOCKLEY, a township in Philadelphia co. Pennsylvania.

BLOOMFIELD, a township in Ontario co. New York. By the state cenfus of 1796, 1510f the inhabitants were electors.

BLOOMING Vale, a tract of land in the township of Manlius, New-York state, on Butternut Creek.

BLOUNT, a new county in the flate of Teneffee.

BLOUNTSVILLE, in N. Carolina, is on the post road from Halifax to Plymouth, 49 miles from Plymouth, and 55 from Williamstown.

BLUEFIELDS Bay, lies S. caftward of Savannah-la-mar, in the ifland of Jamaica, having good anchorage for large veffels. N. lat. 18. 10¹/₂. W. long. 78.

BLUEHILL, a township in Hancock co. District of Maine, on the W. side of Union R. 344 miles N. E. of Boston, and 13 E. of Penobscot; having 274 inhabitants.

BLUE HILL Bay, is formed by Nafkeag Point on the W. and Mount Defart I. on the E. It extends northerly up to a mountain on the E. of Penobfcot R. which, from its appearance at fea, is called *Blue Hill*. Union R. empties into this bay.

BLUE Hills, a range of mountains in New England; whole first ridge in New-Hampshire passes thro: Rochester, Barrington, and Nottingham.

BLUE Mountains, in Northampton co. Pennfylvania, extend from S. W. to N. E. and a fhort way across the Delaware.

Alfo, a range of mountains which run from S. E. to N. W. through Surry co. in the ifland of Jamaica.

BLUE Ridge. The first ridge of the Allegbany Mountains, in Pennfylvania and Virginia, is called the Blue Ridge; and is about 130 miles from the Atlantic. It is about 4000 feet high, meafuring

and the North Mountain is a large fertile vale. The paffage of the Potowmack through this ridge is one of the most stupendous scenes in nature. See Alleghany Mountains, and Potowmack River.

BLUE Licks, on the main branch of Licking R. in Kentucky, are fituated about 8 miles westerly from the Upper Blue Licks. Both are on the N. eaftem fide of the river: the latter is about 15 miles N. E. of Millers.

BLUE Spring, lies between Big Barren and Little Barren river, S. branches of Green R. in Mercer's co. Kentucky; about 22 miles S. wefterly from Sulphur Spring, and 13 S. of Craig's Fort, on the N. fide of Green R.

BLUE Stone Creek, a small western branch of the Great Kanhaway.

BOCCA-CHICA, the ftrait or entrance into the harbour of Carthagena, in Terra Firma, S. America ; defended by feveral forts and guns, which were all taken by the British forces in 1741.

BOCCA-DEL-DRAGO, a ftrait between the island of Trinidad and Andalusia, in the province of Terra Firma, S. America.

BODWELL's Falls, in Merrimack R. lie between Andover and Methuen, about s miles below Patucket Falls. A company was incorporated in Feb. 1796, for building a bridge near this fpot; between the two states of Masiachusetts and New-Hampfhire.

BOEUF, Le, a place in the N. weftern corner of PenniyWania, at the head of the N. branch of French Creek, and so miles from Fort Franklin, where this Creeks joins the Alleghany; mcafuring the diftance by water. The French fort of Le Boeuf, from which the place has it name, lay about 2 miles E. from Small Lake, which is on the N. branch of French Creek; and from Le Bocuf, there is a portage of 14 miles norther'y to Presque Ifte, in Lake Erie ; where the French had another fort.

From Le Boeuf, to Preique Isle, is a continued chelhut-bottom iwamp (except for about one mile from the former, and two from the latter) and the road between these two places, for 9 miles, 15 years ago, was made with logs, laid upon the fwamp. N. lat. 42. r. W. long. 79, 53. 20. BOHEMIA, a broad, navigable river,

furing from its bafe; and between it | ro miles long, which runs W. N. W. into Elk River, in Maryland, 11 miles below Elkton.

> BOHIO, a river of Chili, in S. America. BOLABOLA, one of the Society Ifles, which fee.

> BOLINBROKE, a town in Talbot co. eaftern fhore of Maryland, and s miles E. of Oxford. It lies on the N. W. point of Choptank River.

> BOLTON, a township in Chittenden co. Vermont, on Onion R. about 104 miles N. N. E. from Bennington, having 88 inhabitants.

> BOLTON, a township in Tolland co. Connecticut, incorporated in 1720; and was fettled from Weathersfield, Hartford, and Windfor, 14 miles E. from Hartford.

BOLTON, a township in Worcefter co. Maffachusetts ; 18 miles N. E. from Worcefter, and 34 W. from Bofton. It contains 861 inhabitants .-There is a fine bed of limeftone in this. town, from which confiderable quantities of good lime are made yearly.

BOMBARDE, a fort and village on the north peninfula of St. Domingo Ifland, about 3 leagues N. of La Plate Forme ; 6 S. E. of the Mole, and 22 from Port de Paix, as the road runs. N. lat. 19. 42.

BOMBAY Hook, an ifland at the mouth of Delaware R. about 8 miles long and 2 broad, formed by the Delaware on the eastern fide, and Duck Creek and Little Duck Creek on the Maryland fide; thefe are united together by a natural canal. It is propoled to connect Delaware R. with Chefapeak Bay, by a canal from Duck Creek to that. bay, through Chefter R. See Chefter River. The N. W. end of Bombay Hook is about 47 miles from Capes Henlopen and May, from the Hook to Reedy I. is 9 miles.

BOMBAZINE Rapids, on a river, in Lincoln co. Diffrict of Maine, are navigable for boats with fome lading, at a middling pitch of water. They took their name from Bombazire, an Indian warrior, who was flain by the English in attempting to cross them.

BOMBAZINE, a lake, 7 or 8 miles long, in the township of Castleton, Rutland co. Vermont.

BONAIRE, an ifland, almost uninhabited, on the coast of Venizuela, in the kingdom of Terra Firma, about 20. leagues

leagues from the of Curaçoa, and I It is about 18 lea has a good bay a fide, near the m Here formerly we a fort with a few alfo 5 or 6 Indian maize, yams, pota plenty of cattle an fend falted to Cura is a falt pond her come for falt. N. 68. 18.

BONAMY'S Po fide of Chaleur Bay extremity of Eel 1 the fouth limit of gouche river.

BONAVENTUR. and fort, of S: Am miles E. of Cali. long. 75. 18. It Cali, Papayan, Sa BONAVENTURE of Chaleur Bay, lies New-Carlifle, which milton. It was a commerce, but is n BONAVISTA, CL the E. fide of N The cape lies in 1 long 51; 32; and John Cabot; and h 1497, in the fervice of England. The this cape and that leagues apart:

BONHAMTOWN, New-Jerfey, lies ab from New-Brunfwic BOONE Bay, lies Newfoundland I ; 2

of St. George's Harb BOONETON, a fin fex co. New-Jerfey,

between Rockaway houle; 116 miles fro BOON Island, on Diffrict of Maine, b of York R. and Cap

BOONSBORODGH Kentucky, lies on t tucky R. at the mout 30 miles S. E. of L. fame diftance N. E. I fat. 37. 57.

BOON's Creek, a 1 Kentucky R. a N. W. 1 miles merica. ty Ifles, bot co. s miles N. W. ttenden ut 104 n, havand co. o; and Hart-E. from orcefter N. E. m Bofants .--in this quantina a sister e on the Ifland, Forme ; m Port N. lat. A FALLA mouth ng and rare on ek and iryland r by a o conk Bay, to that. Chefter lombay Capes look to ver, in ne, are lading, They ine, an by the em. 8 miles i, Rut-10. uninela, in out 29 leagues

BOO

leagues from the continent; and 14 E. of Euraçoa, and belongs to the Dutch. It is about 18 leagues in compafs, and has a good bay and road on the S. W. fide, near the middle of the ifland. Here formerly were a few houfes, and a fort with a few foldlers. There were alfo 5 or 6 Indian families who planted maize, yams, potatoes, &c. There are plenty of cattle and goats, which they fend falted to Curaçoa annually: There is a falt pond here, where the Dutch come for falt. N. lat. 12. 16. W. long. 68, 18.

BONAMY'S Point, on the fouthern fide of Chaleur Bay, is at the north-weft extremity of Eel river cove, and forms the fouth limit of the mouth of Riftigouche river.

BONAVENTURA, a bav, harbour, and fort, of S: America, in Papayan, 90 miles E. of Cali. N. lat. 3. 20. W. long. 75. 18. It is the ftaple port of Cali. Papayan, Sante Fe, &c.

BONAVENTURE, on the northern fide of Chaleur Bay, lies about 3 leagues from New-Carlifle, which is now called Hamilton.) It was a place of confiderable commerce, but is now declined.

BONAVISTA, Cape and Bay of, lie on the E. fide of Newfoundland Ifland. The cape lies in N. lat. 48. 15. W. long 51. 32. and was diffeovered by John Cabot; and his fon Sebaffian, in 1497, in the fervice of Henry VII. king of England. The bay is formed by this cape and that of Cape Freels, 15 leagues apart:

BONHAMTOWN, in Middlefex co. New-Jerfey, lies about 6 miles N. E. from New-Brunfwick.

BOONE Bay, lies on the W. fide of Newfoundland I; 22 leagues N. by E. of St. George's Harbour. N. lat. 49.35.

BOONETON, a finall post town in Suffex co. New-Jersey, on the post road between Rockaway and Suffex courthouse; 116 miles from Philadelphia.

BOON Ifland, on the coaft of the District of Maine, between the mouth of York R, and Cape Neddock.

BOONSBORDDER, in Maddifon co. Kentucky, lies on the S. fide of Kentucky R. at the mouth of Otter Creek, 30 miles S. E. of Laxington, and the fame diftance N. E. from Danville. N. lat. 37. 57.

BOON's Creek, a fmall N. branch of Kentucky R.

BOOTH Bay, a town and bay on the coaft of Lincoln co. Diffuict of Maine; in N. lat. 41. 42. about 2 miles weft of Pemaquid Point. The bay firetches within the land about 12 miles, and receives two fmall fireams. On it is a town, having 997 inhabitants.

BOPQUAM, or MeQuant Bay, on the E. fide of L. Champlain, is fituated in Swantown, Vermont, and has Hog I. on the N. at the mouth of Michifcoui R.

BOQUET R. paffes through the town of Willsborough, in Clinton co. New-York, and is navigable for boats about 2 miles; and is there interrupted by falls, on which are mills. At this place are the remains of an entrenchment thrown up by General Burgoyne.

BORDENTOWN, a pleafant town in Burlington co. New-Jerfey, is fituated at the mouth of Crofswick's Creek, on the E: bank of a great bend of Delaware R.; 6 miles below Trenton; 9 N. E. from Burlington, by water, and 15 by land, and 24 miles N. E. from Philadelphia; and through this town, which contains about 100 houfes, a line of ftages paffes from New-York to Philadelphia. The fecond division of Heffians was placed in this town, in December, 1776; and by the road leading to it, 600 men of that nation efcap ed, when Gen. Washington furpriled and made prifoners of 886 privates, and 23 Heffran officers, at Trenton.

BORIQUEN; or Crabs Island. See Bieque.

BORGNE, LE, a town on the north fide of the northern peninfula of the island of St. Domingo, 3 leagues W., by N. of Port Margot, and 8 E. by Se of Port de Paix. N. Iat. 19. 49.

BORJA, a town in Peru, fituated on the head waters of Amazon River.

BORJA, a town in Brazil, on the S. eaftern bank of Uraguay River. S. lat. 29. 15. W. long. 56. 30.

BOSCAWEN, a township in Hillsborough co. New-Hampshire, on the western bank of Merrimack R. above Concord; 43 miles N. W. of Exeter, and 38 S. E. of Dartmouth College; having 1108 inhabitants. Boscawen Hills are in this neighbourhood.

BOSTON, the capital of the date of Maffachufetts, the largeft town in New-England, and the third in fize and rank in the United States, lies in 42. 23. 15. N. lat. and 70. 58. 53. Willong. This town

· 9.

town, with the towns of Hingham, Chelfea and Hull, conftitute the county of Suffolk; 176 miles S. W. of Wifcaffet, 61 S. by W. of Portfmouth, 164 N. E. of New-Haven, 251 N. E. of New-York, 347 N.E. of a Philadelphia, and goo N. E. of the city of Washington. Boston is built upon a peniniula of irregular form at the bottom of Maffachufetts Bay, and is joined to the main land by an ifthmus on the fourth end of the town leading to Roxbury. It is two miles long, but is of unequal breadth; the broadeft part is 726 yards. The peninfula contains about 700 acres (other accounts fay 2000) on which are 2376 dwelling houfes. The number of inhabitants in \$790 was 18,038, but the increase has been very confiderable fince. The town is interfected by 97 ftreets, 36 lanes, and 26 alleys, befides 18 courts, &c. most of these are irregular, and not very convenient. State-ftreet, Common-ftreet, and a few others, are exceptions to this general character; the former is very fpacious, and being on a line with Long Wharf, where ftrangers ufually land, exhibits a flattering idea of the town.

Here are nineteen edifices for public worthip, of which nine are for Congregationalists, three for Episcopalians, and two for Baptifts; the Friends, Roman Catholics, Methodists, Sandemanians, and-Universalists have one each. Most of these are ornamented with beautiful fpires, with clocks and bells. The other public buildings are the State-Houfe, Court-Houfe, two Theatres, Concert Hall, Faneuil Hall, Gaol, an Alms-Houfe, a Work-Houfe, a Bridewell and Powder Magazine. Franklin Place, adjoining Federal-freet Theatre, is a great ornament to the town; / it contains a monument of Dr. Franklin, from whom it takes its name, and is encompafied on two fides with buildings, which, in point of elegance, are not exceeded, perhaps, in the United States. Here are kept in capacious rooms, given and fitted up for the purpofe, the Bofton Library, and the valu-able Collections of the Hiftorical Society. Most of the public buildings are handfome, and fome of them are elegant. A magnificent State-Houle is now erecting in Bofton, on the S. fide of Beacon Hill, fronting the Mall, the corner frone | feet into the harbour in a fraight line,

of which was laid with great formality and parade on the 4th of July, 1795; and which overtops the monument on Beacon Hill.

The Market Place, in which Faneuil Hall is fituated, is fupplied with all kinds of provisions which the country affords. The fifth market in particular, by the bounteous supplies of the ocean and rivers, not only furnishes the rich with the rareft productions, but often provides the poor with a cheap and grateful repait.

Bofton Harbour, is formed by Point Alderton on the S. and by Nahant Point on the N. The harbour is capacious enough for 500 veffels to ride at anchor in good depth of water; whilft the entrance is fo narrow as fcarcely to admit two flrips abreaft. It is va+ riegated with about forty islands, of which fifteen only can be properly called fo; the others being fmall rocks or banks of fand, flightly covered with verdure. Thefe iflands afford excellent pasturage, hay and grain, and furnish agreeable places of refort in fummer to parties of pleafure. Caftle Ifland is about three miles from the town; its fortifications, formerly called Caftle William, defend the entrance of the harbour. It is garrifoned by about 50 foldiers, who ferve as a guard for the convicts, who are fent here to hard labour. The convicts are chiefly employed in making nails.

The Light Houfe ftands on a fmall island on the N. entrance of the channel, (Point Alderton and Nantafket Heights being on the S.) and is about 65 feet high. To fteer for it from Cape Cod, the courfe is W. N. W. when within one league of the Cape'; from Cape Cod to the Light-House is about 16 leagues ; from Cape Ann the course is S. W. diftant 10 leagues. A cannon is lodged and mounted at the Light Houfe to answer fignals.

Only feven of the iflands in the bay are within the jurifdistion of the town, and taxed with it, viz. Noddle's, Hog, Long, Deer, Spectacle, Governor's and Apple Islands.

The wharves and quays in Bofton are about eighty in number, and very convenient for veffels. Long Wharf, or Bofton Pier, in particular, extends from the bottom of State freet 1743 The

The breadth i are 17 feet of joining to this convenient what from the name and its form. with fresh water by falt water, at a great exp covered on the and commodiou refpect exceeds in the United 1796, a compar cut a canal bet Roxbury, which The view of proached from t ful and picturelq lar and pleafingly the harbour, and fpires, above wh Beacon Hill rifes top is a gilt eagle the Union, and o lumn are infcript fome of the most the late war. Be eft ground on th fords a most del profpect. The C tains about 45 a refreshing breezes the Mall, a very 500 yards in lengt of trees, to which 100 yards has Charles River and are highly ufeful Bofton ; and both a which mingles its of Myflic River, Charles River brid with Charleftown i and is 1503 feet l ftands on 75 piers, bers 50,000 dollars 19, 1787.

Weft Bofton bridge

180 piers, is Bridge over the gor Abutment Bofton fi Cauleway,

Distance from the e Caufeway to C

meeting-houfe, idth of the Bridge

This beautiful

formality Y, 1795; ument on

h Faneuil with all e country particular, the ocean the rich but often cheap and 1 by Point

y Nahant ur is capato ride at ter; whilft as fcarcely It is va+ iflands, of : properly fmall rocks vered with rd excellent ind furnish fummer to e Ifland is town; its lled Caftle nce of the y about 50 ard for the re to hard chiefly em-

on a fmall of the chany Nantafket id is about t from Cape . W. when Cape; from ufe is about n the courfe . A cannon the Light

in the bay of the town, die's, Hog, vernor's and

s in Bofton r, and very ong Wharf, ilar, extends freet 1743 fraight line, The

The breadth is 104 feet. At the end are 17 feet of water at ebb tide. Adjoining to this wharf on the north is a convenient wharf called Minot's T, from the name of its former proprietor and its form. Veffels are supplied here with fresh water from a well furrounded by falt water, which has been dug at a great expence. Long Wharf is covered on the north fide with large and commodious ftores, and in every respect exceeds any thing of the kind in the United States. In February, 1796, a company was incorporated to cut a canal between this harbour and Roxbury, which is nearly completed.

The view of the town as it is approached from the fea, is truly beautiful and picturefque. It lies in a circular and pleafingly irregular form round the harbour, and is ornamented with fpires, above which the monument of Beacon Hill rifes pre-eminent; on its top is a gilt eagle bearing the arms of the Union, and on the bale of the column are infcriptions, commemorating fome of the most remarkable events of the late war. Beacon hill is the higheft ground on the peninfula, and affords a most delightful and extensive prospect. The Common below it contains about 45 acres always open to refreshing breezes; on its east fide is the Mall, a very pleafant walk above 500 yards in length, adorned with rows of trees, to which an addition of about 100 yards has been lately added. Charles River and Weft Bofton bridges are highly useful and ornamental to Bofton ; and both are on Charles River, which mingles its waters with those of Myflic River, in Boston harbour. Charles River bridge connects Bofton with Charleftown in Middlefex county, and is 1503 feet long, 42 feet broad, ftands on 75 piers, and colt the fubfcribers 50,000 dollars. It was opened June 19, 1787.

	reet long.
Weft Bofton bridge ftands on	1.1.1.1.1.1.1
180 piers, is	3483
Bridge over the gore, 14 piers,	275
Abutment Bofton fide,	871
Caufeway,	334
Diftance from the end of the	334
Caufeway to Cambridge	
meeting-houfe,	7810
idth of the Bridge,	40
This beautiful bridge exce	eds the

other as much in elegance as in length, and coft the fubscribers 76,700 dollars Both bridges have draws for the admiffion of veffels, and lamps for the

benefit of evening paffengers. Seven Free Schools are fupported here at the public expence, in which the children of every clafs of citizens may freely affociate together. The number of fcholars is computed at about 900, of which 160 are taught Latin, &c. There are belides thefe many private fchools.

The principal focieties in the Commonwealth hold their meetings in this town, and are, the Marine Society, American Academy of Arts and Sciences, Maffachuletts Agricultural Society, Maffachuletts Charitable Society, Bofton Episcopal Charitable Society, Maffachufetts Hiltorical Society, Society for propagating the Gofpel, Maffachufetts Congregational Society, Medical Society, Humane Society, Bofton Library Society, Bofton Mechanic Affociation, Society for the aid of Emigrants, Charitable Fire Society, and feven refpectable Lodges of free and accepted Mafons.

The foreign and domeftic trade of Bofton is very confiderable, to fupport which there are three Banks, viz. the Branch of the United States Bank, the Union, and the Maffachuletts Bank the latter confifts of 800 fhares of 500 dollars, equal to 400,000; the capital of the Union Bank is, 1,200,000 dollars, 400,000 of which is the property of the State.

In 1748, 500 veffels cleared out of this port for, and 430 were entered from, foreign parts. In 1784, the entries of foreign and coalting vefiels were 372, and the clearances 450. In 1794, the entries from foreign ports were 567. In 1795, thefe entries amounted to 725, of which the fhips were 96, barques 3, fnows 9, polacre 1, brigs 185, dogger 1, schooners 362, fhallop 1, and floops 65. The principal manufactures confiit of rum, loaf-iugar, beer, fail-doth, cordage, wool and cotton cards, playing cards, pot and pearl alles, paper hangings, hats, plate, glais, tobacco, and chocolate, There are thirty diffilleries, two hreweries, eight fugar houses, and eleven ropewalks.

Eight years ago, the intercourse with the

52

the country barely required two ftages and twelve horfes, on the great road between this and New-Haven, diffant 164 miles; whereas there are now 26 carriages and 100 horfes employed. The number of the different ftages that run through the week from this town is upwards of 20, eight years ago there were only three.

Attempts have been made to change the government of the town from its prefent form to that of a city; but this measure, not according with the democratic spirit of the people, has as yet failed. At an annual meeting in March, nine Selectmen are chosen for the government of the town ; at the fame time a .tchofen a Town Clerk, a Treafurer, 12 Overfeers of the Poor, 24 Fire-wards, 12 Clerks of the Market, 12 Scavengers, 12 Conftables; befides a number of other officers. If the inhabitants do not reap all the advantages they have a right to expect from their numerous officers, it is not for want of wholefome laws for the regulation of the weights, measures and quality of provisions, or other branches of police, but, becaufe the laws are not put in execution.

Befides those called Trained Bands, there are four other military companies in Boston, viz. the Ancient and Honourable Artillery Company, the Cadets, Fusileers and Artillery. The Ancient and Honourable Artillery Company was incorporated in 1638, and the election of a captain and officers of it for the year is on the first Monday in June annually, which is observed here as a day of festivity. Several officers in the American army, who fignalized themfelves in the late war, received their first knowledge of tactics in this military school.

Bofton was fettled as early as 1631, from Charleftown; it was called Shaumut by the Indians; Trimountain by the fettlers in Charleftown, from the view of its three hills; and had its prefent name in token of refpect to the Rev. Mr. Cotton, a minister of Bofton in England, and afterwards minister of the first church here. Bofton was greatly damaged by an earthquake in October 29, 1727, and fince that time has fuffered feverely by numerous fires, the house being mostly built of wood. The last large fire happened July 30,

1794, and confumed 96 houfes, ropewalks, &c. and the account of loffes given in by the fufferers amounted to 209,861 dollars.

It was in Bofton that the Revolution originated which gave independence to America, and from thence flew like an electrical flock throughout the Union. It fuffered much at the commencement of the war, by the lofs of an extensive trade, and other calamities. Bofton feels a pride in having given birth to Benjamin Franklin, and a number of other patriots, who were among the most active and influential characters in effecting the revolution.

BOSTON Corner, a tract of land adjoining Mount Washington, Berkshire co. Massachusetts, containing 67 inhabitants.

BOSTON, NEW, a township in Hillfborough co. New-Hampshire, containing 1202 inhabitants; 12 miles S. W. by W. from Amuskeag Falls; 60 miles W. of Portsmouth, and a like distance N. W. of Boston.

BOTETOURT, a county in Virginia, on the Blue Ridge, W. of which are the Sweet Springs, about 42 miles from the Warm Springs. Its chief town is Fincaftle.

BOTTLEHILL, a village in Somerset co. New-Jersey, z miles N. W. from Chatham, and 15 N. W. of Elizabethtown.

BOUDOIR, LE, a fmall ifland in the Pacific Ocean, S. lat. 17. 52. W. long. from Paris, 15. 25. diffeovered April 2, 1768, by Bougainville. This ifland, the year before, had been diffeovered by Wallis, and named Ofnaburg.—The natives call it Maitea, according to the report of Capt. Cook, who vilited it in 1769. Quiros diffeovered this ifland in 1666, and called it la Dezana. See Ofnaburg.

BOUGAINVILLE's Straits, are at the N. W. end of the ifles of Solomon.

BOUGIE Inlet, on the coaft of North Carolina, between Core Sound and Little Inlet.

BOUNDBROOK, a village in Somerfet co. New-Jerfey, on the N. bank of Rariton River.

BOURBON, a county, laid out and organized in the year 1785, by the State of Georgia, in the fouth-weft corner of the State, on the Miffifippi, including the Natchez country. The The laws of G into effect in been under the niards fince the of the country given up to the treaty of 1795. effablishing the is now in force. BOURBON F Martinico, in the BOURBON C Licking and 1 tains 7837 inhal flaves.

BOURBON, a of the above cor of land formed 1 branches of Lic E. of Lexington non, and 749 W phia, and contai Baptift church, a There are feven vicinity.

Bow, is a to oo. New-Hampf of Merrimack R. 53 miles from Pou 568 inhabitants.

Bowdoin, a co. diffrict of M: bank of Androfec York N. eafterly the mouth of K. and 166 N. E. of 983 inhabitants.

BOWDOINHAN coln co. diffrict from Pownalboro wich S. E. by K 455 inhabitants, a E. from Bofton.

BOWLING Gre ginia, on the poft Fredericksburg, 4 and 25 N. of Ha

BOXBOROUGH dlefex co. Maffa \$12 inhabitants; Bofton.

BOXFORD, a fm co. Maffachufetts, tants. It lies on t rimack R. 7 miles port. In the fout parifhes is a bloom BOYLSTON, a 1 ter co. Maffachufe

fes. TOT of loffes jounted to

Revolution indence to flew like thout the t the comthe loss of calamities. ing given and a numrere among ial charac-

n. of land ad-Berkfhire

g 67 inha-

ip in Hillf-:, containiles S. W. 1; 60 miles ke diftance

n Virginia, which are miles from ief town is

in Somerfet . W. from Elizabeth-

fland in the 2. W. long. red April 2, is ifland, the fcovered by burg.-The ccording to who vifited overed this la Dezana.

is, are at the Jolamon. aft of North ind and Lit-

e in Somerfet N. bank of

laid out and 185, by the e fouth-weft the Miffihez country. The BOY

The laws of Georgia were never carried into effect in this county, and it has been under the jurifdiction of the Spaniards fince their conquest of this part of the country in 1780, till it was given up to the United States by the treaty of 1795. The law of Georgia, effablishing the county of Bourbon, is now in force. See Louisiana.

BOURBON FORT, in the island of Martinico, in the West-Indies.

BOURBON Co. in Kentucky, between Licking and Kentucky rivers, contains 7837 inhabitants, including 908 flaves.

BOURBON, a post town and capital of the above county, stands on a point of land formed by two of the fouthern branches of Licking R.; 22 miles N. E. of Lexington, 21 eatterly of Leba-non, and 749 W. S. W. from Philadelphia, and contains about 60 houfes, a Baptift church, a court-houfe and gaol. There are feveral valuable mills in its vicinity.

Bow, is a township in Rockingham co. New-Hampfhire, on the W. bank of Merrimack R. a little S. of Concord. 53 miles from Portimouth. It contains 568 inhabitants.

BOWDOIN, a township in Lincoln co. diffrict of Maine, on the N. eaftern bank of Androscoggin R.; distant from York N. easterly, 36 miles, and from the mouth of Kennebeck R. 6 miles, and 166 N. E. of Boston. It contains 983 inhabitants.

BOWDOINHAM, a township in Lincoln co. diffrict of Maine, feparated from Pownalborough E. and Wool-wich S. E. by Kennebeck R. It has 455 inhabitants, and lies 171 miles N. E. from Bofton.

BOWLING Green, a village in Virginia, on the post road, 22 miles S. of Fredericksburg, 48 N. of Richmond, and 25 N. of Hanover court-houfe.

BOXBOROUGH, a township in Middlefex co. Maffachufetts, containing Bolton.

BOXFORD, a fmall township in Effex co. Maffachusetts, having 925 inhabitants. It lies on the S. E. fide of Merrimack R. 7 miles wefterly of Newburyport. In the fouthernmost of its two parifhes is a bloomery.

BOYLSTON, a township in Worcester co. Maffachufetts, having \$39 inhabitants ; 10 miles N. E. of Worcefter, and 45 N. W of Bolton. It was incorporated in 1786, having been a parifh of Shrewfbury fince 1742; and contains by furvey, 14,396 acres of land, well watered, and of a rich foil.

BOZRAH, a town in New-London co. Connecticut, formerly a parish in the town of Norwich, 36 miles E. from Hartford.

BRADDOCK's Field, the place where Gen. Braddock, with the first division of his army, confifting of 1400 men, fell into an ambufcade of 400 men, chiefly Indians, by whom be was defeated and mortally wounded, July 9, 1755. The American militia, who were difdainfully turned in the rear, continued unbroken, and ferved as a rear guard, and, under Col. Washington, the late Prefident of the U. S. A. preferved the regulars from being en-tirely cut off. It is fituated on Turtle Creek, on the N. E. bank of Monongahela R. 6 miles E. S. E. from Pittfburg.

BRADDOCK's Bay, on the S. fide of Lake Ontario, 42 miles W. from Great Sodus, and 65 E. from Fort Niagara.

BRADFORD, East and West, are townthips in Chefter co. Pennfylvania.

BRADFORD, a township in Effex co. Maffachusetts, fituated on the S. fade of Merrimack R. opposite Haverhill, and 10 miles W. of Newbury port. It has two parifhes, and 1371 inhabitants. Quantities of leather shoes are made here for exportation; and in the lower parifh some veffels are built. Several ftreams fall into the Merrimack from this town, which fupport a number of mills of various kinds.

BRADFORD, a township in Hillsborough co. New-Hampfhire, containing 217 inhabitants, incorporated in 1760; 20 miles E. of Charlettown.

BRADFORD, a township in Orange co. Vermont, on the W. bank of Connecticut R. about 20 miles above Dartmouth College, having 6 54 inhabitants. There is a remarkable ledge of rocks in this township, as much as 200 feet. high. It appears to hang over, and threaten the traveller as he paffes. The fpace between this ledge and Connecticut River is fcarcely wide enough for a road.

BRAGA, HA, now Fort Dauphin, in the ifland of Cuba. Ds

BRAINTREE

BRAINTREE, a township in Orange co. Vermont, lies 75 miles N. eaftward of Bennington. It joins Kingfton weftward, Randolph on the eaftward, and contains 221 inhabitants.

BRAINTREE, one of the molt ancient townships in Norfolk co. in the state of Maffachuletts, was fettled in 1625, and then called Mount Woolaston, from the name of its founder. It lies on a bay, 8 miles E. of S. from Bofton, and contained, before its division, 400 houses and 2771 inhabitants. Great quantities of granite ftones are fent to Bofton from this town for fale. The bay abounds with fifh and fea fowl, and particularly brants. This town is noted for having produced, in former and latter times, the first characters both in church and state; and, in distant ages, will derive no fmall degree of fame, for having given birth to JOHN ADAMS, the first Vice-Prefident, and the second Prefident of the United States of Ame-rica; a man highly diffinguished for his patriotism, as a citizen; his justice, integrity, and talents, as a lawyer; his profound and extensive crudition, as a writer; and his difcernment, firmnefs, and fuccels, as a foreign minister and ftatefman.

BRANDON, a harbour on the N. fide of Long Ifland, New-York, 9 miles W. of Smithtown, and the fame. diftance from Hampftead Plain.

BRANDON, a township in Rutland co. Vermont, fituated on both fides of Otter Creek, containing 637 inhabitants, and is about 60 miles northerly from Bennington. Here Brandon Creek empties into Otter Creek from the N.E.

BRANDY POTS, are ifles fo called, in the river St. Lawrence, 40 leagues below Quebec.

BRANDYWINE Creek, falls into Chriftiana Creek from the northward, at Wilmington, in Delaware ftate, about 25 miles from its N. and N. weftern fources, which both rife in Chefter co. Pennfylvania. This Creek is famous for a /bloody / battle, fought Sept. 11, 1777, between the British and Americans, which lafted nearly the whole day, and the latter were defeated with confiderable lofs : but it was far from being of that decifive kind which people had been led to expect, in the event of a meeting between the hoftile armies, on nearly equal terms, both as to middle division-5 captainships, viz. LASHIA AL

numbers, and the nature of the ground on which each army was fituated. It was fought at Chadd's Ford, and in the neighbourhood of, and on, the ftrong grounds at Birmingham church. See Delaware, for an account of the celebrated mills on this creek.

BRANDYWINE, a township in Chefter co. Pennfylvania.

BRANFORD, a townflup in New-Haven co. Connecticut, confiderable for its iron works. It lies on the S. fide of a river of the fame name, which runs into Long Ifland Sound, 10 miles E. from New-Haven, and 40 S. of Hartford.

BRASS D'OR, called alfo Labrador, a lake which forms into arms and branches, in the ifland of Cape Breton, or Sydney, and opens an easy communication with all parts of the ifland. See Breton, Cape.

BRASS Ifland, one of the fmaller Vir-gin iflands, fituated near the N. W. end of St. Thomas's Ifland, on which it is dependent.

BRASS Town, in the flate of Tenneffee, is fituated on the head waters of Hiwaffee R. about 100 miles foutherly from Knoxville. Two miles S. from this town, is the Enchanted Mountain, much famed for the curiofities on its rocks. 'See Enchanted Mountain.

BRATTLEBOROUGH, a confiderable township and post town, in Windham co. Vermont, having 1589 inhabitants ; on the W. bank of Connecticut R. about 28 miles E. of Bennington, 61 N. of Springfield, in Maffachufetts, and 311 from Philadelphia. N. lat. 42. 52.

BRAZIL, or Brafil, comprehends all the Portuguele fettlements in America, and is fituated between the equator, and 35. S. lat. and between 35. and 60 W. long.; and is in leugth 2,500 miles, and in breadth 700 miles. Bounded by the mouth of the river Amazon, and the Atlantic ocean on the N.; by the fame ocean on the E.; by the mouth of the river Plata, S; and by moraffes, lakes, torrents, rivers, and mountains, which feparate it from Amazonia and the Spanish possessions, on the W. It has three grand divisions .-1. The northern contains 8 provinces or captainfhips, viz. Para, Marignan, Siara, Petagues, Rio Grande, Payraba, Tamara, and Pernambuco. 2. The Seregippe,

Seregippe, B Saints, Icheos rito Sancto. -3 captainfly Vincent, and of confiderable St. Salvadore. is the chief, a the fecond in a On the coat

where fhips ! their voyage to mando, St. Bar The bays, har harbours of] Porto Seguro Rio de Janeiro the harbour of of St. Salvado river La Plata The climate and mild, whe Africa ; owing wind, which the fca. The chilly daring t tives kindle a f huts. The rin nually overflow the Nile leave lands; and the amazingly rich ductions are, I tobacco, indig brazil wood. lour, hard and in dying, but a kind. Here is ufe in dying) kind of ipeckle work. Here a palm trees, cur variety of cotto abounds in ho. hunted for their ing fent annuall great plenty of game. Befides the neighbouring are janouveras. fomewhat like a raflou, a creatu and afs, but wit harmlefs, the fle the flavour of birds are the hu ma, fometimes (from its having

tong, growing o

he ground nated. It and in the the ftrong urch. See i the cele-

p in Chef-

New-Haerable for the S. fide ne, which 10 miles 40 S. of

Labrador, arms and be Breton, y commuhe ifland.

e N. W. on which

e of Tenad waters iles fouthmiles S. ted Mounriofities on untain. onfiderable Windham habitants ; ecticut R. ton, 61 N. fetts, and at. 42. 52. ehends all America, juator, and ind 60 W. soo miles, Bounded Amazon, ie N ; by ; by the ; and by ivers, and from Amachions, on ivitions .provinces Marignan, , Payraba, 2. The hips, viz. Seregippe, BRA

Seregippe, Bahia, or the Bay of All Saints, Ifheos, Porto Seguro, and Spirito Sancto 3. The fouthern division -3 captainflips, viz. Río Janeiro, St. Vincent, and Del Rey. The number of confiderable cities, are 16; of thefe St. Salvadore, in the Bay of All Saints, is the chief, and is the capital of Brazil; the fecond in rank is Rio de Janeiro.

On the coaft are three fmall iflands, where fhips touch for provisions on their voyage to the South Seas, viz. Fermando, St. Barbaro, and St. Catherine's. The bays, harbours, and rivers, are the harbours of Pernambuco, All Saints, Porto Seguro, the port and harbour of Rio de Janeiro, the port of St. Vincent, the harbour of St. Gabriel, and the port of St. Salvadore, on the N. fhore of the river La Plata.

The climate of Brazil is temperate and mild, when compared with that of Africa ; owing chiefly to the refreshing wind, which blows continually from the fea. The air is not only cool, but chilly during the night, fo that the natives kindle a fire every evening in their huts. The rivers in this country annually overflow their banks, and like the Nile leave a fort of flime upon the lands; and the foil is in many places amazingly rich. The vegetable productions are, Indian corn, lugar canes, tobacco, indigo, balfam, ipecacuanha, brazil wood. The last is of a red colour, hard and dry; and is chiefly ufed in dying, but not the red of the beft kind. Here is also the yellow fultic, of ufe in dying yellow, and a beautiful kind of speckled wood used in cabinet work. Here are five different forts of palm trees, curious ebony, and a great variety of cotton trees. This country abounds in horned cattle, which are hunted for their hides only, 20,000 being fent annually to Europe. There is great plenty of deer, hares and other game. Befides the beafts common in the neighbouring parts of the continent, are janouveras, and a fierce animal fomewhat like a grey-hound, the topiraflou, a creature between a bull and and afs, but without horns, and entirely harmlefs, the fiefh is very good, and has the flavour of beef. The remarkable birds are the humming bird; the lankima, fometimes called the unicorn bird, from its having a horn, 2 or 3 inches tong, growing out of its forehead; the

guira, famcus for changing its colour often, being first black, then ash coloured next white, afterwards fcarlet, and laft of all crimfon ; which colours grow deep-er and richer the longer the bird lives. Of fifh, there is one called the globe fifh, fo called from its form, which is to befet with fpikes like a hedgehog. that it hids defiance to all fifh of prey. Brazil breeds a variety of ferpents and venomous creatures, among which are the Indian falamander, a four legged infect, whole fting is mortal; the ibivaboca, a species of serpent, about 7 yards long, and a half yard in circumference, whole poifon is instantaneously fatal; the rattlefnake attains there an enormous fize; the liboyd, or roebuck fnake, which authors fay are capable of fwallowing a roebuck whole with his horns, being between 20 and 30 feet in l-ngth, and fix feet in circumference, There is a numberless variety of fowl, wild and tame in this country.

The trade of Brazil is very great, and increafes every year. They import as many as 40,000 negroes innually. The exports of Brazil are diamonds, gold, fugar, tobacco, hides, drugs, and medicines; and they receive in return, woolen goods of all kinds, linens, laces, filks, hats, lead, tin, pewter, copper, iron, beef, and cheefe. They alfo receive from Madeira, a great quantity of wine, vinegar and brandy; and from the Azores, £. 25,000 worth of other liquors.

The gold and diamond mines are but a recent difcovery ; they were first opened in 1681, add have fince yielded above five millions fterling annually, of which a fifth part belongs to the crown. Thefe, with the fugar plantations, occupy fo many hands, that agriculture lies neglected, and Brazil depends upon Europe for its daily bread ; although before the difcovery of these mines, the foil was found very fufficient for fubfifting the inhabitants. The diamonds here are neither fo hard, nor fo clear as those of the East Indies, neither do they fparkle fo much, but they are whiter, the Brazilian diamonds are fold ten per cent cheaper than the oriental ones, supposing the weights to be equal. The crown revenue arising from this colony amounts annually to two millions sterling in gold, if some late writers are to be credited, befides D 4 the

he duties and cuftoms on merchandize imported from that quarter. This indeed, is more than a fifth of the precious metal produced by the mines; but every other confequent advantage confidered, it probably does not much exceed the truth.

The Portuguele here live in the most effeminate luxury. When people appear abroad they are carried in a kind of cotton hammocks, called ferpentines, which are borne on negroes' fhoulders : fimilar to palaquins in India. The portrait drawn of the manners, cuftoms, and morals of that nation, in America, by judicious travellers, is very far from being fayourable.

The native Brazilians are about the fize of the Europeans, but not fo ftout. They are fubject to fewer diffempers, and are long lived. They wear no clothing; the women wear their hair extremely long, the men cut their's thort; the women wear bracelets of bones of a beautiful white; the men necklaces of the fame; the women paint their faces, and the men their bodies.

Though the king of Portugal, as rand master of the Order of Christ, be folely in poffeffion of the titles, and though the produce of the crufade belongs entirely to him ; yet in this extenfive country, fix bishopricks have been successively founded, which acknowledge for their fuperior the archbishop of Bohia; which see was established in 1552. One half of the 16 captainfhips, into which the country is divided, belong to the crown; the others being fiels made over to fome of the nobility, who do little more than acknowledge the fovereignty of 'the king of Portugal.

The Portuguefe difcovered this country in 1500, but did not plant it till the year 1549, when they took poffer-fion of All Saints Bay, and built the ci-ty of St. Salvadore. The Dutch invaded Brazil in 1623, and fubdued the northern provinces; but the Portu-guefe agreed in 1661, to pay the Dutch eight tons of gold, to relinquish their interest in this country, which was accepted; and the Portuguele remained in peaceable pofferfion of Brazil, till about the end of 1762; when the Spanish governor of Buenos Ayres, hearing

took, after a month's fiege, the Porteguele frontier fortrefs, St. Sacrament ; but by the treaty of peace it was reftored.

BREAKNECK Hill, opposite Butterhill, at the northern entrance of the highlands, in Hudfon R. about 60 miles N. of New-York. On the S. fide of this hill, about half the diftance as you afcend it, the rocks are fo fituated as to give the fpectator a tolerable idea of a human face, with a nofe, mouth and double chin, but without a forehead. On the noie grows a tree of confiderable fize, which has the appearance only of a fhrub.

BRECKNOCK, a township in Lancaster co. Pennfylvania.

BREME, a cape which forms the S. eaftern fide of the mouth of Oroonoka R. oppofite Cape Araya, in S. America.

BRENTON's Reef, about 3 miles from Newport, is the fouthernmost point of Rhode-Island, about 2 miles E. of Beaver Tail. These two points form the mouth of Newport harbour.

BRENTWOOD, a township in Rockingham co. New-Hampfhire, having 976 inhabitants; diftant 7 miles W, from Exeter, and 19 from Portfmouth. Vitriol is found here, combined in the fame ftone with fulphur.

BRETON, CAPE. The island, or rather collection of iflands, called by the French Les Ifles de Madame, which lie fo contiguous as that they are commonly called but one, and comprehended under the name of the Ifland of Cape Breton, lies between lat. 45. 28. and 47. N. and between 59. 44. and 61. 29. W. long, and about 45 leagues to the eastward of Halifax. It is about 109 miles in length, and from 20 to 84 in breadth; and is feparated from Nova-, Scotia by a narrow firait, called the Gut of Canfa, which is the communication between the Atlantic Ocean and the Gulf of St. Lawrence.

It is furrounded with little flarp pointed rocks, leparated from each other by the waves, above which fome of their tops are vilible, and interfected with lakes and givers. The great Brafs d'Or is a very extensive fheet of water which forms into arms and branches, and opens an easy communication with all parts of the illand. All its harbours are open to the east, turning towards of a war between Portugal and Spain, the fouth. On the other parts of the coaft

coaft there places for in between iflets. ter's at the w very commod the fiftery. ed as annexed to matters o when it was e vernment by t There is a land on this it timber and h beach, birch,

Here are a who have a lie among them, Ifle Madame, this governmen part with Fre families, whole filhery at Afhn in this little towns are Sydne bourg, which l ifland. The p is at Spanish ri the island.

This ifland 1 key to Canada, fifhery in its ne. its protection c ifland; as no 1 without fome strength to fup Louisburg is the purpofes. The peltry tr confiderable ob in the fkins of a rats, wild cats, I both of a red, f Some of thefe w lony of Micmac tled on the Ifland never could rai able to bear arms St. John's, on tinent. Greater derived from the situated near the bour, the worki fifhery, are the c inhabitants. Th direction; and b 8 feet below the f ed without diggi off the waters.

prodigious deman

e Portecrament a was re-

Butter-

e of the t 60 miles I. fide of te as you ted as to idea of a outh and forehead. onfiderance only Lancafis the S. Iroonoka Imerica. iles from point of of Beaorm the 1 Rockhaving iles W. fmouth. I in the and, or lled by , which re comrehendof Cape 28. and 61. 29. to the out 109 0 84 in Novathe Gut nication nd the fharp n each h fome erfected it Brafs water anches, n with arbours.

owards

of the coaft BRE

coaft there are but a few anchoring places for finall veffels, in creeks, or between iflets. 'The harhour of St. Peter's at the west end of the island, is a very commodious place for carrying on the fifhery. This ifland was confidered as annexed to Nova-Scotia in respect to matters of government till 1784, when it was erected into a feparate government by the name of Sydney.

There is a great proportion of arable land on this ifland; and it abounds in timber and hard wood, fuch as pine, beach, birch, maple, fpruce, and fir.

Here are about 1000 inhabitants, who have a lieutenant governor refident among them, appointed by the king. Ifle Madame, which is an appendage to this government, is fettled for the moft part with French Acadians, about 50 families, whole chief employment is the filhery at Afhmot, the principal harbour in this little island. The principal towns are Sydney, the capital, and Louifbourg, which has the beft harbour in the ifland. The prefent feat of government is at Spanish river, on the north lide of the island.

This ifland may be confidered as the key to Canada, and the very valuable fifthery in its neighbourhood depends for its protection on the poffeffion of this island; as no nation can carry it on without fome convenient harbour of ftrength to supply and protect it, and Louisburg is the principal one for these purpoles.

The peltry trade was ever a very inconfiderable object. It confifted only in the fkins of a few lynxes, elks, mufkrats, wild cats, bears, otters, and foxes, both of a red, filver and grey colour. Some of these were procured from a colony of Micmac Indians, who had fettled on the Island, with the French, and never could raife more than 60 men able to bear arms. The reft came from St. John's, on the neighbouring continent. Greater advantages are now derived from the coal mines which are fituated near the entrance of the harbour, the working of which, and the fishery, are the chief employment of the inhabitants. They lie in a horizontal direction; and being no more than 6 or 8 feet below the furface, may be worked without digging deep, or draining off the waters. Notwithstanding the prodigious demand for this coal from tor Brewer, about the year 1643.

New-England, from the year 1745 to 1749, these mines would probably have been forfaken, had not the fhips which were fent out to the French illands wanted ballaft. In one of these mines a fire has been kindled, which could never yet be extinguished. These mines yield a revenue of L.12,000 yearly to the crown.

In 1743, while this ifland belonged to the French, they caught 1,149,000 quintals of dry fifh, and 3,500,000 do. of mud-fifh, the value of both which. including 3, 1164 tons of train oil, drawn from the blubber, amounted to £926, 577 10s. fterling, according to the prime coft of the fifh at Newfoundland. The whole value of this trade, annually, at that period, amounted to a million sterling. No lefs than 564 thips, befides thallops, and 27,000 feamen, were employed in this trade. At prefent the inhabitants of this island take about 30,000 quintals of fifh, annually, which are thipped for Spain and the Straits, principally by merchants from Jerfey (in England) who yearly refort here, and keep ftores of fupplies for the fifnermen.

Though fome fifhermen had long reforted to this ifland every fummer, the French, who took pofferfion of it in August, 1713, were properly the first fettled inhabitants. They changed its name into that of Ifle Royale, and fixed upon Fort Dauphin for their principal fettlement. In 1720, the fortifications of Louisburg were begun. The other fettlements were at Port Touloufe. Neruka, &c. The island remained in the poffestion of the French till 1745. when it was captured by the New-England militia under the command of William Pepperell, Efg. a colonel of the militia, and a fquadron under commodore Warren. It was afterwards refored to the French, and again taken in 1758, by admiral Boscawen and General Amherst, when the garrison, confifting of 5600 men, were made prifoners; and 11 men of war in the harbour, were either taken, funk, burnt, or deftroyed; and it was ceded to Great Britain by the peace of 1763.

BREWER, a ftrait in the Magellanic. fea, about the ifland called Staten Land, which parts it from the ftraits Le Maire. It was discovered by the Dutch naviga-

BREWER'S

BREWER'S-HAVEN, a good harbout, at the N. end of the island of Chiloe, on the coaft of Chili, in S. America, and in the S. Sea. Lat. 42. 30. long. 74. W.

BREWINGTON, FORT, lies in the townfhip of Mexico, New-York, and at the W. end of Lake Oneida, about 24 miles S. E. from Fort Ofwego.

BRIAR Creek, a water of Savannah R. in Georgia. Its mouth is about 50 miles S. E. by S. from Augusta, and 55 N. westerly from Savannah. Here Gen, Prevolt defeated a party of 2000 Americans, under Gen. Ash, May 3, 8779; they had above 300 killed and taken, besides a great number drowned in the river and swamps. The whole artillery, baggage and fores were taken.

BRIDGETOWN, in Cumberland co. district of Maine, having Hebron on the N. W. and Bakerstown (on the W. fide of Androicoggin R.) on the S. E. which three fettlements lie on the northern fide of Little Androscoggin R. It contains 329 inhabitants, and lies 34 miles N. by N. W. from Portland, and 156 N. E. from Bolton. Bridgetown confifts of large hills and vallies : the highland affords red oak, which are often three feet, and sometimes four, in diameter ; and 60 or 70 feet without any branches. The vallies are covered with rock maple, bafs, afh, birch, pine, and hemlock. There is a curiofity to be feen in Long Pond, which lies mostly in Bridgetown, which may afford matter of fpcculation to the natural philosopher. On the easterly fide of the pond is a cove which extends about 100 rods farther E. than the general courfe of the thore, the bottom is clay, and to thoal that a man may wade so rods into the pond. On the bottom of this cove are fones of yarious fizes, which it is evident from various circumftances, have an annual motion towards the fhore; the proof of whis is the mark or track left behind them, and the bodies of clay driven up before them. Some of these ftones are a or 3 tons weight, and have left a track of feveral rods behind them; having at leaft a common cart-load of clay before them, The fhore of the cove is lined with these frones, which it would feem, have crawled out of the water. See Sebage Pond.

BRIDGETOWN, the chief town of Cumberland ca. New-Jerley, and near

the centre of it. It is 50 miles S. S. E. of Philadelphia; 80 S. by E. of Trenton, and 145 S. W. of New-York. BRIDGETOWN, a post town in Queen

Anne's co. Maryland, lies on the weffern fide of Tuckahoe Creek, 8 miles E. from Centreville, as far S. E from Church Hill, and 65 S. W. from Philadelphia.

Alfo the name of a town in Kent co. in the fame flate, fituated on the N, bank of Chefter R. (which feparates this county from that of Ann) 7 miles S. E. from Crofs Roads; and 4 foutherly from Newmarket.

BRIDGETOWN, in the ifland of Antigua. See Willoughby Bay.

BRIDGETOWN, the metropolis of the ifland of Barbadoes, in the Weft-Indies, lying in the S. W. part of the island and in the parish of St. Michael. It is fituated in the innermost part of Carlifle bay, which is large enough to contain 500 fhips, being 1 league long and one broad; but the bottom is foul and apt to cut the cables. This city was burnt down April 18, 1668. It fuffered alio greatly by fires on Feb. 8, 1756, May 14, 1766, and Dec. 27, 1767, at which times the greatest part of the town was destroyed; before these fires it had 1500 houfes, mostly brick, very elegant, and faid to be the fineft and largest in all the Carribbee islands; the town has The ftreets are fince been rebuilt. broad, the houses bigh, and there is also a Cheapfide, where the rents are as high as those in London. It has a college, founded, and liberally endowed by Col. Codrington, the only inftitution of the kind in the Weft Indies ; but it does not appear that its fuccefs has answered the deligns of the founder. The town has commodious wharfs for loading and unloading goods, and is well defended by a number of forts; but it is very fubject to hurricanes. As the wind generally blows from the E. or N. E. the E. part of the town is called the windward, and the W. part leeward. The number of militia for Bridgetown and St. Michael's precinct is 1200 men, who are called the royal regiment of foot guards. This is the feat of the governor, council, affembly, and court of chancery. About a mile from town to the N. E. the governor has a fine feat built by the affembly, called Pilgrims. The church is as large

large as man organ, and a ous clock. taverns, eati boats have la ry letters to monthly. N. This was Barbadoes in had fcarcely which it had ful fires alrea torn from its country made the ftorm of in which abo miferably pe wind was the blow down even lifted for ramparts and tance; and th general was 1 5s. fterling, ftored to its fo BRIDGEW. ton co. New in 1769, and BRIDGEW. merfet co. No 2,578 inhabit: BRIDGEWA thip in Plym containing 49 N. E. from R E. of S. from quantities of manufactured. BRIDGEWA for co. Vermo of Bennington, ants BRIDPORT. co. Vermont, Champlain; a from Benningt

ants. BRIGANTIN New-Jerley, b Egg Harbour. BRIMFIELD fhire co. Maffa Connecticut R. ants; 34 miles and 75 W. of H BRION 1/le, ifles, in the gu BRISTOL, a diffrict of Main

8

S. S. E. of Tren-York. in Queen the weffmiles E. E from rom Phi-

Kent co. the N, feparates 7 miles fouther-

d of An-

lis of the t-Indies, land and It is fr-[Carlifle contain ; and one and apt as burnt ered alio 16. May at which own was ad 1 500 ant, and at in all own has eets are re is alfo : as high college, by Col. 1 of the it does infwered ie town loading well deput it is As the : E. or is called art leelitia for precinct he royal s is the fembly, t a mile overnor lembly, h is as large large as many cathedrals, has a noble organ, and a ring of bells, with a curious clock. Here are large and elegant taverns, eating-houfes, &c. and packet boats have lately been eftablished to carry letters to and from Great Britain monthly. N. lat. 13.9¹/₂. W, long. 60. 2¹/₂.

BRI

This was the flate of the capital of Barbadoes in the fummer of 1780. It had fcarcely rifen from the afhes to which it had been reduced by the dreadful fires already mentioned, when it was torn from its foundations, and the whole country made a scene of desolation, by the form of the 10th of October 1780, in which above 4000 of the inhabitants miferably perished; the force of the wind was then fo great, as not only to blow down the ftrongeft walls, but even lifted fome pieces of cannon off the ramparts and carried them fome yardsdiftance; and the damage to the country in general was estimated at f. 1,320,504 1 5s. fterling, and it is fcarcely yet reftored to its former splendor.

BRIDGEWATER, a township in Grafton co. New-Hampshire, incorporated in 1769, and contains 281 inhabitants. BRIDGEWATER, a township in Somerset co. New-Jersey, which contains 2,578 inhabitants, including 357 flaves.

BRIDGEWATER, a confiderable townfhip in Plymouth co. Maffachufetts, containing 4975 inhabitants; 5 miles N. E. from Raynham; about 30 miles E. of S. from Bofton, in which large quantities of hard ware, nails, &c. are manufactured.

BRIDGEWATER, a township in Windfor co. Vermont, about 55 miles N. E. of Bennington, 'containing 293 inhabitants

BRIDPORT, a township in Addison co. Vermont, on the E. shore of Lake Champlain; about 72 miles N. N. W. from Bennington. It has 449 inhabitants.

BRIGANTINE *Inlet*, on the coaft of New-Jerfey, between Great and Little Egg Harbour.

BRIMFIELD, a township in Hampshire co. Massachuster, fituated E. of Connecticut R.; having 1211 inhabitants; 34 miles S. E. of Northampton, and 75 W. of Boston.

BRION Ifle, one of the Magdalene ifles, in the gulf of St. Lawrence.

BRISTOL, a township in Lincoln co. diffrict of Maine, having 1718 inhabitBRI

ants; diftant 204 miles N. E. from Bofton, and 8 N. of Pemaquid Point.

BRISTOL, a county in the fouthern part of Maffachusetts, E. of a part of the flate of Rhode Island. It has 19 townships, of which Taunton is the chief; and 31,709 inhabitants. The great fachem Phillip refided here; [se Raynham]; and it was called by the Indians Pacukunnawkutt; from which the nation derived the name; but were fometimes flyled the Wamponoags. BRISTOL Co. in Rhode island flate,

BRISTOL Co. in Rhode island state, contains the townships of Bristol, Warren, and Barrington; having 3211 inhabitants, inclusive of 98 slaves. It has Bristol co. in Massachusets, on the N. E. and Mount Hope bay E.

BRISTOL, a fea-port town, and chief of the above county, lies on the weftern fide of the peninfula called Briftol neck, and on the E. fide of Briftol bay; including Popalquafh neck, and all the N. and E part of Briftol neck, to Warren, N.; and to Mount Hope bay, E. It is about 3 miles from Rhode I.; the ferry from the S. end of the township being included which is little more than half a mile broad; 13 miles northerly from Newport, 24 S. E. from Providence, and 63 from Bolton .- Briftol fuffered greatly by the ravages of the late war; but it is now in a very flourifhing state, having 1406 inhabitants, inclusive of 64 flaves. It is beautiful for fituation-a healthful climate-rich foil, and a commodious, fafe harbour. Onions, in confiderable quantities, and a variety of provisions and garden stuff, are raifed here for exportation. N. lat. 40. 40.

BRISTOL, a township in Hartford co. Connecticut, 16 miles W. of the city of Hartford.

BRISTOL, a town in Bucks co. Pennfylvania, 11 miles S. S. E. from Newtown, and 20 N. E. from Philadelphia. It ftands on Delaware R. oppofite Burlington in New-Jerfey; and has about 50 or 60 houfes. It is a great thoroughfare, and is noted for its mills of feveral kinds.

BRISTOL, a township in Philadelphia county.

BRISTOL, a finall town in Charles co. Maryland.

BRISTOL, a township in Addison co. Vermont, E. of Vergennes, having 211 inhabitants.

BRISTOL

BRISTOL Bay, on the N. W. coaft of N. America, is formed by the peninfula of Alaika on the S. and S. E. and by Cape Newnham on the N.; and is very broad and capacious. A river of the fame name runs into it from the E.

BRISTOL, a new town of New-York, in Schoharie co. incorporated in 1797. BRITAIN, NEW. The country lying round Hudfon bay, or the country of the Esquimaux, comprehending Labrador, New North and South Wales, has obtained the general name of New-Britain, and is attached to the government of Lower Canada. A fuperintendant of trade, appointed by the governor general of the four British provinces, and responsible to him, reides at Labrador. The principal rivers which water this country, are the Wager, Monk, Seal, Pockerekefko, Churchill, Nelfon, Hayes, New-Severn, Albany and Moofe rivers, all which empty into Hudfon and James' bay, from the W. and S. The mouths of all the rivers are filled with fhoals, except Churchill's, in which the largeft fhips may lie; but to miles higher the channel is obstructed by fand banks. All the rivers, as far as they have been explored, are full of rapids and cataracts, from 10 to 60 feet perpendicular. Down these rivers the Indian traders find a quick paffage; but their return is a labour of many months. Coper Mine, and Mc. Kenzie's rivers, fall into the North Sea. As far in-land as the Hudson Bay Company have fettlements, which is 600 miles to the weft fort of Churchill, at a place called Hudfon Houfe, lat. 53. long. 106. 27. W. from London, is flat country : nor is it known how far to the eaftward, the great chain feen by navigators from the Pacific Ocean, branches off. From Moole river, or the bottom of the Bay, to Cape Churchill, the land is flat, marfhy and wooded with pines, birch, larch and willows. From Cape Churchill, to Wager's river, the coafts are high and rocky to the very fea, and woodlefs, except the mouths of Pocke. rekefko and Seal rivers. The hills on their back are naked, nor are there any trees for a great diftance inland. The eastern coast is barren, past the efforts of cultivation. The furface is every where uneven, and covered with maffes of flone of an amazing fize. It is a

country of fruitlefs vallies and frightful mountains, fome of an aftonifhing height. The vallies are full of lakes, formed not of fprings, but rain and fnow, fo chilly as to be productive of a few fmall trout only. The mountains have here and there a blighted fhrub, or a little mofs. The vallies are full of crooked, finted trees, pines, fir, birch, and cedars, or rather a fpecies of the juniper. In lat. 60. on this coaft, vegetation ceafes. The whole fhore, like that on the weft, is faced with iflands at fome diffance from land,

The laudable zeal of the Moravian clergy induced them, in the year 1752, to fend miffionaries from Greenland to this country. They fixed on Nefbit's harbour for their fettlement; but of the first party, fome of them were killed, and the others driven away. In 1764, under the protection of the British government, another attempt was made. The miffionaries were well received by the Esquimaux, and the mission goes on with fucces. The knowledge of these northern feas and countries was owing to a project farted in England for the difcovery of a north weft paffage to China and the East Indies, as early as the year 1756. Since then it has been frequently dropped and as often revived, but never yet completed.

Frohisher, about the year 1576, dif-covered the Main of New-Britain, or Terra de Labrador, and those straits to which he has given his name. In 1585, John Davis failed from Portfmouth, and viewed that and the more northern coaffs, but he feems never to have entered the bay. Hudson made three voyages on the fame adventure, the first in 1607, the second in 1608, and his third and last in 1610. This bold and judicious navigator entered the straits that lead into the bay known by his name, coafted a great part of it, and penetrated to eighty degrees and a half, into the heart of the frozen zone. His ardour for the discovery not being abat= ed by the difficulties he ftruggled with in this empire of winter, and world of froft and fnow, he ftayed here until the enfuing fpring, and prepared, in the beginning of 1611, to purfue his difcoveries, but his crew, who fuffered equal hardfhips, without the fame fpirit to fupport them, mutinied, feized upon him and feven of those who were moft

moft faithfu them to the open boat. nions were e waves, or ga were deftroy the fluip and ed home.

Though t original pur gated Hudfo even in its fa vantage to] tries which abound with fkins are exce was granted pany, which 9 or 10 perfo to this bay, it ever fince, individuals w though comp tage to Britai 4 fhips, and feveral forts, Churchill riv Albany, on t are garrifone French, in N ftroyed thefe &c. faid to £.500,000. to the value home returns which yield This include bay. The c that part whi been directed annual produc to upwards (maux.

The whole Britain, inclumentioned, a under their rebi, Frederick wick houfes; Gloucefter, a a houfe on W New-Severn; Churchill's F Fort; South I cheffer, and J faft is the we lately erected.

BRITAIN,

moft

BRI

most faithful to him, and committed them to the fury of the icy feas, in an open boat. Hudfon and his companiens were either fwallowed up by the waves, or gaining the inhospitable coast, were deftroyed by the favages; but the ship and the reft of the men returned home.

Though the adventurers failed in the original purpole for which they navigated Hudson bay, yet, the project, even in its failure, has been of great advantage to England. The vaft countries which furround Hudfon bay, abound with animals, whofe fur and fkins are excellent. In 1670, a charter was granted to the Hudson bay company, which does not confift of above 9 or 10 perfons, for the exclusive trade to this bay, and they have acted under it ever fince, with great benefit to the individuals who compose the company, though comparatively with little advantage to Britain. The company employ 4 fhips, and 130 feamen. They have feveral forts, viz. Prince of Wales fort, Churchill river, Nelfon, New-Severn, Albany, on the W. fide of the bay, and are garrifoned by 186 men. The French, in May, 1782, took and destroyed these forts, and the settlements, &c. faid to amount to the value of L. 500,000. They export commodities \mathcal{L} .500,000. They export commodities to the value of \mathcal{L} .16,000, and carry home returns to the value of \mathcal{L} .29,340, which yield to the revenue which yield to the revenue £.3,734. This includes the fifthery in Hudfon's bay. The only attempt to trade to that part which is called Labrador, has been directed towards the fifnery. The annual produce of the fifhery, amounts to upwards of £.49,000 See Esquimaux.

The whole of the fettlements in New-Britain, including fuch as have been mentioned, are as follow, which fee under their respective heads: Abbitibbi, Frederick, East Main and Bruniwick houses; Moose Fort; Henley, Gloucester, and Osnaburg houses; and a house on Winnipeg lake; Severn, or New-Severn; York Fort, or Nelson; Churchil's Fort, or Prince of Wales Fort; South Branch, Hudson's, Manchester, and Buckingham houses: the last is the westernmost fettlement, and lately erected.

BRITAIN, NEW, a large ifland in the Pacific Ocean, lying N. E. of Dam-

1201210181

pier's Straits, between 4. and 7: S. lat. and 146. and 149. E: long. from Paris: Its N. point is called Cape Stephen's it's E. point Cape Orford; and a bay about the middle of its eaftern coaft, is called Port Montague. These names were given by Capt. Carteret, who vifited this ifland in \$767, and found it much finaller than was supposed by Dampier, who first discovered it to be an island. There is nothing yet difcovered peculiarly different in its productions or its inhabitants, from those of the other illands in its neighbourhood. It has the appearance of a mountainous country, and is covered with large and ftately trees. It is furrounded with many fertile iflands, most of which are faid to yield abundance of plantain and cocoa nut trees.

BRITISH AMERICA. Under the general name of British America, we comprehend the vast extent of country, bounded S. by the United States of America, and the Atlantic Ocean; E. by the fame ocean and Davis's Straits, which divide it from Greenland; extending N. to the northern limits of Hudson bay charter; and westward indefinitely—Lying between 42. 30. and 70. N. lat.; and between 50. and 96. W. long. from Greenwich.

British America is divided into four provinces, viz. 1. Upper Canada; 2. Lower Canada, to which are annexed New-Britain, on the country lying round Hudson bay, and the island of Cape Breton; which illand, in 1784, was formed into a leparate government, by the name of Sydney. 3. New-Brunfwick; 4. Nova-Scotia, to which is annexed the ifland of St. John's. Befices thefe, there is the ifland of Newfoundland, which is governed by the admiral for the time being, and two lieutenant governors, who refide at Placentia and St. John's. The troops flationed at Newfoundland, however, are fubject to the orders of the governor general of the four British provinces. The number of people in the whole of the northern British colonies is perhaps 160,000 or 180,000.

Since the four provinces have been put under a general governor, the governor of each is ftyled lieutenant governor. The refidence of the general governor is at Quebec.

The following information, from Edwards's

Edwards's Hiftory of the Weft Indies, respecting the trade and resources of British America, as being useful to Americans, is inferted under this head. The river St. Lawrence remains usually locked up one half of the year; and although, in 1784, it was confidently faid, that the British provinces would be able in three years to fupply all the Weft Indies with lumber and provifions, yet it was found neceffary to import lumber and provisions into Nova-Scotia, from the United States. Thus, in 1790, there were shipped from the U. S. to Nova-Scotia, alone, 540,000 flaves and heading; 924,980 feet of boards; 285,000 fhingles, and 16,000 hoops ; 40,000 bbls. of bread and flour, and 80,000 bufhels of grain, beyond her own confumption. Newfoundland fur-nifhed the British West Indies with 806,459 quintals of fift; on an average of four years, ending with 1786.

The only provisions exported to Jamaica, from Canada, Nova-Scotia, and St. John's, between 3d of April, 1783, and 26th of October, 1784, were 180 bufhels of potatoes, and 751 hhds. and about 500 hbls. of falted fifh. Of lumber, the quantity was 510,088 feet; 20 bundles of hoops; and 301,324 fhingles; and on an average of five years, from 1768 to 1772, the whole exports to Jamaica, from Canada, Nova-Scotia, and St. John's, were only 33 bbls. of flour, 7 hhds. of fifh, 8 bbls. of oil, 3 bbls. of tar, pitch and turpentine; 36,000 fhingles and flaves, and 27,235 cet of lumber.

From the cuftom house returns it appears that of 1208 cargoes of lumber and provisions imported from N. America, to the British fugar colonies in 1772, only 7 of thole cargoes were from Canada and Nova-Scotia; and that of 701 topfail veffels and 1681 floops, which had cleared outwards from N. America, to the British, and foreign, W. Indies, only 2 of the top. fail veffels, and 11 of the floops were from these provinces: and it has been proved, that in the years 1779, 1780, 1781, and 1782, the fearcity in Canada had been fuch, as to occasion the export of all bread, wheat, and flour, to be prohibited by authority; and in 1784, when a parliamentary enquiry took place concerning what fupplies the W. Indies might expect from Ca-

nada and Nova-Scotia; a thip in the river Thames was actually loading with flour for Quebec.

BROADALBIN, a township in Mont-gomery co. New-York; which, by the state cenfus of 1796, contained 277 inhabitants, who are electors.

BROAD Bay, in the diffrict of Maine, lies on the line of Lincoln and Hancock counties, bounded by Pemaquid Point on the W. and Pleafant Point on the E. On the fhore of this bay was an ancient Dutch fettlement.

BROAD River, is an arm of the fea, which extends along the W. and N. W. fides of Beaufort or Port Royal ifland, on the coaft of S. Carolina, and receives Coofa from the N. W .- Coofa R. may likewife be called an arm of the fea; its waters extend N. weftward, and meet those of Broad R. round a fmall ifland at the mouth of Coola Hatchee R. Thefe two arms embrace all the iflands between Combahee R. and Dawfuskee found, with which also Broad R. communicates. Channels between Broad R. and Coofa form the iflands: The entrance through Broad R. to Beaufort harbour, one of the beft in the ftate, is between Hilton's Head and St. Phillip's Point.

BROAD River, or Cherakee-baw, a water of Savannah R. from the Georgia fide. It empties into the Savannah at Peterfourg. At a triffing expence, it might be made boatable 25 or 30 miles through the beft fettlements in Wilkes' county.

BROAD River, in S. Carolina, rifes by three branches from the N. W. viz. the Ennoree, Tiger, and Packolet; which unite about 40 miles above the mouth of Saluda R.; which, with Broad R. forms Congaree R. Broad R. may be rendered navigable 30 miles in North Carolina.

BROKEN ARROW, or Clay- Catfka, an Indian town in the Creek country, in Weft Florida, on the W. fide of Chata-Uche R.; 12 miles below the Cuffitah. and Coweta towns, where the river is fordable. See Coweta, and Flint R.

BROMLEY, a township in Bennington co. Vermont, about 32 miles N. eafterly from Bennington. It has 71 inhabitants.

BROMLEY, a town in Somerfet co. New-Jerfey.

BROOKFIELD, in the S. W. part of Worcefter

Worcefter c the first tow numbers, 3100 inhabi from Bolton it. It is 64 W. of Wor of this town which fill n it; and, li ponds, abou tities of flo and have a This town v Ipfwich, in rated in 167 BROOKFI co. Vermont lies 80 miles BROOKFI co. diffrict Norridgewall was formerly BROOKFI mery co. Nev fus of 1796, electors. BROOKFIL

field co. Com from Danbur 63

folk co. Long 3,224 inhabi flaves; and b 535 only are part of the houfes, an E terian church New-York. BROOKLY folk co. Maffa families, betv bury, and fep: E. by a narro from Charles Bofton. Large and other ver this town for a place where information, 1 life, may enjoy BROOKLYN

BROOKHA

New-York, o having 1603 in are flaves; and ftate cenfus of byterian chur church, a pow

Worcefter co. Maffachufetts, is among the first towns as to age, wealth, and numbers, in the county; containing groo inhabitants. The great post road from Boston to N. York runs through it. It is 64 miles W. of Boston and 27 W. of Worcefter. The Indian name of this town was Quaboag. The river which still retains the name passes thro' it; and, like its other streams and ponds, abounds with various kinds of fish. Here is iron ore, and large quantities of stone which yield copperas, and have a strong vitriolic quality. This town was fettled by people from Ipswich, in 1660, and was incorporated in 1673.

BROOKFIELD, a township in Orange co. Vermont, has 421 inhabitants, and lies 80 miles northerly from Bennington.

BROOKFIELD, a township in Lincoln co. district of Maine, 14 miles above Norridgewalk on Kennebeck R. and was formerly called Seven mile Brook.

BROOKFIELD, a town in Montgomery co. New York. By the ftate cenfus of 1796, 160 of its inhabitants are electors.

BROOKFIELD, a township in Fairfield co. Connecticut, 6 miles N. N. E. from Danbury.

BROOKHAVEN, a townfluip in Suffolk co. Long I. New-York, containing 3,224 inhabitants. Of these 233 are flaves; and by the flate cenfus of 1796, 535 only are electors. The compact part of the town contains about 40 houfes, an Epifcopalian, and a Preflayterian church. It is 60 miles E. of New-York.

BROOKLYN, a pleafant town of Norfolk co. Maffachufetts, of about 60 or 70 families, between Cambridge and Roxbury, and feparated from Bofton on the E. by a narrow bay, which fets up S. from Charles river, and peninfulates Bofton. Large quantities of fruits, roots, and other vegetables are produced in this town for the Bofton market. It is a place where gentlemen of fortune and information, who, retiring from public life, may enjoy otium cum dignitate.

BROOKLYN, a township in King's co. New-York, on the W. end of Long I. having 1603 inhabitants; of these 405 are flaves; and 224 are electors, by the state census of 1796. Here are a Presbyterian church, a Dutch Reformed shurch, a powder magazine, and fome

elegant homes which lie chiefly on one freet. East R. near a mile broad, feparates the town from New-York.

BROOKLYN, a township in Wyndham co. Connecticut, about zo miles N. of Norwich.

BROTHERTON, an Indian village adjoining New-Stockbridge, (N. York) inhabited by about 150 Indians, who migrated from different parts of Conmeticut, under the care of the Rev. Mr. Occom. These Indians receive an annuity of 2560 dollars, which fum is partly appropriated to the purpole of maintaining a school, and partly to compensate a superintendant, to transad their business, and to dispose of the remainder of their money for their bepefit.

BROUGHTON *ifland*, lies at the mouth of Alatamaha R. in Georgia, and belonged to the late Henry Laurens, Efq. The S. channel, after its feparation from the N. defeends gently, winding by Mc. Intofh and Broughton islands. in its way to the ocean through St. Simon's Sound.

BROWNFIELD, a finall fettlement in York co. diffrict of Maine, which, together with Suncook, contains 250 inhabitants.

BROWN's Sound, is fituated on the N. W. coaft of N. America, in N. lat. 55. 18. W. long. from Greenwich 132. 20. It was thus named by Captain Gray. in 1791, in honour of Samuel Brown, Efq. of Bolton. The lands on the E. fide of this found are tolerably level; but on the W. mountains rife, whole fummits out-top the clouds, and whole wintry garb gives them a dreary afpect. The land is well timbered with various forts of pines. The animals in the vicinity are deer, wolves, fea-otters and feals. The fift-falmon, halibut, and a species of cod, &c .-Ducks, brants, fhags, &cc. are here in plenty in fummer.

BROWNSVILLE, or Red/fone Old fort, is a flourishing post-town in Fayette co. Pennfylvania; on the S. eastern bank of Monongahela R.; between Dunlap and Reditone creeks; and next to Pittsburg is the most confiderable town in the western parts of the flate. The town is regularly laid out, contains about 100 houses, an Episcopalian, and Roman Catholic church, a brewery and diffi flery. It is connected with Bridge-

port,

ng with n Mont-

n the ri-

, by the

277 in-

Maine,

d Han-

emaquid

Point on

bay was

the fea, N. W.

ifland,

receives

R. may

he fea

a fmall

Hatchee

all the

d Daw-

Broad

between

iflands:

R. to

t in the

and St.

baru, a

Georgia

nah at

nce, it o miles

Vilkes'

, rifes V. viz.

ckolet :

ove the

with Broad

p miles

Jka, an

ry, in Chata-

uffitah

iver is

r R.

nning

es N.

as 71

fet co.

art of

rcefter

63

d, and

port, a fmall village on the oppofite fide of Dunlap creek, by a bridge 260 feet long. Within a few miles of the town are 4 Friends' meeting-houfes, 24 grift, faw, oil, and fulling mills. The trade and emigration to Kentucky, employ boat-builders here very profitably; above 100 boats of 20 tons each, are built annually. Byrd's Fort formerly ftood here on the S. fide of the mouth of Redftone Creek, in N. lat. 39. 58. W. long. S1. 122; 37 miles foutherly from Pittfburg; 13 S. by E. of Wafnington, and 345 W. of Philadelphia.

BROYLE, a harbour, cape, and fettlement on the E. fide of Newfoundland I.; 15 miles N. E. from the fettlement of Aquafort, and 30 S. wefterly from St. John's, the capital.

BRUNSWICK, a maritime county in Wilmington diffrict, N. Carolina, containing 3071 inhabitants, of whom 1517 are flaves. It is the most foutherly county of the flate, having S. Carolina on the S. W. and bounded by Cape Fear R. on the E. Smithville is the feat of juffice.

BRUNSWICK, the chief town in the above county, fituated on the W. fide of Cape Fear R.; it was formerly the best built in the whole flate, and carried on the most extensive trade. It lies 30 miles above the capes, about 9 miles N. of Fort Johnson, 17 S. W. of Wilmington, and was formerly the feat of government. In 1780, it was burnt down by the British, and has now only 3 or 4 houses and an elegant church in ruins.

BRUNSWICK, a township in Effex co. Vermont. on the W. bank of Connecticut R. opposite Stratford, in New-Hampshire.

BRUNSWICK, a city in Middlefex co. New-Jerfey, is fituated on the S. W. bank of Rariton R. in a low fituation; the moft of the houfes being built under a hill which rifes W. of the town. It has between 200 and 300 houfes, and about 2500 inhabitants, one half of whom are Dutch. Queen's College was in this city, but is now extinct as a place of infruction. There is a confiderable inland trade carried on here. One of the moft elegant and expensive bridges in America, has been built over the river oppofite this city. Brunfwick is 18 miles N. E. of Princetown, 60 N.

E. from Philadelphia, and 35 S. W4 from New-York. N. lat. 40. 30. W4 long. 74-30.

BRUNSWICK, in Cumberland co. diffrict of Maine, contains 1387 inhabitants, and lies N. E. of Portland 30 miles, and of Bofton 151. It is in N2 lat. 43. 52. on the S. fide of Merry Meeting Bay, and partly on the S. weftern fide of Androfcoggin R. Bowdoin College is to be established in this town. BRUNSWICK, the chief town of

BRUNSWICK, the chief town of Glynn co. Georgia, is fituated at the mouth of Turtle R. where it empties into St. Simon's found, N. lat. 31. 10. It has a fafe harbour, and fufficiently capacious to contain a large fleet. Although there is a bar at the entrance of the harbour, it has depth of water for the largeft fhip that fivings. The town is regularly laid out, but not yet built. From its advantageous fituation, and from the fertility of the back country, it promifes to be one of the moft commercial and flourifhing places in the fate. It lies 19 miles S. of Darien ; 6e S. S. W. from Savannah, and 110 S. E. from Louifville.

BRUNSWICK Houfe, one of the Hudfor Bay Company's fettlements, fatuated on Mooie R. half way from its mouth; S. W. from James's Bay, and N. E. from Lake Superior, N. lat. 50. 30. W. long, 82, 30.

BRUNSWICK, NEW, one of the four British provinces in N. America, is bounded on the S. by the N. fhores of the bay of Fundy, and by the river Miffiquash to its fource, and from thence by a due E. line to Verte Bay; and on the W. by a line to run due N. from the main fource of St. Croix R. in Paffamaquoddy, to the high lands which divide the ftreams which fall into the river St. Lawrence, and the bay of Fundy: and from thence by the fouthern boundary of the colony of Quebec until it touches the fea fhore at the weftern extremity of the bay of Chaleur; then following the course of the fea fhore to the bay of Verte, (in the firsits of Northumberland) until it meets the termination of the eaftern line produced from the fource of the Milliquafh above mentioned, including all the iflands within the faid limits.

The chief towns are St. John's, the capital, Fredericktown, St. Andrews, & St. Ann, the prefent feit of government. The

The princip Magegadavic fet, St. Crois Memramcook empty into Pa St. John's fine country, vales and n which are fet ment. The t timbered. fpruce, hemlos cipally beech, afh. The pit the largest to America, and ply of mafts to The rivers 1

quoddy Bay, dows on their t have been cow of timber; at trunks are ye fire paffed thro very dry feafo accounts, 30 y ftruction to an other particular vince, fee the Nova Scotia, B:

BRUNSWICK tween Nottaway and is about 3 broad, and conts including 6776

BRUTUS, a New.York, thr ca R. Here the ters of Owafco I the towns of Au tus lies 11 miles of Cayuaga Lake Lake Ontario.

BRUYNSWICK county, New-Yo BRYAN, a co.

Chatham co. on t BRYANT's Lie Green R. the mo 27 miles E. of Ci of Sulphur Spring

Kentucky. BUCKINGHAM Wales, lies N. v Houfe, and ftand of Safkafhawen R is the wefternmol Bay company's 1 54. W. long. 110 : S. W 30. W. ind co. 7 inhatland 30 s in Na Merry S. weft-Sowdoin is townown of l at the empties 31. 10. ficiently t. Alrance of ater for ie town t built. on, and ountry; t comin the ien; 60 IOS.E. e Hudits, /ftrom its y, and N. lat. he four rica, is ores of e river d from e Bay; lue N. oix R. lands fall inhe bay by the ony of a fhore bay of nurfe of te, (in until it ern line Milli ing all i's, the rus, & nment.

The

BUC

The principal rivers are St. John's, Magegadavick, or eaftern R. Dickwalfet, St. Croix, Merrimichi, Petitcodiac, Memramcook; all, the 3 laft excepted, errors into Paffamaguoddy bay.

Memramcook; all, the 3 laft excepted, empty into Paffamaquoddy bay. St. John's R. opens a vaft extent of fine country, on which are rich intervales and meadow lands; moft of which are fettled and under improvement. The upland is in general well timbered. The trees are pine and fpruce, hemlock and hard wood, principally beech, birch, maple, and fome afh. The pines on St. John's R. are the largeft to be met with in Britifh America, and afford a confiderable fupply of mafts for the royal navy.

The rivers which fall into Paffamaquoddy Bay, have intervales and meadows on their banks, and muft formerly have been covered with a large growth of timber; as the remains of large trunks are yet to be feen. A raging fire paffed through that country, in a very dry feafon, according to Indian accounts, 50 years ago, and fpread deftruction to an immenfe extent. For other particulars reflecting this province, fee the articles feparately, and Novos-Scotia, Britifh America, &cc.

BRUNSWICK Co. in Virginia, lies between Nottaway and Meherrin rivers, and is about 38 miles long, and 35 broad, and contains 12,827 inhabitants, including 6776 flaves.

BRUTUS, a military township in New-York, through which runs Seneca R. Here the river receives the waters of Owafco L. from the S. E. thro' the towns of Aurelius and Scipio. Brutus lies II miles N. E. from the N. end of Cayuaga Lake, and 19 S. S. E. from Lake Ontario.

- BRUYNSWICK, a plantation in Ulfter county, New-York.

BRYAN, a co. in Georgia, adjoining Chatham co. on the W. and S. W.

BRYANT's Lick, a S: E. branch of Green R. the mouth of which is about 27 miles E. of Craig's Fort, and 10 E. of Sulphur Spring, in Mercer's county, Kentweky.

BUCKINGHAM Houfe, in New South Wales, lies N. wefterly from Hudfon Houfe, and ftands on the northern fide of Safkafhawen R. near its fource, and is the wefternmost of all the Hudfon Bay company's fettlements. N. lat. 54. W. long. 110. 20. BUCK Harbour, in Hancock co. diftrift of Maine, lies W. of Machias, and contains 61 inhabitants.

BUCK Ifland, one of the leffer Virgin Ifles, fituated on the E. of St. Thomas, in St. James's Paffage. Lat. 18, 15. N. long. 63. 30. W.

BUCKLAND, a township in Hampshire co. Massachuletts, containing 718 inhabitants; 120 miles westward from Boston.

BUCKLESTOWN, in Berkley co. Virginia, is a village 8 miles diffant from Martinfburg, and 250 from Philadelphia.

BUCKS Co. in Pennfylvania, lies S. W. from Philadelphia. It is feparated from Jerfey by Delaware R. on the S. E. and N. E. and has Northampton co. on the N. W. It contains 25,401 inhabitants, including 114 flaves. Bucks is a well cultivated county, containing 411,900 acres of land, and is divided into 27 townflups, the chief of which is Newtown. It abounds with lime-ftone, and in fome places are found iron and lead ore. There is a remarkable hill in the N. end of the county called Haycock, in the township of the fame name. It is 15 miles in circumference, having a gradual afcent, and from its fummit is a delightful prospect. The waters of Tohickon Creek wash it on all fides except the weft.

BUCKSTOWN, in Hancock co. diffrict of Maine, on the E. fide of Penobscot R. contains 316 inhabitants : and lies 260 miles N. E. from Boston.

BUCKTOWN, in Dorchefter county, Maryland, lies between Blackwater and Transquacking creeks, 12 miles from their mouths at Fishing Bay, and 8⁺/₂ miles S. E. from Cambridge.

BUCKTOWN, a township in Cumberland co. district of Maine, near Portland, containing 453 inhabitants.

BUDDS Valley, a place in Morris co. N. Jerfey, fituated on the head waters of Rariton.

BUEN-AIRE, one of the Leeward Ifles in the Weft-Indies It is final; lies eaftward of Curaçoa, and belongs to the Dutch.

BUENOS AYRES, is one of the most contiderable towns in South-America, and the only place of traffic to the fouthward of Brazil. It is the capital of Paraguay, or La Plata, in the S. division and province of La Plata. S. lat. 34. E

an elegant cathedral, a fmall Indian church, and about 4000 houfes. The houses are generally two stories high, fome built of chalk, and others of brick; most of these are tiled. Buenos Ayres has its name on account of the excellence of the air, and is fituated on the S. fide of the river La Plata, where it is 7 leagues broad, 50 leagues from the fea. The fhips get to it by failing up a river that wants depth, is full of iflands, fhoals and rocks; and where ftorms are more frequent and dreadful, than on the ocean. It is neceffary to anchor every night at the fpot where they come to; and on the most moderate days, a pilot must go to found the way for the ship. After having reached within three leagues of the city, the thips are obliged to put their goods on board fome light veffel, and to go to refit, and wait for their cargoes at Icunado de Barragan, fituated 7 or 8 leagues below.

Here we meet with the merchants of Europe and Peru; but no regular fleet comes here as to the other parts of Spanish America; 2, or at most 3, register ships, make the whole of their regular intercourfe with Europe. The returns are chiefly gold and filver of Chili and Peru, fugar and hides. Thofe who have now and then carried on a contraband trade to this city, have found it more advantageous than any other whatever. The benefit of this contraband is now wholly in the hands of the Portuguese, who keep magazines for that purpose, in fuch parts of Brazil as lie near this country.

The most valuable commodities come here to be exchanged for European goods, fuch as Vigogma wool from Peru, copper from Coquimbo, gold from Chili, and filver from Potofi. From the towns of Corientes and Paraguay, the former 250, the latter 500 leagues from Buenos Ayres, are brought hither the finest tobacco, fugars, cotton, thread, yellow wax, and cotton cloth; and from Paraguay, the herb, to called, and to highly valued, being a kind of tea drank all over S. America by the better fort ; which one branch is computed to amount to a million of pieces of eight, annually, all paid in

35. W. long. 57. 54. This city is a goods, no money being allowed to pair bishop's fee, is well fortified, and de-fended by a numerous artillery. It has and Buenos Ayres is chiefly for cattle and mules to an immenfe value. When the English had the advantage of the Affiento contract, negro flaves were brought hither by factors, and fold to the Spaniards .- It was founded by Don Pedro de Mendoza, in 1535, but afterwards abandoned. In 1544, another colony of Spaniards came here, who left it alfo; but it was rebuilt in 1582, and is at prefent inhabited by Spaniards and native Americans. It is furrounded by a spacious plain, and pleasant country, abounding with all good things; and there is perhaps no place in the universe where meat is better or cheaper. See La Plata R. and province.

BUFFALOE Lake, in Brit. America, is near Copper Mine R. N. late 62, 30. W. long. from Greenwich 110. The Copper Mine Indians inhabit this country.

BUFFALOE Lick. See Great Ridge. BUFFALOE Creek, in New-York, is a water of Niagara R. from the E. into which it empties, near its mouth, opposite Lake Erie. The Seneca Indians have a town 5 miles from its mouth, which is able to furnish 80 warriors. N. lat. 42. 52.

BUFFALOE, a township W. of Sufquehanna R. in Pennfylvania. See Northumberland County.

BUFFALOE R. in the Tenneffee government, runs S. weftward into Ten. neffce R. in N. lat. 35. 10.

BUFFALOE R. a water of the Ohio, which it enters at the S. bank, 60 miles above the mouth of the Wabaih.

BUFFALOE Low Lands, a tract of land in Northumberland co. Pennfylvania, about 88 miles S. E. from Prefque Ifle.

BUFFALOE Swamp, in Pennfylvania, See Great Swamp.

BUCARALLI POINT, on the N. W. coaft of N. America, lies in the 54th degree of N. lat. and 39th of W. long. and forms the N. eaftern fide of Dixon's Entrance, as Washington or Queen Charlotte's Iflands form its S. weftern fide.

BULFINCH's Harbour, fo named by Capt. Ingraham, on the N. W. coaft of N. America, lies in N. lat. 46. 521. W. long. 123. 71.

BULLIT'S LICK, lies on Salt R. in Kentucky, from which falt fpring the river

river takes it from the R Saltfburgh ; worked in the BULL Ma which form t harbour, S. C BULLOCK eaftern fide of BULLOCK,

gia. BULLS Bay bay in Newto S. of St. John of that island. and is very fai The only dang from Bread-an with 9 feet w Lat. 50. 50.] BULLS IAa Charleftown ha

BULLSKIN, Pennfylvania. BUNCOMB,

ern county of perhaps the mo gan diftrict, bon of Tenneffee ; ; South Carolina. fes through But many large riv teree, Broad R. BURGEO Ifes

Newfoundland I Eclipfe I. lies in . 57. 31.

BURKE Co. i Carolina, has 81 ing 595 flaves. town.

BURKE Co. in Georgia, contain cluding 595 flave Louisville, and W

BURKE, a tow in Vermont ; dift 134 miles N. E. BURLINGTON co. New-York, towns in 1797, by ture.

BURLINGTON, the chief in Chi fituated on the S. the E. bank of J has 332 inhabita healthy and agre

66

to pafs n Peru cattle When of the were fold to by Don it afteranother e, who n 1582, aniards rroundpleafant l good o place etter or wince ierica, 18 39. W. he.Copcountry. t Ridge. York, is E. into uth, op-Indians

> mouth, varriors. of Suf-

a. See

effee goito Ten.

e Ohio, 60 miles

h. tract of Pennfyl-1 Preique

fylyania.

e N. W. the 54th W. long. f Dixon's weltern

named by W. coaft 46. 52 1.

ialt R. in pring the river BUR

river takes its name. It lies 20 miles from the Rapids of the Ohio, near Saltfburgh; and is the first that was worked in the country.

BULL Ifland, one of the 3 illands which form the N. part of Charlestown harbour, S. Carolina.

BULLOCK's Point and Neck, on the eaftern fide of Providence R. Rhode-I. BULLOCK, a new county in Georgia.

BULLS Bay, or Baboul Bay, a noted bay in Newtoundland I. a little to the S. of St. John's harbour, on the E. fide of that ifland. It has 14 fathom water, and is very fafe, being land-locked .-The only danger is a rock, 20 yards from Bread-and-Cheele Point, another with 9 feet water off Mogotty Cove. Lat. 50. 50. N. long. 57. 10. W.

BULLS Island, a finall isle N. of Charleftown harbour. See S. Carolina. BULLSKIN, a township in Fayette co. Pennfylvania.

BUNCOMB, the largeft and moft weftern county of North Carolina, and perhaps the most mountainous and hilly in the United States. It is in Mor-gan diffrict, bounded W. by the flate of Tenneffee; and S. by the ftate of South Carolina. The Blue Ridge paffes through Buncomb, and gives rife to many large rivers, as Catabaw, Wateree, Broad R. and Pacolet.

BURGEO Ifes, lie in White Bear Bay, Newfoundland I. Great Burgeo, or Eclipfe I. lies in N. lat. 47. 35. W. long. 57. 31.

BURKE Co. in Morgan diffrict, N. Carolina, has \$118 inhabitants, includ. ing 595 flaves. Its capital is Morgantown.

BURKE Co. in the Lower district of Georgia, contains 9467 inhabitants, including 595 flaves. Its chief towns are Louisville, and Waynesborough. BURKE, a township in Caledonia co.

in Vermont ; diftant from Bennington, 134 miles N. E.

BURLINGTON, a township in Otlego co. New-York, was divided into two towns in 1797, by an act of the legiflature.

BURLINGTON, is a pleafant township, the chief in Chittendon co. Vermont, fituated on the S. fide of Onion R. on the E. bank of Lake Champlain. It has 332 inhabitants. It is in this 8.21

the governor and patrons of the college of Vermont, intend to found a feminary of learning, where youth of all denominations may receive an education.

In digging a well about 15 rods from the bank of the river, frogs have been found, at the depth of 25 feet, where no cavities or communication with the water appeared, through which they might have paffed; and when exposed to the heat of the fun, they became full of life and activity. Here fumps of trees are found 40 feet deep. It is conjectured that these animals mult have been covered up fome hundred years ago, by fome inundation of the river. Burlington is 22 miles northerly of Vergennes, 122 from Bennington, and 332 in the fame direction from New-York city, N. lat. 44. 30.

BURLINGTON, or Ouinefkea Bay, on the E. fide of Lake Champlain, about 34 miles N. by E. from Crown Point, 69 S. E. from Lake St. Francis in St. Lawrence R. and 70 foutherly from St. John's. N. let. 44. 22.

BURLINGTON Co. in New-Jerfey, extends acrois from the Atlantic ocean on the S. E. to Delaware R. and part of Huntingdon co. on the N. W. in length about 60 miles. A great proportion of it is barren ; about 4ths of it, however, is under good cultivation, and is generally level, and is pretty well watered. It has 18,095 inhabitants, including 227 flaves.

BURLINGTON, city, the chief town of the above county, is under the government of a mayor, aldernien, and common council. The extent of the township is 3 miles along the Delaware, and a mile back ; being about 18 miles N. E. of Philadelphia, and 18 from Trenton. The ifland, which is the most populous part, is about a mile each way. It has 4 entrances over bridges, and caufeways, and a quantity of bank meadow adjoining. On the illand are about 160 houses, 1000 white, and 140 black inhabitants; few of the last are flaves. The main freets are conveniently fpacious, and moftly ornamented with rows of trees. The town is opposite Briftol in Pennfylvania, where the river is about a mile wide. Under the fhelter of Mittinicunk and Burlington iflands, is a fafe harbour, healthy and agreeable fituation, that commodiously fituated for trade; but

E 2

ton

too near the opulent city of Philadelphia to admit of any confiderable increase of foreign commerce. Burlington was first fettled in 1677, and has an academy and free school. Mittinicunk I. belongs to the latter, and yields a yearly profit of £. 180. Burling-ton has a place of public worthip for the Friends, and another for the Epifcopalians; the former denomination of christians are the most numerous. Here are two market houfes, a courthouse, and the best gaol in the state. There is likewife a nail manufact ry and an excellent diffillery. N. lat. 40.8. BURLINGTON, a township on the eaftern fide of Unadilla R. in Otfego co. New-York, is 11 miles W. of Cooperftown. By the ftate cenfus of 1796, 438 of its inhabitants are electors.

BURNT-COAT Island. See Penobfeot Bay.

BURTON, a small township in Grafton co. New Hampshile, which was incorporated in 1766, and contains 141 inhabitants.

BURTON, a township in the British province of New-Brunswick, fituated in Sunbury co. on the river St. John. BUSEY Town, in the island of St.

Domingo, lies uear Port-au-Prince, and has a fort.

BUSH Town. See Harford, Maryland. BUSHWICK, a finall, but pleafant town, in King's co. Long I. New-York. The, inhabitants, 540 in number, are chiefly of Dutch extraction; 99 of thefe are electors.

BUSHY Run, a N. E. branch of Sewickly Creek, near the head of which is General Boquet's Field. The creek runs S. wefterly into Youghiogeny R. so miles S. E. from Pittfburg, in Pennfylvania.

BUSTARD R. in Upper Canada, runs into St. Lawrence R. S. weltward of Black R. in a bay of its own name. It runs a great way inland, and has communication with feveral lakes; and at its mouth lie the Ofiers Islands. N. lat. 49. 20. W. long. 68. 5.

BUTLER's Town, on the W. fide of the head waters of the Ohio.

BUTTERFIELD, a fettilement in Cumberland co. district of Maine, having 185 inhabitants. It lies about 43 miles N. from Falmouth, on Caico Bay; having Butterfield Slip on the N. and Bucktown on the South. BYR

BUTTERHILL, a high round hill, on the W. bank of Hudson river, at the northernentrance of the highlands. In paffing this hill, ascending the river, the passenger is prefented with a charming view of New-Windsor and Newburgh.

BUTTON's Bay, in the W. part of Hudíon bay, N. of, and near to Churchhill River. Sir Thomas Button loft his fhip here, and came back in a floop built in the country. Button's Ifles lie on the fouthern fide of Hudfon ftraits, at the entrance of Cape Chilley.

BUXALOONS, an Indian town on the N. W. bank of Alleghany R.; nearly 25 miles from Fort Franklin, at its mouth.

BUXTON, a township in York co. district of Maine, fituated on Saco R.; 16 miles N. wefterly from Pepperelborough, at the mouth of that river, and 18 miles N. E. of Boston; containing 1564 inhabitants.

BUZZARD's Eay, in Maffachufetts, together with Barnftable Bay on the N.E. form the peninfula whole extremity is called Cape Cod. It lies between N. lat. 41. 25. and 41. 42. and between 70. 38. and 71. 10. W. long. from Greenwich, running into the land about 30 miles N. E. by N. and its breadth at an average is about 7 miles. Its entrance has Seakonet Point and rocks W. and the Sow and Pigs off the S. W. end of Cattahunk, one of the Elizabeth iflands, on the Eaft.

BYBERRY, a township in Philadelphia co. Pennfylvania.

BYEFIELD, a parifh in Newbury, Effex co. Maffachufetts. In a quarry of limeftone here, is found the *albeflos*, or incorruptible cotton, as it is fometimes called. Beautifully variegated marble, which admits a good polifh, has likewife been found in the fame vicinity. Here is alfo a flourifhing woolen manufactory established on a liberal fcale; and machinery for cutting nails.

BYRAM R. is a finall fiteain, only noticeable as forming part of the weltern boundary of Connecticut. It fails into Long I. found, opposite Captain's Islands.

BYRAN Town, in Charles co. Maryland, is about 9 miles N. E. from Port Tobacco 3 and 24 S. E. from the Federal City.

BYRD, FORT, lies on the eastern bank

bank of 1 S. fide of Creek; 35r about 39 N. On or near part of the lat. 39.58. BYRON'S Labrador.

C ABARI

CABELA, coaft of Tern N. lat. 10. 3 CABIN Pol Surry co. Vin Chipoak creek terfburgh, 87 S. S. W. of P CABO DE C on the S. fid N. lat. 19. 57.

CABO DE S moft point of a N. lat. 18, 30. CABOT, a to Vermont. It of land betwee Connecticut R. 15 mile falls in containe near

Contains 1202 i CABRON, C Presque ifle de S St. Domingo, 22 old Cape Franço

CACAPEHON which runs abo along the wefter and empties in miles N. from F

CACHIMAYO, America, which within 2 leagues

CADIZ, a town ifland of Cuba, Havannah, and Santo.

CAEN, the chi French Guiana, Cayenne.

CAERNARVON cafter co. Penníyly

CÆSARIA R. New Jerley, em Bay, after a S. we 30 miles. It is no

68

hill. on at the ids. In e river. charmd New-

part of Churchton loft 1 a floop Iftes lie ftraits, n on the ; nearly , at its

> Vark co. Saco R. ; perelbover, and intaining

chufetts, on the extremibetween between ng. from nd about breadth Its enocks W. . W. end Elizabeth

Philadel-

lewbury, a quarry afbeflos, is fomeariegated d polifh, fame viing woola liberal ng nàils. am, only the weft-It falls Captain's

> o. Maryom Port the Fede-

e eaftern bank CES

bank of Monongahela R.; on the S. fide of the mouth of Red-Stone Creek; 35miles S. from Pittfburg, and about 39 N. W. from Ohiopyle Falls. On or near this fpot ftands the compact part of the town of Brownfville. N. lat. 39. 58. W. long. 81. 12.

BYRON's Bay, on the N. E. coaft of Labrador.

ABARRUS, a new co. in the diftriet of Salifbury, North- Carolina. CABELA, or Cabella, a cape on the coaft of Terra Firma, in S. America.

N. lat. 10. 3. CABIN Point, a finall post-town in Surry co. Virginia, fituated on Upper Chipoak creek, 26 miles E. S. E. of Peterfburgh, 87 from Portfmouth, and 329 S. S. W. of Philadelphia. N. lat. 37.

CABO DE CRUZ, a bold point of land on the S. fide of the ifland of Cuba. N. lat. 19. 57.

CABO DE ST. JUAN, the N. eafternmost point of the island of Porto Rico. N. lat. 18. 30.

CABOT, a township in Caledonia co. Vermont. It is fituated on the height of land between lake Champlain and Connecticut R. about 17 miles from the 15 mile falls in the above named R. and contains 1202 inhabitants.

CABRON, Cape, the N. E. point of Presque ifle de Samana, in the island of St. Domingo, 22 leagues S. E. by E. of old Cape François, N. lat. 19. 23.

CACAPEHON, a river of Virginia, which runs about 70 miles N. eatterly along the weltern fide of North Ridge, and empties into Potowmack R. 30 miles N. from Frederickftown.

CACHIMAYO, a large R. in Peru, S. America, which falls into the ocean within 2 leagues of La Plata.

CADIZ, a town on the N. fide of the island of Cuba, near 160 miles E. of Havannah, and 50 N. from Spiritu Santo.

CAEN, the chief city of Cayenne, in French Guiana, in S. America. See Cayenne.

CAERNARVON, a township in Lancafter co. Penníylvania.

CÆSARIA R. or Cohanfie Creek, in New Jersey, empties into Delaware Bay, after a S. wefterly course of about 30 miles. It is navigable for veffels of

100 tons as far as Bridgetown, 20 miles from its mouth.

CAGHNEWAGA, a tribe of Indians in Lower Canada, fome of whom inhabit near Montreal.

CAGHNEWAGA, the name of a finall village or parish on the N, fide of Mohawk R. in the township of Johnstown, about 24 miles W. of Schenectady. It is not improbable that the tribe of Indians mentioned in the preceding ar-ticle formerly inhabited this place. See Johnhown.

CAHORIA, a fettlement in the N. western territory, N. of Kaskaskias.

CALABEZA, a town of S. America, in Terra Firma, on Oroonoko river.

CALCAYLARES, a jurifdiction in S. America, and empire of Peru, fubject to the bifhop of Cofco, about 4 leagues W. of that city; exuberant in all kinds of grain and fruits, and fugar equal to any of the refined fugar of Europe. Formerly it produced 80,000 arobas ; but the quantity is now faid to be much lefs.

CALAIS, a township in Caledonia co. Vermont, 105 miles N. eafterly of Bennington. It has 45 inhabitants.

CALDERSBURGH, a township in Orleans co. in Vermont, is about 151 miles N. E. from Bennington, and II W. of Connecticut river.

CALEDONIA, NEW, a very large ifland in the Pacific Ocean, S. W. and not far diftant, from the New Hebrides, first difcovered by Capt. Cook, in 1774. It is about \$7 leagues long; its breadth is various and no where exceeds ten leagues. It is inhabited by a race of fout, tall, well proportioned Indians of a fwarthy or dark cheinut brown. A few leagues diftant are two finall iflands, called ifland of Pines and Botany ifland.

CALEDONIA Co. in Vermont, contains 24 townships and has Connecticut river S. E.; Orleans and Chittenden counties N. W.; Effex co. N. E.; and Orange co. of which, until lately, it formed a part, S. W.

CALEDONIA, a port on the ifthmus of Darien, in the N. Sea, 25 leagues N. W. from the river Atrato. It was attempted to be established by the Scotch nation in 1698, and had at first all the promiting appearance of fuccels ; but the English influenced by narrow nat tional prejudices, put every impedi-E 3

ment

ment in their way; which joined to the unhealthiness of the climate, defroyed the infant colony. See Darien.

Call, a city of New Granada, S. America, fituated on the river Cauca. The ftaple port for this city, as alfo for thefe of Popayan, Santa Fe, and the fouthern parts of Terra Firma, is Bonaventura in the diffried of Popayan. The road by land from that port is not paffable for beafts of burden; fo that travellers, with their baggage, are carried on the backs of Indians in a chair, with which weight they crofs rivers and mountains, being entirely flaves to the Spaniards, who thus fubfitute them in the room of horfes and mules. N. lat. 3. 15. W. long. 76. 30.

CALIBOGIE River and Sound, on the coaft of S. Carolina, from the outlet of May and New rivers.

CALIFORNIA, an extensive peninfula of N. America, lying between the tropic of Cancer and the 38, N. lat.; washed on the E. by a gulph of the fame name, and on the W. by the Pacific ocean, or great S. Sea; lying within the three capes or limits of Cape St. Lucas the river Collerado and Cape Blanco de San Sebaftian, which is called its weftern limit. The gulf which washes it on the E. called the gulf of California, is an arm of the Pacific ocean, intercepted between Cape Corientes on the one fide, and Cape St. Lucas on the other; that is between Mexico or New Spain on the N. E. and that of California on the W. The length of California is about 300 leagues, in breadth it bears no proportion, not being more than 40 leagues acrofs, from fea to fea. The country is very fruitful, abounds with domeftic animals brought thither originally from Spain, and with fome wild animals not known in Old or New-Spain. The climate is fultry, the heat in fummer being exceffively fevere. The Roman Catholics talk of having met with confiderable fuccefs in converting the Californians to Chriftianity. The Chief town is St. Juan.

Cortes difcovered this country in 1536; but Sir Francis Drake was the first who took possession of it, in 1578; and his right was confirmed by the principal king or chief in the whole country.

CALLAO, a fea-port town in the empire of Peru, being the port or harbour CAL

of Limz, and is fituated 2 leagues from that city. On the N. fide runs the river which waters Lima, on which fide is a fmall fuburb built only of reeds. There is another on the S. fide; they are both called Pitipifti, and inhabited by Indians. To the E. are extensive plains, adorned with beautiful orchards watered by canals cut from the river. The town, which is built on a low flat point of land, was strongly fortified in the reign of Philip IV.; and numerous batteries command the port and road, which is the greateft, fineft, and fafeft in all the South Sea. There is anchorage every where in very deep water, without danger of rocks or fhoals, except one, which is 3 cables-length from the shore, about the middle of the island of St. Lawrence, opposite La Galatea. The little island of Callao lies just before the town. In the opening between these two islands, there are two fmall iflots, or rather rocks; there is also a third very low, but half a league out at fea, S. S. E. from the N. W. point of the island of St. Lawrence. Near the fea-fide is the governor's houfe, which, with the viceroy's palace, take up two fides of a fquare; the parish church makes a third ; and a battery of 3 pieces of cannon forms the fourth. The churches are built of canes interwoven, and covered with clay, or painted white. Here are 5 monasteries, and an hospital. The houses are in general built of flight materials; the fingular circumftance of its never raining in this country, renders ftone houfes unneceffary ; and befides, these are more apt to suffer from earthquakes, which are frequent here. The most remarkable happened in the year 1746, which laid 4ths of Lima level with the ground, and entirely demolifhed Callao; where the destruction was fo entire, that only one man, of 3000 inhabitants, was left to record this dreadful calamity. S. lat. 12. 1. W. long. 77.

CALLACALLES, a river of Chili which falls into the S. Sea at Baldivia.

CALLIAQUA, a town and harbour at the S. W. end of St. Vincent, one of the Caribbee islands. The harbour is the best in the island, and draws thither a great part of the trade, and the principal inhabitants of the island.

CALOS, a bay on the W. coaft of the

the peninfu excellent fi Not far fi town of Se hiards from of fifh here dians and t and return v CALM

N. America

on the north CALN, 1 fhips in Che CALPOLA Mexico, wh of jafper and CALVERT W. fhore (about 33 mil CAMANA, rica, in the the bifhop of but full of d the South Se tends to the

abounds in g ver mines. CAMBRIDO

co. New-Har gin, and S. of CAMBRIDG ington co. No

of 1790, it co including 41 fus of 1796, electors.

CAMBRIDO Middlefex co. the largest and thips of the cou bridge, Little my, contain 3 houses, one f for Episcopali pleafant feats, The elegant this town with ed under the compact part o fituated 31 m on the N. ban which is a brid bridge. It co ling houfes.] fides the edific ward Univerfity Congregational handfome com

buildings are 4

CAM

the peninfula of E. Florida, where are excellent fifting banks and grounds. Not far from this is a confiderable town of Seminole Indians. The Spaniards from Cuba take great quantities of fifh here, and barter with the Indians and traders for fkins, furs, &c. and return with their cargoes to Cuba. CALM Point, on the N. W. coaft of

N. America, lies within Briftol Bay, on the northern fide.

CALN, East and West, two townthips in Chefter co. Pennfylvania.

CALPOLALPAN, a mountain in New Mexico, which abounds with quarries of jafper and marble of different colours.

CALVERT Co. in Maryland, on the W. fhore of the Chefapeak; it is about 33 miles long, and narrow.

CAMANA, a jurifdiction of S. America, in the empire of Peru, under the bishop of Arequipa, very extensive, but full of defarts, some distance from the South Sea coaft. Eaftward it extends to the borders of the Andes; abounds in grain, fruits, and some filver mines.

CAMBRIDGE, a township in Grafton co. New-Hampfhire, E. of Androfcoggin, and S. of Umbagog Lake.

CAMBRIDGE, a township in Wash-ington co. New York. By the census of 1790, it contained 4996 inhabitants, including 41 flaves. By the state cenfus of 1796, it appears there are 623 electors.

CAMBRIDGE, the half fhire town of Middlefex co. Maffachufetts, is one of the largest and most respectable townfhips of the county. Its 3 parifhes, Cambridge, Little Cambridge, and Menotomy, contain 3 Congregational meeting houfes, one for Baptiffs, and another for Episcopalians; a number of very pleafant scats, and 2115 inhabitants. The elegant bridge which connects this town with Bofton has been defcrib ed under the head of Bofton. The compact part of the bridge is pleafantly fituated 32 miles weltward of Botton, on the N. bank of Charles river, over which is a bridge leading to Little Cambridge. It contains about 100 dwelling houfes. Its public buildings, befides the edifices which belong to Harward Univerfity, are the Epifcopal and Congregational meeting-houles, and a handfome court-house. The college buildings are 4 in number, and are of chief town.

CAM

brick, named Harvard, Hollis, and Maffachuletts Halls, and Holden Chapel. They ftand on a beautiful green which fpreads to the N. W. and exhibit a pleasing view. This university, as to its library, philosophical apparatus and profefforthips, is at prefent the first literary institution on this continent. It takes its date from the year 1638, 7 years after the first fettlement in the township, then called Newtown. Since its eftablishment, to July, 1794, 3399 ftudents have received honorary degrees from its fucceffive officers. It has generally from 140 to 200 ftudents. The library contains upwards of 12,000 volumes. The cabinet of minerals, in the muleum, contains the more ufeful productions of nature; and excepting what are called the precious flones, there are very few fubftances yet difcovered in the mineral kingdom, but what may be found here. The university owes this noble collection of minerals, and feveral other natural curiofities, to the munificence of Dr. Lettform, of London, and to that of the republic of France. N. lat. 42. 23. 28. W. long. from Greenwich 71. 7. 30.

CAMBRIDGE, a post town of Ninety-Six diffrict, in the upper country of S. Carolina, where the circuit courts are held. It contains about 60 houfes, a coutt-house and a brick gaol. The college by law inftituted here is no better than a grammar school. [See South Carolina.] It is 80 miles N. N. W. of Columbia; 50 N. by W. of Auguita in Georgia, 140 N. W. of Charlestown, and 762 S. W. of Philadelphia. N. lat. 34. 9.

CAMBRIDGE, the chief town of Dorchefter co. Maryland, is fituated on the S. fide of Choptank R. about 13 miles E. S. E. from Cook's Point at its mouth; 9 W. S. W. from Newmarket, and 57 S. E. from Baltimore. Its fituation is healthy, and it contains about so houfes and a church. N. lat. 38. 34.

CAMBRIDGE, in Franklin co. Vermont, is fituated on both fides of La Moille R. about 20 miles W. of Lake Champlain, and has 359 inhabitants.

CAMDEN Co. in Edenton district, N. Carolina, is on the N. E. corner of the state. It has 4033 inhabitants, including 1038 flaves. Jonefborough is the E4

CAM.

t, one of

rbour is

s thither

ne prin-

coaft of

the

CAMDEN Diffrict, in the upper country of S. Carolina, has Cheraws diffrict on the N. E. Georgetown district on the S. E. and the flate of N. Carolina on the N.; and is divided into the following counties, Fairfield, Richland, Clarendon, Claremont, Kerfhaw, Salem and Lancaster. It is 82 miles from N. to S. and 60 from E. to W. and contains 38,265 inhabitants, including 8865 flaves. This diffrict is watered by the Wateree, or Catabaw R. and its branches; the upper part is variegated with hills, generally fertile and well watered. It produces Indian corn, wheat, 1ye, barley, tobacco, and cotton. The Catabaw Indians, the only tribe which refide in the ftate, live in the N. part of this diffrict. See Catabaru.

CAMDEN, a post town, and chief of Camden district, S. Carolina, in Kerfhaw co. ftands on the E. fide of Wateree R.; 35 miles N. E. of Columbia; 55 S. W. of Cheraw; 120 N. by W. of Charlestown, and 643 S. W. of Philadelphia. It is regularly laid out, and contains about 120 houses, an Episcopal church, a court-house and gaol. The navigable river on which the town ftands, enables the inhabitants to carry on a lively trade with the back country. N. lat. 34. 12. W. long. 80. 54.

This town, or near it, was the scene of two battles in the late war. On the 16th of August, 1780, between Gen. Gates and Lord Cornwallis, in which the American general was defeated. The other was a brifk action between Lord Rawdon and Gen. Greene, on the 25th April, 1781. Lord Rawdon fallied out of the town with 800 men, and attacked the American camp, which was within a mile of the town. The Americans had 126 men killed, and 100 taken prifoners, and the Britifh had about 100 killed. The town was evacuated the oth of May, in the fame year, after Lord Rawdon had burned the gaol, mills, many private houses, and part of his own baggage.

CAMDEN Co. in the lower diffrict of Georgia, at the S. E. corner of the flate, on St. Mary's R. contains 305 inhabitants, including 70 flaves. Chief town St. Patrick's.

CAMDEN, a finall poft town on the western fide of Penobicot bay, district of Maine, and the S. easternmost townthip of Lincoln co. having Thomastown on the S. W.; 35 miles N. N. E. from Pownalborough, and 228 miles N. E. from Bofton.

CAMDEN, a village in Kent co. flate of Delaware; about 4 miles S. W. from Dover, and 5 N. wefterly from Frederica.

CAMILLUS, one of the military townfhips in New-York, W. of Salt Lake, and about 18 miles S. W. from Fort Brewington.

CAM Ifland, one of the finaller Virgin Ifles, in the W. Indies; fituated near St. John's in the King's Channel. N. lat. 18. 20. W. long. 63. 25.

CAMPBELL Co. in Virginia, lies E. of Bedford co. on Staunton R. It is 45 miles long, and 30 broad, and contains 7685 inhabitants, including 2488 flaves.

CAMPBELLTOWN, a village in Dauphin co. Pennfylvania, which ftands near a water of Quitipihilla Creek; 13 miles E. of Harrifburgh, and 96 N. W. of Philadelphia.

CAMPBELLTOWN, in N. Carolina, is a large and flourishing town on a branch of Cape Fear R. 100 miles above Wilmington; having, according to Bartram, "above 100 houles, many wealthy merchants, respectable public buildings, a vaft refort of inhabitants and travellers, and continual brick commerce by waggons, from the back settlements, with large trading boats."

CAMPBELL'S Fort, in the flate of Tenneflee, flands near the junction of Holfton R. with the Tenneflee; diffant 135 miles from Abingdon, in Washington co. Virginia, and 445 W. of Richmond in Virginia.

CAMPBELL's Salines, in North Holfton, in the ftate of Tenneffee, are the only ones that have yet been difcovered on the upper branches of the Tennefice, though great fearch has been made for them. Large bones, like thole found at Big Bone Lick, have been dug up here; and other circumftances render the tract which contains the falines a great natural curiofity. Capt. Charles Campbell, one of the first explorers of the western country, made the difcovery of this tract in 1745. In 1753, he obtained a patent for it from the governor of Virginia. His fon, the late Gen. William Campbell, the fame who behaved to gallantly in the years 1780, and 1781, became owner of it on his death.

death. But his death, and dear, th ed, and fa Since that the a confiderabl fands of peo it, with fall at a low proabout 300 ac as rich a foil this flat, pits tain the falt y

tain the falt v from 30 to 4 through the 1 to 10 feet; yc lime-ftone roc through whis into the pits, buckets and p are placed in pits. The h are covered w coal mine has from it.

CAMPEACE ence of Oldand province the bay of C fhore. Its ho ftone; when ta was a large to had confiderab art and induf dock and fort, garrifon, whi town and harbe ftormed and tal and French buc and laft in 168 united, and plu in 15 leagues ro two months; to the fort and vernor, who kep would not ran the pillage by a the French bu feast of their kir by burning to fterling, of Ca was a part of the der. The port It was a stated 1 which great qu neighbourhood, ed there, and which they ente near the bottom

naftown E. from s N. E.

s. W. y from

town-Lake, Fort

fmaller fituated hannel.

lies E. It is 45 ontains flaves. n Dauftands

ik; 13

N. W.

lina, is branch : Wil-) Barrealthy dings, travelrce by ments, ate of ion of diffant fhing-Rich-1 Hol-

ire the overed neffee, de for found ig up render ines a harles ers of difco-53, he e goe late e who 1780, n his

leath.

CAM

death. But it was not till the time of his death, when falt was very fcarce and dear, that falt water was difcovered, and falt made by a poor man. Since that time it has been improved to a confiderable extent, and many thous

fands of people are now fu it, with erior quality, and tract confifts of at a l about of falt marsh land, of as rich a foil as can be imagined. In this flat, pits are funk, in order to obtain the falt water. The best is found from 30 to 40 feet deep; after passing through the rich foil or mud, from 6 to 10 feet; you come to a very brittle lime-ftone rock, with cracks or chafins, through which the falt water iffues into the pits, whence it is drawn by buckets and put into the boilers, which are placed in furnaces adjoining the pits. The hills that furround this flat are covered with fine timber; and a coal mine has been difcovered not far from it.

CAMPEACHY, a town in the audience of Old-Mexico, or New-Spain, and province of Yucaten, fituated on the bay of Campeachy, near the W. fhore. Its houses are well built of ftone; when taken by the Spaniards it was a large town of 3000 houses, and had confiderable monuments of Indian art and industry. There is a good dock and fort, with a governor and garrifon, which commands both the town and harbour. It has been often ftormed and taken, both by the English and French buccaniers, in 1659, 1678, and laft in 1685, when these treebooters united, and plundered every place within 15 leagues round it, for the space of two months; they afterwards fet fire to the fort and town, which the governor, who kept the field with his men, would not ranfom; and to complete the pillage by a fingular piece of folly, the French buccaniers celebrated the feast of their king, the day of St. Louis, by burning to the value of £.50,000 fterling, of Campeachy wood, which was a part of their fhare of the plunder. The port is large but shallow. It was a ftated market for logwood, of which great quantities grew in the neighbourhood, before the English landed there, and cut it at the iffhmus, which they entered at Triefte Island, near the bottom of the bay, 40 leagues |

death. But it was not till the time of his death, when falt was very fearce and dear, that falt water was diffeover-15. 40. long. 91. 30.

CAMPO BELLO, a long and narrow ifland, on the E. coaft of Wafhington co. diffrict of Maine, and the N. eafternmoft of all the iflands of the diffcict. It lies at the mouth of a large bay into which Cobfcook river empties, and has communication with Paflamaqueddy bay on the N. by two channels; the one between the W. fide of Deer I. and the continent; the other into the mouth of Paflamaqueddy bay, between Deer I. and the N. end of Campo Bello I. which lies in about N. lat. 44. 48. The S. end is 5 miles N. wefterly from Grand Mannan I.

CAMPTON, a finall township in Grafton co. New-Hampshire, fituated on the E. bank of Pemigewasset, the N. head water of Merrimack R.; 35 miles N. E. of Dartmouth College, and 67 N. W. of Portsmouth. It was incorporated in 1761, and contains 395 inhabitants. N. lat. 43. 51.

CANAAN, a thriving township in Lincoln co. district of Maine, fituated on Kennebeck R. about 7 miles N. of Hancock, and \$33 N. by E. of Boston; incorporated in 1788, and contains 454 inhabitants.

A plantation in Hancock co. is also thus named, having 132 inhabitants.

CANAAN, a township in Grafton co. New-Hampshire, 10 miles E. of Dartmouth College; incorporated in 1761. In 1775 it contained 67, and in 1790, 483 inhabitants.

CANAAN, a township in Litchfield co. Connecticut, E. of Housatonick R. having Massachus et al. Here is a forge and flitting mill, erected on a new construction; and the iron used here is faid to be excellent. In the mountains of Canaan, are found valuable specimens of minerals, particularly lead and iron. It lies 60 miles N. of New-Haven, and 40 N. W. from Hartford.

CANAAN, a township in Effex co. Vermont, is the N. easternmost town in the state. It stands at the foot of the Upper Great Monadnock, and has 19 inhabitants,

CANAAN, a township in Columbia co. New-York, having Kinderhook on the W. and Massachuletts E. It has 6692 inhabitants, including 35 flaves 3

663

661 of the free inhabitants are electors. CANADA. The British provinces of Upper and Lower Canada, conftituted vegetables; tobacco, in particular, by act of parliament in 1791, comprehend the territory heretofore called Canada. They lie between 61. and 81 W. long. from London, and between 42. 30. and 52. N. lat. In length about 1400 miles, and in breadth 500. Bounded N. by New-Britain and unknown countries; E. by New-Britain and the gulf of St. Lawrence; S. 10, and foutherly, by the province of New-Brunfwick, the diffrict of Maine, New-Hampfhire, Vermont, New-York, and the Lakes; the western boundary is un-defined. The province of Upper Canada is the fame as what has been commonly called the Upper Country. It lies N. of the great Lakes, and is feparated from New-York by the river St. Lawrence, here called the Cataraqui, and the lakes Ontario and Erie.

"Lower Canada lies on both fides the river St. Lawrence, between 61. and 71. W. long. from London ; and 45. and 52. N. lat. and is bounded S. by New-Brunfwick, Maine, New-Hampfhire, Vermont, and New-York; and W. by Upper Canada."

The line between Upper and Lower Canada commences at a ftone boundary on the N. bank of lake St. Francis, in St. Lawrence R. at the cove W. of Point au Boudet, thence northerly to Ottawas R. and to its fource in lake Tomifcaning, thence due N. till it frikes the boundary of Hudfon bay, or New-Britain. Upper Canada to include all the territory to the weftward and fouthward of faid line, to the utmost extent of the country known by the name of Canada.

Winter continues, with fuch feverity, from December to April, as that the largest rivers are frozen over, and the fnow lies commonly from four to fix feet deep during the winter. But the air is to ferene and clear, and the inhabitants fo well defended against the cold, that this feafon is neither unhealthy nor unpleafant. The fpring opens fuddenly, and vegetation is furrifingly rapid. The fummer is delightful, except that a part of it is extremely hot. Though the climate be cold, and the winter long and tedious, the foil is in general very good, and in

well, and i ltivated. Quebec, and

an

er St. Lawrence, rkable for the

meadow

wa.

richnels grounds in Canada

tered, yield excellent gri feed great numbers of great and imall cattle. From Quebec, the capital, to Montreal, which is about 170 miles, in fail-ing up the river St. Lawrence, the eye is entertained with beautiful landfcapes, the banks being in many places very bold and fteep, and fhaded with lofty trees. The farms lie pretty close all the way, feveral gentlemen's houfes, neatly built, fhew themfelves at intervals, and there is all the appearance of a flourishing colony; but there are few towns or villages. Many beautiful iflands are interfperfed in the channel of the river, which have an agreeable effect upon the eye.

By the Quebec act, paffed by the parliament of Great Britain in the year 1791, it is enacted, that there shall be within each of the provinces of Upper and Lower Canada, a legiflative council, and an affembly, who, with the confent of the governor, appointed by the king, shall have power to make laws. The legiflative council is to confift of not fewer than feven members for Upper, and fifteen for Lower Canada; to be fummoned by the governor, who must be authorized by the king. Such members are to hold their feats for life; unlefs forfeited by four years continual abfence, or by fwearing allegiance to fome foreign power. The house of affembly is to confift of not lefs than fixteen members from Upper, and not lefs than fifty from Lower Canada; cholen by the freeholders in the feveral towns and districts. The council and affembly are to be called together at least once in every year, and every affembly is to continue four years, unless fooner diffolved by the governor.

British America is fuperintended by an officer, ftyled Governor General of the four British provinces in N. America, who, befides other powers, is commander in chief of all the British troops many parts both pleafant and fertile, in the four provinces and the governments ments attac foundland. a lieutenan fence of t the powers trate.

Upper tlemen 40,00

and Fr 10,000 loya parts of the in 1784, cont vinces may n fouls, which both by natu tions.

As many 1 inhabitants o man Catholi prefent gover fion, rights, granted them the 14th of the people as terians, and a ferent fects of The amou the province 1786, was 3 amount of imp 325,1161. wheat, flour, of various kin feng and oth

principally of amount of 2 confifted of ru fee, fugar, wit late, provision goods.

This counts English as eas fettled by the kept pofferfion was taken by I the treaty of P by France to t whom it has en One of the dents which country, is th 1663, which mountains of miles long, at tract into a p rica, and Bri particulars con

CANADA, a

CAN

foundland. Each o f the provinces has nor, who, in the aba lieutenant mor general, has all fence of th the powers requisite to a chie trate.

ough an infant fet-Upper C tlemen fome, to contain 40,00 only 20,000 British nch inhabitants, exclusive of and Fre ro,000 loyalifts, fettled in the upper parts of the province. Lower Canada, in 1784, contained 113,012. Both provinces may now contain about 150,000 fouls, which number is multiplying both by natural increase and by emigrations.

As many as about nine tenths of the inhabitants of thefe provinces are Roman Catholics, who enjoy, under the prefent government, the fame provi-tion, rights, and privileges, as were granted them in 1774, by the act of the 14th of George III. The reft of the people are Episcopalians, Prefbyterians, and a few of almost all the different fects of Chriftians.

The amount of the exports from the province of Quebec, in the year 1786, was 343,2621. 198. 6d. The amount of imports in the fame year was 325,116l. The exports confilted of wheat, flour, bifcuit, flaxfeed, lumber of various kinds, fifh, potafh, oil, ginfeng and other medicinal roots, but principally of furs and peltries, to the amount of 285,9771. The imports confifted of rum, brandy, molaffes, coffee, fugar, wines, tobacco, falt, chocolate, provisions for the troops, and dry goods.

This country was difcovered by the English as early as about 1497; and fettled by the French in 1608, who kept poffeffion of it till 1760, when it was taken by the British arms, and, at the treaty of Paris, in 1763, was ceded by France to the crown of England, to whom it has ever fince belonged.

One of the most remarkable accidents which hiftory records of this country, is the earthquake in the year \$663, which overwhelmed a chain of mountains of freeftone more than 300 miles long, and changed the immense tract into a plain. See British Ame-rica, and Britain, New, for further particulars concerning this country.

CAN

ments attached to them, and New- | Newfoundland I, between White and Hare bays, which laft lies N. of it.

CANADA Creeks. There are three creeks which bear this name; one a water of Wood creek, which it meets 4 or 5 miles N. N. W. of Fort Stanwig or New Fort Schuyler. The other two are northern branches of Mohawk R.; the upper one mingles its waters with the Mohawk in the township of Herkemer, on the German flats, 16 miles below Old Fort Schuyler; over the mouth of it is a fightly and inge-nioufly conftructed bridge. The other empties into the Mohawk 13 miles below. Both thefe are long, rapid and unnavigable freams, and bring a confiderable acceffion of water to the Mohawk. The lands on these creeks are exceedingly rich and valuable, and faft fettling.

CANANDAQUA, a post town, lake, and creek, in Ontario co. New-York. It is the fhire town of the co. fituated on the N. end of the lake of the fame name, at its oulet into Canandaqua creek. The lake is about 20 miles long and 3 broad, and fends its waters in a N. eaftward and eaftward courie 35 miles to Seneca R. This is the feite of an ancient Indian town of the fame name, and ftands on the road from Albany to Niagara, 22 miles E. from Hartford in Geneffee R. ; 16 miles W. of Geneva, and 235 miles N. W. from New-York city, measuring in a straight line, and 340 by Albany road. This fettlement was begun by Meffrs. Gorham and Phelps, and is now in a flourishing flate. There are about 30 or 40 houfes, fituated on a pleafant flope from the lake; and the adjoining farms are under good cultivation. By the flate cenfus of 1796, it appears there are 291 electors in this township.

CANADA SAGA, or Seneca Lake, a handsome piece of water from 35 to 40 miles long, and about 2 miles broad, in New-York. At the N. W. corner of the lake ftands the town of Geneva, and on the E. fide between it and Cayuga, are the towns of Romulus, Ovid, Hector and Ulyffes, in Onondago co. New-York. Its outlet is Scayace R. which also receives the waters of Cayuga Lake, 9 miles N. E. from the mouth of Canada Saga, 18 miles below Geneva, on the fame fide of the lake ftands CANADA, a bay on the E. fide of the Friend's Settlement, founded by Jemima Jemima Wilkinfon; there are 80 families in it, each has a fine farm, and are quiet, industrious people.

CANAJOHARY, a post town in Mont-mery co. New-York, fituated on the fide of Mohawk R. comprehending a very large district of fine country, 40 miles W. of Schenectady, and 56 miles from Albany. In the flate cenfus of 1796, 730 of the inhabitants appear to be electors. A creek named Canajohary enters the Mohawk in this town. In this township, on the bank of the Mohawk, about 50 miles from Schenectady, is Indian Cafile, fo called, the feat of old king Hendrick, who was killed in Sept. 1755, at Lake George, fighting for the British and Americans against the French. Here are now the remains of a British fort, built during that war, about 60 paces square. A gold coin of the value of about 7 dol-lars was found in these ruins in 1793. About a mile and half W. of this fort fands a church, which is called Brandt's church, which the neted chief of that name is faid to have left with great re-Inctance. This was the principal feat of the Mohawk nation of Indians, and abounds with apple trees of their planting, from which is made cider of an excellent quality.

CANANEA, a fmall oblong island in the captainship of Brazil, S. America, belonging to the Portuguese, opposite the mouth of Ararapiza R.; on the S. fide of which stands the town of Cananea to guard the entrance of the bay. This island lies about 37 leagues from St. Vincent. S. lat. 25. 10. W. long. 47. 12.

CANAR ATAN, or Great Canar, a village dependent on the city of Cuenca, under the jurifdiction of the province of Quito, in Peru. It is remarkable for the riches contained in the adjacent mountains.

CANAS, or Tinta, a jurifdiction in Peru, S. America, fubject to the bifhop of Cufco, 18 leagues from that city. The Cordillera divides it into two parts, Canas, and Canches; the former abounding in corn and fruits, the latter in cattle. In the meadows are fed no lefs than 30,000 mules, brought hither from Tucuma to patture; and a great fair is held here for thefe creatures. In Canas is the famous filver mine called *Condonoma*. CANASERAGA Creek runs N. weltward into Geneffee R. at Williamfburgh in N. York finte

CANAWISQUE, a W. branch of Tioga R. rifes in Pennfylvania.

CANCHES See Canas.

CANDIA, a township in Rockingham co. New-Hampshire, which of Cheffer, about 36 miles weltward of Rockinghouth. The foil is but indifferent. It was incorporated in 1767, and contains 1040 inhabitants.

CANDLEMAS Shoals, are about two degrees of latitude due north of Port Praffin, difcovered, named, and paffed, by Mendana, in \$ 569.

CANETTE, a city in Peru, S. America, and capital of the jurifdiction of its name, which produces vaft quantities of wheat, maize, and fugar canes. It is fubject to the archbishop of Lima, and is 6 leagues from that city. S. lat. 12. 14. W. long. 75. 38.

CANIADERAGO, a lake in Otlego co. New-York, nearly as large as Otlego lake, and 6 miles W. of it. A ftream called Oaks Creek iffues from it, and falls into Sufquehannah R. about 5 miles below Otlego. The beft cheefe in the ftate is faid to be made on this creek.

CANICODEO Greek, a S. W. head water of Tioga R. in New-York, which interlocks with the head waters of Geneffce R. and joins Coneffeo creek 26 miles W. N. W. from the Painted Poft.

Caniffex, a fmall river of the District of Maine.

CANNARES, Indians of the province of Quito, in Peru. They are very well made, and very active; they wear their hair long, which they weave and bind about their heads, in form of a crown. Their clothes are made of wool or cotton, and they wear fine fashioned boots. Their women are handfome, and fond of the Spaniards; they generally till and manure the ground, whilft their hufbands at home, card, fpin, and weave wool and cotton. Their country had many rich gold mines, now drained by the Spaniards. The land bears good wheat and barley, and has fine vineyards. The magnificent palace of Theomabamba was in the country of the Cannares.

CANNAVERAL, CAPE, the extreme point of rocks on the E. fide of the peninfula of E. Florida. It has Molquitos

tos Inlet N. by E. Thi lina by chart 28. 35. W. CANNAY of Wafhingt of N. Amer CANNESI the N. ban Miffifippi. CANOE about 200 r forming the . Valley. CANONNI co. Rhode-If of Newport, led Beaver light-houfe) the S. end of about 7 mile ing about on ing the W. and the W. from the Na point is Jame of the Indiar was incorpora town. The cing grain an Jameftown co cluding 16 ft: CANONSBI ton co. Penní the W, bran which runs N 5 miles below rons are fevei are about 50 7 miles N. E. 15 S. W. of] CANSO, OF and fmall fifhi of Nova-Scoti N. of Halifax ifle is finall, n from Cape Ca ern-most land has a good har are two bays c thefe on the (Salmon R. or quantity of 1 there. It is b ery in the wor ftone and plaif the Gut of Ca nel is very nar

fage from the .

tos Inlet N. by W. and a large fhoal S. by E. This was the bounds of Carolina by charter from Charles II. N. lat. 28, 24, W. long, 81, 9.

28. 35. W. long. 81. 9. CANNAYAH, a village on the N. fide of Washington I.; on the N. W. coaft of N. America.

CANNESIS, a town of Louifiana, on the N. bank of Red R. a branch of the Miffifippi

CANCE Ridge, a rugged mountain about 200 miles W. of Philadelphia, forming the E. boundary of Bald Eagle Valley.

CANONNICUT Island, in Newport co. Rhode Ifland, hes about 3 miles W. of Newport, the S. end of which, (called Beaver Tail, on which ftands the light-house) extends about as far S. as the S. end of Rhode I. It extends N. about 7 miles, its average breadth being about one mile; the E. fhore forming the W. part of Newport-harbour, and the W. fhore being about 3 miles from the Narraganley fhore. On this point is Jameftown. It was purchased of the Indians in 1657, and in 1678, was incorporated by the name of Jamef-The foil is luxuriant, produtown. eing grain and grafs in abundance .---Jamestown contains 507 inhabitants, including 16 flaves.

CANONSBURG, a town in Washington co. Pennfylvania, on the N. side of the W. branch of Chartier's Creek, which runs N. by E. into Ohio R. about 5 miles below Pittsburg. In its environs are several valuable mills. Here are about 50 houses and an academy; 7 miles N. E. by E. of Washington, and 15 S. W. of Pittsburg.

CANSO, or Cancean, an illand, cape and fmall fifting bank on the S. E. coaft of Nova-Scotia, about 40 leagues E. by N. of Halifax; N. lat. 45. 20. The ifle is finall, near the continent; N. E. from Cape Canfo, which is the S. eaftern-most land of Nova-Scotia. Canfo has a good harbour 3 leagues deep. Here are two bays of fafe anchorage. Near these on the continent is a river called Salmon R. on account of the great quantity of falmon taken and cured there. It is believed to be the best fifthery in the world of that fort. Limeftone and plaister of Paris are found on. the Gut of Canfo. This gut or channel is very narrow, and forms the paifage from the Atlantic into the gulf of

CAP 71 St. Lawrence, between Cape Breton

ifland and Nova-Scotia. CANSO, a townfhip in the neighbourhood of the above named place, in Halifax county.

CANTA, a town and jurifdiction under the archbishop of Lima, in Peru. It is celebrated for excellent papas, which meet with a good market at Lima, 5 leagues distant S. S. W. Here are innumerable flocks of thecp, the pastures being very rich and extensive. S. lat. 11. 48. W. long. 75. 43.

CANTERBURY, a township in Rockingham co. New Hampshire, fituated on the eastern bank of Merrimack R. 14 miles N. by W. of Concord, 45 N. W. of Exeter, and 54 from Portsmouth. It contains 1038 inhabitants.

CANTERBURY, a township in Windham co. Connecticut, on the W. fide of Quinnabaug R. which separates it from Plainfield. It is 7 miles E. by S. of Windham, and about 10 or 12 N. of Norwich.

CANTON, a new townflip in Norfolk co. Maffachutetts, incorporated in 1797, it being formerly the northerly part of Stoughton.

CANY Fork, in the flate of Tenneffee, is a fhort navigable river, and runs N. W. into Cumberland R. W. of the Salt Lick, and opposite Salt Lick Creek, 50 miles in a flraight line from Nafhville.

CAPALITA, a large town of North-America, and in the province of Guaxaca. The country round abounds with fheep, cattle, and excellent fruit.

CAPE ST. ANDREW'S, on the coaft of Paraguay, or La Plata, S. America. S. lat. 38. 50. W. long. 59. 46.

CAPE ST. ANTONIO, or Anthonio, is the point of land on the fouthern fide of La Plata R. in S. America, which, with Cape St. Mary on the northward, forms the mouth of that river. S. lat. 36. 32. W. long. 56. 34.

CAPE ST. AUGUSTINE, on the coaft of Brazil, S. America, lies fouthward of Pernambuco. S. lat. 10. 15. W. long. 35. 13.

CAPE BLOW-ME-DOWN, which is the fouthern fide of the entrance from the bay of Fundy into the Bafin of Minas, is the eafternmost termination of a range of mountains, extending about 80 or 90 miles to the gut of Annapolis; bounded N. by the thores of the bay

h of Ti-

N. weft-

Tilliam(-

ingham Chefter, mouth. was in-

s 1040 nut two of Port

paffed, Ame-

tion of quanticanes. Lima,

S. lat.

Otlego

s Otie-

ftream

it, and

5 miles

in the

head

which

of Ge-

rek 26

ainted

Vistrict

ovince

y well

their

bind

rown.

r cot-

boots.

y till

their

and

coun-

now

land

I has

: pa-

:oun-

reme

e pe-

tos

fond

cek.

napolis river.

CAPE COD, anciently called Malleherre, by the French, is the S. ealtward point of the bay of Maflachuletts, op-pointe Cape Ann. N. lat. 42. 4. W. long. from Greenwich, 70, 14. See Barnflaple co. and Province Town.

CAPE ELIZABETH, a head-land and township in Cumberland co. district of Maine. The cape lies in N. lat. 43. 33. E. by S. from the centre of the town 9 miles; about 20 S. wefterly of Cape Small Point, and 12 N. E. from the mouth of Saco R. The town has Portland on the N. E. and Scarborough S. W. and contains \$355 inhabi-tants. It was incorporated in \$765, and lies 126 miles N. E. of Bofton.

CAPE FEAR, is the fouthern point of Smith's I. which forms the mouth of Cape Fear R. into two channels, on the coaft of N. Carolina; S. W. of Cape Look-Out, and remarkable for a dangerous shoal called the Frying Pan, from its form. Near this cape is Johnfon's Fort, in Brunfwick co. and diffrict of Wilmington. N. lat. 33. 32. Wi long. 78. 25.

CAPE FEAR R. more properly Clarendon, affords the best navigation in N. Carolina. It opens to the Atlantic ocean by two channels. The S. weftern and largeft channel between the S. W. end of Smith's I. at Bald Head, where the light-house stands, and the E. end of Oakes I. S. W. from Fort Johnston. The new inlet is between the fea-coast and the N. E. end of Smith's I. It will admit veffels drawing 10 or 11 feet, and is about 3 miles wide at its entrance, having 18 feet water at full tides over the bar. It continues its breadth to the flats, and is navigable for large veficls 21 miles from its mouth, and 14 from Wilmington; to which town veffels drawing 10 or 12 feet can reach without any rick. As you afcend this river you leave Brunfwick on the left, and Wilmington on the right. A little above Wilmington, the river divides into N. E. and N. W. branches. The former is broader than the latter, but is neither to deep nor to long. The N. W. branch rifes within a few miles of the Virginia line, and is formed by the junction of Haw and Deep rivers. Its general course is S. eafterly. Sea

of Fundy, and S. by the thores of An- | veffels can go 25 miles above Wilmington, and large boats 90 miles, to Fa-yetteville. The N. E. branch joins the N. W. branch a little above Wilmington, and is navigable by fea veffels 20 miles above that town; and by large boats to South Washington, 40 miles further, and by rafts to Sarecto, which is nearly 70 miles. The whole length of Cape Fear river is about 200 miles. CAPE MAY, is the S. weffernmoft point of the flate of New-Jersey, and

of the county to which it gives name. N, lat. 39. W. long. 75. 2. It lies 20 miles N. E. from Cape Henlopen, which forms the S. W. point of the mouth of Delaware bay, as Cape May does the N. E.

CAPE MAY Co. fpreads northward. around the cape of its name, is a healthy, fandy tract of country, of fufficient fertility to give fupport to 257 # industrious and peaceable inhabitants. The county is divided into Upper, Middle, and Lower precincts.

CAPERIVACA, a large river in Guiana, S. America.

CAPIAPo, a harbour in Chili, S. America.

CARACCAS, a province of Terra Firma, S. America, lying on the fouthern coaft of the Caribbean Sea. This coaft is hordered in its greateft length by a chain of mountains, running E. and W. and divided into many fruitful vallies, whole direction and opening are towards the N. It has maritime fortified towns, Puerto Cahelo, and La Guayra. The Dutch carry thither to the Spaniards all forts of European goods, efpecially linen, making valt returns of filver and cocoa. The cocoa tree grows here in abundance. There are from 500 to 2000 trees in a walk, or plantation. These nuts are passed for money, and are used as fuch in the bay of Campeachy. N. lat. 10. 12. W. long. 67. 10. See St. John de Leon.

CARAMANTA, a province of Terra Firma, S. America, lying on the river Cauca, bounded N. by the diffrict of Carthagena; E. by New-Granada; and S. and W. by Popayan, in the audience of Panama. It is a valley, furrounded by high mountains; and there are waters from which the natives extract very good falt. The capital of the same name lies in N. lat, 5. 18. W. long. 75. 15.

CARANGAS

CARANCA diction under 70 leagues V very barren in abounding in number of fils ed, among w and by the m remarkable. forming an ad the ftone; fui richeft. The ver in this p ble, being fo defarts, when only, detached ed with any c are called pap the ground a the appearance proves that t fusion. Some weighed from a Paris foot ir CARAVAG rica, famed fo CARDIGAN Dartmouth C The township name, which ! CARIACO, of Comana, T On the north Fort St. Yago, 63. 30. and 1 Bordones. CARIACOU illes dependen W. Indies;

Ifle Rhonde. from the N. er tains 6913 acr tivated land, lion lbs. of cot potatoes and p It has two fin town called Hi CARIBEANA New Andaluha CARIBBEE . dies, extend in the ifland of Po

of the Antilles, rica. The fea main land and Caribbean Sea leads N. wefty gulf of Mexic Honduras. T CAR

CARANGAS, a province and jurifdiction under the bishop of Plata, and 70 leagues W. of that city, in Peru, very barren in corn and grain, &c. but abounding in cattle. Here are a great number of filver mines conftantly worked, among which that called Tureo, and by the miners Machacado, is very remarkable. The fibres of the filver forming an admirable intermixture with the ftone; fuch mines are generally the richeft. There are other maffes of filver in this province equally remarkable, being found in the barren fandy defarts, where they find, by digging only, detached lumps of filver, unmixed with any ore or ftone. These lumps are called papas, because taken out of the ground as that root is, and have the appearance of melted filver; which proves that they are thus formed by fusion. Some of these papas have weighed from 50 to 150 marks, being a Paris foot in length.

CARAVAGA, a river in Peru, S. America, famed for its golden fands.

CARDIGAN, about 20 miles E. of Dartmouth College, New-Hampfhire. The township of Orange once bore this name, which fee.

CARIACO, a large gulf in the province of Comana, Terra Firma, S. America. On the northern fide at its mouth is Fort St. Yago, in N. lat. 10. 7. W. long. 63, 30, and on the fouthern fide Cape Bordones.

CARIACOU, is the chief of the fmall ifles dependent on Grenada-I. in the W. Indies; fituated 4 leagues from Ifle Rhonde, which is a like diffance from the N. end of Grenada. It contains 6913 acres of fertile and well cultivated land, producing about a million lbs. of cotton, befides corn, yams, potatoes and plantains for the negrees. It has two fingular plantations, and a town called *Hillfbarough*.

CARIBEANA, now called Paria, or New Andalufia, which fee.

CARIBBEE Iflands, in the Weft-Indies, extend in a femicircular form from the island of Porto Rico, the eafternmost of the Antilles, to the coast of S. America. The sea thus inclosed, by the main land and the isles, is called the Caribbean Sea; and its great channel leads N. westward to the head of the gulf of Mexico, through the Sea of Honduras. The chief of these islands

are Santa Cruz, Sombuca, Anguilla, St. Martin, St. Bartholomew, Barbuda, Saba, St. Euffatia, St. Chriftopher, Nevis, Antigua, Montferat, Guadaloupe, Defeada, Mariagalante, Dominico, Martinico, St. Vincent, Barbadoes, and Grenada. Thefe are again claffed into Windward and Leeward ifles by feamen, with regard to the ufual courfes of fhips, from Old Spain or to the Canaries, to Carthegena or New-Spain and Porto Bello. The geographical tables and maps clafs them into great and fittle Antilles; and authors vary much concerning this laft diffinction. See Antilles.

The Charaibes or Caribbees were the ancient natives of the Windward iflands, hence many geographers confine the term to these ifles only.' Most of these were anciently pollessied by a nation of cannibals, the terror of the mild and inoffensive inhabitants of Hispaniola ; who frequently expressed to Columbus their dread of these fierce invaders. Thus when these islands were afterwards difcovered by that great man, they were denominated Charibbean Ifles. The infular Charaibs are supposed to be immediately descended from the Galibis Indians, or Charaibes of South-America.

CARIBOU, an island towards the E, end of Lake Superior, in N. America, N. W. of Crois Cape, and S. wefterly of Montreal Bay.

CARIPOUS, a nation of S. America, inhabiting a country to the N. of the river Amazon; who are at perpetual war with the Caribbees.

CARLISLE, the chief town of Cumberland co. Pennfylvania, on the poft road from Philadelphia to Pittfburg; is 125 miles W. by N. from the former, and 178 E.from the latter, and 18 S.W. from Harrisburgh. Its fituation is pleafant and healthy, on a plain near the fouthern bank of Conedogwinet creek, a water of the Sufquehannah. The town contains about 400 houses, chiefly of ftone and brick, and about 1 500 inhabitants. The fireets interfect each other at right angles, and the public build. ings are a college, court-house and gaol, and 4 edifices for public worfhip. Of these the Presbyterians, Germans, Epifcopalians, and Roman Catholics, have each one. Dickinfon College, named after the celebrated John Dickinfon.

· /* · ·

infon, Efq. author of feveral valuable tracts, has a principal, 3 profeffors, a philosophical apparatus, and a library containing near 3000 volumes. Its revenue arifes from \pounds . 4000 in funded certificates, and 10,000 acres of land. In 1787 there were 80 fludents, and its reputation is daily increasing. About 40 years ago this spot was inhabited by Indians, and wild beafts.

CARLISLE, a bay on the W. fide of the ifland of Barbadoes, in the Weft-Indies, fituated between James and Charles Forts, on which ftands Bridgetown, the capital of the ifland, in N. lat. 13.9. W. long. 60. 3. CARLOS, a fort on the N. coaft of

CARLOS, a fort on the N. coaft of Terra Firma, on an island which commands the channel between the gulf of Venezuela, and that of Maracaybo on the S. little more than 20 miles N. from the town of Maracaybo.

CARLOS, or Juan Ponce. See Calos. CARLOS, a town of Veragua, in New-Spain, 45 miles S. W. of Santa Fe. It ftands on a large bay, N. lat. 7.40.W. long. 82. 10.

CARLOSA, a town in the interior part of Brazil, in the 25th degree of S. latitude, on the S. E. fide of St. Francis R. and N. by W. from Villa Nova. CARMEL, a township in Dutchel's county, New-York. By the flate cenfus of 2796, 237 of its inhabitants were electors.

CARMELO, a river on the coaft of New-Albion, S. eaftward of Francisco Bay, N. lat. 36. 55. A little northward from it is Sir Francis Drake's harbour, where that navigator lay five weeks.

CARNERO, a cape in the S. Sea, near Santa Maria, on the coalt of Peru. Lat. 1. 35. S. long. 77. 20. W.

CARNESVILLE, the chief town of Franklin co. Georgia, 100 miles N.W. of Augusta. It contains a court-house, and about 20 dwelling-houses.

CAROLINA. See North Carolina, and South-Carolina.

CAROLINE Co. in Virginia, is on the S. fide of Rappahanuock R. which feparates it from King George's co. It is about 40 miles fquare, and contains 17,489 inhabitants, including 10,292 flaves.

CAROLINE Co. on the eastern shore in Maryland, borders on Delaware state to the E. and contains 9506 inhabitants, including 2057 flaves. Its chief town Danton.

CARORA, 2 town of Terra Firma, N. America, about 110 miles N.E. from Gibraltar on Maracaybo Lake.

CAROUGE, POINT, the northernmoft extremity of the ifland of St. Domingo, in the W. Indies; 25 miles N. from the town of St. Jago. CARR, a finall plantation in Lincoln

CARR, a imall plantation in Lincoln co. diffrict of Maine.

CARRANTASCA LAGOON, is a large gulf on the S. fide of the bay of Honduras, about 70 miles N. W. of Cape Gracios a Dios, and nearly as far S. E. from Brewer's Lagoon.

CARTER, a new co. in the flate of Tennefice, formed of a part of the co. of Washington.

CARTERET Cape. See Roman.

CARTERET, a maritime co. of Newbern diftrict, N. Carolina, on Core and Pamlico Sounds. It contains 3732 inhabitants, including 713 flaves. Beaufort is the chief town.

CARTERSVILLE, a town in Powhatan co. Virginia, on the S. fide of James R. 40 miles above Richmond.

CARTHAGENA, a bay, harbour, and town, and the chief fea-port in Terra Firma, S. America. The city of Carthagena is large, rich and frongly fortified, and the chief of the province of the fame name, with a bifhop's fee, and one of the best harbours in America. The entrance into this is fo narrow that only one thip can enter at a time; and it is defended by three forts. All the revenues of the King of Spain from New-Granada and Terra Firma, are brought to this place. Sir Francis Drake took this city, and carried off immense plunder in 1585. The French plundered it in 1697; but admiral Version in 1741, though he had taken the caftles, was obliged to abandon the fiege, for want of skill in the commanders of the land forces, and the ficknefs that was among them, not to mention the difference between the admiral and the general. The ftreets of the town are straight, broad and well paved. The houses are built of ftone or brick, and are one fory high. Here is alfo a coust of inquisition. N. lat. 10. 27. W. long. 75. 22.

CARTHAGO, formerly a confiderable town of New Spain in N. America, in the province of Cofta Riea, with a bifhop's op's verm rable ma. C. betw Ricco it ap has Thou chan C. co. with tons

clear

furna

the p ore is ore, ; fined CA Peter Miffi river. CA La P miles CA **fpread** on the the N. are a 300 6 inhabi cultiva

and on

is the

fea' co

cludes

about

The v arms of countr R, who are can flows v Kennel Elizabe Stroude R. Fon fumples This r Bay on is not g mills u

natives

6 miles

a good

op's fee, and the feat of a Spanish governor; at prefent mean and inconfiderable; and is 360 miles W. of Panama. N. lat. 9. 5. W, long. 83.

CARVEL OF ST. THOMAS, a rock between the Virgin Mes E, and Porto/ Rico on the W. At a fmall diffunce it appears like a fail, as it is white and has two points. Between it and St. Thomas, paffes Sir Francis Drake's channel.

CARVER, a township in Plymouth co. Massachusetts. Here is a pond with such plenty of iron ore, that goo tons have been dragged out of the clear water in a year. They have a furnace upon a stream which runs from the pond; and the iron made of this ore is better than that made out of bog ore, and some is almost as good as refined iron.

CARVER's River, a branch of St. Peter's R. which empties into the Miffifippi. See St. Pierre or Peter's river.

CASACORES, a lake in Paraguay or La Plata in S. America, about 160 miles long.

Casco Bay, in the diffrict of Maine, fpreads N. W. between Cape Elizabeth on the S. W. and Cape Small Point on the N. E. Within thefe points, which are about 40 miles apart, are about 300 finall illands, fome of which are inhabited, and nearly all more or lefs cultivated. The land on thefe iflands, and on the opposite coaft on the main, is the beft for agriculture of any on the fea coaft of this country. Cafco includes feveral bays. Maquoit Bay lays about 20 miles N. of Cape Elizabeth. The waters of Cafco extend feveral arms or creeks of falt water into the country. The waters go up Meadow's R. where veffels of a confiderable fize are carried by the tide, and where it flows within one mile of the waters of Kennebeck. On the E. fide of Cape Elizabeth is the arm of the fea called Stroudwater. Farther E. is Prefumpfcot R. Formerly called Prefumpca, or Prefumpkeag, which rifes in Sebago Pond. This river opens to the waters of Cafco Bay on the E. of Portland ; its extent is not great, but it has feveral valuable mills upon it. Rayal's R. called by the natives Westecustego, falls into the bay 6 miles from Prefumpfcot R. It has a good harbour at its mouth for fmall

veffels; and has feveral mills upon it; a miles higher a full obfructs the navigation. Between it and Kennebeck there are no rivers; fome creeks and harbours of Cafeo Bay throw themfelves into the main land, affording harbours for fmall veffels, and interfecting the country in various forms.

CASPEAN, or Beautiful, a fmall lake in Greenborough, Vermont. It has Hazen block-hoafe on its weftern fide, It is a head water of La Moille river.

CASQUIPIBIAC, a river on the northern fide of Chaleur Bay, about a league from Black Cape, N. W. by N. in the bottom of Cafquipibiae Cove, at the diftance of about one league from which is the great river of Cafquipibiac. It lies about weft from the former, and affords a finall cod and falmon fifthery.

CASSITAH, an Indian town in the western part of Georgia, which, as well as the Coweta town, is 60 miles below the Horse Ford, on Chattahouse river.

CASTILE DEL ORO. See Terra

X CASTINE, the fhire town of Hancock co. diffrict of Maine, is fituated on Penobicet bay. It was taken from the town of Penohfcot, and incorporated in Feb. 1796. It is named after a French gentleman who refided here 130 years ago, as alfo

CASTINE *River*, which is about ramiles long, is navigable for 5 miles, and has feveral mills at the head of it. It empties into Ponobícot bay.

empties into Ponobícot bay. CASTILETOWN, a township in Richmond co. Staten I. New-York, which contains 805 inhabitants, including 114 flaves. 114 of its inhabitants are electors.

CASTLETON, a township and river in Rutland co. Vermont, 20 miles S. E. of Mt. Independence, at Ticonderoga. Lake Bombazon is chiefly in this town, and fends its waters into Castleton R. which, rifing in Pittsford, passes through this town in a S. westerly course, and falls into Pultney R. in the town of Fairhaven, a little below Col. Lyon's iron works. Fort Warner stands in this town. Inhabitants 805

CASTOR'S R. in Newfoundland IQA and, empties in the harbour of St. John's. Its fize is confiderable for 15 miles from the fea.

CASTRO, a firong town in S. America, in Chili, and capital of the ifland of F Chilor.

Chiloe. It was taken by the Dutch in 9643, and is 180 miles S. of Baldivia; fubject to Spain.

CASTRO VIRREYNA, or Viregna, a town and jurifdiction in S. America, in Peru, fubject to the archbifhop of Lima, remarkable for its valuable wool, grain, fruits, filser mines, tohacco, and wholefome air. The town is 125 miles S.E. of Lima. S. lat. 12. 50. W. long. 74.45. CASWELL Co. in Hillfborough diftrict, N. Carolina, borders on Virginia N. It contains 10,056 inhabitants, of whom 2,736 are flavet. Leefburg is the chief town.

CAT Island, or Guanahani, one of Bahama islands. It was the first land discovered by Columbus, to which he gave the name of St. Salvadore, on Oct. 11, 1492. It lies on a particular bank to the E. of the Great Bahama Bank, from which it is parted by a narrow channel, called Exuma Sound. N. lat. 24, 30. W. long. 74:030.

CATABAW River. See Wateree.

CATABAW Indians, a imall tribe who have one town called Catabaw, fituated on the river of that name, N. lat. 44. 39, on the boundary line between N. and S. Carolina, and contains about 450 inhabitants, of which about 150 are fighting men. They are the only tribe which refides in the flate: 144,000 acres of land were granted them by the proprietary government. These are the remains of a formidable nation, the braveff and most generous enemy the fix nations had; but they have degenerated fince they have been furrounded by the whites.

CATARAQUA, Catarakui, or Cateragui, appear in old maps, thus varied, as the name of Lake Ontario, and its outlet Iroquois R.; but thele names are now obfolefe.

CATAWESSY, a township in Northumberland co. Pennsylvania, fituated on the S. E. bank of the E. branch of Sufquehannah R. opposite the mouth of Fishing Creek, and about 20 miles N. E. of Sunbury.

CATHANCE, or Cathants, a finall river in Lincoln co. Maine, which rifes in Topfham, and empties into Merry Merting Bay, and has feveral mills upon it. CATHERINE'S ISLE, ST. a finall ifland in the captainfhip of St. Vincent's, in Brazil, belonging to the Portuguefe, 4.7 leagues S. of Cananea I. It is about 25

miles from N. to S. inhabited by Indians, who affift the Portuguefe againft their enemies, the natives of Brazil. S. lat. 27. 10. W. long. 47. 15. Alfo, a pleafant ifland on the harbour

of Sunbury, in the flate of Georgia. Alfo, a fmall productive ifland on the tle,

her

Lin

wes

tain

are fequ is fit

illo.

C like Tru

C

calle

at t

eafty

ing i its h

and

to n

Near

proje

miles

pend

parts

differ

direc

they

view

water

fpect

is att

ger;

force

veffel

pieces

head :

war, a

a ftro

noe r

India

dange

the wa

the U

the m

the fi

and th

kingu

Indian

States

ftate o

lollars

of the

hands d

Salary's

Th

Par

Allo, a imail productive fland on the fouth coaft of St. Domingo, zo leagues eaftward of the town of St. Domingo. CATHERINE's Town, in Ontario co.

New-York, lies 3 miles S. of the S. end of Seneca lake.

CATO, a military township in New-York state, 12 miles S. E. of lake Ontario, and about 20 S. of Ofwego Fort. CATTAHUNK, one of the Elizabeth isles, in the state of Massachusetts. See Buzzard's Bay.

CAUCA, a river in the ifhmus of Darien, whole fource is in common with that of La Magdalena, in the lakePapos, near the 3th degree of S. latitude, and which falls into this laft river,

CAVALLO, a fea-port town in the province of Venezuela; on Terra Firma, or ifthmus of Darien, 25 miles N. E. of St. Jago de Leon. It is well fortified, and in a former war was unfuccefsfully attacked by Commodore Knowles. Lat. 10. 15. long. 68. 12.

CAVAILLON, a town on the S. fide of the S. peniníula of the ifland of St. Domingo, about 3 leagues N. E. of Les Cayes, and 5 W. by S. of St. Louis. N. lat. 18, 16.

CAVENDISH, a townfhip in Windfor co. Vermont, W. of Weathersfield, ou Black river, having 491 inhabitants. Upon this river, and within this townfhip, the channel has been worn down 100 feet, and rocks of very large dimenfions have been undermined and thrown down one upon another. Holes are wrought in the rocks of various dimenfions, and forms; fome cylindrical, from 1 to 8 feet in diameter, and from 1 to 15 feet in depth; others are of a fpherical form, from 6 to 20 feet diameter, worn almost perfectly finooth, into the folid body of a rock.

CAVIANA, an ifland in S. America, towards the N. W. fide of Amazon R. and in 30' N. latitude.

CAVOGLIERO, a bay on the S. fide of the island of St. Domingo, at the mouth of the river Romaine, 24 leagues E. of St. Domingo.

CAXAMARQUA, a jurifliction in Peru, S. America, under the bifhop of Truxillo, lying lying between the two Cordilleras of the Andes; it produces plenty of all kinds of grain, fruits and vegetables; alfo eattle, and efpecially hogs. They have here a confiderable trade with Chincay, Lima, Truxillo, &c. Here the Indians weave cotton for fhips' fails, bed curtains, quilts, hammocks, &c. There are fome filver mines, but of little confequence. The town of the fame name is ituated N. E. from the city of Truxillo.

CAXAMARQUILA, a fmall jurifdistion likewife in Peru, under the bishop of Truxillo.

h

ce

1.

th

s,

b

0-

OF

it.

nd

t-

t.

de

it.

es

is.

or

ON

18.

n-

IT.D.

ge

nd

les

li-

al,

m

Ea

14-110

ca,

R.

ide

the

ues

ru,

llo.

ing

CAYAHAGA, or Cayuga, fometimes called the Great River, empties in at the S. bank of lake Erie, 40 miles eaftward of the mouth of Huron ; having an Indian town of the fame name on its hanks. It is navigable for boats ; and its mouth is wide, and deep enough to receive large floops from the lake. Near this are the celebrated rocks which project over the lake. They are feveral miles in length, and rife 40 or 50 feet perpendicular out of the water. Some parts of them confit of feveral itrata of different colours, lying in a horizontal direction; and fo exactly parallel, that they refemble the work of art. The view from the land is grand, but the water prefents the most magnificent profpect of this fublime work of nature ; it is attended, however, with great danger; for if the least storm arises, the force of the furf is fuch that no veffel can escape being dashed to pieces against the rocks. Col, Broads-head suffered shipwreck here in the late war, and lolt a number of his men, when a ftrong wind arole, fo that the laft canoe narrowly elcaped. The heathen Indians, when they pais this impending danger, offer a facrifice of tobacco to the water.

Part of the boundary line between the U.S. A. and the Indians, begins at the mouth of Cayahaga, and runs up the fame to the portage between that and the Tulcarawa branch of the Mufkingum.

The Cayuga nation, confifting of 500 Indians, 40 of whom refide in the United States, the reft in Canada, receive of the flate of New-York an annuity of 2300 dollars, befides 50 dollars granted to one of their chiefs, as a confideration for hands fold by them to the flate, and 500 dollars from the United States, agreeably to the treaty of 1794. See Six Nationr.

CAYENNE, a province in S. America, belonging to the French, and the only part of the continent which they poffefs, bounded N. and E. by the Atlantic ocean; S. by Amazonia; and W. by Guiana, or Surinam. It extends s₄0 miles along the coaft of Guiana, and nearly 300 miles within land; lying between the equator and the 5th degree of N. lat. The coaft is low and marfhy, and fubject to inundations, from the multitude of rivers which rufh down the mountains with great impetuofity. The foil is in many places fertile, produling fugar, tobacco, Indian corn, fruits, &c. The French have taken poffeffion of an ifland upon the coaft called alfo Cayenne, which, as likewife the whole country, takes its name from the river that is northward of it.

CAYENNE R. rifes in the mountains near the lake of Parima, runs through the country of the Galibis, a nation of Charibbee Indians, and is 100 leagues long; the ifland which it environs, is 18 leagues in circuit, is good and fertile, but unhealthy. In 1752, the exports of the colony were 260, 541 lbs. of arnotto, 80,363 lbs. fugar, 17,919 lbs. cotton, 26,881 lbs. coffee, 91,916 lbs. cocoa, be-fide timber and planks. The French first fettled here in 1625, and built the fort of Ceperon, but were often forced to quit it, yet returned thither again, as in 1640, 1652, and 1654, and were forced to leave it for want of reinforcements. The Dutch fettled here in 1656, but were driven out by M. de la Baire. The Dutch had their revenge in 1676, and drove out the French ; but were themfelves beat out, the year after, by d'Eftrees.

CAYES, LES, a fea-port town on the S. fide of the S. peninfula of the illand of St. Domingo, 13 leagues W. by S. of St. Louis. N. lat. 18, 12.

CAVLOMA; a jurifdiction under the bifhop of Arequipa, 32 leagues E. of that city, in S. America, in Peru, famous for the filver mines in the mountains of the fame name; which are very rich, though they have been worked for a long time. The country round it is cold and barren. There is an effice here for receiving the king's fifths, and vending quickfilver.

Farmans, 3 fmall iflands, 55 leagues

CEN

N. N. W. of the island of Jamaica, and the Weit-Indies; the most foutherly of which is called the Great Caymans, which is inhabited by 160 people, who are defendance of the old hurcaniers are defcendants of the old buccaniers. It has no harbour for fluips of burden, only a tolerable anchoring place on the S. W. The climate and foil are fingularly falubrious, and the people are vigorous, and commonly live to a great age. They raife all kind of produce for their own ute and to fpare. Their chief employment is to pilot veffels to the adjaent iflands, and to fifh for turtle ; with which last they supply Port Royal and other places in great quantities. Great Caymans lies in N. lat. 15. 48. W. long. 80. 50.

CAYMITE, GRANDE, an island on the N. fide of the S. peninfula of the land of St. Domingo, 2 leagues long and one broad.

CAYUGA, a beautiful-lake in Onondaga co. New-York, from 35 to 40 miles ong, about a miles wide, in fome places , and abounds with falmon, hafs, catfifh, eels, &c. It lies between Seneca and Owalco lake, and at the N. end impties into Scayace R. which is the S. callern part of Seneca R. whole waters run to lake Ontario. On each fide of the lake is a ferry house, where good attendance is given. The refervation lands of the Cayuga Indians lie on both fides of the lake at its northern end.

CAZARES, a town of Mexico. See Angelo.

CAZENOVIA, a new and thriving township, in Herkemer co. New-York, to miles weltward of Whiteftown. By e fate cenfus of 1796, 274 of its inhabitants are electors.

CECIL, a township in Washington co. Pennfylvania.

CEDAR Point, a port of entry in Charles co. Maryland, on the E. fide of Patowmac R. about 12 miles below Port Tobacco, and 96 S. by W. of Bal-timore. Its exports are chiefly tobacco and Indian corn, and in 1794, amounted in value to 18,593 dollars. CEDAR Point, a cape on the W. fide

of Delaware Bay in St. Mary's co. Maryland.

CEDAR Lick, a falt fpring in the ftate of Tenneffee, 19 miles from Nafhville, from Big Spring, and 6 from Little Spring.

CHA

Mu of taw

to e

Ma Riv of t

flow

nam

by (

But

The

Cha

pure

of th

fefs

Firr

the

gort

it ;

Cru

whe

fteep

hor

and

drau

gob

5 lea

trave

fort

Here

toife

it be

toife

to th

N. 1

15 43

calde

and t

river

ral V

CI

C

on th

rence

on th

is the

vince

CI

Penn

of Co

town

ed ci

Here

(rian)

Court

· CO.

C

(

Queen Anne's co. and on the E. fide of Chefapeak bay in Maryland. It lies be-tween the forks of Confica creek, which runs into Chefter R. and has been lately laid out; 18 miles S. of Chefter; 34 S. E. by E. of Baltimore, and 95 S. W. by S. of Philadelphia. N. lat. 39. 6. CESSARES, a territory northward of Patagonia in S. America, in the 48th degree of S. lat. inhabited by a mixt tribe of that name defound from the Son

of that name defcended from the Spaniards; being the people of 3 thips that were wrecked on this coaft in 1 540.

CHABAQUIDDICK Ifle, belongs to Duke's co. Maffachufetts. It lies near to, and extends across the E. end of Martha's Vineyard ifland.

CHACAPOYAS, a jurifdiction under the bifhop of Truxillo, in Peru, S. America. The Indians make a great variety of cottons and tapeftry here, which for the liveliness of the colours and neatness of the work deferve attention. They alfo make cotton fail cloth. It lies within the Cordilleras.

CHACTAW Hills, in the N. W. corner of Georgia river.

CHACTAWS, or flat heads, are a powerful, hardy, fubtile and intrepid race of Indians, who inhabit a very fine and extensive tract of hilly country, with large and fertile plains intervening, between the Alabama and Miffifippi rivers, and in the western part of the state of Georgia. This nation had, not many years ago, 43 towns and villages, in three divisions, containing 12,123 fouls, of which 4,041 were fighting men. They are called by the traders Flatheads, all the males having the fore and hind part of their skulls artificially flattened when young. These men, unlike the Muicogulges, are flovenly and ne-gligent in every part of their drefs, but otherwife are faid to be ingenious, fenfible and virtuous men, bold and intrepid, yet quiet and peaceable. Some late travellers, however, have observed that they pay little attention to the moft neceffary rules of moral conduct, at least that unnatural crimes were too frequent among them. Different from most of the Indian nations bordering on the United States, they have large plan-taions or country farms, where they employ much of their time in agricultural improvements, after the manner of the white people. Altho' their territo-CENTREVILLE, the chief town of ries are not ith to large as those of the Muscogulge

Mufcogulge confederacy, the number of inhabitants is greater. The Chactaws and Creeks are inveterate enemies to each other.

CHADBOURNE's River, diffrict of Maine, called by fome Great Works River, about 30 miles from the mouth of the Bonnebeag Pond, from which it flows. It is faid to have taken its latter name from a mill with 18 faws, moved by one wheel, erected by one Lodors. But the project was foon laid afide, The former name is derived from Mr. Chadbourne, one of the first fettlers, who purchafed the land on the mouth of it, of the natives, and whofe posterity poffefs it at this day.

CHAGRE, a river and town in Terra Firma, S. America. The river opens to the N. Sea, and was formerly called Lagortas, from the number of alligators in it; has its fource in the mountains near Cruces, and its mouth is in N. lat. 9, where there is a firong fort, built on a fteep rock, on the E. fide, near the fea fhore. This fort has a commandant, and lieutenant, and the garrifon is draughted from Panama, to which you go by this river, landing at Cruces, about 5 leagues from Panama, and thence one travels by land to that city. Opposite to fort Chagre is the royal cuttom-house. Here the river is broadeft, being 120 toiles over; whereas, at Cruces, where it begins to be navigable, it is only 20 toiles wide ; from the town of Chagre, to the mouth of the river, is 21 miles N. W. by W. but meafuring by water is 43 miles. There is at Cruces an alcalde, who lives at the cuftom-houfe, and takes an account of all goods on the river. Chagre fort was taken by Admiral Vernon, in 1740.

CHALCO Lake. See Mexico.

than that ya shi di to an a andt

at

00

m

on bty of

he

ge

CHALEURS, a deep and broad bay on the W. fide of the gulph of St. Lawrence. From this bay to that of Verte, on the S. in the S. E. corner of the gulf, is the N. E. fea line of the British province of New-Brunswick.

CHAMBERSBURG, a polt town in Pennfylvania, and the chief of Franklin co. It is fituated on the eaftern branch of Conogocheague creek, a water of Potowmac R. in a nich and highly cultivated country, and healthy fituation...... Here are about 200 houfes, 2 Prefbyterian churches, a fione gaol, a handlome court-house built of brick, a paper and

他方地,安于家山都了

merchant mill. It is 58 miles E. hy S. of Bedford, 11 N. W. of Shippenfburg, and 157 W. of Philadelphia. N. lat. 39. 53. W. long. 77. 30. CHAMBLEE R. or Sorell, a water of

CHAMBLEE R. or Sorell, a water of the St. Lawrence, iffuing from lake Champlain, 300 yards wide when loweft. It is shoal in dry seasons; but of fufficient breadth for rafting lumber, &c. spring and fall. It was called both Sof rell and Richlieu when the French hell Canada.

CHAMBLEE Fort, is handfome and well built, on the margin of the river of the fame name, about 12 or 15 miles 8. W. from Montreal, and r. of St. John's fort. It was take the Americans, Oct. 20, 1775, and retaken by the Britifh, Jan. 18, 1776. N. lat. 45. 45. CHAMPLAIN, a lake next in fize to lake Ontario, and lies E.N.E. from it, forming a part of the dividing line between the flates of New-York and Vermont. It took its name from a French

mont. It took its name from a French governor, who was drowned in it. It was before called Corlaer's lake. Reck-oning its length from Fairhaven to St. John's, a courfe nearly N. it is about 200 miles ; its breadth is from 1 to 18 miles, being very different in different places the mean width is about 5 miles; and it occupies about 500,000 acres. Its depth is sufficient for the largest veffels. There are in it above fixty illands of different fizes; the most confiderable are North and South Hero, and Motte island. North Hero, or Grand Ifle, is 24 miles long, and from 2 to 4 wide. It receives at Ticonderoga the waters of Lake George from the S. S W. which is faid to be 100 feet higher than the waters of this lake. Half the rivers and streams which rife in Vermont fall into it. . There are feveral which come to it from New-York flate and fome from Canada; to which laft it fends its own waters, a N. courfe, thro' Sorell or Chamblee river, into the St. Lawrence. This lake is well fored with fifh, particularly fahnon, fahnontrout, flurgeon and pickerel; and the land on its borders, and on the banks of its rivers, is good.

The rocks in feveral places appear to be marked, and flained, with the former furface of the lake, many feet higher than it has been fince its difference in 1608. The waters generally rife from about the 20th of April, to the F 3 20th

oth of June, from 4 to 6 feet; the reatest variation is not more than 8 et. It is feldom entirely fhut up with ice, until the middle of January. Be-tween the 6th and 15th of April the ice generally goes off; and it is not unommon for many square miles of it to difappear in one day.

CHAMPLAIN, a township the most northerly in Clinton co. New-York, hich takes its name from the lake on which it lies. It was granted to fome Canadian and Nova-Scotia refugees, who were either in the fervice of the United States, during the war, or fied to them for protection. The indigence or ill habits of these people occasioned the breaking up of the settlement; and a better fet of inhabitants have now taken their place. The lands are fertile; and two rivers run through it, well flored with fifh. It has \$75 inhabi-tants, and 3 flaves. By the flate cen-fus of 1796, 76 of the inhabitants are electors.

CHANCEFORD, a township in York co. Pennfylvania.

CHAPALAN, one of the largest lakes in Mexico, or New Spain.

CHAPPEL HILL, a post town in O-range co. N. Carolina, fituated on a branch of Newhope creek, which emp-ties into the N. W. branch of Cape Fear R, This is the fpot chofen for the feat of the University of North-Carolina. Few houses are as yet crected ; but a part of the public buildings were in fuch forwardneis, that fludents were dmitted, and education commenced in Jan. 1796. The beautiful and elevated scite of this town commands a pleafing and extensive view of the furrounding country ; 12 miles S. by E. of Hillfborough, and 472 S. W. of Philadelphia. N. lat. 35. 40. W. long. 79. 6. CHARLEMONT, a township in Hampfhire co. Maffachufetts, 16 miles W. of Deerfield, having 665 inhabitants. CHARLES R. in Maffachuffetts, call-

ed anciently Quinobequin, is a confiderable ftream, the principal branch of which rifes from a pond bordering on Hopkinton. It paffes through Hollifton and Bellingham, and divides Med-way from Medfield, Wrentham, and Franklin, and thence into Dedham, where, by a curious bend it forms a penintula of goo acres of land. A fream called Mother Brook, runs out of this inhabitants, of whom only 163 52 are free.

CHA

I river in this town, and falls into Neponfit R. forming a natural canal, uniting the two rivers, and affording a numb of excellent mill-leats. From Dedham the courfe of the river is northerly, dividing Newton from Needham, Wef ton, and Waltham, paffing over romantic falls; it then bends to the N.E. and E. through Watertown and Cambridge, and paffing into Bolton harbour, mingle with the waters of Mystic R. at the point of the peninfula of Charlestown. It is navigable for boats to Watertown, 7 miles. The most remarkable bridges on this river are those which connect Bofton with Charleftown and Cambridge. See Bofton. There are 7 paper mills on this river, befides other mills.

CHARLES Co. on the wettern fhore of Maryland, lies between Potowmack and Patuxent rivers. Its chief town is Port Tobacco, on the river of that name. Its extreme length is 28 miles, its breadth 24, and it contains 20,613 inhabitants, including 10,085 flaves. The country has few hills, is general'y low and fandy, and produces tobacco, Indian corn, fweet potatoes, &c. CHARLES CITY Co. in Virginia, lies

between Chickahominy and James rivers. It contained formerly part of what now forms P.ince George's co. It has 5588 inhabitants, including 3141 flaves.

CHARLES, a cape of Virginia, in about N. lat. 37. 15. It is on the M. fide of the mouth of Chefapeak bay, having Cape Henry opposite to it,

CHARLES, a cape on the S. W. part of the firait entering into Hudson Bay. N. lat. 62. 40. W. long. 75. 75.

CHARLESTOWN, a post town in Ce-cil co. Maryland, near the head of Chefapeak bay; 6 miles E. N. E. from the mouth of Sufquehannah R.; 10 W. S. W. from Elkton, and 50 S. W. by W. from Philadelphia. Here are about zo honfes, chiefly inhabited by fifhermen employed in the herring fifhery. N. lat. 39- 34-

CHARLESTON, a diffrict in the Low. er country of S. Carolina, fubdivided into 14 parifies. This large diffrict, of which the city of Charletton is the chief town, lies between Santee and Combahee rivers. It pays 21,4731. 144. 6d. fter. taxes. It fends to the ftate legiflature 48 reprefentatives and 13 fenators, and 1 member toCongress. It contains 66986 CHARLESTON,

form whit belo the l thefi abor 12 1 The The ocea roun bree fmol rend part ftate of gi from rich com they the i ford the I ally ed h ners mak plea iftic Cha it or of tl that color they luxu thole enla the t tion mer T is fl: and regu pect carry healt a pla rene

e C Car

the

(am

form

ley :

but

unit

CHARLESTON, the metropolis of S. Carolina, is the moft confiderable town in the flate; fituated in the district of the fame name, and on the tongue of land formed by the confluent ftreams of Afh-ley and Cooper, which are fhort rivers, but large and navigable. These waters unite immediately below the city, and form a fpacious and convenient harbour; which communicates with the ocean just below Sullivan's I.; which it leaves on the N. 7 miles S. E. of Charlefton. In these rivers the tide rifes, in common, about 61 feet; but uniformly rifes 10 or 12 inches more during a night tide. The fact is certain; the caufe unknown. The continual agitation which the tides occasion in the waters which almost furround Charleston-the refreshing feabreezes which are regularly felt, and the finoke arifing from to many chimneys, render this city more healthy than any part of the low part of the low country in the fouthern states. On this account it is the refort of great numbers of gentlemen, invalids from the W. India islands, and of the rich planters from the country, who come here to fpend the fickly months, as they are called, in queft of health and of the focial enjoyments which the city affords. And in no part of America are the focial bleffings enjoyed more ration-ally and liberally than here. Unaffected hospitality-affability-ease of manners and address-and a disposition to make their guefts welcome, eafy and pleafed with themfelves, are characteriftics of the respectable people of Charlefton. In fpeaking of the capital, it ought to be observed, for the honour of the people of Carolina in general, that when in common with the other colonies, in the contest with Britain, they refolved against the use of certain luxuries, and even necefiaries of life; those articles, which improve the mind. enlarge the understanding, and correct the tafte, were excepted; the importation of books was permitted as formerly.

er.

of

rt

th

s, y,,

es

4.

at

38

s.

ut

of

ng

urt

y.

:e-

m V.

by

ut

arry:

w.

in-

of

nief

bater, ure ind 186

DN,

The land on which the town is built, is flat and low, and the water brackifh and unwholefome. The fireets are pretty regularly cut, and open beautiful profpects, and have fubterranean drains to carry off filth and keep the city clean and healthy; but are too narrow for fo large a place and fo warm a climate. Their general breadth is from 35 to 66 feet. The houfes which have been lately built, are brick, with tiled roofs. Th buildings in general are elegant, and most of them are neat, airy and well furnished. The public buildings are, an exchange, a ftate-houfe, an armoury, a poor-houfe and an orphan's houfe. Here are feve ral respectable academies. Part of th old barracks has been handfomely fitted up, and converted into a college, an there are a number of fludents; but i can only be called as yet a respectable academy. Here are two banks-a branc of the national bank, and the S. Carolina bank, eftablished in 1792. The house for public worthip are two Epifcop churches, two for Independents, one for Scotch Prefbyterians, one for Baptifts; one for German Lutherans, two for Methodifts, one for French Protestants, a meeting-houle for Quakers, a Roman Catholic chapel, and a Jewish synagogue.

CHA

Little attention is paid to the public markets; a great proportion of the moft wealthy inhabitants having plantations from which they receive inpplies of almost every article of living. The country abounds with poultry and wild ducks. Their beef, mutton and veal are not generally of the beff kind; and few fifh are found in the market.

In 1787, it was computed that there were 1600 houses in this city, and 15,000 inhabitants, including 5,400 flaves; and what evinces the healthine's of the place, upwards of 200 of the white inhabitants were above 60 years of age. In 1791, there were 16,359 inhabitants, of whom 7684 were flaves. This city has often fuffered much by fire, the laft and most defirultive happened as late as June, 1796.

Charlefton was incorporated in 1783, and divided into three wards, which choic as many wardens, from among whom the citizens elect an intendant of the city. The intendant and wardens form the city-council, who have power to make and enforce bye-laws for the regulation of the city.

The value of exports from this port, in the year ending Nov. 1787, amounted to 505, 1791, 198, 5d. fter. The number of veffels cleared from the cuftomhouse the fame year, was 947, meafuring 62, 118 tons; 735 of theie, meafuring 41, 531 tons, were American; the others belonged to Great Britain, Ireland, Spain, France, and the United Nether-F 4 lands. In the year 1794, the value of exports amounted to 3,846,39 dollars. It is 60 miles S. W. by S. of Georgetown; 150 E. by S. of Augusta; 497 S. by W. of Richmond; 630 S. W. by S. of Washington city; 763 S. W. by S. of Philadelphia; and 1110 S. W. of Bofton. The light-house lies in N. lat. 32.41.52. White Point at the S. end of the town, N. lat. 32.44.30. W. long.

GHA

So. 39.45. Knoxville, the capital of the flate of Tenneffee, is much nearer to this than to any fea-port town in the Atlantie Ocean. A waggon road of only 35 miles is wanted to open the communication; and the plan is about to be excuted by the flate.

CHARLESTOWN, a township in Montgomery co. New York, on the S. fide of Mohawk river, about 32 miles W. of Schenectady. By the state census of 1796, 456 of the inhabitants are electors.' CHARLESTOWN, a township in Mafon co. Kentucky, situated on the Ohio at the mouth of Lauren's creek. It contains but few houses, and is 6 miles N. of Washington, and 60 N. E. of Lexington. N. lat. 38. 43. CHARLESTOWN, a township in Chef-

ter co. Pennfylvania.

/ CHARLESTOWN, a post town in Chefhire co. New Hampthire, on the E. fide of Connecticut R. 30 miles S. of Dartmouth College; upwards of 70 N. of Northampton, 116 N. of W. of Bofton, 120 W. by N. of Portfmouth, and 431 N. N. E. of Philadelphia. It was incorporated in 1753, and contains 90 or 100 houfes, a Congregational church, a court-house and an academy. The road from Boston to Quebec passes through this town. N. lat. 43. 16. W. long. 72. 19. A finall internal trade is carried on here.

CHARLESTOWN, the principal town in Middlefex co. Maffachufetts, called *Mijharwan* by the aboriginal inhabitants, lies N. of Bofton, with which it is connected by Charles-River Bridge. The town, properly fo called, is built on a peninfula, formed by Myflic R. on the E. and a bay, fetting up from Charles-River on the W. It is very advantageoufly fituated for health, navigation, trade, and manufactures of almost all the various kinds. A dam acrofs the mouth of the bay, which fets up from Charles-River, would afford a great

88

CHA

the

bces.

are

thop

fort.

S. fic

fulph

ofai

calle

as to

thoes

Bath

faid

lofes

Blac

mile

owin

fprin

ticul

guts

moul

quak

cuity

altitu

quad

to be

miles

tain

but :

36.

C

the i

of B

CI

Ifan

lame

the e

beau

who

4 m

feas (

moul

frait

trees

a bea

at th

degn

Lond

mon

excel

The

W. |

fruit

N. L

number of mill-feats for manufactures. Bunker's, Breed's, and Cobble (now Barrell's) hills, are celebrated in the hiftory of the American Revolution. The fecond hill has upon its fummit a monument crected to the memory of Major Gen. Warren, near the fpot where he fell, among the first facrifices to American liberty. The brow of the hill begins to be ornamented with elegant houles. All thefe hills afford elegant and delightful prospects of Bofton, and its charmingly variegated harbour, of Cambridge and its colleges, and of an extensive tract of highly cultivated country. It contains within the neck or parifh about 250 houfes, and about 2000 inhabitants. The only public buildings of confequence are a handfome Congregational church, with an elegant fteeple and clock, and an almshoufe, very commodious and pleafantly fituated. 1000

Before the destruction of this town by the British in 1775, feveral branches of manufactures were carried on to great advantage, fome of which have been fince revived; particularly the manufacture of pot and pearl affres, thip-building, rum, leather in all its branches, filver, tin, brafs, and pewter. Three rope-walks have lately been crected in this town, and the increase of its houfes, population, trade, and navigation, have been very great within a few years paft. This town is a port of entry in conjunction with Bolton. At the head of the neck there is a bridge over Myttic R. which connects Charleftown with Malden.

CHARLESTOWN, a village in Berkley co. Virginia, fituated on the great road leading from Philadelphia to Winchefter; 8 miles from Shepherdflown, and 20 from Winchefter.

CHARLESTOWN, a township in Washington co. Rhode Island flate, having the Atlantic ocean on the fouthward, and separated from Richmond on the northward by Charles-river, a water of Pawcatuck. Some of its ponds empty into Pawcatuck R. others into the Ica. It is 19 miles N. W. of Newport, and contains 2022 inhabitants, including 12 flaves.

A few years ago there were about soo Indians in the flate; the greater part of them refided in this townfhip. They are peaceable and well disposed

to

to government, and speak the English language.

of

ot

es

6.

n

r,

mdk

at

ic

١.

ui

sly

n

Sore Bost Share

N

e

ar n

74.14

CHARLESTOWN, the only town in the ifland of Nevis, one of the Caribbees, belonging to Great-Britain. In it are large houses and well furnished fhops, and it is defended by Charles fort. In the parifh of St. John, on the S. fide of the town, is a large fpot of fulphurcous ground, at the upper end of a deep chaim in the earth, commonly called Sulphur Gut, which is fo hot as to be felt through the foles of one's thoes. A fmall hot river, called the Bath, is thought to proceed from the faid gut; and after running half a mile, lofes itfelf in the fands of the fea. Black-Rock pond, about a quarter of a mile N. from the town, is milk-warm, owing to the mixture of hot and cold fprings, yet it yields excellent fifth ; par-ticularly fine eels, filver fifth, and fiimguts. A prodigious piece of Nevis mountain falling down in an earthquake, feveral years ago, left a large va-cuity, which is ftill to be feen. The altitude of this mountain, taken by a quadrant from Charleftown bay, is faid to be a mile and a half perpendicular; and from the faid hay to the top, four miles. The declivity from this mountain to the town is very fteep half way, but afterwards eafy of afcent. N. lat. 16. 55. W. long. 62. 42.

CHARLESTOWN, or Offins, one of the four principal towns in the island of Barbadoes.

CHARLETON Island, or Charles Mand, is fituated at the bottom of James's bay, in New South Wales, on the coaft of Labrador, and yields a beautiful profpect, in fpring, to those who are near it, after a voyage of 3 or a months in the most uncomfortable feas on the globe, and that by the vaft mountains of ice in Hudion bay and ftraits. The whole ifland, foread with trees and branches, exhibits, as it were, a beautiful green tuft. The air, even at the bottom of the bay, though in 51 degrees, a latitude nearer the fun than London, is exceffively cold for nine months, and very hot the other three, except on the blowing of a N.W. wind. The foil on the E. fide, as well as the W. bears all kinds of grain; and fome fruits, gooleberries, ftrawberries, and dewberries, grow about Rupert's bay. N. lat. 52. 30. W. long. 82.

CHA

CHARLETON, a township in Worcefter co. Maffachufetts, incorporated in 1754, and, until then, formed the westerly part of Oxford. It is 60 miles S.W. of Boston, 15 S.W. of Worcefter, and contains 1965 inhabitants. Quinebaugh R. forms fome of its rich intervale lands, and furnishes excellent mill feats for this, and many adjacent towns.

CHARLOTTE Fort, in S. Carolina, is fituated on the point of land when Tugeloo and Broad rivers, uniting their waters, form Savannah R. According to Bartram, it is one mile below Fort James, Dartmouth. N. lat. 34. W. long. 82. 35. CHARLOTTE Haven, lies at the mouth of Charlotte R. in E. Florida; having Carlos bay on the S. and Rock Point on the northward. N. lat. 27. W. long. 82. 40. Charlotte R. is fed by Spisitu Santo Lagoon, which communicates, by Delaware R. with Chat-

ham or Punjo bay, which is go miles

S. E. from Charlotte Haven. CHARLOTTE, a confiderable towns fhip on the E. fide of Lake Champlain, and the S. wefternmoft in Chittenden co. Vermont. Shelburne on the N. feparates this town from Burlington. It contains 635 inhabitants. Split Rock, in Lake Champlain, lies off this town. CHARLOTTE Go. in Virginia, lies S. W. of Richmond, on the head waters of Staunton R. and contains 10,078 inhabitants, including 4816 flaves. The court houfe is 21 miles S. S. W. of Prince Edward court-house, and 379 about the fame courfe, from Philadelphia.

CHARLOTTEBURG, a town in Brunfwick co. N. Carolina. It flands on an ifland, and has an inlet and found of the fame name, a little S. of it.

CHARLOTTE, or Charlottefoille, a post-town in Salisbury difficit, N. Carolina, and chief town of Mecklenburg co. fituated on Steel creek, which joins the Sugaw, and falls into Catabaw R. about to miles N. of the S. Carolina boundary, and 44 S. of Salisbury. Here are about 40 houres, a courthouse and gaol.

CHARLOTTESVILLE, the capital of Albemaric Albemarle co. in Virginia, lies on the post road from Richmond to Danville, in Kentney, 86 miles W.N.W. of the former, and 557 caftward of the latter, and 40 S. E. by B. of Staunton.' It contains about 45 houles, a courthoule and a guol, fituated about halr a mile N. from a water of Rivanna river. CHARLOTTE Town, the capital of the ifland of St. John's, in the gulf of St. Lawrence. Allo, the name of a town on the S. W. fide of the ifland of Dominica, in the W. Indies; and fituated on the S. fide of a deep bay.

CHARLOTIA, a town on the E. fhore of St. John's R. Eaft Florida, where that river is about half a mile wide. It was founded by Den. Rolle, Eiq. and is fituated on a high bluff, 15 or 20 feet perpendicular from the river; and is in length half a mile, or more. The aborigines of America had a very great town in this place, as appears from the great tumuli and conical mounts of earth and fhells, and other traces of a lettlement which yet remain. The river, for near 12 miles above Charlotia, is divided into many channels by a number of iflands.

CHARTIER, a township in Washington co. Pennsylvania.

, CHARTIER'S Creek. See Canon/burg and Morganza.

CHARTRES, a fort which was built by the French, on the eastern fide of the Miffifippi, 3 miles northerly of La Prairie du Rocher, or the Rock Meadows, and 22 miles northerly of St. Genevieve, on the weftern fide-of that river. It was abandoned in 1772, being untenable by the constant washings of the Miffifippi in high floods. The village fouthward of the fort was very inconfiderable in 1778. A mile above this is a village fettled by 170 warriors of the Piorias and Mitchigamias tribes of Illinois Indians, who are idle and debauched.

CHATHAM, a maritime township in Barnstaple co. Maffachusetts, situated on the exterior extremity of the elbow of Cape Cod, conveniently for the fifthsry; in which they have usually about to reff. employed. It has 1140 inhabitants, and lies 95 miles S. E. of Bolton. See Cape Cod. CHATHAM, a township in Grafton

co. New-Hampfnire. It was incorporated in 1767, and in 1750 contained 38 inhabitants.

C. H A

CHATHAM, a flourishing township in Middlefex co. Connecticut, on the eastern bank of Connecticut R. and opposite Middleton city. It was a part of the township of Middleton till 1767. CHATHAM, a township in Effect co. N. Jersey, is situated on Passaic R. 13 miles W. of Elizabethtown, and nearly the same from Newark.

light

ed.

featte

huts

the cl

brick

river

miles

at th

Tuc

New

s bre

S. S.

ghan

fitual

lake

wate

Fran

corne

is a I

harb

ble o

This

the I

CI

St.

Han

Main

able

the I

C

S. /

Plati

Plat

rold

Ain

Virg

COUF

mile

is 2

100

50 11

boat

a po

the

rive

the

ting

in a

Gre

C

C

CH

CHATHAM, a township of Columbia co. New-York. By the state cenfus of 1796, 380 of its inhabitants were electors.

CHATHAM Co. in Hillfborough diftrict, N. Carolina, about the center of the flate. It contains 9221 inhabitants, of whom 1632 are flaves. Chief town, Pittfburg. The court-houfe is a few miles W. of Raleigh, on a branch of Cape Fear River.

CHATHAM, a town of S. Carolina, in Cheraws diffrict, fituated in Chefferfield co. on the W. fide of Great Pedee R. Its fituation, in a highly cultivated and rich country, and at the head of a navigable river, bids fair to render it a place of great importance. At prefent it has only about 30 houfes, lately built

CHATHAM Co. in the lower diffrict of Georgia, lies in the N. E. comer of the flate, having the Atlantic ocean F, and Savannah river N. E. It contains 10,769 inhabitants, including \$201 flaves. The chief town is Savannah, the former capital of the flate.

CHATHAM, or Punjo bay, a large bay on the W. fide of the S. end of the promontory of E. Florida. It receives North and Delaware rivers.

CHATHAM Houfe, in the territory of the Hudfon bay company, N. lat. 55. 23. 40. W. long. from Greenwich 98. CHATA-HATCHI, or Hatchi, is the fargett river which falls into St. Rofe's bay in W. Florida. It is also called Pea R. and runs from N. E. entering the bottom of the bay through fevera mouths; but fo fhoal that only a fmall boat or canoe can pais them. Mr. Hutchins afcended this river about 29 leagues, where there was a fmall fettlement of Couffac Indians. The foil and timber on the banks of the river refemble very much those of Escambia. CHATAUCHE, or Chatabuthe, a river in Georgia. The northern part of Appalachicola river bears this name. It is about 30 rods wide, very rapid, and full

of

of fhoals. The lands on its banks are light and fandy, and the clay of a bright red. The lower creeks are fettled in feattering clans and villages from the head to the mouth of this river. Their huts and cabins, from the high colour of the clay, refemble clufters of new-burned brick kilns. The diftance from this river to the Talapofe R. is about 70 miles, by the war-path, which croffes at the falls, just above the town of the Tuckabatches.

nia

of

:c-

論

of

18; n;

of

in

r-

ee rd

2

nty ftrates

l,

CHATAUGHQUE Lake, in Ontario co. New-York, is about 18 miles long, and 3 broad. Conewango R. which runs a-S. S. E. courfe, connects it with Alleghany R. This lake is conveniently fituated for a communication between lake Erie and the Ohio; there being water enough for boats from Fort Franklin on the Alleghany to the N.W. corner of this lake; from thence there is a portage of 9 miles to Chataughque harbour on lake Erie, over ground capa-ble of being made a good waggon road. This communication was once uled by the French.

CHAUDIERE R. a S. E. water of the St. Lawrence, rifing in Lincoln and Hancock counties, in the district of Maine. The carrying place from boatable waters in it, to boatable waters in the Kennebeck, is only 5 miles. CHAYANTA, a jurification in Peru,

S. America; under the archbishop of Plata, 50 leagues from the city of La This country is famous for its Plata. gold and filver mines. The latter are ftill worked to advantage.

CHEAT R. rifes in Randolph co. Virginia, and after purfuing a N.N.W. courfe, joins Monongahela R. 3 or 4 miles within the Pennfylvania line.) It is 200 yards wide at its mouth, and 100 yards at the Dunkards fettlement, so miles higher, and is navigable for boats except in dry feasons. There is a portage of 37 miles from this R. to the Potowmack at the mouth of Savage river.

CHEBUCTO, a bay and harbour on the S. S. E. coaft of Nova-Scotia, diftinguished by the loss of a French fleet in a former war between France and Great-Britain. Near the head of this bay, on the W. fide, flands the city of Halifax, the capital of the province.

CHEDABUCTO, or Milford Haven, a

CHE

10

part of Nova-Scotia, at the mouth of the gut of Canfo. Opposite to its mouth flands Ifle Madame. Salmon R. falls into this bay from the W. and is remarkable for one of the greatest fiftherics in the world.

CHEGOMEGAN, a point of land about 60 miles in length, on the S. fide of lake Superior. About 100 miles W. of this cape, a confiderable R. falls into the lake; upon its banks abundance of virgin copper is found.

CHEKOUTIMIES, a nation or tribe of Indians, who inhabit near the S. bank of Saguenai R. in Upper Canada.

CHELMSFORD, a township in Mid. dlefex co. Maffachuletts, fituated on the S. fide of Merrimack R. 26 miles N. westerly from Boston, and contains 1144 inhabitants. There is an ingenioufly conftructed bridge over the R. at Pawtucket Falls, which connects this town with Dracut. The route of the Middlefex canal, defigned to connect the waters of Merrimack with those of Bofton harbour, will be foutherly thro' the E. part of Chelmsford.

CHELSEA, called by the ancient natives Winnifimet, a town in Suffolk co. Maffachufetts, containing 472 inhabi tants. Before its incorporation, in 1738, it was a ward of the town of Bolton. It is fituated north eafterly of the metropolis, and leparated from it by the ferry acrois the harbour, called Winnifimet.

CHELSEA, a township in Orange co. Vermont, having 239 inhabitants.

CHELSEA, the name of a parish in the city of Norwich (Conn.) called the Landing, lituated at the head of the river Thames, 14 miles N. of New-London, on a point of land formed by the junction of Shetucket and Norwich, or Little rivers, whole united waters conflitute the Thames. It is a bufy, commercial, thriving, romantic, and agreeable place, of about 150 houles, alcending one above another in tiers, on artificial foundations, on the fouth point of a high, rocky hill.

CHEMUNG. The western branch of Sufquehannah R. is fometimes fo called See Tioga River.

CHEMUNG, is a township in Tioga co. New-York. By the ftate cenfus of 1796, 81 of its inhabitants were electors. arge and deep bay on the catternmost It has Newton W. and Owego F about bout 160 miles N.W. from New-York

city, measuring in a firaight line. Between this place and Newton, Gen. Sullivan, in his victorious expedition against the Indians, in 1779, had a def-perate engagement with the Six Nations, om he dejeated. The Indians were frongly intrenched, and it required the oft exertions of the American army with field pieces, to diflodge them ; although the former, including 2 50 tories, amounted only to 800 men, while the Americans were 5000 in number, and well appointed in every respect.

CHESENGO, is a northern branch of Sulquehannah R. Many of the military ownships are watered by the N.W. manch of this river. The towns of Fayette, Jerico, Greene, Clinton, and Chenengo, in Tioga co. lie between this river and the E. waters of Sulquehannab. CHENENGO, a post town, and one of the chief in Tioga co. New-York. The fettled part of the town lies about 40 iles N.E. from Tioga point, between Chenengo R. and Sufquehannah ; has the own of Jerico on the northward. By the flate centus of 1796, 169 of its inabitants are electors. It was taken off from Montgomery co. and in 1791, it had only 45 inhabitants. It is 375 miles N. N. W. of Philadelphia.

CHENESSEE, or Geneffee R. rifes in Pennfylvania, near the fpot which is the highest ground in that state, where the enternmost water of Alleghany river, and Pine creek, a water of Sulquehannah, and Tioga R. rife. Fifty miles from its fou ce there are talls of 40 feet, and 5 from its mouth of 75 feet, and a little ove that of 96 feet. These falls furnifh excellent mill-feats, which are improved by the inhabitants. After a ourse of about 100 miles, mostly N.E. by N. it empties into lake Ontario, 41 miles E. of Irondequat or Rundagut bay, and so E. from Niagara falls.

The fettlements on Cheneffee R. from its mouth upwards, are, Hartford, On-tario, Wadiworth and Williamfburgh. The last mentioned place, it is probable, will foon be the feat of extensive commerce. There will not be a carrying place between New-York city and Wiliamfourgh, when the wettern canals and seks that be completed. The carrying places at prefent are as follows, viz. Albany to Schenectady 16 miles, from the head of the Mohawk to Wood creek

CHE

1, Ofwego Falls, 2; CheneffedFalls, 2; fo that there are but 21 miles land carrie neceffary; in order to convey commodi ties from a tract of country capable of maintaining feveral millions of people. The famous Cheneffee flats lie on the borders of this river. They are about so miles long, and about 4 wide; the foil is remarkably richy quite clear of trees, producing grafs near to feet high. These flats are estimated to be worth 6.200,000, as they now lie. They are mostly the property of the Indians.

CHEPAWAS, or Chipervays, an Indian nation inhabiting the coaft of lake Superior and the iflands in the lake. They could, according to Mr. Hutchins, furnifh 1000 warriors 20 years ago. Other tribes of this nation inhabit the country round Saguinam or Sagana bay and lake Huron, bay Puan, and a part of lake Michigan. They were lately hof-tile to the United States, bur, by the treaty of Greenville, August 3, 1795, they yielded to them the ifland de Bois Blanc, See Six Nations.

CHEPAWYAN Fort, is fituated on a peninfula at the S. weftern end of Athapelcow lake, N. lat. 58. 45. W. long 110. 18.; in the territory of the Hud. fon bay company. 3010 82 CHEPELLO, an ifland in the bay of Panama, S. America, and in the province of Darjen, 3 miles from the town of Panama, and supplies it with provi-fions and fruits. N. lat. 8. 46. E. long. 80. 45. CHEPOOR, a fmall Spanish town on

the ifthmus of Darien and Terra Firma, in S. America, feated on a river of the fame name, 6 leagues from the fea. Lat. 10. 42. long. 77. 50.

CHEQUETAS, or Seguataneio, on the coaft of Mexico, or New-Spain, lies 7 miles weftward of the rocks of Seguataneio. Between this and Acapulco, to the caftward, is a beach of fand of 18 leagues extent, against which the fea breaks to wiolently, that it is impoffible for boats to land on any part of it; but there is a good anchorage for fhipping at a mile or two from the fhore, during the fair feafon. The harbour of Cheque tan is very hard to be traced, and of great importance to fuch veffels as cruize in thefe leas, being the moft fecure, har-bour to be met with in a wast extent of coaft, yielding plenty of wood and warer; and the ground near it is able to

e de Lord vas u Сн rovin mot afh s CHI countr lina of diftrie on th Camd miles vided Chefte cenfus habita habita the fta a fen Georg Cong Great Aream is this The Chath trict i from town. Сн on T ket of fions 1 Сн Tenno was f branc the m Knox Сн tion, 1 in the the for neffee rokee rate t Tenn Creek of the to the Six N at W Great them yet fe drawn Holfto

be

Lord Anion touched here, the place was uninhabited.

of he ut he of

h. th

re

ân

eyrer aid of se 5is

「二日日

「「「「「「「」」」

19 1,

er.

27

OBABE

hn hn a lu

e

f

CHERA, a river near Colan, in the revince of Quito, in Peru, running to Amotage ; from whence Paita has its afh water. CHERAWS, a diffrict in the upper ountry of S. Carolina, having N. Carolina on the N. and N. E. ; Georgetown diffrict on the S. E. and Lynche's creek on the S. W. which feparates it from Camden diffriel. Its length is about 83 miles and its breadth 63; and is fubdivided into the counties of Darlington, Chefterfield and Mariborough. By the cenfus of 1791, there were 10,706 inhabitants, of which 7618 were white inhabitants, the reft flaves. It fends to the flate legiflature 6 reprefentatives and a fenators ; and in conjunction with Georgetown diftrict, sone member to Congress. This diftrict is watered by Great Pedee R. and a number of fmaller ftreams, on the banks of which the land is thickly fettled and well cultivated. The chief towns are Greenville and Chatham. The court-house in this diftrict is 52 miles from Camden, as far from Lumberton, and 90 from George-town. The mail ftops at this place.

CHERIPPE, an inconfiderable village on Terra Firma, from which the market of Panama is furnished with provifions weekly.

CHEROKEE, the ancient name of Tenneffee R. The name of Tenneffee was formerly confined to the fouthern branch which empties 15 miles above the mouth of Clinch R. and 18 below Knoxville.

CHEROKEES, a celebrated Indian nation, now on the decline. They refide in the northern parts of Georgia, and the fouthern parts of the flate of Tenneffee; having the Apalachian or Cherokee mountains on the E. which leparate them from N. and S. Carolina, and Tenneffee R. on the N. and W. and the Creek Indians on the S. The country of the Cherokees, extending weltward to the Millifippi and northward to the Six Nations, was furrendered, by treaty at Weftminster, 1729, to the crown of Great-Britain. The prefent line between them and the flate of Tenneffee is not yet fettled. A line of experiment was drawn in 1792, from Clinch R. acrois Holfton to Chilhove mountain; but 583

he defended by a few men. When the Cherokee commissioners not annear. ing, it is called a line of experiment. The complection of the Cherokees is hter than that of the neighbouri Indians. They are robuft and wel made, and taller than many of their neighbours; being generally 6 feet high a few are more, and fome lefs. Their women are tall, flender, and delicate. The talents and morals of the Chero kees are held in great effeens. Th were formerly a powerful nation; but by continual wars in which it has been their definy to be engaged, with the northern Indian tribes, and with the whites, they are now reduced to about 1 500 warriors ; and they are becoming weak and pufillanimous. Some writers eftimate their numbers at 2 500 warriors. They have 43 towns now inhabited.

CHERRY Valley, a post town in Otfego co. New-York, at the head of the creek of the fame name, about 12 miles N. E. of Cooperftown, and 18 foutherly of Conajohary, 61 W. of Albany and 336 from Philadelphia. It contains about 30 houfes, and a Prefbyterian church. There is an academy here, which contained in 1796, 50 or 60 fcho-lars. It is a spacious building, 60 feet by 40. The township is very large, and lies along the E. fide of Otiego lake and its outlet to Adiquatangie creek. By the fate cenfus of 1796, it appears that 620 of its inhabitants are electors. This fettlement fuffered feverely from the Indians in the late war

CHESAPEAK, is one of the largeft and fafelt bays int the United States. Its entrance is nearly E.N.E. and S.S.W. between Cape Charles, lat. 17. 12. and Cape Henry, lat. 37. in Virginia, 12 miles wide, and it extends 270 miles to the northward, dividing Virginia and Maryland. It is from 7 to 18 miles broad, and generally as much as 9 fathoms deep; affording many commodi ous harbours, and a fafe and eafy navigation. It has many fertile islands, and thefe are generally along the E. fide of the bay, except a few folitary ones near the weftern fliore. A number of navigable rivers and other ftreams empty into it, the chief of which are Sufguehannah, Patapico, Patuxent, Potowmack, Rappahannock, and York, which are all large and navigable. Chelapeak bay affords many excellent fisheries of henring and fhad. There are also excelent

lent crabs and oyfters. It is the refort of Springfield. It contains 177 houfes, wans, but is more particularly remarkable for a species of wild duck, called canvasback, whole flesh is entirely free from any fifty tafte, and is admired by epicures, for its richnels and delicacy. In a commercial point of view, this bay is of immenfe advantage to the neighbouring flates, particularly to Virginia. Of that fate it has been observed, with fome little exaggeration, however, that " every planter has a river at his door."

CHEESADAWD Lake, about 210 miles N. E. by E. of the Canadian house, on the E. end of Slave lake, in the Hudion bay company's territory; is about 35 miles in length and the fame in breadth. Its western shore is mountainous and rocky.

CHESHIRE Co. in New-Hampfhire. lies in the S. W. part of the ftate, on the E. bank of Connecticut river. It has the flate of Maffachufetts on the fouth, Grafton co. on the N. and Hillfborough co. E. It has 34 townships, of which Charleftown and Keene are the chief, and 28,772 inhabitants, including 16 flaves.

CHESHIRE, a township in Berkshire co. Maffachufetts; famous for its good cheefe; 140 miles N. wetterly from fton. Bo

CHESHIRE, a township in New-Haven co. Connecticut, 15 miles N. of New-Haven city, and 26 S. W. of Hartford. It contains an Epifcopal church and academy, and three Congregational churches.

CHESNUT Hill, a township in Northampton co. Pennfylvania.

CHESNUT Creek, a branch of the Great Kanhaway, in Virginia, where it croffes the Carolina line. Here, it is faid, are iron mines. CHESNUT Ridge. Part of the Alle-

hany mountains, in Pennfylvania, are thus called, S. eastward of Greensborough.

CRESTER, a township in Lunenburg co. Nova Scotia, on Mahone bay, fettied originally by a few families from New-England. From hence to Windfor is a road, the diftance of 25 miles. CHESTER, a fmall plantation in Lincoln co. Maine, 9 miles from Titcomb. It has 8 or 9 families.

CHESTER, a township in Hampshire co. Maflachufetts, adjoining Weftfield and 1119 inhabitants.

the fu

in De

2 bur

and 3

to pr

place.

of De

phia;

in bre

of wh

and 2

are fl

north

Thefe

bar ir

CH

na, 21

and s

office

CH

the e

rifes 1

ware

Ando

town

paffin

miles.

and

direa

bay,

ifland

on th

cates

poled

long, an ha

on U

Delay

doah

of la

len's

form

W.c

long.

5. C:

the d

6866

white

repre

ftate

CI

co. V

of Ja

and 6

Ham

C

C4

CH

CH

CHESTER, a large, pleafant, and ele-gant township, in Rockingham co. New-Hampfhire. It is 21 miles in length; and on the W. fide is a pretty large lake, which fends its waters to Merrimack R. It was incorporated in 1722, and contains 1902 inhabitants, who are chiefly farmers. It is fituated on the E. fide of Merrimack R. 14 miles N.W. of Haverhill, as far W. of Excter, 35 W. by S. of Portimouth, 6 northerly of Londonderry, and 306 from. Philadelphia. From the compact part of this town there is a gentle defcent to the fea, which, in a clear day, may be feen from thence. It is a post town, and contains about 60 houses and a Congregational church.

Rattleinake hill, in this township, is a great curiofity : it is half a mile in diameter, of a circular form, and 400 feet high. On the S. fide, 10 yards from its bafe, is the entrance of a cave, called the Devil's Den, which is a room 15 or 20 feet square, and 4 feet high, floored and circled by a regular rock, from the upper part of which are dependent many excreicences, nearly in the form and fize of a pear, which, when approached by a torch, throw out a sparkling luttre of almost every hue. It is a cold, dreary place, of which many frightful ftories are told by those who delight in the marvellous.

CHESTER, a township in Windfor co. Vermont, W. of Springfield, and II miles W. by S. of Charleftown, in New-Hampfhire, and contains 981 inhabitants.

CHESTER, a borough and post town in Pennfylvania, and the capital of Delaware co. pleafantly fituated on the W. fide of Delaware R. near Marcus Hook, and 13 miles N.E. of Wilmington. It contains about 60 houfes, built on a regular plan, a court-houfe and a gaol. From Chefter to Philadelphia is 20 miles by water, and 15 N. E. by land; here the river is parrowed by iflands of marth, which are generally banked, and turned into rich and immeniely valuable meadows. The firft colonial affembly was convened here, the 4th of December, 1682. The place affords genteel inns and good entertainment, and is the refort of much on the E. and about 20 miles N. W. of company from the metropolis, during. the

the fummer feafon. It was incorporated in December, 1795, and is governed by a burgefics, a conftable, a town-clerk, and 3 affiftants; whole power is limited to preferve the peace and order of the place.

CHESTER Co. in Pennfylvania, W. of Delaware co. and S. W. of Philadelphia; about 45 miles in length, and 30 in breadth. It contains 33 townships, of which West-Chester is the shire town, and 27,937 inhabitants, of whom 145 are flaves. Iron ore is found in the northern parts, which employs 6 forges. These manufacture about 1000 tons of bar iron annually.

in

ed es 6

m rt to be

.

is in ois on lo is -n na he

FRUT NOSTERSPONDED

CHESTER Court-Houfe, in S. Carolina, 22 miles S. of Pinckney court-houfe, and 58 N. W. of Columbia. A poltoffice is kept here.

CHESTER R. a navigable water of the caftern fhore of Maryland, which rites two miles within the line of Delaware flate, by two fources, Cyprus and Andover creeks, which unite at Bridgetown; runs nearly S. weftward; after pafing Chefter it runs S. nearly 3 miles, when it receives S. E. creek, and 15 miles farther, in a S. W. direction, it empties into Chefapeak hay, at Love point. It forms an ifland at its mouth, and by a channel on the E. fide of Kent I. communicates with Eaftern bay. It is propoled to cut a canal, about 11 miles long, from Andover creek, a mile and an half from Bridgetown, to Salifbury, on Upper Duck creek, which falls into Delaware at Hook ifland.

CHESTER, a fmall town in Shannandoah co. Virginia, fituated on the point of land formed by the junction of Allen's or North R. and couth R. which form the Shannandoah; 16 miles S. by W. of Winchefter. N. lat. 39. 2. W. long. 78. 22.

CHESTER Co. in Pinckney diffrict, 6. Carolina, lies in the S. E. corner of the diffrict, on Wateree R. and contains 6866 inhabitants; of whom 5866 are whites, and 938 flaves. It fends two reprefentatives, but no fenator, to the ftate legiflature.

CHESTER, a town in Cumberland co. Virginia, fituated on the S.W. bank of James R. 15 miles N. of Blandford, and 6 S. of Richmond.

CHESTERFIELD, a township in Hampshire co. Massachufetts, 14 miles

W. of Northampton. It contains 180 houles, and 1183 inhabitants.

CHESTERFIELD, a township in Che-fhire co. New-Hampshire, on the E. bank of Connecticut R. having Weftmoreland N. and Hinfdale S. It was incorporated in 1752, and contains 1905 inhabitants. It lies about as miles S. by W. of Charlestown, and about 90 or 100 W. of Portimouth. About the year 17 30, the garrifon of fort Dummer was alarmed with frequent explosions and with columns of fire and fmoke emitted from West river mountain, in this township, and 4 miles diffant from that fort. The like appearances have been observed at various times fince: particularly one in 1752, was the mol fevere of any. There are two places, where the rocks bear marks of having been heated and calcined.

CHESTERFIELD Co. in S. Carolina, is in Cheraws district, on the N. Carolina line. It is about 30 miles long, and 29 broad.

CHESTERFIELD Co. in Virginia, is between James and Appamatox rivers. It is about 30 miles long, and 25 broad 5 and contains 14,214 inhabitants, including 7487 flaves.

CHESTERFIELD Inlet, on the W. fide of Hudfon bay, in New South Wales upwards of 200 miles in length, and from 10 to 30 in breadth-full of iflands. CHESTERTOWN, a post town and the capital of Kent co. Maryland, on the W. fide of Chefter R. 16 miles S. W. of Georgetown, 38 E. by S. from Baltimore, and 81 S. W. of Philadelphia. It contains about 140 houfes, a church, college, court-house, and gaol. The college was incorporated in 1782, by the name of Washington. It is under the direction of 24 truftees, who are empowered to fupply vacancies and hold effates, whole yearly value shall not exceed f.6000 currency. In 1787, it had a permanent fund of f.1250 a year fettled upon it by law. N. lat. 39. 12. W. long. 75. 57.

CHETIMACHAS. The Chetimachas fork is an outlet of Miffifippi R. in Louifiana, about 30 leagues above New-Orleans, and after running in a foutherly direction about 8 leagues from that river, divides into two branches, one of which runs S. wefterly, and the otner S. eafterly, to the diffance of 7 leagues, when they both empty their waters into

the

the Mexican gulf. On the Chetimachas, 6 leagues from the Miffifippi, there is a fettlement of Iadians of the lame name; and thus far it is uniformly too yards broad, and from z to 4 fathoms deep, when the water is lowelt Some drifted logs have formed a fhoal at its mouth on the Miffifippi; but as the water is deep under them, they could be eafily removed; and the Indians fay there is nothing to impede navigation from their village to the gulf. The banks are more elevated than thole of the Miffifipi, and in fome places are fo high as never to be overflowed. The natural productions are the fame as on the Miffifippi, but the foil, from the extraordinary fize and compactuefs of the canes, is fuperior. If meafures were adopted and purfued with a view to improve this communication, there would foon be, on its banks, the most prosperous and important fettlements in that colony.

CHI

CHETIMACHAS, GRAND LAKE OF, in Louisiana, near the mouth of the Missifippi, is 24 miles long, and 9 broad. Lake de Portage, which is 13 miles long, and 11 broad, communicates with this lake at the northern end, by a ftrait a quarter of a mile wide. The country bordering on these lakes, is low and at, timbered with cyprefs, live and other kinds of oak; and on the eaftern fide, the land between it and the Cha-falaya R. is divided by innumerable treams, which occasion as many islands. ome of these freams are navigable. A little diftance from the S. eathern fhore of the lake Chetimachas, is an ifland where perions paffing that way gene-rally halt as a refting place. Nearly opposite this illand, there is an opening which leads to the fea. It is about 150 yards wide, and has 16 or 17 fathom vater.

CHETTENHAM, a township in Montcomery co. Pennfylvania.

CHIAMETLAN, a maritime province of Mexico, in N. America, with a town of the tame name, faid to be 37 leagues either way, from N. to S. or from E. to W. It is very fertile, contains mines of filver, and produces a great deal of honey and wax. The native Indians are well made and warlike. The river St. Jago empties into the fea here, N. W. from the point of St. Blas. The chief town is St. Sebaltian.

CHD

CHIAPA, a river and inland province of Mexico or New-Spain, in the audi-ence of Mexico. This province is bound-ed by Tobafco on the N.; by Yucatan N. E.; by Socurnufco S. E.; and by Vera Paz on the E. It is 85 leagues from E. to W. and about 30 where narroweft, but fome parts are near 200. It abounds with great woods of pine, cy-prefs, cedar, oak, walnut, wood-vines, aromatic gums, balfams, liquid amber, tacamahaca, copal, and others, that yield pure and fovereign balfams; alfo with corn, cocoa, cotton and wild cochineal; pears, apples, quinces, &c. Here they have achiotte, which the natives mix with their chocolate to give it a bright colour. Chiapa abounds with cattle of all forts; it is famous for a fine breed of horfes, fo valuable, that they fend their colts to Mexico, though 500 miles off. Beafts of prey are here in abundance, with foxes, rabbits, and wild hogs. In this province there is variety of fnakes, particularly in the hilly parts, fome of which are faid to be 20 teet long, others of a curious red colour, and streaked with white and black, which the Indians tame, and even put them about their necks. Here are two principal towns called Chiapa, The Chiapefe are of a fair complexion, courteous, great mafters of mulic, painting and mechanics, and obedient to their fuperiors. The principal river is that of Chiapa, which, running from the N. thro' the country of the Quelenes, at last falls into the fea at Tabafco. It is well watered; and by means of Chiapa R. they carry on a pretty brilk trade with the neighbouring provinces, which chiefly confifts in cochineal and filk; in which laft commodity the Indians employ their wives for making handkerchiefs of all colours which are bought up by the Spaniards and fent to Europe. Tho' the Spaniards reckon this one of their pooreft provinces in America, as having no mines or fand of gold, nor any harbour on the South Sea, yet in fize it is inferior to none but Guatimala. Belides, it is a place of great importance to the Spaniards, becaufe the ftrength of all their empire in America depends on it; and into it is an easy entrance by the river Tabafco, Puerto Real, and its vicinity to Yucatan.

CHIAPA, the name of two towns in the above province; the one is fome-

times city, inhab is a b dicial on a and and S from (is 800 ther p gentry accou poveri and th This chofer town, them W. k Th Indos, dians. count river ' and is pa, of Barthe manki and ha Madri iards privile very. place 1 in it, of Ind river 1 they of In the flocker planta from t make Spania exchan things 20,000 Сн ver in feveral ning S 6 mile ticut a that ri Сн runs 1 Its mo and al times called *Cividad Real*, or the Royal city, and the other *Chiapa de los Indos*, inhabited by Spaniards. Cividad Real is a bifhop's fee, and the feat of the judicial courts. It is delightfully fituated on a plain, furrounded with mountains, and almoft equally diffant from the N. and S. feas, and 100 leagues N. W. from Guatimala. The bifhop's revenue is 8000 ducats a year. The place is neither populous nor rich 3 and the Spanifh gentry here are become a proverb on account of their pride, ignorance, and poverty. It has feveral monafteries 5 and the cathedral is an elegant flruchure. This city is governed by magiftrates choien amongfi the burgefies of the town, by a particular privilege granted them by the king of Spain. N. lat. 27. W. long. 96. 40.

6

d

The other town, called Chiapa de los Indos, that is, as belonging to the Indians, is the largest they have in this country, and lies in a valley near the river Tabasco, which abounds with fift, and is about 12 leagues N. W. of Chia-pa, or Cividad Real. The celebrated Bartholomew de las Cafas, the friend of mankind, was the first bishop of Chiapa ; and having complained to the court of Madrid of the cruelties of the Spaniards here, procured the people great privileges, and an exemption from flavery. This is a very large and rich place with many cloifters and churches in it, and no town has fo many Dons of Indian blood as this Chiapa. On the river they have feveral boats, in which they often exhibit fea-fights and fieges. In the environs are feveral farms well flocked with cattle, and fome fugar plantations. Wheat is brought here from the Spanish Chiapa, and of it they make hard bifcuit, which the poorer Spaniards and Indians carry about and exchange for cotton wool, or fuch little things as they want. There are about 20,000 Indians in this town.

CHICAPEE, or *Chickabes*, a fmall river in Maffachufetts, which rifes from feveral ponds in Worcefter co. and running S. W. unites with Ware river, and 6 miles further empties into the Connectiaut at Springfield, on the E. bank of that river.

CHICCAMOGGA, a large creek which runs N. wefterly into Tenneffee river. Its mouth is 6 miles above the Whirl, and about 27 S. W. from the mouth of the Hiwaffee. N. lat. 15. 18. The Chiccamogga Indian towns lie on this creek, and on the bank of the Tenneffer. See Chickamages.

See Chickamages. CHICHESTER, Upper and Lower, two townships in Delaware co. Pennfylvania.

CHICHESTER, a fmall township in Rockingham co. New-Hampshire, about 35 miles N. W. of Exeter, and 45 from Portsmouth. It lies on Suncook R.; was incorporated in 1727, and contains 491 inhabitants.

CHICKAHOMINY, a fmall navigable river in Virginia. At its mouth in James river, 37 miles from Point Comfort, in Chefapeak bay, is a bar, on which is only 12 feet water at common flood tide. Veffels paffing that, may go 8 miles up the river; those of 10 feet draught 12 miles; and veffels of 6 tons burden may go 32 miles up the river.

CHICKAMACOMICO *Creek*, in Dorchefter co. Maryland, runs foutherly between the towns of Middletown and Vienna, and empties into Fifthing bay.

CHICKAMAGES, a part of the Cherokee nation of Indians, known by this name, inhabit 5 villages on Tenneffee river. See *Chiccamogga*. CHICKASAW Bluff, is on the eaftern

CHICKASAW Bluff, is on the eaftern bank of the Miffifippi, within the territories of the United States, in N. lat. 35. The Spaniards erected here a firong flockaded fort, with cannon, and furnifhed it with troops, all in the fpace of 24 hours, in the month of June, 1795. It has fince been given up according to the treaty of 1796.

CHICKASAW, a creek which falls into the Wabash from the E. a little below Poft St. Vincent.

CHICKASAW, a river which empties into the Miffifippi, on the E. fide, 104 miles N. from the mouth of Margot, and 67 S. W. of Mine au fer. The lands here are of an excellent quality, and covered with a variety of uleful timber, canes, &c. This river may be afcended during high floods upwards of 30 miles with boats of feveral tons burden.

CHICKASAWS, a famous nation of Indians, who inhabit the country on the E. fide of the Miffifippi, on the head branches of the Tombigbee, Mobile and Yazoo rivers, in the N. W. corner of the flate of Georgia, and N. of the country of the Chactaws. Their country is an extensive plain, tolerably well water-

-ed

ed from fprings, and of a pretty good foil. They have 7 towns, the central one of which is in N. lat. 34. 23. W. long. 89. 30. The number of fouls in this nation has been formerly reckoned at 1725, of which 575 were fighting men. There are fome negroes among the Chickafaws, who either were taken captive in war, or ran away from their mafters, and fought fafety among the Indians.

In 1539, Ferdinand de Soto, with 900 men, befides feamen, failed from Cuba with a defign to conquer Florida. He travelled northward to the Chickafaw country about lat. 35. or 36.; and 3 years after died, and was buried on the bank of Miffifippi river.

CHICOMUZELO, a town in the province of Chiapa, in New-Spain, having a cave very narrow at the entry, but fpacious within, with a flagnant lake, which is, however, clear, and is 2 fathoms deep towards the banks.

CHIHEMECOMET Island, or Chickminock-cuminock, on the coaft of North-Carolina, lies between Roanoke island and the northern entrance into Pamlico found.

CHIHOHOEKI, an Indian nation who were confederates of the Lenopi or Delawares, and inhabited the weffern bank of Delaware R. which was anciently called by their name. Their fouthern boundary was Duck creek, in Newcaftle county.

CHIKAGO R. empties into the S. W. end of lake Michigan, where a fort formerly flood. Here the Indians have ceded to the United States, by the treaty of Greenville, a tract of land 6 miles fquare.

CHIGNECTO Channel, the N. weffern arm of the bay of Fundy, into which Petitcodiac R. falls. The fpring tides rife here 60 feet.

CHILAPAN, a town in New-Spain, in the country of the Cohuixcas. Between this and Tcoiltylan is an entire mountain of loadftone.

CHILCA, a town in the jurifdiction of Canette in Peru, S. America, celebrated for its excellent faltpetres of which gunpowder is made in the metropolis. It abounds with plenty of fifh, fruits, pulfe, and poultry, in which it carries on a very confiderable trade with Lima, to leagues diffant. S. lat. 12, 31. W. long. 76+5.

CHI

Ch

on its

guay.

tions.

Chili

fruit.

and

tobac

fome

fome

Euro

brand

ceives

the h

The .

nies is

been f

even

thoug

to Bu

league

and pi Th

in a g

live fc

and it

numbe

not ful

honeft

but, li

are ver

live in

the con

and w

pufhed

and wi

Spania

ineffect

to alce

Chili.

are 40 this be

all the

confide

fuppof

and the

manda

Vicero

to the

to was

as chie

prefide

inferio

vince, i

the de

ountry

Diego

St.]

CHILI, in South-America, is bounded by Peru, on the N.; by Paraguay or La Plata, on the E: by Patagonia, on the S.; and by the Pacific occan on the W. It is in length about 1260 miles, in breadth 580; between 25 and 44. S. lat. and between 65. and 85. W. long. It lies on both fides of the Andes. Chili proper, fies on the W.; and Cuyo or Cutic, on/the E. The principal towns in the former, are St. Jago and Baldivia; in the latter, St John de Frontiera.

The climate of Chili is one of the most delightful in the world, being a medium between the intense hears of the torrid, and the piercing colds of the frigid zones. Along the coaft of the Pacific ocean, they enjoy a fine temperate air, and a clear ferene fky, moft part of the year; but fometimes the winds that blow from the mountains, in winter, are exceeding harp. There are few places in this extensive country, where the foil is not exuberantly rich; and were its natural advantages feconded by the industry of the inhabitants, Chili would be the most opulent kingdom in America.

The horles and mules of Chili, are in great effeem, particularly the former. Prodigious numbers of oxen, goats and fheep are fattened in the luxuriant paftures of Chili, and indeed this is the only part of hufbandry to which the inhabitants pay any confiderable attention. An ox well fattened, may be purchased for four dollars. Turkeys, geefe, and all kinds of poultry, are found here in the fame profusion. The coafts abound with many excellent fift; there are alfo vaft numbers of whales and fea wolves. The foil produces Indian and European corn, hemp, grapes, and all other fruits. The European fruit trees are obliged to be propped to enable them to fuftain the weight of the fruit. Orange trees are in bloom, and bear fruit throughout the year. Olives alfo, and almond trees, thrive exceedingly well; and the inhabitants prefs a kind of mufcadine wine from the grapes, which far exceeds any of the kind made in Spain.

Mines of gold, filver, copper, tin, quickfilver, iron and lead, abound in this country. Vaft quantities of gold are wafhed down from the mountains by brooks and torrents; the annual amount of which, when manufactured, is eftimated at no lefs than 8000,000 dollars. Chili

Chili has always had commercial connections with the neighbouring Indians on its frontiers, with Peru and Paraguay. The Indians, in their tranfactions, are found to be perfectly honeft. Chili fupplies Peru with hides, dried fruit, copper, falt meat, horfes, hemp, and corn; and receives in exchange, tobacco, fugar, cocoa, earthen ware, fome manufactures made at Quito, and fome articles of luxury brought from Europe. To Paraguay fhe fends wine, brandy, off, and chiefly gold; and receives in payment, mules, wax, cotton, the herb of Paraguay, negroes, &c. The commerce between the two colonies is not carried on by fea; it hath been found more expeditious, fafer, and even lets expensive to go by land, though it is 354 leagues from St. Jago to Buenos Ayres, and more than 40 leagues of the way are amidit the inows

n

i,

n

de ie a la din

id fo

8. IN

5.

to

in

es

ut

:5,

ii-

ne

ny

n,

in

old

ns

ial

js

rs.

CHI

and precipices of the Cordilleras. The Indians in this country are ftill in a great measure unconquered; they live fcattered in the deferts and forefts, and it is impoffible to afcertain their numbers. Those Indians, which are not fubject to the Spanish yoke, are very honeft in their commercial transactions; but, like almost all other Indians, they are very fond of fpirituous liquors. They live in fmall huts, which they build in the course of a day or two at farthest; and which they abandon when hard pufhed by an enemy. They are brave and warlike, and all the attempts of the Spaniards to fubdue them have proved ineffectual. It is almost equally difficult to afcertain the number of Spaniards in Chili. The Abbé Raynal fays, there are 40,000 in the city of St. Jago; if this be true, the aggregate number in all the provinces of Chili muft be more confiderable than has been generally fuppofed.

St. Jago is the capital of this country, and the feat of government. The commandant there, is fubordinate to the Viceroy of Peru, in all matters relating to the government, to the finances, and to war; but he is independent of him as chief administrator of juffice, and prefident of the royal audience. Eleven inferior officers, diffributed in the province, are charged under his orders, with the details of administration. This country was first diffeovered by Don Diego d'Almagro, in 1525.

CHILHOWEE Mountain, in the foutheaftern part of the flate of Tenneflee, and between it and the Cherokee country. CHILISQUAQUE, a township on Sufquehannah R. in Pennsylvania.

CHILLAKOTHE, an Indian town on the Great Miami, which was defroyed in 1782 by a body of militia from Kentucky. Gen. Harmar fuppofes this to be the "English Tawixtwi," in Hutchins's map. Here are the ruins of an old fort, and on both fides of the river are extensive meadows. This name is applied to many different places, in honor of an influential chief who formerly headed the Shawanoes. See Tawixtwi.

CHILLAKOTHE, OLD, is an Indian town deftroyed by the forces of the U. S. in 1780. It lies about 3 miles S. of Little Mimia R. The country in its vicinity is of a rich foil, and is beautifully chequered with meadows.

CHILMARK, a township on Martha's Vineyard I. Duke's co. Maffachusetts, containing 771 inhabitants. It lies 99 miles S. by E. of Boston. See Martha's Vineyard.

CHILOE, a confiderable island of Chili, S. America, the S. part of which is divided from the continent by a narrow fea, and the continent there forms a bay; it is fituated between 4a. and 44. of S. latitude, being about 1 50 miles in length and a1 in breadth. The ifland produces all neceffary provisions, excepting wine, and quantities of ambergris are found on the coaft. It has an indifferent fort called Chacao. Caftro, the chief town, ftands between two brooks, with a finall caftle which commands the harbor. It has no other defence, and the houfes are few and fcattered.

CHILLOAS, a jurifdiction in the biftoprick of Truxillo, in S. America.

CHILQUES, a jurifdiction of S. America, in Peru, fubject to the bifhop of Culco, 8 leagues S. E. from that city. Its commerce confifts in woolen manufactures, grain of all kinds, cows, fleep, &c.

CHIMBO, a jurifdiction in the province of Zinto, in S. Amercia, in the torrid zone. The capital is also called by the fame name.

CHIMBORAZO, in the province of Quito, is the higheft point of the Andes, and the higheft mountain as yet known in the world; being, according to Condamine, 19,200 feet; according to G 2 . others, others, 20,608 feet, above the level of the fea. It lies nearly under the line, hei being in 1. 41. 40. S. lat. yet its tops are covered with ice and fnow, and the country adjacent is often pierced with intolerable cold from the winds which

intolerable cold from the winds which blow from the mountain. CHINCA, a large and pleafant valley in the diocefe of Lima, in Peru. Pizarro defired the king of Spain that this might be the limits of his government on the S. and that the river St. Jago fhould bound it on the N. The valley bears good wheat, and Spanish vines thrive well in it.

CHINCACOCA, a lake in Peru, in the town of Cuanuca.

CHIPAWAS. See Chepawas.

CHIPPAWAY, an inconfiderable place ear the falls of Niagara, to miles from Queenftown.

CHIPPEWAY R. runs S. weftward into Miffifippi R. in that part where the confluent waters form lake Pepin, in N. lat. 44. W. long. 93. 54. CHIRAGOW. See Plein river.

CHIRAGOW. See Plein river. CHIRAGOW. See Plein river. CHISSEL, a fort in the flate of Ten-neffice, 24 miles from English ferry, on New river; 43 from Abingdon, and roy from Long island, on Holfton. CHETTENDEN Go. in Vermont, lies on lake Champlain, between Franklin co. on the N. and Additon S.; La Moille river paffes through its N. W. comer, and Onion never divides it near-ly in the center. Its chief town is Burly in the center. Its chief town is Buragton. This county contained, by the cenfus of 1791, 44 townships and 7301 inhabitants. Since that time the northern counties have been taken from it, fo that neither its fize or number of inhabitants can now be afcertained.

CHITTENDEN, a township in Rutland co. Vermont contains 159 inhabi-tants. The road over the mountain paffes through this township. It lies 7 miles E. from the fort on Otter creek, in Pittsford, and about 60 N. by E. from Bennington.

CHITTENENGO, or Canaferage, a confiderable ftream which runs northerly into Lake Oneida, in the ftate of w-York.

CHOCOLATE Creek, a head-water of Tioga R. in New York, whole mouth lies to miles S. W. of the Painted Polt. CHOCOLOCO-CA, which the Spaiards call Caltro Virreyna, a town of Peru, 60 leagues S. eastward of Lima,

is very famous for its filver mines, which are at the top of a great mountain, al-ways covered with fnow, and but a leagues from the town. The flones of the mine are of a dark blue colour; thefe, being calcined and powdered, then fleep-ed in water and quickfilver, the filth is feparated and the filver melted and form-ed into have. ed into bars. These veins are not very rich, but the metal is very fine. They make plenty of wine here, where it attains a greater degree of perfection, ow-ing to the purenels of the air, than it is observed to have elfewhere.

CHOCOPE, a town in the jurifdiction of Truxillo, in S. America, in Peru ; 14 leagues fouthward of St. Pedro. Here are about 90 or 100 houles, and about 60 or 70 families, chiefly Spaniards, with fome of the other caffs, but not above 25 Indian families. It has a church built of brick, both large and decent. The people here mention a rain that fell in 1726, which lafted 40 nights, beginning conftantly at 4 or 5 in the evening, and ceafing at the fame hour next morning, which laid most of the houses in ruins. S. lat. 7. 46.

CHOCORUA, a mountain in Grafton co. New-Hampfhire, on the N. line of Strafford co. N. of Tamworth.

CHOCUITO, or rather Chucuito, or Titi Caca, a large lake near Paria, in S. America, and in Peru, into which a reat number of rivers empty themfelves. It is 240 miles in circumference, and in fome parts 80 fathoms deep; yet the water cannot be drank, it is fo very turbid. It abounds in fifh, which they dry and falt, and exchange with the neighbouring provinces for brandy, wines, meal, or money. It is faid the ancient Yncas, on the conqueft of Peru, by the Spaniards, threw into this lake, all their riches of gold and filver. It was this lake into which the Ynca Huana Capac, threw the famous chain of gold, the value of which was immense. It abounds with flags and ruthes, of which Capac Vaupanchi, the fifth Ynca, built a bridge for transporting his army to the other fide.

CHOISEUL Bay, on the N. W. coaft of the iflands of the Arfacides, W. of Port Praflin. The inhabitants on this bay, like those at Port Praflin, have a cultom of powdering their hair with lime, which burns it and gives it a red appearance. Barnet ...

CHOPS,

of t tying C Caro foun of w Eder C into foun but I form by tl way, Virg Ci ton d inhal 2377 CI caftle navis from and town and a decli prof_j Dela with great vigal Chef at th Swed their CI abov ware Wilr It 9 mil tion Chri caftle mile Wilm Сн fa ift lies 1 Pedr Refo W. 1 30. S wich

2302.0

C aret

fee. C

are three miles from Swan-Mand; which fee.

CHOPTANK, a large navigable river of the eaftern fhore of Maryland emp-

tying into Chefapeak bay. CHOWAN Co. in Edenton diffrict, N. Carolina, on the N, fide of Albemarle found. It contains 5011 inhabitants, of whom 2588 are flaves. Chief town, Edenton.

P-is

ry

ey

N-

is

on

14

ire

art

ith

ve

ch

nt.

iat

rem-

ext

fes

ton

of

OF S.

1 2

-m-

ice,

p; 1 fo

ich

rith

dy, the

ru,

ke,

Hu-

1 of

nfe.

, of

nca,

my

oaft

. of

this

ve a

with

red

OPS,

It

CHOWAN R. in N. Carolina, falls into the N. W. corner of Albemarle found. It is 3 miles wide at the mouth. but narrows fast as you ascend it. It is formed 5 miles from the Virginia line, by the confluence of Meherrin, Nottaway, and Black rivers, which all rife in Virginia.

CHRIST CHURCH, a parish in Charleston diffrict, S. Carolina, containing 29 54 inhabitants, of whom 566 are whites, 2377 flaves.

CHRISTIANA, a post town in Newcaftle co. Delaware, is fituated on a navigable creek of its name, 12 miles from Elkton, 9 S. W. of Wilmington, and 37 S. W. of Philadelphia. The town, confifting of about 50 houles, and a Prefbyterian church, stands on a declivity which commands a pleafant profpect of the country towards the Delaware. It carries on a brifk trade with Philadelphia in flour. It is the greatest carrying place between the navigable waters of the Delaware and Chefapeak ; which are 13 miles afunder at this place. It was built by the Swedes, in 1640, and thus called after their queen.

CHRISTIANA Creek, on which the above town is fituated, falls into Delaware R. from the S. W. a little below Wilmington.

It is proposed to cut a canal of about 9 miles in length, in a S. weftern direction from this creek, at the town of Christiana (6 miles W. S. W. of Newcaftle) to Elk R. in Maryland, about a mile below Elkton. See Delaware, and Wilmington.

CHRISTIANA, ST. one of the Marquefa ifles, called by the natives Waitahu, lies under the fame parallel with St. Pedro, 3 or 4 leagues more to the weft. Refolution bay, near the middle of the W. fide of the ifland, is in lat. 9. 55. 30. S. long. 139. 8. 40. W. from Green-

CHOPS, THE, in Kennebeck river, rethree miles from Swan-Ifland; which e. CHOPTANK, a large navigable river f the caftern fhore of Masyland emp-ing into Chefapeak bay.

CHRISTIANSBURG, the chief town of Montgomery co. Virginia. It contains very few houfes; has a court-houfe and gaol, fituated near a branch of Little R.

a water of the Kanhaway. N. lat 37. 5. CHRISTIANSTED, the principal town in the island of Santa Cruz, fituated on the N, fide of the ifland, on a fine harbour. It is the refidence of the Danifh governor, and is defended by a ftone fortrefs.

CHRISTMAS Ifland, in the Pacific ocean, lies entirely folitary, nearly equal-ly diftant from the Sandwich iflands on the N. and the Marquefas on the S. It was fo named by captain Cook, on ac-count of his first landing there, on Christmas day. Not a drop of fresh Christmas day. Not a drop of fresh water was found by digging. A ship touching at this defolate isle must expect nothing but turtle, fifh, and a few birds. It is about 15 or 20 leagues in circumference, and bounded by a reef of coral rocks, on the W. fide of which there is a bank of fine fand, extending a mile into the fea, and affording good anchorage. N. lat. 1. 59. W. long. 157. 30.

CHRISTMAS Sound, in Terra del Fuego, South America, in N. lat 55. 21. long. 69. 57.

CHRISTOPHERS, ST, an island in the Weft-Indies, belonging to Great-Britain, commonly called by the failors, St. Kitts; by the ancient Indians, Ay-ay; and by the Charaibes, Liamniga, or the fertile ifland, is fituated in N. lat. 17. W. long. 62.; and is 20 miles long and 7 broad, containing about 80 fquare miles. It was discovered in November, 1493, by Columbus himfelf, who was fo pleafed with its appearance, that he honoured it with his own chriftian name ; but it was neither planted nor poffefied by the Spaniards. It is however, the oldeft of all the British territories in the Weft Indies. In 1626, it was fettled by the French and English conjointly; but entirely ceded to the latter by the peace of Utrecht. Great quantities of indigo were formerly raifed here. In 1770, the exports amounted to above wich; and the W. end of Dominica 6.419,000 fterling, in fugar, molafies, G 3 and

and run; and near £.8000 for cotton. Befides cotton, ginger, and the tropical fruits, it produced, in 1787, 231,397 ewt. of fugar, and in 1790, but about 113,000 cwt. It is computed that this ifland contains 6000 whites and 36,000 negroes. In February, 1782, it was taken by the French, but reftored to Britain by the treaty of 1783. CHUMBI VILCAS, a jurifdiction fub-

CHUMBI VILCAS, a jurifdiction fubject to the bishop of Cusco, in S. Americ, and empire of Peru, about 40 leagues from that city; it produces corn, fruits, large pastures for cattle, and mines of gold and filver.

CHURCH Greek Town, in Dorchefter eo. Maryland, lies at the head of Church creek, a branch of Hudson R. 7 miles S. wefterly from Cambridge.

CHURCH HILL, a village in Queeen Anne's co. Maryland, at the head of S. E. Creek, a branch of Chefter R.; N. W. of Bridgetown, and N. E. of Centreville 8 miles, and 85S. W. from Philadelphia. N. lat. 40. 9. W. long. 75. 53.

CHURCH HILL, Fort, in New N. Wales, ftands at the mouth of Seal R. on the E. fide of Hudson Bay; 120 miles N. N. E. of York fort. N. lat. 48. 58. W. long. 94. 13.

CHURCHILL R. in New South Wales, runs N. eafterly into the W. fide of Hudíon bay, at Church Hill fort, in lat. 58. 57. 32. N. long. 94. 12. 30. W. See New-Britain, Shechary, Sc.

CHURCHTOWN, a village, to called, in the N. E. part of Lancaster co. Pennfylvania, about so miles E. N. E. of Lancaster, and 50 W. N. W. of Philadelphia. It has 12 houles, and an Epifcopal church; and in the environs are two forges, which manufacture about 450 tons of bar iron annually.

CIACICA, a jui idiction in S. America, in Peru, fubject to the archbishop of Plata, and 90 leagues distant from that city; abounding in cocoa, cattle, and fome fiver mines.

CIBOLA, or Civola, the name of a town in, and alfo the ancient name of, New-Granada, in Terra Firma, South-America. The country here, though not mountainous, is very cool; and the Indians are faid to be the whiteft, wittieft, moft fincere and orderly of all the aboriginal Americans. When the country was difcovered, they had each but one wife, and were exceffively jealous. They worthipped water, and an old

woman that was a magician; and believed fhe lay hid under one of their lakes.

CICERO, a military township in New-York, on the S. W. fide of Oneida lake, and between it, the Salt lake, and the Salt springs.

CINALOA, called by fome Cinoleo, province in the audience of Galicia, in Old Mexico, or New-Spain. It has the gulf of California on the W. the province of Culiacan on the S. and the kingdom of New-Mexico on the N. and E. From S. E. to N. E. it is about 100 leagues; and not above 40 where broadeft. On the E. fide it is bounded by the high, craggy mountains, called Tepecfuan, 30 or 40 leagues from the fea. It is well watered, its rivers abound with fifh, and the air is ferene and healthful. It abounds with all forts of fruit, and grain, and cotton. The natives are hardy and industrious, and manufacture cotton cloth, with which they clothe themfelves.

CINCINNATI, a flourishing town in the territory of the U.S. N.W. of the Ohio, and the prefent feat of government. It flands on the N. bank of the Ohio, opposite the mouth of Licking R. 2½ miles S. W. of Fort Washington, and about 8 miles wefterly of Columbia. Both these towns lie between Great and Little Miami rivers. Cincinnati contains about 200 houses; and is 82 miles N. by E. of Frankfort; 90 N.W. of Lexington, and 779 W. by S. of Philadelphia. N. lat. 39. 22. W. long. 85.

CINCINNATUS, is the S. eafternmoft of the military townships of New-York state. It has Virgil on the W. and Salem, in Herkemer co. on the E. and lies on two branches of Tioughnioga R. a N. western branch of the Chenango. The centre of the town lies 53 miles S. W. by W. or Cooperstown, and 39 S. E. by S. of the S. E. end of Salt Lake. N. lat. 42. 30.

CIRENCESTER. See Marcus Hook. CITY Point, in Virginia. See Bermuda Hundred.

CIVIDAD REAL, the capital city of Chiapa, in New-Spain. Chilton, an Englishman, fays the Indians called it Sacatlan, and that, in 1570, it contained about 100 Spanish inhabitants. See Chiapa.

CIVIDAD REAL, is the capital of the province

provi of Pa CL pri offici mout river rect 1 above thence with t fippi | and u anni the fa CL W.o of fo which 21 mi CL betwe North in cir ters o Michi them D'Etr into la of the fels of D'Etr CL CL bay, i bas at of wo CL. 0. N Conne mount fide of mouth Po tín \$764, CL. S. Ca bitant the co CL CL Camd 30 mi tains CL centre ed by Aream . SOF

of Paraguay. CLAIR, ST. a county in the territory N. W. of the Ohio; was laid off 27th April, 1790. Its boundaries are thus officially deficibed : "Beginning at the mouth of the Little Michillimackinack river; running thence foutherly in a direct line to the mouth of the Little river above fort Maffac, upon the Ohio river; thence with the Ohio to its junction with the Miffifippi; thence up the Miffi-fippi to the mouth of the Illinois river; and up the Illinois to the place of be-ginning, with all the adjacent iflands of the faid rivers Illinois and Miffifippi. CLAIR, ST. a fort in the territory N. W. of the Ohio, is fituated 25 miles N. of fort Hamilton, on a fmall creek which falls into the Great Miami; and 2.1 miles S. of fort Jefferson.

CLAIR, ST. I.ake, lies about half way between lake Huron and lake Erie, in North America, and is about 90 miles in circumference. It receives the waters of the three great lakes, Superior, Michigan, and Huron, and difcharges them through the river or ftrait, called D'Etroit (which is in French, the ftrait) into lake Erie. Its channel, as alto that of the lake, is fufficiently deep for veffels of very confiderable burden. See D'Etroit.

n

c - c

d

id sf -. fkdd.

n it

CLAM Town. See Egg barbour.

CLARE, a township on St. Mary's bay, in Annapolis co. Nova-Scotia. It has about 50 families, and is composed of woodland and falt marfh.

CLAREMONT, a township in Cheshire o. New-Hampshire, on the E. fide of Connecticut river, opposite Ascutney mountain, in Vermont, and on the N. fide of Sugar R.; 24 miks S. of Dartmouth college, and 121 S. W. by W. of Po timouth. It was incorporated in 1764, and contains 1435 inhabitants.

CLAREMONT Co, in Camden diffrict, S. Carolina, contains 2479 white inha-bitants, and 2110 flaves. Statefburg is the county town.

CLARENDON. See Cape Fear river. CLARENDON Co. the fouthernmost in Camden district, S. Carolina, is about 30 miles long and 30 broad, and contains 1790 whites and 602 flaves.

CLARENDON, a township near the centre of Rutland co. Vermont, watered by Otter Creek and its tributary Arcams; 14 or 15 miles E. of Fairha-

province of Guaira, in the E. division ven, and 44 N. E. of Bennington. It contains 1478 inhabitants. On the S. E. fi e of a mountain in the westerly part of Clarendon, or in the edge of Tinmouth, is a curious cave, the mouth of which is not more than 11 feet in diameter. In its descent, the paffage makes an angle with the horizon of 35 or 40 degrees; but continues of nearly the fame diameter through its whole length, which is 311 feet. At that diftance from the mouth, it opens into a spacious room, 20 feet long, 121 wide, and 18 or 20 feet high. Every part of the floor, fides and roof of this room appear to be a folid rock, but very rough and uneven. The water is continually percolating through the top, and has formed stalactites of various forms ; many of which are conical, and fome have the appearance of maffive columns. From this room there is a communication by a narrow paffage to others equally curious.

CLA

CLARKE, a new county of Kentucky, between the head waters of Kentucky and Licking rivers. Its chief town is Winchefter.

CLARKSBURG, the chief town of Harrifon co. Virginia. It contains about 40 houfes, a court-houfe, and gaol; and flands on the E. fide of Monongahela R. 40 miles S. W. of Morgantown.

CLARKSTOWN, in Orange co. New-York, lies on the W. fide of the Tappan Sea, 2 miles diftant; northerly from Tappan township, 6 miles, and from New-York city, 29 miles. By the flate cenfus of 1796, 224 of its inhabitants are electors.

CLARKSVILLE, the chief town of what was till lately called Tenneffee co. in the flate of Tenneflee, is pleafantly fituated on the E. bank of Cumberland R. and at the mouth of Red river, opposite the mouth of Muddy Creek. It contains about 30 houses, a court-house and gaol, 45 miles N. W. of Nashville; 220 N. W. by W. of Knoxville, and 940 W. by S. of Philadelphia.

N. 1 st. 36, 25. W. long. 88. 57. CLARKSVILLE, a final fettlement in the N. W. territory, which contained, in 1791, about 60 louls. It is fituated on the northern bank of the Ohio, oppofite Louisville, a mile below the Rapids, and 100 miles S. E. of Poft Vincent. It is frequently flooded, when the river is high, and inhabited by people, G4

ble, who cannot, at prefent, find a bet- | nearly as large as the main river, is naer fituation.

104

CLAVERACK, a post town in Columbia co. New-York, pleafantly fituated on a large plain, about 21 miles E. of Hudion city, near a creek of its own name. It contains about 60 houfes, a Dutch Church, a court house, and a aol. The township, by the census of 1791, contained 3262 inhabitants, including 340 flaves. By the ftate cenfus of 1796, there appears to be 412 electors. It is 231 miles from Philadelphia CLERK's Ifles, lie S. W. from; and at the entrance of Behring's ftraits, which separate Afia from America. They rather belong to Afia, being very near, and S. S. W. from the head land which lies between, the straits and the gulf of Anadir, in Afia. They have their name in honour of that able navigator, Capt. Clerk, the companion of Capt. Cook. In other Maps they are called St Andrea Ifles.

CLERMONT, a post town in Colum-bia co. New-York, 6 miles from Red Hook, 15 from Hudson, 117 miles N. of New York, and 212 from Philadel-phia. The township contains 867 inhabitants, inclusive of 113 flaves.

CLERMONT, a village 13 miles from Camden, South Carolina. In the late war, here was a block-houfe encompaffed by an abbatis. It was taken from col. Rugely, of the British militia, in Dec. 1781, by an ingenious ftratagem of lieut. col. Washington.

CLIE, LAKE LE, in Upper Canada, about 38 miles long, and 30 broad; its vaters communicate with those of Lake Huron.

CLINCH Mountain, divides the waters of Holfton and Clinch rivers, in the state of Tennessee. In this mountain, Burk's Garden, and Morris's Nob, might be defcribed as curiofities.

CLINCH, or Pelefon, a navigable branch of Tenneffee R. which is equal in length to Holfton R. its chief branch, but lefs in width. It rifes in Virginia, and after it enters into the flate of Tenneffec, it receives Powel's, and Poplar's creek, and Emery's river, befides other ftreams. The course of the Clinch is S. W. and S. W. by W. Its mouth, 150 yards wide, lies 35 miles below Knoxville, and 60 above the mouth of the Hiwaffee. It is boatable for up-wards of 200 miles; and Powel's R.

vigable for boats 100 miles.

CL

New-

N. W

and F

Unadi

the N

ftream

co. di

Hallo

Paris, wealth

contai

newly

houfe,

an edi

fituate

this f

ments

(in Ju

any i

dians

CL

coaft (N. lat

Gray

New-CL

CL

who i

New.

OCL New-

ramus

Berkl

of Me

ties in

count

where

ver w of W

and f

miles

Moof

Nova

Tata

Nova

erly, t of the there

chann 60 tu

Co

Co in the

CL N. W

Co

27

CLI

CL

CLINTON, the most northern county of the ftate of New-York, is bounded N. by Canada ; E. by the deepeft waters of Lake Champlain, which line feparates it from Vermont; and S. by the county of Washington. By the census of 1791, it contained 1614 inhabitants, including 17 flaves. It is divided into 5 townfhips, viz. Plattfburg, the capital, Crown Point, Willfborough, Champlain, and Peru. The length from N. to S. is about 96 miles, and the breadth from E. to W. including the line upon the lake, is 36 miles. The number of fouls is now (1796,) effimated to be 6,000. By the flate cenfus, in Jan. 1796, there were 624 perions entitled to be electors. A great proportion of the lands are of an excellent quality, and produce abundance of the various kinds of grain cultivated in other parts of the flate. The people manufacture earthen ware, pot and pearl afhes, in large quantities. which they export to New-York or Quebec. Their wool is excellent; their beef and pork fecond to none; and the price of stall-fed beef in Montreal 60 miles from Plattfburgh, is fuch as to encourage the farmers to drive their cattle to that market. Their forests fupply them with fugar and molaffes, and the foil is well adapted to the culture of hemp. The land carriage from any part of the country, in transporting their produce to New-York, does not exceed 18 miles. The carrying place at Tic nderoga is 11 miles; and from Fort George, at the S. end of the lake of that name, to Fort Edward, is but 14 miles. The fmall obstructions after that are to be removed by the proprietors of the northern canal. From this country to Quebec, are annually fent large rafts ; the rapids at St. Johns's and Chamblee, being the only interruptions in the navigation, and those not fo great, but that at fome feafons, batteaux with fixty bushels of falt can afcend them. Salt is fold here at half a dollar a bushel. Saranac, Sable, and Boquet rivers water Clinton co. The first is remarkable for the quantity of falmon it produces.

CLINTON, a township in Dutchels co. Neg-York, above Poughkeepsie. It is large and thriving, and contains 4607 inhabitants, including 176 slaves. 666 of its inhabitants are electors.

CLINTON,

CLINTON, a fettlement in Tioga co. New-York, bounded by Fayette on the N. Warren of the S. Green on the W. and Franklin in Otfego co. on the E. Unadilla R. joins the Sufquehannah at the N. E. corner, and the confluent fream runs S. W. to Warren.

CLINTON, a plantation in Lincoln co. diffrict of Maine, lies 27 miles from Hallowell.

d

'nf

t

ir

e

0

O

ir

s

1,

n

git

e

n

ie it

r

N

is

١t

d

IS

t,

ľ.

rie ...s

È,

IS

i.

3

2

CLINTON, parifh, in the township of Paris, 7 miles from Whitestown, is a wealthy, pleasant, flourishing settlement, containing several handsome houses, a newly crected Presbyterian meetinghouse, a convenient school house, and an edifice for an academy delightfully situated, but not yet finissed. Between this settlement, and the Indian settlements at Ouzida, a distance of 12 miles, (in June 1996) was wilderness without any imbabitants, excepting a few Indians at the Old Oneida village.

CLINTON'S Harbour, on the N. W. coaft of N. America, has its entrance in N. lat. 52. 12. W. long. 136. Capt. Gray named it after gov. Clinton of New-York.

CLIOQUOT. See Clyoquot.

CLISTINOS, a fierce nation of Indians who inhabit round Hudson bay. See New-Britain.

CLOSTER, a village in Bergen co. New-Jerfey, nearly 7 miles S. E. of Peramus, and 16 N. of New-York city.

CLYOQUOT, a found or bay on the N. W. coast of America, westerly from Berkley's Sound. See Hancock's Harbour. COATZACUALCO, a navigable river of Mexico, or New-Spain, which empties into the gulph of Mexico, near the country of Onohualco.

COBBESECONTE, or Copfecced, which in the Indian language fignifies the land where flurgeons are taken, is a finall river which rifes from ponds in the town of Winthrop, in the diffrict of Maine; and falls into the Kennebeck within 3 miles of Nahunkeag Ifland, and 15 from Moofe Ifland.

COBEQUIT, or Colchefter river, in Nova-Scotia, rifes within 20 miles of Tatamogouche, on the N. E. coaft of Nova-Scotia; from thence it runs foutherly, then S. W. and W. into the E. end of the Bafin of Minas. At its mouth there is a fhort bank, but there is a good channel on each fide, which veffels of 60 tuns burden may pafs, and go 40

miles up the river. There are fome fcattered fettlements on its banks.

COBESEY, in the diffrict of Maine. See Pitt/lon.

COBEZA, or Cobija, an obscure port and village in the audience of Los Charcus, in Peru, S. America. The place is inhabited by about 50 Indian families, and is the most barren spot on the coaft. This is, however, the nearest port to Lipes, where there are filver mines, and also to Potofi, which is yet above soo leagues distant, and that through a defart country.

COBHAM, a finall town in Virginia, on the S. bank of James R. opposite Jamestown; zo miles N. W. of Suffolk, and 8 or 9 S. W. of Williamsburg.

COBHAM Ifle, mentioned by Captain Middleteton, in the journal of his voyage for finding a N. E. paffage. Its two extremities bear N. by E. and E. by N. in N. lat. 63. E. long. from Churchill, 3. 50. which he takes to be the Brook Cobham of Fox.

COBLESKILL, a new town in the co. of Schoharie, New-York, incorporated March, 1797.

COCALICO, a township in Lancaster co. Pennsylvania.

COCHECHO, a N. W. branch of Piscataqua R. in New-Hampshire. It riles in the Blue Hills in Strafford co. and its mouth is 5 miles above Hilton's Point. See Piscataqua.

COCHABAMBA, a province and jurifdiction in Peru, 50 leagues from Plata, and 56 from Potofi. Its capital of the fame name is one of the richeft, largeft, and most populous in Peru, as it is the granary of the archbishoprick of Plata; and in some spots filver mines have been diffeovered.

COCKBURNE, a townflip in the northern part of New-Hampfhire, Grafton co. on the E. bank of Connecticutriver, S. of Colebrooke.

COCKERMOUTH, a town in Grafton co. New-Hampfhire, about 15 miles N. E. of Dartmouth College. It was incorporated in 1766, and in 1775, contained 118 inhabitants; and in 1790, 373. COCKSAKIE. See Coxakie.

COD. See Cape Cod, Barnflable co. and Progincetown.

CODORUS, a township in York co. Pennsylvania.

COEYMANS, a township in Albany co. New-York, 12 miles below Albany.

TOS

By the state census of 1796, 389 of its inhabitants are electors.

106

COHONAWAGA, a parifh in the townhip of Johnftown, Montgomery co, New York, on the W. fide of Mohawk R. 26 miles W. of Schenectady. This place, which had been fettled near 80 years, and which was the feat of Sir William Johnfon, was moftly deftroyed by the Britifh and Indians, under the command of Sir William, in the year 1780. In this action, Johnfon evinced a want of feeling which would have dilgraced a favage. The people deftroyed in this expedition, were his old neighbours, with whom he had formerly lived in the habits of friendfhip. His eftate was among them, and the inhabitants had always confidered him as their friend and neighbour. Thefe unfortunate people, after feeing their houfes and property contiumed to afhes, were hurried, fuch as could walk, into cruel captivity; thofe who could not walk, fell victums to the tomahawk and fcalping kuife. See Capharwaga.

ing kuife. See Cagonawaga. COBANZY, or Cagaria, a fmall river, which rifes in Salen co. New-Jerfey, and running through Cumberland co. empties into Delawarg R. opposite the upper end of Bombay Hook. It is about 30 miles in length, and is navigable for veffels of 100 tons to Bridgetown, 20 miles from its mouth.

COHASSET, a township in Norfolk co. Masset, which was incorporated in \$770, and contains \$17 inhabitants. It has a congregational church, and r26 houses, scattered on different farms. Cohasset rocks, which have been to fatal to many vessels, lie off this town, about a league from the shore. It lies 25 miles S. E. of Boston; but in a straight line not above half the distance.

COHOEZ, or the Falls in Mohawk R. between 2 and 3 miles from its mouth, and ro miles northward of Albany, are a very great natural curiofity. The river above the falls is about 300 yards wide, and approaches them from the N. W. in a rapid current, between high banks on each fide, and pours the whole bedy of its water over a perpendicular rock of about 40 (fome fay more) feet in height, which extends quite acrois the river, like a mill-dam. The banks of the river, immediately below the falls, are about 100 feet high. A bridge 1100 feet long, and 24 feet wide, refting on

13 piers, was crected, at the expense of 12,000 dollars, in 1794, a mile below the falls, from which a fpectator may have a grand view of them: but they appear most romantically from Lansin, burgh hill, 5 miles E. of them.

COHONGORONTO is the name of Potowmack R. before it breaks through the Blue Ridge, in N. lat. 39.45. Its whole length to the Blue Ridge may be about 160 miles; from thence it alfumes the name of Potorumack, which fee,

COHUIXCAS, a country in New-Spain, in which there is a confiderable mountain of loadftone, between Tcoiltylan and Chilapan.

COKESBURY COLLEGE, in the town of Abington, in Harford co. Maryland, is an inftitution which bids fair to promote the improvement of fcience, and the cultivation of virtue. It was founded by the Methodifts, in 1785, and has its name in honour of Thomas Coke, and Francis Afbury, the American bishops of the Methodist Episcopal church, The edifice is of brick, handfomely built, on a healthy fpot, enjoying a fine air, and a very extensive prospect. The college was crected, and is wholly fupported by fubfcription and voluntary donations. The ftudents, who are to confift of the fons of travelling preachers, annual fubfcribers, members of the fociety, and orphans, are inftructed in English, Latin, Greek, logic, rhetoric, hiftory, geography, natural philosophy, and affronomy; and when the finances of the college will admit, they are to be taught the Hebrew, French, and German languages. The rules for the private conduct of the fundents extend to their amulements; and all tend to promote regularity, encourage industry, and to nip the buds of idleness and vice. Their recreations without doors are, walking, gardening, riding, and bathing ; within doors they have tools and accommodations for the carpenter's, joiner's, cabi-net maker's, or turner's bulinefs. These they are taught to confider as pleafing and healthful recreations, both for the body and mind.

body of its water over a perpendicular rock of about 40 (fome fay more) feet in height, which extends quite across the river, like a mill-dam. The banks of the river, immediately below the falls, are about 100 feet high. A bridge 1100 feet long, and 24 feet wide, reffing on league a fail t before againt thefe f a man point . till the and th a chan oil, fu goat f gated 1 where return came night | fifting others, too, a with t Col co. N. of De town; of Co of 179 tors. Col New] in 170 Norwi N. W conten blifhed COL tenden of lak Onion Colche town. Col fax co. bank (from i mack wide, tains a S. W Richn Co Cobegi Co ca, is of Li highf 18 420 and fe flourif COL

ow

hey in_†

of igh Its

af-

in,

in-

lan

wn

1d,

10-

nd is nd patiente py to he

in

ic.

y,

es

be

an

te

Ňr,

te

tq

ir

Bin a-i- fe

ig he

d

10

y

ts

15

g

0

18

leagues diftant. They have a maft with a fail fastened to it. They always go before the wind, being unable to ply against it; and therefore only fit for thefe feas, where the wind is always in a manner the fame, not varying above a point or two all the way from Lima, till they come into the bay of Panama; and there they must fometimes wait for a change. Their cargo is usually wine, oil, fugar, Quito cloth, foap, and dreffed goat fkins. The float is usually navigated by 3 or 4 men, who fell their float where they difpofe of their cargo; and return as paffengers to the port they came from. The Indians go out at night by the help of the land-wind, with fishing floats, more manageable than the others, though these have masts and fails too, and return again in the day-time with the fea-wind.

COLCHESTER, a township in Ulster co. N. York, on the Popachton branch of Delaware river, S. W. of Middletown; and about 50 miles S. W. by S. of Cooperstown. By the state census of 1796, 193 of its inhabitants are electors.

COLCHESTER, a large township in New London co. Connecticut, settled in 1701; about 15 miles westward of Norwich, 25 S. E. of Hartford, and 20 N. W. of New London city. It is in contemplation to have a post office established in this town.

COLCHESTER, the chief town in Chittenden co. Vermont, is on the E. bank of lake Champlain, at the mouth of Onion river, and N. of Burlington, on Colchefter bay, which fpreads N. of the town.

COLCHESTER, a post-town in Fairfax co. Virginia, fituated on the N. E. bank of Ocquoquam creek, 3 or 4 miles from its confluence with the Potowmack; and is here about 100 yards wide, and navigable for boats. It contains about 40 houles, and lies 16 miles S. W. of Alexandria, 106 N. by E. of Richmond, and 172 from Philadelphia.

COLCHESTER R. Nova Scotia. See Cohequit.

COLD Spring, in the island of Jamaica, is a villa, 6 miles from the highlands of Liguania. The grounds are in a high flate of improvement. Cold fpring is 4200 feet above the level of the fea; and few or none of the tropical fruits will flourish in fo cold a climate. The ge-

neral flate of the thermometer is from 55. to 65.; and even fometimes fo low as 44.: fo that a fire there, even at noon-day, is not only comfortable, but necefiary a great part of the year. Many of the English fruits, as the apple, the peach, and the ftrawberry, flourish there in great perfection, with feveral other valuable exotics, as the tea-tree and other oriental productions.

COL

COLD Spring Cove, near Burlington, New-Jerley, is remarkable for its fand and clay, used in the manufacture of glass; from whence the glass works at Hamilton, 10 miles W. of Albany, are supplied with these articles.

COLEBROOKE, in the northern part of New Hamphire, in Grafton co. lies on the E. bank of Connecticut R. oppolite the Great Monadnock, in Canaan, flate of Vermont; joining Cockburne on the fouthward, and Stuartstown on the northward; 126 miles N. W. by N. from Portfinouth.

COLEBROOKE, a rough, hilly town thip on the N. line of Connecticut, in Litchfield co. ; 30 miles N. W. of Hartford city. It was lettled in 1756. Here are 2 iron works, and feveral mills, on Still R. a N. W. water of Farmington R. In digging a cellar in this town, at the close of the year 1796, belonging to Mr. John Hulburt, the work men, at the depth of about 9 or 10 feet, found three large tulks and two thigh bones of an animal, the latter of which meafured each about 4 feet, 4 inches in length. and 12 inches in circumference. When first discovered they were entire, but as foon as they were exposed to the air they mouldered to duft. This adds another to the many lacts, which prove that a race of enormous animals, now extinct, once inhabited the United States.

COLERAIN, a township in Lancaster co. Pennsylvania.

COLERAIN, a town on the N. bank of St. Mary's river, Camden co. Georgia, 40 or 50 miles from its mouth. On the 29th of June, 1796, a treaty of peace and friendfhip was made and concluded at this place, between the Prefident of the United States, on the one part, in behalf of the United States, and the king's chiefs and warriors of the Creek nation of Indians, on the other. By this treaty, the line between the white people and the Indians, was eftablished to run "from the Currahee mountain to the

the head or fource of the main fouth branch of the Oconee river, called, by the white people, Appalatohee, and by the Indians, Tulapoeka, and down the middle of the fame." Liberty was alfo given by the Indians to the Prefident of the United States, to " establish a trading or military post on the S. fide of Alatamaha, about 1 mile from Beard's bluff, or any where from thence down the river, on the lands of the Indians ;" and the Indians agreed to " annex to faid post a tract of land of five miles square; and in return for this and other tokens of friendship on the part of the Indians, the United States ftipulated to give them goods to the value of 6000 dollars, and to furnish them with two black finiths with tools.

COL

108

COLRAINE, a township in Hampshire co. Massachusetts, which contains 229 houses, and 1417 inhabitants.

COLIMA, a large and rich town of Mechoacan and New-Spain, on the S. Sea, near the borders of Xalifca, and in the most pleasant and fruitful valley in all Mexico, producing cocoa, caffia, and other things of value, befides fome gold. Dampier takes notice of a volcano near it, with two fharp peaks, from which fmoke and flame iffue continually. The famous plant oleacazan grows in the neighbourhood, which is reckoned a catholicon for reftoring decayed firength, and a specific against all forts of poifon. The natives apply the leaves to the parts attected, and judge of the fuccels of the operation by their flicking or falling off.

COLUMBIA, a township in Washington co. district of Maine, on Pleasant R. adjoining Machias on the N. E. and was formerly called Plantations No. 12 and 13. It was incorporated in 1796. The town of Machias lies 15 miles to the eastward. It is 9 miles from Steuben.

COLUMBIA County, in New-York, is bounded N. by Renfidaer, S. by Dutchefs, E. by the flate of Maffachuletts, and W. by Hudíon R. which divides it from Albany co. It is 32 miles in length and 21 in breadth, and is divided into eight towns; of which Hudíon, Claverack, and Kinderhook are the chief. It contained, in 1790, 27,732 inhabitants, and in 1796, 3560 electors.

COLUMBIA College. See New-York

COM

Co

molt

ginia

in Ch

19 mi

Col

gin if

the N

25. W

New-I

built i

400 m

is bar

it has

caque

20. W

Co

S. fid

very 1

and 3

johar

Alleg

rifes t

fide of

trance

the fc

on the

into

havin

on w

niere

were

plant

whon

of in

choad

built

ftatio

to fe

the

have

boro

Hifp

Cali

C

Penc

ated

mou

of a

abou

dettr

of th

In

quak

47/18

of N.

Co

Co

Co

COLUMBIA, TERRITORY OF. See Washington, or the Federal, city. COLUMBIA, a post town, the capital of Kershaw co. and the feat of government of South-Carolina. It is fituated in Camden diffrict, on the E. fide of the Congaree, just below the confinence of Saluda and Broad rivers. The fireets are regular, and the town contains upwards of 70 houfes. The public offices have, in some measure, been divided, for the accommodation of the inhabitants of the lower counties, and a branch of each retained in Charleftown. It lies 115 miles N. N. W. of Charleftown, 35 S. W. of Camden, 85 from Augusta, in Georgia, and 678 S. W. of Philadelphia. N. lat. 14. r. W. long. 80. 57.

COLUMBIA, a flourishing post town in Goochland co. Virginia, on the N. fide of James river, at the mouth of the Rivanna. It contains about 40 houses, and a warehouse for the inspection of tobacco. It lies 45 miles above Richmond, 35 from Charlottefville, and 328 S. W. of Philadelphia.

COLUMBIA, a town newly laid out, in Lancaster co. Pennsylvania, on the N. E. bank of Susquehannah river, at Wright's ferry; 10 miles W. of Lancaster, and 76 W. by N. of Philadelphia.

COLUMBIA Co. in the Upper diffrict of Georgia, is bounded by Savannah E. on the N. E. and E. which feparates it from the flate of S. Carolina, N. W. of Richmond co. Its fhape is very irregular.

COLUMBIA, a town in the N. W. territory, on the N. bank of Ohio river, and on the W. fide of the mouth of Little Miami R.; about 6 miles S. E. by E. of Fort Wafhington, S. E. by S. ot Cincinnati, and S7 N. by W. of Lexington, in Kentucky. N. lat. 39. 20. COMANA, a town and province in the northern division of Terra Firma, S. America. It lies on the N. eafternmoft part of the fea coaft.

COMARGO, a town of New-Leon, in N. America, fituated on the S. fide of Rio Bravo, which empties into the gulf of Mexico on the W. fide.

COMBAHEE, a confiderable river of South-Carolina, which enters St. Helena found between Coofa and Afhepoo rivers.

COMBAHEE Ferry, on the above river is 17 miles from Jackfonfborough, 15 fromPocotaglio and 52 fromCharleftown. COMFORT

COMFORT, POINT, is the S. caffern-COMFORT, POINT, is the S. eattern-most part of Elizabeth-city co. in Vir-ginia, formed by James R. at its mouth in Chefapeak bay. Point Comfort lies 19 miles W. by N. of Cape Henry. COMMANDES, one of the fmall Vir-gin ifles, in the West-Indies, fituated to the N. N. E. of Tortula. N. lat. 18.

pital

ern

ated

the

e of 'eets

up-

fices

, for

ants

h of

115

W.

eor-

hia.

own

· N.

the

ifes.

) of

ich-

328

put,

the

, at an-

hia.

rift

E.

s it

. of

rre-

W.

ver,

of

E.

y S.

ex-

0.

the

S.

noft

, in

; of

gulf

of

ena

poo

ri-15

wp. RT

25. W. long. 63. Sec. Sugar

COMPOSTELLA, a very rich town in New-Spain, and province of Xalifco, built in 1531, fituated near the S. Sea, 400 miles N. W. of Mexico. The foil is barren and the air unhealthful; but it has feveral mines of filver at St. Pecaque, in its neighbourhood. N. lat. 21. 20. W. long. 109. 42. See Culiacam.

CONAJOHARY, a post town, on the S. fide of Mohawk river, New-York, very large, 36 miles above Schenectady. and 318 from Philadelphia. See Canajohary.

CONAWANGO, a northern branch of Alleghany river, in Pennfylvania, which rifes from Chataughque lake.

CONCEPTION, a large bay on the E. fide of Newfoundland illand, whole entrance is between Cape St. Francis on the fouthward, and Flamborough-head on the northward. It runs a great way into the land in a fouthern direction, having numerous bays on the W. fide, on which are two fettlements, Carboniere and Havre de Grace. Settlements were made here in in 1610, by about 40 planters, under governor John Guy, to whom king James had granted a patent of incorporation.

CONCEPTION of Salaye, a fina'l town of N. America, in the province of Me-choacan, in Mexico or New-Spain, was built by the Spaniards, as well as the stations of St. Michael and St. Philip, to fecure the road from Mechoacan to the filver mines of Zacatea. They have also given this name to feveral boroughs of America; as to that in Hifpaniola ifland, and to a fea-port of California, &c.

CONCEPTION, by the Indians called Penco, a city in Chili. S. America, fituated on the edge of the fea, at the mouth of a river, and at the bottom of a bay of its own name. It lies in about 37. S. lat. It was feveral times dettroyed by the powerful confederacy of the Indians, and as often repaired. of late, have commonly held their fef-In 1730 it was deftroyed by an earth- | fions here; and from its central fitua-

17/3

within the audience and jurifdiction of St. Jago, and is governed by a correff. dore. The Spanish inhabitants her are the most warlike and hardy of a in S. Americas they are all trained arms from their childhood, to be read torefult the attack of the Chilefe Indian whom they have reafon to confider a formidable enemy.

The inhabitants, and even the women, excel in horfemanship; they are very dextrous in managing the lance or noofe ; and it is very rare to fee the mifs their aim, though at full fpeed, with the noofe, which they throw 40 or 50 yards, and fo halter the object of their diversion or revenge. This noo is made of thongs of cow hide; thefe they twift with oil, till rendered fupple and pliant to command ; and fo ftro that, when twifted, they will, it is faid, hold a wild bull, which would break a halter of hemp of twice the thickness

The foil here is fruitful, aboundi with corn and excellent wine. Th fruit trees bear fo luxuriantly here, that they are forced to thin the fruit, otherwife the branches would break, nor could the fruit come to maturity. This city has a church and fix very famous monasteries; but the dwelling houses make no great appearance. Here the women go out in the night to the shops, to buy fuch neceffaries as they want for their families, it being contrary to the cuftom of this country for women of any character, to go abroad in the day-time on fuch affairs. It is an open town; and the few batteries it has, are kept in very indifferent order.

CONCHUCOS, a jurifdiction in the empire of Peru, in S. America, under the archbishop of Lima; it begins 40 leagues N. N. E. of the metropolis, and runs along the center of the Cordillera. It produces fruits, grain, &c. and affords extensive pasture for cattle of all kinds. Several branches of the woollen manufactory are carried on here, which conffitute its greateft commerce with the other provinces.

CONCORD, a post town of New-Hampfhire, very flourishing, and pleafantly fituated on the W. bank of Merrimack river, in Rockingham co. 8 miles above Hookfet falls. The legiflature. quake, and fince that rebuilt. It is tion, and a thriving back country, it will

will probably become the permanent at of government. Much of the trade of the upper country centers here. A handfome toll bridge across the Merrinack, connects this town with Pembroke. It has 3747 inhabitants, and was incorporated in 1765. The Indian name was Penacook. It was granted by Maffachufetts, and called Rumford. The compact part of the town contains about 170 houfes, a congregational church, and an academy, which was incorporated in 1790. It is 54 miles W. N. W. of Portimouth, 58 S. W. of Dartmouth college, and 70 northward from Bofton. N. lat. 43. 12. W. long. 71. 29.

CONCORD, in Effex co. Vermont, lies on Connecticut river, opposite a part of the 15-mile falls.

CONCORD, in Maffachuletts, a poft town, one of the most confiderable towns in Middlefex co. fituated on Concord river, in a healthy and pleafant fpot, nearly in the center of the county, and 18 miles N. W. of Bolton, and 17 E. of Lancaster. Its Indian name was Mulquetequid; and it owes its prefent name to the peaceable manner in which it was obtained from the natives. The first fettlers, among whom were the Rev. Meffirs. Buckley and Jones, having fettled the purchafe, ob-tained an act of incorporation, Sept. 3, \$635; and this was the most diftant fettlement from the fea-fhore of New-England at that time. The fettlers never had any contest with the Indians ; and only three perfons were ever killed by them within the limits of the town. In 1791, there were in this township 225 dwelling houses, and 1590 inhabitants; of the latter there were 80 perfons upwards of 70 years old. For 13 years previous to 1791, the average number of deaths was 17; one in four of whom were 70 years old and upwards. The public buildings are, a congregational church, a fpacious ftone gaol, the beft in New-England, and a very handfome county court-houfe. The town is accommodated with three convenient bridges over the river; one of which is 208 feet long, and 18 feet wide, supported by 12 piers, built after the manner of Charles river bridge. This town is famous in the hiftory of the revolution, having been the feat of the provincial congress in 1774, and the

fpot where the first opposition was made to the British troops, on the memorable 19th of April, 1775. The general court have frequently held their feffions here when contagious difeases have prevailed in the capital. N. lat. 42.25.

CONCORD, a fmall river of Mafiachufetts, formed of two branches, which unite near the centre of the town of Concord, whence it takes its courfe in a N. E. and N. direction through Bedford and Billerica, and empties itfelf into Merrimack R. at Tewkfbury. Concord R. is remarkable for the gentlenefs of its current, which is fcarcely perceivable by the eye. At low water mark it is from 100 to 200 feet wide, and from 3 to 12 feet deep. During floods, Concord R. is near a mile in breadth; and when viewed from the town of Concord, makes a fine appearance.

CONCORD, a township in Delaware co. Pennfylvania.

CONCORD, a fettlement in Georgia, on the E. bank of the Miffifippi, about a mile from the S. line of Tenneffee, 108 miles N. from the mouth of Yazoo R. and 218 below the Ohio. N. lat. 33. 55. W. long. 91. 25.

CONDE, FORT, or Mobile city, is fituated on the W. fide of Mobile bay, in Weft-Florida, about 40 miles above its mouth in the gulf of Mexico. N. lat. 30. 42. W. long. 87. 57.

CONDECEDO, a cape or promontory of N. America, in the province of Yucatan, 100 miles W. of Merida. N. lat. 20. 50. W. long, 91. 27.

CONDESUYOS DE AREQUIPA, à jurifdiction under the bifhop of Arequipa, 30 leagues N. of that city, in Peru, Here is cultivated the wild cochineal: the Indians carry on a great trade with this article; they grind it, and mix four ounces of it with 12 ounces of violetmaize, of which they form cakes of 4 ounces each, and fell it for a dollar a pound. Thefe cakes they call magnos. This place alfo abounds with gold and filver mines, which are not fo carefully worked as formerly.

CONDUSKEEG, a fettlement in the diffrict of Maine, in Hancock co. containing 567 inhabitants.

CONEGOCHEAGUE Creek, rifes near Merceriburg, Franklin co. Pennfylvania, runs foutherly in a winding courfe, and after fupplying a number of mills, emptics ties int port, if miles S of the l CON nemaus kemani fing th ridge, empties N. E. (boats, miles 1 branch CON or Para cefe of CON Tioga deo Cre CON ter co. CON neffee (Its wat CON S. Care of Sali union | Watere CON is the n Near it Bath. CON States (ancient ated be between Its gre length Maffacl the four and W. ftate co equal to divided New-H don, v from V Tolland fame d state of are div thips at one or and fche The n 100.

ties into the Potowmack, at William port, in Washington co. Maryland ; 19 miles S. E. of Hancock, and 8 miles S. of the Pennsylvania line.

me

The

hei

afes

lat.

Gu-

lich

of

: in

ed-

in-

on-

refs

iv-

cit

om

m-

ind

m-

are

ia,

mt

08

R.

13.

fi-

ıy,

ve

N.

u-

N.

17-

ia,

u,

l':

th

ur

±-

4

.

s. id ly

20

2-

21

z,

CONEMAUGH Rive", and Little Conemaugh, are the head waters of Kifkemanitas, in Pennfylvania : after paffing through Laurel hill and Chelnut ridge, Conemaugh takes that name and empties into the Alleghany, 29 miles N. E. of Pittfburg. It is navigable for boats, and there is a portage of 18 miles between it and the Frankftown branch of Juniata river.

CONENTES, LAS, a city of La Plata or Paraguay, in S. America, in the diocefe of Buenos Ayres.

CONESTEO, a N. western branch of Tioga R. in New-York. See Canicodeo Creek.

CONESTOGA, a township in Lancafter co. Pennfylvania.

CONESUS, a finall lake in the Geneffee country, N. York, which fends its waters N. W. to Geneffee river.

CONGAREE, a confiderable river of S. Carolina, formed by the confluence of Saluda and Broad rivers. The union of the waters of Congaree and Wateree, form the Santee.

CONHOCTON Greek, in New-York, is the northern head water of Tioga R. Near its mouth is the fettlement called Bath.

CONNECTICUT, one of the United States of North-America, called by the ancient natives Qunnihticut, is fituated between 41. and 42. 2. N. lat. and between 71. 20. and 73. 15. W. long. Its greatest breadth is 72 miles, its length 100 miles; bounded N. by Maffachusetts; E. by Rhode I.; S. by the found which divides it from Long I. and W. by the ftate of New-York. This ftate contains about 4674 fquare miles; equal to about 2,640,000 acres. It is divided into 8 counties, viz. Fairfield, New-Haven, Middlefex and New-London, which extend along the found from W. to E.; Litchfield, Hartford, Tolland, and Windham, extend in the fame direction on the border of the state of Massachusetts. The counties are divided and fubdivided into townthips and parifhes; in each of which is one or more places of public worthip, and fchool-houfes at convenient diftances. The number of townships is about 100. Each township is a corporation

invelted with powers fufficient for their own internal regulation. The number of representatives is fometimes 180; but more commonly about 160; a number fully adequate to legiflate for a wife and virtuous people, well informed, and jealous of their rights ; and whose external circumftances approach nearer to equality than those, perhaps, of any other people in a flate of civilization, in the world.

The principal rivers in this fate are, Connecticut, Houfatonick, the Thames and their branches, which, with fuch others as are worthy of notice, will be described under their respective names.

The whole of the fea-coast is indented with harbours, many of which are fafe and commodious; those of New-London and New-Haven are the most important. This fate fends feven reprefentatives to Congress.

Connecticut, though fubject to the extremes of heat and cold, in their feafons, and to frequent fudden changes, is very healthful. It is generally broken land, made up of mountains, hills and vallies; and is exceedingly well watered. Some finall parts of it are thin and barren. Its principal productions are Indian corn, rye, wheat in many parts of the ftate, oats, and barley, which are heavy and good, and of late, buck wheat-flax in large quantities-fome hemp, potatoes of feveral kinds, pumpkins, turnips, peas, beans, &c. &c. Fruits of all kinds which are common to the climate. The foil is very well calculated for pafturage and mowing, which enables the farmers to feed large numbers of neat cattle and horfes.

The trade of Connecticut is principally with the West-India islands, and is carried on in veffels from 60 to 140 tons. The exports confift of hories, mules, oxen, oak flaves, hoops, pine boards, oak plank, beans, Indian corn, fifh, beef, pork, &c. Horfes, live cattle, and lumber, are permitted in the Dutch, Danish, and French ports. A large number of coalting vefiels are employed in carrying the produce of the ftate to other ftates. To Rhode-Ifland, Maffachufetts, and New-Hampfhire, they carry pork, wheat, corn and rye-Te North and South Carolina, and Georgia, butter, cheefe, falted beef, cyder, apples, potatoes, hay, &cc. and receive

II2

in return, rice, indigo and money. But as New-York is nearer, and the flate of the markets always well known, much of the produce of Connecticut, especially of the western parts, is carried there; particularly pot and pearl afhes, flax feed, beef, pork, cheefe and butter, in large quantities. Most of the produce of Connecticut river from the parts of Maffachufetts, New-Hampfhire and Vermont, as well as of Connecticut, which are adjacent, goes to the fame market. Confiderable quantities of the produce of the eaftern parts of the ftate, are marketed at Bofton, Providence, and Norwich. The value of the whole exported produce and commodities from this flate, before the year 1774, was then effimated at about 6.200,000 lawful money, annually. In the year ending Sept. 30, 1791, the amount of foreign exports was 710,340 dolls. befides articles carried to different parts of the United States, to a great amount. In the year 1792-749,925 dolls.—in the year 1793—779,239 dolls. and in the year 1794-806,746 dolls. This state owns and employs in the foreign and coafting trade, 32,897

tons of fhipping. The farmers in Connecticut, and their families, are moftly clothed in plain, decent, homefpun cloth. Their linens aud woollens are manufactured in the family way; and although they are generally of a coarfer kind, they are of a fironger texture, and much more durable than those imported from France and Great-Britain. Many of their cloths are fine and handsome. Here are large orchards of mulberry trees; and filk-worms have been reared fo fuccefffully, as to promise, not only a fupply of filk to the inhabitants, but a furpluffage for exportation.

In New-Haven, are linen and button manufactories. In Hartford, a woollen manufactory has been eftablifhed; likewife glafs works, a fnuff and powder mill, iron works, and a flitting mill. Iron works are eftablifhed alfo at Salifbury, Norwich, and other parts of the ftate. At Stafford is a furnace at which are made large quantities of hollow ware, and other ironmongery, fufficient to fupply the whole ftate. Paper is manufactured at Norwich, Hartford, New-Haven, and in Litchfield county. Ironmongery, hats, candles, leather,

thoes and boots, are manufactured in this flate. A duck manufactory has been established at Stratford.

The ftate of Connecticut is laid out in fmall farms, from 50 to 300 and 400 acres each, which are held by the farmers in fee fimple; and are generally well cultivated. The flate is chequered with innumerable roads or highways croffing each other in every direction. A traveller in any of these roads, even in the most unsettled parts of the state, will feldom pais more than two or three miles without finding a houfe or cottage, and a farm under fuch improvements, as to afford the neceffaries for the fupport of a family. The whole ftate refembles a well cultivated garden, which, with that degree of industry that is neceffary to happinefs, produces the neceffaries and conveniences of life in great plenty.

The inhabitants are almost entirely of English descent. There are no Dutch, French, or Germans, and very few Scotch or Irifh people, in any part of the ftate. The original flock from which have forung all the prefent in-habitants of Connecticut, and the numerous emigrants from the ftate, to every part of the U. States, confilted of 3000 fouls, who fettled in the towns of Hartford, New-Haven, Windfor, Guilford, Milford and Wethersfield, about the years 1635 and 1636. In 1756, the population of the flate amounted to 130,611 fouls; in 1774, to 197,856; in 1782, to 202,877 whites, and 6273 Indians and negroes; in 1790, to 237,946 perfons, of whom 2764 were flaves.

The people of Connecticut are remarkably fond of having all their difputes, even those of the most trivial kind, fettled according to law. The prevalence of this litigious spirit, affords employment and fupport for a numerous body of lawyers. That party fpirit, however, which is the bane of political happiness, has not raged with fuch violence in this flate, as in Maffachufetts and Rhode Ifland. Public proceedings have been conducted generally with much calmnefs and candour. The people are well informed in regard to their rights, and judicious in the methods they adopt to fecure them. The flate enjoys an uncommon fhare of political tranquillity and unanimity. All

All the pea Conne and cat very fe The bu tionalif copaliar The in the 461,23 the fuf May 17 of the w of Conn fylvania Ther pleafant inland, cities, i diction Hartfor of the ft holden a latter in cities a Middlet Farmine ford, F Windha confider In no tion of a ed to tl every to diftricts, ichool k of every one thin tax on th the inha fupport (for the e The law shall be through Yale of learni year 170 Acade Greenfie ham, an flourifhi The founded

granted a law of form of not been

All religions, that are confiftent with the peace of fociety, are tolerated in Connecticut; and a fpirit of liberality and catholicifm is increasing. There are very few religious fects in this state. The bulk of the people are Congregationalist. Besides these, there are Epifcopalians and Baptists.

400

rm

well

vith

ling tra-

the

hree

cot-

ove-

for

hole

len,

that

the.

t) in

rely

no

part rom

in-

10

d of

is of

uil-

the

to

56 3

273

to

were

redif-

ivial

The

af-

or a

Fhat

bane

aged

s in

'ub-

ge-

our.

gard

the

iem.

re of

All

The damage fultained by this flate in the late war, was effimated at \$61,2351. 16s. 1d. To compensate the fufferers, the General Court, in May 1792, granted them 500,000 acres of the weftern part of the referved lands of Connecticut, which lie weft of Pennfylvania.

There are a great number of very pleafant towns, both maritime and inland, in Connecticut. It contains five cities, incorporated with extensive jurifdiction in civil causes. Two of these Hartford and New-Haven, are capitals of the state. The General Assembly is holden at the former in May, and at the latter in October, annually. The other cities are New-London, Norwich and Middleton. Weathersfield, Windfor, Farmington, Litchfield, Milford, Stratford, Fairfield, Guilford, Stamford, Windham, Suffield and Enfield, are all confiderable and very pleafant towns.

In no part of the world is the education of all ranks of people more attended to than in Connecticut. Almost every town in the flate is divided into diffricts, and each diffrict has a public fchool kept in it at a greater or lefs part of every year. Somewhat more than one third of the monies arifing from a tax on the polls and rateable effate of the inhabitants, is appropriated to the fupport of fchools in the feveral towns, for the education of children and youth. The law directs that a grammar fchool fhall be kept in every county town throughout the flate.

Yale College is an eminent feminary of learning, and was founded in the year 1700. See Yale College.

Academies have been eftablished at Greenfield, Plainfield, Norwich, Windham, and Pomfret, some of which are sourishing.

The confliction of Connecticut is founded on their charter, which was granted by Charles II. in 1662, and on a law of the flate. Contented with this form of government, the people have not been difpored to run the hazard of 113

framing a new conffitution fince the declaration of independence.

Agreeable to this charter, the fupreme legiflative authority of the flate is vefted in a governor, deputy governor, twelve affiftants or counfellors, and the reprefentatives of the people, ftyled the General Affembly. The governor, deputy governor and affiftants are annually chosen by the freemen in the month of May. The representatives (their number not to exceed two from each town) are chosen by the freemen twice a year, to attend the two annual feffions, on the fecond Tuefdays of May and October. The General Affembly is divided into two branches, called the upper and lower houfes. The upper houfe is composed of the governor, deputy govermor and affiftants. The lower house of the reprefentatives of the people. No law can pais without the concurrence of both houses.

Connecticut has ever made rapid advances in population. There have been more emigrations from this, than from any of the other states ; and yet it is at present full of inhabitants. This increafe may be afcribed to feveral caufes. The bulk of the inhabitants are induftrious, fagacious hufbandmen. Their farms furnish them with all the necessaries, most of the conveniences, and but few of the luxuries of life. They, of courfe, must be generally temperate, and if they choose, can subfift with as much independence as is confistent with happinels. The fubfiltence of the farmer is fubstantial, and does not depend on incidental circumflances, like that of most other professions. There is no necessity of ferving an apprentices this to the business, nor of a large stock of money to commence it to advantage. Farmers, who deal much in barter, have lefs need of money than any other clafs of people. The ease with which a comfortable fubfiftence is obtained, induces the hufbandmah to marry young. The cultivation of his farm makes him ftrong and healthful. He toils cheerfully through the day-eats the fruit of his own labour with a gladfome heartat night devoutly thanks his bounteous God for his daily bleffings-retires to reft, and his fleep is fweet. Such circumftances as these have greatly contributed to the amazing increase of inhabitants in this ftate. Befides, the

people

people live under a free government, and have no fear of a tyrant. There are no overgrown eftates, with rich and ambitious landlords, to have an undue and pernicious influence in the election of civil officers. Property is equally enough divided, and mult continue to be fo, as long as effates defcend as they now do. No perfon is prohibited from voting. He who has the most merit, not he who has the most money, is generally chosen into public office. As inftances of this, it is to he observed, that many of the citizens of Connecticut, from the humble walks of life, have arisen to the first offices in the state, and filled them with dignity and reputation. That bale bufinels of electioneering, which is fo directly calculated to introduce wicked and defigning men into office, is yet but little known in Connecticut, A man who wilhes to be cholen into office, acts wifely, for that end, when he keeps his defires to himfelf.

A thirst for learning prevails among all ranks of people in the flate. More of the young men in Connecticut, in proportion to their numbers, receive a public education, than in any of the ftates.

The revolution, which fo effentially affected the government of most of the colonies, produced no very perceptible alteration in the government of Con-necticut. While under the jurifdiction of Great-Britain, they elected their own governors, and all fubordinate civil officers, and made their own laws, in the fame manner, and with as little control as they now do. Connecticut has ever been a republic; and perhaps as perfect and as happy a republic as has ever exifted. While other flates, more monarchical in their government and manners, have been under a neceffity of un-dertaking the difficult talk of altering their old, or forming new conftitutions, and of changing their monarchical for republican manners, Connecticut has uninterruptedly proceeded in her old track, both as to government and manners; and, by thefe means, has avoided those convulsions which have rent other ftates into molent parties.

The prefent territory of Connecticut, at the time of the first arrival of the English, was possefied by the Pequot, CON

fmaller tribes of Indians. In 1774 there were of the defcendants of the ancient natives, only 1363 perfons ; the greater part of whom lived at Mohegan, between Norwich and New-London. From the natural decrease of the Indians, it is imagined that their number in this flate do not now exceed 400.

The first grant of Connecticut was made by the Plymouth council to the Earl of Warwick, in 1630. The year following the Earl affigned this grant to Lord Say and Seal, Lord Brook, and nine others. Some Indian traders fettled at Windfor in 1633. The fame year, a little before the arrival of the English, a few Dutch traders settled at Hartford, and the remains of the fettlement are still visible on the bank of Connecticut river. In 1634, Lord Say and Seal, &c. fent over a finall number of men, who built a fort at Saybrook, and made a treaty with the Pequot Indians for the lands on Connecticut R. Mr. Haynes and Mr. Hooker left Maffachusetts-bay in 1634, and fettled at Hartford. The following year Mr. Eaton and Mr. Davenport feated themfelves at New-Haven.

In 1644, the Connecticut adventurers purchased of Mr. Fenwick, agent for Lord Say and Seal, and Lord Brook, their right to the colony, for £.1600.

Connecticut and New-Haven continued two diffinct governments for many rears. At length, John Winthrop, Efq. who had been cholen governor of Connecticut, was employed to folicit a royal charter. In 1662, Charles II. granted a charter, conflituting the two colonies for ever one body corporate and politic, by the name of " The governor and company of Connecticut." New-Haven took the affair ill; but in 1665, all difficulties were amicably adjufted; and as has been already observed, this charter ftill continues to be the bafis of their government.

CONNECTICUT, the most confiderable river in the eaftern part of the United States, rifes in the highlands which leparate the ftates of Vermont and New-Hampfhire from Lower Canada. It has been furveyed about 25 miles beyond the 45th degree of latitude, to the head ipring of its northern branch; from which, to its mouth, is upwards of 300 miles, through a thick fettled country ; the Mohegan, Podunk, and many other having upon its banks a great number

of the m towns in 80 to Loc mouth. and New W. as lik and part o the city of runs a S. The navi which, lil thro' whi ed by fall New-Ham are called the river i cond rema merly call named Bel breadth of in other pl depth of t and comm Sept. 179 vere droug is faid, " feet wide, rock divid nels, each the river in dry, being the whole channel, w breadth of tonifhing 1 pitches, on of half a 1 that where A bridge this fall, by 365 feet la middle by 1 the higheft it. This i but it is co 30 miles a Agar Falls water, betw feet wide. of Lebanon ford in Ver connects W with Rock withstandin rent at Bell the falmon taken many proceed no of the iflan 10月10月1日

towns in the United States. It is from 80 to 100 rods wide, 130 miles from its mouth. Its courfe between Vermont and New-Hampshire is generally S. S. W. as likewife through Massachusetts, and part of Connecticut, until it reaches the city of Middleton; after which it runs a S. S. E. courfe to its mouth. The navigation of this beautiful river, which, like the Nile, fertilizes the lands thro' which it runs, is much obstructed by falls. Two of these are between New-Hampfhire and Vermont, the first are called the Fifteen mile falls. Here the river is rapid for 20 miles. The fecond remarkable fall is at Walpole, formerly called the Great Fall, but now named Bellows' Falls. Above thefe, the breadth of the river is in fome places, 22, in other places not above 16 rods. The depth of the channel is about 25 feet; and commonly runs full of water. In Sept. 1792, however, owing to the fevere drought, the water of the river, it is faid, "paffed within the space of 12 feet wide, and 21 feet deep." A large rock divides the ftream into two channels, each about 90 feet wide. When the river is low the eaftern channel is dry, being croffed by a folid rock ; and the whole ftream falls into the weftern channel, where it is contracted to the breadth of 16 feet, and flows with aftonishing rapidity. There are feveral pitches, one above another, in the length of half a mile; the largest of which is that where the rock divides the ftream. A bridge of timber was projected over this fall, by col. Hale, in the year 1784, 365 feet long, and supported in the middle by the ifland rock ; under which the higheft floods pal's without injuring This is the only bridge on the R. it. but it is contemplated to creft another. 30 miles above, at the middle bar of Agar Falls, where the paffage for the water, between the rocks, is above 100 feet wide. This will connect the towns of Lebanon in N. Hampfhire, and Hartford in Vermont; as the former bridge connects Walpole in N. Hampfhire, with Rockingham in Vermont. Notwithstanding the velocity of the current at Bellows' Falls, above described, the falmon pais up the river, and are taken many miles above; but the thad proceed no farther. On the fleep fides of the ifland rock, at the fall, hang fe-1010月19月

CON

here

ient

ater

be-

ton.

ndi-

er in

was

the

year

nt to

and

fet-

lame

the

d at

ttle-

Con-

and

er of

ook,

In-

It R.

left

ttled

Mr.

lem-

irers

t for

ook,

onti-

nany

nop,

or of

cit a

II.

two

orate

: go-

ut."

it in

1 ad-

ferv-

e the

ider-

Jnit-

hich

New-

t has

yond

head

from

300

itry;

mber

of

10.

of the most flourishing and pleasant | yeral arm chairs, fecured by a counteroife; in these the fishermen fit to catch falmon with fifting nets. In the course of the river through Maffachusetts, are the falls at South-Hadly, around which, lock and canals were completed in 1795, by an enterprifing company, incorporated for that purpose in 1792; by the Legiflature of Maffachufetts. In Connecticut the river is obstructed by falls at Enfield; to render which, navigable in boats, a company has been incorporated, and a fum of money raifed by lottery, but nothing effectual is yet done. The average descent of this river from Weathersfield in Vermont, 150 miles from its mouth, is two feet to a mile, according to the barometical obfervations of J. Winthrop, Efq. made in 1786. The rivers or streams which fall into Connecticut R. are numerous; fuch of them as are worthy of notice will be feen under their respective names.

At its mouth is a bar of fand which confiderably obstructs the navigation; it has to feet water on it at full tides, and the fame depth to Middleton, from which the bar is 36 miles diftant. Above Middleton, there are fhoals which have only 6 feet water at high tide; and here the tide ebbs and flows but about 8 inches. Three miles above that city, the river is contracted to about 40 rods in breadth, by two high mountains. On almost every other part of the river the banks are low, and spread into fine extenfive meadows. In the fpring floods, which generally happen in May, thefe meadows are covered with water. At Hartford, the water fometimes rifes 20 feet above the common furface of the river, and the water having no other outlet but the above-mentioned firait, it is fometimes a or 3 weeks before it returns to its usual bed. These floods add nothing to the depth of water on the bar at the mouth of the river, as the bar lies too far off in the found to be affected by them. This river is navigable to Hartford city, upwards of 50 miles from its mouth; and the produce of the country for 200 miles above it is brought thither in boats. The boats which are used in this business are flatbottomed, long and narrow, and of fo light a make as to be portable in carts. Before the construction of locks and canals on this river, they were taken out at three different carrying places, all of H 2 which

115

which made 15 miles. It is expected that in a few years the obstructions will be all removed. Sturgeon, falmon, and fhad, are caught in plenty in their feafon, from the mouth of the river upwards, excepting flurgeon, which do not afcend the upper falls; befides a variety of fmall fifh, fuch as pike, carp, perch, &c.

There is yet a ftrong expectation of opening a communication between this river and the Merrimack, through Sugar R. which runs into the Connecticut at Claremont in N. Hampfhire, and the Contoocook, which falls into the Merrimack at Bolcawen.

From this river were employed in 1789, three brigs, of 180 tons each, in the European trade; and about 60 fail, from 60 to 150 tons, in the W. India trade, befides a few fishermen, and 40 or 50 coaffing veffels. The number has confiderably increafed fince.

CONNECTICUT, a fream in Long Island, N. York, which falls into a bay at the S. fide of the ifland. It lies 2 miles to the fouthward of Rockonkama pond.

CONTINENTAL Village, was fituated on North R. in New-York state. Before its deftruction by Sir Henry Clinton, in Oct. 1777, there were here barracks for 2,000 men.

CONVERSATION Point, a head land on the S. fide of a bay on the coaft of California, N. lat. 32. 30. W. long. 119.

CONWAY, a township in the province of New-Brunfwick, Sudbury co. on the weftern bank of St. John's R. It has the bay of Fundy on the S. and at the westernmost point of the township there is a pretty good harbour called Mufquash cove.

CONWAY, a township in the N. E. corner of Strafford co. New-Hampfhire, on a bend in Saco river, incorporated in 1765, and contains 574 inhabitants. It was called Pigwacket by the Indians,

CONWAY, a thriving township in Hampshire co. Massachusetts, incorporated in 1767, and contains 2092 inhabitants. It lies 13 miles N. W. of Northampton, and 115 N. W. by W. of Bofton.

CONYA, a river in Surinam, or Dutch Guiana, S. America.

COOLOOME, an Indian town fituated on the W. fide of Talapoole R. a r. 96

COOK'S R. in the N. W. coaff of N. America, lies N.W. of PrinceWilliam's found, and 1000 miles N. W. of Nootka found. N. lat. 59. 30. W. long. 153. 12. and promifes to vie with the moft confiderable ones already known. It was traced by Capt. Cook for 210 miles from the mouth, as high as N. lat. 61. 30. and fo far as is difcovered. opens a very confiderable inland navigation by its various branches. The inhabitants feemed to be of the fame race with those of Prince William found ; and like them had glafs beads and knives, and were also clothed in fine furs.

COOKHOUSE, on the Cooquago branch of Delaware R. is fituated in the township of Colchester, New-York, 18 miles S. of the mouth of Unadilla river.

COOPER's Ifland, one of the leffer Virgin Ifles in the Weft-Indies, fituated S. W. of Ginger Ifland, and uninhabited. It is 5 miles long, and 1 broad. N. lat. 18. 5. W. long. 62. 57.

COOPER, a large and navigable river which mingles its waters with Afhley R. below Charleston city in S. Carolina. Thefe form a fpacious and convenient harbour, which communicates with the ocean, just below Sullivan's island, which it leaves on the N. 7 miles S. E. of the city. In these rivers the tide rises 61 feet. Cooper R. is a mile wide at the ferry, 9 miles above Charleftown.

COOPER's Town, a post town and township, in Otsego co. New-York, and is the compact part of the township of Otfego, and the chief town of the country round Lake Otfego. It is pleafant-ly fituated at the S. W. end of the lake, on its banks, and those of its outlet : 12 miles N. W. of Cherry Valley, and 73 W. of Albany. Here are a court-houfe, gaol, and academy. In 1791, it contained 292 inhabitants. In 1789, it had but 3 houfes only; and in the fpring 1795, 50 houses had been erected, of which above a fourth part were refpectable 2 ftory dwelling houfes, with every proportionable improvement, on a plan regularly laid out in squares. N. lat. 42. 44. W. long. 74. 48.

COOPER's Town, Pennfylvania, is fituated on the Sufguehannah river. This place, in 1785, was a wildernefs. Nine years after, it contained 1800 inhabitants-a large and handfome church, bettering

hettering lumes, a Four hur laid unde bringing and cond town. COOP' land, lies and 22 N furing in Coos, Upper an necticut 1 above Da is the cou R. on Jol Coos lies S. of the diftance f in Kennet and was f Coosa bama R. mouth, c Gillivray' mouth of COOSA of S. Carc burg diftri courfe, e Whale B fort island COOSA which rife rokees' co forms Ala rally S. ru the Natch Upper Cr broken of pid, and f ly navigab COOSA post town lina, fituat R. over w erected. I about 40 gaol. T Beaufort, from Beau Charlefton COOTS vania, is fi hoca creek R. It co man Luth united. I A State of the second sec

bettering houfe-a library of 1200 volumes, and an academy of 64 fcholars. Four hundred and feventy pipes were laid under ground, for the purpole of bringing water from Weft Mountain, and conducting it to every house in town.

COOP's Town, in Harford co. Maryland, lies 12 miles N. W. of Harford, and 22 N. eafterly of Baltimore; meafuring in a ftrait line.

Coos, or Cobos, the country called Upper and Lower Coos, lies on Connecticut R. between 20 and 40 miles above Dartmouth college. Upper Coos is the country S. of Upper Amonoofuck R. on John and Ifrael rivers. Lower Coos lies below the town of Haverhill, S. of the Lower Amonooluck. The diftance from Upper Coos, to the tide in Kennebeck R. was measured in 1793, and was found to be but go miles.

COOSADES, an Indian town on Alabama R. about 60 miles above its mouth, on Mobile R.; below Mc. Gillivray's town, and opposite the mouth of the Oakfuskee.

COOSA HATCHEE, or Coofarw, a river of S. Carolina, which rifes in Orangeburg diffrict, and running a S. S. W. courfe, empties into Broad R. and Whale Branch, which feparate Beaufort island from the main land.

COOSA, or Coofa Hatcha, a river which rifes in the high lands of the Cherokees' country, and joining Tallapoofe, forms Alabama R. Its courfe is generally S. running through the country of the Natchez, and other tribes of the Upper Creeks, the roughest and most broken of the whole nation. It is rapid, and full of rocks and fhoals, hardly navigable for canoes.

COOSAWATCHIE, or Coofabatchie, a post town in Beaufort district. S. Carolina, fituated on the S.W. fide of Coofa R. over which a bridge has been lately erected. It is a flourishing place having about 40 houfes, a court-houfe and gaol. The courts formerly held at Beaufort, are held here. It is 33 miles from Beaufort, and 77 W. S. W. of Charlefton.

COOTSTOWN, in Berks co. Pennfylvania, is fituated on a branch of Sauhoca creek, a branch of the Schuylkill R. It contains 40 houses, and a German Lutheran and Calvinist church united. It is 17 miles N. N. E. of

COO Reading, and 73 N. W. by N. of Phi-

ladelphia. COPIAPO, an open town in the bifhop-rick of St. Jago, or Chili Proper, in S. America, famous for its mines of iron, brafs, tin, and lead; which, however, are not worked. The gold mines have drawn about 900 people here. There are also great quantities of load-ftone, and lapis-lazuli, 14 or 15 leagues diftant; where there are also feveral lead mines. On the high mountains of the Cordillera, 40 leagues E. S. E. from the port, are mines of the fineft fulphur, not needing to be cleanfed, and which fells for 3 pieces of eight a quintal, at the port, from whence it is carried to Lima. Fresh-water is very fcarce. Salt-petre is found in the vale an inch thick on the ground. Between this and Coquimbo is no town or village, only 3 or 4 farms. Lat. 25. 10. S. long. 75. 14. W.

COPPER MINE, a large river of New-Britain, reckoned to be the most northern in North-America. Taking a northerly courfe it falls into the fea in lat. 72. N. and about 110. W. long. from Greenwich. The accounts brought by the Indians of this river to the British ports in Hudfon bay, and the specimens of copper produced by them, induced Mr. Hearne to fet out from Fort Prince of Wales in Dec. 1770, on a journey of discovery. He reached the river on the 14th July, at 40 miles diftance from the fea, and found it all the way incumbered with fhoals and falls, and emptying itfelf into it over a dry flat of the fhore, the tide being then out, which feemed by the edges of the ice to rife about 12 or 14 feet. This rife, on account of the falls, will carry it but a very finall way within the river's mouth; fo that the water in it has not the leaft brackifh tafte. Mr. Hearne had the most extenfive view of the fea, which hore N. W. by W. and N. E. ; when he was about 8 miles up the river. The fea at the river's mouth, was full of iflands and fhoals; but the ice was only thawed away about three-fourths of a mile from the fhore, on the 17th of July. The Ef-quimaux had a quantity of whale-bone and feal fkins at their tents on the fhore.

COQUIMBO, a town of St. Jago, or Chili Proper, in S. America, fituated at the lower end of the vale, bearing the fame name, on a gently rifing ground. The river of Coquimbo gives name to H₃ the

unia, is river. ternefs. 800 inchurch, e and a

ettering

N.

m's

ootng. the

wn.

210

N.

red.

avi-

e in-

race

and ;

and

fine

uago

n the

1, 18

iver.

leffer

nated

abit-

d. N.

river

Ifhley

olina.

enient

th the

fland,

S. E.

e rifes

de at

n and

k, and

hip of

coun-

afant-

e lake.

et: 12

and 73

houfe,

it con-

89, it

fpring

ted, of

refpect-

h every

a plan

N. lat.

wm.

the agreeable valley through which it rolls to the fea; and the bay at its mouth is a very fine one, where fhips lie fafely and commodioufly, though the coaft is rocky, fome islands lying to as to keep off the winds. The town is properly called La Serena, from the agreeablenefs of the climate; being continually ferene and pleafant. The ftreets are well laid out, and there are s or 6 convents; but the houfes are not handfome. The foil is fruitful in corn, wine, and oil, and the brooks bring down quantities of gold duft after heavy rains. Here are no gold mines, but plenty of copper; one of which, 5 leagues N. from the city on Mount Cerro Verde, or Green Hill, is high, and fhaped like a fugar loaf; fo that it may ferve as a land mark to the port. It lies 260 miles N. of St. Jago, and juftly boafts of one of the fineft fituations in the world ; but the arbitrary government of Spain renders it a place of little importance.

CORAL River, in New Mexico, runs a courfe W. by S. and empties into the head of the gulf of California, close by the mouth of Collerado river.

CORAM, a post town in Suffolk co. Long I. New-York. It has about 60 houses, and lies 62 miles eastward of New-York city, and 10 from Smithtown.

CORCAS, or Grand Corcas, an island almost in the form of a crescent, N. of St. Domingo, in the windward passage, about 7 leagues W. of Turk's I. and about 20 E. of Little Inagua, or Heneagua. N. lat. 21. 55. W. long. 70. 55. CORDILLERA. See Andes.

CORDOVA, DE LA NUEVA ANDA-LUSIA, a city of Peru, in S. America, in the jurifdiction of Charcas, 80 leagues S. of Santiago del Eftero. Here is the Episcopal church of Tucuman, with fome monasteries, and a convent. It is fruitful in grain, honey, wax, fruits, cotton, and fugar. It abounds with faltpits, and has luxuriantpafturesfor mules. It drives a great trade with Buenos Ayres. The inhabitants are Spaniards, who are farmers, and manufacturers of cotton cloth, which they fend to Potofi. S. lat. 31 30. W. long. 63. 30. In Cordova, in the Tucuman, there has been found the greateft inftance of longevity fince the days of the patriarchs. From indifputable evidence, a negrefs, named

Louisa Truxo, was alive in 1774, aged one bundred and seventy-five years.

CORE Sound, on the coast of North-Carolina, lies S. of, and communicates with, Pamlico.

CORIENTES, a cape of Mexico, or New-Spain, on the N. Pacific ocean. N. lat. 21. W. long. 109. 30. Alfo, the name of the S. westernmost point of the island of Cuba.

CORIENTES, LOS, a finall city within the government of Buenos Ayres, in S. America, was built by the Spaniards on the confluence of the Parana and Paraguay, 80 leagues higher than Santa Fe, on the Rio de Plata.

CORINTH, a township in Orange co. Vermont, W. of Bradford, containing 578 inhabitants.

CORK Bay, on the E. fide of Newfoundland Ifland.

CORNISH, a township in Cheshire co. New-Hampshire, on the E. bank of Connecticut R. Between Claremont and Plainfield, about 15 miles N. of Charlestown, and 16 S. of Dartmouth College. It was incorporated in 1763. In 1775, it contained 309, and in 1790-982 inhabitants.

CORNWALL, a township in Addison co. Vermont, E. of Bridport, on Lake Champlain, containing 826 inhabitants.

CORNWALL, New, a township in Orange co. New-York, of whose inhabitants, 350 are electors.

CORNWALL, a township in Litchfield co. connecticut, about 9 miles N. of Litchfield, 11 S. of Salisbury, and about 40 W. by N. of Hartford city.

CORNWALL, a finall town in Upper Canada, on the bank of Iroquois R. near Lake St Francis, between Kingston and Quebec, containing a finall church, and about 30 or 40 houses,

CORNWALLIS, a town in King's co. in the province of New-Brunswick, fituated on the S. W. fide of the Basin of Minas; 18 miles N. W. of Falmouth, and 55 N. W. of Annapolis.

Alfo a river in the fame province, navigable for veffels of 100 tons 5 miles; for veffels of 50 tons 10 miles.

CORO, a town of S. America, in Terra Firma, at the bottom of the gulf of Venezuela, 60 miles W. of La Guaira. N. lat. 11. W. Jong. 70.

COROPA, a province of S. America, fituated between the river Amazon and the lake Parime.

CORTLANDT,

Col northe Chefte Newants, inhabi Co its na rich m Tinfig niards other barren of Gu by the and th reache 90 lea where much hourin the foi On th bays, rom's, Verag S. fea conver town Co S. An Cuíco city. cattle. exhau Co from fide of St. D the fo N. lat Co taacu the pr rica. the to ice an 1553, entere prove coinci prieft on the cordin 15.59 Co Spani ming na, N

aged Northlicates

co, or ocean. Alfo, oint of

withres, in niards 1 Par-Santa

ge co. aining New-

ire co. nk of nt and harlefollege. 1775, 82 in-

ddifon Lake itants. ip in inha-

chfield N. of about

Upper ois R. ingíton hurch,

g's co. k, fitulafin of nouth,

ovince, miles;

rica, in he gulf a Gua-

nerica, on and

ANDT,

COT

CORTLANDT, a township in the northern part of the county of West Chefter, on the E. bank of Hudson river, New-York, containing 1932 inhabitants, of whom 66 are flaves. Of its inhabitants, in 1796, 305 were electors.

COSTA RICA, or the Rich Coaft, as its name fignifies, is fo called from its rich mines of gold and filver, those of Tinfigal being preferred by the Spamiards to the mines of Potofi ; but in other respects, it is mountainous and barren. It is fituated in the audience of Guatimala, in New Spain, bounded by the province of Veragua on the S. E. and that of Nicaragua on the N. E. It. reaches from the N. to the S. fea, about 90 leagues from E. to W. and is 50 where broadeft, from N. to S. It has much the fame productions as its neighhouring provinces; and in fome places the foil is good, and it produces cocoa. On the N. fea it has two convenient bays, the most westerly called St. Jerom's, and that near the frontiers of Veragua, called Caribaco; and on the S. fea it has feveral bays, capes, and convenient places for anchorage. Chief town Nycoya.

COTABAMBO, a jurifdiction in Peru, S. America, fubject to the bishop of Cusco, and lies 20 leagues S. W. of that eity. It abounds in grain, fruits, and cattle. Its rich mines are now almost exhausted.

COTEKUX, LES, a town on the road from Tiburon to Port Salut, on the S. fide of the S. peninfula of the ifland of St. Domingo, $13\frac{1}{2}$ leagues E. by S. of the former, and 4 N. W. of the latter, N. lat. 18, 12.

COTOPAXI, a large volcano near Lataacungo, an affiento or dependence on the province of Quito in Peru, S. America. It lies nearly under the line, yet the tops of it are generally covered with ice and fnow. It first fnewed itself in 1553, when Sebastian de Belacazar first entered these countries, which eruption proved favourable to his enterprise, as it coincided with a prediction of the Indian priefts, that the countryshould be invaded on the burfting of this volcano; and accordingly it to happened; for before 1559 he had subdued all the country.

COTUY, a canton and town in the Spanish part of the island of St. Domingo, bounded E. by the bay of Samana, N. by the chain of mountains called COU

Monte-Chrift, W. by the territory of la Vega, and S. by the chain of mountains called Sévico. In 1505, the gold mines were worked here. In the mountain of Meymon, whence comes the river of the fame name, there is a copper mine, fo rich, that when refined will produce 8 per cent. of gold. Here are alfo found excellent lapis-lazuli, a ftreaked chalk, that fome painters pre-fer to bole for gilding; loadstone, e. meralds, and iron. The iron is of the best quality, and might be conveyed from the chain of Sévico by means of the river Yuna. The foil here is excellent, and the plantanes produced here are of fuch fuperior quality, that this manna of the Antilles is called at St. Domingo Sunday plantanes. The people cultivate tobacco, but are chiefly employed in breeding fwine. The inhabitants are called clownifh, and of an unfociable character.

The town is fituated half a league from the S. W. bank of the Yuna, which becomes unnavigable near this place, about 13 leagnes from its mouth in the bay of Samana. It contains 160 fcattered houfes, in the middle of a little favanna, and furrounded with woods, 30 leagues northerly of St. Domingo, and 15. S. E. of St. Yago. N. lat. 19-11. W. long. from Paris 72. 27.

COUDRAS, a finall ifland in St. Lawrence river, about 45 miles N. E. of Quebec.

COUNTRY Harbour, fo called, is about 20 leagues to the caftward of Halifax, in Nova-Scotia.

COUPEE, or Cut Point, a fort turn in the river Millifippi, about 35 miles above Mantchac fort, at the gut of Ibberville, and 259 from the mouth of the river. Charlevoix relates that the river formerly made a great turn here, and fome Canadians, by deepening the channel of a fmall brook, diverted the waters of the river into it, in the year 1722. The impetuofity of the ftream was fuch, and the foil of fo rich and loofe a quality, that in a fhort time the point was entirely cut through, and the old channel left dry, except in inundations: by which travellers fave 14 leagues of their voyage. The/new channel has been founded with a line of 30 fathoms, without finding bottom.

The Spanish fettlements of Point Coupeé, extend 20 miles on the W. fide H 4 of

of the Miffifippi, and there are fome plantations back, on the fide of La Faufe Riviere, through which the Miffifippi paffed about 70 years ago. The fort at Point Coupeé is a fquare figure, with four baftions, built with flockades. There were, fome years fince, about 2000 white inhabitants and 7000 flaves. They cultivate Indian corn, tobacco, and indigo; raife vaft quantities of poultry, which they fend to New Orleans. They alfo fend to that city iquared timber, flaves, &c.

COVENTRY, a township in Tolland co. Connecticut, 20 miles E. of Hartford city. It was settled in 1709, being purchased by a number of Hartford gentlemen of one Joshua, an Indian,

COVENTRY, in Rhode-Island state, is the N. easternmost township in Kent co. It contains 2477 inhabitants.

COVENTRY, a township in the northern part of New-Hampshire, in Graston co. It was incorporated in 1764, and contains 80 inhabitants.

COVENTRY, a township in Orleans co.' Vermont. It lies in the N. part of the ftate, at the S. end of Lake Memphremagog. Black R. passes through this town in its course to Memphremagog.

gog, COVENTRY, a township in Chefter co. Pennsylvania.

Cowe, is the capital town of the Cherokee Indians, fituated on the foot of the hills, on both fides of the river Tennefice. Here terminates the great vale of Cowe exhibiting one of the most charming, natural, mountainous landscapes that can be seen. The vale is closed at Cowe by a ridge of high hills, called the *fore mountains*. The town contains about 100 habitations,

In the conflitution of the flate of Tenneffee, Cowè is described as near the line which separates Tenneffee from Virginia, and is divided from Old Chota, another Indian town, by that part of the Great Iron or Smoaky mountain, called Unicoi, or Unaca mountain.

COWETAS, or Kowetas, a town of the Lower Creeks, in East-Florida, called the Bloody town. [See Apalachicola-town.] It lies on the W. bank of Chata-Uche R. and contains 280 men.

COW AND CALF PASTURE Rivers, are head branches of Rivanna river, in Virginia.

Cows Ifland. See Vache.

COWTENS, a place fo called, in S, Carolina, between Pacolet river and the head branch of Broad river. This is the fpot where Gen. Morgan gained a complete victory over lieut. col. Tarleton, Jan. 11, 1781, having only 12 men killed and 60 wounded. The Britifh had 39 commiffiqued officers killed, wounded and taken prifoners; 100 rank and file killed, 200 wounded, and 500 priffners. They left behind 2 pieces of artillery, 2 flandards, 800 mufkets, 35 baggage waggons, and 100 dragoon horfes, which fell into the hands of the Americans. The field of battle was in an open wood.

COXHALL, a township in York co. district of Maine, containing 775 inhabitants.

COXSAKIE, a township in the weftern part of Albany co. New-York, containg 3406 inhabitants, of whom 302 are flaves. Of the citizens 613 are electors.

COYAU, a fettlement on Tenneffee river, 30 miles below Knoxville.

CRAB-ORCHARD, a post town, on Dick's river, in Kentucky, 8 miles from Cumberland river, and 25 miles S. E. of Danville. The road to Virginia passes through this place.

CRANBEERY, a thriving town in Middlefex, co. New-Jerfey, 9 miles E. of Princeton, and 16 S. S. W. of Brunfwick. It contains a handfome Prefbyterian church, and a variety of manufacturies are carried on by its induffrious inhabitants. The ftage from New-York to Philadelphia paffes through Amboy, this town, and thence to Bordentown.

CRANBERRY Islands, on the coaft of the diffrict of Maine. See Mount Defer: Island.

CRANEY, a finall island, on the S. fide of James river, in Virginia, at the mouth of Elizabeth river, and 5 miles S. W. of Fort George, on Point Comfort. It commands the entrance of both rivers.

CRANSTON, is the fouth-eafternmoft township of Providence co. Rhode-1fland, fituated on the W. bank of Providence R. 5 miles S. of the town of Providence. The compact part of the town contains 50 or 60 houses, a Baptist meeting house, handsome schoolhouse, a diftillery, and a number of faw and grift mills, and is called Pawtuxet, from the river, on both fides of whole mouth

mouth bridge town. as you townfh CR Caroli S. by Its chi 10,469 flaves. CRE of littl Dauph CRE Maryl cocy R creeks miles the Po northe CRE defcrib or Muj followi journal fa rive the W lages o ground the To line bet Chaeta have fr fome o that ar ftand in gether, down t ftreams tain a c eat and has a p near th various the nam Upper public of the (Upper. Coofas Pocunt laffie,] Tawal Weelu tle, W: followi land an fa and

he

is

le-

in

d,

nk

00

es

ts,

011

hé

in

0.

a-

ſł-

n--

22

re

fee

on

m

Ε.

ia

in E.

if-

y-

u-

us

rk

y,

of

e-

s.

ne

es

3-

of

ft

1-

i-

0-

le

1-

W

t,

ſe

h

mouth it ftands, and over which is a bridge, connecting the two parts of the town. It makes a pretty appearance as you pais it on the river. The whole townfhip contains 1877 inhabitants. CRAVEN Co. in Newbern diffrict, N. Carolina, is bounded N. by Pitt, and S. by Carteret and Onflow counties. Its chief town is Newbern. It contains 10,469 inhabitants, of whom 3658 are flaves.

CREE INDIANS, THE, inhabit weft of little lake Winnipeg, around fort Dauphin, in Upper Canada.

CREGER'S Toron, in Frederick co. Maryland, lies on the W. fide of Monococy R. between Owing's and Hunting creeks, which fall into that river; 9 miles foutherly of Ermmt/burg, near the Penufylvania line, and about 11 northerly of Fredericktown.

CREEKS, an Indian nation already defcribed under the name of Muskogulge or Mufkogee, in addition to which is the following particulars from the M. S. journal of an intelligent traveller. Coofa river, and its main branches, form the Weftern line of fettlements or villages of the Creeks, but their hunting grounds extend 200 miles beyond, to the Tombigbee, which is the dividing line between their country and that of the Chactaws. The fmalleft of their towns have from 20 to 30 houses in them, and fome of them contain from 150 to 200, that are wholly compact. The houses stand in clusters of 4, 5, 6, 7, and 8 together, irregularly distributed, up and down the banks of the rivers or fmall ftreams. Each clufter of houfes contain a clan, or family of relations, who eat and live in common. Each town has a public fquare, hot-houfe and yard near the centre of it, appropriated to various publicules. The following are the names of the principal towns of the Upper and Lower Creeks, that have public squares; beginning at the head of the Coola or Coola Hatcha river, viz. Upper Utalas, Abbacoochees, Natchez, Coofas, Oteetoocheenas, Pinc Catchas, Pocuntullahafes, Weeokes, Little Tallaffie, Tufkeegees, Cooladas, Alabamas, Tawalas, Pawactas, Autobas, Auhoba, Weelunipkees Big, Weelumpkees Little, Wacacoys, Wackfoy, Ochees ... The following towns are in the central, inland and high country, between the Coofa and Tallapoofee rivers, in the dif-

trict called the Hillabees, viz. Hillabees, Killeegko, Oakchoys, Slakagulgas, and Wacacoys. On the waters of the Tallapoofee, from the head of the river downward, the following, viz. Tuckabatchee, Tchaffa, Totacaga, New York, Chalaacpaulley, Loguipogus, Oakfuskee, Ufala Little, U ala Big, 30gahatches, Tuckaba chees, Big Tailaffee, or half way house, Clewaleys, Cooiahatches, Coolamies, Shawaneic, or Savanas, Kenhulka, and Muckeleies. I he towns of the Lower Creeks, beginning on the head waters of the Chattahoofee, and to on downwards are Chelu Ninny, Chattahoofee, Hohtatoga, Cowetas, Cuffitahs, Chalagaticaor, Broken Arrow, Euchees feveral, Hitchatees feveral, Palachuolo, Chewackala. Befides 20 towns and villages of the Little and Big Chehaus, low down on Flint and Chattahoofee rivers. From their roving and unfteady manner of living, it is impoffible to determine, with much precision, the number of I dians that compose the Creek nation. Gen. M'Gillivray eftimates the number of gun-men to be between 5 and 6000, exc usive of the Seminoles; who are of little or no account in war, except as fmall parties of marauders, acting independent of the general intereft of the others. The whole number of individuals may be about 25 or 26,000 Duls. Every town and village has one established white trader in it, and generally a family of whites, who have fled from fome part of the fron-They often to have revence, tiers. and to obtain plunder that may be taken, use their influence to fend out predatory parties against the settlements in their wicinity. The Creeks are very badly armed; having few rifles, and are mostly armed with mulkets. For near 40 years paft, the Creck Indians have had little intercourfe with any other foreigners, but those of the English nation. Their prejudice in fav ur of every thing English, has been carefully kept alive by tories and others to this day. Most of their towns have now in their poffession British drums with the arms of the nation, and other emblems painted on them, and fome of their iquaws preferve the remnants of British flags. They ftill believe that " The Great King over the water" is able to keep the whole world in fubjection. The land of the country is a common

flock ;

flock ; and any individual may remove from one part of it to another, and occopy vacant ground where he can find it. The country is naturally divided into 3 districts, viz. the Upper Creeks, Lower and middle Creeks, and Seminoles. The upper diffrict includes all the waters of the Tallapoofee, Coofahatchee, and Alabama rivers, and is called the Abbacoes. The Lower or Middle diffrist includes all the waters of the Chattahoofee and flint rivers, down to their junction, and although occupied by a great number of different tribes, the whole are called Cowetaulgas, or Coweta people, from the Cowetan town and tribe, the most warlike and ancient of any in the whole nation. The Lower or Southern district, takes in the river Appalachicola, and extends to the point of East-Florida, and is called the country of the Seminoles. Agriculture is as far advanced with the Indians, as it can well be, without the proper implements of hufbandry. A very large majority of the nation being devoted to hunting in the winter, and to war or idlenefs in fummer, cultivate but fmall parcels of ground, barely fufficient for fubfiftence. But many individuals, (particularly on Flint river, among the Chehaws, who poffets numbers of negroes) have fenced fields, tolerably well cultivated : having no ploughs, they break up the ground with hoes, and featter the feed promifcuoufly over the ground, in hills, but not in rows. They raife horfes, cattle, fowls, and hogs. The only articles they manufacture are earthen pots and pans, balkets, horfe-ropes or halters, imoaked leather, black marble pipes, wooden fpoons, and oil from acorns, hickory nuts, and cheinuts.

CREEKS, confederated nations of Indians. See Mufcogulge.

CREEKS Croffing Place, on Tenneffee river, is about 40 miles E. S. E. of themouth of Elk R. at the Muscle shoals, and 36 S. W. of Nickajack, in the Georgia western territory.

CROIX, ST. a fmall navigable river in Nova-Scotia, which runs into the Ayon, or Pigiguit. See Avon.

CROIX, ST. a river which forms part of the boundary line between the United States and the British province of New-Bruniwick, and empties into Pasfamaquoddy bay. Which is the true St. Croix is undetermined. Commis-

fioners are appointed by both countries, in conformity to the late treaty, to decide this point.

CROIX, ST. a river in the N. W. territory, which empties into the Miffifippi from the N. N. E. about 50 miles below the falls of St. Anthony.

CROIX, ST. or Santa Cruz, an ifland in the West-Indies, belonging to the king of Denmark, lying about 5 leagues S. E. of St Thomas, and as far E. by S. of Crab island, which lies on the E. end of Porto Rico. It is about 30 miles in length, and 8 where it is breadeft, and is rather unhealthy. It is faid to produce 30,000 or 40,000 hhds. of fugar annually, and other W. India commodities in tolerable plenty. It is in a high flate of cultivation, and has about 3000 white inhabitants, and 30,000 flaves. A great proportion of the negroes of this ifland have embraced christianity, under the Moravian miffionaries, whole influence has been greatly promotive of the profperity of this ifland. N. lat. 17. 50. W. long. 64. 30. See Danifb Weft-Indies.

CROOKED Ifland, one of the Bahama or Lucayo iflands, in the W. Indies. The middle of the ifland lies in N. lat. 23. W. long. 73. 30.

23. W. long. 73. 30. CROOKED Lake, in the Genefice country, communicates in an E. by N. direction with Seneca lake.

CROOKED Lake, one of the chain of finall lakes which connects the lake of the Woods with lake Superior, on the boundary line between the U. States and Upper Canada, remarkable for its rugged cliffs, in the cracks of which are a number of arrows flicking.

CROOKED R. in Camden co. Georgia, empties into the fea opposite Cumberland island, 12 or 14 miles N. from the mouth of St. Mary's. Its banks are well timbered, and its course is E. by N.

CROSS Cape, in Upper Canada, projects from the N. E. fide of St. Mary's river, at the outlet of lake Superior, opfite the falls, in N. lat. 46. 30. W. long 84. 50.

CROSS-CREEK, a township in Washington county, Pennsylvania.

CROSS Creeks. See Fayetteville.

CROSS-ROADS, the name of a place in North Carolina, near Duplin courthoule, 23 miles from Sampion courthoule, and 23 from South-Washington. CROSS-ROADS, a village in Kent co. Maryland, co. road Lar Ma Wi ton line

Phi

ker

All

14

Hu

Fai

thr

pan

this

the

foli

the

flat

pill

Cre

tate

per

pla

thr

fro

To

260

W

int

fin

wit

pi.

mi

tov

cal

wh

ed

its

till

by

an

T

by

lal

Pu

an

Lur

St.

1

(

. Ma

tow

fror

oth

. (

Maryland, fituated 2 miles S. of Georgetown, on Saffafras R. and is thus named from 4 roads which meet and crofs each other in the village.

ies,

de-

w.

ffi-

iles

and

the

5 tar

on

tuo

t is

000

w.

nty.

and

and

1 of

ced

nif-

reen

of

ng.

ha-

ies.

lat.

flee

N.

1 of

e of

the

ates

its

lich

tor-

m-

rom

are

N.

10-

ry's

op-

Ŵ.

afh-

iace

urt-

urt-

ton.

co.

and,

It

CROSS-ROADS, a village in Chefter co. Penníylvania, where 6 different roads meet. It is 27 miles S. E. of Lancafter; 11 N. by W. of Elkton, in Maryland, and about 18 W. N. W. of Wilmington in Delaware.

CROSSWICKS, a village in Burlington co. New Jerfey; through which the line of ftages paffes from New-York to Philadelphia. It has a respectable Quaker meeting house; 4. miles S. W. of Allen Town, 8 S. E. of Trenton, and 14 S. W. of Burlington.

CROTON R. a N. eaftern water of Hudson R. rifes in the town of New-Fairfield, in Connecticut, and running through Dutchefs co. empties into Tappan bay. Croton bridge is thrown over this river 3 miles from its mouth, on the great road to Albany. This is a folid fubstantial bridge, 1400 feet long, the road narrow, piercing through a flate hill. It is supported by 16 stone pillars. Here is an admirable view of Croton Falls, where the water precipitates itself between 60 and 70 feet perpendicular; high flate banks, in fome places 100 feet; the river fpreading into three ftreams, as it enters the Hudion.

CROW Creek, falls into the Tenneffee, from the N. W. opposite the Crow Town, 15 miles below Nickajack Town. CROWS Meadows, a river in the N. W. territory, which runs N. weftward into Illinois R. opposite to which are fine meadows. Its mouth is 20 yards wide, and 240 miles from the Mifflifippi. It is navigable between 15 and 18 miles.

CROWN Point, is the most foutherly township in Clinton co. New-York, fo called from the celebrated fortrefs, which is in it, and which was garrifoned by British troops, from the time of its reduction by gen. Amherst in 1759, till the late revolution. It was taken by the Americans the 14th of May 1775, and retaken by the British the year after. The point upon which it was erected, by the French in 1731, extends N. into lake Champlain. It was called Kruyn Punt, or Scalp Point by the Dutch, and by the French, Pointe à la Chevelure. The fortrefs they named Fort St. Frederick. After it was repaired

by the British, it was the most regular and expensive of any constructed by them in America. The walls are of wood and earth, about 16 feet high and about 20 feet thick, nearly 150 yards fquare, and furrounded by a deep and broad ditch, dug out of the folid rock. The only gate opened on the N. towards the lake, where was a draw-bride and a covert-way, to fecure a communication with the waters of the Lake, in cafe of a fiege. On the right and left, as you enter the fort, is a row of ftone barracks, not inelegantly built, which are capable of containing 2000 troops. There were formerly feveral out-works, which are now in rains, as is indeed the cafe with the principal fort, except the walls of the barracks. The famous fortification called Ticonderoga is 15 miles S. of this; but that fortrefs is alfo fo much demolished, that a stranger would fcarcely form an idea of its original confiruction. The town of Crown Point has no rivers; a few ftreams, however, iffue from the mountains, which enfwer for mills and common ufes. In the mountains, which extend the whole length of lake George, and part of the length of Lake Champlain, are plenty of moofe, deer, and almost all the other inhabitants of the foreft. In 1790, the town contained 203 inhabitants. By the fate cenfus of 1796, it appears there are 126 clectors. The fortreis lies in N. lat. 44. 20. W. long. 73. 36.

CROYDEN, a township in Cheshire co. New-Hampshire, adjoining Cornish, and about 18 miles N. E. of Chariestown. It was incorporated in 1763. In 1775, it contained 143, and in 1790, 537 inhabitants.

CRUCES, a town of Terra Firma, S. America, 5 leagues from Panama, and fituated on Chagre rive.

CRUZ, SANTA, a confiderable town on the N. coaft of the island of Cuba, about 30 miles E. by N. of the Havannah, and 115 N. W. by N. of Cadiz.— Alfo the chief town of Cuzumel island.

CRUZ, SANTA, a town of Mexico, or New Spain, about 75 miles N. by E. of St. Salvadore, on the Pacific ocean. It is fituated on the gulf of Dulce, which communicates with the fea of Honduras.

CRUZ, SANTA, DE LA SIERRA, a. government and generalship, alfo a juritdiction,

ridiction and Bishoprick, under the 1492. It was taken possession of by bithop of Charcas, 90 leagues E. of Plata, in Peru.

CRUZ, Santa, an ifland in the W. Indies. See St Croix.

CUBA, is the most valuable island of all the Spanish West Indies, and is fituated between 20. and 23. 30. N. lat. and between 74. and 85. 15. W. long.; 100 miles S. of Cape Florida, and 75 N. of Jamaies; and is nearly 700 miles in length, and generally about 70 in breadth. A chain of hills runs through the middle of the island from E. to W. but the land near the fea is in general level, and flooded in the rainy feafon, when the fun is vertical. This noble ifland, the key of the Weft-Indies, is supposed to have the best foil, for fo large a country, of any in America, and contains 38,400 fquare miles. It produces all the commodities known in the Welt-Indies, particularly, ginger, long pepper, and other spices, caffia, fiftula, mattick, and aloes. It also produces tobacco and fugar; but from the want of hands, and the lazine's of the Spanpards, it does not produce, including all its commodities, fo much for exportation as the small island of Antigua. Not an hundredth part of the island is yet cleared. The principal part of the plantations are on the beautiful plains of Savannah, and are cultivated by about 25,000 flaves. The other inhabitants amount to about 30,000.

The course of the rivers is too fhort to be of any confequence to navigation; but there are feveral good harbours in the ifland, which belong to the principal towns, as the Havannah, St. Jago, Santa Cruz, and La Trinidad. Belides the harbours of these towns there is Cumberland harbour. The tobacco raifed here is faid to have a more delicate flayour than any raifed in America. There are a vaft number of fmall ifles round this noble ifland, the channels feparating which, as well as the rivers in the ifland, abound with fifh. There are more aligators here than in any other place in the Weft Indies. In the woods are fome very valuable trees, particularly cedars, to large, it is faid, that canoes made of them will hold 50 men. Birds there are in great variety, and in number more than in any of the other iflands. This ifland was discovered by the famous Chriftopher Columbus, in between the Blue Ridge and the tide

CUL

the Spaniards in 1511, and they foon exterminated the mild and peaceable natives to the amount of 500,000. The hills are rich in mines, and in fome of the rivers there is gold duft. The copper mines only are worked, which are in the eastern part of the island. Here are also fountains of bitumen.

CUBAGUA, an island of America, fituated between that of Margaretta and Terra Firma, fubject to Spain, and is about 8 miles long. There are a number of pearls got here, but not of the largeft fize. N. lat. 10. 15. W. long. 34. 30.

CUENCA, or Bamba, a city and confiderable jurifdict on in the province of Quito, in Peru, under the torrid zone ; lying in 25. 3. 49. S. lat. The town is computed to contain 20, or 30,000 people; and the weaving of baize, cottons, &c. is carried on by the women, the men being averfe to labour, and prone to all manner of profligacy. It is fituated on the river Curary, or St. Jago; which, after many windings from W. to E. falls at laft into the river Amazon. The town ftands at the foot of the Cordillera mountains. It has two convents, and lies about 170 miles S. of Quito.

CUEYTE, a river in the island of Cuba, which abounds with aligators.

CULIACAN, a province of Guadalaxara, in the audience of New-Galicia, in Mexico, or New-Spain. It has Cinaloa on the N. New-Bilcay and the Zacatecas on the E. Chiametlan on the S. and the gulf of California on the W. It is 60 or 70 leagues long and 50 broad. It abounds with all forts of fruit. The great river La Sal in this country is well inhabited on each fide. According to Dampier, it is a falt lake or bay, in which is good anchorage, though it has a narrow entrance, and runs 12 leagues E, and parallel with the fhore. There are feveral Spanish farms, and falt ponds about it; and 5 leagues from it are two rich mines, worked by flaves belonging to the citizens of Compostella. Here alfo is another great river, whole banks are full of woods and paftures. On this river, Guzman, who discovered the country, built a town, which he called St. Michael, which fee. CULPEPPER, a county in Virginia,

waters,

court from Charl Cu New-Firma its na niard defen fays] a gre ed L are fe fo fha enter the 1 garet 64. 1 CI bay (provi is fit abou C and C E. p of th of fh lat. 20 1 C of C Wil mou and ca. two dres the mel and and hou wer . fide W Ski 11 nor lies

the

CON

N.

Ðu

water

ants,

waters, which contains 22,105 inhabitauts, of whom 8226 are flaves. The court-house of this county is 45 miles from Fredericksburg, and 95 from Charlottesville.

CUMANA, or Comana, the capital of New-Andalufia, a province of Terra Firma, S. America. It fometimes gives its name to the province. The Spaniards built this city in 1520, and it is defended by a ftrong caftle. This town, fays Dampier, ftands near the mouth of a great lake, or branch of the fea, called Laguna de Carriaco, about which are feveral rich towns; but its mouth is fo fhallow that no fhips of burden can enter it. It is fituated 3 leagues S. of the N. Sea, and to the S. W. of Margaretta, in about 10. 20. N. lat. and in 64. 20. W. long.

CUMANAGATE, a finall town in a bay on the coaft of Terra Firma, in the province of Cumana, or Andalufia. It is fituated on a low flat fhore, which abounds with pearl oyfters.

CUMBERLAND, a harbour in the ifland of Juan Fernandes.

CUMBERLAND, a harbour on the S. E. part of the island of Cuba, and one of the finesk in the West-Indics, capable of sheltering any number of ships. N. lat. 20. 30. W. long. 76. 30. It is 20 leagues E. from St. Jago de Cuba.

CUMBERLAND, an island on the coaft of Camden co. Georgia, between Prince William's found at the S. end, and the mouth of Great Satilla R. at its N end, and 20 miles S. of the town of Frederica. Before the revolution there were two forts, called William and St. Andrews, on this island. The former, at the S. end, commanded the inlet of Amelia's found, was ftrongly pallifadoed and defended by 8 pieces of camon, azd had barracks for 200 pien, florehoufes, &c.; within the pallifadoes were fine fprings of water.

CUMBERLAND, a harbour on the E. fide of Washington's itles, on the N. W. coast of N. America. It lies S. of Skitikife, and N. of Cummashawaa.

CUMBERLAND, a bay in the moft northern part of America; its mouth lies under the polar circle, and runs to the N. W. and W. and is thought to communicate with Baffin's bay on the N.

CUMBERLAND Houfe, one of the Hudion bay company's factories is fitu-

ated in New South Wales in North America, 158 miles E. N. E. of Hudfon's house, on the S. fide of Pine-Ifland lake. N. lat. 53. 56 41. W. long. 102. 13. See Nelfon river.

CUM

COMBERLAND, a fort in New Brunfwick, atuated at the head of the bay of Fundy, on the E. fide of its northern branch. It is capable of accomodating 300 men.

CUMBERLAND, a county of New-Brunfwick, which comprehends the lands at the head of the bay of Fundy. on the balon called Chebecton, and the rivers which empty into it. It has feveral townships; those which are fettled are Cumberland, Sackville, Amherft, Hillfborough, and Hopewell. It is watered by the rivers Au Lac, Miffiquafh. Napan Macon, Memramcook, Percoudia, Chepodie, and Herbert. The z first rivers are navigable 3 or 4 miles for veffels of 5 tons. The Napan and Macon are fhoal rivers; The Herbert is navigable to its head, 12 miles, in boats ; the others are navigable 4 or 5 miles.

CUMBERLAND, a town of New-Brunfwick, in the county of its own name. Here are coal mines.

CUMBERLAND Go. in the diftrict of Maine, lies between York and Lincoln counties; has the Atlantic ocean on the S. and Canada on the N. Its fea coaft, formed into numerous bays and lined with a multitude of fruitful iflands, is nearly 40 miles in extent in a ftraight line. Saco river, which runs S. eafterly into the ocean, is the dividing line between this county and York on the S. W. Cape Elizabeth and Cafco bay are in this county. Cumberland is divided into 24 townflips, of which Portland is the chief. It contains 25,450. inhabitants.

CUMBERLAND Co. in New-Jerfey, is bounded S. by Delaware bay, N. by Gloucefter co. S. E. by Cape May, and W. by Salem co. It is divided into 7 townfhips, of which Fairfield and Greenwich are the chief; and contains \$248 inhabitants, of whom 220 are flaves.

CUMBERLAND, the N. eafternmoft town(hip of the flate of Rhode-Ifland, Providence co. Pawtucket bridge and falls, in this town, are 4 miles N. E. of Providence. It contains 1964 inhabitants, and is the only town in the flate which has no flaves.

CUMBERLAND Co. in Pennfylvania,

CUM

120

is bounded N. and N. W. by Mifflin; E. and N. E. by Sufquehannah R. which divides it from Dauphin; S. by York, and S. W. by Franklin co. It is 47 miles in length, and 42 in breadth, and has 10 townships, of which Carlisle is the chief. The county is generally mountainous; but between North and South mountain, on each fide of Conedogwinet creek, there is an extensive, rich, and well cultivated valley. It contains 18,243 inhabitants, of whom 223 are flaves.

CUMBERLAND, a township in York co. Pennfylvania. ---- Alfo the name of a township in Washington co. in the fame fate.

CUMBERLAND Co. in Fayette difrict, N. Carolina, contains 8671 inhabitants, of whom 2181 are flaves. Chief town Fayetteville.

CUMBERLAND, a townflip of the above county, in N. Carolina.

CUMBERLAND, a post town and the chief township of Alleghany co. Mary-land, lies on the N. bank of a great bend of Potowmack R. and on both fides of the mouth of Will's creek. It is 148 miles W. by N. of Baltimore, 109 meafured miles above Georgetown, and about 105 N. W. of Washington city. Fort Cumberland ftood formerly at the W. fide of the mouth of Will's creek.

CUMBERLAND Co. in Virginia, on the N. fide of Appamatox river, which divides it from Prince Edward. It contains 8153 inhabitants, of whom 4434 are flaves. The court-houfe is 28 miles from Powhatan court-houfe, and 52 from Richmond.

CUMBERLAND Mountain, occupies a part of the uninhabited country of the state of Tennessee, between the districts of Wathington and Hamilton and Mero district; and between the two first mamed diffricts and the ftate of Kentucky. The ridge is about 30 miles broad, and extends from Crow creek, on Tenneffee R. from S. W. to N. E. The place where the Tenneffee breaks through the Great ridge, called the Whirl or Suck, is 250 miles above the Mufcle floats. Limeftone is found on both fides the mountain. The mountain confilts of the most stupendous piles of craggy rocks of any mountain in the weftern country. In feveral parts

CUM

ing w

was c

ten oo

thire a

habitt of No.

of B

1779. Cu

an ifla

to the

from 1

Terra

grees

contin

long,

were f

tience

where

be em

friend

only t

for its'

ly on

the Di

defett

one of

elegan

Indies

merou

houfes

zines |

All k

by eng

trived,

the do

ren, t

brough

quanti

it has,

produc

mand 1

colonie

render

the D

which

bitants

harbou

tions i

at this

and the

for trac

hand,

Spanift

fels; fe

with a.

The

The

Cu

the Indians on foot. In one place particularly, near the fummit of the mountain, there is a most remarkable ledge of rocks of about 30 miles in length, and 200 feet thick, fhewing a perpendicular face to the S. E. more noble and grand than any artificial fortification in the known world, and apparently equal in point of regularity.

CUMBERLAND R. called by the Indians "Shawanee," and by the French "Shavanon," falls into the Ohio 10 miles above the mouth of Tennefice R. and about 24 miles due E. from fort Maffac, and 1113 below Pittfburg. It is navigable for large veffels to Nafhville in Tenneffee, and from thence to the mouth of Obed's or Obas R. The Caney fork, Harpeth, Stones, Red, and Obed's, are its chief branches; fome of them are navigable to a great diffance.

The Cumberland mountains in Virginia feparate the head waters of this river from those of Clinch R. It runs S. W. till it comes near the S. line of Kentucky, when its courfe is wefterly, in general, through Lincoln co. receiving many ftreams from each fide; thence it flows S. W. into the flate of Tenneffee, where it takes a winding courfe, inclofing Summer, Davidson, and Tennefiee counties; afterwards it takes a N. weftern direction and re-enters the state of Kentucky; and from thence it preferves nearly an uniform diffance from Tenneffee R. to its mouth, where it is 300 yards wide. It is 200 yards broad at Nafhville, and its whole length is computed to be above 450 miles.

CUMBERLAND-River, a place fo called, where a post office is kept, in Tenneffee, 13 miles from Cumberland mountain, and 80 from the Crab-Orchard in Kentucky.

CUMMASHAWAS, or Cumma fbawaa, a found and village on the E. fide of Washington island, on the N. W. coaft" of N. America The port is capacious and fafe, and its mouth lies in 53. 2. 30. N. lat. and in 228. 22. W. long. In this port Capt. Ingraham remained fome time; and he observes, in his journal, that here, in direct opposition to most other parts of the world, the women maintained a precedency to the men in every point; infomuch that a man dares not trade without the concurrence of his wife; and that he has often been of it, it is inacceffible for miles, even to | witness to men's being abused for parting

ing with fkins before their approbation was obtained: and this precedency often occafioned much diffurbance.

CUMMINGTON, a township in Hamphire co. Massachuletts, having 873 inhabitants; lying about 20 miles N. W. of Northampton, and 120 N. W. by W. of Boston. It was incorporated in 1779-

t

t

5

8

Ŀ

F

k

p,

CURASSOU, Curaçoa or Querifoa, an island in the West-Indics, belonging to the Dutch, 9 or 10 leagues N. E. from Cape Roman, on the continent of Terra Firma. It is fituated in 12 degrees N. lat. 9 or 10 Lagues from the continent of Terra Firma, is 30 miles long, and 10 broad. It feems as if it were fated, that the ingenuity and patience of the Hollanders fhould every where, both in Europe and America, be employed in fighting against an unfriendly nature; for the ifland is not only barren, and dependent on the rains for its water, but the harbour is naturally one of the worft in America: yet the Dutch have entirely remedied that defect; they have upon this harbour one of the largeft, and by far the molt elegant and cleanly towns in the Weft Indies. The public buildings are numerous and handfome; the private houses commodious; and the magazines large, convenient, and well filled. All kind of labour is here performed by engines; fome of them fo well contrived, that thips are at once lifted into the dock.

Though this ifland is naturally barren, the industry of the Durch has brought it to produce a confiderable quantity both of tobacco and sugar; it has, befides, good salt works, for the produce of which there is a brifk demand from the English islands, and the colonies on the continent. But what renders this island of most advantage to the Dutch, is the contraband trade which is carried on between the inhabitants and the Spaniards, and their harbour being the rendezvous to all nations in time of war.

The Dutch thips from Europe touch at this ifland for intelligence, or pilots, and then proceed to the Spanish coafts for frade, which they force with a ftrong hand, it being very difficult for the Spanish guarda coft to take these veffels; for they are not only ftout thips, with a number of guns, but are manned

with large crews of chofen feamen, deeply interefted in the fafety of the veffel and the fuccefs of the voyage. They have each a fhare in the cargo, of a value proportioned to the flation of the owner, fupplied by the merchants upon credit, and at a prime coft. This animates them with an uncommon courage, and they fight bravely, becaufe every man fights in defence of his own property. Befides this, there is a conitant intercourfe between this ifland and the Spanifh continent.

Curaffou has numerous warehoufes. always full of the commodities of Europe and the East-Indies. Here are all forts of woolen and linen cloth, laces, filks, ribbands, iron utenfils, naval and military ftores, brandy, the fpices of the Moluccas, and the calicoes of India, white and painted. Hither the Dutch West-India which is also their African Company, annually bring three or four cargoes of flaves; and to this mart the Spaniards themfelves come in finall veffels, and carry off not only the beft of the negroes, at a very high price, but great quantities of all the above forts of goods ; and the feller has this advantage, that the refuse of warehouses and mercers' fhops, and every thing that is grown unfafhionable and unfaleable in Europe, go off here extremely well; every thing being fufficiently recommended by its being European. The Spaniards pay in gold or filver, coined or in bars, cocoa, vanilla, jefuits bark, cochineal, and other valuable commodities.

The trade of Curaffou, even in times of peace, is faid to be annually worth to the Dutch, no lefs than f. 500,000. but in time of war the profit is ftill greater, for then it becomes the common emporium of the Weft-Indies ; it affords a retreat to thips of all nations. and at the fame time refuses none of them arms and ammunition to deftroy one another. The intercourfe with Spain being then interrupted, the Spanith colonies have fearcely any other market from whence they can be well fupplied either with flaves or goods. The French come hither to buy the beef, pork, corn, flour, and lumber, which are brought from the continent of N. America, or exported from Ireland; fo that, whether in peace or in war, the trade of this island flourishes extremely.

extremely. The Dutch took this island from the Spaniards in 1632.

CURIACO, a bay in Terra Firma, S. America, on the North Sea.

CURRITUCK Co. is fituated on the fea coaft of Edenton diffrict, N. Carolina, and forms the N. E. corner of the ftate; being bounded E. by Currituck found, N by the flate of Virginia, S. by Albemarle found, and W. by Camden co.; containing 5219 inhabitants, of whom 1103 are flaves. Difmal fwamp lies in this county, on the S. fide of Albemarle found, and is now fuppofed to contain one of the molt valuable rice eftates in America. In the midft of this Difmal, which contains upwards of 350,000 acres, is a lake of about 11 miles long and 7 miles broad. A navigable canal, 20 feet wide and 51 miles long, connects the waters of the lake with the head of Skuppernong river. About 500 yards from the lake, the proprietors have erected feveral faw mills: and as the water of the lake is higher than the banks of the canal, the company can at any time lay under water about 10,000 acres of rich fwamp, which proves admirably fitted for rice. For an account of the other Difmal, fee Great Difmal.

CURRITUCK, or Caratunk, a townfhip in the diffrict of Maine, 28 miles above Norridgewalk. In 1792 this was the uppermoft fettlement on Kennebeck river, and then confifted of about 20 families.

Cusco, the ancient capital of the Peruvian empire, in S. America, is fituated in the mountainous country of Peru, in 12. 25. S. lat. and 70. W. long. and has long been on the decline. It is yet a very confiderable place, having about 20,000 inhabitants. This famous city was founded by the first Ynca, or Inca Mango, as the feat and capital of his empire. The Spaniards, under Don Francisco Pizarro, entered and took poffeffion of it in the year 1534. On a mountain contiguous to the N. part of the city, are the ruins of the famous fort and Palace of the Yncas, the ftones of which are of an enormous magnitude. Three fourths of the inhabitants are Indians, who are very industrious in manufacturing baize, cotton and leather. They have also here, as well as at Quito, a take for painting; fome of their performances have been admired

CALLY GARGING TOL

even in Italy, and are difperfed all over South-America.

wax.

Fronti

in Nev

of Yu

fituated

leagues

town i

See In.

the N.

branch

about.

Broad

Philad

thire (

field of

habita

to Al

was in

miles '

35 the

New-I

was in

14 inh

of Con

opposit

coln co

cumfei

in Lin

Booth

lately

over it

N. E.

8. W.

6. 15.

rolina.

and fo

a boat

burder

to Hal

fax, ui

Wade

from

difcha

above

5113

DA

DA.

DAI

DAI

DAI

DAI

Cri

\$7.

Cu

Cu

CUSCOWILLA, in East-Florida, is the capital of the Aluchua tribe of Indians, and stands in the most pleasant fituation that could be defired in an inland country; upon a high, fwelling ridge of fand hills, within 300 or 400 yards of a large and beautiful lake, abounding with fifth and fowl. The lake is terminated on one fide by extensive forefts, confifting of orange groves, overtopped with grand magnolias, palms, poplar, tilia, live-oaks, &c.; on the other fide by extensive green plains and meadows. The town confits of go habitations, each of which confifts of z houses, nearly of the same fize, large and convenient, and covered clofe with the bark of the cypress tree. Each has a little garden spot, containing corn, beans, tobacco, and other vegetables. In the great Alachua favannah, about 2 miles diftant, is an inclosed plantation, which is worked and tended by the whole community, yet every family has its particular part. Each family gathers and deposits in its granary its proper thare, fetting apart a fmall contribution for the public granary, which flands in the midft of the plantation.

CUSHAI, a finall river which empties into Albemarle found, between Chowan and the Roanoke, in North Carolina.

CUSHETUNK Mountains, in Hunterdon co. New-Jerfey.

CUSHING, a township in Lincoln co. district of Maine, separated from Warren and Thomaston by St. George's R. It was incorporated in 1789, contains 942 inhabitants, and lies 216 miles W. by N. of Boston.

CUSSENS, a fmall R. in Cumberland co. Maine, which runs a S. E. courfe to Cafco-bay, between the towns of Freeport and North-Yarmouth.

CUSSEWAGA, a fettlement in Pennfylvania.

CUSSITAH, an Indian town in the weftern part of Georgia, 12 miles above the Broken Arrow, on Chattahoofee river.

CUTTS Island, a finall island on the coast of York co. Maine. See Neddock river, Cape.

CUYA, or Cutio, a province of Chili, in S. America, and in the government of Santa Cruz in the Sierra. The principal commodities are honey and wax.

wax. The chief town is St. John de Frontiera.

CUZCATLAN. See St. Sebastian R. in New-Spain.

he

s, a-

nd ge

la

d-

ke

ve

¢4

s,

he

ıd

50

2

ge

th

as

n,

s.

2

n,

he

as

h-

er

n

in

es

an

a. r-

0.

ir...

R.

ns

v.

nd

fe

of

n-

he

ve

lee

he

ck

li,

he

nd

ix.

CUZUMEL, an ifland in the province of Yucatan, and audience of Mexico, fituated in the bay of Honduras; 15 leagues long and 5 broad; its principal town is Santa Cruz. N. lat. 19. long. 87.

CYPRUS Swamp, in Delaware state. See Indian river.

delinité santiens di lana dé sante anné

DAGSBOROUGH, a post town in Suffex co. Delaware, fituated on the N. W. bank of Peper's creek, a branch of Indian river, and contains about 40 houses. It is 19 miles from Broad hill, or Clowe's and 127 S. from Philadelphia.

DALTON, a fine townfhip in Berkfhire co. Maffachufetts, having Pittffield on the W. and contains 554 inhabitants. The ftage road from Bofton to Albany runs through it. Dalton was incorporated in 1784, and lies 135 miles W. by N. of Bofton, and about 35 the fame courfe, from Northampton. DALTON, a townfhip in Grafton co. New-Hampthire, firft called Apthorpe, was incorporated in 1784, and has only 14 inhabitants. It lies on the E. bank of Connecticut R. at the 15 mile falls, opposite Concord, in Effex co. Vermont.

DAMERISCOTTA Great Bay, in Lincoln co. Maine, is about 4 miles in circumference.

DAMERISCOTTA R. a finall fiream in Lincoln co. Maine, which falls into Booth-bay. A company has been lately incorporated to build a bridge over it.

DAMPIER's Straits, are between the N. E. point of New Guinea, and the S. W. point of New-Britain. S. lat. 6, 15. E. long. from Paris, 146.

DAN, a confiderable river of N. Carolina, which unites with the Staunton, and forms the Roanoke. In May, 1795, a boat 53 feet long, and about 7 tons burden, pafied from Upper Saura town to Halifax, about 200 miles above Halifax, under the direction of Mr. Jeremiah Wade. She brought about 9 hhds. from the above place, 6 of which the difcharged at St. Taminy, 40 miles above Halifax; to which place the R.

has been cleared by the donations of individuals. From St. Taminy to Halifax, the brought about 5000 wei through the falls, which hitherto had been deemed impaffable. Mr Wade thinks, fafe navigation for boats of a larger burden may be made at a imall expence. The famous Burfted hill ftands on the bank of the Dan, in Virginia, near the borders of N. Carolina. It appears to have been an ancient volcano. There are large rocks of the lava, or melted matter, from 1000 to 1500 weight, lying on the fummit of the hill. The crater is partly filled, and covered with large trees.

DANBURY, a post town in the co. of Fairfield, in Connectiout. It was fettled in 1687, and the compact part of the town contains 2 churches, a courthoufe, and about 60 dwelling-houfes. On its fmall ftreams are iron works, and feveral mills. Mr. Lazarus Beach prefented to the Muleum in New-York city, a quire of paper, made of the afbeftos, at his paper mill in Danbury, March, 1792, which the hotteft fire would not confume. It lies about 70 miles N. E. of New-York city, and 33 N. W. by. W. of New-Haven. This town, with a large quantity of military ftores, was burnt by the British on the 26th of April, 1777.

DANBY, a township in Rutland co. Vermont, E. of Pawlet, and contains 1206 inhabitants. It lies about 32 miles N. of Bennington.

DANIEL, Port, on the northern fide of Chaleur Bay, is a commodious harbour for veficies of a confiderable draught of water. It affords a cod fifthery, and is about 9 leagues from Plato, weftnorth-weft of Cape Defpair.

DANISH AMERICA. In the Weff-Indies the Danes paffers the islands of St. Thomas, St. Croix, or Santa Cruz, and St. John's; which are described under their respective names.

The Danifh policy, in refpect to their iflands, is wife, and deferving of imitation. Thefe iflands were ill managed, and of little confequence to the Danes, whilf in the hands of an exclusive company; but fince the late king bought up the company's flock, and laid the trade open, the iflands have been greatly improved. Santa Cruz, a perfect defert a few years fince, has been brought to a high flate of cultivation, producing I

annually between 30 and 40,000 hhds. of fugar, of upwards of 13 cwt. each, nd contains 3000 whites and 30,000 negroes. By an edict of the Danifh king, no flaves are to be imported into his iflands after the year 1802; till then, their importation is encouraged by a law operating as a bounty. Many of the inhabitants of Greenland, and negroes of the Danifh W. India iflands, have embraced Chriftianity under the Moravian miffionaries, who are unwearied in their humane exertions to promote the happine's of those who can befow no earthly reward.

DANVERS, a township in Effex co. Maffachufetts, adjoining Salem on the N. W. in which it was formerly comprehended by the name of Salem vilage. It confifts of two parifhes, and contains 2425 inhabitants, and was incorporated in 1757. The most confiderable and compact fettlement in it, is formed by a continuation of the principal ftreet of Salem, which extends more than two miles toward the country, having many work thops of mechanics, and feveral for retailing goods. Large quantities of bricks and coarfe earthen ware are manufactured here. Another pleafant and thriving fettlement is at the head of Beverly R. called New-Mills; where a few veffels are built and owned. The town of Danvers receives an annual compensation of f. 10 from the propri-etors of Eslex bridge, for the obstruction of the river.

DANVILLE, a thriving post town in Mercer co. and formerly the metropolis of Kentucky, pleafantly fituated in a large, fertile plain, on the S. W. fide of Dick's R. 35 miles S. S. W. of Lexington. It confitts of about co houses, and a Prefbyterian church. From Leefburg to Danville, the country, for the first 20 miles, is of an inferior rate for lands in this country; but round Lex-ington, and from Leefburg to Lexing. ton and Boonfborough, is the richeft land in the country. It is 40 miles S. by E. of Frankfort, 83 from Louifville, 201 from Hawkins in Tenneffee, and \$30 from Philadelphia. N. lat. 37. 30. W. long. 85. 30.

DANVILLE, a very thriving townfhip in Caledonia co. Vermont. It was a wildernets, without fo much as a fingle family, a few years ago, and now con-

in march

DAR

tains 574 inhabitants. It lies 8 miles N. W. of Barnet.

DARBY, a finall town in Delaware co. Pennfylvania, on the E. fide of Darby creek. It contains about 50 houfes, and a Quaker meeting-houfe, and lies 7 miles S. W. by W. of Philadelphia. There are two townfhips of this name, in the county, called Upper and Lower, from their relative fituation.

DARIEN, or Terra Firma Proper, is the northern division of Terra Firma or Caftile del Oro. It is a narrow ifthmus, that, properly fpeaking, joins N. and S. America together; but is generally reckoned as part of the latter. It is bounded on the N. by the gulf of Mexico; on the S. by the South fea; on the E. by the river or Gulf of Darien, and on the W. by another part of the South Sea and the province of Veragua. It lies in the form of a bow or crefcent, about the great bay of Panama, in the South-Sea, and is 300 miles in length. Its breadth has generally been reckoned 60 miles from N. to S.; but it is only 37 miles broad from Porto Bello to Panama, the two chief towns of the province. The former lies in N. lat. 9. 34. 35. W. long. 8r. 52. 3 the latter in N. lat 8. 57. 48. W. long. 82. This province is not the richeft, but is of the greateft importance to Spain, and has been the fcene of more actions than any other in America. The wealth of Peru is brought hither, and from hence exported to Europe. Few of the rivers in this country are navigable, having thoals at their mouths. Some of them bring down gold duft; and on the coaft are valuable pearl fifheries. Neither of the oceans fall in at once upon the fhore, but are intercepted by a great many valuable iflands, that lie icattered along the coaft. The islands in the bay of Panama are numerous : in the gulf of Darien are three of con-fiderable fize, viz. Golden Island ; another, the largeft of the three, and the illand of Pines; befides fmaller ones. The narroweft part of the ifthmus is called fometimes the ifthmus of Panama. The country about it is made up of low fickly vallies, and mountains of fuch flupendous height, that they feem to be placed by nature as eternal bar-riers between the Atlantic and Pacific oceans, which here approach fo near each other, that, from these mountains, the

the wa at the very fi tains | but by ing th fmall 1 ocean, two fe diggin countr miles, faved. of fue fay; t length wear ifthmu tween Gulf into a round ble thi The of the that th provin the poo ed to f and of parts perhap greate iector dition Pateri taffrop ill-fate ed, in John] memoi The f great 6.900 fcribe Engli Hamb ayer, the c Willi Spanil left S ment tion, Engla fine, furviv and r of thi Diff. S.S.

....

the waters of both can be plainly feen at the fame time, and feemingly at a very finall diftance. The rocky mountains here forbid the idea of a canal; but by going into 12. N. lat. and joining the head of Nicaragua lake to a fmall river, which runs into the Pacific ocean, a communication between the two feas becomes practicable; and by digging 30 miles through a level, low country, a tedious navigation, of 10,000 miles, round Cape Horn, might be faved. What would be the confequences of fuch a junction, is not eafy to fay; but it is very probable, that, in a length of years, fuch a junction would wear away the earthy particles of the ifthmus, and form a broad strait between the oceans; in which cafe, the Gulf stream would ceafe, being turned into a different channel; and a voyage round the world become an inconfiderable thing.

are ar-cs, ies ia, ne, er,

is or

ns, nd

lly is xi-

on

in the ea, ith

les les the The

the in is

ers

em the ici-ici-a lie

nds is: on-d; the

es.

is

na-

up

of

em ar-

ific

ear

ns,

the

The Scotch nation had fo just an idea of the great importance of this ifthmus, that they got poficifion of a part of the province in 1699, and though among the pooreft nations in Europe, attempted to form an eftablishment more useful and of more real importance, all the parts of the plan confidered, than had perhaps ever been undertaken by the greatest nation in the world. The projector and leader of the Darien expedition was a clergymen, of the name of Paterion. The rife, progress, and cataffrophe, of this well-conceived, but ill-fated undertaking; has been defcribed, in a very interetting manner, by Sir John Dalrymple, in the 20th vol. of his memoirs of Great-Britain and Ireland. The fund indicribed, for carrying this great project into effect, amounted to f. 900,000 fterling, viz. f. 400,000 fubfcribed by the Scotch, 300,000 by the English, and 200,000 by the Dutch and Hamburghers. The Darien council aver, in their papers, that the right of the company was debated before King William III. in the prefence of the Spanish ambaffador, before the colony left Scotland; and while the eftablifument of the colony had been in agitation, Spain had made no complaints to England or Scotland against it. In fine, of 1200 brave men, only 30 ever furvived war, thipwreck, and difeate, and returned to Scotland. The ruin of this unhappy colony happened thro' 131

the fhameful partiality of William III.

and the jealoufy of the English nation. The strong country, where the co-lony fettled and built their forts, was a territory never possible by the Spaniards, and inhabited by a people continually at war with them. It was at a place called Acta, in the mouth of the river Darien : having a capacious and strongly situated harbour. The country they called New-Caledonia. It was about mid-way between Porto Bello and Carthagena; but near 50 leagues diftant from either.

DARIEN, GULF OF, runs S. eafterly into Terra Firma. On the eaftern fide of its mouth, is the town of St. Sebaftian.

DARIEN, a town in Liberty co. Georgia, by the heights of which glides the N. channel of Alatamaha R. about 20 miles above Sapelo I. and 10 below Fort Barrington. It lies 47 miles S. S. W. of Savannah. N. lat. 31. 23. W. long. 80. 14.

DARLINGTON, the most fouthern county of Cheraw's diffrict, S. Carolina; bounded S. and S. W. by Lynch's creek. It is about 35 miles long, and 21 broad.

DARTMOUTH-COLLEGE. See Hanover.

DARTMOUTH, a town in Grafton co. New-Hampfhire, north west of the foot of the White Mountains; 33 miles N. E. of Haverhill, New Hampthire, and 87 N. westerly of Portfmouth. It contains III inhabitants, and was incorporated in 1772.

DARTMOUTH, a thriving fea-port town in Briftol co. Maffachuletts, fituated on the W. fide of Accushnet R. 70 miles foutherly of Bofton. It was incorporated in 1664, and contains 2499 inhabitants. N. lat. 41. 37. W. long. 70. 52.

DARTMOUTH, a town in Elbert co. Georgia, fituated on the peninfula formed by the confluence of Broad and Savannah rivers, 2 miles from Fort James Dartmouth, which is a mile below Charlotte Fort, which fee. The town and fort derive their names from James, earl of Dartmouth, whole influence in the British councils obtained from the king, a grant and powers to the Indian trading company in Georgia to treat with the Creeks, for the territory called the New Purchafe, ceded

in difcharge of debts due to the traders. This tract contains about 2,000,000 of acres, lying upon the head of the Great Ogechee, between the banks of the Savanhah and Alatamaha, touching on the Oconee, including all the waters of Broad and Little rivers. This territory comprehends a body of excellent, fertile land, well watered by innumerable rivers, creeks and brooks.

DAUPHIN, FORT, a jurifdiction, fort and fea-port town in the N. part of the ifland of St. Domingo. This division contains 5 parifhes. Its exports from Jan. 1, 1789 to Dec. 31 of the fame year, confifted of fugar, coffee, cotton, indigo, fpirits, molaffes, and tanned hides, in value 35,252 dolls. 13 cents. The town of Fort of Dauphin is remarkable for a fountain conftructed by the orders of M. de Marbois, which coft 10,678 dollars. N. lat. 19. 41.

Coft 10,678 dollars. N. lat. 19. 4x. DAUPHIN, FORT. See Ha Braga. DAUPHIN, an ifland about 10 miles long, in the mouth of Mobile bay, 5 miles from Maffacre I. with a fhoal all the way between them. Thefe are fuppoled formerly to have been but one, and went by the general name of Maffacre, fo called by Monf. d'Ibberville, from a large heap of human bones found thereon at his landing. It was after-wards called Dauphin I. The W. end, a diftance of between 3 and 4 miles, is a narrow flip of land with fome dead trees; the reft is covered with thick pines, which come close to the water's edge on the E. fide, forming a large bluff. There is the remains of an old French post on the S. fide of the island, and of fome old houfes of the natives. N. lat. 30. 10. W. long. 88. 7.

DAUPHIN, a fort in the island of Gape Breton, round which the French had their principal fettlement, before they built Louisburg.

DAUPHIN Co. in Penniylvania, was formerly contained in that of Lancaster, until erected into a separate county, March 4, 1785. Its form is triangular; its contents 586,400 acres, and is surrounded by the counties of Missin, Cumberland, York, Berks, and Northumberland. It is divided into 9 townships, the chief of which is Harrifburg; the number of its inhabitants x8,177. Nearly one half of the land is under cultivation; but the northern part is very rough and mountainous.

DAX

In feveral of the mountains is found : abundance of iron ore of the first quality; a furnace and forge have been erected which carry on brifkly the manufacture of pig, bar iron, &c. The first fettlers here were Irish emigrants, who were afterwards joined by a number of Germans. In the town of Derry, on the bank of Swatara creek is a remarkable cavern; its entrance is under a high bank, and nearly 20 feet wide, and about 8 or 10 feet in height. It defcends gradually nearly to a level with the creek. Its apartments are numerous, of different fizes, and adorned with stalactites curiously diversified in fize and colour. Near the foot of Blue Mountain is a mineral fpring, much celebrated by the country people for its efficacy in removing rheumatic and other diforders.

DAVIDSON, a county in Mero diftrict in Tenneffee, bounded N. by the ftate of Kentucky, E. by Sumner, and S. by the Indian territory. Its chieftown Nafhville, lies on the great bend of Cumberland river.

DAVID'S Town, on the Affanpink R. Hunterdon co. N. Jerfey, 10 or 72 miles from Trenton. Between thefe towns a boat navigation has lately been opened by means of three locks, erected at a confiderable expense. It is proposed to render this river boatable 10 or 15 miles further, in which diftance, no locks will be neceffary.

DAVID'S ISLAND, ST. a parish in the Bermuda Islands, which fee.

DAVIS'S Strait, a narrow fea, lying between the N. main of America, and the weftern coaft of Greenland; running N. W. from Cape Farewell, lat. 60 N. to Baffin's Bay in 80. It had its name from Mr. John Davis, who firft difcovered it. It extends to W. long. 75. where it communicates with Baffin's Bay, which lies to the N. of this firait, and of the North Main, or James's Ifland. See Baffin's Bay.

DAWFUSKEE, an ifland on the coaft of S. Carolina, which forms the N. E. fide of the entrance of Savannah R. and S. W. fide of the entrance of Broad R. and admits of an inland communication between the two rivers.

DAXABON, Dajabon, or Dababon, which the French call Laxabon, is a town and fettlement of Spaniards on the line between the French and Spanifudivisions

divi It v whe the terri trem and river cont town bank leag w, long D nia. abou appe fione repea and D ing t gift Unit conc ville D ſmal end a of C D New John Spea D tal o by tl fettle thip mile conta build an er It is of 1 Area year ling fpace joins Milt ed h card D fey, bury num in fu

divisions of the island of St. Domingo. It was fettled to prevent finuggling, when the Spaniards had their finare of the island. It is bounded E. by the territory of St. Yago, N. by the extremity of the bed of the Grent-Yaqui, and the bay of Mancenilla, W. by the river and little island of Maffacre. It contains about 4000 perfons. The town flands 400 fathoms from the E. bank of Maffacre river, more than So leagues N. W. of St. Domingo, and 28 W. of St. Yago. N. lat. 19. 32. W. long. from Paris 74. 9.

18.

n-

11'-1'2

n-

set

it. vel

U-

ed

in

ue

ch

OF

nd

if-

he

nd

ief

nd

R.

cs

118

1-

at

:d

15

10

ne

ig id

1-

t.

ts

ft

5.8

t,

18

A

5.

d

2

R

π,

e-

he

18

DAY'S Point, on James R. in Virginia. There is a plantation here of about a 1000 acres, which at a diftance appears as if covered with fnow; occafioned by a bed of clam fhells, which by repeated ploughing have become fine, and mixed with the earth.

DE BOIS BLANC, an island belonging to the N.W. territory, a voluntary gift of the Chipeway nation to the United States, at the treaty of peace concluded by gen. Wayne, at Greenville, in 1795.

DEAD CHEST Island, one of the fmaller Virgin ifles, fituated near the E. end of Peter's ifland, and W. of that of Cooper's.

DEADMAN'S Bay, on the E. fide of Newfoundland ifland, lies S. of St. John's harbour, and N. W. of Cape Spear.

DEDHAM, a post town, and the capital of Norfolk co. Maffachufetts, called by the aboriginals Tiot, and by the first fettlers, Clapboard Trees. The townthip was incorporated in 1637, is 7 miles in length, and 6 in breadth, and contains 1659 inhabitants. Its public buildings are 3 congregational churches, an epitcopal church, and a court houfe. It is pleafantly fituated, It miles S. W. of Bofton, on Charles R. A finall ftream furnishes water most part of the year to 2 grift mills, 2 faw mills, 2 fulling mills and a leather mill, all in the fpace of three quarters of a mile, and joins Neponfit R. on the borders of Milton. A wire manufactory is erected here, for the use of the fish-hock and card manufacturers in Bolton.

DEAL, in Monmouth co. New-Jerfey, about 7 miles fouthward of Shrewfbury. This place is the refort of great numbers of people from Philadelphia, in fummer, for health and pleafure. DEE

DEET Spring, in the flate of New-York, is a curiofity, and lies about 9 miles S. of Oneida lake, at the head of Chittenengo creek, and so miles S. W: of Oneida caftle.

DEEP R. in North-Carolina, rifes in Wachovia, and unites with Haw R. and forms the N. W. branch of Cape Fear river.

DEERFIELD, a township in Cumberland co. New Jersey.

DEERFIELD R. or the Pocomtic, rifes in Stratton, in Bennington co. Vermont, and after receiving a number of fireama from the adjoining towns, unite on entering Maffachuletts; thence winding in an E. direction, it receives North R. and empties into Connecticut R. between the townships of Greenfield and Deerfield, where it is about 15 rods wide. Excellent tracts of meadow ground lie on its banks.

DEERFIELD, a very pleafant town in Hampfhire co. Maffachufetts, on the W. bank of Connecticut R. from which the compact part of the town is feparated by a chain of high hills. It is in the midft of a fertile country, and has a fmall inland trade. The compact part of the town has from 60 to 100 houfes, principally on one ftreet, and a handfome congregational church. It was incorporated in 1681, and contains 1330 inhabitants; 17 miles N. of Northampton, and 109 N. by W. of Bofton.

The houfe in which the Rev. Mr. Williams and his family were captivated by the Indians in the early fettlement of this town, is ftill flanding, and the hole in the door, cut by the Indians with their hatchets, is ftill flewn as a curiofity. An academy, incorporated in 1797, by the name of "The Deerfield Academy," is eftablished in this town.

DEERFIELD, a well fettled agricultural town in Rockingham co. New-Hampfhire, and was a part of the township of Nottingham, 19 miles S. E. of Concord, and 35 N. W. of Portfmouth. It contains 1619 inhabitants, and was incorporated in 1766.

DEER Ifland, an ifland and townfhip in Penobicot bay, in Hancock co. diffrict of Maine, containing 682 inhabitants. It was incorporated in 1789, and lies 305 miles N. E. of Boston.

I 3

DEER,

DEER, an ifland in Paffamaquoddy

DEERING, a township in Hillshorough co. New-Hampfhire, incorporat-ed in 1774. It contains 928 inhabi-tants, and lies 15 miles S. W. of Con-cord, and 54 miles W. of Portfmouth.

DEFIANCE, a fort in the N. weftern territory, fituated on the point of land formed by the confluence of the rivers of Au Glaize, and the Miami of the lake, nearly half way between Fort Wayne on the Miami, and lake Erie. N. lat. 41. 41. W. long. 84. 43.

DE LA MARCH, a western water of Illinois R. in the N. W. territory. It is 30 yards wide, and navigable 8 or 9 miles.

DELAMATTENOOS, an Indian tribe, in alliance with the Delawares

DE LA WAR, a town in King William's co. Virginia, fituated on the broad peninfula formed by the confluence of the Pamunky and Mattapony. The united fiream thence affumes the name of York R. It lies 20 miles N. by W.

of Williamfburg in N. lat. 37. 31. W. DELAWARE Bay and River. The bay is 60 miles long, from the cape to the entrance of the river, at Bombay Hook ; and occupies a space of about 630,000 acres; and is fo wide in fome parts, as that a ship, in the middle of it, cannot be feen from the land. opens into the Atlantic N. W. and S. E, between Cape Henlopen on the right, and Cape May on the left. These capes are 18 or 20 miles apart.

Delaware R. was called Chihohocki by the aboriginals, and in an old Nurenberg map is named Zuydt R. It rifes by two principal branches in New-York ftate. The northernmost of which, called the Mohawk's or Cookqugo branch, rifes in lake Uftayantho, lat. 42. 25. and takes a S. W. courfe, and turning S. eaftwardly, it crofies the Pennfylvania line in lat. 42.; about 7 miles from thence, it receives the Popachton branch from the N. E. which rifes in the Kaats Kill mountains. Thence it runs fouthwardly, until it ftrikes the N. W. corner of New-Jerfey, in lat. 41. 24.; and then paffes off to fea through Delaware bay; having New-Jerfey E. and Penntylvania and Delaware W. The bay and river are navigable from the fea up to the great or lower falls at Trenton, 155 flort courie, foft banks, numerous

miles ; and are accommodated with buoys and piers for the direction and fafety of hips. A 74 gun fhip may go up to Philadelphia, 120 miles by the fhip channel from the fea. The diffance acrofs the land, in a S. E. courfe, to New-Jerfey coaft, is but 60 miles. Sloops go 35 miles above Philadelphia, to Trenton falls; boats that carry 8 or 9 tons, 100 miles farther, and Indian canoes 150 miles, except feveral finall fails or portages. For other particulars relating to this river, See Henlopen, May, Bombay-Hook, Reedy I. Schuylkill, Lebigb, &cc.

It is in contemplation to connect the waters of Chefapeak bay with those of Delaware R. by 4 different canals, viz. Elk R. with Christiana creek-Broad creek, another branch with Red Lion creek-Bohemia, a third branch of the Elk, with Apoquinemy creek; and Chefter R. wi h Duck creek.

DELAWARE, a small river of East Florida. See Charlotte Haven.

DELAWARE, one of the United States of N. America, is fituated between 18. 29. 30. and 19. 54. N. lat. and between 75. and 75. 48. W. long. being in length 92 miles, and in breadth 24 miles-containing 2000 fquare miles: or 1,200,000 acres. It is bounded E. by the river and bay of the fame name, and the Atlantic ocean; on the S. by a line from Fenewick's ifland, in N. lat. 38.29. 30. drawn W. till it interfects what is commonly called the tangent line, dividing it from the state of Maryland; on the W. by the faid tangent line, paffing northward up the peninfula, till it touches the weftern part of the territorial circle; and thence on the N. by the faid circle, defcribed with a radius of 12 miles about the town of Newcastle, which divides This this state from Pennsylvania. state derived its name from Lord De-La-War, who was inftrumental in eftablishing the first fettlement of Virginia. It is divided into 3 counties, Newcastle, Kent and Suffex; whole chief towns are Wilmington, Newcaftle, Dover, and Lewes. Dover is the feat of government. The number of inhabitants in 1790, was 59,094, of whom 887 were flaves.

The eaftern fide of the flate is indented with a large number of creeks, or imall rivers, which generally have a thoals,

fhoals, five ma and bay and we head w Nantic and Bo fapeak ble 20 veffels (The

parts o cepted, level. water, overfpr land, re pofes o the her fpine, runs th clined t It is d part of able ch waters the eaf weft to thrubs fwamps the hig

Dela ftate. country United the diff in whic ful pro and ple the Del miles in rally a ber, an purpofe to the foil is quality The

very fa cepting county ftate is The he comma dywine fcendin the low as alm In the

fhoals, and are fkirted with very extenfive marfhes, and empty into the river and bay of Delaware. In the fouthern and weftern parts of this flate, fpring the head waters of Pocomoke, Wicomico, Nanticoke, Choptank, Chefter, Saffafras and Bohemia rivers, all falling into Chefapeak bay; fome of them are navigable 20 or 30 miles into the country, for veffels of 50 or 60 tons.

a, 8

1-

al

er

I.

he

of

z.

n

he

nd

ıft

es

8.

en th

n-

00

nd

ic

e-

vn

ly

m

rd

-l-

nd

e-

ut

es

nis

a-

h-

It

le,

ns

nd

n-

in

re

lt-i

or

a

us

ls,

The ftate of Delaware, the upper parts of the county of Newcaftle excepted, is, to fpeak generally, low and level. Large quantities of ftagnant water, at particular feafons of the year, overfpreading a great proportion of the land, render it equally unfit for the purpofes of agriculture, and injurious to the health of the inhabitants. The fpine, or higheft ridge of the peninfula, runs through the ftate of Delaware, inclined to the eaftern or Delaware fide. It is defignated in Suffex, Kent, and part of Newcaftle county, by a remarkable chain of fwamps, from which the waters defcend on each fide, paffing on the eaft to the Delaware, and on the weft to the Chefapeak. Many of the fnrubs and plants, growing in thefe fwamps, are fimilar to those found on the higheft mountains.

Delaware is chiefly an agricultural ftate. It includes a very fertile tract of country; and fearcely any part of the United States is better adapted to the different purpoles of agriculture, or in which a great variety of the most ufeful productions can be fo conveniently and plentifully reared. The foil along the Delaware river, and from 8 to 10 miles into the interior country, is generally a rich clay, producing large timber, and well adapted to the various purpoles of agriculture. From thence to the fwanps above mentioned, the foil is light, fandy and of an inferior quality.

The general afpect of the country is very favourable for cultivation. Excepting fome of the upper parts of the county of Neweaftle, the furface of the ftate is very little broken or irregular. The heights of Chriftiana are lofty and commanding; fome of the hills of Brandywine are rough and ftony; but defcending from thefe, and a few others, the lower country is fo little diverified, as almost to form one extended plain. In the county of Newcaftle the foil confifts of a ftrong clay; in Kent, there is a confiderable mixture of fand; and in-Suffex, the quantity of fand altogether predominates. Wheat is the ftaple of this ftate. It grows here in fuch perfection as not only to be particularly fought by the manufacturers of flour throughout the Union, but alfo to be diffinguifhed and preferred, for its fuperior qualities, in foreign markets. This wheat poffeffes an uncommon foftnefs and whitenefs, very favourable to the manufactures of fuperfine flour, and in other refpects far exceeds the hard and finty grains raifed in general on the higher lands. Befides wheat, this ftategenerally produces plentiful crops of Indian corn, barly, rye, oats, flax, buckwheat, and potatoes. It abounds in natural and artificial meadows, containing a large variety of graffes. Hemp, cotton, and filk, if properly attended to, doubtlefs would flourifh very well. The county of Suffex, befides pro-

The county of Suffex, befides producing a confiderable quantity of grain, particularly of Indian corn, poffeffes excellent grazing lands. This county alfo exports very large quantities of lumber, obtained chiefly from an extensive fwamp, called the Indian River or Cyprefs Swamp, lying partly within this ftate, and partly in the ftate of Maryland. This morafs extends fix miles from eaft to weft, and hearly twelve from north to fouth, including an area of nearly fifty thousand acres of land. The whole of this fwamp is a high and level bafon, very wet, though undoubtedly the higheft land between the fea and the bay, whence the Pokomoke defcends on one fide, and Indian River and St. Martin's on the other. This fwamp contains a great variety of plants, trees wild beafts, birds and reptiles.

Almost the whole of the foreign exports of Delaware are from Wilmington : the trade from this state to Philadelphia is great, being the principal fource whence that city draws its ftaple commodity. No lefs than 265,000 barrels of flour, 300,000 buthels of wheat, 170,000 bushels of Indian corn, befides barley, oats, flax-feed, paper, flit iron, inuff, falted provisions, &c. &c. to a very confiderable amount, are annually fent from the waters of the Delaware ftate; of which the Christiana is by far the most productive, and probably many times as much to as any other creek or 14 river

river of like magnitude in the Union-a45,000 barrels of flour, and other ar-ticles, to the amount of 80,000 dollars more, being exported from this creek ; of which, to the value of 550,000 dollars, are manufactured on its northern bank, within two or three miles of the navigation. Among other branches of ine naviga-try exercifed in and near Wilmington, are, a cotton manufactory, (lately how-ever burnt); a bolting cloth manufac-tory has lately been established by an ingenions European; both of which have promifed fair to be a lafting advantage to the country. In the county of New-caftle are feveral fulling-mills, two fnuff-mills, one flitting-mill, four paper-mills, and fixty mills for grinding grain, all of which are turned by water. But though Wilmington and its neighbourhood are probably already the greatest feat of manufactures in the United States, yet they are capable of being much improved in this respect, as the country is hilly and abounds with running water; the Brandywine alone might, with a moderate expense, when compared with the object, be brought to the top of the hill upon which Wilmington is fituated, whereby a fall fufficient for forty mills, in addition to those already built, would be obtained. The heights near Wilmington afford a number of agreeable profpects; from fome of which may be feen the town, the adjacent meadows, and four adjoining states. No regular account of the births and burials has been kept, but the place is healthy. The number of children under fixteen, is probably equal to that of any town which is not more populous, and, according to an accurate account taken the year 1794, there were upwards of 160 perions above 60 years old. The legif-lature of this state, in 1796, passed an act to incorporate a bank in this town.

There is no college in this state. There is an academy at Newark, incorporated in 1769. The legislature, during their fession in January 1796, passed an act to create a fund for the establishment of schools throughout the state.

Wheat is the ftaple commodity of this ftate. This is manufactured into flour and exported in large quantities. The exports from the port of Wilmington, where a number of fquare rigged veffels are owned, for the year 1786, in the article of flour, was 20,783 barrels DEL

other

mills. mills 2000 t

fide of

fome o

depth

above with a been in

ried to It is

with with f

fucceed on bot

chines

Oliver

manua

now fi

means

use of

invent

the fh

the up fideral

in flo

packi

nual

in pro tranfp

the p

quire

the ca

mills fame

is ver

mill v

There

princi

gethe

loadit

bridg

view.

this

other

from

1791

ditto

ditto

ditto

ditto

ligio

terial

Epife

Meth

In

Be

nifh

superfine, 457 do. common, 256 do. middling, and 146 do. thip ftuff. The manufacture of flour is carried to a higher degree of perfection in this flate than in any other in the Union. Befides the well constructed mills on Red clay and White clay creeks, and other fireams in different parts of the flate, the cele-brated collection of mills at Brandywine merit a particular description. Here are to be feen, at one view, 12 merchant mills (befides a faw mill) which have double that number of pairs of ftones, all of fuperior dimensions, and excellent conftruction. These mills are 3 miles from the mouth of the creek onwhich they fland, half a mile from Wilmington, and 27 from Philadelphia, on the post road from the eastern to the fouthern states. They are called the Brandywine mills, from the stream on which they are crected. This ftream rifes near the Welch mountains in Pennfylvania, and after a winding course of 30 or 40 miles through falls, which furnish numerous feats (130 of which are already occupied) for every species of water works, empties into Christiana creek, near Wilmington. The quantity of wheat manufactured at these mills, annually, is not accurately afcertained. It is effimated, however, by the beft in-formed on the fubject, that these mills can grind 400,000 bufhels in a year, But although they are capable of manu-facturing this quantity yearly, yet from the difficulty of procuring a permanent fupply of grain, the inftability of the flour market and other circumftances, there are not commonly more than from about 290 to 300,000 bufhels of wheat and corn manufactured here annually. In the fall of 1789, and fpring of 1790, there were made at the Brandywine mills 50,000 barrels of fuperfine flour, 1354 do. of common, 400 do. middling, as many of fhip fluff, and 2000 do. corn meal. The quantity of wheat and corn ground, from which this flour, &c. was made, was 308,000 bufhels, equal to the export of those articles from the port of Philadelphia for the fame year.

Thefe mills give employ to about 200 perfons, viz. about 40 to rend the mills, from 50 to 70 coopers to make cafks for the flour, a fufficient number to man 12 floops of about 30 tons each, which are employed in the transportation of the wheat and flour, the reft in various other

zh.

han

the

and

ms

le-

dy-

on.

12

ich

of

and

are

on

711-

on

the

the

on ifes

fyl-

30

nifh

rea-

iter

ek,

an-

ills

ear,

nu-

om

the

ces,

om

leat

90,

/ine

ur,

ng,

orn

orn

was

the

t of

100

lls,

for

12

are

the

ous

her

It in-

of

other occupations connected with the mills. The navigation quite to thefe mills is fuch, that a vefiel carrying 1000 bufhels of wheat may be laid along fide of any of these mills; and beside fome of them the water is of fufficient depth to admit veffels of twice the above fize. The veffels are unloaded with aftonishing expedition. There have been inftances of 1000 bulhels being carried to the height of 4 ftories in 4 hours. It is frequently the cafe that veffels with 1000 buffels of wheat come up with flood tide, unlade and go away the fucceeding ebb with 300 barrels of flour on board. In confequence of the machines introduced by the ingenious Mr. Oliver Evans, three quarters of the manual labour before found neceflary is now infficient for every purpole. By means of these machines, when made use of in the full extent proposed by the inventor, the wheat will be received on the fhallop's deck-thence carried to the upper loft of the mill-and a confiderable portion of the fame returned in flour on the lower floor, ready for packing, without the affiftance of manual labour but in a very finall degree, in proportion to the hufiness done. The transportation of flour from the mills to the port of Wilmington, does not require half an hour; and it is frequently the cafe that a cargo is taken from the mills and delivered at Philadelphia the fame day. The fituation of these mills is very pleafant and healthful. The first mill was built here about 50 years fince. There is now a fmall town of 40 houfes, principally ftone and brick, which, together with the mills and the veffels loading and unloading befide them, furnish a charming prospect from the bridge, from whence they are all in full view.

Befides the wheat and flour trade, this flate exports lumber and various other articles. The amount of exports from the year ending September 30th, 1791, was 119,878 dollars, 93 cents ditto 1792, 133,972 dollars, 27 cents ditto 1793, 93,559 dollars, 45 cents ditto 1794, 207,985 dollars, 33 cents ditto 1795, 158,041 dollars, 21 cents. In this flate there is a variety of religious denominations. Of the Prefbyterian fect, there are 24 churches—of the Epifcopal 14—of the Baptift, 7—of the Methodifts, a confiderable number, ef-

pecially in the two lower counties of Kent and Suffex: the number of their churches is not exactly afcertained. Befides thefe there is a Swedish church at Wilmington, which is one of the oldest churches in the United States.

There are few minerals in this flate, except iron; large quantities of bog iron ore, very fit for caffings, are found in Suffex co. among the branches of Nanticoke R. Before the revolution this ore was worked to a great amount; but this bufinefs has fince declined. Wheat and lumber are the flaple commódities of this flate. The other articles of produce and manufacture, are Indian corn, barley, oats, flax-feed, falted provisions, paper, flit iron, fouff, &ce-

Settlements were made here by the Dutch about the year 1623, and by the Swedes about the year 1627. Their fettlements were comprehended in the grant to the duke of York; and William Penn united them to his government by purchafe. They were after, wards feparated, in fome measure, from Pennfylvania, and denominated th Three Lower Counties. They had their own affemblies, but the governor o Pennfylvania ufed to attend, as he did in his own proper government. At the late revolution, the three counties were erected into a lovereign ftate; and have ettablished a republican constitution.

DELAWARE Co. in Pennfylvania, in S. W. of Philadelphia co. on Delawar river. 'It is about 21 miles in length, and 15 in breadth, containing 115,200 acres, and fubdivided into 19 township the chief of which is Chefter. The number of inhabitants is 9,483. The lands bordering on the Delaware are low, and afford excellent meadow and pasturage; and are guarded from inundations by mounds of earth or dykes, which are fometimes broken down in extraordinary freshes in the R. If this happens before cutting the grafs, the crop of hay is-loft for that feafon, and the reparation of the breaches is expenfive to the proprietors. Great numbers of cattle are brought here from the western parts of Virginia, and North-Carolina, to be fattened for fupplying the Philadelphia market.

DELAWARE, a new county in the flate of New-York, on the head waters of Delaware river, taken from Otfego county.

DELAWARE,

DELAWARE, a township in Northpton co. Pennfylvania.

198:

DELAWARES, an Indian nation formerly numerous and powerful, and who poffeffed part of Pennfylvania, New-Jerfey and New-York. This name was doubtless given them by the Europeans; for they call themfelves Lennilenape, that is, Indian men; or Woapanachky, which fignifies a people living towards the rifing fun. They now refide about half way between lake Erie and Ohio R. They are an ingenious and intelligent people; and like the Six Nations, are celebrated for their courage, peaceable difpolition, and powerful alliances. Almost all the neighbouring nations are in league with them, efpecially the Mahikan, Shawanves, Cherokees, Twichtwees, Wawiachtanos, Kikapus, Moshkos, Tuckachihas, Chippeways, Ottawas, Putewoatamies, and Kalkafkias. The Delawares were lately hoftile, but made peace with the United States, 1795, and ceded fome lands. The United States, on the other hand, have engaged to pay them in goods, to the value of 1000 dollars a year for ever. Twenty years ago, the Delawares could furnish 600 warriors ; but their number is confiderably decreafed by war fince that time.

DELIVERANCE, CAPE, is the S.E. point of the land of Louifiade. Bougainville was here, and named it in 1768. DEL REY, a captainship in the fouthern division of Brazil, whole chief town is St. Salvadore.

DEL SPIRITU SANTO, a river which falls into the gulf of Mexico, at the N. W. end of the peninfula of Florida.

DEMERARA, a river in Dutch Guiana, in S. America, is about two miles wide at its mouth, opposite the fort, on the E. bank of the river, and about \$5 miles diftant from Abary creek. It is fearcely a mile wide, 12 miles above the fort; and its courfe is from S. to N. It is navigable upwards of 200 miles for veffels which can pais the bar at its mouth, which is a mod bank, not having above 24 teet at the highest tides. The difference between high and low water mark, is from 10 to 12 feet. The fort, if properly supplied with men and ammunition, is able effectually to guard its entrance. Staebroeck, the leat of government, ftands .Transwert.

on the E. fide of the river, 11 miles above the fort.

DEMERARA, a diffrict in Dutch Guiana, which, together with Effequebo, form one government, and have the fame court of police, but each has a separate court of justice. The two districts contain about 3000 whites and 40,000 flaves. Demerara R. which gives name to the diffrict, paffes thro' it, and is usually visited by 40 or 50 large thips from Holland, who often make two voyages in a year, befides upwards of 250 imaller veffels, under the Dutch and other flags. The plantations are regularly laid out in lots along the fea-fhore, called façades, about a quarter of a mile wide, and extending iths of a mile back into the country. Each lot contains about 250 acres each ; and when fully cultivated. the proprietor may obtain a fimilar tract back of the first, and so on in progreffion. Each lot will contain 120,000 cotton trees, averaging ufually half a pound a tree. Such a plantation is reckoned well stocked to have 120 negroes. The fhores of the rivers and creeks are chiefly planted with coffee, to the diftance of about 30 miles from the fea; thence 30 miles further up, the foil becomes clayey and more fit for fugar canes. Beyond this, the fineft kinds of wood, for building, furniture, &c. are cut. See Dutch America.

DEMI-QUIAN, a river, fwamp and lake on the western fide of Illinois R. in the N. W. territory. The river runs a S. S. E. courfe, is navigable 120 miles, and has the fwamp of its name on the northern bank near its mouth; which laft is 50 yards wide, 32 miles above Sagamond, and 165 miles above the Miffifippi. The lake is of a circular form, 200 yards W. of the river, is 6 miles acrofs, and empties into the Illinois by a fmall paffage 4 feet deep, 174 miles from the Miffilippi.

DENNEY's River, diftrict of Maine, 22 miles E. of Machias. The country between this river and Machias, in 1794, was a wildernets. The banks of the river were at this time thinly fettled by a regular and well disposed people.

DENNIS, a part of Y armouth in Barn-fable co. Mallachuletts, which was incorporated into a township in 1793.

DENTON, the chief town of Caroline co. in Maryland ; fituated on the E. fide

of

of Chop of Chop ly, and ter co. l DERI Vermon the E. C DERI Connect

formed tuck ar town wa Haven into two in its i trade . finall to the fall which t works o to the St fatonick this tow

DER **fylvania** from P Derby a ware riv DER

Pennfyl Swatera fluence celebrat Dauphi

DER

nah R. two oth in Penn the othe DERI Hampfh mack H 362 inh in 1751 It is 49 DES.

Americ Capac l to trani and wh DES da, the difcover voyage, that na loupe,

miles S. S. E o DEPT of Choptank creek, the E. main branch of Choptank R. It is laid out regularly, and has a few houses, and lies 7 miles S. of Greensborough, and 37 S. S. E of Chefter.

....

he

5 2

wo

ich

ro'

50

ten

les

ter

m-

ots

es,

nd

he

50

:d,

ar

0-

00

a

is

IC-

nd

te,

m

p,

eft

re,

nd

in

12

:8.

he

ch

ve

he

ar

6

li-

7.4

ie,

ry

4.

he

)y

n-

n-

ne

le

DEFTFORD, a township in Gloucester co. New. Jersey.

DERBY, a township in Orleans co. Vermont, on the N. line of the state, on the E. shore of lake Memphremagog.

DEREY, a town in New-Haven co. Connecticut, on the point of land formed by the confluence of Naugatuck and Houfatonick rivers. This town was fettled in 1665, under New-Haven jurifdiction, and is now divided into two parifhes, and has an academy in its infancy. It has a confiderable trade with the Weft-Indies for fo finall town, and a number of mills on the falls of Naugatuck, and ftreams which fall into it, and iron and other works on Eight-mile R. which falls into the Stratford. The Stratford or Houfatonick R. is navigable 12 miles to this town.

DERBY, a town in Chefter co. Pennfylvania, 7 miles from Chefter, and 5 from Philadelphia. It is fituated on Derby creek, which empties into Delaware river, near Chefter.

DERBY, a township in Dauphin.co. Pennfylvania, fituated on the E. fide of Swatera creek, 2 miles above its con fluence with the Susquehannah, and celebrated for its curious cave. See Dauphin co.

DERBY, a township on Susquehannah R. in Pennfylvania. There are two other townships of the same name in Pennfylvania; the one in Missin co. the other in that of Westmoreland.

DERRYFIELD, a township in New-Hampshire, on the E. bank of Merrimack R. Hillsborough co. containing 362 inhabitants, and was incorporated in 1751; the foil is but indifferent. It is 49 miles W. of Portsmouth.

DESAQUADERO, a river in Peru, S. America, over which the Ynca Huana Capac built a bridge of flags and rufnes, to transport his army to the other fide, and which remained a few years fince.

DESEADA, Defirada, or Defiderada, the first of the Caribbee islands, discovered by Columbus in his fecond voyage, anno 1494, when he gave it that name. It is fituated E. of Guadaloupe, and subject to the French; and

is of little confequence except in time of war, when it is the refort of a number of privateers. It is so miles long and g broad, and looks at a diffance like a galley, with a low point at the N. W. end. The Spaniards make this in their way to America, as well as Guadaloupe. N. lat. 16. 40. W. long. 61. 20.

N. lat. 16. 40. W. long. 61. 10. DESEADA, or *Cape Defire*, the fouthern point of the firsits of Magellan, in S. America, at the entrance of the South Sea. S. lat. cz. A. long. 74. 18. W.

Sea. S. lat. 53. 4. long. 74. 18. W. DESEST ISLAND, MOUNT, on the coaft of the diftrict of Maine, Maffachufetts, contains about 200 families, divided into two different fettlements, about 15 miles apart.

DESESPOIR, Cape, or Defpair, on the northern fide of Chaleur Bay, is about 3 leagues west-fouth-west of Bonaventure Asland. There is a large cod fifthery here.

DESPAIR, a bay on the S. weftern fide of Newfoundland island, adjoining to Fortune bay on the N. eastward; which fee.

DETOUR DES ANGLOIS, or English Turn, is a circular direction of the river Miffifippi, fo very confiderable, that ver fels cannot pais it with the fame wind that conducted them to it, and muft either wait for a favourable wind, or make faft to the bank, and haul clofe: there being fufficient depth of water for any vefiel that can enter the river. The two forts and batteries at this place on both fides the river, are more than fufficient to ftop the progrefs of any veffel whatever. Dr. Cox, of New-Jerfey, afcended the Miffifippi to this place, anno 1698, took pofferfion and called the country Carolina. It lies 18 miles below New-Orleans, and 87 above the Balize. The banks of the river are fettled and well cultivated from this to New-Orleans, and there is a good road for carriages all the way.

D'ETROIT, one of the principal towns, and beft fortified, in the N. W. territory; fituated on the weffern bank of the firait St. Clair, or D'Etroit R. between lake Erie and lake St. Clair; 18 miles N. of the W. end of the former, and 9 miles below the latter. Fort D'Etroit is of an oblong figure, built with flockades, and advantageoufly fituated, with one entire fide commanding the river. It is near a mile in circumference, and enclofes about 300 wooden houfes and a Roman

Roman Catholic church ; built in a regular manner, with parallel ftreers, offing each other at right angles. Its fituation is delightful, and in the centre of a pleafant and fruitful country. For 8 miles below, and the fame diffance above Fort D'Etroit, on both fides of the river, the country is divided into regular and ell cultivated plantations; and from the contiguity of the farmer's houfes to each other, they appear as two long extended villages. The inhabitants, who were mostly French, were about 2000 in number in 1778, 500 of whom were as good markimen as the Indians chemfelves; and as well accuftomed to the woods. They raife large flocks of black cattle, and great quantities of torn, which they grind by wind mills, and manufacture into excellent flour. The chief trade of D'Euroit confifts in a barter of coarfe European goods with the natives for furs, deer fkins, tallow, &c. By the treaty of Greenville, Aug. 3, \$795; the Indians have ceded to the United States the post of D'Etroit, and ill the land to the N. the W. and the 5. of it, of which the Indian title has been extinguished by gifts or grants to the French or English governments, and fo much more land is to be annexed to D'Etroit as shall be comprehended between Rohne R. on the S.; lake St Clair on the N.; and a line the general courfe whereof shall be 6 miles from the W. end of lake Erie and D'Etroit river. The fort, &c. was delivered up by the British in July, 1796, according to trea-ty. It lies 18 miles N. of lake Erie, 724 N. W. by W. from Philadelphia. N. lat. 42. 40. W. long. 82. 56.

D'ETROIT River, or Strait of St. Clair, flows from lake St. Clair into the W. end of lake Erie, forming part of the boundary between the United States and Upper Canada. In afcending it, its entrance is more than 3 miles wide; but it perceptibly diminifhes; fo that opposite the fort, 18 miles from lake Erie, it does not exceed half a mile in width; from thence to lake St. Clair it widens to more than a mile. The channel of the ftrait is gentle, and wide and deep enough for fhipping of great burden, although it is incommoded by feveral islands, one of which is more than feven miles in length. Thefe iflands are of a fertile foil, and from their fituation afford a very agreeable

appearance. The length of the river is 28 miles; and feveral ftreams fall into it chiefly from the N. W. viz. Bauche, Clora, Curriere, D'Etroit, and Huron rivers.

DEVIL'S Mouth, a name given by failors to a frightful volcano, near Leon Nicaraguay, in New-Spain, feated near the lake. N. lat. 13. ro.W. long.65. 10.

DEVIL'S Nofe, a promontory on the S. fide of lake Ontario, 16 miles E. of Fifting bay, and 23 N. W. of the mouth of Genetice river.

DEVIL'S Ifland, on the E. fide of Chelapeak bay, is in Somerfet co. Maryland, between Fishing bay and Nanokin river.

DEWAERT, an inconfiderable ifland lying at fome diftance E. of Terra Magellanica, S. America. It had its name from the first discoverer.

DEWEE, an ifland in South-Carolina, which forms one of the three harbours of Charleftown city.

DIAMOND, or Round Ifland, one of the Grenadilles, in the W. Indies. See Rhonde ifle.

DICKENSON College. See Carlifle, in Pennfylvania.

DICK'S R. in Kentucky, is a branch of Kentucky R. which it joins in a N. W. direction. It is about 50 miles long, and 45 yards wide at the mouth, and has a number of excellent mill feats, and runs through a body of first rate land.

DICKWASSET, or Digdeguafb, a river, in the British province of New-Brunswick, which empties into Paffamaquoddy bay.

DIEP Town, or Deep Town, a town on the N. weftern fide of the ifland of St. Christopher's, in the West-Indies, lying on a bay of the fame name.

DIGBY, fitnated on the S. E. fide of Annapolis bay, 18 miles S.W. of Annapolis, and 33 N. by E. of Yarmouth, is one of the most confiderable of the new fettlements of Nova-Scotia.

DIGGES Cape, on the S. fide of Hudfon ftraits, N. lat. 62.41. W. long. 78. 50.

DIGHTON, a post town in Bristol co. Massachuletts, 7 miles from Taunton, and 20 from Warren, in Rhode-Mand. There are 236 houles in the township, and 1793 inhabitants.

DIN WIDDIE, a co. in Virginia, S. of Appamattox R. which divides it from Chetterfield, It is about 30 miles long, and

and zo broad, and its chief town is Peterfburg. DESAFFOINTMENT, a bay on the N.

er is into

rche,

uron

by

Leon

near

. 10. 1 the

5. of

the

le of

Ma-

ano

land

Ma-

ame

lina,

ours

ie of

See

lifte,

anch

in a

niles

uth,

eats,

rate

Jew-

affa

town

nd of

dies,

le of

An-

buth,

f the

Ind-

1.50.

l co.

nton,

and.

ship,

S. of

from

ong,

and

W. coaft of N. America. N. lat. 52. 15. W. long. 129.

DISMAL, a fwamp in the township of Milton, Lincoln co. district of Maine.

DISMAL Swamp, called the Great Difmal, to diffinguith it from another fwamp called Difmal, in Currituck co. is a very large bog extending from N. to S. near 30 miles, and from E. to W. at a medium about 10 miles; partly in Virginia, and partly in North-Carolina. No lefs than 5 navigable rivers, belides creeks, rife out of it; whereof two run iato Virginia, viz. the S. branch of Elizabeth, and the S. branch of Naniemond river, and 3 into North Carolina, namely, NO R. North-Weft R. and Perquimons. All their hide their heads, properly fpeaking, in the Difinal, there being no figns of them above ground. For this reafon there must be plentiful fubterraneous ftores of water to feed fo many rivers, or elfe the foil is fo replete with this element drained from the highlands that furround it, that it can abundantly afford these supplies. This is most probable, as the ground of the fwamp is a mere quagmire, trembling under the feet of those that walk upon it, and every impression is instantly filled with water. The fkirts of the iwamp, towards the E. are overgrown with reeds, 10 or 12 feet high, interfperfed every where with ftrong bamboo briars. Among thefe grow here and there a cyprefs or white cedar which laft is commonly miltaken for the juniper. Towards the S. end of it is a large tract of reeds, which being conftantly green, and waving in the wind is called the green fea. In many parts, efpecially on the borders, grows an ever green fhrub, very plentifully, called the gall buth. It bears a berry which dies a black colour like the gall of an oak, whence it has its name. Near the middle of the Difmal the trees grow much thicker, both cyprefs and cedar. There being always green, and loaded with very large tops, are much exposed to the wind and eafily blown down, the boggy ground affording but a flender hold to the roots. Neither beaft, bird, infect, or reptile, approach the heart of this horrible defert ; perhaps deterred by the everlating

and bufnes which the fun can neve penetrate, to warm the earth : nor indeed do any birds care to fly over it, any more than they are faid to do over the lake Avernus, for fear of the noifome exhalations that rife from this vaft body of filth and naftinefs. Thele noxious vapours infect the air round about, giving agues and other diftempers to the neighbouring inhabitants. On the western border of the Difinal is a pine fwamp, above a mile in breadth, great part of which is covered with water knee deep; the bottom, however, is firm, and the pines grow very tall, and are not eafily blown down by the wind. With all these difadvantages, the Difmal is, in many places pleafing to the eye, though difagreeable to the other fenfes.

This dreadful fwamp was judged impaffable, till the line, dividing Virginia from N. Carolina, was carried through it, in N. lat. 36, 28. in the year 1728, by order of king George H. Although it happened then to be a very dry feafon, the men who were employed in pushing the line were not altogether free from apprehennions of being ftaryed; it being to whole days before the work was accomplified, though they proceeded with all poffible diligence and refolution, and befides had no difaster to retard them.

This fwamp is chiefly owned by two companies. The Virginia company, of which General Washington is one, owns 100,000 acres: the North-Carolina company owns 40,000 acres. In the midft of the fwamp is a lake, about 7 miles long, called Drummond's pond, whole waters difcharge themfelves to the S. into Pafquotank river, which empties into Albemarle found ; on the N. into Elizabeth and Nanfemond rivers, which fall into James R. A navigable canal is now digging to connect the navigable waters of the Pafquotank and Elizabeth rivers. The distance about 14 miles. This canal will pais about a mile E. of Drummond's pond, and will receive water from it. The Canal company are incorporated by the concurring laws of Virginia and North-Carolina. This canal, when finished, will open an inland navigation from the head of Chefapeak: hay, including all the rivers in Virginia, thade, occasioned by the thick thrubs to Georgetown in South-Carolina; and when

when the fhort canal from Elk river to Chriftiana creek is opened, the communication will extend to Philadelphia and the other ports connected with Delaware river. Such an extensive inland communication muft be beneficial in time of peace, and in time of war will be effentially ferviceable.

DIXON's Sound, on the N. W. coaft of N. America, is the paffage into the found between the main land and Washington's or Queen Charlotte's islands, from the N. W. This seems to be what is called in America Barrells' Sound; which see.

DOBB's Ferry, on Hudson river, is 26 miles above New-York city.

DOBB's Co. in Newbern diffrict, N. Carolina, has been divided into two counties, viz. Glafgow and Lenoir, fince the cenfus of 1790, and the name no longer exifts. It contained 6893 inhabitants, of whom 1915 were flaves.

Doc's Island, one of the finaller Virgin islands, fituated on the west of Virgin Gorda, and E. of Tortula. N. lat. 18, 20, W. long. 62, 55.

DOG-RIBBED Indians, inhabit round lake Elande, in the N. W. part of N. America. They are often at war with the Arathapetcow Indians. Both thefe tribes are among the most favage of the human race. They trade with the Hudfon bay company's fettlements. Edlande, lake lies N. of the Arathapefcow fea, or lake, and near the arctic eircle.

DOMINGO, ST. an ifland in the Atlantic ocean, at the entrance of the gulf of Mexico, is one of the four great Antilles, the largest of them all, except the island of Cuba, and proved the cradle of European power in the new world. Christopher Columbus landed on it the 6th of Dec. 1492. The natives called it Hayti, fignifying high or mountainous land. Charlevoix fays it was called Quifqueya, that is, great country, or mother of countries. Others fay it had the name of Bobio, which means, a country full of habitations and villages. Columbus called it Hifpaniola, or Little Spain, which name the Spaniards still retain, though St. Domingo is the name commonly used by other nations; fo called from St. Domingo, the capital of the Spanish part; which was thus named by Columbus in honour of his father. St. Domingo is fituated between

17. 55. and 20. N. latitude, and between 71. and 77. W. longitude from Paris. It lies 45 leagues E. N. E. of Jamaica, 22 S. E. of Cuba, and 20 N. W. by W. of Porto Rico; and is, not including the fmall dependent iflands that furround it. 160 leagues long from E. to W. and from 60 to 70 broad from N. to S. When the Spaniards difcovered the ifland, there were on it at leaft a million of happy inhabitants, and Bartholomew de las Cafas, fays there were three millions. Such, however, were the cruelties of the Spaniards, and to fuch an infamous height did they carry their oppreffion of the poor natives, that they were reduced to 60,000 in the fhort fpace of 15 years | It formed five kingdoms, each governed by fovereigns called caciques. The names of thefe kingdoms were Maqua Marien, Higuay, Maguana, and Xaraguay. The Spa-niards had pofieffion of the whole of the island for 120 years. At last, about the year 1630, a handful of English, French, and other Europeans, came and forced them to fight in its defence, and after repeated wars for 50 years, they were forced to divide the ifland with the French. Thefe latter, being the only furvivors of the first free-booters or buccaniers, or having infenfibly acquired an afcendency among them, had, fo early as 1640, formed this affembly of individuals, born under the domination of almost all the powers of Europe, into a French colony, under the direction of the general government, first established at St. Christopher's, and afterwards at Martinico. The Spanish part is by far the most extensive and the moft fertile; that of the French the beft cultivated. The whole ifland now belongs to the French republic, the Spaniards having ceded their part of it to that power in the treaty of 1795.

The Spaniards, however ungrateful to the diffeoverer of the new world during his life, would not leave his duft out of their territories. The remains of Columbus, who died the 20th of May, 1506, were first deposited in Seville, afterwards removed to the cathedral in the city of St. Domingo, and lastly conveyed to the Havannah in a 74 gun ship; and on the 19th of January, 1796, all that was mortal of that great man, was committed to the earth the third time, with great parade and ceremony. The

The following particulars relating to this famous ifland are founded on the beft authority, and many circumftances require a feparate view of the two artificial divitions of the ifland, viz. the French and Spanifh territories, before they were united under one head. They are both alike in poffeffing the various productions common to the W. Indies. The European cattle are fo multiplied here that they run wild in the woods ; few of these are in the French part in comparison with the Spanifh.

ris.

ca

w.

the

it.

and

S.

if-

ion

nil-

iel-

in-

op-

hey

lort

all-

ng-

ay,

pa-

the

the

ch.

ced

fter

/ere

the

mly

uc-

fo

r of

na-

Eu-

the

mt,

and

the

the

the

fit

eful

du-

duft

s of

lay,

, af-

the

ryed

np;

all

was

ime,

The

The two great chains of mountains, which extend from E. to W. and their numerous fours, give the ifland an afpect, at a diftance, not fo favourable as it deferves. They are, however, the caufe of the fertility of the ifland. They give fource to innumerable rivers, repel the violence of the winds, vary the temperature of the air, and multiply the refources of human industry. They abound with excellent timber, and mines of iron, lead, copper, filver, gold, fome precious ftones, and even mercury .-With respect to the vegetable class in this island, it would be difficult, even in a work devoted to the fubject, to express or paint all their majefty. Here are the mountains of Cibao, Selle, and Hotte, reckoned 1000 fathoms above the level of the fea. In the bowels of the first, the cruel Spaniards condemned thoufands of the natives, to facrifice their lives, in fearch of gold. The mines are not now worked, although Valvarde thinks they might be to advantage. In the plains, in the Spanish part, the heat is nearly uniform, but varies in proportion to their diffance from the mountains. In the plains, the thermometer is fometimes at 99. In the mountains it rarely rifes above 72, or 77. There, the nights are cool enough to render a blanket not unwelcome; and there are mountains where even a fire is a very agreeable companion in fome evenings. The contrast of violent hears and heavy rains renders St. Domingo humid; hence the tarnished appearance of almost all metals, however brilliant the polifh they may originally have had. This is particularly observable on the fea fhore, which is more unhealthy than the interior parts of the illand. The fouthern part of the ifland is pretty much fubject to hurricanes, called here fouthern gales, because they are not at-OR GRA

tended with fuch dreadful confequences as the hurricanes in the windward iflands.

The Spanish part is computed to contain about 90 leagues in its greatest length from E. to W. 60 leagues in its greatest breadth; having a furface of about 3,200 square leagues. About 400 square leagues of this surface is in mountains, which are generally more capable of cultivation than those in the French part, and have sometimes a soil that disputes the preference with that of the vallies. There remains therefore a fine fertile surface of more than 2,700 square leagues, divided into vallies and plains. of various lengths and breadths.

Many circumfrances confpired to render this ifland a place of importance to the Spaniards. It was a key to the gulf of Mexico, a convenient place for their hipping to touch at, an excellent rendezvous for their fquadrons and fleets, and an important hold for naval operations of all forts; but from the impolitic measures of the government, and the reftraints on commerce, it proved rather a burden than an advantage to the mother country.

The cantons or jurifdictions, beginning at the westernmost point of the Spanifh frontiers, on the jouthern coaft or narrows, are, Babaruco, poffeffed by the brigands or fugitive Spanish and French negroes, who inhabit the mountain of Bahoruco), Neybe, Azua, Bani or Vani, the city of St. Domingo, and territory dependent thereon, St. Laurent des Mines, Samana, Cotuy, La Vega, St. Yago, Daxabon, St. Raphael, Hincke, Banique, and St. John of Maguana. Over the whole of the Spanish part of the ifland, mountains and plains, are fpread 12'5,000 inhabitants; of whom 110,000 are free, and 15,000 flaves; which does not amount to 40 individuals to one fquare league. The Spanifh creoles are infentible of all the treafures which furround them, and pals their lives without withing to change their lot; while the French portion furnishes three fifths of the produce of all the French Weft-India colonies put togeth r; or more than 10 millions fterling. The drefs and mode of living of the Spanish creoles indicate pride, lazinefs, and poverty. A capital, which of itfelf indicates decay, little infignificant towns here and there, a few colonial fettle-

ments,

nents, for which the name of manufactories would be too great an honour, immense possessions called Hattes, where beafts and cattle are raifed with little care, in different grades of domeftication; as the domeftic, the gentle, and the fly. Those called wild or mountaineers, as also the fby, colt the herdfmen, called pioneers and lancers, immenfe labour and danger in the chafe. The hattes are the most numerous fort of Spanish settlements, and of an extent far difproportioned to their utility. Some are feveral fquare leagues, and do not contain above 500 head of cattle, great and finall. Some are called horfehattes, others cattle-hattes, according to the name of the animals they contain; others used in breeding pigs are called corails. A finall piece of wood land, called venerie, frequently ferves as a boundary between the hattes, common to those on both fides of it, and alfo thelters the cattle from the heat of the fun. The woodland likewife attracts the wild animals, and leffens the labours of the huntfinan. In these hattes, the people lodge miferably, and have but poor fubfiltence. The finall provision farms called Conacos, fall generally to the lot of the poorer colonifts, or most commonly people of colour, or freed people.

DOM

144

The fupply of horned cattle to the French part of the island cannot be efsimated at lefs than 15,000 head annually: of which the Spaniards furnish four fifths. Thefe at 30 dollars a head, and bringing them by the Spaniards, cannot be lefs than 450,000 dollars. This forms three quarters of the produce of the colony ; and the impost paid to government is 10 per cent. The number of 200,000 head of cattle is the number in the general cenfus taken by order of the prefident in 1780, and if we count the cattle exempted from the tribute, they may amount to 250,000 ; without comprehending horfes, mules and affes, which, with an augmentation eftimated fince 1780, would make a flock of 300,000 head, and an annual production of 60,000; and suppole a fifth part of the young ones perish accidentally, there still remains 48,000. The refources of the colonifts are very confined, and their few establishments all below mediocrity. There are but 22 fugar manufactories of any confeDOM

affirm

minat

if con

tidera

the fl

exclue

civil a

coloui

the pc

admit

civil

thofe

jor pa

mixed

and f

betray

a pre

troub

colour

witho

have

make

Portu

treme

well a

ciple a

emanc

felf at

fate of

of fre

master

ed, in

the of

againf

thofe

obferv

write :

courfe

badnet

nothin

and on

is very

travell

gle ha

carry

rifhme

ftate o

that L

tive cr

his ac

comm

part, i

watere

numbe

of this

of the

Th

Few

Th

quence; the reft being not worth naming; and even thefe 22 have altogether but about 600 negroes, Of these 6 produce fyrup, and fome fugar; but the others which are called trapachies, where animals are employed to turn the mills and prefs the canes, without thelter in the open air, make nothing but fyrop. The whole of which produce is generally used in the colony ; imall quantities are fometimes fent to Porto Rico, or to Old Spain; and the goodnels of the fugar has proved that of the foil, but nothing in favour of the manufacturer. The coffee raifed here is excellent; each tree in a flate of bearing will produce on an average a pound weight, and is fometimes of a quality equal to that of Mocha, yet chocolate is preferred to it. Cotton grows naturally at St. Domingo, of an excellent quality, even without care in ftony land, and in the crevices of the rocks. The numerous roots of indigo are only obstacles to the feeble cultivation of the fields, where it grows fpontaneoufly. All these valuable productions have thared the fate of depopulation. Tobacco, fays Valverde, has here a larger leaf than in any other part of America; it grows every where, and equals fometimes that of Cuba or the Havannah. It is as much effeemed as this latter, in the manufactures of Seville, and is even preferable to it in fegars. Its cultivation has lately become more general. The kernel of the cocoa nut of St Domingo is more acidulated than that of the cocoa nut of Venezuela and Caraca, to which it is not inferior ; and experience proves, that the chocolate made of the two cocoas has a more delicate flavour than that made of the cocca of Caraca alone. Achiote, ginger, and caffia have fhared the fate of the other productions.

The population of the Spanish part is composed of whites, freed people, and flaves. There are also a few creoles recembling the Indians, having long, ftraight and black hair, who pretend to be defcendants of the ancient natives. They are, however, thought to be defcended from a mixture of the aborigines and the Spaniards. There were, however, in 1744, feveral Indians at Banique, who proved their defcent from the fubjects of the unfortunate cacique *Henri*; although historical authority affirms affirms that the whole race was exterminated.

ies.

um

th-

no-

lich

ny;

to

the

hat the

Lere

of

re a

of a

yet

ton

e in

the

ligo

iva-

ion-

inc.

ula-

here

t of

and

the

as

Se-

1 fe-

ome

coa

ated

uela

ior ;

alate

: de-

gin-

e of

part

ople,

coles

ong,

d to

ives.

de-

rigi-

vere,

is at

from

ique

ority

arms

the

an

The freed people are few in number, if compared with the whites, but coniderable in proportion to the number of the flaves. The people of colour are excluded from almost all employments, civil as well as military, as long as the colour of the fkin betrays its origin; but the political constitution of the country admits of no diffinction between the civil rights of a white inhabitant and those of a free person. Indeed the ma-jor part of the Spanish colonists are of a mixed race: this an African feature, and fometimes more than one, often betrays; but its frequency has filenced a prejudice that would otherwife be a troublesome remembrancer. People of colour are admitted to the priefthood without difficulty; but the Spaniards have not yet brought themfelves to make negro priefts and bifhops like the Portuguefe. Slaves are treated with extreme mildnefs, and are ufually fed as well as their mafters. A religious principle and an illicit affection tend to their emancipation. A flave can redeem himfelf at a price fixed by law. Thus the fate of the flave is foftened by the hope of freedom and the authority of the mafter by the habit of being confounded, in fome fort, with those who were the other day in flavery. The laws against flaves are much neglected; those in their favour are very exactly obferved.

Few of the creoles can either read or write; hence the want of focial intercourfe, which is also augmented by the badness of the roads. The roads are nothing but paths paffable only on foot and on horfeback ; and 8 leagues a day is very great work, in which fpace the traveller often does not meet with a fingle habitation, and must confequently carry with him every neceffary for nourifhment and lodging. Such is the low state of commerce in the Spanish part, that Don Antonio de Valverde, a native creole, goes fo far as to affert, in his account of the territory, that the commerce in cattle, with the French part, is its only fupport.

The whole island is in general well watered by rivers and brooks without number, but certain spaces are deprived of this advantage. From the formation of the ifland, their courses are but fhort, 145

and few of them navigable to any dif tance. It is generally impossible to con-ceive, from the tranquil aspect that these rivers usually wear, what they become when they overflow their banks. A river that but now hardly covered the pebbles on its bed, or wet the foot of the traveller, is changed by one tempeftuous fhower into a flood, menacing all that it approaches; and fhould its banks give way, it fpreads its watery devaltation over the plains. Many of these are infested with alligators. The only lakes or ponds worth notice are those of Henriquelle and Salt pond; the former is a great curiofity. See Henriquelle.

The chief of the iflands which furround St. Domingo, part of which be-longed to the Spanish part, are Altavele, Saone, Beate, St. Catherine, on the S. fide from W. to E. Mone, and Monique on the S.E. Caymite, and Gonave on the W. between the two peninfulas, and La Tortue, on the N. fide, towards the W. end of the island, and that of Avache on the S. fide of the fouthern peninfula.

The ancient division line which feparated the French from the Spanish part of the island extended from the river des Anses a Pitre or Pedernales, on the S. fide, to that of Maffacre, on the N. fide, at the head of the bay of Mancenille, which, together with the large bay which fets up from the weftward, between Cape St. Nicholas and Cape Dame Marie, S. W. of the former, and 43 leagues apart, moulds this division of the island into fuch a figure, as can be beft comprehended by a view of the map; fuffice it to fay, that it contains 2, 500,000 acres of land, of an extremely fertile foil, prefenting an agreeable variety of hills, vallies, woods and freams.

The French part of St. Domingo, containing 2,500,000 acres, of which 1,500,000 were under high cultivation in 1789, was then divided into 10 jurifdictions, which were fubdivided into 52 parifhes. Weft jurifdictions, Port au Prince, St Mark, Le Petite Goave, and Jeremie-in the north, Cape Francois, Fort Dauph'n, and Port de Paixthose in the fouth, Les Cayes, St. Louis, and Jacmel. Before the late revolution, there were in these parishes about 42,000 white people, 44,000 free people of colour, and 600,000 flaves. Other accounts

146

counts make them confiderably lefs; the above, however, is from good authority. The number of deaths, during 1789, according to the bills of mortality, 7121-the number of births the fame year, 4131. The excess of deaths, 2889, will be the lefs aftonifhing, when it is confidered, that in the years, 1787, and 1788, there had been imported into the colony nearly 60,000 new negroes. The exports from Jan. 1, 1789, to Dec. 31, of the fame year, were 47, 516, 531 lbs. white fugar, 93, 573, 300 brown fugar; 76, 835, 419 lbs. coffee; 7,004, 274 lbs. cotton; 758, 628 lbs. indigo; and other articles, as tanned hides, molaffes, fpi-rits, &c. to the value of 46,873 livres. The total value of duties on the above exportations, amounted to 770,801 dol-lars, 3 cents. Port au Prince is the feat of the French government in this iff and, in time of peace, and a place of confiderable trade. Cape François exceeds Port au Prince in the value of its productions, the elegance of its buildings, and the advantageous fituation of its port. It is the governor's relidence in time of way. The Mole, though inferior to these in other respects, is the first port in the ifland for fafety in time of war, being by nature and art ftrongly fortified. The other towns and ports of any note, are fort Dauphin, St. Mark, Leogane, Petit Goave, Jeremie, Les Cayes, St. Louis, and Jacmel, which fee under their different names.

The most ancient town in this island, and in all America, built by Europeans, is St. Domingo; of which an account is given below. To these particular observations, we add the following, of a more general nature : The fugar and indigo plantations were in the flat, the coffee in the mountainous lands. The plantations were for the most part enclofed with live hedges, ftraight and well dreffed; the dwelling and manufactory houses were built and laid out with great neatness and tafte; every habitation poffeded a private hospital for the accommodation of its fick negroes, who were parentally dealt with ; the roads were excellent; and from the general hospitality and cheerfulness of its former inhabitants, it was confidered as one of the most enviable fpots on earth. Such was the French part of St. Domingo in 1789; but, alas! it is no more : the destructive ravages of an unrelenting infurrection, of frightful maffacres and conflagrations, have laid wafte all those beautiful fettlements, reduced the buildings to affres, and laid low in dust or feattered in exile, its wretched inhabitants.

fathe

bella

foun

1493

In r

its bi

remo

of th

built

fign

lis of the c

Fatho

ma;

ing o thom

and t

roug

but a

the fc

form

the fi

with

about

deal (

ticula

tions

the I

its cr

from

and

pleafi

ftreet

from

the h

marb

ftyle

Italy

tion a

erect

plank

thisc

difh c

is thr

fort o

clay !

amaz

Comet

pillar

houfe

handf

unifo

built

cover

palm

platfc

duct i

clima

The first interference of the National Affembly, in the affairs of the colonies, was by a decree of the 8th of March, 1790, which declared, " That all free perfons, who were proprietors and refi-dents of two years ftanding, and who contributed to the exigencies of the ftate, fhould exercise the rights of voting, which conftitute the quality of French citizens." This decree, though in fact it gave no new rights to the people of colour, was regarded with a jealous eye by the white planters; whole pride and refentment dictated to them to repel the people of colour from their affemblies. This feems to be the true fource of their calamities; to develope which, and the dreadful confequences, belong to the profeffed historian.

DOMINGO, ST. the capital of the Spanish part of the island of St. Domingo, or Hifpaniola, is fituated on the W. bank of the Ozama, a league below the mouth of Itabella river, in which diftance it is 24 feet deep, having a bottom of mud or foft fand, and banks 20 feet perpendicular height; but N. of the city this height is reduced to 4 feet. The Ozama is navigable for 9 or 10 leagues, and has feveral fugar manufactories, tile kilns, and provision farms on its banks. The road before the mouth of the Ozama is very indifferent, and lies exposed from W. S. W. to E. It is impoffible to anchor in it in the time of the South winds; and the north winds drive the veffels from their moorings out into the fea, which here runs extremely high. The port of St Domingo is magnificent in every respect ; a real natural bason, with a great number of careenings for the veffels that can get at them. There is a rock at the entrance, which will only admit veffels drawing 18 or 20 feet water; which it is afferted might be removed without great difficulty.

The city of St Domingo was originally founded on the E. fide of the Ozama, in 1494, by Bartholomew Columbus, who gave it the name of new Ifabella. Authors aftert that Chriftopher Columbus gave it the name of histather,

father, and that the inhabitants of Ifabella on the N. coaft of the island, founded by Chriftopher Columbus in 1493, removed to New-Ifabella in 1496, In 1502 a hurricane deftroyed most of its buildings, which induced Ovando to remove the inhabitants to the W. fide of the river. The new city was foon built, and that with a grandeur of defign not unworthy of the first metropolis of the New World. The plan of the city is a trapezium of about 540 fathoms on the E. fide, along the Ozama; 'near 500 fathoms on the S, bordering on the fea; and of about 1800 fathoms in circumference. To the W. and to the N. of the city, the land is rough and rocky for about half a league, but after that it becomes good, and the country delightful. Towards the fea the feite of the city lies very high, which forms an infurmountable dyke against the fury of the waves. It is furrounded with a rampart 8 feet in diameter, and about so feet high. There is a great deal of ordnance at St. Domingo, par-ticularly caft ordnance, but the fortifications are not firong; and the height of the Ileignes commands it entirely; and its crown is not more than 250 fathoms from the ditch. The freets are fpacious, and ftrait as a line, which gives it a pleading appearance. Ten of thefe ftreets run from N. to S. and ten others from E. to W. The greatest part of the houses, first built, are of a fort of marble found in the vicinity, and in the ftyle of the ancient towns of Spain and Italy : those of a more recent construction are of tapia, a fort of pife. To crect these buildings, a case is made of plank's, between pillars of masonry: this case is filled by degrees with a reddifh clay, which is rammed down as it is thrown in, until it forms a folid, or fort of wall, between the pillars. The clay thus prefied together, acquires an amazing hardnefs, and the walls are fometimes fo folid and ftrong, that the pillars of majonry are useless. The houses of St. Domingo are tolerably handfome, in a fimple ftyle, and nearly uniform. A confiderable part of these built within these 15 years, are of wood, covered with the leaves or taches of palm trees. The roofs are generally platformed, being fhaped fo as to conduct the rain-water to the cifterns. The climate of the capital is, happily, very

of

0

;m

h

:5

ic h

15

>-

;

1-

n

le

it

it

-

1111

Ľ,

temperate. The nights of those months' which answer, to the winter in Europe, are even found to be cold.

Among a number of public edifices that merit attention, in this declining city, we may reckon the ruins of the houfe that Diego, fon of Chriftopher Columbus, had begun, entirely of hewed ftone. The walls are yet remaining, and fome of the fculpture round the windows. The roof and ceilings are fallen in, the lower floor is become a pen for cattle ; and a Latin infcription over the portal, is now hidden by the hut of a herdfman. The cathedral, of the fame fort of ftone as the houfe of Diego Columbus, stands on the S. E. Opposite its entrance is a fine fpacious oblong fquare, at the S. W. end of which is the town house. The cathedral is a noble Gothic pile begun in 1512, and finished in 1540, and was constructed after the model of a church at Rome. It merits admiration on account of the boldness of its vault, which notwithstanding the ravages of earthquakes in its neighbourhood, has never, till within these 15 or 20 years, had a fingle flaw. The dust of Columbus rested within this pile until the year 1796, when it was removed. Here are 3 convents for men; which have increased in importance fince 1782; 2 nunneries, 3 hospitals, a college, and a gaol. The convent of the Cordeliers was built by Ovando in 1503, on a lit-tle hill containing a mine of mercury. All the 3 parochial churches of St. Domingo, are beautiful, rich in ornaments, in vales of gold and filver fet with pre-cious ftones, in pictures, in flatues of marble and of metal; but the cathedral furpaffes the others in every refpect. The population of the city of St. Domingo is not very confiderable; yet it is extraordinarily augmented fince the year 1780. The cenfus lately taken, amounts ed to 20,000, of every age and fex. But this is far below the exact number. The cenfus is taken by the Spanish priefts or vicars, and who go from house to house to verify those who do not per-form their paschal duties. This lift does not comprehend children under 7 years of age, nor heads of families abfent from their home or from the city. But the principal caufe of the inexactnefs, is, one half of the parochial territory of the city is on the outfide of the walls.

K a

This

This territory comprehends the part called the Plains, a great part of the Monte-de-Plate, and again as well to the E. as to the W. of the city, a very confiderable number of country feats and provifion habitations, where there are a great many families of blacks, of people of colour, and white cultivators i to that there are always 5 or 6000 not included in the cenfus.

Notwithstanding the declining fituation of the Spanish territory of the island, it is far more prosperous than it was 60 years ago. A census even of 1737 shows, that the total population at that time did not surpais 6000 souls, and the capital contained hardly 500.

The Spanish capital is 70 leagues E. by S. of Port au Prince, the road runs half the way along the fea coaft, through Bany, Azua, and Neybe, and thence by the lakes Henriquelle and Brackifhpond. In this route you have to crofs two large rivers, Nifai and Neybe, befides II fmaller ftreams. It is go leagues S. E. of Cape François, going by the road through St. Raphael, Azua, &c. ; and about 100 leagues by that of Dahabon, St. Yague, and La Vega. N. lat. 18. 19. 30. W. long. from Paris 72. 37. See Domingo, St. the preceding article. DOMINICA, the laft of the leeward Charaibee or Caribbee iflands, taking. them from N. W. to S. E.; but the Spaniards call it the laft of the windward illands. It is fituated about half way betwixt Guadaloupe on the N. W. and Martinico on the S. E. 15 leagues from each, between 15. 20. and 15. 44. 10 N. lat. and between 61. 17. and 61. 30. W. long. being about 29 miles in length from Crab-Point S. to the N.W. cape of Agufha bay on the N.; and nearly 16 miles broad from Raymond bay E. to Coulihaut on the W.; and contains 186,436 acres of land, and is divided into 10 Parifhes, viz. St. John, St. And drew, St. Peter, St. Joleph, St. Paul, St. David, St. George, St. Patrick, St. Luke, and St. Martin. The illand contains many high and support mount contains many high and rugged mount tains, intersperfed with fertile vallies, and is watered by upwards of 30 rivers, befide a number of rivulets, Several of the monntains contain unextinguished volcanoes, which frequently discharge vaft quantities of burning fulphur. Here are feveral hot fprings, effected efficacious in removing tropical diforders. B

ir

0

lu

n

It

w

of

iſ

is

an

in

al

9. G

th

ha

M

m

dif

in

old

the

mi

in

by

in

ín

W

ing

abo

bro

Ch

ton

in

hat

Col

ing

fett

ber

it fi

2 11

abo

chi

col

ous

256 N.

Doi

2 11

1

1

Some of the waters are faid to be hot enough to coagulate an egg. Here are valt fwarms of bees, which produce a great quantity of wax and honey; they hive in the trees, and are thought to have been transported from Europe : the native bee of the West Indies being a finaller species, unprovided with ftings, and very different in its manners from the European. The forefts afford an inexhaustible quantity of role wood, fo effected by cabinet makers. The fruits and other productions are fimilar to those in the neighbouring islands; but the foil being generally thin, is more adapted to the rearing of cotton than fugar. The beft eye-ftones that are known, are found on the fhores of this ifland. They have their name from the use which is made of them, for clearing the eyes of any dirt. They are fhaped like a lentil, fmooth and fleek, but much fmaller, and of a grey coldur. The value of exports, according to the current London prices in 1788, amounted to 302,9871. 158. fter. including exports to the American states, value 7,164l. 5s. The cargoes in 162 veffels, confifted of 71,302 cwt. 1 qr. 21 lbs. of fugar-63,392 gall. of rum-16,803 gall. molaffes-1,194 cwt. 3 qrs. 2lbs. cacac-18,149 cwt. 3 grs. 6 lbs. coffer-11,250 lbs. indigo-970,816 lbs cotton-161 cwt. ginger, befides hides, dying woods, &c. The number of inhabitants, in the fame year, appears to have been 1236 whites-445 free ne-groes, &c. and 14,967 flaves. There are also about 30 families of Charaibes, the remains of the ancient natives. The only towns here of any note are Charlotte town, the capital and the feat of government, formerly called Roffeau, on the S. W. fide of the island, and Portfmouth, fitutated at the head of Prince Rupert's bay.

Dominica, from its local fituation, between Martinico and Guadaloupe, ia the beft calculated of all the British polfessions in that part of the world, for fecuring to her the dominion of the Charaibean sea. A few ships of war in Prince Rupert's bay would effectually ftop all intercourse of the French settlements with each other, as not a vession can pass but is liable to capture, by ships cruising off that bay, and to windward of the island. It is a separate government and a free port. The anchorage is good good all round the coaft of Dominica; but it has no port or bay for retiring into; but the vefiels have the advantage of fhelter behind many of its capes.

It was difcovered by Chriftopher Columbus, Nov. 3, 1493; and had its name from being difcovered on a Sunday. It was taken by the French in the late war, and reftored to Britain at the peace of 1783.

DOMINICA, LA, one of the Marquefa iflands, called by the natives *Heevarga*, is the largeft of them all, extending E. and W. 6 leagues; is about 16 leagues in circuit, full of rugged hills, and of a barren aspect; but is inhabited. S. lat. 9. 44. The long. of the W. end from Greenwich is 139. 13. W.

¢

r t

e

e

n

r

e

1

Ņ

ę

e L

I

B,

s

Γ,

0

e

e

he

te

)÷

n

te

۱,

18

b-

1-

n

ly

e-

ps of

nt

iś

d

DON CHRISTOPHER'S Cove, lies on the N. fide of the ifland of Jamaica, having St. Anne's bay on the W. and Mammee bay on the S. E. It is remarkable for having given fhelter to the difcoverer of America, during a ftorm, in 1503, and for being the fcite of the old town of Sevilla de Nueva.

DONDON, an interior fettlement in the French part of the island of St. Domingo, 3 leagues N. W. of St. Raphael in the Spanish part, and 13 leagues E. by N. of Les Gonaives.

DONEGAL. There are 3 townships in Pennsylvania of this name; the one in Lancaster co. the other in that of Westmoreland, and the third in Washington co.

DOOBOUNT Lake, newly difcovered, about 60 or 70 miles long, and 20 or 30 broad; lies fouth-east of the head of Chefterfield inlet, in New South Wales.

DORCHESTER, a township in Grafton co. New Hampshire, incorporated in 1761. In 1790 it contained 175 inhabitants. It lies N. E. of Dartmouth College about 17 miles.

DORCHESTER, an ancient and thriving township in Norfolk co. Massachufetts, settled as early as 1630. A number of towns have been taken off from it fince its first settlement. It is fituated 2 miles S. by E. of Boston, and is now about 6 miles long and 3½ broad. The chief manufactures here are paper, chocolate, south, leather, and shoes of various forts. It has a handsome church, 256 houses, and 1922 inhabitants. The N. E. point of the peninfula, called Dorchester neck, approaches within half 2 mile of Castle Island, and its N. W.

point within half a mile of the S. part of Bofton. Forts were erected on the heights in the late war; and this town and its vicinity fuffered much during the early part of the war.

DORCHESTER, in Cumberland co. New-Jerfey, lies on the E. fide of Morris R. about 5 miles from its mouth in the bay, and 17 eaftward of Fairfield.

DORCHESTER Co. in Maryland, lies on the E. fide of Chefapeak bay; on the S. fide of Choptank R. which feparates it from Talbot co. It has feveral iflands on its coaft; the chief of thefe, from the mouth of Hudson river, are, James, Taylor's, Barren, Hooper's, and Goldsborough's, which last lies between Hungary river and Fishing bay. The length of the county from E. to W. is about 33 miles, and its breadth from N. to S. 27 miles. The number of its inhabitants 15,875, of whom 5337 are flaves. The lands in the northern parts are fomewhat elevated, but in the fouthern parts low and marfhy, particularly along Fishing bay, and up its waters, Transquaking, Blackwater, and Fea-rim creek, and along Hungary R. an arm of the Chefapeak. The produce is chiefly wheat, corn, and lumber. Its chief town is Cambridge.

DORCHESTER, a finall town of Charleftown diffrict, S. Carolina, feated on the N. E. bank of Afhley R. 18 miles W. N. W. of Charleftown city.— This place was fettled and named as early as 1700, by a colony from Dorchefter and its vicinity in Maffachufetts; and a part of its inhabitants, about the year 1750, left it and fettled Midway, in Georgia.

DORLACH, a township in Otlego co. New York. By the flate centus of 1796, 433 of its inhabitants are electors.

DORSET, a township in Bennington co. Vermont, having Rupert W. Manchefter S. and Danby N.; and contains 958 inhabitants, 27 miles N. by E. of Bennington.

DOUGLASS, a township, the fouthernmost in Worcester co. Massachusetts, having the flate of Rhode-Island on the S. and that of Connecticut on the S. W. and through it passes the middle road from Boston to New-York. It is a very rocky township, and contains 1080 inhabitants. It lies 16 miles S. of Worcester, and 47 S. W. of Boston. It was incorporated anno 1746, and received K 3

its name in honour of William Douglafs, M. D. of Bofton, a native of Scotland, and a confiderable benefactor to the town.

DOUGLASS, a township in Montgomery co. Pennsylvania.

DOUGLASS, a cape on the N. W. coaft of N. America, which forms the W. fide of the entrance into Cook's R. opposite Point Bede, which forms the E. fide. It has a very lofty promontory, whose elevated fummit appears above the clouds, forming two exceeding high mountains. Lat. 58. 56. N. long. 206. IO. E.

DOUTY's Falls, in York co. Maine, a place where a post office is kept; 7 miles from Berwick, and 8 from Sandford.

DOVER, a township in Norfolk co. Maßachusetts, incorporated anno 1650. It contains 485 inhabitants, and lies 15 miles southward of Boston.

DOVER, a confiderable township in Strafford co. New-Hampfhire, and the fhire town of the county; fituated on the fouthern fide of Cochecho R. about A miles above its junction with Salmon Fall R. which together form the Pifcataqua; 10 miles S. by E. of Rochefter, 6 from Berwick, in Maine, and 14 N. W. by N. from Portimouth. The Indians named it Winichahanat, and Cochecho; by the first fettlers; it was called Northam. It was incorporated in 1633, and contains 1998 inhabitants. The public buildings are a Congregational church, court-house and gaol. At Dover is a high neck of land, between the main branch of Piscataqua and Back R. about two miles long, and half a mile wide, rifing gently along a fine road, and declining on each fide, like a thip's deck. It commands an extensive and variegated profpect of the rivers, bays, adjacent thores, and diftant mountains. It has often been admired by travellers as an elegant figuation for a city, and by military gentlemen for a fortrefs. The first fettlers pitched here, but the trade has long fince been removed to Cocheco falls; and this beautiful fpot is almost deserted of inhabitants. N. lat. 43. 11. W. long. 70. 50.

DOVER, a township in Monmouth co. New Jersey, between Shrewsbury and New-Stafford, and extends from the sea to the county line. Although a large township, it contains only 910 inhabitants, who live mostly upon the sea-shore. There is but one church,

the property of a generous and benevolent individual; who gives liberty to minifters of all denominations to preach in it whenever they pleafes

DOVER, the metropolis of Delaware ftate, in Kent co. on the S. W. fide of Jones creek, about 41 miles N. W. from its mouth, in the Delaware; 12 miles from Duck creek, 48 from Wilmington, and 76 S. S. W. of Philadelphia. It contains about 100 houfes, built principally of brick. There are 4 ftreets, which interfect each other at right angles, in the centre of the town. The area included within thefe interfections extends into a spacious parade; on the E, fide of which is an elegant flate-house. The town has a lively appearance, and drives on a confiderable trade with Philadelphia, chief. ly in flour. N. lat. 39. 10. W. long. 75.34.

DOVER, a town in York co. Pennfylvania, on Fox Run, which falls into Conewago creek, near its mouth, in the Sufquehannah. It contains a German Lutheran and Calvinift church, united ; and about 40 houfes.

DOWNE, or Downs, a township in Cumberland co. New-Jersey.

DOWNS, a township of New-Jersey, in Cumberland county.

DOWNINGS, a post town of Pennfylvania, in Chefter co. on the E. fide of Brandywine creek; 33 miles W. by N. of Philadelphia, and near 7 N. W. of Westchefter.

DOYLSTOWN, a village in Bucks co. Pennfylvania, 10 miles S. W. of Howell's ferry, on Delaware R. 15 N. W. of Newton, and 33 W. by N. of Philadelphia.

DRACUT, a township in the northernmost part of Middlesex co. on the norn bank of Mernimack R. opposite Patucket Falls. It contains 1217 inhabitants, and lies 30 miles N. by W. of Boston, and 28. S. W. of Exeter, in New-Hampshire.

DRAKE, a harbour in California, fo called after the celebrated Sir Francis Drake, who difcovered and took pofferfion of the peninfula of California, for his miftrefs, Queen Elizabeth. N. lat. 28, 15. W. long, 111, 39.

DRAKE, SIR FRANCIS, or Drake's Bay, a bason in the middle of the Virgin ifles, in the Weft Indies, 3 or 4 leagues broad, and 6 or 7 long, the fineft

DUC

fineft that can be imagined; and in which fhips may anchor, landlocked, and fheltered from all winds.

DRESDEN, a township in Lincoln co. district of Maine, fituated 9 miles from Wiscasser Point, 15 from Fort Weston, at Hallowell, and 180 N. by E. of Boston. Swan island is in this township.

DRINNON'S Lick. See Jefferson's co. DROMORE, a township in Lancaster

co. Pennfylvania. DROWNED LANDS. See Orange co. New-York.

DRUMMOND, or Accomac courthoufe, in Virginia, is on the polt road from Philadelphia to Norfolk, 20 miles from Belhaven, and 194 from Philadelphia.

DRYDEN, a military township in the state of New-York, having Ulysse W. and Virgil on the E.; and on the S. the town of Owego, in Tioga co, The centre of the town lies 8 miles E. of the S. end of Cayuga Lake,

DRY TORTUGAS. See Toringa.

DUANESBURGH, a township in Albany co. New-York, containing 1470 inhabitants; of whom 260 are electors, and 5 flaves,

DUBLIN, a township in Cheshire co. New-Hampshire, on a branch of Ashuelot R. and N. of the Great Monadnock. containing 901 inhabitants. It is 28 miles S. E. of Charlestown, and 82 W. of Portsmouth. Incorporated in the year 1771.

DUBLIN, a pleafant town in Philadelphia co. Pennfylvania, 10 miles N. E. of Philadelphia, and as far S. W. of Briftol. Alfo, a township in Huntingdon co. in Pennfylvania.

DUCK, a river in Tenneffee, which rifes on the N. W. fide of the Cumberland mountain. It runs a N. W. courfe, and empties into the Tenneffee in N. lat. 36. W. It is 200 yards wide 5 miles from its mouth, which is 57 miles wefterly of Nafhville; and is boatable 90 miles.

DUCK-CREEK-CROSS-ROADS, or Salifbury, a confiderable thriving and post town in the flate of Delaware, fituated on Duck Creek, which in part divides Kent and Newcassle counties. It contains about 90 houses in one fireet, and carries on a confiderable trade with Philadelphia, and is one of the largest wheat markets in the flate. It lies 12 miles N. by W. of Dover, and 36 from Wilmington.

DUCKTRAP, a village in the district of Maine, where a post office is kept in Hancock co.; containing 278 inhabitants; 12 miles from Belfast and 32 from Penobleot.

DUDLEY, a township in Worcester co. Massachusetts, containing 1114 inhabitants. It is 18 miles southward of Worcester, and 55 miles S. W. of Boston.

DUKE's Co. in Maffachufetts, comprehends Martha's Vineyard I. Chabaquiddick I. Norman's I. and the Elizabeth iflands; fituated on the S. E. coaft of the ftate. The number of inhabitants is 3265. They fend 3 reprefentatives, and, in conjunction with Nantucket I. one fenator to the General Court. Thefe iflands are defcribed feparately. Chief town, Edgarton.

[•] DUMFRIES, a port of entry and poft town in Virginia, and chief town of Prince William co. It lies on the N. fide of Quantico creek, 4 miles above its entrance into the Potowmack, and to miles from Colchefter. Its public edifices are an Epifcopal church, a court houfe and gaol. The exports from this port for one year ending the 30th of Sept. 1794, amounted in value to \$5,635 dollars. It lies 28 miles N. by E. of Frederickfburg, and 185 S. W. of Philadelphia.

DUMMER Fort, is fituated on Connecticut R. in the town of Chefterfield, New-Hamp(hire.

DUMMER, a township in Grafton co., New-Hampshire, incorporated 1773. It is to the S. W. of lake Umbagog, on the waters of Upper Amonooluck and of Androscoggin rivers.

DUMMERSTON a township in Windham co. Vermont, N. of Brattleborough, containing 1501 inhabitans.

containing 501 inhabitans. DUNBARTON, a township in Hillsorough co. New-Hampshire, incorporated in 1765, and containing 917 inhabitants; 9 miles S. of Concord, and 53 W. of Portsmouth.

DUNCANSBOROUGH, a township of Vermont, on the W. ide of lake Memphremagog.

DUNDERBERG, in English, Thunder bill, is fituated on the W. fide of Hudfon R, at the S. E. entrance of the highlands, opposite Peek's Kill; and is remarkable for its echoes.

DUNCARD's Bottom, a tract of fine K 4 lands

DUR

lands on the E. fide of Cheat R. in Vir- | ly poifed on another rock as to be eafily ginia, about 22 miles from its mouth, and 49 W. S. W. from Fort Cumberland.

152

DUNKARD's Town. See Ephrata.

DUNLOPE, a fort on the W. bank of Little Miama R. about 12 miles above Columbia, in the N, W. territory

DUNSTABLE, a township in Hillsborough co. New-Hampshire, on the W. fide of Merrimack R. below the town of Merrimack, and separated by the state line from Pepperel and Dunstable in Middlefex co. Maffachufetts. It was incorporated in 1746, contains 632 inhabitants, and lies about 40 miles N. W. of Bofton.

DUNSTABLE, a township of Masiachufetts, in the northern part of Middiefer co. and on the fouthern bank of Merrimack R. It contains 380 inhabitants, and lies 37 miles N. wefterly of Bofton.

DUPAGE, a circular lake on the S.E. fide of Plein river, or rather an enlargement of the channel of that river, 5 miles from its mouth. Plein and Theakiki there form the Illinois.

DUPLIN Co. in Wilmington diffrict, North-Carolina, is bounded E. by Onflow, and S. W. by Sampson. The number of inhabitants is 5662 of whom 1383 are flaves. The chief town is Sarecto, on the N. E. branch of Cape Fear.

DU QUESNE, FORT. See Pittfburg. DURANGO, a town in the province of Zacatecas, and audience of Guadalaxara, in New Spain, 10 leagues from Nombre de Dios, and is a bifhop's fee, at the confluence of feveral rivers which render it convenient for trade.

DURHAM, a township in Cumberland co. district of Maine, on the S. W. bank of Androscoggin R. which feparates it from Bowdoin on the N.E. It was incorporated in 1789, contains 724 inhabitants, and lies 145 miles N. cafterly of Bofton. N. lat. 43. 55.

DURHAM, a post town in-Strafford co. New-Hampshire, on Oyster river, near where it joins the Piscataqua; 16 miles W. of Portfmouth. It was incorporated in 163, and contains 1247 inbabitants. It was formerly a part of Dover, which adjoins it on the N. and was called Oyfter river. On the top of a hill in this town is a rock, computed to weigh 60 or 70 tons, fo exact-

i setter

DUT

moved by one's finger. Its fituation appears to be natural.

DURHAM, a township in New-Haven co. Connecticut, fettled from Guildford in 1698, and incorporated in 1708. It is about 22 miles S. W. of Hartford, and 18 miles N. E. of New-Haven. It was called Cagingchague by the Indians; which name a fmall river that chiefly rifes here, ftill bears.

DURHAM, a township in Bucks co. Pennfylvania.

DUROT, a bay on the N. fide of the S. peninfula of the ifland of St. Domingo.

DUTCHESS Co. in New-York, is on the E. fide of Hudson R. It has the state of Connecticut on the E. West-Chefter on the S. and Columbia co. on the N. It is about 48 miles long and 23 broad, and contains 15 townships, of which Poughkeepfie and Fifh-Kill are the chief. It contains 45,266 inhabitants; of these 6013 are qualified to be electors, and 1856 are flaves. Dutchefs co. fends 7 reprefentatives to the affembly of the ftate. In the year 1792, a remarkable cavern was difcovered in this county, at a place called by the Indians Sepafcot, at Rhynbeck. A lad, by chance, paffing near its entrance, which lies between two huge rocks, on the declivity of a fteep hill, on prying into the gloomy receis, faw the top of a ladder, by which he descended about 10 feet, and found himfelf in a fubterraneous apartment, more capacious than he chose to investigate. He found, however, that it had been the abode of perfons, who probably during the war, had taken thelter here, as bits of cloth and pieces of leather were fcattered about its floor. It fince appears to be divided by a narrow paffage into two apartments; the first being about 17 feet in length, and fo low that a child of eight years old could but just walk upright in it; the breadth is about \$ or 10 feet. The fecond between 12 and 14 feet in length, but much higher and broader than the first. Like many other caverns in the United States, it poffeffes a petrifying quality; and the water, which is conftantly percolating through the roofs of its apartments, has formed a variety of transparent and beautiful stalactites. They have the appearance of icicles, and may be broken off

off by inches But the fkel to folid of the v with fo axe fro now in who er - free ai receffes refpiral very cle Dua feffion ces, no retain (the pro part of taken the Wi lic are fmall i and th which chiefly provifi Dut is boun by Cay try cal a Span 5. and coaft f to the menis ney, w acquifi empire It is di viz. Si Demer tricts, numbe provin quebo and (wide : 300 n navig differe Paran In ber, a health comm fevers y. 1 off by the hand, if not more than two inches in circumference.

Gly

ion

Ia-

08.

rd,

It

In-

hat

2000

.00

the

in-

on

the

ft-

on

nd

ps,

in-

ied

es.

to

ear

ca-

ed

k.

:h-

ge

on

he

ed

a

ci-

He

he

ng

its

at.

irs

ito

ild

lk

8

12

er

ny

ú

he

ng

as

nd

he

ēn

off,

But what is most to be admired is the fkeleton of a large fnake, turned into folid ftone by the petrifying quality of the water before mentioned. It was with fome difficulty torn up with an axe from the rock it lay upon, and is now in the poff-ffion of the gentleman who explored the cavern. A want of free air was experienced in the inmost receffes of the cavern, by a difficult refpiration, though the candles burnt very clear. The air alfo was very warm.

DUTCH AMERICA. The only poffeffion which the Seven United Provinces, now called the Batavian Republic, retain on the continent of America, is the province called Dutch Guiana. A part of thefe poffeffions have been lately taken by the English. The islands in the Weft-Indies belonging to the republic are St. Eustatius and Curaffou. The similar islands Bonaire and Aruba; which are appendages to Curaffou, and chiefly improved in raising cattle and provisions for that island.

Dutch Guiana, in South-America, is bounded N. by the Atlantic ocean ; E. by Cayenne; S. by an unexplored country called Amazonia; W. by Oronoko, a Spanish settlement. It lies between 5. and 7. N. lat. extending along the coaft from the mouth of Oronoko R. to the river Marowyne. Thefe fettlements were effeemed by admiral Rodney, who captured them in 1780, as an acquifition of more value to the British empire, than all their Weft-India iflands. It is divided into 3 diffinct governments, viz. Surrinam, Berbifch, Effequebo, and Demerara. The two last are two diftricts, forming one government. A number of fine rivers pais through this province; the chief of which are Effequebo, Surrinam, Demerara, Berbifch, and Canya. Effequebo is 21 miles wide at its mouth, and is more than goo miles in length. The others are navigable, and are defcribed under their different names. The chief towns are Paramabiro and Staebroeck.

In the months of September, October, and November, the climate is unhealthy, particularly to ftrangers. The common difeafes are putrid and other fevers, the dry belly-ache, and the dropfy. 100 miles back from the fea, you

come to quite a different foil, a hilly country, a pure, dry, wholefome air, where a fire fometimes would not be difagreeable. Along the fea coaft, the water is brackifft and unwholefomethe air damp and fultry. The thermometer ranges from 75. to 90. thro' the year. A north-east breeze never fails to blow from about 9 o'clock in the morning through the day, in the hotteft feafons. As the days and nights, throughout the year, are very nearly of equal length, the air can never become extremely heated, nor the inhabitants fo greatly incommoded by the heat, as those who live at a greater distance from the equator. The leasons were formerly divided regularly into rainy and dry; but of late years. fo much dependence cannot be placed upon them, owing probably to the cour try's being more cleared, by which means a free paffage is opened for the air and vapours. The water of the lower parts of the rivers is brackift. and unfit for ule; and the inhabitants are obliged to make use of rain water, which is here uncommonly fweet and good.

About 70 miles from the fea on the river Surrinam, is a village of about 40 or 50 houfes, inhabited by Jews. This village and the towns above mentioned, with the intervening plantations, contain all the inhabitants of this colony, which amount to 3,200 whites, and 43,000 flaves. The buildings on the plantations are many of them coftly, convenient and airy. The country around is thinly inhabited with the native Indians, a harmlefs friendly fet of beings. They are, in general, fhort of stature, but remarkably well made, of a light copper colour, ftraight black hair, without beards, high cheek bones, and broad fhoulders. In their ears, nofes and hair, the women wear ornaments of filver, &c. Both men and women go naked. One nation or tribe of them tie the lower part of the leg of the female children, when young, with a cord bound very tight for the breadth of 6 inches about the ancle, which cord is never afterwards taken off but to put on a new one; by which means the flefh, which fhould otherwife grow on that part of the leg, increases the calf to a great fize, and leaves the bone beylow nearly bare. This, though it muft render

render them very weak, is reckoned a great beauty by them. The language of the Indians appears to be very foft. They are mortal enemies to every kind of labour; but neverthelefs, manufacture a few articles, fuch as very fine cotton hammocks, earthen water pots, balkets, a red or yellow dye called Roucau, and fome other trifles, all of which they bring to town and exchange for fuch articles as they ftand in need of. They paint themfelves red, and fome are curioufly figured with black. Their food confilts chiefly of fifh and crabs and caffava, of which they plant great quantities, and this is almost the only produce they attend to. They cannot be faid to be abfolutely wander. ing tribes, but their huts being merely a few crofs flicks, covered with branches, fo as to defend them from the rain and fun, they frequently quit their habitations, if they fee occasion, and eftablish them elfewhere. They do not fhun the whites, and have been ferviceable against the runaway negroes.

DUT

154

On each fide of the rivers and creeks are fituated the plantations, containing from 500 to 2000 acres each, in number about 5 co in the whole colony, producing at prefent annually about 16,000 hads. of lugar, 12,000,000lbs. coffee, 700,000lhs. cocoa, 8 50,000lbs. cotton : All which articles (cotton excepted) have fallen off within 15 years, at leaft one third, owing to bad management, both here and in Holland, and to other caules. Of the proprietors of these plantations, not above 80 refide here. In the woods are found many kinds of good and durable timber, and fome woods for ornamental purposes, particularly a kind of mahogany called copic. The foil is perhaps as rich and as luxuriant as any in the world ; it is generally a rich, fat, clayey earth, lying in fome places above the level of the rivers at high water (which rifes about 8 feet) and in most places below it. Whenever from a continual course of cultivation for many years, a piece of land becomes impoverifhed (for manure is not known here) it is laid under water for a certain number of years, and thereby regains its fertility, and in the mean time a new piece of wood land is cleared. This country has never experienced those dreadful feourges of the | the latter are chosen by the governor

Weft-Indies, hurricanes : and droughts from the lowners of the land, it has not to fear; nor has the produce ever been deftroyed by infects or by the blaft. In fliort, this colony, by proper management, might become equal to Jamaica or any other. Land is not wanting; it is finely interfected by noble rivers, and abundant creeks; the foil is of the best kind, it is well fituated, and the climate is not very unhealthy, and is growing better, and will continue fo to do the more the country is cleared of its woods, and cultivated.

The rivers abound with fifh, fome of which are good; at certain feafons of the year there is plenty of turtle. The woods abound with plenty of deer, hares, and rabbits, a kind of buffaloe, and two fpecies of wild hogs, one of which (the peccary) is remarkable for having fomething like its navel on the back.

The woods are infefted with feveral species of tygers, but with no other ravenous or dangerous animals. The rivers are rendered dangerous by alligators from four to feven feet long, and a man was a fhort time fince crushed between the jaws of a fifh, but its name is not known. Scorpions and tarantulas are found here of a large fize and great venom, and other infects without number, fome of them very dangerous and troublefome. The torporific cel allo, the touch of which, by means of the bare hand or any conductor, has the effect of a ftrong electrical fhock. Serpents alfo, fome of which are venomous, and others, as has been afferted by many credible perfons, are from 25 to 50 feet long. In the woods are mon-keys, the floth, and parrots in all their varieties; alfo fome birds of beautiful plumage, among others the flamingo, but few or no finging birds.

The river Surrinam is guarded by a fort and two redoubts at the entrance, and a fort at Paramaribo, but none of them of any firength, fo that one or two frigates would be fufficient to make themfelves mafters of the whole colony a and never was there a people who more ardently wished for a change of go-vernment than the inhabitants of this colony. The interior government confifts of a governor and a fupreme and inferior council; the members of from

from a doub cipal inhabi mer in the powers, and over all crit cuted and la the interior those of a 1 ture are en require no

court. The cold about 1600 directors. a corps of by the cov corps of ch as the cour planters fro ed at pofts on a corde on the land fible, to de and the co tacks of runaway fl beginnings ficacy of th nual additi at fuch an country vel much lofs to do thefe This co French as and was al of its unh 1650 it wa men, and i by Charles confiderabl ment of ar driven out whofe de compofe at inhabitant ed great taken by having g time of th York, ea the Engli ed to Jan hind the English, underftoo At prefer fion of th DUTC DUT

from a double nomination of the principal inhabitants, and those of the former in the fame manner. By these powers, and by a magistrate presiding over all criminal affairs, justice is executed and laws are enacted necessary for the interior government of the colony; those of a more general and public nature are enacted by the directors, and require no approbation here by the court.

The colony is guarded farther by about 1600 regular troops, paid by the directors. These troops, together with a corps of about 250 free negroes, paid by the court here, and another imall corps of chaffeurs, and fo many flaves as the court thinks fit to order from the planters from time to time, are difperfed at posts placed at proper distances on a cordon, furrounding the colony on the land fide, in order, as far as poffible, to defend the diffant plantations and the colony in general from the attacks of feveral dangerous bands of runaway flaves, which from very fmall beginnings have, from the natural prolificacy of the negro race, and the continual addition of fresh fugitives, arrived at fuch an height as to have coft the country very great fums of money and much lofs of men, without being able to do these negroes any effectual injury.

This colony was first possefied by the French as early as the year 1630 or 40, and was abandoned by them on account of its unhealthy climate. In the year 1650 it was taken up by fome Englishmen, and in 1662 a charter was granted by Charles II. About this time it was confiderably augmented by the fettlement of a number of Jews, who had been driven out of Cayenne and the Brazils, whofe defcendants (with other Jews) compose at present one half of the white inhabitants of the colony, and are allowed great privileges. In 1667 it was taken by the Dutch, and the English having got poffeffion about the fame time of the then Dutch colony of New-York, each party retained its conqueft, the English planters most of them retired to Jamaica, leaving their flaves behind them, whole language is still English, but fo corrupted as not to be underftood at first by an Englishman .-At prefent this colony is in the poffeffion of the Britifh.

DUTCHMAN's Point, a point of land

on the Vermont fide of lake Champlain, about 16 miles S, of the Canada line. The British held a stockaded hut here, garrisoned by fix foldiers, fince the peace of 1783. It has fince been delivered up to the United States.

155

DUXBOROUGH, a maritime township in Plymouth co. Maffachufetts, incorporated in 1637. 20 veffels, the greater part from 60 to 90 tons, are owned here. It is a healthy town, and contains 1460 inhabitants; not a greater number than it contained 50 years ago. It lies S. by E. of Plymouth, 3 miles, acroi's Plymouth bay by water, and 8 round by land, and 38 S. E. by S. of Bofton. Within the harbour are Clarke's I. confifting of about 100 acres of excellent land, and Sauquish I. which was formerly joined to the Gurnet, by a narrow piece of fand; but the water has infulated it. The Gurnet is an eminence at the fouthern extremity of the beach, on which is a light-houfe built by the ftate. The Indian name of the town was Mattakeelet, or Namakeefet. It was fettled by capt. Standish and his affociates. The captain came to Plymouth with the first fettlers in 1620.

DUXBURY, a township in Hillsorough co. New-Hampshire, incorporated in 1763; first called Dantzick, joined with Sutton in the enumeration of 1775. It has only 169 inhabitants.

DUXBURY, a township in Chittenden co. Vermont, about 20 miles S. E. of Burlington, and contains 39 inhabitants.

in **E**

EARL, a township in Lancaster co. Pennsylvania.

EASTANALLEE, the north-eaft head branch of Alabama R. in Georgia, on which flands the town of Eaftanallee.

EAST BETHLEHEM, a township in Washington co. Pennsylvania.

EAST CHESTER, a township in West Chester co. New-York, on Long-Island sound, about 8 miles S. W. of Rye, 5 northerly of West Chester, and 17 N. E. of New-York. It contains 740 inhabitants; of whom 106 are electors, and 75 flaves.

EASTER, an ifle in the Pacific ocean. S. lat.

on-

me

of

lor

m

S. lat. 27. S. W. long. 109. 41. It is barren, and has no freih water. EASTERN Ifland, on the E. fide of

Chefapeak bay, at the mouth of Chefter river.

EASTERN-PRECINCT, in Somerset co. New-Jersey, contains 2068 inhabitants, of whom 468 are flaves.

EASTERN-RIVER, a fettlement in Hancock co. diftrict of Maine, containing 240 inhabitants.

EASTERTON, a village in Dauphin co. Pennfylvania, on the E. fide of Sufquehannah R. 4 miles N. by W. of Harrifburg, and 111 N.W.by W. of Philadelphia.

EAST FLORIDA. See Florida.

EAST GREENWICH, a post town and the chief township in Kent co. Rhode-Ifland; 16 miles S. of Providence, and 22 N. N. W. of Newport, and contains 1824 inhabitants. The compact part, called Greenwich town, has a number of dwelling-houfes, a meeting-houfe, and handlome courthouse ; and, although its commerce is greatly reduced, carries on the fifheries to advantage, and fends fome veffels to the Weff-Indies. It is fituated on the N. W. part of Narraganiet bay. Both this town and Warwick are noted for making good cyder; and formerly for raifing tobacco for exportation.

EAST HADDAM, a township in Middlefex co. Connecticut, situated on the E. side of Connecticut R. opposite to Haddam, of which it was formerly a part. It was settled in 1704, and lies 14 miles southwardly of Middleton, and 21 N. W. of New-London.

EASTHAM, a township in Barnstable co. Massachuletts, about 10 miles long, fituated on the peninsula of Cape Cod, between Chatham and Wellsleet, and 95 or 100 miles S. E. of Boston. It contains 1834 inhabitants.

EAST HAMPTON, a township in Himpshire co. Massachusetts, 6 miles S. of Northampton, and 105 W. by S. of Boston. It contains 457 inhabitants, and is divided from the W. bank of Connecticut R. by the celebrated mountain called Mount Tom.

EAST HAMPTON. a handlome town in Suffick cc. New York, on the S. E. coaft o Long-Ifland, 12 miles E. N. E. of South Hampton, and ros E. of New-York city. It has a Prefbyterian church, an academy, and about 80 dwelling-

魏帝 2

houses in one fireet. The township contains 1497 inhabitants, of whom 214 are electors. Gardner's Island is annexed to this town.

EAST HARTFORD, in Hartford co. Connecticut, lies on the E. bank of Connecticut R. opposite to Hartford. The compact part of it lies in one broad freet a mile and a half in length. Here are a number of hills on the different freams which water the town; also iron and glass works. EAST HAVEN, a township in New-

EAST HAVEN, a township in New-Haven co. Connecticut, on the E. fide of New-Haven harbour. There is a fort 2 miles from the mouth of the bay opposite Smith's point to defend the paliage. The Scotch Captain and other finall islots and rocks lie on the S. shore.

EAST HAVEN, a township in Effex co. Vermont, W. of Maidstone, 11 miles S. E. of the southern end of Willoughby's lake, and 18 N. by W. of the upper bar of the 15 mile falls on Connecticut river.

EAST KINGSTON, in Rockingham co. New-Hampfhire, a part of Kingfton; which fee. In 1790 it contained 358 inhabitants; and now 906.

EAST MAIN, is that part of New-Britain, or Labrador, in North-America, which lies on the E. fide of James's bay; as part of New South Wales on the W. fide of the fame bay is called WEST MAIN.

The Hudson's bay factory called East Main, is fituated on the S. part of East Main, between Rupert and Slade rivers, both of which run westward into James's bay.

EASTON, a post town of Pennsylvania, and capital of Northampton co. pleafantly fituated at the mouth of the Lehigh; and on the W. fide of Delaware R. It is regularly laid out, and contains about 150 dwelling houses, a church, court-house, register's office, and an academy. It is 12 miles N.E. of Bethlehem, and 70 N. of Philadelphia.

EASTON, the chief town of Talbot co. Maryland, formerly called Talbot Court-Houfe, is on the E. fide of Chefapeak bay, near the forks of Treadhaven R, 12 miles from its junction with Choptank R. It has a handfome court-houfe, and market-houfe; about 150 dwellinghoufes, and feveral flores for the fupply of the adjacent country. It is 5 miles S, wefterly of Williamfburg, 37 S, of Chefter

Chefter Town, and 118 S. W. of Philadelphia.

EASTON, a township in Washington co. New-York. In 1790 it contained a 539 inhabitants, of whom 48 were flaves. By the state census of 1796, it appears that 347 of its present inhabitants are electors.

EASTON, or Eastown, a township important for its iron manufactures, fituated in Briftol co. Maffachufetts, near the head of Raynham R.; 6 miles N. W. of Raynham, and 12 W. of Bridgewater. It contains 1466 inhabitants. The beft mill-faws in the ftate are made here. The art of making fteel was introduced here by Capt. Eliphalet Leonard, in 1786. It is made in quantities ; and is cheaper than imported steel, and equal in quality for large work, fuch as plough fhares, horfe fhoes, &c. which require large quantities of hard fteel. But for edge tools, in general, it is found to be of inferior quality to what is imported. The manufacture of linfeed oil began here in 1792, and from an annual flock of 3000 bufhels of feed, there has been annually produced near 5000 gallons of oil.

EASTON'S Beach and Bay, in the flate of Rhode-Island, is separated from Sachweaft beach and bay by Easton's point. Both lie at the southern end of Rhode-Island.

EAST R. in the ftate of New-York, and the waters of North or Hudson R. form York I. The communication between North R. and Long-Island found is by East R. along the eastern fide of New-York Island.

EAST OF NORTH HAVEN, or Quinepauge R. in Connecticut, rifes in Southington, not far from a bend in Farmington R. and paffing through Wallingford and North-Haven, empties into New-Haven harbour. It has been contemplated to connect the fource of this river with Farmington R.

EAST-TOWN, in Chefter co. Pennfylvania.

EAST-WHITELAND, a township in Chefter co. Pennsylvania.

EAST WINDSOR, a township in Hartford co. Connecticut; separated from Windsor by Connecticut R. and about 7 miles N. E. of Hartford. The compact part of the town lies on one broad street of about 2 miles in length. In the township are 3 Congregational

churches. The lands are fertile ; and befides those articles common to the ftate, produce large quantities of good tobacco.

EATON, a finall town in the northern part of Stafford co. New-Hampfhire; 3 miles N. of the Great Offipee lake, and about 56 N. by W. of Portimouth. It was incorporated in 1766, and contains 253 inhabitants.

EATONTOWN, improperly called Edentown, a pleafant village in New-Jerfey, about a mile S. of the town of Shrewfbury, in the fame townfhip. It is a place of fome bufinefs and thriving.

EBENEZER, a post town, and the capital of Effingham co. Georgia, feated on the S.W. bank of Savannah R. 5 miles from Abercorn, 25 N.N.W. of Savannah, 75 S. E. of Louifville, and 860 S. W. of Philadelphia. It contains but a few houses; and was settled in 1735, by a number of Protestants driven out of Saltsburg, in the Electorate of Bavaria, by perfecution.

EDEN, a township in Hancock co. district of Maine, incorporated in 1796, taken from the northerly part of Mount Defert.

EDEN, a township in Orleans co. Vermont, N. W. of Craftsbury, adjoining.

EDENTON, a diftrift on the fea-coaft of North-Carolina, bounded N. by the ftate of Virginia; E. by the ocean; W. by Halifax diftrift, and S. by Newhern. It is fubdivided into nine counties, viz. Chowan, Pafquotank, Perquimins, Gates, Hertford, Bertie, and Tyrrel. It contains 53,770 inhabitants, of whom 19,198 are flaves. Its chief town is Edenton. The wood is chiefly pine, oak, cyprefs, and juniper; of all which there is abundance.

EDENTON, the capital of the above diltrict, is a post town and port of entry, at the head of a bay on the N. fide of Albemarle found, and at the N. E. fide of the opening of Chowan R. It contains above 150 indifferent wooden buildings, and a few handfome ones. The public buildings are an ancient brick Episcopal church, a court-house and gaol. In or near the town lived the proprietary, and the first of the royal governors. Its fituation is advantageous for trade, but unhealthy; which doubtlefs has tended to retard its prosperity. Its exports in the year ending Saptember 30, 1794, amounted

157

whom land is

ford co. of Con-. The e broad . Here lifferent a; alfo

n New. E. fide is a fort bay opthe paid other f. fhore. n Effex ne, 11 of Wil-W. of falls on

ingham Kingfntained

New-Ameriames's ales on called

ed Eaft of Eaft rivers, ames's

nfylvaon co. of the Delat, and ufes, a ce, and E. of lphia. Talbot Talbot Chefathaven Chophoule, ellingfupply miles S, of

hefter

to the value of 50,646 dollars. It is 97 miles N. of Newbern, 257 N. N. E. of Wilmington, 139 S. S. E. of Peterf-burgh, and 440 S. W. of Philadelphia, N. lat. 36. 6. W. long. 77. 11.

EDESTON, a plantation in Hancock co. diffrict of Maine; containing 110 inhabitants.

EDGARTON, a port of entry and poft town of Maffachuletts, and the chief town of Duke's co. fituated on the E. fide of the ifland of Martha's Vineyard. The fertile island of Chabaquidick is within the jurifdiction of Edgarton ; which has a fmall trade to the West-Indies. The exports in 1794 for one year ending Sept. 30th, amounted to \$1257 dollars value. It lies about 14 miles S. of Barnftable co. on the main, and 94 miles S. S. E. of Bofton. It was incorporated in 1671, and contains 1352 inhabitants.

EDGCOMB, a township in Lincoln co. district of Maine, containing 855 inhabitants. It was incorporated in 1774, and lies 180 miles N. by E. of Bofton.

EDGCOMB, a county of Halifax diftrict, N. Carolina, bounded S. by Pitt co. S. W. by Wayne co. and Tar R. which affords it communication with feveral counties in the fate ; W. by Nath co. and E. by Martin and Halifax counties. It contains 10,255 inhabitants, of whom 2009 are flaves.

EDGEFIELD Co. in S. Carolina, is the fouthernmost in the district of Ninety Six; bounded N. by Saluda R. which divides it from Newbury co.; S. W. by Savannah R. which feparates it from the flate of Georgia; E. by Orangehurg diffrict, and W. by Abbeville co. The ridge of elevated land which divides the waters of Saluda from those of Savannah R. paffes nearly through the middle of the county. Edgefield co. is about 34 miles long and 24 broad, and contains 13,289 inhabitants, of whom 1619 are flaves.

EDGEFIELD COURT-HOUSE, in the above county, where is a post-office, is so miles from Abbeville court-house; 25 from Augusta and 60 from Columbia. EDGEMONT, a township in Delaware co. Pennfylvania,

EDISTO, or Ponpon, a navigable river in S. Carolina, which rifes in two branch-

on the N. fork, and form Edifto river; which, having paffed Jackfonburg, leaving it on the S., branches and embraces Edifto, and feveral fmaller ifles.

EDWARD, a fort in Nova-Scotia, in the town of Windfort in Hants co. faid to be large enough to contain 200 men. It is fituated on Avon R. which is navigable thus far for vellels of 400 tons ; those of 60 tons can go 2 miles higher.

EDWARD, a fortification in Washington co New-York, now in ruins. It is fituated on the E. bank of Hudfon R. about 14 miles S. by E. of Fort George; on the fouthern extremity of Lake George, and 19 S. by W. of Skenefborough, on South bay, an arm of lake

Champlain. N. lat. 43.7. W. long. 74. EEL Cove and River, L'anfe et la Riviere à l'Anguille, on the fouth fide of Chaleur bay, is about 3 leagues from, Maligath, about weft. This cove abounds with falmon, and great quantities of that fifh is taken annually, by a few inhabitants who are fettled here.

EEL RIVER Indians, inhabit the lands on Eel R. a head branch of Wahash R. They were lately hoffile; but ceded fome land at the mouth of the river to the U. States, at the treaty of Greenville, in 1795; when government paid them a fum of money, and engaged to pay them in goods, to the value of 500 dollars annually for ever.

EFFINGHAM, formerly Leavitfown, a township in Strafford co. New-Hampthire, S. E. of Offipee pond, on Offipee river, incorporated in 1766, and has 1 54 inhabitants.

EFFINGHAM Co. in the lower diffrict of Georgia, is bounded by Savannah R. on the N. eaftward, which leparates it from S. Carolina; by Ogechee R. on the S. weltward, which divides it from Liberty co. It contains 2424 inhabitants, including 750 flaves. Chief towns; Ebenezer and Elberton.

EGG-HARBOUR, a town in Globcefter co. New-Jerfey, on Great Egg Harbour; famons for the exportation of pine and cedar.

EGG HARBOUR R. GREAT AND LITTLE. Great Egg Harbourriver rifes between Gloucester and Cumberland counties, in New-Jerfey. After run-ning E.S.E. a few miles it becomes the es from a remarkable ridge in the inte-rior part of the flate. These branches unite below Orangeburgh, which flands divisional line between Cape May and Gloucester counties, and falls into the bay of its own name. The islet from the the the Atlan river abo fifh, perc find a r This riv veffels of Little 77 miles Inlet. I rifes in G ties, and a few mi ble 20 mi townfhip lington (acres; th and barro The con called C meetingdozen ho the Weff captains a number in Little the place Ecc . E. fide o land co. EGMO cific oces The Spi S. lat. 1 wich 16. EGRE thire co. inhabita miles S. W. of E EIGH the coalt Little E Barnega ELBE diftrict o between S. E. co confluen On the l lin coun ELBE above ci burg, a houfe. ELBE ham co. Ogeeche It is ab

48 N. 1

the Atlantic ocean lies in 39. 22. The river abounds with theepfhead, rock-fifh, perch, oyfters, clams, &c. which find a ready market at Philadelphia. This river is navigable 20 miles for veficls of 200 tons.

iver:

eav-

races

a, in

faid

nen.

navi-

ons ;

her.

ing-

It is

n R.

orge,

Lake

efbo-

lake

. 74.

et la

de of

from

cove

anti-

by a

lands

hR.

ceded

er to

reen-

paid

ed to

500

own.

amp-

flipce

l has

Aria

hR:

es it

t. on

from

habi-

wns;

Flot-

Egg

ion of

AND

rrifes

rland

run-

es the

y and

to the

from

the

e.

Little Egg Harbour Inlet, lies about 17 miles N. E. of Great Egg Harbour Inlet. It receives Mulicus R. which rifes in Gloucefter and Burlington counties, and forms part of the divisional line a few miles from the bay. It is navigable 20 miles for veffels of 60 tons. The townflip of Little Egg Harbour, in Burlington co. confilts of about 23,000 acres; the most of which, being thin and barren, is not under improvement. The compact part of the township is called Clam Town, where there is a meeting-house for Friends, and about a dozen houfes. It has a fmall trade to the Weft. Indies. During the late war captains Ferguion and Collins burnt a number of privateers and other veffels in Little Egg Harbour, and deftroyed the place.

Eog Mand, a fmall iAand on the N. E. fide of Delaware bay, in Cumberland co.

EGMONT, an island in the South Pacific ocean, discovered by capt. Carteret. The Spaniards called it Santa Cruz. S. lat. 19. 20. E. long. from Greenwich 164. 30.

EGREMONT, a township in Berkshire co. Maffachusetts, containing 759 inhabitants incorporated in 1760-15 miles S. W. of Stockbridge, and 145 W. of Bolton.

EIGHTEEN-MILE, or Long Beach, the coalt of New-Jersey, lies between Little Egg Harbour inlet, and that of Barnegat.

ELBERT, a new county, in the upper district of Georgia, on the tract of lan. between Tugulo and Broad rivers. The S. E. corner of the county is at their confluence, at the town of Petersburg. On the N. W. it is bounded by Franklin county.

ELBERTON, the feat of justice in the above co. is 23 miles N. W. of Peterfburg, and 30 S. E of Franklin courthouse.

ELBERTON, a post town in Effingham co. Georgia, on the N. E. bank of Ogeechee R. containing about 30 houfes. It is about 19 miles W. of Ebenezer,

long. 80. 30.

ELUTHERA, or Alabaster, one of the Bahama or Lucaya iflands, where above 60 families formerly fettled under Dep. Gov. Holmes, and crected a fmall fort.

ELIAS, MOUNT ST. a mountain near the shore of the N. W. coast of North-America, N. W. of Admiralty Bay, and S. E. of Prince William's found.

ELIZABETH, CAPE. See Cape Elizabeth and Cafco Bay.

ELIZABETH CITY Co. in Virginia, lies between York and James rivers, having Warwick and York counties on the W. and Chefapeak bay on the E. and N. There are feveral fmall iflands on its fea-coaft, the chief of which are Long and Egg islands. Point Comfort is the S. eaftern extremity of the co. It contains 3450 inhabitants, of whom 1876 are flaves.

ELIZABETH Iflands, feveral fmall islands on the S. E. fide of Buzzard's bay, extending S. wefterly from the extremity of Barnstable co. in Massachufetts, and bearing N. W. from Martha's Vineyard; fituated between 41.24. and 41. 32. N. lat. and between 70. 38. and 70. 56. W. long. They are about 16 in number; the chief of which are Nathawn, Pafqui, Nathawenna, Pinequefe, and Chatahunk islands. All these belong to Duke's county.

ELIZABETH, a fhort fouthern arm of James R. in Virginia. It affords an excellent harbour, and large enough for 300 fhips. The channel is from 150 to 200 fathoms wide; and at common flood tide it has 18 feet water to Norfolk, which flands near the mouth of its eaftern branch. The S. branch rifes in the Difinal Swamp. Craney island, at the mouth of Elizabeth, lies 5 miles S. W. of Point Comfort, at the mouth of James river.

ELIZABETH'S ISLAND, QUEEN, in the straits of Magellan, in S. America. Here fresh water, herbs fit for fallad, and wild fowl may be had in great plenty. The thores also abound with fhell-fifh.

ELIZABETH, a township in Lancaster co. Penniylvania, containing about 30 houfes, and a Dutch church ; 18 miles N. W. by W. of Lancaster, and 84 W. by N. of Philadelphia.

ELIZABETHTOWN, a post town and 48 N. W. of Savannah, and 55 S. E. | borough, in Effex county, New-Jerfey ; pleafantly

pleafantly fituated on a fmall creek which empties into Arthur Kull. Its foil is equal to any in the ftate. In the compact part of the town, there are about 150 houfes, two brick churches, one for Prefbyterians, very handfome, the other for Epifcopalians, and an academy. This is one of the oldeft towns in the ftate, having been purchafed of the Indians as early as 1664, and fettled foon after. It lies 6 miles foutherly of Newark, and 15 S. W. by W. of New-York.

ELIZABETHTOWN, a village of Alleghany co. Pennfylvania, fituated on the S. E. fide of Monongahela R. between Redftone Old Fort, and Pittfburg, about 18 miles from each, and 6 above the mouth of the Youghagany. Many heats are built here for the trade and emigration to Kentucky, and in the environs are feveral faw mills. N. lat. 40. 13. W. long. 79. 22.

ELIZABETHTOWN, a post town of Maryland, and capital of Washington co. formerly called Hagarstown, seated in the fertile valley of Conegocheague. It has feveral fireets regularly laid out. The houses are principally built of brick and ftone, in number about 300. Epifcopalians, Prefbyterians, and German Lutherans have each a church. The cours-house and market-house are handfome buildings, and the gaol is of stone, and fubftantial. The trade with the weftern country is confiderable; and there are a number of mills in the neighbourhood, on Antietam creek. See Hagarfown.

ELIZABETHTOWN, the chief town of Tyrrel co. in Edenton diffrict, North-Carolina, has a gaol, court-houfe, and a few dwelling-houfes. It is 40 miles from Fayetteville, and 55 from Wilmington.

ELIZABETHTOWN, a post town and the chief in Bladen co. N. Carolina, is fituated on the N. W. branch of. Cape Fear. It contains a court-house, gaol, and about 30 houses; 36 miles southward of Fayetteville, and 47 N. W. of Wilmington.

ELK, a creek in Northumberland co. Pennfylvania, which uniting with Penn's creek, falls into the Sufquehannah, 5 miles below Sunbury.

ELK, a navigable river of the eastern fhore of Maryland, which rifes in Chefter co. Pennfylvania, by two branches ; Big and Little Elk creeks. At their confluence flands Elkton. The canais in contemplation from Elk R, to Delaware bay, are noticed under Delaware bay.

ELK, a fhort navigable river, in the flate of Tenneffee: It rifes on the N. W. fide of Cumberland mountain, runs S. wefterly, and falls into the Tenneffee a little above the Muscle shoals; about 40 miles W. N. W. of the Creeks' Crofling Place.

ELKHORN, a finall water of Kentucky river. The Elkhorn lands are much effected, being fituated in a bend of Kentucky river, in Fayette co. in which this finall river, or creek, rifes.

ELK Lake, one of the chain of finalt lakes which connects the lake of the Woods with lake Superior. N. lat. 48.41. W. long. 93. ELKRIDGE, a finall town in Ann

ELERIDGE, a finall town in Ann Arundel co. Maryland, fituated on the S. bank of Patapico R. and on the W. fide of Deep Run. This place is famous for the bright tobacco called *kite's foot*. It is 8 miles S. W. of Baltimore, and 19 N. W. of Annapolis. N. lat. 39. 12. 30:

ELKTON, a post town of confiderable trade, at the head of Chefapeak bay, in Maryland, and the capital of Cecil co. It is fituated at the confluence of the head branches of Elk R. 13 miles from its mouth at Turkey Point, and a mile above French town. The tide flows up to the town, and it enjoys great advantages from the carrying trade, between Baltimore and Philadelphia, Upwards of 2 50,000 bufhels of wheat are collected here annually, for fupplying those markets, or the neighbouring mills. Elkton confifts of one ftreet, in which are about 90 houfes, a court-houfe, and gaol. On the W. fide of the town is an academy. It is 12 miles S. W. of Chriftiana bridge, 10 N.E. of Charleftown, 47 S. W. of Philadelphia, and 56 N. E. of Baltimore.

ELLINGTON, a township of about 200 families, in Tolland co. Connecticut. It lies about 12 miles N. E. of Hartford city, and 6 W. of Tolland.

ELLIS R. in the diffrict of Maine, is a branch of Saco river.

ELMORE, the fouthernmost township in Orleans co. in Vermont; and contained, by the cenfus, only 12 inhabitants.

EMERY'S

500 to employe the We place bi The pu al churc priated capacion public o at prefei eter aca tchool, a ly for fe This and abo corporat it had from the rate the where th chiefly o Thenur 174 miles N Philade "Ph founded Phillips porated It is a 1 fitution board o governn tor and £.15,00 not yet nual inc monly b 1794, a feet, tw of conve is excee kind in Exer thip in ftate, ha Volunto The fev here, a Hopkin 2495 inl EXE1 Pennfyl EXET in Wil fituated Fear, ab ton, and

Exu.

heit nais elavare the N. uns effee pout eks'

tucinch d of hich mall the lat.

Ann the w. faalled Balolis.

able bay, co. the rom mile s up vanween ards lecthofe ills. hich and n is . of

rlefd 56 bout ecti-E. of d.

hip conabit-RY's

e, is

EXU

500 tons. An equal number is alio employed in the foreign trade, chiefly to the West-Indies. The situation of this place bids fair for extensive population. The public edifices are 2 Congregational churches, an elegant building appropriated for the academy, a handlome and capacious court-house, and a gaol. The public offices of the ftate are kept here at prefent. Befides the celebrated Ex. eter academy, there are here an English ichool, and 6 or 8 private schools, chiefly for females.

This township is of irregular figure, and about 4 miles square. It was incorporated in 1638; prior to which, it had the name of Swamfcot Falls, from the falls of the river, which feparate the fresh from the tide water; where the body of the town is fituated; chiefly on the western fide of the river. The number of inhabitants in 1775, was 1741-and in 1790, 1722. It lies 54 miles N. of Bofton, and 402 N. E. of Philadelphia. N. lat 42. 59. W. long. 71. "Phillips Exeter Academy" was founded and endowed by the hon. John Phillips, LL. D. of Exeter, and incorporated by act of Affembly in 1781, It is a very respectable and useful inflitution, under the inspection of a board of truftees, and the immediate government and instruction of a preceptor and an affiftant. It has a fund of f.15,000, a part of which is in lands not yet productive. The prefent annual income, is £.480. It has commonly between 50 and 60 ftudents. In 1794, a building was erected, 76 by 36 feet, two ftories high ; which in point of convenience, and perhaps elegance, is exceeded by few buildings of the kind in the United States.

EXETER, the N. westernmost townthip in Wathington co. Rhode-Ifland ftate, has North-Kingston on the E. and Voluntown, in Connecticut, on the W. The feveral branches of Wood R. unite here, and take a S. course between Hopkinton and Richmond. It contains 2495 inhabitants, of whom 37 are flaves. EXETER, a township in Luzern co.

Pennfylvania. EXETER, a town in New-Hanover co. in Wilmington district, N. Carolina; fituated on the N. E. branch of Cape Fear, about 36 miles N. from Wilmington, and 22 from the N. river.

FAI

365

fituated on the E. of the Great Bank, between Stocking ifles on the S. W. and Long-ille on the E. Is is now minhabited, excepting two families, yet is one of the best of the Bahamas, not only for its fertility, but for the excellence of its anchoring ground, in the Sound to which it gives name; where all the British navy could ride in fafety. N. lat 24. 30. W. long. 74. 30.

EXUMA Sound, lies E. of the Great Bahama Bank, between it and the ifle of Guanahani. N. lat. 24. W. long. 75.

F 在当时期的 水口 经制度的运行 网络

FABIANE, a river in Louifiana, which runs S. eaftward into the Miffifippi, in N. lat. 39. 30.; 16 miles above Jaftioni R. and 50 below the Iowa town and rapids.

FABIUS, one of the military townthips in New-York.

FAIRFAX Co. in Virginia, is about 25 miles long, and 18 broad; on the W. bank of Potowmack river. It contains 12,320 inhabitants, of whom 4574 are flaves. Chief town, Alexandria. FAIRFAX, a township in Franklin co. Vermont, E. of Georgia, and on the bank of La Moille R. and contains 254 inhabitants; and is about 9 miles from lake Champlain.

FAIRFIELD, a plantation in Lincoln co. district of Maine, on the S. E. bank' of Kennebeck R. S. of Canaan, and oppolite Hancock; about 17 miles fry Pittftown, and 7 from Fort Halifax, contains 492 inhabitants, and is 225 miles N. E. of Bofton.

FAIRFIELD, a new township in Herkemer county, New-York.

FAIRFIELD, a township in Franklin co. Vermont, E. of St. Alban's; and contains 129 inhabitants. It is 13 miles S: of the Canada line, and as far from the nearest part of lake Champlain.

FAIRFIELD, a township in Washington co. New-York. By the ftate cenfus of 1796, 29 f its inhabitants are electors.

FAIRFIELD, a township in Cumberland co. New-Jerfey, on Cohanzy creek, and at the head of Black creek; 25 miles S. by E. of Salem, in Salem co.

FAIRFIELD Co. in Connecticut, is the EXUMA Ifle, one of the Bahama ifles, S. westernmost in the state; bounded

W. by the ftate of New-York, E. by New-Haven co. N. by Litchfield, and S. by Long-Ifland found. It's fhape is very irregular. It is divided into 13 townfhips, of which Fairfield and Danbury are the chief; and contains 36,250 inhabitants including 433 flaves. It is feparated from New-Haven co. and part of Litchfield co. by Stratford R. The other parts of the country are watered by fmall fireams, as Sagatuck, Salco, Peganook, Five Mile, Rodens, Mill, and Mayamus rivers. Several harbours, and a number of fmall ifles lie along the found, in the towns of Greenwich, Stamford, Norwalk, Fairfield, and Stratford. The face of the county is rough, but the foil is good.

FAIRFIELD, the Unquowa of the Indians, a polt town and port of entry of Connecticut, and capital of the above county, is pleafantly fituated on Mill-Run, a little above its entrance into Long Ifland found, 22 miles S. W. by W. of New-Haven, and 64 From New-York. It contains about 200 houfes, a neat Congregational church, and a court-houfe. About 4 miles N. W. of the body of the town, and in the townfhip is the beautiful parish of Greenfield, in which is a flourishing academy. A high eminence in the centre of the parish commands a delightful prospect, Fairfield was settled from Weathersfield in 1639, and in 1736 contained 400 families. It was burnt by a party of tories and British, under the command of gov. Tryon, in 1777; the loss fuftained, amounted to upwards of 6.40,000. Fairfield carries on a confiderable trade to the W. Indies. The exports for one year, ending Sept. 30th, 1794, amounted to 77,425 dollars,

FAIRFIELD, a township in Westmoreland co. Pennsylvania,

FAIRFIELD Co. in Camden diffrict, S. Carolina, between Wateree R, which divides it from Lancafter co. and Broad R. which feparates it from Newbury and Union counties. It contains 6138 white inhabitants, and 1485 flaves. Its chief town is Winfborough.

FAIRHAVEN, in Brittol co, Maffachuletts, lies on the N, W. fide of Buzzard's bay, and on the eaftern fide of Acculanter river, oppointe to Bedford; when fee.

FAIRHAVEN, a confiderable townthip in Rutland co. Vermont, N. W. of

Poultney. It contains 545 inhabitants, and is 54 miles N. of Bennington.

FAIRLEE, a townfhip in Orange co. Vermont, on the W. bank of Connecticut R. 16 miles N. of Dartmouth College. The townfhip is hilly, but of a good foil, and has feveral glades of excellent land. It contains 463 inhabitants.

FAIR WEATHER, CAPE, on the E. coaft of Patagonia, in S. America, lies northerly from Cape Virgin Mary. S. lat. 51. 45. W. long. from Greenwich 68. 10.

FALKLAND Ifes, lie at no great diftance from the ftraits of Magellan, at the utmost extremity of S. America, between 50. and 56. W. long. and 51. and 53. S. lat. These islands were difcovered by Sir Richard Hawkins, in 1594; the chief of the two islands he named Hawkins' Maidenland, in honour of Queen Elizabeth. The foil of thefe illands is had, and the fhores are beaten by perpetual forms. A British fettlement was made here, of which they were dispossefied by the Spaniards, in 1770, foon after it had been offablished. The Spaniards now fend criminals to thefe inhospitable shores from their settlements in America.

FALL R. is an inconfiderable fream, rifing in Watuper Pond, in Rhode-Ifiand, and after a fhort N. W. courfe, empties into Taunton river.

FALLS, a township in Bucks county, Pennfylvania.

FALLEN CITY, or Old Jerufalem, a range of rocks among the Virgin ifles in the Weft-Indies, S. W. of Virgin Gorda. N. lat. 18. 10. W. long. 62. 53.

FALLING Spring, a branch of James R. in Virginia, where it is called Jackfon's river, rifing in the mountain 20 miles S. W. of the Warm Spring. The water falls over the rock 200 feet, which is about 50 feet higher than the fall of Niagara. Between the fheet of water and the rock below, a man may walk acrofs dry.

FALMOUTH, a township, formerly including Portland, in Cumberland co. Maine, containing 2991 inhabitants. It is fituated on Calco bay, 136 miles N. N. E. of Boston. Incorporated in 1718.

FALMOUTH, a township in Hants co. Nova Scotia; fituated on the S. E. fide of the Bafin of Minas opposite Windlor, 28 miles N. W. of Halifax. FALMOUTH, a maritime township in Barnstable

Barnftal on the N on the y 77 miles Sandwig It was tains 16 33 W. 1 FALN co. Virg Rappah: Frederic and cor and abou S. W. c Richmo ladelphi tobacco FALN Penniyl of Cona Lancalte FALM the S. fh the Wef on the E W.; an at the N which is FALN ca, in tl ed the F of Martl the adio and the houfes. load for floops an FALS point of FALSI vania, in Philadel FAMI the N. E lan, in garrifon time it h 44. W. FANN Pennfyls FAQU 'ed N. t William and 20 b habitant FARE Weft G entrance

Barnstable co. Massachusetts, fituated on the N. E. part of the Vineyard found, on the W. fide of the bay of its name; 77 miles S. E. by S. of Boston, 18 from Sandwich, and 9 from Holme's Hole. It was incorporated in 1686, and contains 1637 inhabitants. N. lat. 41. 33 W. long. 70. 35. 'It is a post town. FALMOUTH, a post town in Stafford

ts,

.00

ti-

ol-

fa

ex-

nit-

E.

lies

S.

lich

dif-

ica,

51.

dif-

in

he

lour

hefe

aten

ttle.

vere

770.

The

e in-

ents

am,

-10-

urfe,

nty,

m, a

ifles

irgin

- 53. ames

ack-

miles

vater

18 2-

Nia-

d the

dry.

nerly

d ça.

s. It

bs N.

1718.

lants

S. E.

polite

lifax.

nip in

stable

21

co. Virginia, fituated on the N. bank of Rappahannock river, nearly opposite to Fredericksburg. It is irregularly built, and contains an Episcopalian church and about 150 houses. It is 23 miles S. W. of Dumfries, 70 N. by E. of Richmond, and 207 S. westerly of Philadelphia. Confiderable quantities of tobacce are inspected here.

FALMOUTH, a town in Lancaster co. Penniylvania, fituated on the S. E. side of Conawago creek, 20 miles westerly of Lancaster. It has been lately laid out. FALMOUTH, a town and harbour on the S. shore of the island of Antigua, in the West-Indies. It has English harbour on the E. and Rendezvous bay on the W.; and situated in St. Paul's parish, at the N. W. corner of the harbour, which is well fortified.

FALMOUTH, in the island of Jamaica, in the Weft Indies, commonly called the Point, is fituated on the S. fide of Martha Brae harbour; and including the adjoining villages of Martha Brae and the Rock, is composed of 220 houses. Here 30 capital stationed ships load for Great Britain, exclusive of sloops and smaller craft.

FALSE Cape Horn, the fouth-western point of Terra del Fuego.

FALSINGTON, a village in Pennfylvania, in Bucks co. 28 miles N. E. of Philadelphia.

FAMINE Port, a fortrels feated on the N. E. coaft of the ftraits of Magellan, in S. America. Here a Spanish garrifon perished for want; fince which time it has been neglected. S. lat. 55. 44. W. long. 70. 20.

FANNET, a township in Franklin co. Pennsylvania.

FAQUIER Co. in Virginia, is bound ed N. by Loudon and E. by Prince William. It is about 55 miles long and 20 broad, and contains 17,892 inhabitants, of whom 6642 are flaves.

FAREWELL, CAPE, the SI point of West Greenland, on the N. fide of the entrance of Davis's straits; North America. N. lat. 59. 37. W. long. 42. 42. FARMINGTON, a very flourifhing township of excellent land, in Lincoln co. district of Maine, on Sandy river, 35 miles N. W. of Hallowell, 30 fame course from Harrington, and 204 N. N. E. of Boston. Number of inhabitants, about 1200. A very few years fince this township was a wildernes.

FARMINGTON, a large, pleafant, and wealthy town in Hartford co. Connecticut, 10 miles S. W. of Hartford city, 32 N. E. of New-Haven, and 22 E. of Litchfield. Farmington river, a water of Connecticut, meanders delightfully through charming intervales, which beautify and enrich this town. The houses, in the compact part of this town, fland chiefly on a fireet which runs N. and S. along the gentle declivity of a hill, which alcends E. of the intervales; about the centre of the freet ftands a large and handfome Congregational church. This town was fettled as early as 1645, and its limits then were very extensive. Several towns have been fince taken from it.

FARMINGTON, a finall river of Connecticut, which paffes through the town of Farmington, where it receives Cambridge or Poquabock R, from the S. W. when it acquires the name of Windfor R. and falls into Connecticut R, in the town of Windfor, about 4 miles above Hartford city.

FAVOURABLE Lake, in N. lat. 52.48. W. long. 93. 10. is the fource of two large rivers, at the mouth of one of which, emptying into Winnipeg lake, ftands the Canadian house. The other is the S. W. branch of Severn river.

FAWN, a township in York co. Pennfylvania.

FAYETTE, a fettlement in Tioga co. New-York, between the Unadilla and the main branch of the Chenengo. It is laid out into 100 lots of a fquare mile each, as nearly as the ground will permit.

FAYETTE Co. in Pennfylvania, is bounded N. by Weftmoreland, S. by part of Maryland and Virginia, and W. by Monongahela R. It is 39 miles in length and 29 in breadth, and contains 473,280 acres; divided into 31 townfhips, of which Union is the chief. The number of inhabitants is 13,325, of whom 282 are flaves.

FAYETTE, a district of N. Carolina, L 4 comprehending

comprehending 6 counties, viz. Moore, Cumberland, Sampion, Richmond, Robefon, and Anion. It is bounded N. by Hillfborough, S. E. by Wilmington and Newbern, W. by Salifbury, and S. by the ftate of S. Carolina. It is 120 miles in length, and 50 in breadth, and contains 34,020 inhabitants, of whom 5,678 are flaves.

168

FAYETTEVILLE, fo called in honour of the Marquis La Fayette, a flourishing polt town of North-Carolina, the feat of juffice for the above diffrict, and pleafantly fituated in Cumberland co. on the W. fide of the N. W. branch of Cape Fear R. nearly at the head of navigation, and 100 miles above Wilmington, and 61 foutherly of Raleigh. On the bank of the river, ftand a few buildings and the tobacco warehoufes, which have received in one feafon 6000 hhds. of tobacco, equal in quality to that of Petersburgh. The compact part of the town is fituated about a mile from the river, near the junction of Blount's and Crois creek ; on which laft it is chiefly erected, and from that circumstance was formerly named Crofs Creek. On both fides the creek are about 400 houses, 2 handsome edifices for the fupreme, district, and county' courts, and the meetings of the town officers and its citizens. The Free Mafons' lodge is alfo a large and handfome building. The town is regularly laid out, and its principal ftreets are 100 feet wide. Here are three mills, two confiderable diffilleries and breweries, and feveral extenfive tan yards. The trade to Wilmington is very confiderable, to which it fends down tobacco, wheat, flour, beef, pork, flax-feed, hemp, cotton, butter, lumber, flaves, naval ftores, &c. The boats used in transporting these articles to Wilmington, contain about 120 barrels, and make their returns of European and India goods, &c. in from 10 to 20 days. The fituation of the town is agreeable and healthy, and well adapted for establishing manufactories. The country immediately round the town is confiderably elevated, and the foil dry and barren; but near the water courses, which are numerous, the foil is as rich as any in the ftate. Since the fire in 1792, which deftroyed many houfes, the people begin to build with brick, which are here made of a good quality, and fold reafonably. The town ftands

in a fettlement of Scotch Highlanders, and is 55 miles N. W. of Camden in S. Carolina, 100 S. W. of Tarborough, 147 S. W. by S. of Halifax, 379 S. by W. of Wathington city, and 526 S. W. by S. of Philadelphia.

FAYETTE, a co. of Kentucky, furrounded by Clarke, Bourbon, Scott, Franklin, Woodford, Madditon, and Mercer counties. Chief town Lexington.

FAYSTOWN, a township in Chittenden co. Vermont, uninhabited in 1790.

FEAR POINT, CAPE, at the mouth of Cape Fear R. in N. Carolina, 4 miles S. S. E. of the light-house on Bald Head.

FEDERAL City. See Washington city. FEDERALSBURG, a village in Maryland, on the E. fide of Chefapeak bay, fituated on Marshy Hope creek, partly in Dorchefter and partly in Caroline co. 5 miles E.N.E. of Hunting-Creek town, and about 20 N. E. of Cambridge.

FE D'ANTIOCHIA, SANTA, the molt northern town of Popayan, a diffrict of Terra Firma, S. America. It is fituated 200 miles N. of Popayan city, near the confines of the province of Carthagena, on the banks of St. Martha river, and near 180 miles S. of its conflux with the Magdalena. Thither the inhabitants removed from Antiochia, 15 leagues from it, now an inconfiderable place, whereas Santa Fe d'Antiochia is a confiderable place, and capital of the audience of Santa Fe.

FE DE BAGOTA, SANTA, the capital of New-Granada, S. America, fituated on the banks of the little river Pati, a water of the Magdalena; is 180 miles E. of the bottom of Bonaventura bay. It is an arch-bifhop's fee, and the feat of an university founded by king Philip III. in 1610. Near this city are gold mines. The air is temperate and healthful, and provisions plenty. S. lat. 4. 10.W. long. 74. 5.

FE, or FOY, SANTA, a place in the middle of Veragua, a province in the audience of Guatimala, in North America, where the king of Spain keeps officers for cafting and refining gold. It ftands at the fource of a river which runs into the North Sea.

FE, SANTA, the capital of New-Mexico, in N. America. It is fituated near the fource of Rio del Nort, 130 leagues from its mouth, in the gulf of Mexico, EME fee, whi 7 miles river. EMM miles fr

EMM flourithi ryland, Tom's the Mo the Pen N. E. I

W. of 30. ENCI

fee. END times a tains.

END the N. S. coaff E. long

ENFI Connect necticut bounded fetts lin of Maffa and was contained

town ar and a m compact to the n or 18 m

ENFI New-H of Dart

porated ants, cl ENG. Cape, in

and of erly of of Cape N. lat.

25. ENG harboun the S. 1 of Faln fied, an fenal, v fhips o long, 6 ENG

lage in

EMERY'S R. a fmall river in Tenneffee, which runs S. E. into the Tenneffee, 7 miles N. by E. of the mouth of Clinch river.

in

gh, by

w.

ur-

ott,

and

ng-

en-

90.

uth

on

ity.

IFY-

ay,

rtly

có.

wn,

noft

t of

itu-

near

tha-

ver.

with

bit-

zues

ace,

míi-

udi-

api-

tua-

ati,

niles

bay.

feat

hilip

gold'

. 4.

1 the

1 the

me-

s of-

runs

Mex-

near

gues

xiço,

It

EMMAUS, a Moravian fettlement, 8 miles from Bethlehem, in Pennfylvania.

EMMITSBÜRG, or Emmifburgh, a flourithing village in Frederick co. Maryland, fituated between Flat Run and Tom's creek, weftern head waters of the Monococy, and about a mile S. of the Pennfylvania line. It is 24 miles N. E. by E. of Frederick, and 50 N. W. of Baltimore. N. lat. 39. 10. 30.

ENCHANTED Mountain, See Tenneffee.

ENDLESS *Mountains*, a name fometimes applied to the Alleghany mountains.

ENDEAVOUR Straits, are between the N. point of New-Holland, and the S. coafl of New-Guinea. S. lat. 10, E. long. from Paris 140.

ENFIELD, a township in Hartford co. Connecticut, on the E. bank of Connecticut R. opposite to Suffield, and bounded on the N. by the Maffachufetts line: It was granted by the court of Maffachufetts, to Springfield, in 1648, and was fettled in 1681. In 1769 it contained 214 English families. In the town are two Congregational churches, and a meeting-house for Shakers. The compact part of the town, contiguous to the river, is very pleasant. It is 16 or 18 miles N. of Hartford.

ENFIELD, a township in Grafton co. New-Hampshire, about 11 miles S. E. of Dartmouth College. It was incorporated in 1761, and has 724 inhabitants, chiefly farmers.

ENGANNO, TROMPEUR, or Falfe Cape, is the eafternmost land of the ifland of St. Domingo, 5½ leagues northerly of Point de l'Epée, and 22 S. E. of Cape Raphael, or Round Mountain. N. lat. 19. 3. W. long. from Paris 71. 25.

ENGLISH Harbour, one of the beft harbours in the illand of Antigua, on the S. fhore, a mile S. E. of the mouth of Falmouth harbour. It is well fortified, and has a royal navy yard and arfenal, with conveniencies for careening fhips of war. N. lat. 17. 8. 25. W. long. 61. 27. 30.

ENGLISH NEIGHBOURHOOD, a village in Bergen co. New-Jerfey, on a N.

E. branch of Hackinfack R. W. of, and in the vicinity of Fort Lee.

ENGLISHTOWN, in New-Jerfey, a fmall village in the N. weftern part of Monmouth co. on the road from Princetown to Shrewfbury, 21 miles from the former, 6 W. of Monmouth courthoufe, and 18 E. of Princetown.

ENGLISH TURN. See Detour dei Anglois.

ENO, a river in N. Carolina, which unites with Little and Flat rivers in Orange co. and forms the Neus, about 17 miles below Hillfborough.

ENGREE, a N. W. branch of Broad R. in S. Carolina. It separates Pinckney and Ninety-Six diffricts, and joins Broad R. about 5 miles below Tyger R.

ENOSBURG, a township in Franklin co. Vermont, about 18 or 20 miles E. of Swantown.

EPHRATA, or Dunkard Town, a village in Lancaster co. Pennfylvania, fituated on the N. W. fide of Calico creek, which, joining the Conestoga, falls into the Sufquehannah. It lies 22 miles N. of the town of Lancaster, and upwards of 60 W. of Philadelphia, It is fituated in a romantic and fequeftered vale, and poffeffed by a religious community called Tunkers, who are mostly of German defcent, and believe in general redemption. They use great plainnefs of drefs and language, and will neither fwear, nor fight, nor go to law, nor take interest for the money they lend. They have many peculiarities ; but their innocent manners have acquired them the name of the harmlefs Tunkers. This fettlement is fometimes called Tunker's Town, and confifts of about 40 buildings; of which 3 are places of worfhip. They fublift by cultivating their lands, by attending a printing-office, a grift-mill, a papermill, an oil-mill, &c. and the fifters by fpinning, weaving, fewing, &c. Befides this congregation at Ephrata, there were in 1770, 14 others of this fect in various parts of Pennfylvania, and fome in Maryland. The whole, exclusive of those in Maryland, amounted to upwarde of 2000 fouls.

EPPING, a plantation in the diffrict of Maine, of about 25 familes, 12 miles from Narraguague.

EPPING, a township in Rockingham co. New-Hampshire, taken from the N. W. part of Exeter, and incorporated in

1741. In 1790 it contained 1233, now 2740 inhabitants. It is 6 miles N. W. of Exeter, and 18 W. of Portimouth.

EFSOM, a township in Rockingham co. New-Hampshire, lies E. of Pembroke, adjoining ; 10 miles E. of Concord, and 36 miles N. W. of Portsmouth. It was incorporated in 1727 ; in 1775 it contained 387, and in 1790, 799 inhabitants.

ERIE, FORT, a ftrong fortification in Upper Canada, fituated on the N. fhore of lake Erie, and on the W. bank of Niagara R. 27 miles S. by E of Niagara Fort, and 18 above the carrying place at the Falls of Niagara. N. lat. 42. 59. W. long. 78. 20. 30.

ERIE, a lake of the fourth magnitude in North-America, and through which runs the line between the United States and Upper Canada. D'Etroit R. on the W. brings the waters of the great. lakes with which lake Erie has a communication on the N. W. and Niagara R. on the E. forms its communication with the waters of lake Ontario and the river St. Lawrence. It is fituated between 41. and 43. N. lat. and between 78. 48. and 83. W. long. Its form is elliptical. Its length is about 225 miles; and its medium breadth about 40. It affords good navigation for fhipping of any burden. The coaff on both fides of the lake is generally favourable for the paffage of batteaux and canoes. Its banks in many places have a flat fandy shore, particularly to the eaftward of the peninfula called Long Point, which runs upwards of 18 miles into the lake, and being composed of fand is very convenient to haul boats out of the furf upon it, when the lake is too rough for failing and rowing; yet in fome places, chiefly on the S. fide towards both ends of the lake, it would be dangerous to approach and impoffible to land, by reafon of the perpendicular height of the rocks. Some of thefe, (as at Cayahoga, which are already defcribed) are magnificent beyond defcription, and muft also inspire dread in the boldeft breaft, when viewed from the water. Lake Erie has a great yariety of fine fifh, fuch as flurgeon, cel, white fish, trout, perch, &c. Lakes Huron and Michigan afford communication with lake Erie, by veffels of 8 feet draught. There are portages into the waters of lake Erie from the Wa-

bath, Great Miami, Mufkingum, and Alleghany, from 2 to 16 miles. The portage between the Ohio and Potowmac will be about 20 miles, when the obstructions in the Monongahela and Cheat rivers are removed.

ERIE's, an Indian nation, called by the French du Chat, or Cat-nation. They were extirpated by the Iroquois about the year. 1655. Were it not for the lake which ftill bears the name of that nation, one would not have known that they ever exifted.

ERROL, a fmall town on lake Umbagog, in the N. eafternmost settled part of Grafton co. New-Humpshire, incorporated in 1774.

ERVINE, a township in Ontario co. New-York. Of its inhabitants 93 are qualified to be electors.

ESCAMBIA, one of the most confiderable rivers that fall into the bay of Penfacola in West-Florida, empties itself near the head of the N. branch, about 12 or 15 miles from Penfacola, through feveral marches and channels, which have a number of iflands between them, that are overflowed when the water is high. A fhoal near its mouth prevents veffels drawing more than 5 or 6 feet, from entering; but there is from 2 to 4 fathoms of water afterwards. Capt. Hutchins alcended it in a boat upwards of 80 miles, and from the depth of water there, it appealed to be navigable for pettiaugers many miles further. It is uncertain where its fource is. The course is very winding. At the mouth of the river on the W. fide was the town of Cambleton, fettled by French Protestants in 1766, but was afterwards abandoned.

The lands in general on each fide of the river, are rich, low or fwampy, admirably adapted for the culture of rice The great number of rivulets or corn. which fall into this river from the high circumjacent country, may be led over any part of the rice lands, at any feafon of the year. The numerous iflands at the mouth of the river, fome of very confiderable extent, are not inferior for rice to any in America. The fettlements made by Meffrs. Tait and Mitch-ell, capt. Johnion, Mr. McKinnon, and fome others, are very evident proofs of this affertion; who within two years of their first settlement, had nearly cleared all the expenses they had been at in making

making very confiderable eftablishments; and would entirely have done it in another year, had not the Spaniards taken poffeffion of the country.

he

he

nd

by

on.

for of

wn

)a-

art

or-

co.

аге

er-

en-

out

ich

m, r is

nts

cet,

1 to

ipt.

rds

waible

It

The

auth

the

nch

irds

of

ad-

rice

ligh

over

ifon

s at

con-

ttle-

tch-

and

is of

ears

ear-

it in

king

for

ESCATARI, a finall island about 5 leagues N. of Louisbourg, in the island of Cape Breton.

Esopus. See King flon, New York.

ESPIRITU SANTO, ISLES DEL, fituated on the S. W. of Providence, in the W.-Indies. See Andros Ifles.

ESFIRITU SANCTO, a bay on the W. coaft of East Florida, in 27. 8. N. lat. It has a good harbour, 4 fathom water, and fafe anchorage; but the land all about the coaft is very low, and cannot be feen from a fhip's deck when in 7 fathom water. Several low, fandy iflands and marches, covered with mangrove bufhes, lie before the main land. Here are immensive numbers of fifh in the fummer time, which may be caught with a feine, enough to load a fhip, (if the climate would admit of curing them) even in a few days.

ESQUIMAUX. See Labrador and New-Britain.

ESQUIMAUX, a large bay on the Labrador coaft, into which a river of the fame name empties. It lies in the N. W. part of the gulf of St. Lawrence, near the mouth of the ftraits of Belleisle. Efquimaux islands lie across its mouth.

ESSEQUEBO Diffriet and River. Elfequebo is a diffriet of Dutch Guiana, in S. America, and receives its name from the large navigable river which waters it. See Demerara and Dutch America.

ESSEX Co. in Maffachuletts, is bounded N. by the flate of N. Hampfhire ; E. & S. by the ocean, and the town of Chelfea in Suffolk co.; W. by Middlefex co. ; in length about 38 miles, in breadth 25; and is shap d triangularly, Chelsea being the acute point. The chief islands on its coaft, belonging to it, are Cape Anne and Plumb islands. It is fubdivided into 22 townships, which contain 7644 houfes and 57,913 inhabitants; being the most populous, of its fize, of any in the state, having about 135 fouls to a fquare mile. The first settlement in Massachusetts Proper was made in Salem, the capital of the county, in 1628, by John Endicot, Efg. one of the original patentees, and many years governor of the colony. It was made a fhire in 1643, being one of the three into which the colony was first divided. Effex co. pays about one feventh part of the frate tax, elects fix fenators and counfellors for the government of the commonwealth, and one reprefentative in the legislature of the United States.

The face of the country is pleafingly variegated with hills, vales, woods, and plains. The land is generally fruitful; but is more favourable to barley than moft other parts of the flate. Quarries of marble and limeflone are found in this county; and the flea coaft is indented with a number of good harbours. Merrimack river interfects the N. part of Effex county: between it and the New-Hampfhire line are the towns of Methuen, Haverhill, Almfbury and Salifbury.

ESSEX Co. in Virginia, is bounded E. and N. E. by Rappahannock river, which divides it from Richmond. It is about 55 miles long and 12 broad, and contains 9122 inhabitants, of whom 5440 are flaves.

ESSEX Co. in New-Jerfey, is in the eaftern part of the ftate, and divided from Staten-Ifland by Newark bay. It is about 25 miles in length and 16 in breadth, and has three townfhips, viz. Newark, Elizabethtown and Acquackanack, which contain 17,785 inhabitants, of whom 1171 are flaves. The foil is very fertile, and its fruits and other productions meet with a quick fale in New-York city. Effex couny has within it 7 Prefbyterian churches, 3 for Epifcopalians, 1 for Anabaptifts, and 2 for Dutch Calvinifts.

ESSEX Co. in Vermont, is the northeasternmost in the state.

ESSEX, a township in Chittenden co. Vermont, contains 354 inhabitants. It lies between Jericho on the S. E. and Colchefter on the N. W.

ESTAPA, or *Eflage*, a town belonging to the province of Tabaíco, and audience of Mexico, in New-Spain, N. America. It is mentioned by Dampier. as fituated on Tabaíco R. 4 leagues beyond Villa de Mofe. It is faid to be a place of confiderable trade; and fo ftrong, that it repulfed capt. Hewet, when he attacked it with 200 defperate buccaneers.

ESTAPO, a firong town in New-Spain, inhabited by Spaniard and native Americans; fituated at the smooth L 2 of

161

of the river Tlalue. N. lat. 17 30. W. long. 103. 5.

ESTRER Town, in Lancaster co. Pennfylvania, fituated on the E. bank of Suiquehannah R. a little N. of Harrifburg.

ETECHIMINES, Indian nations on the borders of Nova-Scotia. See Malecites and Scoudick.

EUPHASEE, the ancient name of Hiwallee R. in Tenneflee; also the name of an Indian town on its S. W. bank, 28 miles from its mouth. See Hiwaffee.

EUSTACE, or Enflacia, called alfo Metanzas, or Slaughter, (from a butchery made on it by the Spaniards.) It is an inconfiderable ifland, about 20 miles in circuit. It forms, with a long point of land, the entrance to the harbour of St. Augustine, in East-Florida.

EUSTATIA Town, in the island of Bustatia or Eustatius, in the Caribbean fea in the West-Indies. N. lat. 17. 29. W. long. 63. 5.

EUSTATIUS, ST. or Euflatia, is the chief island belonging to the Dutch in the Weft-Indies, fituated in the Caribbean fea, in 17. 29. N. lat. and in 63. 10. W. long. and 3 leagues N. W. of St. Chriftopher's It is only a mountain, about 29 miles in compais, rifing out of the fea, like a pyramid, and almost round; but though so finall and inconveniently laid out by nature, the industry of the Dutch has turned it to to good account, that it is faid to contain 5000 whites, and 15,000 negroes. The fides of the mountains are laid out in very pretty fettlements; but they have neither fprings nor rivers. The produce is chiefly fugar and tobacco. This island, as well as Curaffou, is engaged in the Spanish contraband trade, for which, however, it is not fo well fitnated; and it has drawn the fame advantage from its conftant neutrality. But in the laft war between Great-Britain and Holland, admiral Rodney, having been tent to reduce it with a confiderable land and fea force, obliged it to furrender at difcretion, on the 3d of February, 1781. The private property of the inhabitants was confifcated, with a degree of rigour very uncommon among civilized nations, and very inconfistent with the humanity and generofity by which the British nation uled to be characterized. The reafon affigned was, that the inhabitants of St.

Euftatius had affifted France and the United States with naval and other flores. The Britifh merchants, as well as those of France and America, fuffered immense loss by effects deposited in this island. On the 27th of November, the fame year, it was retaken by the French, under the command of the marquis de Bouille, who had an inconfiderable force. The Dutch first took possifion of this island in the year 1635.

EVANSHAM, the capital of Wythe co. in Virginia, is fituated on the E. fide of Reedy creek, which falls into the Great Kanhaway, Woods or New river. It contains a court-houfe, gaol, and about 25 houfes; 40 miles W. by S. of Chriftianburg, 242 in a like direction from Richmond, and 518 S. W. by W. of Philadelphia.

EVESHAM, a township in Burlington co. New-Jersey, fituated between the forks of Moore's creek, which runs N. wefterly to Delaware R. It is 7 miles eafterly of Haddonfield, 16 E. of Philadelphia, and 25 S. of Burlington.

Here is an Indian fettlement, called Edge Pittick, a tract of land referved by the ancient natives. They have fome hundreds of acres of improved lands, about 30 houfes, and a meeting-houfe. They formerly had a minister of their own order, who flatedly officiated in the Indian language.

EXETER, a post town in Rockingham co. New-Hampfhire, and, next to Portfmouth, the most confiderable fea-port town in the flate. It is fituated at the head of navigation on Swamfcot, or Exeter R. a branch of the Pifcataqua, 15 miles S. W. of Portfmouth, and a like diftance N. W. of Newburyport, in Effex co. Maffachufetts. The tide rifes here 11 feet. It is well fituated for a manufacturing town, and has already a duck manufactory in its infancy, 6 faw mills, a fulling mill, flitting mill, paper mill, fnuff mill, 2 chocolate and 10 grift mills, iron works, and a printing offices. The faddlery bufinefs is carried on here to greater extent, than in any town on this fide Philadelphia. Before the revolution thip-building was a profitable bufinels; and the veffels were employed in the West-India trade. Notwithstanding the loss of this market, there are four or five veffels, of different burden, built here annually; the river being capable of floating down those of 500

Averfton and Evefham; about 15 miles E. of Philadelphia, and 11 S. of Burlington city.

FOREST, a finall island in the British territories, at the mouth of Lake Ontario, between which and Grand Island is a narrow channel. It lies 9 miles foutherly of Fort Frontinac, and 6 N. westerly of Roebuck I. in the fame lake, and within the line of the United States.

B

B

C.

۵

2

B

8

f

1

.

Ŀ

81

21

8

I

l

2

Ľ

۱

۱

t

1

t

2

b

FORKED DEER, a navigable river in Tenneffee, which runs westerly into Missifippi R. between the Obian and Hatchy. It is about 76 yards wide, 7 miles from its mouth.

FORKS, a township in Northampton co. Pemfylvania.

FORMOSE, a fmall fettlement at the S.E. end of Newfoundland island, at the head of Bear Cove.

FORT BALIZE, at the mouth of Miffifippi river, lies 105 miles below the city of New-Orleans.

FORT BLOUNT, ftands on Cumberland R. in the ftate of Tenneffce.

FORT BREWINGTON, in New-York ftate, is fituated at the W. end of Oneida Lake, and on the N. fide of Onondago R. at its mouth in the lake.

FORT CHARTRES, in the N. W. territory, is fituated on the E. bank of Miffilippi R. 6 miles W. by S. of St. Phillips, and 19 W. N. W. of Kalkafkias village.

FORT DAUPHIN, a fmall lake, or rather arm of Little Winnipeg lake, and weft of it.

FORT EDWARD, a pleafant village in Washington co. New-York, on the E. bank of Hudson R. 49 miles N. of Albany. It has its name from the large fort built here in 1755; of which there are no remains but large mounds of earth.

FORT ANNE, a village on the head waters of Wood creek, in Washington co. New-York, 60 miles N. E. of Albany city. It has its name from a small picket fort, erected in the reign of Queen Anne, of which there is no veftige left.

FORT GEORGE, lies at the S. end of lake George, 62 miles N. of Albany. Here are the remains of the old forts, George, and William Henry. The fituation is pleafant, but there is hardly the appearance of a village. See George, lake.

FORTROYAL, in the island of Grenada. See St. George's.

FORTROYAL, one of the principal towns in the island of Martinco, in the West-Indies. It is the feat of government in the island; its fireets are regular, the houses agreeable, and the people gay and luxurious. The citadel which defends the town cost the French $\pounds.325,000$ fterling. The harbour here is one of the best in the West-Indies, and the ships of war winter in it.

FORTUNE, a large bay towards the S. W. part of Newfoundland ifland; across the mouth of which lies Micklon ifland, and S. of it Peter's ifland. This extensive bay is interspersed with small ifles, and within it are many bays. It has great depth of water throughout.

FOSTER, a township in Providence co. Rhode-Island, containing 2268 inhabitants; 17 miles westerly of Providence, and 31 N. W. of Newport.

FOXBOROUGH, a township in Norfolk co. Massachuletts, containing 674 inhabitants, 26 miles S. of Bolton. It was formerly a part of Dorchester, and was incorporated in 1778.

Fox, a river in the N. W. territory, which rifes in the S. and runs about 50 miles N. where it approaches very near to, and parallel with, Ouisconfin, a N. eaftern branch of the Miffifippi river. From the Great Carrying Place here, through lake Winnebago, it runs carerly, then N. E. to bay Puan, about 180 miles. From the carrying place to Winnebago it is navigable for canoes a or 5 miles. From bay Puan its current is gentle; from thence to Winnebago lake it is full of rocks and very rapid. Its breadth is between 70 and 100 yards. The land on its borders is good, thinly wooded with hickory, oak, and hazel. See Onifconfing and Winne-

Fox, a northern water of Illinois river, 34 miles below the mouth of Plein river.

FRAMINGHAM, a township in Middlefex co. Maffachufetts, containing 1598 inhabitants. It was incorporated in 1700, and is 24 miles W. S. W. of Boston.

FRANCESTOWN, an interior townthip in Hillsborough co. New-Hampthire, on the E. fide of Contecook R. about 21 miles to the S. W. of Concord. It was in incorporated in 1772, and

in 1790, 982.

174

FRANCISBOROUGH, a fettlement in York co. district of Maine, containing 311 inhabitants.

FRANCIS, ST. a lake, or extension of the river St. Lawrence, between Kingfton and Montreal, through which paffes the line dividing Upper from Lower Canada.

FRANCIS, ST. a river in the province of Lower Canada, which riles from lake Memphremagog, and runs northward into the river St. Lawrence. It is not all the way navigable; elfe it would afford an important communication from the northern parts of Vermont to the markets of Montreal and Quebec.

FRANCIS, ST. a fmall river in Louifiana, which runs a S. E. courfe into the Miffilippi, 108 miles above Arkanfas R. and 70 miles above Margot R. on the E. fide of the Miffifippi. It is remarkable for nothing but the general rendezvous for the hunters from New-Orleans, who winter there, and collect falt meat, fuet, and bear's oil, for the fupply of that city. Kappas Old fort formerly flood at the mouth of this river, on the fouthern fide. It was built by the French during their wars with the Chickafaw Indians.

Allo, the name of a finall river in the N. W. territory, which runs a S. W. by W. courie into Miffifippi, between Cold and Rum rivers, 60 miles above St. Anthony's Falls. The country a little above it is hilly, and the foil pretty good. To the N. E. are the fmall lakes called the Thoufand lakes. The Miffilippi here is not above go yards wide.

FRANCIS, ST. in Brazil, S. America, a long and large river which runs N. easterly, and thence S. E. till it empties into the ocean, N. E. of the town of Scregeppe del Rey. It has a number of towns and fettlements, chiefly on its head waters.

FRANÇOIS, CAPE ST. a jurifdiction, city, and port in the N. weftern part of the ifand of St. Domingo. This jurifdiction is in the North division of the ifland, in what was called the French part of it; and contains 13 parifies. Its exports from Jan. 1, 1789, to Dec. 31, of the fame year, were as follow : 21,187,636lbs. white fugar, 7,268,531 | queddy, and 234 N. E. of Botton.

FRA

and contained in 1775, 200 inhabitants, | lbs. brown fugar, 32, 545, 524lbs. coffee, 269,240lbs. cotton, 245,177lbs. indigo; tanned hides, molaffes, Tpirits, &c. to the value of 21,789 livies. Total value of duties on exportation, 253,590 dollars, 37 cents. Cape François exceeds Port au Prince in the value of its productions, the elegance of its buildings, and the advantageous fituation of its port. The city, which is the governor's refidence in time of war, is fituated on a cape at the edge of a large plain, 20 leagues, long, and on an average 4 broad, between the fea and the mountains. There are few lands better watered, but there is not a river that will admit a floop above 3 miles. This fpace is cut through by ftraight roads, 40 feet broad, uninterraptedly lined with hedges of lime and lemon trees, intermixed with long avenues of lofty trees, leading to plantations which produce a greater quantity of fugar than any fpot of the fame fize in the world. The town, which is fituated in the most unhealthy place of this extensive and beautiful plain, had, fome years fince, feveral elegant public buildings, as the governor's houfe, the barracks, the magazine, and two hospitals, called the boufes of Providence, founded for the benevolent and humane purpole of fupporting those Europeans who came thither without money or merchandife. The harbour is admirably well fituated for thips which come from Europe, being only open to the N. from whence fhips receive no damage, its entrance being fprinkled over with reefs that break the force of the waves. Before its destruction in 1793, this city contained about 8000 inhabitants; whites, people of colour, and flaves. See St. Domingo.

FRANÇOIS, OLD CAPE, the northeasternmost point of the island of St. Domingo or Hifpaniola; having Balfamo bay N. W. and Scotch bay S. S. E.

FRANCONIA, a townfhip in Grafton co. New-Hampfhire, 14 miles N. E. of Haverhill (N. H.) on Connecticut river. Incorporated in 1764, first called Morriftown. It contains 72 inhabitants.

FRANKFORT, a township in Hancock co. district of Maine, on the W. fide of Penobicot bay. It has a few houses, regularly built, and lies 8 miles W. of Penobicot, 123 W. of Paffama-The

FRI fant, t Pennfy ofac and ar tains a an E on ele E. of FR. Herke town, FR Hamp which 13 mi of the Fort FR ton c fide (It c about Rich F Kent on t abou the C gula

hand

hand

a tob

of H

ville

by S

Ŵ.

F

¢0.

Ven

orde

vani

neig

the

fite

lat.

mil

nor

~ F

mol Cai

It :

and

ed .

E.I

ryl

F

The 1

tants.

The township contains 891 inhabi-

d

0

24

18

of

1-

je

r-

he

t-

er

8.

ht

ly

237

of

ch

30

d.

oft

nd

:e.

he

he

he

he

ne

le.

ed

ie-

ce

ice

iat

)re

n-

:s.

St.

h.

St.

fa-

E.

on

of

er.

01'-

m-

N.

ew

iles

na.

on.

he

FRANKFORT, or Frankford, a pleafant, thriving village in Philadelphia co. Pennfylvania, fituated on the N. E. fide of a creek of the fame name, a mile and an half from Delaware R. It contains about 50 houfes, chiefly of ftone, an Epifcopal and a German church ; on elevated ground, about 5 miles N. E. of Philadelphia.

FRANKFORT, 2 new township in Herkemer co. New-York, E. of Whiteftown, adjoining.

FRANKFORT, a thriving village in Hampfhire co. Virginia, on a creek which empties into Potowmack R. It is 13 miles N. W. of Rumney, 4 miles S. of the Potowmack, and 10 S. S. E. of Fort Cumberland.

FRANKFORT, the capital of Pendleton co. Virginia, is fituated on the W. fide of a S. branch of Potowmack R. It contains a court-house, gaol, and about 30 houses; 180 miles N. W. of Richmond.

FRANKFORT, the metropolis of Kentucky, is fituated in Franklin co. on the N. E. bank of Kentucky R. about 50 miles from its confluence with the Ohio. It is a flourishing town, regularly laid out, and has a number of handfome houfes. The flate-houfe is a handfome ftone building. Here is alfo a tobacco warehoufe. It is 30 miles N. of Harrodfburg, 40 N. by W. of Danville, 123 from Louifville, and 790 W. by S. of Philadelphia. N. lat. 38. 14. W. long. 95. 28.

FRANKLIN, FORT, is in Alleghany co. Penniylvania, near the poft called Venango, and was crefted in, 1787 in order to defend the frontiers of Pennfylvania from the depredations of the neighbouring Indians. It is feated on the S. W. bank of Alleghany R. oppofite the mouth of French creek. N. lat. 41. 1. 40. W. long. 79. 41; 53 miles S. S. E. of Preique Ide, and 63 northward of Pittfburg.

FRANKLIN Co. the north-wefternmost in Vermont, bounded N. by Lower Canada, and W. by lake Champlain. It was lately taken from Chittenden co. and contains 20 townships.

FRANLIN Co. in Pennfylvania, bounded N. by Mifflin, N. E. by Cumberland, E. by York, S. by Washington co. in Maryland; W. by Bediord co. and N. W.

by Hunterdon. It is computed to contain 800 fquare miles, equal to 512,000 acres. It lies chiefly between the N. and S. Mountains, and comprehends the middle part of the beautiful and rich valley of Connegocheague ; which is watered by the creek of its name. which falls into Potowmack at William's Port in Maryland. This county exhibits a most luxurious landscape in fummer, from the top of South Mountain. Iron ore is found here fufficient already to furnish work for a furnace and forge. The county is divided into 11 townthips, which contain 15,655 inhabitants, of whom 330 are flaves.

FRANKLIN Co. in Kentucky, is bounded N. by Scott co. N. W. and W. by Shelby, S. E. by Fayette, and S. by Woodford. Chief town, Frankfort.

FRANKLIN Co. in Halifax diftrict, N. Carolina, contains 7559 inhabitants, of whom 2717 are flaves. It is bounded N. by Greenville, S. by Johnston, N. E. by Warren, S. W. by Wake, and W. by Orange co. Chief town, Louisburg.

FRANKLIN Co. in Virginia, is bounded Ni by Bedford, N. W. by Botetourt, W. by Montgomery, S. W. by Henry, S. by Patrick, and E. by Campbell co. It is about 40 miles long, and 25 broad, and contains 6842 inhabitants, including 1073 flaves. A range of the Alleghany Mountains paffes through it on the N. W. It is confequently hilly in general.

FRANKLIN Co. in Georgia, is fituated in the Upper Diffrict, bounded E. and N. E. by Tugulo R. which feparates it from the flate of S. Carolina; W. and N. W. by the country of the Cherokees; S. by the head branches of Broad R. and S. E. by Elbert co. It contains roar inhabitants, of whom 156 are flaves. The court-houfe is 17 miles from Halton's Ford on Tugulo R. 25 from Elberton, and 77 from Wathington.

FRANKLIN-COLLEGE, See Lancaster, in Pennfylvania.

FRANKLIN, a township in Norfolk co. Maffachusetts; taken from Wrentham, and incorporated in 1779, and contains 17,000 acres of land. It has troi inhabitants; is bounded N. by Charles R. which separates it from Medway, and lies 30 miles S. of Boston.

FRANKLIN, a final ille at the mouth of

of St. George's R. in Lincoln co. Maine; 4 leagues fouthward of Thomafton.

FRANKLIN, a new township in Dutchels co. New-York. By the ftate census of 1796, it appears there are 210 of its inhabitants qualified to be electors.—Alfo, a new township in Delaware county, of whose inhabitants 239 are electors. It lies S. W. from, and borders on Harperssield, and its W. line runs along the S. eastern bank of Susquehannah R. This town was divided by an act of the Legislature, 1797.

Legislature, 1797. FRANKLIN, a township in Westmoreland co. Pennfylvania.—Also, 3 others in the same state, viz. in York co. Fayette co. and in Washington co.

FRANKLIN, a township, the northernmost in New-London co. Connecticut, 6 miles N. W. of Norwich. It contains above 1000 inhabitants, who are chiefly wealthy farmers,

FRANKSTOWN, a township in Huntingdon co. Pennsylvania, fituated on the Frankstown branch of Juniatta R. so miles W. of Huntingdon.

FRAYLES, an ifland near the coaft of New-Andalufia, Terra Firma.

FRAXLES, Los, a clump of rocks which rife above water on the S. fide of the ifland of St. Domingo, 4 leagues N. W. of the ifland of Beate, nearly oppolite the ifles called the Seven Brothers, in the bay of Monte Chrift, on the N. fide of the ifland. These rocks are also called the Brothers or Monks. The rapidity of the currents renders this part of the coaft very dangerous.

FREDERICA, a village in Kent co. ftate of Delaware, fituated between the two main branches of Mother Kill, a ftream which falls into Delaware 7 miles from the town, and 3 S. E. of James's creek, which leads up to Dover. It contains about 40 houfis, and lies 13 miles E. of Dover, and 88 from Philadelphia.

FREDERICA, a town of Glynn co. in Georgia, is fituated on St. Simon's ifland, in a very pleafant fituation, and was built by gen. Oglethorpe. The fortrefs was beautiful and regular, but is now in ruins. The town contains but few houfes, which ftand on an eminence, upon a branch of Alatamaha river, which wafhes the W. fide of this agreeable ifland, and forms a bay before the town, affording a fafe and commodiIt is

built

rand

It is

by ot W. 1

Ame the ci ants grazi their

goud

a roa

da in

place

350 l

long. Fi

bayc

Sant

Sant

ca.

F

F

of la

near

and

Brit

ed w

a ful

up a

the a

in S

co.

F

F

fon

It (

cree

fall

Otte

w.

cree

and

nor

fite

of V

W.

J

fide

F

F

Fi oceai and i

FE

ous harbour for veffels of the largeft burden, which may lie along the wharf. It was fettled by fome Scotch highlanders, about the year 1735, who accepted of an eftablishment both here and at Datien, to defend the colony, if needful, against the neighbouring Spaniards. N. lat. 17.15. W. long. 80.

rien, to defend the colony, in necessary against the neighbouring Spaniards. N. lat. 31. 13. W. long. 80. FREDERICK GO. in Maryland, is bounded N. by Pennfylvania, W. and N. W. by Washington, E. by Baltimore, and S. W. by Potowinack R. On the Monocacy river and its branches are about 37 grift-mills, a fornace, iron forge, and a glafs manufactory, called the Etna glafs works, which are in a thriving flate. This county is about 30 miles each way, reckoning from the extreme parts. The Cotoftiny Mountain extends from the Potowinack in a N. direction through this county into Pennfylvania, between the South Mountain and Monocacy Creek; the eaftern parts are generally level. It contains 30,791 inhabitants, including 3641 flaves. Chief town, Fredericktown.

FREDERICK Co. in Virginia, is bounded N. by Berkley, S. by Shanandoah; W. by Hampfhire, and E. by Shanandoah R. which feparates it from Loudon co. It is 30 miles in length, and zo in breadth, and contains 19,681 in-habitants, of whom 4250 are flaves. Iron ore is found here in great plenty ; and works have been erected which produce 160 tons of bar iron, and 650 tons of pig, annually. In 1 year 300 tons of bar iron were manufactured. Pots and other utenfils, caft thinner than ufual of this iron, may be fafely thrown into or out of the waggon, in which they are transported. Both this and Berkley co: has a good foil. Between the waters of Opeckan creek and the Shanandoah is the richeft limeftone land in the eafters parts of the ftate.

Near the North Mountain in this county is a curious cave, by fome called Zaney's Cave. Its entrance is on the top of an extensive ridge. You defeend 30 or 40 feet as into a well, from whence the cave then extends, nearly borizontally, 400 feet into the earth, preferving a breadth of from 5 to 12 feet. After entering this cave a few feet, the mercury, which, in the open air, was at 50, role to 57 of Fahrenheit's thermometeri After this may be added the Natural Well It is faid to be a rich and regularly built city, and a bifhop's fee. Baudrand makes it 9 leagues from the river. It is allo called Santa Fe de Grenada; by others New-Mexico. N. lat. 36. W. long. 104.

FE, SANTA, a city of Paraguay, S. America, 150 leagues S. by S. W. of the city of Affumption. The inhabitants are chiefly employed in bufbandry, grazing, and weaving cloth. They fell their productions and manufactures to good profit in Brazil. From hence is a road to Potofi in Peru, and to Corbuda in Tucumana; which being eafy and convenient, is very advantageous to this place, the diffance not being above 350 leagues. It frands on the W. fide of Paraguay river. S. lat. 30. 45. W. long. 60. 40.

FELIPE, Y SANT-YAGO, a large bay on the N. fide of the island Espiritu Santo. See Tierra Austral del Espiritu Santo.

FELIX, ST. an island in the Pacific ocean, N. N. W. of Juan Fernandes, and due west of Copiapo, in S. America. S. lat. 26. W. long. from Paris 83. FELL's Point. See Baltimore.

FER, POINT AU, on the W. coaft of lake Champlain, lies in Clinton co. nearly 5 miles S. of the division line between New-York and Lower Canada, and 25 miles S. of St. John's. The British occupied a barrack here, furnished with one field piece, a few men, and a fubaltern officer. It has been given up according to treaty.

FERDINAND NARONKA, an ifland on the coaft of Brazil, South America, lies in S. lat. 3. 56. W. long. 32. 43.

FERMANAGH, a township in Mifflin co. Pennsylvania.

FERRISBURGH, a township in Addifon co. Vermont, on lake Champlain. It contains 481 inhabitants. Otter creek, Little Otter and Lewis's creeks fall into the lake here. The mouth of Otter creek lies in N. lat. 44. 11. 45. W. long: 73. 9. 47.

W. long: 73. 9. 47. FIDLERS Elbow, a bend of Wood creek, between the outlet of South bay and the mouth of the creek, at the northern end of lake Champlain, oppofite the mouth of Eaft bay. The mouth of Wood creek lies in N. lat. 43. 32. W. long. 73. 15. 12.

FIG-TREE Buy, lies on the S. W.

the West-Indies, at the head of which stands Sandy-fort town. The bay is fecured by a fort on each fide.

FINCASTLE, a post town in Virginia, and capital of Bottetourt co. fituated on the E. fide of Catabaw creek, a small ftream which falls into James R. on the W. fide of the Morth Mountain. Here are about 50 houses, a court-house and gaol. It lies on the post road from Richmond to Kentucky, 36 miles easterly of Lexington, and 192 W. by N. of Richmond.

FINDLEY, a township in Washington co. Pennsylvania.

FISHERSFIELD, a township in Hillsborough co. New-Hampshire, incorporated in 1763, containing 331 inhabitants. Sunapee pond lies partly here, and in the township of Wendel. It is about 16 miles easterly of Charlesftown.

FISHER'S Ifland, in Long-Ifland found, lies opposite to Groton in Connecticut, is about 10 miles in length and 2 in breadth, having a light foil, favourable for raising theep. It produces also wheat and other grain. It is annexed to the township of Southhold, in Suffolk co. on Long-Island.

FISHING Bay, in Maryland, lies on the E. fide of Chefapeak bay, partly in Dorchefter and Somerfet counties. It receives feveral rivers from each county, the chief of which are Wicomico, Nanticoke; allo Transquaking and Blackwater creeks. The entrance into this large bay lies between Goldsborough and Devil's iflands.

FISHING Bay, on the S. fide of lake Ontario, is about 37 miles E. of Fort Niagara.

FISHING-CREEK, a township on Sufquehannah river, in Pennfylvania. See Northumberland Co.

FISHKILL, a post town in Dutchefs co. New, York, 5 miles E.of Hudfon R. on Fishkill or creek, at the foot of the Highlands, which rife S. of it; containing about 30 houses, a church for Epifcopalians, and one for Low Dutch. The township is very extensive, and contained, in 1790, 5941 inhabitants, of whom 60r were flaves. It lies 14 miles S. by E. of Poughkeepsie, opposite Newburgh, and 66 N. of New-York city. There are a few houses only at the Landing, on the margin of the river. FISH Kill, or Greek, on which the town town above deferibed ftands, and from which it derives its name, is fmall, and empties into Hudfon R. about a mile below the Landing, and nearly oppofite

FLA

New Windfor. Alfo, the name of a fmall ftream which runs S. W. into Oneida Lake.

Likewife, a fiream, which rifes from Saratoga lake, and runs 6 miles eafterly to the Hudfon. Its mouth is opposite Batten kill, 2 miles above Saratoga town; and on the N. fide of which Gen. Burgoyne's army laid down their arms as priloners.

FITCHBURGH, a post town of Maffachusetts, Worcester co. 23 miles N. of Worcester, 24 from Concord, and 42 N. W. of Boston. It has 2152 inhabitants.

FITZWILLIAM, a township in Chefhire co. New Hampshire, about 16 miles E. of Connecticut R. and separated from Royalston in Worcester co. Massachufetts, by the flate line. It was incorporated in 1773, and contains 1038 inhabitants.

FINE Fort, is fituated 185 miles W. S. W. of Winnipeg lake, N. lat. 49. 42. W. long. 102.

FLAMBOROUGH, a factory of the Hudson bay company, on the S. western fide of Hudson bay.

FLATBUSH, the chief town of King's co. Long-Ifland, New-York. It is a pleafant and healthy town, fituated on a imall bay which opens E. from New-York harbour, and is 5 miles S. by E. from New-York city. It contains a number of dwelling houfes, mostly in one freet; many of which are elegant and commodious. The inhabitants are chiefly of Dutch extraction. It contains 941 inhabitants, of whom 107 are qualified electors, and 378 are flaves. The productions are various kinds of fruit, vegetables, grain, &c. which find a ready market in the metropolis. The land lies low; and in fummer the whole township appears like an extensive gar-The public buildings are a den. Dutch church, a court-house, and an academy, called Erasmus Hall, the most flourishing of all the academies in the frate. It is in a pleafant and health-ful fituation, 4 miles from Brookline ferry

A bloody battle was fought near this town on the 27th of August, 1776, when the Americans were defeated by the British with great loss. The remains of the American army retreated to New-York under the cover of a thick fog.

FLATLANDS, a fmall township in King's co. Long-Island, distant from New-York city 6 or 7 miles. It contains 423 inhabitants, of whom 44 are qualified to be electors, and 137 are flaves.

FLAT Rock, is an expansive, clear, flat rock, but a little above the furface of the ground, and near the banks of a delightful rivulet of excellent water, which is one of the head branches of Great Ogeechee R. in Georgia. This is a common rendezvous or camping place for traders and Indians.

FLATTERY, CAPE, fo named by captain Cook, on account of its promifing at a diffance what it denied on a nearer approach. Lat. 48. 15. kong. 235. 30. E. This cape, captain Ingraham of Bofton, found to be the S. fide of the entrance of the ftraits of Juan de Fuca. N. lat. 48. 25. W. long. 124. 52. See Fuca.

FLEMINGTON, a finall post town of New-Jerfey, in Hunterdon co. lies about 6 miles N. eastward of Amwell on Delaware R. 23 N. N. W. of Trenton, 9 S. of Pittflown, and 53 N. E. by N. of Philadelphia. It contains about a dozen compact houses.

FLETCHER, a township in Franklin co. Vermont, containing only 47 inhabitanta. It has Cambridge on the S. E. and Georgia W.

FLINT River, a confiderable river of Georgia, which rises in the country of the Creek Indians, and running a S. and thence a S. W. courfe, joins the Appalachicola, at its entrance into Florida. The Flint is about 30 rods wide, and from 12 to 15 feet deep in fummer, and has a gentle current. The territory lying on' this river, especially on the upper part of it, prelents every ap-pearance of a delightful and fruitful region in fome future day; it being a rich foil, and exceedingly well fituated for every branch of agriculture, and offers an uninterrupted navigation to the bay of Mexico, and Atlantic ocean, and thence to the West India islands and over the whole world. There are a number of villages of Creek Indians on this river.

FLINT, a finall river, about a8 miles long, in the Genefice country, in New, York,

berlan ants. Saddle try in vation pine a FLO Newand 50 of its elector rated. FLO to Spa N. la long. breadt of W while t rida e from S N. by co, E. by the from 1 form o that fa and In na, Ap bia, M all rife into th pal bay Mobile Apalao capes a and ca the per differen are, in foils ; about & unfruit of Indi The ba Florida of a fup to the fine lan deferibe The ir and pla almolt and red

pine, h

York,

darqui

FL

170 .

York, which runs N. N. E. into Canandargua creek.

FLINTSTON, a plantation in Cumberland co. Maine, having 180 inhabitants. It has one eminence in it called Saddle-Back mountain, but the country in general is level enough for cultivation. One half of it is covered with pine and white oak

FLORIDA, a township in Orange co. New York, 6 or 8 miles S. of Goshen, and 50 N. W. of New-York city. 377 of its inhabitants are qualified to be electors. It has been lately incorporated.

FLORIDA, East and West, belonging to Spain, fituated between 25 and 31 N. lat. and between 80. and 91. W. long. about 600 miles in length. Its breadth is various; the broadeft part of West Florida is about 130 miles, while the narrow peninfula of East Florida extends, in the fame direction, from S. to N. 400 miles. It is bounded. N. by Georgia, S. by the gulf of Mexico, E. by the Atlantic ocean, and W. by the Miffifippi, which feparates it from Louisiana, and is nearly of the form of the letter L. Among its rivers that fall into the Atlantic, St. John's and Indian rivers are the chief. Seguana, Appalachicola, Chatahatchi, Elcambia, Mobile, Pascagoula and Pearl rivers all rife in Georgia, and run foutherly into the gulf of Mexico. The princi-pal bays are St. Bernard's, Afcenfion, Mobile, Peníacola, Dauphin, Joseph, Apalachy, Spiritu Sancto; and the chief capes are Blanco, St. Blaize, Anclotte, and cape Florida at the extremity of the peninfula. The climate is little different from that of Georgia. There are, in this country, a great variety of foils; the eastern part of it, near to, and about St. Augustine, is by far the most unfruitful; yet even there, two crops of Indian corn are annually produced. The banks of the rivers which water the Floridas, and the parts contiguous, are of a fuperior quality, and well adapted to the culture of rice and corn. The fine lands near the river Efcambia, are deferibed under the account of that R. The interior country, which is high and pleafant, abounds with wood of almost every kind; particularly white and red oak, live oak, laurel magnolia, pine, hickory, cyprefs, red and white cedar. The live oaks, though not tall,

contain a prodigious quantity of timber. The trunk is generally from 12 to 20 feet in circumference, and rifes 10 or 12 feet from the earth, and then branches into 4 or 5 great limbs, which grow in nearly a horizontal direction, forming a gentle curve. "I have ftepped fays Bartram, "above 50 paces, on a ftraight line, from the trunk of one of thefe trees to the extremity of the limbs." They are ever green, and the wood almoft incorruptible. They bear a great quantity of finall acorns, which is agreeable food when roafted, and from which the Indians extract a fweet oil, which they ufe in cooking hominy and rice.

The laurel magnolia is the most beautiful among the trees of the forest, and is ufually 100 feet high, though fome are much higher. The trunk is perfectly crect, rising in the form of a beautiful column, and fupporting a head like an obtuse cone. The flowers, which are on the extremity of the branches, are large, white and expanded like a role. and are the largest and most complete of any yet known ; when fully expanded. they are from 6 to 9 inches diameter. and have a most delicious fragrance. The cyprefs is the largest of the American trees. " I have feen trunks of thefe trees," fays Bartram; "that would measure 8, 10 and 12 feet in diameter, for 40 and 50 feet fhaft." The trunks make excellent fhingles, boards, and other timber; and when hollowed, make durable and convenient canoes. The garden vegetables are in high perfection : the orange and lemon trees grow here, without cultivation, to a large fize, and produce better fruit than in Spain and Portugal. The intervales between the hilly parts of this country are extremely rich. The principal town in West Florida is Peníacola; in East Florida. St. Augustine.

The Spanish firength in the Floridas, and Louisiana, in 1790, was as follows, according to Mr. Melford's account: Troops and levies at St. Augustine and on St. John's river, 400-St. Mark's, 100-Penfacola, 350-Mobile and Tombigbee, 150-at the Natchez, 200-Red river, 100-Illinios river, 300-in all 1600 men, called the Orleans or Louitiana Regiment.

The number of American families that have been Spanish subjects fince 1783, amounts to 1720, viz. at Tensau, near

The reetreated a thick

uhip in

it from

It con-

44 ale e flaves. clear, furface iks of a water, iches of This amping ned by promifd on a long. Ingra-S. fide luan de 5. 124. own of s about n Delnton, 9 y N. of a dozranklin inhab-: S. E. iver of ntry of a S. ns the to Flowide, mmer, terriilly on ry apful rea rich ed for offers te bay and Is and are a Ins on miles

New

York,

ear Mobile bay, 90-on Tombigbee er, 130-at the Natchez on the i, 1500. All the fettlers in these districts are under the immediate orders of the military commandants, and fubject to martial law; with an apcal from fage to fage; up to the viceof Mexico. The property of the fobject at his decease is to be managed by the commandant, whole fees, by law, are enormous.

Until the year 1586 the continent of North-America went by the name of Florida. It received this name from hn Ponce, because when he landed in N. lat. 38. 8. in April 1513, the found the country there in full bloom, Florida has frequently changed mafters, belonging alternately to the French and paniards. Weft-Florida, as far as Perdido R. was owned and occupied by the French; the remainder, and all Eaft-Florida, by the Spaniards, previous to their being ceded to the British, at the peace of 1763. The British divided this country into E. and W. Florida. During the American war, both the Floridas were reduced by the Spaniards, and guaranteed to the crown of Spain by the definitive treaty of 1783.

FLORIDA, CAPE, the fouthernmoft oint of land of the peninfula of Eaft-Florida. It is 100 miles N. of the ifland of Cuba. N. lat. 25. 20. W.

long. 80. 80. FLORIDA KEYS, or Martyr's Iflands, a number of rocks and fand banks, bounded W. by the gulf of Mexico, E. - that of Florida. The great fand bank extends from the peninfula of Eaft-Florida inward, to the gulf of Mexico, in the form of a hook ; its W. point is divided from the bank called the Dry Tortugas, by Tortuga channel.

FLORIDA, GULF OF, is the channel between the peninfula of Florida and the Bahama islands, N. of the island of Cuba; and through which the Gulf Stream finds a paffage, and runs to the N. E. along the American coaft. See Gulf Stream and Mexico.

FLOWERTOWN, in Pennfylvania, is a fmall village about 12 miles N. of Philadelphia, in Montgomery co.

FLOYD, a new township in Herkemer co.

FLUSHING, a town in Queen's co. New-York, fituated on the N. W. part | ton co. New-Jerfey, which lies between

of Long Island, and on the S. fide of Hell Gate ; 7 miles E. by N. of New-York city. It contains 1607 inhabi-tants; of whom alo are qualified electors, and 340 are flaves.

FOR

FLUVANNA. See James River. FLUVANNA, a county of Virginia, bounded N. by Albemarle, N. E. by Louifa, E. by Goochland, W. by Amherit, and S. by Fluvanna or James river, which divides it from Buckingham. It is about 22 miles long, and 20 broad, and contains 3021 inhabitants, including 1466 flaves. There is great plenty of marble, both white and variegated with blue, red and purple veins, found here, on lames R. at the mouth of Rockfift; where it forms a large precipice, overhanging a navigable part of the river.

FOGGY Cape, on the N.W. coaft of N. America, is fituated on the S. eaftern fide of the peninfula of Alafka, and W. of Kifhtac ifland.

FOGGY I/le, on the fame fide of the peninfula as the above, lies a fhort way S. by W. of Foggy Cape.

FOLLOWFIELD, a township in Washington county, Pennfylvania: East and Weft Followfield are also two townships, in Chefter co. Pennfylvania.

FONSECA, GULF OF, lies in New-Spain on the Pacific ocean, 40 miles S. E. of the town of St. Miguel, and about 290 miles N. W. of Cape Blanco, on the weftern fide of the gulph of Nicoya.

FONTAINE, BELLE, a fettlement in the N. W. territory, fituated on the E. fide of the Miffifippi, about 18 miles N. of St. Phillips, and 23 below Cahokia.

FONT, or FONTE, STRAITS DE, lie on the N. W. coaft of N. America, in N. lat. 54. 35. W. long. 9. 55. There is a large island in the middle of the entrance. This is thought to be the fame ftrait that De Fonte, a Spanish admiral, discovered in 1640, whole account of it has been long treated as fabulous. It has been feen by captains Gray and Ingraham, of Bolton.

FORALONES, in the island of Gunra, and coaft of Peru, in S. America, are old walls of tome ancient building in the time of the Yncas, which ferve here as light-houfes for the fhipping which fail from Callao to Paita, on the S. Sea. coaft.

FORESTERTON, a village in Burling-Averfton is thus

Maryla

fuated

出现意识的

FRE

Well of

is fome

fide of Newinhabi-

199 (**1**99

er.

irginia, E. by y Am-James ickingig, and There is ite and purple at the orms a navigacoaft of S. eaftca, and : of the ort way Wafhlaft and wnfhips, n Newniles S. id about nco, on Nicoya.

n the E. niles N. shokia. DE, lie rica, in There is the enthe fame admiral, count of abulous. ray and

ment in

Gunra, rica, are Iding in erve here ig which ie S. Sea

Burlingbetween Ayerfton FRE

Well on the lands of Mr. Lewis. It is fomewhat larger than a common well, and rifes as near the furface of the earth as in the neighbouring artificial wells; and is of a depth, as yet unknown. It is ufed with a bucket and windlafs as an ordinary well. It is faid there is a current in it tending femibly downwards. Chief town, Winchefter.

FREDERICK Houfe, a trading flation in Upper Canada, on the head water of Abbitibbe river. N. lat. 48. 35. W. long. 82. 6.

FREDERICK, a fort in Washington co. Maryland, fituated on the N. E. bank of Potowmack R. near the S. line of Pennsylvania.

FREDERICK, a township in Montgomery co. Pennsylvania.

FREDERICK, a town on the N. fide of Saffafras R. in Cecil co. Maryland, and separated by that river from George Town in Kent co. It lies 6 miles S. W. of Warwick, and 14 E. of Grove point in Chefapeak bay. N. lat. 39. 22. 30. FREDERICKSBURG, a post town in Spotfylvania co. Virginia; fituated on the S. W. bank of Rappahannock river, 110 miles from its mouth in Chefapeak bay. It is an incorporated town, and regularly laid out into feveral ftreets. the chief of which runs parallel with the river, and in all contains upwards of 200 houses, two tobacco warehouses, and feveral ftores of well afforted goods. Its public buildings are an Epifcopal church, an academy, court-houfe and gaol. It is a place of confiderable trade and contains about 2000 inhabitants, of whom 587 are flaves. A forge in this neighbourhood made fome time ago, about 300 tons of bar iron in a year, from pigs imported from Maryland. It is 50 miles S. S. W. of Alexandria, 68 N. by E. of Richmond, 102 S. W. cf Baltimore, and 205 S. W. of Philadelphia. N. lat. 38. 22. W. long. 77. 36. FREDERICKSTOWN, a township in Dutchefs co. New-York, which con-

tains 5932 inhabitants, of whom 188 are qualified to be electors, and 63 are flaves.

FREDERICKTON, a confiderable township in the province of New-Brunswick, 90 miles up St. John's R. which is thus far navigable for floops.

FREDERICKTOWN, a post town of Maryland, and capital of Frederick co. Suated on both fides of Carroll's creek, M

FRE

a small stream that empties into Monocacy R. over which are two bridges. The freets are regularly laid out, interfecting each other at right angles. The dwelling-houfes, chiefly of ftone and brick, are about 700 in number, many of which are handfome and commodious. The public edifices are, one church for Prefbyterians, two for German Lutherans and Calvinifts, and one for Baptifts, an elegant court-houle, a gaol, and a brick market-houfe. It is a very flourishing town, and has confiderable trade with the back country. The Etna glafs works are fituated miles above the town, on Tufkarora creek. Fredericktown is 4 miles E. of Cotoctin mountain, 47 W. by N. of Baltimore, 24 E. of Sharpfburg, and 148 S. W. by W. of Philadelphia, N. lat. 39. 24.

FREEHOLD, a town in Monmouth co. New-Jerfey, 15 miles W. of Shrewfbury, and 20 S. E. by S. of New-Brunfwick. In this town was fought the obflinate battle called the Monmouth battle, on the 28th of June, 1778. See Monmouth. There is an academy in this town. Freehold contains 3785 inhabitants, of whom 627 are flaves. See Upper Freebold.

FREEHOLD, a township in Albany co. New-York, containing 1822 inhabitants, of whom 562 are qualified electors, and 5 are flaves.

FREEPORT, a township in Cumberland co. district of Maine, fituated at the head of Casco bay; adjoining to Durham on the N. E. and to North Yarmouth on the S. W.; about 10 miles N. E. of Portland, and 140 N. by E. of Botton. It was incorporated in 1789, and contains 1330 inhabitants.

FREESTONE-GAP, a place to called, in Tennestiee, 25 miles from Hawkin's court-house, and 35 from Cumberland mountain.

FREETOWN, a thriving township in Bristol co. Massachusetts, incorporated in 1683; contains 2202 inhabitants, and lies 50 miles southerly of Boston.

FRENCH, a fmall river in Maffachufetts, has its fource in a fmall pond, on the borders of Leicefter and Spencer, in Worcefter co. and runs through Oxford and joins Quinebauge river, in Thompson township, in Connecticut, It derives its name from the French Protestants, who obtained a settlement M in in the town of Oxford, after the revocation of the edict of Nantz, in 1685.

FRENCH AMERICA. The only part of the continent which the French nation now poffels, is the district or pro-vince of Cayenne, and the island of the fame name on its coaft, in S. America. In the West-Indies the French claim the following illands, to which the read-er is referred for a particular defcription : Sti Damingo, or Hifpaniola, Guadaloupe, St. I.ucia, Tobago, St. Bartbalamew, Defeada, and Marigalante.

Defeada, and Marigunants in the laft nations who made fettlements in the W. Indies ; but they made ample amends by the vigour with which they purfued then, and by that chain of judicious and admirable measures which they uled in drawing from them every advantage that the nature of the climate would yield, and in contending against the difficulties which it threw in their way.

FRENCH BROAD, a navigable river in Tenneffee, which rifes on the S. E. fide of the Great Iron and Bald mountains, in N Carolina. It is formed by two main branches, which receive feveral ftreams in their course. These unite about 58 miles from the fource of the Nolachucky, the eaftern branch; thence it flows N. westerly about 25 miles, and joins the Holfton 11 miles above Knoxville, and is 400 or 500 yards wide. The navigation of this branch is much interrupted by rocks, as is alfo the Ten. neffee branch, which joins the main river so miles below this.

A large, clear, medicinal fpring, faid to be efficacious in curing many difeafes, has been lately difcovered on the waters of this river, about 30 miles in a direct line from its mouth. The water is fo hot, that a patient at first going into it can fcarcely fupport it. Nearer the mouth of the river, a valuable lead mine has been discovered.

FRENCH Creek, a N. weftern water of Alleghany river, into which it falls along the N. fide of Fort Franklin, 80 miles N. by E. of Pittiburg, It affords the nearest paffage to lake Erie. It is navigable with fmall boats to Le Beuf, by a very crooked channel; the portage thence to Prefque Ifle, from an adjoining peninfula, is 15 miles. This is the ufu-al route from Quebec to Ohio.

FRO

name of a falt fpring, near which the town of Nafhville now ftands.

FRENCHMAN's Bay, lies on the fea coaft of Lincoln co. Maine, and is formed by Mount Defert island on the weftward, and the peninfula of Goldíbo. inland circular communication with Blue Hill bay.

FRENCH Town, in Cecil co. Maryland, lies on the E. fide of Elk R. a mile S. of Elkton, from which it is feparated by Elk creek. Elk ferry is 6 miles below this.

FRENEUSE Lake, a large collection of water, through which St. John's R. in New-Brunfwick, paffes. In fome maps this appears only as a dilation of the river; but in others it appears as a large lake of very irregular figure, and receiving confiderable ftreams from the circumjacent country.

FRIEDBURG, a Moravian fettlement in Wachovia, or Surry co. N. Carolina. FRIEDLAND, a Moravian fettlement

in Wachovia.

FRIEDENSHUETTEN, a Moravian fettlement, whole name fignifies Tents of Peace, fituated on Stifquehannah R. in Pennfylvania, about 24 miles below Tioga point; eftablished by the United Brethren in 1765. It then confifted of 13 Indian huts, and upwards of 40 houses, built after the European manner, with a neat chapel. Next to the houfes the ground was laid out in gardens; and between the fettlement and the river about 250 acres were divided into regular plantations of Indian corn.

FRIEDENSTADT, or Town of Peace, a Moravian fettlement which was eftablished between Great Beaver and Yellow creeks; about 40 miles N. W. of Pittfburg. It was abandoned in 1773.

FROBISHER's Straits, lie a little to the northward of Cape Farewell and Weft Greenland, and were difcovered by Sir Martin Frobisher. N. lat. 63. W. long. 42.

FROG's Point or Neck, in Weft Chefter co. New-York, lies on the coaft of Long-Ifland Sound, 9 miles from Harlaem heights.

FRONTINAC, FORT, a fortrefs in Canada, fituated at the head of a fine bay or harbour, on the N. W. fide of the outlet of Lake Ontario, where all forts FRENCH Lick, in Tenneffee, is the of yeffels may ride in fafety. It is a league

league fr a fhort about 30 winter ab than at (cultivated ropean a Here is o pects in fummer. mouth of ber of b different and the b veffels at and from is, that tion bet Quebec, gerous, full of ro gether w quois In abandon they had in 1689. repaired tifh, und 1759, to peace in A rive the deput from its near Cad Clie; fr fhort por angle of that is no fouthwar ronto. Frontena King fon. FROW Canfo, a Cape Br long, and FRYD co. Penn FRYI called fro trance of dina; the 32.6 mi 24 S. E. Bald He FRYS pleafanth diffrict o the N. b

ich the

the fea s forme weftoldfborard. has an with

Maryk R. a t is fery is 6

llection in's R. a fome ation of urs as a re, and

P

tlement arolina, tlement

om the

oravian Tents of R. in below United ifted of of 40 in mant to the in garent and divided in corn. Peace, s eftabnd Yel-W. of n 1773ittle to ell and

lat. 63. ft Chefcoaft of m Har-

covered

is in Cafine bay to of the all forts It is a league FRY

league from the mouth of the lake, and a thort diftance S. of Kingston, and about 300 miles from Quebec. The winter about this place is much fhorter than at Quebec ; and the foil is fo well cultivated, as to produce all forts of European and Indian corn, and fruits. Here is one of the most charming profpects in the world, during fpring and fummer. The St. Lawrence and the mouth of Lake Ontario, contain a number of beautiful and fertile iflands of different magnitudes, and well wooded, and the bay often prefents to the view veffels at anchor, and others paffing to and from the lake. But the misfortune is, that the advantageous communication between this lake, Montreal and Quebec, is fomewhat difficult and danerous, on account of the river being full of rocks and water falls. This, together with the ambuscades of the Iroquois Indians, induced the French to abandon and deftroy the ftrong works they had erected here. This happened in 1689. After this they re-took and repaired the place. At length the Britifh, under col. Bradstreet, took it in 1759, to whom it was confirmed at the peace in 1763.

A river has lately been furveyed by the deputy furveyor general of Canada, from its entrance into the lake at Kenty, near Cadaraqui, to its fource in lake St. Clie; from which there is an eafy and fhort portage acrofs N. W. to the N. E. angle of Lake Huron, and another that is neither long nor difficult, to the fouthward, to the old fettlement of Toronto. This is a flort route from Fort Frontenac to Michillimackinack. See King flon.

FROWSACK *Channel*, or the Gut of Canfo, a ftrait between Nova-Scotia and Cape Breton Island, 5 French leagues long, and one broad.

FRYDUFFRIN, a township in Chefter co. Pennsylvania.

FRYING-PAN, a dangerous fhoal fo called from its form. It lies at the entrance of Cape Fear R. in North-Carolina; the S. part of it is in N. lat. 33. 32. 6 miles from Cape Fear pitch, and 24 S. E. by S. from the light-house on Bald Head.

FRYSBURGH, or Fryburg, a township pleafantly fituated in York co. in the diffrict of Maine, in a bow formed by the N. branch of Great Offipee R. It Maryland.

was incorporated in 1777, has a flourifhing academy, and contains 447 inhabitants. This is the ancient Indian village Peckwalket, through which the upper part of Saco meanders; 60 miles from the fea, and 120 N, by E. of Bofton. N. lat. 44. 2. W. long. 70. 47.

FUCA, STRAITS OF JUAN DE, lie on the N. W. coaft of N. America. The entrance lies between Cape Flattery on the S. fide, in N. lat. 48. 25. W. long. 324. 52. to the opposite coaft of the Quadras ifles, in N. lat. 48. 53. 30. It communicates with Pintard's found, and thus forms Quadras lifles; in the S. eaftern coaft, of which lies Nootka found. See Pintard found. The Spaniards jealous of the function of the American coaft, eftablished a fettlement at this place.

FUEGO. See Terra del Fuego.

FULL MOON Shoal. See Hatteras. FUNDY, a large bay in N. America, which opens between the islands in Penobicot bay, in Lincoln co. Maine, and Cape Sable, the S. weftern point of Nova-Scotia. It extends about 200 miles in a N. E. direction; and with Verte bay, which pushes into the land in a S. W. direction from the farits of Northumberland, forms a very narrow ifthmus, which unites Nova-Scotia to the continent; and where the division line runs between that province and New-Brunfwick. From its mouth up to Paffamaquoddy bay, on its N. W fide, fituated between the province of New-Brunswick and the district of Maine, are a number of bays and iflands on both fides, and thus far it contracts its breadth gradually. It is 12 leagues acrofs from St. John's, in New-Brunfwick, to the Gut of Annapolis, in Nova-Scotia; where the tides are rapid, and rife 30 feet. Above this it preferves nearly an equal breadth, until its waters are formed into two arms, by a peninfula, the western point of which is called Cape Chignecto. At the head of the N. eastern arm, called Chignecto channel, which, with bay Verte forms the ifthmus, the tides rife 60 feet. In the Bafin of Minas, which is the E. arm or branch of this bay, the tides rife 40 feet. These tides are fo rapid as to overtake animals feeding on the fhore. FUNKSTOWN. See Jerufalem, in

M 2

GABARON,

educated a state of the state o

lite anabal , and G if as and

ABARON, a bay on the S. W. of I Louisburg, in the island of Cape Breton.

GABORI, a bay on the S. E. coaft of Cape Breton ifland. The entrance into it, which is not more than 20 leagues rom the illes of St. Pierre, is between iflands and rocks about a league in dth. The bay is 2 leagues deep, and affords good anchorage.

GABRIEL, ST. an ifland in the great river La Plata, S. America, discovered by Sebaftian Cabot, in the year 1 526.

GACHPAS, an Indian tribe, formerly in alliance with the Delawares.

GAGE's Town, a fettlement in Sunhury co. New-Brunfwick ; on the lands granted to general Gage, on the W. fide of St. John's R. on the northern fhore of the bay of Fundy. The general's grant confifts of 20,000 acres of land; the up-land of which is in general very bad. There is fome intervale on the river fide, on which are a few fettlers's exclusive of these settlements, there is very little good land of any kind.

GALEN, a military township in the ftate of New-York, fituated on Canada que creek, 12 miles N. W. of the N. end of Cayuga lake, and 13 S. by E. of Great Sodus. It is bounded S. by Junius.

GALETS, an ifland at the E. end of lake Ontario, and in the state of New-York, 5 miles S. westward of Roebuck ifland, 5 northerly of Point Gaverie, and . S. E. of Point au Goelans.

GALETTE, LA, a neck of land in the river St. Lawrence, in Canada. From the point opposite to l'isle de Montreal, a road might be made to Galette, so as to fave 40 leagues of navigation, which the falls render almost impracticable, and always very tedious. The land about La Galette is very good ; and in two days time a barque may fail thence to Niagara, with a good wind. La Galette is a league and a half above the fall called les Galots.

GALIBIS, or Charaibes, a nation of Indians inhabiting near New-Andalufia, in S. America; from which the Charaibes of the West-Indies are thought to be defeended.

GAL

co or New-Spain, containing 7 provinces. Guadalaxara is the capital city. GALIPAGO Ifes, the name of feveral uninhabited ifles in the South Sea, on both fides the equator, not far from the coaft of Terra Firma; belonging to Spain. They lie between 3. N. and 4. S. lat. and hetween 83. 40. and 89. 30. W. long. There are only 9 of them of any confiderable fize; fome of which are 7 or 8 leagues long, and 3 or 4 broad. Dampier faw 14 or 15 of them. The chief of these are Norfolk, nearest the continent, Wenmore among the N. wefternmost and Albemarle the westernmost of all. A number of fmall ifles lie W. from thefe, on both fides the equator; one of which, Gallego I. lies in the sft degree of N. lat. and 102. of W. long. Many of these isles are well wooded, and fome have a deep black mould. Vaft quantities of the fineft turtle are to be found among these islands, where they live the greatest part of the year; yet they are faid to go from thence over to the main to lay their eggs, which is at least 100 leagues distant.

S GALLAN, ST. a fmall ifland on the coaft of Peru, in lat. 14. S. 5 miles N. of the high land Morro Veijo, or Old Man's Head ; between which island and the high land, is a most eligible station to cruize for veffels bound for Callas, N. or S.

GALLIOPOLIS, a post town in the N. W. territory, fituated on a bend of the Ohio, and nearly opposite to the mouth of the great Kanhaway. It is faid to contain about 100 houses, all inhabited by French people. It is 140 miles eaftward of Columbia, 300 S. W. of Pittf-burg, and 550 S. W. of Philadelphia. N. lat. 39. 2. W. long. 83. 9.

This town is faid to be on the decline, their right to the lands not being fufficiently fecured.

GALOTS, the lowest of the falls on the river St. Lawrence in Canada. Between the neck of land la Galette and les Galots is an excellent country, and no where can there be feen finer forefts.

GALOTS, D'ISLE AUX, an ifland in the river St. Lawrence, in Canada; 3 leagues beyond l'ifle aux Chevres, in N. lat. 43 33.

GALLO, an ifland in the provinco of Popayan, S. America, in N. lat. 2. 40. Captain Dampier fays it is fituated in a GALICIA, an audienc in Old Mexi- deep bay, and that off this ifland there

GASPE S. of Prov the wester

REAL

star male

rovin-

feveral

ea, on

om the

ing to

and 4.

9. 30.

hem of

ich are

broad.

reft the

. weft-

ernmuft

lie W.

uator :

the sft

. long.

vooded,

mould.

e are to

where

e year;

ice over

which is

on the

niles N.

or Old

and and

e ftation

Callao,

n the N.

d of the

e mouth

a faid to

nhabited

iles eaft-

of Pittf-

delphia.

the de-

ot being

falls on

da. Be-

lette and

try, and

r forefts.

ifland in

inada; 3

evres, in

ovinco of

t. 2. 40.

nated in a

and there

18

.

The

city.

is not above 4 or 5 fathom water; but at Segnetta, which is on the N. fide, a vefiel may ride in deep water, free from any danger. The illand is high, provided with wood and good water, and having good fandy bays, where a fhip may be cleaned. Alfo, the name of an island of the S. fea, near the coaft of Peru, which was the first place posses by the Spaniards, when they attempted the conquest of Peru.

GALLOWAY, a township in Gloucester co. New-Jerfey.

GALWAY, a township in the new county of Saratoga, in New-York. By the fate cenfus of 1796, it appears that 491 of its inhabitants are qualified to be electors.

GAMBLE's Station, a fort about 12 miles from Knoxville, in Tenneffce.

GAMMON, POINT, anciently called Point Gilbert, by Gofnold, forms the caftern fide of the harbour of Hyanis or Hyennes, in Barnstable co. Massachusetts. GANNELOR, a finall island in the

gulf of St. Lawrence, in N. lat. 48. near Bird island.

GARAZU, a town in Brazil; and province of Pernambuco, 25 miles N. of Olinda.

GARDNER, a township in Worcester co. Maffachufetts, incorporated in 1785. It contains about 14,000 acres, well watered, chiefly by Otter R. The road from Connecticut R. thro' Petersham, Gerry, and Templeton on to Bofton, passes through it. It contains 531 inhabitants, and is 26 miles N. by W. of Worcefter, and 60 N. W. of Bofton.

GARDNER's Island, or Isle of Wight, lies at the E. end of Long-Ifland, in New-York ftate, fheltered within Oyfter Pond and Montauk points; 10 miles N. W. of the latter, and as far S. W. of Plumb I. It contains about 3000 acres of fertile land, the property of one perfon, and yields excellent grafs, wheat and corn. Fine theep and cattle are raifed on it. It is annexed to Eaft Hampton, and lies 40 miles fouth-wefterly of Newport, Rhode-Ifland.

GASPE, or Gachepe, a bay and head-land S. of Florell ifle, which lies be-tween it and Cape Rofiers, on the E. coaft of Lower Canada, and W. fide of the gulf of St. Lawrence.

GASPEE, or Namquit Point, 7 miles S. of Providence (R. I.) projecting from the weftern fhore of Providence river,

30

GEM

remarkable as being the place where the British armed schooner, called the Galpee, was burnt, June 10, 1772, by about 60 men from Providence, painted like Narraganset Indians. For the caufe of this transaction, see Gordon's

Hift. of the Amer. Rev. vol. I. p. 311. GASPESIA, a tract of country on the S. fide of the mouth of St. Lawrence R. and on the N. fide of Chaleurs bay, in Lower Canada. Its E. extremity is Cape Rofiers. The Indians called Gafpefians inhabit here.

GATES Co. in Edenton eastern diftrict, N. Carolina, is bounded N. by the ftate of Virginia, S. by Chowan co. It contains 5392 inhabitants, including 2219 flaves. Chief town, Hertford.

GAY Head, is a kind of peninfula on Martha's Vineyard, between 3 and 4 miles in length, and 2 in breadth, and almost separated from the other part of the island by a large pond. The Indians inhabiting this part, when lately numbered, amounted to 203. The foil is good, and only requires cultivation to produce most vegetables in perfection. There are evident marks of there. having been volcanoes formerly on this peninfula. The marks of 4 or 5 craters are plainly to be feen. The most foutherly and probably the most ancient, as it is grown over with grafs, now called the Devil's Den, is at least 20 rods over at the top, 141 at the bottom, and full 130 feet at the fides, except that which is next the fea, where it is open. A man now alive relates, that his mother could remember when it was common to fee a light upon Gay Head in the night time. Others fay, their anceftors have told them, that the whalemen used to guide themfelves in the night by the lights that were feen upon Gay Head. The fea has made fuch encroachments here, that, within 30 years, it has fwept off 15 or 20 rods. The extremity of Gay Head is the S. W. point of the Vineyard, N. lat. 41.20.W. long. from Greenwich 70. 50.

GEKELEMUEKPECHUENK, a town of the Delaware Indians, on a creek of the fame name, a head water of the Mufkingum. This was the northernmost Moravian fettlement on Mutkingum R. It lies 12 miles N. E. by N. of Salem, and 78 N. wefterly of Pittfburg.

GEMESIE, a fort on the river St. John's, which was taken by the English in 1674. M 3

GENESSEE,

GENESSEE, a township in Ontario co. New-York, having 217 electors.

GENESSEF Country, à large tract of land in the ftate of New-York, bounded N. and N. W. by lake Ontario, S. by Pennfylvania, E. by the weftern part of the military townfhips, in Onondago eo. and W. by lake Erie and Niagara R. It is a rich tract of country, and well watered by lakes and rivers; one of the latter, Geneffee R. gives name to this tract. It is generally flat, the rivers fluggifh; the foil moift, and the lakes numerous.

GENESSEE River. See Cheneffee.

GENEVA, a lake in Upper Canada, which forms the W. extremity of lake Ontario; to which it is joined by a fhort and narrow ftrait.

GENEVA, a post town in Onondago co. New-York, on the great road from Albany to Niagara, fituated on the bank of the N. W. corner of Seneca lake, about 74 miles W. of Oneida caftle, and 92 W. of Whitestown. "The Friends settlement lies about 18 miles below this. Here were 20 log-houses, and a few other buildings several years ago, which have much increased fince." GENEVIEVE, ST. or Missier, a village in Louissan, on the western bank of the Missifippi, nearly opposite to the village of Kaskaskias, 12 miles southerly of Fort Chartres. It contained about 20 years ago, upwards of 100 houses, and 460 inhabitants, besides Negroes.

GEORGE'S ST. a cape and iflands nearly opposite to the river Apalachicoha on the coaft of E. Florida. Cape St. George's lies about 6 leagues to the eastward of Cape Blaize, being an elbow of the largeft of St. George's iflands, in N. lat. 29. 8. There is a large fhoal running out from it a confiderable way, but how far has not yet been afcertained. The coaft between it and Cape Blaize; forms a kind of hollow bay, with deep foundings and a foft bottom. There are two iflands to the N. W. of St. George's Cape; that nearest to it is fmall, and remarkable for a clump of ftraggling trees on the middle of it; 'the other is pretty large, and of a triangular form, and reaches within 3 leagues of Cape Blaize, 'having a paffage 'at each end of it for fmall craft 'into the bay, between these islands and the river Apalachicola; but this bay is full of fhoals and oyster-banks, and not above

two or three feet water at most, in any of the branches of that river.

GEORGE, FORT, was fituated on Point Comfort, at the mouth of James R. and 5 miles N. E. of Craney illand, at the mouth of Elizabeth R. in Virginia. See Comfort.

GEORGE, FORT KING, an ancient, fort in Georgia, which flood 5 miles N. E. of the town of Darien, in Liberty co. fituated at the head of a creek which flows into the ocean opposite Sapelo I. It is now in ruins.

GEORGE, LAKE, in East Florida, is dilation of the river St. Juan, or St. John, and called also Great Lake. It is about 15 miles wide, and generally about 15 or 20 feet deep, excepting at the entrance of the river, where lies a bar, which carries 8 or 9 feet water. The lake is beautified with two or three fertile iflands. The largest is about 2 miles broad, and commands a most delightful and extensive prospect of the waters, iflands, E. and W. thores of the lake, the capes, the bay and mount Royal ; and to the S. the view is very extensive. Here are evident marks of a large town of the aborigines, and the island appears to have been once the cholen refidence of an Indian prince. on the fcite of this ancient town ftands a very pompous Indian mount, or conical pyramid of earth, from which runs in a fraight line, a grand avenue or Indian highway, through a magnificent grove of magnolias, live oaks, palms and orange trees, terminating at the verge of a large, green, level favanna. From fragments dug up, it appears to have been a' thickly inhabited town.

See St. John's river. GEORGE, LAKE, lies to the fouthward of lake Champlain, and its waters lie about 100 feet higher. The portage between the two lakes is a mile and a half; but with a fmall expence might be reduced to 60 yards; and with one or two locks might he made navigable through; for batteux. It is a most clear, beautiful collection of water; 36 miles long, and from 1 to 7 wide. It emboloms more than '200 iflands, fome fay 365; very few of which are any thing more than barren rocks, covered with heath, and a few cedar, fpruce and hemlock trees, and fhrubs, and abundance of rattle-inakes. On each fide it is fkirted by prodigious mountains ;

ountains;

GEO

mountains; from which large quantities of red cedar are annually carried to New-York for thip timber. The lake is full of fishes, and some of the best kind, as the black or Ofwego bafs, alfo large speckled trouts. It was called lake Sacrament by the French, who, in former times, were at the pains to procure this water for facramental uses in all their churches in Canada : hence probably it derived its name. The remains of Fort George stand at the S. end of the lake, about 14 miles N. by W. of Fort Edward, on Hudfon river. The famous fort of Ticonderoga, which ftood at the N. fide of the outlet of the lake, where it discharged its waters into lake Champlain, is now in ruins. See Champlain and Ticonderoga.

GEORGE's, ST. an island and parish belonging to the Bermuda isles, in the West-Indies. N. lat. 32.45. W. long. 63. 30.

GEORGE's, Sr. a large and deep bay on the W. fide of Newfoundland island, N. lat. 48, 12.

GEORGE'S BANK, ST. a fifting bank in the Atlantic ocean, E. of Cape Cod, in Maflachufetts. It extends from N. to S. between 41. 15. and 42. 22. N. lat. and between 67. 50. and 68. 40. W. long.

GEORGE'S KEY, ST. was one of the principal British settlements in the bay of Honduras. It was taken by the Spaniards during the American war, but retaken by the British soon after.

The British fettlements on the Mosquito shore, and in the bay of Honduras, were furrendered to the crown of Spain, at the Spanish convention, figned at London, the 14th of July, 1786.

GEORGE'S RIVER, ST. in St. Mary's co. Maryland, is a very broad but fhort creek, whole mouth lies between Piney Point and St. Mary's R. on the N. bank of the Potowmack, opposite the island of the fame name.

GEORGE'S RIVER, ST. in Lincoln co. diffrict of Maine, or rather an arm of the fea, lies about 2 leagues S. W. of Penobicot bay. Four leagues from the mouth of this river stands Thomaston. This river is navigable for brigs and ships of a large burden up to the narrows; and from thence about 4 miles higher, to nearly the head of the tide, for sloops and schooners of 80 or 90 tous. It is about half a league wide up

to the narrows. Of late feveral confiderable veffels have been built in this river, which are employed in coaffing, and fometimes in foreign voyages. There are now owned in this river, though it does not in all exceed 4 leagues in length, τ brig, 2 topfail fchoohers, and 9 floops: in all about 1100 tons. The navigation, however, is generally interrupted in winter, when not only the freams through the country, but the falt water rivers are locked up until fpring. Fifth abound here, of almoft all kinds, in their feafon; and even lobfters; oyfters, clams, and other delicacies of the aqueous kind, are plenty in this river.

GEORGE's, ST. a villagenearly in the centre of Newcaftle co. Delaware, on a creek of its own name, which falls into Delaware R. 4 miles below, a little above Reedy Island. It is 17 miles S. by W. of Wilmington, and 45 S. W. of Philadelphia.

GEORGE's, ST. the capital of the ifland of Grenada, in the W. Indies formerly called Fort Royale, which name the Fort ftill retains. It is fituated on a fpacious bay, on the W. or lee fide of the ifland, not far from the S. end, and poffeffes one of the fafeft and most commodious harbours in the British W. Indies, which has lately been fortified at a very great expence, and declared a free port. This town was defroyed by a dreadful fire in 1771, and on November 1, 1775, it met with the like miffortune; and the lofs was valued at £. 500,000. The town now makes a very handfome appearance, has a fpacious fquare or parade; the houfes are built of brick, and tiled or flated; fome few are built of ftone, excepting the warehouses and dwelling houses round the harbour, which are moftly wooden build-These are in a great measure ings. feparated from the town by a very fleep and rocky hill, the houfes on which, with the trees which ferve for flade, have a romantic appearance. The town is computed to contain about 2000 inhabitants, many of whom are wealthy merchants. This was its fitution before the infurrection of the negroes ; of its prefent fate we have not authentic information.

GEORGETOWN, the chief town of Suffex co. Delaware, is fituated 16 miles W. S. W. of Lewistown, and 103 S. of M 4. Philadelphia.

Philadelphia. It contains about 30 houfes, and has lately been made the feat of the county courts.

184

GEORGETOWN, a post town in Maryland, fituated in Kent co. on the E. fide of Chefapeak bay, of about 30 houses. It is 9 miles from the mouth of the river Saffafras, being seated on the S. fide opposite to Frederick, 60 N. E. of Chefter, and 65 S. W. of Philadelphia.

GEORGETOWN, a village of Fayette co. Pennfylvania, fituated on the S. E. fide of Monongahela R. at the mouth of George's creek. Here a number of boats are annually built for the trade and emigration to the weftern country. It lies 16 miles S. W. of Union.

GEORGETOWN, a poft town and port of entry, in Montgomery co. Maryland, and in the territory of Columbia. It is pleafantly fituated on a number of fmall hills, upon the northern bank of Potowmack R.; bounded eaftward by Rock creek, which feparates it from Washington city, and lies 4 miles from the capitol, and 8 N. of Alexandria. It contains about \$30 houfes, feveral of which are elegant and commodious. The Roman Catholics have eftablished a college here, for the promotion of general literature, which is at prefent in a very flourishing state. The building being found inadequate to contain the number of fludents that applied, a large addition has been made to it. Georgetown carries on a fmall trade with Europe and the W. Indies. The exports in one year, ending Sept. 30, 1794, amounted to the value of 128,924 dollars. It is 46 miles S. W. by W. of Baltimore, and 148 S. W. of Philadelphia.

GEORGETOWN, in Lincoln co. diftrict of Maine, is fituated on both fides of Kennebeck R. It was incorporated in 1716, is the oldeft town in the county, and contains 1333 inhabitants. It is bounded foutherly by the ocean, wefterly by the towns of Harpswell and Brunfwick, N. wefterly by Bath, and eafterly by Woolwich; being entirely furrounded by navigable waters, excepting about 2 miles of land, which divides the waters of Winnagance creek, a part of the Kennebeck, from an arm or influx of Cafco bay, called Stephen's R. The entrance at the mouth of Kennebeck R. is guided on the E. by Parker's ifland, belonging to this township. It GEO

contains about 28,000 acres of land and falt marsh, and is inhabited by more than one third part of the people of the township. This was the fpot on which the Europeans first attempted to colonize New-England, in the year 1607. It is a part of what was called Sagadahock ; and the patentees of the Plymouth company began here to lay the foundation of a great state. They fent over a number of civil and military officers, and about 100 people. By various miffortunes they were forced to give up the fettlement, and in 1608, the whole number who furvived the winter returned to England.

There was a tradition among the Norridgewalk Indians, that these planters invited a number of the natives, who had come to trade with them, to draw a small cannon by rope, and that when they were ranged in a line, the white people discharged the piece, and thereby killed and wounded feveral of them. The resentment of the natives at this treacherous murder, obliged the-Europeans to reimbark the next fummer. Georgetown is 15 miles S. of Pownalborough, and 170 N. by E. of Boston.

GEORGETOWN, a post town of Georgia, in the co. of Oglethorpe, 50 miles S. W. of Augusta, surrounded by a poor country; but nevertheles, exhibits marks of growing prosperity.

GEORGETOWN, a large maritime diftrift in the lower country of S. Carolina, fituated in the S. E. corner of the state; bounded N. E. by the state of N. Carolina, S. E. by the ocean, S. W. by Santee river, which divides it from Charlefton diffrict, and N. W. by Camden and Cheraw districts. It is about 112 miles from N. to S. and 63 from E. to W. and is divided into the parifhes of All Saints, Prince George, and Prince Frederick. It contains, according to the cenfus of 1790, 22,122 inhabitants, of whom 13,131 are flaves. It fends to the state legislature 10 representatives and 3 fenators, and pays taxes to the amount of 35851. 128. 6d.

GEORGETOWN, a post town, port of entry, and capital of the above diffrict, and is fituated on a spot near which several streams unite their waters, and form a broad stream called Winyaw bay, 12 miles from the sea. See Pedee River. Its fituation connects it with an extenfive Gve back and wou ance, w trance of rupts th above II spects a tains abo wood. court-ho churches Baptifts, There is Indies. ing Sept 21,5110 N. of C mington ladelphi GEOI of N. A 37. and and gr. miles in in bread Atlantic rida; V E. and neffee ft into par but late and Loy 24 cou diffrict Chatha Scriven the Up Washin lin, Og coln, V lock, C princip the feat former Brunfw Louifvi the ftat records late leg licly b The Georg it from which and A the oth merou Little

/ more of the which colo-1607. agadamouth oundaover a fficers, us mifup the whole returnig the plantatives, em, to e, and a line, : piece, feveral he naoblige next iles S. by E. f Georo miles y a poor s marks ime dif-Caroliof the tate of S. W. it from y Cams about rom E. parifhes Prince ling to bitants, t fends ntatives to the port of diffriet,

nd and

hich fers, and aw bay, River. n extenfive

GEO

five back country of both the Carolinas; and would be a place of vaft importance, were it not for a bar at the entrance of Winyaw bay, which interrupts the entrance of veffels drawing above II feet water, and is in many respects a dangerous place. It contains tains above 300 houses, built chiefly of wood. The public buildings are a court-house, gaol, and academy; 3 churches, of which the Epifcopalians, Baptifts, and Methodifts have one each. There is here a fmall trade to the Weft Indies. The exports for one year, ending Sept. 30, 1795, were to the value of 21,511 dollars. It is 60 miles N. E. by N. of Charlefton, 127 S. W. of Wilmington, N.Carolina, and 681 from Philadelphia, N. lat. 33.24. W. long. 79.35. GEORGIA, one of the United States of N. America, is fituated between 30. 37. and 35 N. lat. and between 80. S. and 91. 8. W. long. being about 600 miles in length, and on an average 250 in breadth. It is bounded E. by the Atlantic ocean; S. by E. and W. Florida; W. by the river Miffifippi; N. E. and N. by S. Carolina and the Tenneffee state. It was formerly divided into parifhes, afterwards into 3 diffricts, but lately into two districts, viz. Upper and Lower, which are fubdivided into 24 counties as follow: In the lower district are Camden, Glynn, Liberty, Chatham, Bryan, M'Intofh, Effingham, Scriven, and Burke. The counties in the Upper District are Montgomery, Washington, Hancock, Greene, Franklin, Oglethorpe, Elbert, Wilkes, Lincoln, Warren, Jefferson, Jackson, Bullock, Columbia, and Richmond. The principal towns are Augusta, formerly the feat of government, Savannah, the former capital of the ftate, Sunbury, Brunswick, Frederica, Washington, and Louisville, which is the metropolis of the ftate; and here are deposited the records of the ftate, fuch of them as a late legislature did not order to be publicly burnt.

The principal rivers which water Georgia are, Savannah, which separates it from S. Carolina; Ogeechee river, which runs parallel with the former, and Alatamaha, which runs parallel with the others. Befides these and their numerous branches, there is Turtle river, Little Sitilla, Great Sitilla, Crooked R.

and St. Mary's, which forms a part of the fouthern boundary of the United States. The rivers in the middle and weftern parts will be noticed under the head of Georgia Western Territory. All these are flored with a great variet yof fifh, as rock, mullet, whiting, fhad, trout, drum, bafs, catfifh, white, brim, and fturgeon; and the bays and lagoons are fupplied with oyfters, and other fhell-fith, crabs, fhrimps, &c. The clams, in particular, are large, their meat white, tender, and delicate. The fhark and great black ftingray are infatiable cannibals, and very troublefome to the fifhermen. The chief lake or marfly is Ekanfanoka, by fome called Ouaquaphenogaw, which is 300 miles in circumference.

GEO

The eaftern part of the ftate, between the mountains and the ocean, and the rivers Savannah and St. Mary's, a tract of country more than 120 miles from N. to S. and from 50 to 80 E. and W. is level, without a hill or ftone. At the diffance of about 40 or 50 miles from the fea board, or falt marfh, the lands begin to be more or lefs uneven. until they gradually rife to mountains. The vaft chain of the Alleghany or Appalachian mountains, which commence with the Kaats Kill, near Hudsón R. in the ftate of New-York, terminate in Georgia, 60 miles S. of its northern boundary. From the foot of this mountain spreads a wide extended plain, of the richeft foil, and in a latitude and climate well adapted to the cultivation of most of the productions of the fouth of Europe, and of the East Indies. In the low country, near the rice fwamps, bilious complaints and fevers of various kinds are pretty univerfal, during the months of July, August, and September : but the fertility of the foil, and the eafe with which it is improved, are a fufficient inducement to fettlers, and an unfailing fource of wealth. Before the fickly featon approaches, the rich planters, with their families, remove to the fea-iflands, or fome elevated, healthy fituation, for the benefit of the frefh air. In the winter and fpring, pleurifies, peripneumonies, and other inflammatory diforders, occasioned by violent and fudden colds, are confiderably common, and frequently fatal. Confumptions, epilepfies, cancers, palfies, and apoall and transfell (, and plexics

plexies, are not fo common among the inhabitants of the fouthern as northern climates.

GEO

The winters in Georgia are very mild and pleafant. Snow is feldom or never feen f nor is vegetation often prevented by fevere frofts. Cattle fubfift tolerably well during the winter, feeding in the woods and favannas, and are fatter in that feafon than in any other. In the hilly country, which begins about 50, and in fome places roo miles, from the fea, the air is pure and falubrious, and the water plenty and good. From June to September the mercury in Fahrenheit's thermometer commonly fluctuates from 76. to go. In winter from 40. to 60. The most prevailing winds are S. W. and E.; in winter N. W. The E. wind is warmeft in winter and coeleft in fummer. The S. wind in fummer and fall particularly, is damp, fultry, unelaftic, and of courfe unhealthy. In the S. E. parts of this flate, which lie within a few degrees of the torrid zone, the atmosphere is kept in motion by impreflions from the trade winds. This purifies the air; fo that it is found to ave falutary effects on confumptive habits.

In the low lands are the rice fields. In the interior and hilly parts, wheat, Indian corn, and the other productions more common to the northern ftates. Rice is at prefent the ftaple commodity of the ftate; tobacco, wheat and indigo are the other great articles of produce. Befides thefe the flate yields cotton, filk, corn, potatoes, oranges, figs, olives, pomegranates, &c. The forefts confift of oak, hickory, mulberry, pine, cedar, &c. The whole coaft is bordered with iflands; the principal of which are Skidaway, Waffaw, Offabaw, St. Catherines, Sapelo, Frederica, Jekyl, Cumberland, &c. These islands are fur rounded by navigable creeks, between which and the main land is a large extent of falt marsh, fronting the whole fate, not lefs, on an average, than 4 or 5 miles in breadth, interfected with creeks in various directions, admitting, through the whole, an inland navigation, between the iflands and the main land, from the N. E. to the S. E. corners of the flate. The E. fides of thefe iflands are, for the most part, clean, hard, fandy beaches, exposed to the wash of the ocean. Between these islands are

the entrances of the rivers from the interior country, winding through the low falt marfhes, and delivering their waters into the founds, which form capacious harbours of from 3 to 8 miles over, and which communicate with each other by parallel falt creeks.

GEO

The foil and its fertility are various, according to fituation and different improvement. The islands in their natural state are covered with a plentiful growth of pine, oak, hickory, live oak [an uncommonly hard and very valuable wood] and fome red cedar. The foil is a mixture of fand and black mould, making what is commonly called a grey foil. A confiderable part of it, particularly that whereon grow the oak, hickory and live oak is very rich, and yields on cultivation, good crops of indigo, cotton, corn, and potatoes. The foil of the main land, adjoining the marfhes and creeks is nearly of the fame quality with that of the iflands : except that which borders on those rivers and creeks, which ftretch far back into the country. On thefe, immediately after you leave the falts, begin the valuable rice fwamps, which, on cultivation, afford the prefent chief staple of commerce.

The foil between the rivers, after you leave the fea board, and the edge of the fwamps, at the distance of 20 or 30 miles, changes from a grey to a red colour, on which grows plenty of oak and hickory, with a confiderable intermixture of pine. In fome places it is gravelly, but fertile, and fo continues for. a number of miles gradually deepening the reddifh colour of the earth, till it changes into what is called the Mulatto foil, confifting of a black and red earth. The Mulatto lands are generally ftrong, and yield large crops of wheat, tobacco, corn, &c. To this kind of land fucceeds by turns a foil nearly black and very rich, on which grow large quantities of black walnut, mulberry, &cc. This fucceftion of different foils continues uniform and regular, though there are fome large veins of all the different foils intermixed; and what is more remarkable, this fucceffion, in the order mentioned, ftretches acrois this state nearly parallel with the fea coaft, and extends through the feveral flates, nearly in the fame direction, to the banks of Hudfon river.

Cotton was formerly planted here, only

Indian every y phlox I The li ftalk fo rife up fucceffi year be The ba not qui phlox of filky as kind w rate la cotton feveral their p new I into t lately from iflands to a g of the This and is acquif cotton diffing the gro plante on the was bi the B profpe of S. C to rail of co Moft in thi The and th which fome 1 of Ar port lumbe fnake and li mers 1,000 The ports 1 5,74 value 458,9

only by

that on

ed two

the inthe low eir wan capa-3 miles th each

various, ent imir natulentitul ive oak aluable he foil mould, a grey partie oak. h, and s of in-. The ing the he fame except ers and into the y after aluable

ion, af-

f com-

fter you e of the o miles. our, on ickory, of pine. fertile, f miles colour what is ng of a Aulatto d yield rn, &c. y turns ich, on f black fuccefiniform ne large mixed: his fuctretches vith the he feve-

d here, only

rection,

GEO

only by the poorer class of people, and that only for family use. They planted two kinds, the annual and the Weft Indian; the former is low, and planted every year; the balls are large, and the phlox long, ftrong, and perfectly white. The latter is a tall perennial plant, the falk fomewhat fhrubby, feveral of which rife up from the root for feveral years fucceffively, the ftems of the former year being killed by the winter frofts. The balls of the West-India cotton are not quite fo large as the other, but the phlox or wool is long, extremely fine, filky and white. A plantation of this kind will laft feveral years, with moderate labour and care. The culture of cotton is now much more attended to ; feveral indigo planters have converted their plantations into cotton fields. A new species is about to be introduced into this flate, the feed of which was lately brought by Capt. Jofiah Roberts from Waitahoo, one of the Marquefa islands in the S. Pacific ocean, and fent to a gentleman in Georgia by a member of the Hiftorical Society in Bofton. This cotton is of a very fine texture, and is expected will prove a confiderable acquisition to the southern states. The cotton at present raised in Georgia, is diffinguished by some into two kinds, the green and black feed ; the former is planted in the Upper Country, the latter on the fea-iflands and adjacent lands, and was brought, about the year 1788, from the Bahamas. And there is now a prospect, that in a few years the States of S. Carolina and Georgia may be able to raile more than ten millions of pounds of cotton annually for exportation. Molt of the tropical fruits would flourish in this State, with proper attention. The fouth-western part of this State, and the parts of East and West Florida, which lie adjoining, will, probably, in fome future time, become the vineyard of America. The chief articles of export are rice, tobacco, indigo, fago, lumber, naval ftores, leather, deer-fkins, fnake-root, myrtle and bees wax, corn, and live flock. The planters and farmers raife large flocks of cattle, from 1,000 to 1,500 head, and fome more. The value in sterling money, of the exports of Georgia, in the year 1755, was 1 5,7441 .-- in 1772, 121,6771.-- in 1791, value in dollars 491,472-in 1792, 458,973-in 1794, 501,383-in 1796, GEO

676,154, and in 1796, 950,158. In 1790, the tonnage employed in this flate was 28, 540, and the number of American feaman 11,225. In return for her exports Georgia receives W. India goods, teas, wines, cloathing, and dry goods of all kinds. From the northern States, cheefe, fish, potatoes, apples, cider, and fhoes. The imports and exports are principally to and from Savannah, which has a fine harbour, and is the place where the principal commercial bufinels of the State is transacted. According to the cenfus of 1790, the number of inhabitants amounted to \$2,548, of whom 29,264 were flaves. The increafe by emigration and otherwife, has been very confiderable fince. The different religious fects are Prefbyterians, Episcopalians, Baptifts, and Methodifts. They have but few regular ministers among them. The citizens of Georgia have lately revised and altered their conftitution, and formed it upon a plan fimilar to the federal Conftitution of the United States. The literature of this State, which is yet in its infancy, is commencing on a plan which, if ever carried into effect, will be very advantageous to the State. A college with ample and liberal endowments, is inftituted in Louisville, a high and healthy part of the country, near the centre of the State. There is also provision mad for the inftitution of an academy in each county of the State, to be supported from the fame funds, and confidered as parts and members of the fame inftitution, under the general fuperintendance and direction of a prefident and board of truftees, felected for their literary accomplifhments from the different parts of the State, and invefted with the cuftomary powers of corporations. This inftitution is denominated The Univerfity of Georgia. The funds for the fupport of literary inftitutions are principally in lands, amounting in the whole to 50,000 acres, a great part of which is of the best quality, and at prefent very valuable; together with nearly 6000l. fterling in bonds, houfes, and town lots in Augusta. Other public property to the amount of 1000l. in each county, has been fet apart for the purposes of building and furnishing their refpective academies. The funds originally defigned to fupport the literary orphan-houfe, founded by the Rev. Geo. Whitefield.

Whitefield, are chiefly in rice plantations parts of this territory where the Indian On the death of the d negroes. Counters of Huntingdon, to whom Mr. Whitefield bequeathed this property, as truthee, the legislature, in the year 1792,

GEO

triffee, the legillature, in the year 1792, paffed a law vefting it in 13 commit-tioners, with powers to carry the origi-nal intention of Mr. Whitefield into execution; and in compliment to the Countefs, the feminary is flyled Hun-tingdon College. This State was first lettled in the year 1732, and was the only colony fettled at the expence of the crown. GEORGIA WESTERN TERRITORY. Under this name is included all that part of the State of Georgia which lies weft of the head waters of those rivers which fall into the Atlantic Ocean. This ex-tensive tract of country embraces fome of the fineft land in the United States, is interfected with a great number of noble of the fineft land in the United States, is interfected with a great number of noble rivers, which may be feen by an infpec-tion of the map, and is inhabited (ex-cept fuch parts wherein the Indian title has been extinguished) by three nations of Indians, viz. the Mufkogulge or Creek, the Chactaws, and Chickafaws. The Cherokees also have a title to a finall portion of the northern part of this ternitory, on the Tenneffee river. this territory, on the Tenneffee river. These nations together can furnish be-tween 3 and 9000 warriors. About 2000 families of white people inhabit those


parts of this territory where the Indian title has been extinguished, chiefly at the Natchez, and the Yaxoo river, on the banks of the Mislifippi, and a confider-able number on the Tombigbee river, and fcattered among the Creek Indians. This territory, for reasons which will hereafter appear, has lately become an object of much public attention and inquiry, in Europe, as well as in the United States; and on this account, the follow-ing defcription of it and flatement of facts relative to the fale of certain parts of it, and the claims of the United States, &c. have been collected and arranged with great care from the most authentic fources that can be obtained, and given under this head for the information of the public. * This territory, lying between the 31ft and 35th degrees of N. latitude, is not subject to the extremes of heat or cold : the climate is temperate and delightful through the year; and except in low grounds, and in the neighbourhood of ftagnant waters, is very healthful. White frofts, and fometimes thin ice, have been feen as far S. as the 31ft degree of latitude; but fnow is very uncommon in any part of this territory. A perfon refiding at the Natchez writes to his friend, in the eaftern part of Geor-


vifited


GEO

The fources whence the author has derived his information, in drawing up the followrecount, are Capt. Thomas Hutchins's " Hiftorical narrative and topographical defcripn of Louifiana and Weft Florida," comprehending alfo many of the rivers and fettlements in the Georgia Weftern Territory ; published in 1784. Private letters and journals ; minutes taken from verbal deferiptions of gentlemen of veracity and intelligence who have re-

nutes taken from verbal deferiptions of gentlemen of veracity and intelligence who have re-fided in that country. The journals and laws of the State of Georgia-State Papers and Re-ports both printed and M.S. of Congrefs, and of Agents of the feveral companies who have purchafed lands in this territory. † The letter here alluded to contains the following paragraphs: "Our navigation is ex-cellent; our high lands preferable to Beach Ifland, § when in its bloom; flock is as eafy come at as where you are; lands are rifing fail, and I expect will be very high in a few years. The canes in common, on the high lands, larger than in the river-fwamps, I meang in the caftern part of Georgia] from 30 to 35 feet high, and upwards, and in many aces fland fo thick, that one can fearcely walk a mile in half an hour. Some families must be coming to this most flourishing country in the world. I with you to advide any of my relations you fee to come with all hafte; if they can get here, and are turned out naked in the world, in one year they might be fixed again. I am fure could I have time to fay as much as I with to fay, you would be with me this fall. I could venture to almost promife, if you would be wife and come, to make good any deficiencies you might find in the place." The Author is in poffeffion of the original letter, above mentioned, which has every mark The Author is in ponemon of the original letter, above mentioned, which has every mark of authenticity; and the above extracts are inferied, as containing the fimple, bunch de-foription of a plain farmer; and on which more dependence is to be placed, than on the most elaborate and elegant deforiptions, of interefted individuals. § Alluding to a remarkably fertile ifland in the caftern part of Georgia, in the neighbourbood of the writer's correspondent, and with which both were well acquainted.







vilited it, fay of that part of the territo-ry which borders on the Miffifippi, that "the water is good for 20 miles back from the river, and the country healthy and pleafant, and of all others that they have feen the most defirable." Mr. Hutchins, fpeaking of the fame tract, fays, "the climate is healthy and temperate, the country delightful and well watered, and the profpect is beautiful and extensive; variegated by many inequalities, and fine meadows, feparated by innumerable copfes, the trees of which are of different kinds, but mostly of walnut and oak. The elevated, open, and airy fituation of this country, renders it lefs liable to fevers and agues (the only diforders ever known in its neighbourhood) than fome other parts bordering on the Miffifippi, where the want of a fufficient defcent to convey the waters off, occasions numbers of ftagnant ponds whole exhalations infect the air." Another traveller defcribes the country between the Tombigbee. and the Coofa and Alabama as being healthy, well watered with many pleafant rivulets, affording delightful fituations for fettlements, and the water pure and very good.

To give a just view of the rivers, and to afcertain the advantages derived from them to this territory, it is neceffary to trace them from their mouths in the Gulf of Mexico. The Miffifippi bounds this territory on the W. The free navigation of this noble river is now enjoyed by the inhabitants of the United States. It empties, by feveral months of different depths, from 9 to 16 feet, into the Gulf of Mexico, in about lat. 29 N. The bars at the mouth of this river frequently thift; after paffing them into the river, there is from 3 to 10-fathoms of water, as far as the S. W. pafs; and thence to the Millouri, a diffance of 1,142 computed miles, 12, 15, 20, and 30 fathoms is the general depth.

In alcending the Miffifippi there are extensive natural meadows, with a profpect of the Gulf of Mexico on each fide, the diffance of 32 miles, to a place called Detour-aux-Plaquemines, in W. Florida. Thence 20 miles to the fettlements, the banks are low and marfhy, generally overflowed and covered with thick wood, palmetto bufhes, &cc. apparently impenetrable by man or beaft. Thence to Detour-des-Anglois, at the

bend of the river, the banks are well inhabited; as also from hence to New-Orleans 18 miles, which diffance there is a good road for carriages. Veffels pass from the mouth of this river to New Orleans 105 miles, in 7 or 8 days, commonly; fometimes in 3 or 4. From New-Orleans, the capital of

Louisiana, there is an easy communication with West-Florida by Bayouk Creek, which is a water of lake Ponchartrain, navigable for veficls drawing four feet water, fix miles up from the lake, to a landing place two miles from New Orleans. For nearly 50 miles, as you proceed up the river, both its banks are fettled and highly cultivated, in part by emigrants from Germany, who furnifh the market with indigo of a fupcrior quality, cotton rice, beans, myrtle, wax, and lumber. In 1762, fome rich planters attempted the cultivation of canes and the making of fugar, and crected mills for the purpose. This fugar was of an excellent quality, and fome of the crops were large; but fome winters proving fo fevere as to kill the canes, no dependence can be placed on the culture of that article.

The fettlements of the Acadians, which were begun in the year 1763, extend on both fides of the river, from the Germans, to the river Ibberville, which is 99 miles above New-Orleans, and 270 from Penfacola, by way of lakes. Ponchartrain and Maurepas.

At Point Coupee, 35 miles above the Ibberville, are fettlements extending 20 miles on the W. fide of the river, which 30 years ago, had 2,000 white inhabitants, and 7,000 flaves, who were employed in the cultivation of tobacco, indigo, Indian corn, &c. for the New-Orleans market, which they furnished allo with poultry, and abundance of fquared timber, flaves, &c.

Mr. Hutchins, from his perfonal knowledge, defcribes the country on both fides of the Miffilippi, between thelatitudes 30. and 31. bordering on Georgia, as follows:

"Although this country might produce all the valuable articles railed in other parts of the globe, fituated in the fame latitudes, yet the inhabitants principally cultivate indigo, rice, tobacco, Indian corn, and fome wheat; and they raife large flocks of black cattle, horfes, mules, hoge, fheep, and poultry. The fheep

1.1

theep are faid to make the fweeteft mutton in the world. The black cattle, when fat enough for fale, which they commonly are the year round, are driven across the country to New-Orleans, where there is always a good market.

This country is principally timbered with all the different kinds of oak, but moftly with live-oak, of the largeft and beft quality, uncommonly large cyprefs, black walnut, hickory, white ash, cherty, plum, poplar trees, and grape vines; here is found alfo a great variety of fhrubs and medicinal roots. The lands bordering the rivers and lakes, are gene-rally well wooded, but at a fmall diftance from them are very extensive natural meadows, or favannas, of the moft lux-uriant foil, composed of a black mould, about one and a half feet deep, very loofe and rich, occasioned in part, by the frequent burning of the favannas; below the black mould is a fliff clay of different colours. It is faid, this clay, after being exposed fome time to the fun, becomes fo hard, that it is difficult either to break or bend, but when wet by a light flower of rain, it flackens in the fame manner as lime does when expoled to moifture, and becomes loofe and moulders away, after which it is found excellent for vegetation."

After paffing the 31th degree of N. lat. from W. Florida into Georgia, you enter what is called the *Natchez Coun*try, bordering on the Miflifuppi. Fort Rofailie, in this country, is in lat. 31.40. 243 miles above New-Orleans.

243 miles above New-Orleans. "The foil of this country is fuperior to any of the lands on the borders of the river Miffifippi, for the production of many articles. Its fituation being higher, affords a greater variety of foil, and is in a more favourable climate for the growth of wheat, sye, barley, oats, &c. than the country lower down, and nearer to the fea. The foil alfo pro-duces in equal abundance, Indian corn, rice, hemp, flax, indigo, cotton, potherbs, pulle of every kind, and pafturage; and the tobacco made here, is eemed preferable to any cultivated in other parts of America. Hops grow wild; all kinds of European fruits arrive to great perfection and no part of the known world is more favourable for the raising of every kind of flock. The riling grounds, which are clothed with grais and other herbs of the fineft verdure, are well adapted to the culture of vines: the mulberry trees are very numerous, and the winters fufficiently moderate for the breed of filk worms. Clay of different colours, fit for glafs works and pottery, is found here in great abundance; and alfo a variety of ftately timber, fit for house and fhip building, &cc."

Another gentleman, well informed, * fays, " The lands on the Miffifippi, extending eastward about 20 miles, are hilly, without flones or fand, extremely rich, of a deep black foil, covered thick with canes, white and black oak, walnut, hickory, ash, fome fugar maple, beech, and dogwood ; that there are very few ftreams or fprings of water; that the water is not good, and taftes as if im-pregnated with fulphur; that the coun-try is much infefted with infects; that the land is high and bluff three-fourths of the diftance along the river Miffifippi, and a part overflowed and drowned." But it is apprehended that this defcription is not perfectly juft, fo far as it applies to the fcarcity and badnefs of the water; as a gentleman of refpectable character, who refided 9 months at the Natchez, fays, "The lands on the Miffilippi are more level, and better watered, than is above reprefented ; and that the water is good, and the country healthy and remarkably pleafant."

This country was once famous for its inhabitants, the Natchez Indians; who, from their great numbers, and the improved flate of fociety among them, were confidered as the moft civilized Indians on the continent of America. Nothing now remains of this nation but their name, by which their country continues to be called. The diffrict of the Natchez, as well as all along the eaftern bank of the Miffifippi to the river Ibberville, was fettling very faft by emigrations from the northern States, till the capture of the Britift troops on the Miffifippi, 1779, put an eather ftop to it.

"From fort Rofailie to the Petit Goufre is 31¹/₂ miles. There is a firm rock on the eaft fide of the Miffifippi for near a mile, which feems to be of the nature of lime-flone. The land near the river is much broken and very high, with

* Mr. Ifaac Perry, of Burke county, Georgia.

with a on it. F river, is what is compute tance the and the on the f north fic neral is fide is 1 hills and are not are fhade ber. A moft at 1 tween a faid to b even as down. Chitto, o This riv yards wi yards, a canoes 3 and a ha are close broken. the high right, w of water, covered o further, er, on t fame rang cliffs. lands an and cont but brok This lan Gen. Put and other as a pro order of Weft-Flo for the ca very fit i five miles fides of th not fo m as fome p miles and pid water yards in firm rock as much at a mod fream to nel is abou

to the culy trees are nters fufficolours; fit , is found and alfo a for house nformed, * fifippi, exmiles, are extremely ered thick k, walnut, ple, beech. very few that the as if im-the counets ; that e-fourths Miffifippi, rowned. defcripas it ap-is of the **fpectable** hs at the the Mif-

er waterand that country t." as for its s; who, the imthem, merica. tion but country frift of ong the the rivfaft by States, oops on ire ftop

e Petit a firm iffilippi be of id near y high, with

county,

GEO

with a good foil, and feveral plantations on it. From the Petit Goufre to Stoney river, is 41 miles. From the mouth to what is called the fork of this river, is computed to be 21 miles. In this diftance there are feveral quarries of flone, and the land has a clay foil, with gravel on the furface of the ground. On the north fide of this river, the land in general is low and rich; that on the fouth fide is much higher, but broken into hills and vales; but here the low lands are not often overflowed; both fides are shaded with a variety of useful timber. At the fork, the river parts almost at right angles, and the lands between and on each fide of them are faid to be clay and marl foil, not fo uneven as the lands on this river lower down. From Stoney river to Loufa Chitto, or Big Black river, is 10 miles. This river, at the mouth, is about 30 yards wide, but within, from 30 to 50 yards, and is faid to be navigable for canoes 30 or 40 leagues. About a mile and a half up this river, the high lands are close on the right, and are much broken. A mile and a half further, the high lands appear again on the right, where there are feveral fprings of water, but none as yet have been difcovered on the left. At about 8 miles further, the high lands are near the river, on the left, and appear to be the fame range that comes from the Yazoo cliffs. At fix miles further, the high lands are near the river on both fides, and continue for two or three miles, but broken and full of fprings of water. This land on the left was chosen by Gen. Putnam, Capt. Enos, Mr. Lyman, and other New-England adventurers, as a proper place for a town; and, by order of the governor and council of West-Florida, in 1773, it was referved for the capital. The country round is very fit for fettlements. For four or five miles above this place, on both fides of the river, the land is rich, and not fo much drowned, nor fo uneven, as fome parts lower down. About fix miles and a half further, there is a rapid water, ftones and gravel bottom, a 60 yards in length; and in one place a firm rock almost across the river, and as much of it bare, when the water is at a moderate height, as confines the ftream to nearly 20 feet ; and the channel is about four feet deep.

101

From the Loufa Chitto to the Yazon Cliffs, is 40 miles. From this cliff the high fands lie north-eaftward and fouthfouth-caftward, bearing off from the river, full of cane and rich foil, even on the very highest ridges. Just at the S. end of the cliffs, the bank is low, where the water of the Miffifippi, when high, flows back and runs between the bank and high land, which ranges nearly northerly and fouth-fouth-easterly to the Loufa Chitto, occasioning much wet ground, cyprefs fwamp, and ftagnant ponds. From the Cliffs, is feven miles and a half to the river Yazoo. The mouth of this river is upwards of 100 yards in width, and was found by Mr. Gaul to be in lat. 32.37. and by Mr. Purcell in 32.28.N. The water of the Miffifippi, when the river is high, runs up the Yazoo feveral miles, and empties itfelf again by a number of channels, which direct their courfe across the country, and fall in above the Walnut Hills. The Yazoo runs from the N. E. and glides through a healthy, fertile and pleafant country, greatly refembling that about the Natchez, particularly in the luxuriancy and diversity of its foil, variety of timber, temperature of climate, and delightful fituation. It is remarkably well watered by fprings and brooks ; many of the latter afford convenient feats for mills. Further up this river the canes are lefs frequent, and fmaller in fize, and at the diffance of 20 miles there are fcarcely any. Here the country is clear of under-wood, and well watered, and the foil very rich, which continues to the Chactaw and Chickafaw towns, on the eaftern and north-western branches of Yazoo river. Thefe branches unite 50 miles from the Millifippi, following the courfe of the river; the navigation to their junction, commonly called the Fork, is practicable with very large boats in the fpring feafon, and with fmaller ones a confiderable way further, with the interruption of but one fall, where they are obliged to make a fhort portage, 20 miles up the N.W. branch, and 70 miles from the Miffifippi. The country in which the Chactaw and Chickafaw towns are fituated, is faid to be as healthy as any part of the continent, the natives fcarcely ever being fick. Such of them as frequent the Millippi, leave its banks as the fummer approach-es, left they might partake of the fevers

that

that fometimes visit the low, fwampy lands bordering upon that river. Wheat, it is faid, yields better at the Yazoo than at the Natchez, owing probably to its more northern fituation. One very confiderable advantage will attend the fet-tlers on the river Yazoo, which those at the Natchez will be deprived of, without going to a great expense; that is, the building with stone, there being great plenty near the Yazoo, but none has yet been difcovered nearer to the Natchez than the Petit Goufre, or Little Whirlpool, a diftance of about 31 miles. Between this place and the Balize, there is not a ftone to be feen any where near the river. Though the quantity of good land on the Miffilippi and its branches, from the Bay of Mexico to the river Ohio, a diftance of nearly one thousand miles, is valtly great, and the conveniences attending it; fo likewife we may effeem that in the neighbourhood of the Natchez, and of the river Yazoo, the flower of it all.

About a mile and a half up the Yazoo river, on the N. fide, there is a large creek, which communicates with the Miffifippi above the river St. Francis, about 100 leagues higher up, by the course of the river. It paffes through feveral lakes by the way. At the diftance of 12 miles from the mouth of the river Yazoo, on the S. fide, are the Yazoo hills. There is a cliff of folid rock at the landing place, on which are a variety of broken pieces of fea-fhells, and fome entire. Four miles further up, is the place called the Ball Ground, near which a church, fort St. Peter, and a French fettlement, formerly flood. They were deftroyed by the Yazoo Indians in 1729. That nation is now entirely extinct." [Hutchins.]

From about 20 miles eaftward of the Miffifippi, to Half way or Pearl river, the diffance of about 60 miles, (fome fay lefs) is "a fine, level country, very fertile, and better watered than nearer the Miffifippi. There is fome mixture of fand with loam, the timber the fame, with the addition of black-jack, and poft-oak. This traft is interfperfed with what the French call *Prairies* or Savannas, which are extensive intervals of 1000 and 2000 acres of excellent land, of a deep black foil, free of all timber and trees. It is this kind of land which, the Indians cultivate. From the Miffi-

GEO

fippi to this river, there are no Indians. To a tract of this country, extending along the Miffifippi from the 31ft degree of latitude to the Yazoo river, at the S. end, 30 miles wide, and narrowing as you proceed northerly to the width of 15 miles, the Indian title has been extinguished. It was at first pur-chaled by the English; but they not having completed the payment for it, before it fell into the hands of the Spaniards, they, (the Spaniards) in the year 1792, paid the balance. At Wal-nut Hills, the Spaniards have a fort, which, according to treaty is to be given up (if not already done) to the United States. To the country N. of the Yazoo, the Indian title is not yet extinguished. About one half of the fouthern part, a diftance of about 50 miles up the Yazoo, is owned by the Chactaws, the northern half by the Chickafaws." The gentleman who gives the above information, and who was in this country in the year 1792, fays, " that the Yazoo is about 90 yards wide; is boatable 100 miles; that he croffed the country by different routes, 3 or 4 times from the Miffifippi to the Tombigbee ; paffed over the Yazoo feveral times ; went up and down the river on the fhore, and fays that the lands to the E. of the Yazoo (the diffance of about 100 miles) are very excellent."

Pearl river is about 40 yards wide ; a branch of it paffing E. of the Natchez and neareft, in Coxe's map, bears the name of Buffaloe river. On the E. fide of Pearl river, commence the Chactaw fettlements, and extend thick to the Chickafaw Hay river; thence, about 40 miles eaftward, the fettlements are fparle, and extend near to the Tombigbee. This is a numerous nation, containing about 3000 hunters, a peaceable and friendly people. The country inhabited by thefe Indians is noted in Coxe's map, to be " poor and barren land, covered generally with long-leafed pine." Other accounts reprefent it as much the fame as that between the Miffifippi and Pearl rivers, with the addition of fome pine land, and better watered. The ftreams on which the Chactaws are fettled, as laid down on Coxe's map, are, proceeding from W. to E. the Homachitta, (called by Purcell Hoftaphatcha) Chactaw, and Souhawtee, which unite, and

and th of Hor Gulf o fame ri la; wh this ri the nor chiefly White, appears a courf empties tance b and is Pearl ri From Chactav branche tolerabl oak and watered country of the w bee; the is more favanna good la the way The nat on the l they cal lands, a on the r ly overg ral defe tract be fippi C map, re bee and of fine 1 Mobile Wel Mobile, tory. the bay IS OF I way thr of Mob fathoms depende is only places n not go v Hutchi miles lo The tid bay, and Thence boat na

o Indians. extending e 31ft deo river, at nd narrowrly to the in title has it first purt they not ent for it. ds of the rds) in the At Walwe a fort. is to be ne) to the ntry N. of is not yet alf of the about so ned by the If by the man who , and who ear 1792, t 90 yards ; that he nt routes. ippi to the Yazoo fen the river the lands e distance ery excel-

ds wide ; a atchez and the name E. fide of actaw fethe Chickt 40 miles parfe, and ee. This ing about d friendly abited by 's map, to overed gethe fame ilippi and n of fome ed. The ws are fetmap, are, ne Homaaphatcha) nich unite, and

G E O and the main ftream retains the name of Homachitta till it empties into the Gulf of Mexico. This is probably the fame river that Hutchins calls Pafeagou-

la; which fee. The head branches of this river fpread extensively through the northern part of this territory, chiefly weftward of the Chaetaw nation. White, or Bluff river, on Coxe's map, appears to rife in about lat. 33. N. takes a courfe to the E. of the Chaetaws, and empties into the Tombigbee, fome diftance below the head of the tide water, and is laid down as about the fize of Pearl river.

From the compact fettlements of the Chactaws eastward to the wettern branches of the Tombigbee, the land is tolerably good : the timber generally oak and pine, with fome hickory, well watered and level. Of this kind is the country a diffance of about 40 miles W. of the western branches of the Tombigbee; thence to the Tombigbee, the land is more uneven, interspersed with large favannas, and the whole generally good land, and pretty well watered; the water, however, has a limy tafte. The natural growth much the fame as on the Miffifippi. The intervale, or as they call it in this country, the bottom lands, are generally about a mile wide on the river, extremely rich, and thickly overgrown with canes. This general description will apply to the whole tract belonging to the "Georgia Miffifippi Company." Mr. Coxe, on his map, remarks that, " On the Tombigbee and Alabama rivers there are bodies of fine rich land, but low down, towards Mobile bay, unhealthy."

We have now arrived eaftward to the Mobile, the principal river in this territory. "On the bar at the entrance of the bay of Mobile, there is only about 15 or 16 feet water; two-thirds of the way through the bay, towards the town of Mobile, there is from two to three fathoms; and the deepeft water to be depended on in the upper part of the bay is only 10 or 12 feet, and in many places not fo much. Large veffels cannot go within feven miles of the town." [Hutchins.] "This hay is about 30 miles long, and from 10 to 12 wide. The tide flows 60 or 70 miles above this bay, and is 16 far navigable for fea veffels. Thence 150 or 200 miles north, is good boat navigation, fmooth water, gene-

rally 100 to 150 yards wide, and eight to 10 feet deep." [M. S. Minutes from Mr. Perry.] " The bay of Mobile terminates a little to the north-eaftward of the town, in a number of marfhes and lagoons; which fubject the people to fevers and agues, in the hot feafon. * The river Mobile, as you afcend it, di-vides into two principal branches, about 40 miles above the town; one of which, called the Tanfaw, falls into the eaft part of the bay; the other empties itfelf close by the town, where it has a bar of 7 feet ; but there is a branch a little to the eaftward of this, called Spanish river, where there is a channel of 9 or 10 feet, when the water is high ; but this joins Mobile river about 2 leagues above the town. Two or three leagues above the Tanfaw branch, the Alabama river falls into Mobile river, after running from the north-caft a course of about 130 miles; that is, from Alabama fort, fituated at the confluence of the Coofa, and Talipoofee, both very confiderable rivers; on which and their branches are the chief fettlements of the Upper Creek Indians. The French fort at Alabama was evacuated 1763, and has not fince been garrifoned. Above the confluence of Alabama and Mobile, the latter is called the Tombigbee river, from the fort of Tombighee, fituated on the weft fide of it, about 96 leagues above the town of Mobile. The fource of this river is reckoned to be about 40 leagues higher up, in the country of the Chickafaws. The fort of Tombigbee was taken poffeffion of by the English. but abandoned again in 1767, by order of the commandant of Peníacola. The river is navigable for floops and fchooners about 35 leagues above the town of Mobile. The banks, where low, are partly overflowed in the rainy feations, which adds greatly to the foil, and adapts it particularly to the cultivation of rice. The fides of the river are covered in many places with large canes, fo thick that they are almost impenetra-ble; there is also plenty of remarkable large red and white cedar, cyprefs, elm, afh, hickory, and various kinds of oak. Several people have fettled on this river,

• Mr. Coxe, in his map, extends Mobile Bay fome diffance north of the 31ft degree of latitude. Other accounts fay this bay does not extend into the State of Georgia. N who 104

who find the fail to answer beyond ex-Station. The lands near the mouth of the Mobile river are generally low ; as you proceed upwards, the land grows er, and may with propriety be divided into three ftages. First, low rice lands, on or near the banks of the river, of a most excellent quality. Secondly, what are called by the people of the country, fecond low lands, or level flat cane lands, about 4 or 5 feet higher than the low rice lands. And, thirdly, the high upland or open country. The first, or low lands, extend about an half or three-quarters of a mile from the rivcr, and may almost every where be eafily drained and turned into most excellent rice fields, and are capable of being laid under water at almost all feafons of the year. They are a deep black mud or flime, which have in a fucceffion of time been accumulated, or formed by the overflowing of the river. The fecond low grounds being, in general, formed by a regular rifing of about 4 or 5 feet higher than the low lands, appear to have been originally the edge of therriver. The fecond clafs or kind of land is in general extremely rich, and covered with large timber and thick ftrong canes, extending in width upon an average three-quarters of a mile, and in general a perfect level. It is excellent for all kinds of grain, and well calculated for the culture of indigo, hemp, flax, or tobacco. At the extremity of these second grounds, you come to what is called the high or uplands, which is covered with pine, oak, and hickory, and other kinds of large timber. The foil is of a good quality, but much inferior to the fecond or low land. It answers well for raising Indian corn, potatoes, and every thing elfe that delights in a dry foil. Further out in he country again, on the west fide of this river, you come to a pine barren, with extensive reed swamps and natural meadows or favannas, which afford excellent ranges for innumerable herds of cattle. On the east of the river Mobile, towards the river Alabama, is one entire extended rich cane country, not inferior, perhaps, to any in America. Whenever portages are made between the Mobile and Tennessee river, or their branches, which are probably but a few miles apart, the Mobile will be the first river for commerce (the Mififippi ex-LC W

cepted) in this part of the world, as if affords the florteft and most direct com-munication to the fea." [Hutchins.] In addition to, and confirmation of, the above account of Capt. Hutchins, feveral other gentlemen of intelligence who have been in this country, fay that "the Tombigbee is navigable for fea veffels 60 miles into the State of Georgia ;"" others, that " it is navigable in boats of 20 tons up to the junction of 10 and 20 Mile Creek. The Alabama and Coola are navigable for boats of 40 tons, as high as the big fhoals of Coofa river. The principal rivers which meander through this tract of country, are Seprey's and Cane Brake rivers, both which fall into the Tombigbee, and are navigable for boats as high as the 33d degree of latitude; and the Cawhawbon river, which falls into Alabama river, below the junction of Coofa and Oakfuskee, are boatable as far N. as the rivers laft mentioned. The foil on the E. fide of Tombigbee, is of a reddifh caft, producing naturally oak, hickory, and abundance of very high grafs. The country appears well calculated for the culture of wheat, corn, rye, oats, and barley. The bottoms or intervales on the rivers are not fubject to inundations, and are exceedingly rich. The country is well watered with good wholefome water. Further north, the country becomes uneven and fomewhat hilly, that part particularly which divides the waters of Tombigbee from Tenneffee river, but as you defcend to a lower latitude, the country is more level; and down about the mouth of Cane Brake river, and thence acrois to the Alabama, is almost one entire cane brake."

"The ridge which divides the Tombigbee and Alabama rivers is flony, and the foil inferior to that on the rivers; of this defcription alfo is the country lying between the Cawhawbon and Alabama rivers; but the bottom lands on the water courfes are exceedingly rich. The country is pleafant and healthy, being generally overgrown with high grafs, well calculated for farming, particularly for raifing cattle. There are many extensive and rich bot-

• Col. Hammond, late Surveyor General

toms

toms of The rive bee next rich land fome diff into mar healthy, Coxe's vance ea territory first to th the Cha Capt. H river Ef that fall See Efe Hatcha in the empties which is broad. the bay deepeft ; 16 or 17 er (for have ley only a them. river abo banks ve cambia. chicola, are defi heads. The n are wate Tennefie This no as latitu Hutchin equal pa fee Comp in this p inhabita neffee, in receives, Hiwaffee po or Be under th lers fpea the Ten comment Of th State of ture, pa 22 milli compani of their by the a 920

ø

rect comchins.] nation of, Intchins. telligence , fay that le for fea of Georrigable in nStion of Alabama sats of 40 of Coofa hich mescountry, ie rivers, mbigbee, is high as and the into Alaof Coo-:as far N. The foil , is of a ally oak, ery high well caleat, corn, ottoms or ot fubject ceedingly watered Further leven and uticularly Tombigit as you e country about the nd thence oft one enthe Tomis ftony, n the rivthe counwbon and tom lands rceedingly afant and vergrown

rld, as it

or General

toms

lated for

ng cattle.

rich bot-

GEO

toms of cane land on the Alabama. The river which falls into the Tombig-bee next above Seprey's river, has much rich land on its banks, and is boatable fome diftance in finall boats, and fpreads into many branches, through a pleafant, healthy, and well watered country." [Coxe's M. S. Letter.] As you ad-vance eastward of the Alabama, in the territory we are defcribing, you come first to the Escambia river, and then to the Chatta Hatcha, or Pea river, which Capt. Hutchins thus defcribes-" The river Escambia is the most confiderable that falls into the bay of Peníacola. See Escambia River. The Chatta Hatcha or Pea river, which also heads in the Georgia Western Territory, empties from the N. E. into Rofe Bay, which is 30 miles long and from 4 to 6 broad. The bar at the entrance into the bay has only 7 or 8 feet water, at deepeft ; but, after croffing the bar, has 16 or 17 feet. The mouths of the river (for almost all the fouthern rivers have feyeral mouths) are fo fhoal, that only a fmall boat or canoe can pais them. Mr. Hutchins afcended this river about 75 miles, and found that its banks very much refembled those of Efcambia. Further east are the Appalachicola, Flint, and Alabaha rivers, which are defcribed under their respective heads.

The northern parts of this Territory are watered by the great bend of the Tennefice, and its tributary fireams. This noble river bends fouthward as far as latitude 34. 15. according to Capt. Hutchins' map, and divides, into nearly equal parts, the purchase of the Tennesfee Company. North of the Tennefiee, in this purchase, there is not an Indian inhabitant. From the fouth, the Tenneffee, in its courfe through Georgia, receives, befides finaller ftreams, the Hiwaffee, Chiccamauga, and Occochappo or Bear Creek, which are defcribed under their respective heads. Travellers fpeak of the lands on the hend of the Tenneffee, in terms of the higheft commendation.

Of the territory deferibed above, the State of Georgia, by act of their legiflature, paffed Jan. 7, 1795, fold about 22 millions of acres to four different companies, whole names and the limits of their refpective purchases, as defined by the act, follow. 2. "All that tract or parcel of land in-cluding iflands, beginning on Mobile bay, where the lat. 31. N. of the equator inter-fects the fame, running thence up the faid bay to the mouth of the lake Ten-faw; thence up the faid lake Tenfaw, to the laboration interduced output to the Alabama river, including Curreys and all other iflands therein; thence up the faid river Alabama, to the junction of the Coofa and Oakfulkee rivers; thence up the Coofa river, above the Big Shoals, to where it interfects the latitude of 34. N. of the equator ; thence a due W. course to the Miffifippi river ; thence down the middle of the faid river, to the latitude of 32. 40; thence a due E. courfe to the Dan or Tombigbee river; thence down the middle of the faid river to its junction with the Alabama river; thence down the middle of the faid river to Mobile bay; thence down the faid Mobile bay, to the place of beginning, fhall be fold unto James Gunn, Matthew M&Allifter, and George Walker, and their affociates, called The Georgia Company."

GEOO

a. "All that tract of country, including iflands, within the following boundaries, viz. beginning on the river Miffilippi, at 31. 18. N. lat. thence a due E. courfe to the middle of Dan or Tombigbee river; thence up the middle of the faid river to N. lat. 32. 40; thence a due W. courfe along the Georgia Company line, to the river Miffilippi; thence down the middle of the fame, to the place of beginning, fhall be fold to Nicholas Long, Thomas Glaffcock, Ambrofe Gordon, and Thomas Cummings, and their affociates, called The Georgia Miffilippi Cumpany."

3. " All that tract of country, including iflands, within the following boundaries, viz. beginning at the Miffifippi river, where the northern boundary line of the State firikes the fame; thence along the faid northern boundary line, due E. to the Tenneffee river; thence along the faid Tenneffee river, to the mouth of Bear Creek ; thence up Bear Creek, to where the parallel of latitude 25 British statute miles S. of the northern boundary line of the State interfects the fame; thence along the laft mentioned parallel of latitude, across Tombigbee or Twenty Mile Creek, due W. to the Miffifippi river ; thence up the middle of the laid river, to the beginning, shall be fold to John B. Scott, N 2 John

John C. Nightingale, and Wade Hampton, called The Upper Miflifippi Company.

196

4. "All that tract of land, including iflands, within the following boundaries, viz. beginning at the mouth of Bear Creek, on the S. fide of Tenneffee river; thence up the faid creek to the moft fouthern fource thereof; thence due S tolat. 34. 10. N. thence due E. 120 miles; thence a due N. courfe to the Great Tenneffee river; thence up the middle of the faid river to the northern boundary line of the State; thence a due W. courfe along the faid line to where it interfects the Great Tenneffee river, below the Mufcle Shoals; thence up the faid river to the place of beginning, thall be fold to Zachariah Cox, Mathias Maher, and their affociates, called The Tenneffee Company."

halt be fold to Zachariah Cox, Mathias Maher, and their affociates, called The Tenneffee Company." The fame law enacts alfo, " that all lands lying weth ard and fouthward of the eaftern boundary of the feveral Companies' purchafes, and not included therein, effimated at one-fourth of the whole lands lying weftward and fouthward of the eaftern boundary of the faid purchafes, and fuppofed to contain 7,2 50,000 acres, fhall be, and the fame is hereby declared to be referved and fet apart to, and for the ufe and benefit of this State, to be granted out, or otherwife difpofed of, as future legiflatures may direct." [Act of Georgia Legiflature of Jan. 7th, 1795.]

The purchase-money, amounting to 500,000 dollars, was duly paid by the respective Companies, into the State treasury of Georgia, agreeably to the terms of the act. This land was foon after fold by the original Companies, to various gentlemen, principally in the Middle and Eaftern States. The fale of this territory excited a warm and violent opposition in Georgia. The act authorifing this fale, was by certain leading men in the State, declared to be " an ulurped act,-repugnant to the principles of the Federal Conftitution, and of the Constitution of Georgia-oppofed to the good of the State, and obtained by fraud, atrocious fpeculation, corruption and collution," In confequence of these representations, a determination was formed by a powerful party, to fet afide and annul at the fucceeding feffion of the legislature, this offenfive, " ulurped act." Efforts were ac-

GEOO

cordingly made, and with fuccefs, to obtain a legiflature fuited to the accomplifhment of their defigns. Accordingly, on the 13th of Feb. 1796, an act was paffed declaring the above-mentioned " ufurped act" null and void ; and all the grants, rights and claims arifing therefrom, of no validity or effect ; and that the faid territory was the fole property of the State." To complete the utter annihilation of this odious act, as far as poffible, the legiflature ordered, that, in their prefence, and that of the public officers of the State, the feveral records, documents and deeds, in the feveral public offices, fhould be " expunged from the faces and indexes of the books of record of the State; and the enrolled law, or usurped act, publicly burnt." All this was accomplished three days after the paffing of the act. These unprecedented proceedings were attended and followed with most difagreeable and tumultuary effects. The original purchafers of thefe lands, the then holders, and all those who had been intermediately concerned, who had by this time become a numerous and respectable body, fcattered through the United States, were, for the moment, thrown into an unpleafant dilemma, and for a time this bufinefs was the general topic of conversation. The title to the lands purchased by the above named companies, has been still further embarrassed by a claim brought forward in behalf of the United States. As it may be matter of curiofity to the reader, and perhaps of interest, to examine into the title of the feveral companies to their respective purchases, under existing circumftances, a fummary ftatement of the claims, and of the facts and arguments in their fupport, (though foreign to the express design of this work) is printed at the end, to which the reader is referred.

GEORGIA, a township in Franklin co. Vermont, contains 340 inhabitants. It is situated on Lake Champlain, opposite to the N. end of South Hero Island, and joins Milton on the S. and St. Alban's on the north. La Moille river croffes the extremity of the S. E. corner of this township.

GEORGIA, Southern, acluster of barren islands, in the South Sea, and E. of the coast of Terra del Fuego; about lat. 54. 35. S. and long. 36. 30. W. One

One leagu GI ven in in the GI fituat tainin from delph Ġı Penni GE of H Mont cenfu habita State of w the fo fite I Whit necta GE bia co 1796, GE Penní of Ph the fe **fevera** rior el bitant chief contai ftone, and c ftreet, public nift a meetin ftocki ed, an als to excell pleafa to the nufact gregat mothe derive a lean one of Some **fylvan** There State. believ them,

Franklin phabitants, plain, oplero Island, nd St. Alloille river S. E. cor-

fter of barand E. of go; about 6. 30. W. One GER One of them is between 50 and 60

leagues in length. GEORGIANA, the name originally gi-

ven in the charter, to a tract of country in the province of Maine. GERARDSTOWN, a neat little town,

fituated in Berkely co. Virginia, containing about 30 or 40 houfes; 10 miles from Martinfburg, and 254 from Philadelphia.

GERMAN, a township in Fayette co. Pennsylvania:

GERMAN FLATS, the chief township of Herkemer co. taken from that of Montgomery, in New-York. By the centus of 1790, it contained 1307 inhabitants, including 20 flaves; by the State centus of 1796, 4194 inhabitants, of whom 684 are electors. It lies on the fouth fide of Mohawk river, oppofite Herkemer. It is 24 miles E. of Whitestown, and 60 miles weft of Schenectady.

GERMANTOWN, (N. Y.) in Columbia co. containing 516 inhabitants. In 1796, it had 75 gualified voters.

GERMANTOWN, in Philadelphia co. Pennfylvania, is fituated 7 miles north of Philadelphia city, and was effeemed the fecond town in the country, until feveral inland towns eclipfed it, by fuperior establishments and number of inhabitants. It is a corporation, conlifting chiefly of High and Low Dutch, and contains about 250 houfes, chiefly of stone, some of which are large, elegant and commodious; built chiefly on one ftreet, about two miles in length. The public buildings are a German Calvinift and Lutheran church, a Friend's meeting-houfe, and an academy. Knit ftockings, of cotton, thread and worfted, are manufactured here by individuals to a confiderable extent, and of an excellent quality. It is an ancient town, pleafantly fituated, and by its vicinity to the metropolis, well adapted for manufactures. Here is the principal congregation of the Mennonifts, and the mother of that fect in America. They derive their name from Menno Simon, a learned man of Witmars, in Germany, one of the reformers, born in 1505. Some of his followers came into Pennsylvania, from New-York, in 1692. There are about 4000 of them in the State. They do not, like the Tunkers, believe in general falvation; yet, like them, they will neither fwear nor fight,

nor bear any civil office, nor go to law, nor take intereft for money, though many break that rule. They use great plainnets in their drefs, &c. and practife many of the rites of the primitive Chriftian church. This town is alfo rendered famous, by the battle fought in it, on the 4th of Oct. 1777.

GERMANTOWN, a polt-town and the capital of Stokes co. N. Carolina. It is fituated near the Town Fork of Dan river, and contains a court-houfe, gaol, and about 30 houfes. It is 528 miles S. W. by S. of Philadelphia.

GERMANTOWN, the chief town of Hyde co. in Newbern diffrict, N. Carolina.

GERMANY, a township in York co. Pennsylvania.

GERRISH *Mand*, a fmall ifle near Cape Neddock, clofe to the main land of the Diftrict of Maine.

GERRY, a township in Worcester co. Maffachusetts. It was incorporated in 1786, and contains 14,000 acres of land, on which are 740 inhabitants. It is 30 miles N. W. of Worcester, and 65 N. W. by W. of Boston.

GETTYSEURGH, a fmall town in York co. Pennfylvania, fituated at the head of Rock Creek, one of the head waters of the Monococy, and contains about 30 houses. It is 9 miles north of the Maryland line, 8 miles from Millerftown, 15 from Abbotthown, 36 from Williamfport in Maryland, and 118 W. by S. of Philadelphia.

GIBBAWAYS an Indian tribe refiding in Upper Canada, on the E. fide of Detroit river, opposite to Fort Gibralter.

GIBRALTER, an ancient town in the province of Venezuela, in Terra Firma. It is fituated on the fouth-eaftern fide of Maracaibo Lake. The country in its vicihity is well watered with rivers, and bears the beft quality of cacao, and very large cedars. The beft Spanish tobacco is made here, called Tabago de Maracaibo, from which the valuable fnuff is made, vulgarly called *Mackaba* fnuff. The air, however, is fo unhealthy, that very few but labourers live in the town; the wealthier fort reforting to Merida or Maracaibo.

GILL, a new township, in Hampshire co. Massachusetts, on the west bank of Connecticut river, a little below the mouth of Miller's river, on the opposite fide, and named after his Honour, Mo-N 3 fea

les Gill, Lieutenant-Governor of Maffachusetts.

108

GILLORI, an island on the coast of Weft-Florida, is divided from Dauphin Island by a narrow channel, through which a boat may pals with fome difficulty; and between Gillori and the main land, on the west fide of Mobile Bay, there is a chain of finall iflands, and oyster shells, through which is a passage of 4 feet, called Passe au Heron.

GILMANTOWN, a township in Strafford co. New Hampfhire, fouth-wefterly of Lake Winnipifeogee, and 52 miles N. W. of Portfmouth. It was incorporated in 1727, and contained 775 inhabitants in 1775; and in 1790, 2613.

GILSON, a township in Cheshire co. New-Hampshire, containing 298 inhabitants. It is fituated on the E. fide of Ashuelot river, and joins Keene on the fouth.

GINGER Island, one of the smaller Virgin illes, fituated between the Round Rock on the north, and Cooper's Ifle on the fouth, between which is the King's Channel. N. lat. 18. 5. W. long. 62. 53.

GIRTY's Town, an Indian village in the N. W. Territory, near the head of the navigable water or landing on St. Mary's river, where the Indians ceded at the treaty of Greenville, a tract of 2 miles square to the United States.

GLADE Road, at Bonnets' Tavern, miles from Bedford, on the road from Philadelphia to Pittfburg Forks; the fouthernmost is called the Glade Road; the northernmost the Old, or Forbe's Road, and goes by Ligonier. These roads unite 28 miles from Pittfburg. In the Glades, a tract of country at the entrance of the Alleghany Mountains, they cannot raife corn, as the earth is fubjected to froft from Sept. to June.

GLADY Creek, a finall ftream which flows through the east bank of Little Miami river in the N.W. Territory.

GLAIZE, Au, a S. S. W. branch of the Miami of the Lake, which interlocks with St. Mary's river. By the treaty at Greenville, the Indians have ceded to the United States a tract of land 6 miles fquare, at the head of its navigable waters, and 6 miles fquare at its confluence with the Miami, where Fort Defiance now ftands.

GLASGOW, a new county in Newbern diffrict, N. Carolina, taken from | tants.

GLO

Dobbs' co. It is bounded N. by Edgcomb, S, by Lenoir, E. by Pitt, and W. by Wayne.

GLASTONBURY, a township in Bennington co. Vermont, having only 34. inhabitants. It has good intervale lands, and lies N. E. of Bennington, adjoining.

GLASTONBURY, a handfome little town in Hartford co. Connecticut, fituated on the east fide of Connecticut river, opposite to Weathersfield, and of which it formed a part until 1690. In the township are 2 meeting-houses; and on Roaring Brook and other fmall freams are 17 mills of different kinds and 1 forge.

GLOUCESTER Houfe, belonging to the Hudson's Bay Company, is fituated in New South Wales, on the N. fide of the waters which form a communication through a chain of fmall lakes, between Winnipeg Lake and Albany river. Henley Houfe lies N. E. of this, nearer the mouth of Albany river, in James' Bay. N. lat. 54. W. long. 87. 30.

GLOUCESTER, or Cape Ann, a townthip in Effex co. Maffachufetts, whole east point forms the north fide of the Bay of Maffachusetts. It contains 5317 inhabitants, and is divided into 5 parifhes, and has befides a fociety of Universalists. This is a post-town and port of entry. The harbour is very open and acceffible to large fhips; and is one of the most confiderable fifthing towns in the Commonwealth. At the harbour, properly fo called, are fitted out annually from 60 to 70 bankers; and from Squam and Sandy Bay, two Imall outports, the bay fifthery is carried on with great fpirit, and to a large amount. The exports for one year, ending Sept. 30, 1794, amounted in value to 229,613 dollars. Thatcher's Ifland, on which are two lights of equal height, lies close to the S. E. fide of the township, which is itfelf joined to the continent by a beach of fand which is very rarely overflowed by the water. There is a very fine white fand here fit for making glafs. The harbour is defended by a battery and citadel erected in 1795. It is 16 miles N. E. by E. of Salem, and 34 N. E. of Bofton.

GLOUCESTER, the north-weiternmost township, and the largest, in Providence co. Rhode-Ifland, having Connecticut on the weft, and Maffachufetts on the north; and contains 4025 inhabi-

GLOUCESTER

GLOU is bound Salem, counties and W. on the L on the f Great an both nav about 20 Egg Ha into De fmall ve mouths, herrings illands Man's which Americ fence th vent the Philade is a min tract bo high ft product corn, lu divided bury, ter Tow ford, G bour, a along th on the this cou vigable Mauric about 4 into De fels of lopsion free inh are fou bog iron te pig a Here is Woodb GLO above c ware riv It was f now fea

> GLO ginia, fi name, o of Yor Town, GLO fertile a

Pitt, and p in Ben-; only 34 ale lands, idjoining. ome little cut, fitumnecticut d, and of 690. In afes; and all ftreams id I forge. zing to the ituated in lide of the unication , between ny river. iis, nearer. n James' 7. 30. n, a townts, whole ide of the ains 5317 nto 5 pa-y of Unia and port open and is one of towns in harbour, out annuand from fmall outd on with ount. The Sept. 30,

by Edg-

9,613 dolwhich are s clofe to which is y a beach verflowed fine white The harand citamiles N. N. E. of

a-weitern-, in Proring Con-Tachufetts 15 inhabi-

UCESTER

GLO GLOUCESTER County, in New- Jerley, is bounded N. by Burlington co. S. by Salem, Cumberland, and Cape May counties, E. by the Atlantic Ocean, and W. by Delaware river. Its length on the Delaware is about 30 miles, and on the fea the line is about 22 miles. Great and Little Egg harbour rivers are both navigable for veffels of 200 tons about 20 miles from their mouths. See Egg Harbour. The ftreams which fall into Delaware river are navigable for fmall veffels, a few miles up from their mouths, and afford fome fhad, rock, herrings, and perch. The adjacent islands are Red Bank, Pett, and Old Man's Creek Iflands. The first of which is famous in the history of the American war, for the defperate defence the garrifon upon it made, to prevent the British fleet from paffing up to Philadelphia. The foil of this county is a mixture of fand and loam, and the tract bordering on the Delaware is in a high flate of cultivation. The chief productions are beef, pork, fifh, hay, corn, lumber, butter, cheefe, &c. It is divided into to townfhips, viz. Woodbury, Waterford, Newtown, Gloucefter Township, Gloucester Town, Debtford, Greenwich, Woolwich, Egg Harbour, and Galloway. The first 8 lie along the Delaware, and the other two on the ocean. Mulicus river divides this county from Burlington, and is navigable 20 miles for veffels of 60 tons. Maurice river rifes here, runs foutherly about 40 miles through Cumberland co. into Delaware Bay, is navigable for veffels of 100 tons 15 miles, and for fiallops to miles farther. It contains 13,172

free inhabitants, and 191 flaves. There are found in this county quantities of bog iron ore, which is manufactured into pig and bar iron, and hollow ware. Here is also a glais house. Chief town, Woodbury, 9 miles S. of Philadelphia. GLOUCESTER, a fmall town in the

above county, on the E. fide of Delaware river, 3 miles below Philadelphia. It was formerly the county town, but has now fearcely the appearance of a village.

GLOUCESTER, a post town in Virginia, fituated in the county of its own name, on a point of land on the N. fide of York river, partly oppofite York-Town, 17 miles diftant.

GLOUCESTER County, in Virginia, is fertile and well cultivated, bounded N.

by Piankitank river, which separates it from Middlefex, caft by Matthews coand Chefapeak Bay, N. W. by King and Queen, S. and S. W. by York river, which divides it from York co. It is about 55 miles in length, and 30 in breadth, and contains 13,498 inhabitants, including 7063 flaves. The low lands here produce excellent barley, and Indian corn, the staple produce of the county. Tobacco is little attended to.

GLOUCESTER Houfe, in the territory of the Hudson's Bay Company, is on the N. fide of Mufquacobafton Lake, 120 miles weft of Ofnaburgh houfe. N. lat. 51. 24. W. long. 86. 59.

GLOVER, a township in Vermont, in Orleans co. N. E. of Craftfborough, adjoining.

GLYNN County, in the Lower diffrict of Georgia, bounded east by the ocean, north by Alatamaha river, which feparates it from Liberty co. and fouth by Camden co. It contains 413 inhabitants, including 215 flaves. Chief town, Brunfwick.

GNADENHUETTEN, or Gnadenbutten, a fettlement of the Moravians, or United Brethren, on Mufkingum river, oppofite to Salem, in the lands which belonged to the Mahikan Indians. In 1746 it was a pleafant town inhabited by Chriftian Indians, where were a chapel, miffionary's houfe, and many Indian houfes. This together with Schoenbrun and Saiem were referved by Congress, by an ordinance, May 20, 1785, for the Chriftian Indians formerly fettled there ; Sept. 3, 1788, it was refolved that the plat of each town flould make up 4,000 acres and the grant was made to the United Brethren for propagating the gofpel among the heathen .- Alfo the name of a Moravian fettlement on the S. W. bank of Lehigh river, in Pennfylvania, about 29 miles N. W. of Bethlehem.

GNADENHUETTEN, NEW, a Moravian fettlement on Huron river, which runs fouth easterly into Lake St. Clair, in the N. W. territory. It is about 22 miles from Lake St. Clair, and 28 N. W. of Detroit.

GOAT Island, in the State of Rhode-Ifland, a fmall iflot, opposite to the town of Newport, and on which is Fort The fort has been lately Washington. repaired, and a citadel crected in it. The fort has been ceded to the United States.

N 4

GOAVE

GOAVE LE PETIT, one of the weft jurifdictions of the French part of St. Domingo. It contains five parifhes, is the unhealthieft part of the colony, the inhabitants being fubject to coaftant fevers, occafioned by the badnefs of the waters. Its dependencies, however, are healthy, and remarkable for the culture of coffee. Exports from Jan. 1, 1789, to Dec. 31, of the fame year; 27,090lbs white fugar-655,187 brown-807,865 lbs coffee-90,053lbs cotton-and 210 lbs indigo. The town of the fame name is fituated on the narroweft part of the fouth-weftern peninfula, on the north fide of the neck.

GOELANS, POINT AU, a promontory on the north fide of lake Ontario, about 33 miles fouthwesterly of Fort Frontinac.

GOFFSTOWN, in Hillfborough county, New-Hampfnire, on the weftern bank of Merrimack river, 3 miles from Amufkeag Falls, and 60 miles weft of Portfmouth. It was incorporated in 1761, and contains 1,275 inhabitants. Some pieces of baked earthen ware have been found in this townfhip, from which it is fuppofed that the Indians had learned the potter's art; but of what antiquity thefe remnants are, is uncertain. GOLDEN Ifland lies at the mouth of the river or gulf of Darien, in the province of Terra Firma, in South America, N. lat. 9. W. long. 77. 10.

GOLD River, fituated in Terra Firma, on the iffhmus of Darien, fouthward of the river Santa Maria; affording much gold duft, from whence it has its name. GOLDSBOROUGH, a poft-town in Hancock county, Diftrict of Maine, containing 267 inhabitants. It was incorporated in 1789, is the fouth-eafternmoft town in the county. On the waters of its harbour is the town of Wafhington. It is 47 miles eafteriy of Penobicor, 188 fouth-eaft of Portland, and 330 northeaft of Bofton. N. lat. 44. 19.

GOLPHINGTON, the chief town of Washington county, Georgia, is fitua ed pear the head of Ogeechee river, about 26 miles east-south-east of Oconee town, 37 south-west of Augusta, and 30 north-west of Louisville.

GONAVE, an ifland in the bay of Leogane, in the weftern part of the ifland of St. Domingo. It is 141 leagues long, and uniformly about 3 broad, except a very imall part at each extremity. Petite Gonave, an ille about 2 miles each way, is feparated from the fouth-eaft corner of the former, by a channel 3 miles wide. Gonave is $3\frac{1}{3}$ leagues W. by N. W. of Port au-Prince; and its weft point is $3\frac{1}{3}$ leagues E. by N. of Cape Dame Marie.

GONALVES, a fea-port in the fame ifland, at the head of a bay of its own name, on the north fide of the bay of Leogane. The town is fituated on the great road from Port de Paix to St. Mark, 16 leagues fouth-eaft of the former and 15 N. by E. of the latter, N. lat. 19, 27. W. long. from Paris 75. 2, 30.

GONALVES, a bay in the ifland of Hifpaniola, fouth-eaftward of Cape St. Nicholas, in about 19. 33. N. lat.

GOOCHLAND, a county in Virginia, furrounded by Louifa, Fluyanna, Henrico, Hanover, and Powhatan counties. It is about 40 miles long and 14 broad, and contains 9,053 inhabitants, including 4,656 flaves.

GOOD HOPE, a Danish colony in West Greenland, in N. lat. 64.

GOOSE Creek, a river which falls into Potowmac river, about a mile S. E. of Thorpe, in Fairfax county, Virginia.

GOOSEBERRY Mountain, in New-York State, lies on the W. bank of Hudson's river, about 4 miles fouth of Fort George.

GOOSEBERRY Iflands and Rocks, on the coaft of Effex county, Maffachufetts, have been the occasion of the loss of many valuable veffels. To prevent fuch accidents in future, feamen may attend to the following particular information, which is here inferted for their benefit. The north part of Gooleberry great rock with the north of Cat Island, bears S. 54 W. from the beacon on Baker's Island. The western Gooseberry S. 41 W. the diffance nearly threefourths of a mile. The northern part of the western Gooseberry is viewed from the beacon over the point of land running out from it. The eaftern Goofeberry bears S. 26 W. and it is thoal as far as the western breaker. The eaftern breaker lies S. 35 E. and the western breaker S. 29 E. The eastern breaker is about the fame diftance from the beacon, as the weftern Goofeberry, but the eaftern Goofeberry falls within that diffance. Satan appears S. 32 W, and Halfway rock S. 3 W. at the the dif part of the bea fouthw only i breake the eaf rock w 65 to 1 Goi Cook, W. loi Goi ifland i 35. W Gor Sea, ab Peru, ! Gos land co fide of perelbo and 13 was inc 2,244 1 Gos Delawa ated or name i from th fort her Gos county, mingto Northa Bofton. and con Gos county, on the Mount Gos ty, Pen Gos ty, Co duction N. by northw Gos in Oran miles n by S. o S. of F ly fitua houfes, and Pr thip co whom Gos

the fame of its own the bay of red on the aix to St. f the forlatter, N. Paris 75.

ifland of Cape St. lat. Virginia, na, Hencounties. 14 broad, 15, includcolony in

n falls innile S. E. Virginia, in Newbank of fouth of

Rocks, on chufetts, e loss of vent fuch ay attend prmation, r benefit. ry great nd, bears on Baoofeberry ly threenorthern is viewpoint of e eaftern and it is breaker. E. and The east-: diftance n Gooferry falls ppears S. 3 W. at the

GOS

the diffance of 21 miles. The inner part of Cat Ifland is above 2 miles from the beacon, and with the beacon to the fouthward the Goofeberry rock bears only 12 minutes. The weftern dry breaker extends from 28 to 32; and the eaftern from 31 to 32. Halfway rock with the beacon from Cat Ifland is 65 to the fouthward.

GORE Island, difcovered by Capt. Cook, in his laft voyage. N. lat. 64. W. long, 169.

GORTA, ST. MARIA LA, a finall ifland in the Pacific Ocean, N. lat. 26. 35. W. long. 135.

GORGONA, a finall island of the South Sea, about 12 miles W. of the coaft of Peru, S. lat. 3. 20.

GORHAM, a township in Cumberland county, Maine, on the north-caft fide of Saco river, 15 miles from Pepperelborough at the mouth of the river, and 130 miles N. by E. of Boston. It was incorporated in 1764, and contains 2,244 inhabitants.

GOSCHGOSCHUENCK, a town of the Delawares, confifting of 3 villages fituated on the banks of the Ohio. Its name fignifies the habitation of owls, from the number of these birds who refort here.

GOSHEN, a townwip in Hampfhire county, Maffachusetts, between Cummington and Conway, 14 miles north of Northampton, and 112 W. by N. of Boston. It was incorporated in 1781, and contains 681 inhabitants.

GOSHEN, a township in Addison county, Vermont, adjoining to Salisbury on the W. and 21 miles N. E. by E. of Mount Independence.

GOSHEN, a township in Chefter county, Pennsylvania.

GOSHEN, a town in Litchfield county, Connecticut, famous for the production of excellent cheese. It is 7 miles N. by N. W. of Litchfield, and 50 northward of New-Haven.

GOSHEN, the moit confiderable town in Orange county, New-York, about 58 miles north of New-York city, 20 W. by S. of New-Windfor, and 30 W. by S. of Fifh-Kill. This town is pleafantly fituated, containing about 60 or 70 houfes, an academy, court-houfe, gaol, and Prefbyterian church. The townfhip contains 2,448 inhabitants; of whom 316 are electors.

GOSHEN, a township of the District

of Maine, 8 miles from Buckflown, on Penoblect river.

GOSHGOSHINK, a Moravian fettlement in Pennfylvania, fituated on Alleghany river, about 15 miles above Venango, or Fort Franklin.

GOSPORT, formerly called *Appledore*, a fifting town on Star Ifland, one of the ifles of Shoals, belonging to Rockingham county, New-Hampfhire, containing 93 inhabitants. It lies about 12 miles E. S. E. of Pifcataqua harbour. See Shoals.

GOTHAM, a small village in Maryland, about 4 or 5 miles north of Baltimore city.

GOVANDORE, a bay on the coaft of Chili, in South-America.

GRACIAS A DIOS, a town belonging to the province of Honduras, or Comaiagua, and audience of Guatimala. It is fituated at the mouth of a river upon a rocky mountain, which has fome gold mines in its neighbourhood. It was built the fame year as was Vallidolid, the capital, (from which it lies about 27 leagues to the weft) for the fecurity of the minets. Alfo a cape on this coaft difcovered by Columbus, N. lat. 14. 36. W. lon. 84. 12.

GRAFTON County, in New-Hampfhire, is bounded north by Canada; fouth by the counties of Strafford, Hillfborough, and Chefhire; welt by the State of Vermont, and eaft by the Diftrict of Maine. It comprehends nearly as much territory as all the other four counties, but is by no means to thickly fettled. It is divided into 50 townfhips, and 17 locations, and contains 13,473 inhabitants of whom 21 are flaves. The increase of population fince the enumeration of 1790 has been great.

GRAFTON, a township in the county of its name in New-Hampshire, 13 miles S. E. of Dartmouth college and 19 S. W. of Plymouth. It was incorporated in 1778, and contains 403 inhabitants. *Lapis fpecularis*, commonly called ifing-glais, of the best quality, is found in this town, in a mountain about 20 miles castward of Dartmonth college. It is found adhering to the rocks of white or yellow quartz, and lying in laminz, like sof paper. It is found in other places in the State in smaller pieces.

GRAFTON, the Haffanamifeo of the Indians, a township in Worcester county, Massachusetts, containing 900 inhabitants;

habitants ; 40 miles 6. W. of Bofton, 8 eafterly of Worcelter, and 34 N. W. of Providence,

GRAINGER, FORT. ftands on the N. fide of the mouth of Holfton river in Tenneffee.

GRAINGER, the name given to a new county, in the district of Hamilton, State of Tennessee, formed of parts of the counties of Knox, Jefferion and Hawkins, and called after the maiden name of the Lady of Gov. William Blount.

GRAISO, L'ANCE LA, a fettlement in Louisiana.

GRANADA, or Grenada, the most foutherly of the Caribbee Iflands in the Weft Indies, fituated between 11. 58. and 12. 20. N. lat. and between 61. 20. and 61, 35. W. long. about 20 leagues N. W. of Tobago, and 20 N. of New Andalufia, on the continent of America; 30 leagues S. W. of Barbadoes, and 70 from Martinico. Its extreme length is about 28 miles, and its breadth 1 3 miles. It contains about 80,000 acres of land ; of which (although no lefs than 72,141 acres paid taxes in 1776, yet) the quantity under cultivation never exceeded 50,000 acres. The face of the country is mountainous, but not inacceffible in any part; and it abounds with fprings and rivulets. The exports of the ifland and its dependencies in 1776, were valued at the ports of fhipping, to be worth 6000,000l. fterling. The fugar was the produce of 106 plantations; and they were worked by 18,293 negroes ; which was more than a hoghead of Muscovado fugar of 16 cwt, from the labour of each negro, old and young, employed in its cultivation and manufacture-a return unequalled by any other British island in the West-Indies, St. Christopher's excepted. The exports of 1787 were inferior: by the prices in London, the value of the cargoes was, however, 914,2081, 9s. 3d. and confifted of the following articles shipped off in 188 veffels, viz. 175,548cwt. 9lbs. fugar-670,390 gailons of rum-4,320 gallons molafies -8,812cwt. 2grs. 4lbs. coffee-2,716 cwt. 3qrs. 18lbs. cocoa-2,062,477lbs. cotton-2,8 rolbs. indigo; befides hides, dying woods, &c. The exports to the American States, included in the above fum, amounted to £24,597 48. This island is divided into fix parish-

es, St. George, St. David, St. Andrew,

its chief dependency, Cariacou ifland forms a 7th parifh. Befides St. George's, the capital, the other towns are inconfiderable villages, generally fituated at the bays or thipping places in the fever-al parifhes. Befides the capital, Grenville, or La Bay, is a port of entry, with diffinct revenue officers, independent of St. George's. The white population has decreafed confiderably fince Granada and the Granadines were in poffession of the British. In 1771, there were above 1,600; in 1777 only 1,300, and now there are not above 1,000: of which number, two-thirds are incorporated into five regiments of militia, including a company of free blacks or mulattoes, attached to each. There are likewife about 500 regular troops on the British establishment. The free people of colour amount to 1,115. In 1785 there were 23,926 negro flaves. The above was the ftate of the island prior to the late infurrection.

A chain of mountains croffes the ifland from N. to S. The air is good ; and the foil fruitful in all productions common to the climate. Several of the rivers have their fource in a lake of a circular form, called Grand Etang, in the highest ground in the island. The high road which runs nearly the whole length of the ifland is very near it; and on the opposite fide of the road, in this elevated fpot, is a genteel tavern, for the accommodation of travellers. Here the air is always cooled by refreshing breezes; and the prospect is delightful and extensive. On the fea-coalt, about half way from St. George's to Goave, fome of the high rocks are formed into bafaltic columns from 20 to 30 feet high, and appear like regular majon work, impaired by time.

Granada was difcovered by Columbus in his third voyage in 1498. The Caribbees were a numerous and warlike people, who happily remained in peaceful obfcurity until the year 1650; foon after which the French, by a feries of enormities, exterminated that devoted people. Granada was ceded to Great-Britain in 1763, was taken by the French during the American war, and at the peace of 1783 was reftored to Great-Britain.

GRANADA, a town of Nicaragua and St Patrick, St. Mark, and St. John ; and | audience of Guatimala, in South-America.

ries. on a la of whit great to pillage with o 800 inl long. 8 GR ra Firm mines o Fe de] GRI knot of the leev channe They | tude, a and ro archipe leagues duce c fugar. no runi moft co chain i Vincen quia; Marrin iflands Frigate Becouy and the the tw which acou ar GRA ty, Ve GRA county Hadley ton; contain GR county feparate fetts. bury, a GR garee, low the rivers. built, wooder work, is 40 1 The ce in the trees w

riea. It is feated 70 miles from the fea, on a lake of the fame name, by means of which the inhabitants carry on a great trade. John David, a Dutchman, pillaged this town in the last century with 90 men, when opposed by at least 800 inhabitants. N. lat. 11, 28. W. long. 87.

GRA .

GRANADA, NEW, a province of Terra Firma, South-America. It contains mines of gold, copper, and iron. Santa Fe de Bagota is the capital.

GRANADILLOES, or Grenadines, a knot of dangerous iflands and rocks near the leeward islands, where the greatest channel is but 3 or 4 leagues broad. They lie about the 18th degree of latitude, and are a range of fmall iflands and rocks dependent on Granada. This archipelago, whole length is about 14 leagues, contains 23 islands fit to produce cotton, coffee, indigo, and even fugar. The air is healthy, but there are no running fprings of fresh water. The most confiderable at the N. end of the chain is not above two leagues from St. Vincent, and is called Becouva, or Bequia; but the French called it Little Martinico. Belides this, there are the iflands of Moskitos and Cannaouan; Frigate and Union Iflands are between Becouva and Cariacou. The Grifon, and the Diamond on Rhonde Islands, are the two principal ones among those which fill up the interval between Cariacou and Granada.

GRANBY, a township in Effex county, Vermont.

GRANBY, a township in Hampshire county, Massachusetts, E. of South-Hadley, about 90 miles westerly of Boston; was incorporated in 1768, and contains 596 inhabitants.

GRANBY, a township in Hartford county, Connecticut, on the line which separates Connecticut from Massachufetts. It was formerly a part of Symfbury, and is 18 miles north of Hartford.

GRANBY, a fmall town on the Congaree, in S. Carolina, about 2 miles below the junction of Broad and Saluda rivers. Here a curious bridge has been built, whofe arches are fupported by wooden pillars, ftrongly fecured in iron work, fixed in the folid rock. Its height is 40 feet above the level of the water. The centre arch is upwards of 100 feet in the clear, to give a paffage to large trees which are always brought down by

the floods. The ingenious architect has the toll fecured to him by the Legislature for 100 years.

201

GRANDE, a river in South-America, in Peru, near Cayanta; remarkable for its fands enriched with gold duft.

GRAND BAY, on the S. W. coaft of Newfoundland island, 19 leagues northeasterly of North Cape in the island of Cape Breton.

GRANDE RIVIERE, a fettlement in a billy tract of the island of St. Domingo, 64 leagues fouth-welt of Fort Dauphin, and 44 leagues N. by E. of St. Raphael, in the Spanish part of the island, N. lat. 19. 34. W. long. from Paris 74. 30. Also the name of a small river, in the same island, which rifes at Limonade, and empties into the fea at Qr. Morin, 5 leagues east of Cape Francois.

GRANDE *Riviere*, on the northern fide of Chaleur Bay, is about 6 leagues weft-north-weft of Cape Despair. Here is a cod fiftery.

GRANDE SEAUX, an Indian nation, who inhabit fouth of the Miffouri, and can furnish 800 warriors.

GRAND Fathers, feveral large detached mountains in the fouth east corner of Tennefice, in which are the head waters of French Broad and Cataba rivers.

GRAND Ifles, are two large islands in Lake Champlain; each about 8 or ro miles long, and each forms a township belonging to Vermont. See South Hero, and North Hero.

GRAND Island, at the mouth of Lake Ontario, is within the British territories, having Roebuck and Forest islands on the fouth-wess, and the Thousand Isles on the north-east. It is 20 miles in length, and its greatest breadth is 4 miles.

GRAND Ifland, in Lake Superior, lies on the north fide of the lake.

GRAND *Mand*, in Niagara river, is about 6 miles long and 3 broad. The fouth end is 4 miles north of Fort Erie; and its northern extremity 3 miles fouth of Fort Slufher, and nearly 14 fouth of Niagara fort.

GRAND Lake, in the province of New Brunfwick, near the river St. John's, is faid to be 30 miles in length, 8 or ro in breach, and in fome places 40 fathoms deep.

GRAND MANAN Ifland, lies 6 miles S. by S. E. of Campo Bello Ifland, in the Alantic Ocean, opposite to Paffamaquoddy

George's, re incontuated at the feveral, Grenof entry, ndependwhite poably fince were in in 1771, 777 only ot above vo-thirds iments of v of free to each. o regular lifhment. nount to 3,926 nethe ftate infurrecthe ifland bod; and ons comthe rivers circular he higheft length of nd on the s elevated e accomthe air is breezes ; and exout half we, fome to bafalon work, Colum-8. The

ou ifland

i warlike in peaceso; foon feries of devoted o Greatne French d at the o Greatagua and th-Ame-

rica.

maquoddy Bay, on the eaftern border | fuppofed to be bones of the human kind. of the United States.

204

GRAND River runs a north-weft course into lake Erie, 20 miles below the Forks, 80 miles fouth-west of Presque Isle.

GRANGE, Cape La, or Cape Monte Cbrift, on the north fide of the island of St. Domingo. It is a high hill in the form of a tent, and may be feen by the naked eye at Cape Francois, from which it is 14 leagues E. by N. A strip of land joins it to the territory of Monte Chrift ; fo that at a diftance it feems to be an ifland. The cruifers from Jamaica often lie off here. This cape lies in lat. 19. 54. 30. N. and long. 74. 9. 30. W. from Paris; and with Point de Dunes forms the mouth of the bay of Monte Chrift; which fee.

GRANVILLE, a fine township in Annapolis county, Nova-Scotia. It lies on the north fide of Annapolis river, on the Bay of Fundy, and is 30 miles in length; first fettled from New-Eng-

GRANVILLE, a township in Hampthire county, Maffachusetts, about 14 miles welt of Springfield. It was incorporated in 1754, and contains 1979 inhabitants.

GRANVILLE, a township in Washington county, New-York, containing 2240 inhabitants, of whom 422 are electors. GRANVILLE County, in Hillfbo-rough diftrict in North-Carolina, has the State of Virginia north, and contains 10,982 inhabitants, of whom 4163 are flaves. Chief town Williamsburg. GRANVILLE, a flourishing town in Kentucky.

GRASS, a river in New South Wales. GRATES, a point of land on the east fide of Newfoundland Island.

GRAVE CREEK, on the Ohio, 12 miles down the river from Wheeling. Here is a mound of earth, plainly the work of art, called an Indian grave. It is of a conical form, in height about So feet. It alcends in an angle of about 800. The diameter at the top is about 60 feet ; the margin enclosing a regular concave, funk about 4 feet in the centre. Near the top flands an oak, about a feet in diameter. It is faid the Indians have no tradition what nation ever buried their dead in this manner. On examination, these mounds have been found to contain a chalky fubitance,

enniupria

GRE

RAVESEND, PORT OF, is fituated on the fouth-western fide of the island of Jamaica, in a large bay. It has two channels; the Leeward and the Main Channel, and affords good anchorage for large veficis.

GRAVESEND, a fmall village in King's county, Long-Ifland, New-York, 7 miles N. by E. of the city. The township of its name contains 426 inhabitants.

GRAY, a post-town in the District of Maine, in Cumberland county, 15 miles N. by W. of Portland. The township was incorporated in 1778, and contains 577 inhabitants.

GREAT BANK of NEWFOUNDLAND. This noted fifting bank extends from north to fouth, and is almost of a triangular shape. Between it and the island on the weft is a broad channel of deep water. It lies between 41. 0. and 50. 24. N. lat. and between 49. 45. and 54. 45. W. long.

GREAT BEAR LAKE, a water which runs westward, and flows into M'Kenzie's river in the north-weft part of N. America; not far from the arctic circle. Its mouth is 250 yards wide.

GREAT ALLIGATOR DISMAL. See Difmal. tell' notari bet

GREAT BARRINGTON, a township in the fouth-western part of the State of Maffachusetts, in Berkshire county, lying fouth of Stockbridge, 150 miles weft of Bofton, and 26 E. by S. of Hudfon city, New-York.

GREAT FAMINE, a river in New-York which rifes in the mountains near the fource of Oneida river, and flows N. W. by. W. to Lake Ontario. Its mouth is 10 miles fouth-westerly from the mouth of Black river.

GREAT EGG Harbour, &c. See Egg Harbour.

GREAT ISLAND in Pifcataqua harbour, New-Hampfhire.

GREAT KANHAWAY, a large river which flows through the eaftern bank of the Ohio, in 39. 5. N. lat. nearly 500 yards wide at its mouth. The current is gentle for about 10 or 12 miles, when it becomes confiderably rapid for upwards of 60 miles farther, where you meet with the first falls, when it becomes impoffible to navigate it from the great number of its cataracts.

GREAT Works, or Chadbournes River, in the district of Maine, rifes from Bonnebeag nebeag mouth. mills on of Berv GRE. Labrado lies in 5 GREA GRE. GRE ton and nia. T farvey, thickly maple. GRE. the Alle rates th Alatam At t Great F called B miles fr acres of and me plain, I fwamp l of the The Lie tween t the afcer from th depth, i loured, all kind purfuin tram cou in its fa Horned moderat their ex covers t this plan which w almost a GRE fountain ated nea tween A fuddenly a mode forming over, af of foft r cretion (

fea-fhell kind of copious, ragged

man kind. is fituated e island of t has two the Main anchorage in King's rk,7 miles ownihip of ants. Diffrict of , 15 miles : township d contains NDLAND. inds from of a trianthe ifland el of deep ». and 50. 5. and 54. ter which) M'Kenpart of N.

tic circle, IAL. See townfhip e State of unty, ly-150 miles . of Hud-

in Newtains near flows N. tio. Its erly from

See Egg qua har-

rge river ein bank early 500 e current les, when for uphere you becomes the great es River.

om Bonnebeag nebeag Pond, about 30 miles from its lie feven or eight feet below, fwelling the mouth. There are feveral valuable furface confiderably, immediately above mills on it, within and above the town of Berwick.

GRE

GREAT MECATINA, an ifland on the Labrador coaft. Its fouthern extremity lies in 50. 43. N. lat.

GREAT PELICAN Island. See Pelican. GREAT SODUS. See Sodus.

GREAT SWAMP, between Northampton and Lucern counties, in Pennfylvania. This fwamp, on examination and furvey, is found to be good farm land; thickly covered with beach and fugarmaple.

GREAT RIDGE, one of the ridges of the Alleghany Mountains, which feparates the waters of the Savannah and Alatamaha.

At the fouth-east promontary of the Great Ridge is that extraordinary place called Buffaloe Lick, diftant about 80 miles from Augusta. It occupies feveral acres of ground. A large cane fwamp and meadows, forming an immense plain, lie fouth-east from it; in this fwamp Mr. Bartram thinks the branches of the Great Ogeechee take their rife. The Lick is nearly level, and lies between the head of the cane fwamp, and the afcent of the Ridge. The earth, from the fuperficies to an unknown depth, is an almost white or cinerous coloured, tenacious, fattifh clay, which all kinds of cattle lick into great caves, purfuing the delicious vein. Mr. Bartram could not discover any thing faline in its tafte, but an infipid fweetnefs. Horned cattle, horfes, and deer, are immoderately fond of it; infomuch that their excrement, which aimoft totally covers the earth to fome diftance round this place, appears to be perfect clay; which when dried by the fun and air, is almost as hard as brick.

GREAT SPRINGS, is an amazing fountain of transparent, cool water, fituated near the road, about mid-way between Augusta and Savannah. It breaks fuddenly out of the earth at the basis of a moderately elevated hill or bank, forming at once a basion near 20 yards over, alcending through a horizontal bed of fost rocks, chiefly a testaceous concretion of broken, entire, and pulverized fea-schells, sand, &c. constituting a coarie kind of lime-stone. The ebullition is copious, active, and continual, over the ragged apertures in the rocks, which

Ite leven or eight feet below, fwelling the furface confiderably, immediately above it; the waters delcend fwiftly from the fountain, forming at once a large brook, fix or eight yards over, and five or fix feet deep. There are multitudes of fiffi in the fountain of various tribes; chieffy the feveral fpecies of bream, trout, catfifh, and garr, which are beheld continually afcending and defcending through the rocky apertures. Bartram, from whofe travels the above is taken, obferves, that he croffed no ftream or brook of water within 12 or 15 miles of this fountain, but had in view vaft favannahs, fwamps, and cane meadows, which he conjectures are the refervoirs which feed this delightful grotto.

GRE

200

GREENE, a county in Washington district, State of Tennessee.

GREEN, a township in Franklin county, Pennsylvania.---Alto a township in Washington county in the same State.

GREEN, a post-town in Lincoln county, in the District of Maine, fituated on the east fide of Androscoggin river, 3r miles W. by S. of Pittstown, 39 north of Portland, and 164 N. by E. of Boston, containing 639 inhabitants.

GREEN, a navigable river of Kentucky, which rifes in Mercer county, has a gentle current, and is navigable nearly 1 50 miles. It's course is generally welt; and at its confluence with the Ohio is upwards of 200 yards wide. Between the mouth of Green river and falt river, a diftance of nearly 200 miles, the land upon the banks of the Ohio are generally fertile and rich; but, leaving its banks, you fall into the plain country, which is confidered as little better than barren land. On this river are a number of Salt fprings or licks. There are three fprings or ponds of bitumen near this river, which do not form a ftream, but empty themfelves into a common refervoir, and when used in lamps, answers all the purposes of the best oil. Valt quantities of nitre are found in the caves on its banks; and many of the fettlers manufacture their own gunpowder.

GREEN BAY, or Puan Bay, a fonthweftern branch of Lake Michigan. Sce Michigan, Puan, and Winnebago.

GREEN, a finall river which rifes in the town of Marlborough in Vermont, and falls into Connecticut river above Deerfield, in Maffachufetts.

GREEN BRIAR, a large and fertile county

county of Virginia, furrounded by Bath, 1 Randolph, Harrison, Kanhaway, Botetourt, and Montgomery counties. It is about 100 miles long and 45 broad; and together with Kanhaway county, which was formerly a part of it, contains 6,or cinhabitants, including 319 flaves. There is a large cave on Rich Creek in this county, the earth at the bottom of which is ftrongly impregnated with fulphur. Many fuch are to be found on Green Briar River. The chief town is Lewifburg. At Green Briar court-houfe is a post-office, 30 miles W. by S. of Sweet Springs, and 103 weft of Staunton.

GREEN BRIAR River runs a S. W. courfe, and falls into the eaftern fide of the Great Kanhaway, at the place where that river breaks through the Laurel Ridge, and opposite to the mouth of New river; in N. lat. 38.

GREENBURGH, a townfhip in Weftchefter county, New-York, containing 1400 inhabitants, of whom 122 are flaves, and 164 are electors.

GREENBUSH, a township in Rensfaher county, New-York ; 164 of its inhabitants are clectors.

GREENCASTLE, a town in Franklin county, Pennfylvania, fituated near the Cohegocheague creek. Here are about 80 houses, 2 German churches, and a Prefbyterian church. It is it miles S. by W. of Chamberfburg, and 156 W. by S. of Philadelphia.

GREENE, a county in Kentucky, extending from Ohio river on the north, to Tenneffee State on the fouth, and bordering weft on the Miffifippi river, and east upon Hardin and Jefferson counties.

GREENE, a county in Washington district in the State of Tenneffee, having 7,741 inhabitants, of whom 454 are flaves. Greenville college has been eftablished by law in this county. It is fituated between two fmall northern branches of Nolachucky river, about 15 miles N. W. by W. of Jonefborough, and 54 eaft of the mouth of French Broad river.

GREENE, a township in Tioga co. New-York, on the east fide of Chenengo river.

GREENE, a county in the upper diftrict of Georgia, bounded weft by the upper part of Oconee river, east by The astonishing mountains of ice in Wilkes county, and fouth by that of this country, may well be recorded

101100

itants, including 1,377 flaves. Chief town, Greensborough.

GREENFIELD, a handfome flourifhing town in Hampfhire county, Maffa-, chufetts, about 4 miles north of Deer-field, and 114 W. by N. of Boston. The township lies on the west bank of Connecticut river, was incorporated in 1753, and contains 1.408 inhabitants. A company was incorporated in 1796 to build a bridge over Connecticut river, to connect this town with Montague.

GREENFIELD, a township in Saratoga county, New-York; 380 of the inhabitants are electors.

GREEN Island, or Serpent Island, one of the leffer Virgin Iflands, which is claimed by the Spaniards, and fituated near the East end of Porto-Rico.

GEEEN Island Harbour lies on the western end of the island of Jamaica. It furnishes good anchorage, having Davis's Cove on the north-eaft, and Half-Moon and Orange bays on the fouth-weft.

GREENLAND, a town in Rockingham county, New-Hampfhire, in the vicinity of the ocean, 5 miles foutherly from Portfmouth. It was incorporated in 1713, and contains 634 inhabitants.

GREENLAND. This extensive country properly belongs to neither of the two continents; unlefs, as feems probable, it be united to America to the northward of Davis's Straits. It is bounded by Davis's Straits on the weft; to the northward by fome unknown ocean, or by the north pole; east by the Icy Sea, and a ftrait which feparates it from Iceland; fouth-eaft by the Atlantic ocean; fouth it terminates in a point called Farewell, in N. lat. 59. The weftern coaft, which is washed by Davis's Straits, is high, rocky, bad land, which rears its head, close to the fea, in lofty mountains covered with inow, and inacceffible cliffs, and meets the mariner's eye 40 leagues at fea. The Greenlanders, reckoned to amount to about 7,000, live to the fouthward of the 62d degree of N. lat. or as the inhabitants are wont to fay, in the fouth; but no Europeans live there, fo that those parts are but little known. The European colonies have fixed themfelves to the northward of lat. 62.

Walhington, It contains 5,405 inhab- among its greateft curiolities, Nothing can

can exhi fame tin than the furround forms, I from the the enc Such pro ther; bu and the the viole dashing mind wi As th places, is eafy to tremely this cold forts, a grafs in dandatio of grafs: grow her ley and as thrift feldom a er, even rity, bee foon. affords kinds of tives wil wild gan foxes, an and mife landers h cies of The G trince of have ver concerni Wett Europea that tin headed h accident return he a favou again fol foon bec flowed of of Graen of its ve ny was (miffionar the celeb monarch gion. nued to

protectio

. Chief

flourifh-Maffaof Deer-Bofton. t bank of orated in abitants. n 1796 to ut river, itague. in Sarao of the fand, one which is d fituated 0. s on the Jamaica. having aft, and s on the Rockinge, in the foutherly orporated abitants five couner of the ems proca to the is boundweft; to vn ocean, the Icy es it from Atlantic 1 a point . The d by Dabad land, the fea. ith fnow, neets the ea. The mount to hward of as the inhe fouth : , fo that m. The hemfelves of ice in recorded Nothing can

can exhibit a more dreadful, and at the | try was provided with many towns, fame time a more dazzling appearance, than those prodigious mafles of ice that furround the whole coaft in various forms, reflecting a multitude of colours from the fun-beams, and calling to mind the enchanting fcenes of romance. Such prospects they yield in calm weather; but when the wind begins to blow, and the waves to rife in vaft billows, the violent thocks of those pieces of ice, dashing one against another, fill the mind with horror.

As this country is covered, in most places, with everlasting ice and fnow, it is eafy to imagine that it must be extremely cold. Among the vegetables of this cold country, are forrel of various forts, angelica, wild tanfey, fourvey grafs in great quantities, wild rofemary, dandations in plenty, and various forts of grafs; whortleberries and cranberries grow here. Europeans have fown barley and oats, which grow as high and as thrifty as in warmer climates, but feldom advance fo far as to ear, and never, even in the warmeft places, to maturity, because the frofty nights begin too foon. Unfruitful as this country is, it affords food for fome, though but few kinds of beafts, which furnish the natives with food and raiment. Of the wild game are white hares, rein-deer, foxes, and white bears, who are fierce and milchievous, feals, &c. The Greenlanders have no tame animals but a fpecies of dogs, who refemble wolves. The Greenlanders believe in the doctrince of the transmigration of fouls, and have very fingular and romantic notions concerning a future flate.

Weit Greenland was first peopled by Europeans in the eighth century. At that time a company of Icelanders, headed by one Ericke Rande, were by accident driven on the coaft. On his return he represented the country in fuch a favourable light, that some families again followed him thither, where they foon became a thriving colony, and be-flowed on their new habitation the name of Graenland or Greenland, on account of its verdant appearance. This colo-ny was converted to Christianity by a miffionary from Norway, fent thither by the celebrated Olaf, the first Norwegian monarch, who embraced the true religion. The Greenland fettlement continued to increate and thrive under his protection, and in a little time the coun-

churches, convents, bifhops, &c. under the jurifiliction of the archbifhop of Drontheim. A confiderable commerce was carried on between Greenland and Norway; and a regular intercourfe maintained between the two countries till the year 1406, when the last bishop was fent over. From that time all correfpondence was cut off, and all knowledge of Greenland has been buried in oblivion.

The colony, from its first fettlement, had been haraffed by the natives, a favage people, agreeing in cultoms, garb, and appearance, with the Eignimaux. (See New-Britain.) This nation, called Schrellings, Skralingues, or dwarfifth people, from their finall flature, at length prevailed over the Iceland fettlers who inhabited the weftern district, and exterminated them in the 14th century ; infomuch that when their brethren o the eastern district came to their affistance, they found nothing alive but fome cattle and flocks of theep running wild about the country. The Schrellings have a tradition that these were likewife exterminated, and affirm that the ruins of their houfes and villages still appear. There are reafons, however, for be-lieving that there may be ftill fome defcendants of the ancient Iceland colony remaining in the eaftern diffrict; though they cannot be vifited by land, on account of the flupendous mountains, perpetually covered with fuow, which divide the two parts of Greenland; whilf they have been rendered inacceffible by fea, by the vaft quantity of ice driven from Spitfbergen, or Eaft-Greenland; one would imagine that there muft have been fome confiderable alteration in the northern parts of the world fince the 15th century, fo that the coaft of Greenland is now become almost totally inacceffible, though formerly vifited with very little difficulty. Numerous attempts have been made in the laft and prefent century to difcover the eafternt diffrict, but they have all proved abortive: In these attempts ore has been found, every hundred lbs. of which yielded 26 ounces of filver; and fand, from which an eminent chemilt extracted pure gold.

It is thought the only practicable method of reaching that part of the country will be to coaft north about in finall veffels, between the great flakes

ers have declared, that the currents continually iffuing from the bays and inlets, and running fouthweftward along the fhore, hinder the ice from adhering to the land; fo that there is always a channel open, through which veffels of fmall burden might pafs, especially if lodges were built at fuitable diffances on the fhore, for the convenience and direction of the adventurers.

The Greenland fifhery is productive, and chiefly engroffed by the British and Dutch nations. In 1785 the former employed 153 thips in the whale fiftery, and the Dutch 65.

GREEN MOUNTAINS, a range of mountains extending N. N. E. to S. S. W. and dividing the waters which flow eafterly into Connecticut river, from those which fall westerly into Lake Champlain, Lake George, and Hudfon's river. The afcent from the east to the top of the Green Mountain in Vermont, is much eafier than from the weft, till you get to Onion river, where the mountain terminates. The height of land is generally from 20 to 30 miles from the river, and about the same distance from the New-York line. The natural growth upon this mountain, is hemlock, pine, fpruce, and other evergreens; hence it has always a green appearance, and on this account has obtained the descriptive name of Ver Mons, Green Mountain. On fome parts of this mountain fnow lies till May, and fometimes till June. The chain extends through Maffachufetts and Connecticut, and terminates in New-Haven. Kellington Peak, the highest of these mountains, is about 3,454 feet above the level of the ocean.

GREENSBOROUGH, a post-town, and chief town of Green county, Georgia, 30 miles from Lexington, and 78 W. by S. from Augusta.

GREENSBOROUGH, a thriving village in Caroline county, Maryland; on the weft fide of Choptank Creek, about feven miles north of Danton, and 22 miles S. E. by S. of Chefter.

GREENSBOROUGH, a new township in Orleans county in Vermont. It adjoins to Minden on the north-weft, and Wheelock on the fouth-east, and contains only 19 inhabitants.

GREENSBOROUGH, a very flourishing village, or town, in Georgia, in Green co. one of the most fertile in the miles. It contains about 50 houfes, a

GRE

State, and is 80 miles weft of Augusta, 30 from Washington, and 5 from the Oconce river, the boundary line between the Creek Indians and white people. This town is very near to a large quan-tity of lands which the State has laid off and appropriated for the use of her public University, and which are now in fuch a flate of cultivation, as to afford a handfome revenue for that inflitution.

GREENSBURGH, a post-town, and the capital of Westmoreland county ' Pennfylvania. It is a neat pretty town, fituated on a branch of Sewickly Creek, which empties into Youghiogany river. Here are 100 dwelling houfes, a German Calvinist church, a brick courthouse, and a stone gaol. It is 31 miles S. E. by E. of Pittfburgh, and 270 W. by N. of Philadelphia.

GREENSVILLE, a county of Virginia, encompafied by Brunfwick, Southampton, and Suffex counties, on the weft, north, and eaft, and by the State of North-Carolina on the fouth. It is about 24 miles long, and 20 broad, and contains 6,362 inhabitants, of whom 3,620 are flaves.

GREENVILLE Court-Houfe, in Virginia, ftands on Hick's Ford, 25 miles from Southampton, and 61 from Norfolk.

GREENVILLE, a county in Washington diffrict, S. Carolina; fituated in the N. W. corner of the flate ; bounded eaft by Spartanburg county, in Pinckney diftrict; fouth, by Pendleton; weft, by the State of Georgia, and that tract of country which the State of South-Carolina ceded to the United States; and north, by the State of North-Carolina. It contains 6,503 inhabitants of whom 606 are flaves. Taxes 1921. 6s. 8d. The lands are mountainous and hilly, and well watered, and the climate healthy and agreeable.

GREENVILLE, a post-town of South-Carolina, and chief town of Cheraws diffrict; fituared on the weft fide of Great Pedec river, in Darlington county. It contains about 30 houfes, a courthouse, gaol, and academy. It is 55 miles E. N. E. of Camden, 90 N. E. by E. of Columbia, 135 N. by E. of Charleftown.

GREENEVILLE, a post-town, and the chief town of Pitt county, North Carolina; fituated on the fouth bank of Tar river, diftant from Ocrecock Inlet 110 court-

court. learni IS 23 miles GR in Gr neffee, north river, ville . Jonefb 653 10 GR in the fide of Great Fart] about ery. tionsa to acco Ameri in the l eftabli Wayn a treat tions, GRI town : windw It has a and fer ropean The fi healthy GRI faire co ed in 1 It is 20 and 75 GRE in rank fey, fit ware r miles 1 fouth-e GRE county, Delawa country of East fouth-w t cont 64 are GRE county, bank o from it: are abo

of Virgik, South-, on the ie State of It is about and conom 3,620

in Virginiles from Vorfolk. Washingited in the unded eaft ckney difweft, by t tract of uth-Caroates; and Carolina. of whom - 6s. 8d. und hilly, : climate

of South -Cheraws ft fide of ton couns, a court-It is 55 90 N. E. by E. of

a, and the orth Caronk of Tar Inlet 110 houfes, a court-

GRE court-house and gaol; also a seminary of learning, called the Pitt Academy. It

is 23 miles from Washington and 25 miles from Tarborough.

GREENEVILLE, a fmall post-town in Greene county; in the State of Tenneffee, fituated on the weit fide of the north easternmost branch of Nolachucky river, about fix miles N. by E. of Greenville college, 26 miles north-weft of Jonefborough, 75 eaft of Knoxville, and 653 fouth-weft of Philadelphia.

GREENVILLE, a fort and fettlement in the N. W. Territory, on the fouth fide of a north-wellern branch of the Great Miami, fix miles north-weft of Fort Jefferson on the same branch, and about 23 miles fouth-eaft of Fort Recovery. It is a picketed fort, with baftions at each angle, and capacious enough to accommodate 2,000 men. Here the American legion had their head-quarters in the late war with the Indians. It was eftablished by the late Maj. Gen. A. Wayne in 1793, and here he concluded a treaty of peace with the Indian na-tions, on the 3d of August, 1795.

GRENVILLE BAY, or La Bay, a town and port of entry on the east or windward fide of the island of Granada. It has about 60 dwelling houfes, a church, and feveral rich ftores of India and European goods, and plantation utenfils. The fituation is low, and rather unhealthy.

GREENWICH, a township in Hampfaire county, Maffachufetts, incorporated in 1754, contains 1045 inhabitants. It is 20 miles eafterly of Northampton, and 75 wefterly of Bofton.

GREENWICH, a township, the fecond in rank in Gloucefter county, New-Jer-fey, fitnated on the eaft bank of Delaware river, opposite to Fort Mifflin, 3 miles N. by E. of Woodbury, and 6 fouth-east of Philadelphia.

GREENWICH, a township in Suffex county, New-Jerfey, on the eaft fide of Delaware river, in a mountainous country, about 5 miles north-eafterly of Easton, in Pennfylvania, and 31 fouth-weft of Newton, the fhire town. t contains 2,035 inhabitants, of whom 64 are flaves.

GREENWICH, a town in Cumberland county, New-Jerfey, on the north-weft bank of Cohanzy creek, about 3 miles from its mouth in Delaware Bay. Here-

meeting houfe. It is 15 miles foutheafterly of Salem, and 66 S. by W. of Philadelphia.

GREENWICH, a maritime township in Fairfield county, Connecticut, and the fouth-westernmost of the State, hes about 50 miles weft of New-Haven, and 40 eaft of New-York city. Its fea-coaft on Long Ifland Sound, and that of the township of Stamford on the eastward, has a number of illes and rocks bordering the inlets of the fea and mouths of the creeks. Byram river paffes through this town, the largeft of the small freams which water it, and only noticeable as forming part of the line between Connecticut and New-York.

This tract was purchased of the native Indians in 1640, and fettled under the government of the New Netherlands (now New-York) and was incorporated by Peter Stuyvefant in 1665, who was then governor of the New Netherlands. This town falling within the bounds of Connecticut, was afterwards granted to eight perfons by that colony.

GREENWICH, 'in Rhode Ifland ; fee East Greenwich.

GREENWOOD, a township in Cumberland county, Pennfylvania. Alfo, a township in Mifflin county in the fame State.

GREEN Woods, a vaft foreft of ftately pines in Litchfield county, Connecticut, which cover the face of a part of that These are cloathed in green county. bearded mofs, which being pendant from the boughs, fcreens, many of the trees from the eyes, and gives to the whole a gloomy, wild, and whimfical appearance.

GREGORIA, ST. a town of New-Mexico, fituated on the eaft-fide of Rio Bravo, a few leagues north of St. Antonio.

GREGSTOWN, a village in Somerfet county, New-Jerfey, on the east-fide of Millftone river, 6 miles north-eafterly of Princeton, and about 9 fouth-weft of New-Brunfwick.

GRENADA. See Granada.

GRES, CAPE AU, a promontory on the eastern fide of the Miffifippi in the N. W. Territory, 8 leagues above the Illinois tiver, and the tract of country fo called, extends 5 leagues on that river. There is a gradual defcent back to delightful meadows, and to beautiful and are about 80 houfes, and a Friend's fertile uplands, watered by feveral rivu-

lets,

lets, which fall into the Illinois river, between 30 and 40 miles from its entrance into the Miffifippi, and into the latter at Cape au Gres. The diffance from the Miffifippi to the Illinois acrofs the country, is leffened or increaled, according to the windings of the former river; the finalleft diffance is at Cape au Gres, and there it is between 4 and 5 miles. The lands in this intermediate fpace between the above two rivers are rich, almoft beyond parallel, covered with large oaks, walnut, &cc. and not a ftone to be feen, except upon the fides of the river.

If fettlements were begun here, the French inhabitants acknowledge that the Spanish fettlements on the other fide of the Missing would be abandoned; as the former would excite a constant fucceffion of fettlers, and intercept all the trade of the Upper Missing.

GRISON, one of the finaller Granadillas, fituated between Diamond ifland and Cariacou. It is uninhabited, having no frefh water.

GROS MORNE ftands in the middle of the north peninfula of the island of St. Domingo, between the mountain and the head waters of a river which falls into the lea 4 leagues to the north, and a league and a half weft of Port de Paix. It is equally diftant, 11 leagues north-eaft of Point Paradis, and northweft of Les Gonaives. N. lat. 19, 46. W. long, from Paris 75, 13.

W. long. from Paris 75. 13. GROTON, a township in Caledonia county, in Vermont, is situated westward of and adjoining to Ryegate township on Connecticut river, and 9 miles northwesterly of Stephen's fort on that river. It contains 45 inhabitants.

GROTON, a township in Middlefex county, Massachusetts, 35 miles N. W. of Boston, and contains 1,540 inhabitants.

GROTON, a township in New-London county, Connecticut, having Fisher's Island Sound on the southward, and Thames river on the west; which separates it from New-London, to which it formerly belonged. It was incorporated in 1705, and consists of two parishes, containing 3,946 inhabitants. In 1770 there were 140 Indians here; 44 of whom could read, and 17 were church members. On a height, on the bank of the Thames, opposite New-London city,

food Fort Grifwold, memorable for being formed on the 6th of September, 1781, by Benediët Arnold, a native of Connecticut, after he had become a traitor to his country. Here 70 men, the flower of the town, were put to the iword, after they had furrendered themfelves prifoners. The compact part of the town was burnt at the fame time, and fuftained loss to the amount of 23,2171. Fort Grifwold defends the harbour of New-London.

GROVE Point forms the north fide of the mouth of Saffafras river, in Chefapeak Bay, 5 miles fouth-fouth-weft of Turkey Point.

GROVET'S Creek, in the State of Tennefice, lies 7 miles from King's Spring, and 2 from the foot of Cumberland Mountain.

GRYALVA, a river in the province of Chiapa, in New Spain, which is faid to breed certain amphibious beafts not to be found in any other place. They refemble monkeys, and are fpotted like tygers; they hide themfelves generally under water, and if they fee any man or beaft fivin by, they twift their tails about a leg or arm to draw them to the bottom; and yet it has never been obferved that they eat them.

GRYSON, a new county of Virginia, taken from Montgomery, which bounds it on the north. It has the State of N, Carolina, fouth, Henry and Wythe counties on the eaft and weft.

GUACANA, a village in New Spain, near the mountain Jeruyo, which was deftroyed by a volcano in that mountain, in 1760.

GUACOCKINGO, a town in New Spain, 30 miles fouth-eaft of Mexico.

GUADALAJARRA, or Guadalaxara, a province in the audience of Galicia, in Old Mexico or New-Spain, and its capital, an epifcopal city of the fame name, both large and beautiful. The city was built anno 1531, by one of the family of the Guzmans; and the bifhopric, which was before fettled at Compoftella, was translated thither in 1570. It is fituated on a delightful and fertile plain, watered with feveral fireams and fountains, not far from Baranja river. The air of the country is temperate, and the foil fo fertile, that it yields 100 to one; and all the fruits of Europe grow in luxuriance and abundance. N.

lat. 20 provin ara riv Gu Mexic mount where or Gu Galicia than 6 cific O It has of the Gu. coaft of long. 1 GU iflands France. 1635. and Ca prefent its mou Spain. and in north o fouth of and . 38 parts b a narro thips ca pais it in fertile, that of taken b reftored It was t but was close of burning fulphur, dry clei who fel mountai produce millions and 8,or GUA GUA America GUAL eaft divi ca. Its alfo Gu GUAL diction c rica, am leagues r along the

able for ptember, native of ecome a 70 men, ut to the ed themt part of me time, nount of ends the

orth fide in Chefh-weft of

State of King's Cumber-

province, ch is faid seafts not, . They, otted like generally yy man or heir tails em to the been ob-

Virginia, th bounds ate of N, Wythe

ew Spain, h was denountain,

in New Mexico. lalaxara, Galicia, , and its the fame ul. The one of the he bifhopat Comr in 1570. nd fertile reams and nja river. emperate, rields 100 f Europe ance.

GUA lat. 20. 50. W. long. 104. 49. The

province is watered by the Guadalaxara river.

GUADALAXARA, or Great River, in Mexico or New-Spain, rifes in the mountains of the valley of Toloccan, where ftands the city of Guadalajarra, or Guadalaxara, the capital of New Galicia. After running a courfe of more than 600 miles, it empties into the Pacific Ocean, in the 22d degree of N. lat. It has ftupendous falls, 15 miles fouth of the city of its name.

GUADALOUPE, a fmall ifland on the coaft of California, in N. lat. 90. 5.W. long. 118.

GUADALOUPE, one of the Caribbe islands in the West-Indies belonging to France, having been fettled by them in 1635. The natives called it Caracucita and Caracutira. Columbus gave it its prefent name, from the refemblance of its mountains to those of that name in Spain. It is fituated in 16. 20. N. lat. and in 62. W. long. about 30 leagues north of Martinico, and almost as many fouth of Antigua, being 45 miles long, and 38 broad. It is divided into two parts by a fmall arm of the fea, or rather a narrow channel, through which no ships can venture; but the inhabitants pais it in a ferry-boat. Its foil is equally fertile, and in the fame productions with that of Martinico. This island was taken by the British in 1759, but was reftored at the treaty of peace in 1763. It was taken by the fame power in 1794, but was retaken by the French in the close of the fame year. Here is a high burning mountain, which abounds with fulphur, and imoke iffues out from fundry clefts and chinks. The negroes who fell brimftone fetch it from this mountain. Many years ago this island produced 46 million pounds of fugar, 21 millions of coffee, 320,000 of cotton, and 8,000 pounds of cocoa.

GUAGAQUIL. See Guayaquil.

GUAIRA, a bay in Terra Firma, S. America, in the North Sea.

GUAIRA, a Spanish province in the east division of Paraguay, in S. America. Its city is Cividad Real, called also Guaira, and Oliveros.

GUAMALLES, a province in the jurifdiction of the abp. of Lima, in S. America, and empire of Peru, begins 80 leagues north-eaft of Lima, and extends along the centre of the Cordillera. The

Indian inhabitants apply themfelves to weaving, and making a great variety of baizes, ferges, and other fluffs, with which they carry on confiderable trade with the other provinces.

GUAMAN VILLAS, a juridiation under the abp. of Lima, 7-leagues from Guamanga. It is highly fertile, abounding with corn, fruits, paftures, cattle in great quantities, and all manner of efculent vegetables. The Indians here are equally industrious as those above mentioned, making baizes, corded stuffs, &c. which they tend to Cusco and other provinces.

GUAMANGA, or Guamanca, or St. Juan de la Vittoria, a city of Peru, about 60 leagues fouth-east of Lima, and having Pifco between it and the fea. It was founded by Pizarro, in 1539. The houses are all of stone, covered with flates. There are in it 3 elegant churches, feveral convents, and a rich hofpital; being the feat of a bifhop, under the abp. of Lima, the feat of a governor, and the capital of a fmall province. The air is wholefome and temperate. The foil produces wheat, and the meadows breed numerous herds of cattle. There are in the province mines of gold, filver, iron, lead, copper, and fulphur. The famous quick-filver mines of Guancavelica are 9 or ten leagues from this city. S. lat. 12. 20. W. long. 72. 36.

GUANAHANI, or St. Salvadore. See Cat Ifland.

GUANA PATINA, a volcano near Arequipa, in the valley of Quilea, in S. America, and empire of Peru; whole eruption, affifted by an earthquake, laid Arequipa in ruins in 1600.

GUANCHA BELICA, a jurifdiction fubject to the abp. of Lima, in Peru, 30 leagues north of the city of Guamanga 3 has very rich quick-filver mines, but otherwife very barren. See Guanzavelica.

GUANCHACO, a port or harbour in Peru, S. America, about a leagues north of Truxillo, and the channel of its maritime commerce, fituated in 8. 6. S. lat. in the South Sea.

GUANTA, a juristiction north-northweft of Guamanga 4 leagues, in the mpire of Peru; under the abp. of Lima. Its rich filver mines are nearly exhausted.

GUANZAVELICA, or Guancavelica, O 3 2. town

a town of Petu in South America, and in the audience of Lima. It is rich and abounds in mines of quick-filver ; 120 miles north east of Pifco, and 175 foutheaft of Lima, S. lat. 13. W. long. 88. 30. The famous quick filver mines called Guanzavelica, or El Affiento de Oropejo, not far from the above town, near the city of Oropefo, were difcovered by the Spaniards in 1566, and produce annually a million pounds of quickfilver, which is transported by land to Lima, afterwards to Arica, and thence to Potofi, where they make use of it to melt and refine the filver; and it yields to the Spanish treasury 40,000 ducats a ycar, befides other emoluments. The quick-filver is found in a whitish mais refembling brick illy burned. This fubstance is volatilized by fire, and received in fteam by a combination of glafs vefiels, where it condenses by means of a little water at the bottom of each veffel, and forms a pure heavy liquid.

GUANUCO, or Guanuge, a city and the capital of its jurifdiction, in the abp. of Lima, in Peru, which begins 40 leagues from Lima. It was a fettlement made by the first conquerors, but the city is now in a mean condition. Several kinds of jellies and fweetmeats are made here, and fold to other provinces. It is 192 miles north-east of Lima. S. lat. 19. 21. W. long. 75. 20.

GUARA, a town in its own jurifdiction on the road from Truxillo to Lima, containing about 200 houfes. It has a parifh church, and a convent of Francifcans, furrounded by fine plantations, and delightful improvements. At the fouth end of Guara ftands a large tower with a gate, and over it a kind of re-This tower is crected before a doubt. ftone bridge, under which runs Guara river. It lies in S. lat. 11. 31. 36. Not far from this town are ftill to be feen a great many ruinous remains of the edifices of the Yncas or Incas; fuch as walls of palaces, large dykes, by the fides of fpacious highways, fortreffes, and caftles, erected for checking the inroads of the enemy.

GUARCHI, a jurifdiction 6 leagues eaft of Lima, in Peru, extends itfelf above 40 leagues along the Cordilleras, abounding in grain and fruits. It has fome filver mines, but as the metal is indifferent, few are wrought.

GUARICO, a town fituated on the

north fide of the ifland of St. Domingor but more commonly called *Cape Fran*cois; which fee.

GUARMA, a maritime town of Peru, in South America. South lat. 10, 10, Weft long. 77.49.

GUARMOY, a finall maritime town of Peru, in South America. It is the refidence of a corregidore; has a good harbour, and lies 134 miles north-weft of Lima, S. lat. 18. 3. 53.

GUASCO, a river of Chili in South-America.

GUASTACA, or Panuco, (which fee) a province which borders on New Leon and Mexico, in which province are grain, cochineal, and fome very rich filver mines. All the flores are low, overflowed, unhealthy, and full of fait marfhes.

GUATAVITA, a lake in Terra Firma, South-America, near the city of Santa Fe de Bagota; which fee.

GUATIMALA, Audience and Province of, in New Spain, is about 750 miles in length, and 450 in breadth. It is bounded on the north by Chiapa and Vera Pax; on the fouth and weft by the South Sea, and on the eaft by Honduras. It abounds in chocolate, which they make use of instead of money. It has 12 Provinces under it, and the native Indians profess Chriftianity; but it is mixed with a great many of their own inpersitions.

There is a great chain of high mountains, which runs acrofs it from east to west, and it is subject to earthquakes and forms. It is, however, very fertile, and produces great quantities of chocolate, cochineal cotton, indigo, honey, fome balsam and woad. The merchandize of the province is generally conveyed to the port of St. Thomas in the bay of Honduras, to be fent to Europe. The way acrofs this province to the South Sea is about 65 leagues, and is the next to that from Vera Cruz to Acapulco. This province is called by the Indians Quatuemallac, which fignifies a roiten tree.

St. Jago de Guatimala, the capital city, is fituated in a valley, through the midft of which runs a river between two burning mountains. In 1541 this city was ruined by a dreadful tempeft, and a number of the inhabitants were buried in the ruins. It was rebuilt at a good diftance from the volcano, and became a arge

large and a up by tained coloui there was v it was Amer 8,000 Guati well in trade. Gu ence of rica, a name. ico on ing the weft, a on the league the bay fome, but no The ai ful, eip it prod in Ame aca (w title of Cortez. greatef ing wit honey, It has lead; a fands. coppera drug, 1 late a f provinc vince 1: fchools, rity, 1 upward provinc GUA mention and the 230 mil 120 wel of the g in the which is breadth Chiapa tains a ralthoul

Tak:

d became a

arge

GUA

large and rich town, with a bifhop's fee, and an univerfity ; but it was fwallowed up by an earthquake in 1773. It contained about 60,000 inhabitants of all colours, and was immenfely rich, but there are no traces of it left. The lofs was valued at 15 millions fterling ; and it was the third city in rank in Spanish America. In this dreadful earthquake 8,000 families inftantly perified. New Guatimala is built at some distance, is well inhabited, and carries on a great trade. N. lat. 13.40. W. long. 90.30.

GUAXACA, a province in the audience of Mexico, in New Spain, N. America, and its capital city of the fame name. It reaches from the bay of Mexico on the north to the South Sea, having the province of Tialcala on the northweft, and those of Chiapa and Tabasco on the fouth-eaft. It extends nearly 95 leagues along the South Sea, 50 along the bay of Mexico, and near 120, fay fome, along the confines of Tlascala, but not above 50 on those of Chiapa. The air here is good, and the foil fruitful, especially in mulberry trees; fo that it produces more filk than any province in America. Except the valley of Guaxaca (which is famous for giving the title of Marques dell Valle to Ferdinand Cortez, the conqueror of Mexico) the greateft part is mountainous, yet abounding with wheat; cattle, fugar, cctton, honey, cocoa, plantanes and other fruits. It has rich mines of gold, filver, and lead; and all its rivers have gold in their fands. Caffia, cochineal, cryftal, and copperas abound alto here. Vanilla, a drug, uted as a perfume to give chocolate a flavour, grows plentifully in this province. There were in this province 1 20 monafteries, belides hofpitals, schools, and other places of public charity, 150 confiderable towns, befides upwards of 300 villages. But now the province/is thinly inhabited.

GUARACA, the capital of the laft mentioned province, is a bifhop's fee, and the refidence of a governor. It lies 230 miles fouth of the city of Mexico, 120 welt of Spirito Santo, and 132 fouth of the gult of Mexico, and of Vera Cruz, in the delightful valley of Guazaca; which is 40 miles in length and 20 in breadth; and on the road leading thro! Chiapa to Guatimala. This city contains a very flately cathedral, and feve-TINGO

213

Indians. It carries on a confiderable trade with the N. and S. feas. The river is not fortified, fo that it lies open to invation. The Creolian clergy here' are bitter enemies to the Spanish clergy. According to fome, the proper name of Guaxaca is Antiquera; but this laft, others make a feparate town and bifhop's fee alfo, fituated about 80 miles to the S. W. It is faid to have a ftately cathedral, adorned with many large and high pillars of marble, each of which is one entire ftone. It is fituated in N. lat. 18. 2. W. long. 101.40. Guaxaca is fituated, according to fome, in N. lat. 17.45. W. long. 100.

GUAYALAS, a province and jurifdiction in the archbishopric of Lima, in Peru, S. America; extends along the centre of the Cordilleras, begins 50 leagues N. N. E. of Lima; produces grain, fruits, and pasture for cattle.

GUAYANA, a town in the province. of Paria, in Terra Firma, South-Ame-rica, about 175 miles S. E. by E. of Calabeza, and 75 fouth of the mouth of the gulf of Paria.

GUAYAQUIL, called by fome Guiaquil, by others Guagaquil and Guayakal, a city, bay, harbour, and river, in Peru, South-America. Guayaquil city is the fecond of Spanish origin, being as ancient as 1534; is fituated on the weft fide of the river Guayaquil, north of the island of Puna at the head of the bay, and about 155 miles S. S. W. of Quito, in 2. 11. fouth lat. 79. 17. weit long. Cividad Viega, or Old Town, was its first fituation, but it was removed about a quarter of a league in 1693 by Orellana; and the communication over the great ravins or hollows of water, preferved between the old and new towns by a wooden bridge of half a quarter of a league. The city is about two miles in extent; is defended by three forts, two on the river near the city, and the third behind it, guarding the The churches, entrance of a ravin. convents, and houfes are of wood. It contains about 20,000 inhabitants-Eu . 1 ropeans, creoles and other cafts; befides a number of ftrangers drawn hither by commercial interefts. The women here are famed for their perfonal charms, polite manners, and elegant drefs. I he talt creek here abounds with lobsters . and oyfters; but the fifh in the neighral-thousand families, both Spaniards and bourhood are not effeemed, being full of 1 bones, 03

bones, and unpalatable. But this place is most noted for a shell-fish called turbine, no bigger than a nut, which produces a purple reckoned to exceed all others in the world, and to vie with that of the Tyrians. It is called the purple of Punta, a place in the jurifdiction of Guayaquil. With this valuable and fcarce purple, they dye the threads of cotton, ribbands, laces, &c. and the weight and colour are faid to exceed according to the hours of the day; fo that one of the first preliminaries to a contract is to fettle the time when it shall be weighed. The dye is only the blood of the fifh, preffed out by a particular process; and the cotton fo dyed is called by way of eminence caracollillo. The river Guayaquil is the channel of its commerces and the diftance of the navigable part of it, to the cuftom-houfe of Bababio is reckoned about 24 lea-gues. The commerce of this place is confiderable; the productions of the country alone form the most confiderable part of it: these are cocoa, timber, falt, horned cattle, mules, and colts; Guinea pepper, drugs, and lana de ceibo, a kin i of wool, the product of a very high and tufted tree of that name, being finer than cotton. It is used for matraffes and beds.

GUAYARA, LA, a maritime town, and one of the chief of Caraccas, in South-America.

GUAYNA, a town in the interior part of Brazil on Parana river, a thort dif tance fouth of the tropic of Capricorn.

GUIANA, a large country of South-America, between the rivers Oroonoko and Amazon. The fea-coaft is partly poffeffed by the Dutch and French. See French America or Cayenne, and Dutch America or Dutch Guiana. The most confiderable of the Indian nations of Guiana u'e the Charibbees, the Arvaques, the Yaos, and the Galibis. Thefe are well proportioned, for the most part, are fwarthy, and go naked. The Charaibes, or Caribbees are enterprifing, and fo cautious of furprife, that they post out-guards and centinels with as much care and art as the Europeans. They are faid to have been formerly cannibals. The Galibis are more addicted to peace ; they manufacture hammocks and cotton beds, and are very ingenious. Such as are near the Europeans have learnt to handle fire-arms. The Cha-

raibes in the Weft-Indies are thought to derive their origin from these nations. The Charaibes of Guiana still fondly cherist the tradition of Sir Walter Raleigh's alliance : and to this day preferve the English colours which he left with them at parting, above 180 years fince.

GUIANDOT, a river of Virginia, which rifes in the Cumberland Mountain, and running a N. by W. courfe about 80 miles, talls into the Obio river, about 34 miles below the Great Kanhaway. It is faid to be 60 yards wide at its mouth, and as many miles navigable for cances.

GUIADA, a town of Terra Firma, on the Caracoa coaft. Its harbour is 212 miles eaft of Maracaibo, where, in the years 1739, and 1743, the British were twice repulsed, and loss fome men in attacking this place. S. lat. 10. 39. W. long. 66. 1.

GUILDHALL, a township in Effex coun y in Vermont, is fituated on Connecticut river, and contains 158 inhabitants. It is opposite the mouth of Isracl river in New-Hampshire.

GUILFORD, a township in Franklin county, Pennsylvania.

GUILFORD, a township in Windham county, Vermont, on the west bank of Connecticut river, and opposite to the mouth of Ashuelot river in New-Hampshire. It has Hinsdale on the south-east, and the State of Massachusetts on the south, and contains 2432 inhabitants.

GUILFORD, a post-town of Connecticut, in New-Haven county, fituated on the fouth-fide of Long-Island Sound, about 18 miles E. by S. of New-Haven city. The township is large and is divided into five parishes, and was settled in 1639. It was called *Menuncatuck* by the Indians.

GUILFORD County, in Salifbury diftrict, North Carolina, is bounded eaft by Orange, Weft by Rowan, fouth by Rockingham county, and north by the State of Virginia. It is noted for the extensive and rich tracts called New Garden, Buffaloe and Deep river lands. It contains 7191 inhabitants, inclusive of 576 flaves. Chiet town, Martinville. GUILFORD Court-Houfe. See Martiavuille. It is on the polt-road from Halifax to Salifbury, 48 miles fouthweft of Hillfborough, and 61 eastward of Salifbury.

GUINET,

GU county GU ma Ch the pen eaft by

nerally tends f of N. Gu phenor which diftanc Ife of foundla down thence along t till it a of the ftant t Africa a con ftream of the increaf The w miles, commo hour. ftream, it near welt wi Gulf S ed by t ly driv which 1 Mexico and the the north This h fact : 1 Gulf of than on nent in probabl great ri out of t Stream, Nantuc Bank, t Skilf a know ftream coaft, h Europe

or Penn

Newfou

lat. to

irginia, Moun-. courfe to river, Kanhawide at ivigable

Firma, bour is here, in Britifh me men 10. 39.

n Effex on Coni inhabth of If-

Franklin

indham bank of e to the -Hampath-eaft, 1 on the tants. Connecfituated Sound. v-Haven nd is dis fettled uncatuck bury difded eaft fouth by orth by oted for led New er lands. inclutive rtinville. see Marad from is fouthftward of

UINET,

GUINET, a township in Montgomery county, Pennsylvania.

GUL

GULF OF FLORIDA, or New Bahama Channel, is bounded on the weft by the peniniula of East Florida, and on the east by the Bahama Islands. It is generally about 40 miles wide, and extends from the 25th to the 28th degree of N. latitude.

GULF STREAM. This remarkable phenomenon is a current in the ocean which runs along the coaft, at unequal diftances from Cape Florida to the Ifle of Sables and the banks of Newfoundland, where it turns off and runs down through the Weftern iflands; thence to the coaft of Affica, and along that coaft in a fouthern direction, till it arrives at, and fupplies the place of those waters carried by the conftant trade winds from the coaft of Africa towards the weft, thus producing a contrant circulating current. This ftream is about 75 miles from the flores of the fouthern States, and the diftance increases as you proceed northward. The width of it is about 40 or 50 miles, widening towards the north. Its common rapidity is three miles an hour. A north-east wind narrows the ftream, renders it more rapid, and drives it nearer the coaft. North-weft and weft winds have a contrary effect. The Gulf Stream is fuppoied to be occafioned by the trade-winds that are constantly driving the water to the weftward, which being compreffed in the Gulf of Mexico, finds a paffage between Florida and the Bahama Iflands, and runs to the north-east along the American coast. This hypothefis is confirmed by another fact: It is faid that the water in the Gulf of Mexico is many yards higher than on the western fide of the continent in the Pacific Ocean. It is highly probable that the fand carried down by great rivers into bays, and the current out of these bays meeting with the Gulf Stream, by their eddies, have formed Nantucket Shoals, Cape Cod, George's Bank, the Ifland of Sable, &c.

Skilful navigators, who have acquired a knowledge of the extent to which this ftream reaches on the New-England coaft, have learnt, in their voyages from Europe to New-England, New-York or Pennfylvania, to pais the banks of Newfoundland in about 44. or 45. N. lat. to fail thence in a courfe between.

the northern edge of the Gulf Stream, and the fhoals and banks of Sable Ifland, George's Bank and Nantucket, by which they make better and quicker voyages to America.

GUNPOWDER, a river of the weftern fhore of Maryland, whole chief branches unite a little above Joppa, and empty into Chefapeak Bay, about '12 miles ahove Patapico river. It is navigable only a few miles, by reafon of falls. GUNPOWDER NECK, near the head

GUNPOWDER NECK, near the head of Chefapeak Bay, is a curious peninfula formed by Gunpowder river and Bufh river.

GURNET, THE. See Duxborough. GUYSBOROUGH, or Mancheffer, a township in Nova-Scotia, on Chedabucto Bay, 10 leagues north-west of Cape Canso, and 40 leagues eastward of Halifax, contained 250 families in 1783.

H

HA BRAGA, formerly called Fort Daupbin, a fort in the ifland of Cuba.

HACHA, RIO DE LA, or La Hacha, a province, its chief town, and a river, in Terra Firma or Castile del Oro, in South-America. The province is furrounded on two fides by the ocean, viz. on the N. and N. W. and on the third eaftward by the gulf of Venezuela. The town is fituated at the mouth of the ri ver, and on its weft fide on a little hill about a mile from the fea. The foil about it is very rich, and abounds with productions common to the climate, also European plants and fruits; well fup-plied with falt fprings, veins of gold, and fome gems of great value. The harbour is none of the beft, being expol-ed to the north winds. It is about 8 leagues from New Salamanca, and 18 from Cape Vela, N. by E. and 246 miles east of Carthagena. Here the Spanish galleons touch at their arrival in South-America, from whence expresses are fent to all the fettlements to give them notice of it. In 1595 it was furprised and facked by Sir Francis Drake. N. lat. 11. 30. W. long. 72.

HACKETSTOWN, a finall poff-town in Suffex county, New-Jerley on the north-welt fide of Musconecunk river. It is about three miles above the miner-04 al fpring near Roxbury, on the opposite fide of the river, 22 miles W. by N. of Morriftown, 16 S. W. by W. of Suffex court-house, and 120 N. N. E. of Philadelphia.

HACKINSACK, a river of New-Jerfey which rifes in New-York, and runs a foutherly courfe four or five miles weft of Hudfon's river. It unites with Palfaic river at the head of Newark Bay, and is navigable about 15 miles.

HACKINSACK, the chief town in Bergen county, New-Jerfey, is fituated near the weft bank of the above river, 20 miles north-weft of New-York city. The inhabitants are moftly Dutch. The houfes are chiefly built of fione, in the old Dutch tafte. Here are four public huildings, a Dutch and Epifcopal church, a court-houfe, and a flourifhing academy. The people, who are moftly farmers, carry their produce to New-York.

HADDAM, a town of Connecticut, the fecond in rank in Middlefex county, fituated on the welt fide of Connecticut river, 18 or 20 miles from its mouth, and 10 miles fouth-east of the city of Middletown. This township, including East-Haddam, on the opposite fide of the river, was purchased of the Indians, May 20th, 1662. A fpot in Eaft-Haddam was famous for Indian Pawaws, and was fubject for many years to earthquakes and various noiles, which the first fettlers, agreeable to the superstiti-ous ideas of that age, attributed to these Pawaws. An old Indian being afked what was the reafon of fuch noifes in this place ?--- anfwered, " The Indian's God was very angry becaufe the Eng-lifhmen's God came here .---" Theie noifes are now frequently heard.

HADDONFIELD, a finall town in Gloucefter county, New-Jerfey, 9 miles S. E. by E. of Philadelphia, and 17 from Burlington.

HADLEY, a pleafant town in Hampfhire county, Maffachufetts, lying on the east fide of Connecticut river, nearly oppofite Northampton, 20 miles north of Springfield, and 97 weft of Bofton. The town confifts of two long fpacious ftreets, which run parallel with each other, and with the river. The townfhip contains 882 inhabitants.

HAGARSTOWN, now called Elizabeth Town; which fee. It has a confiderable trade with the weffern country, and has between two and 300 houfes. It is fituated in Washington county, Maryland; is a post-town, 26 miles north-west of Fredericktown, 73 N. W. by W. of Baltimere, and 22 S. by W. of Chambersburg in Pennsylvania.

HALBUT POINT, the north-east point of Cape Anne, in Massachusetts.

HALES, a location in Grafton county, New-Hampfhire, having 9 inhabitants,

HALF MOON, an extensive township in Albany county, New-York. It contains 3,600 inhabitants; of these, 128 are flaves, and 563 are qualified electors. *Waterford*, a neat, compact, thriving village of about 70 or 80 houses, two miles E. N. E. of the Cohoez, and 12 miles north of Albany, on the north bank of the most northerly branch of Mohawk river and on the west bank, of the Hudson, is fituated in this township.

HALLFAX, a county in the eaftern part of the British province of Nova-Scotia. It contains Halifax, the capital: the townships of Londonderry, Truro, Onslow, Colchester, Lawrence, Southampton, Canso, and Tinmouth, The inhabitants are chiefly Irish, Scotch and New-Englanders. It has numerous bays, and rivers; the chief of the latter are Shabbennacadie, which is a boatable river, the Petitcodiac, Memramcook, &c. See Nova-Scotia.

HALIFAX, the capital of the province of Nova-Scotia, in the county of its name, was fettled by a number of Bri-tilh fubjects in 1749. It is fituated on a spacious and commodious bay or harbour, called Chebucto, of a bold and eafy entrance, where a thousand of the largest ships might ride with great convenience and fafety. The town is built on the welt fide of the harbour, on the declivity of a commanding hill, whofe fummit is 236 feet perpendicular from the level of the fea. The town is laid out into oblong fquares; the ftreets parallel and at right angles. The town and fuburbs are about two miles in length; and the general width a quarter of a mile. It contained in 1793 about 4000 inhabitants and 700 houles. At the northern extremity of the town, is the king's naval yard, completely built and fupplied with flores of every kind for the royal navy. The harbour of Halifax is reckoned inferior to no place in British America for the feat of government, being open and acceffible at all featons of the year, when almost all other

223

other harbours in these provinces are locked up with ice; also from its entrance, fituation and its proximity to the bay of Fundy, and principal interior fettlements of the province.

county.

5 miles N.W.

by W.

ift point

county,

bitants.

wnship

It con-

fe, 128 lectors.

hriving

es, two

and 12

th bank

of Mok of the

hip.

eaftern

Nova-

he capi-

mderry,

wrence,

mouth.

, Scotch

imerous

he latter

boatable

mcook,

province

y of its

of Bri-

lated on

or har-

and ea-

of the

eat con-

is built

, on the

, whofe

lar from

1 is laid

reets pa-

he town

niles in

quarter

13 about

es. At

iown, is

ely built

ery kind

bour of

no place

t of go-

effible at

Imoft all other

a. 1

This city lying on the fouth coaft of Nova-Scotia, has communication with Pictou, 68 miles to the north-east on the gulf of St. Lawrence, by a good cart-road, finished in 1792. It is 12 miles northerly of Cape Sambro, which forms in part the entrance of the bay; 27 fouth-easterly of Windfor, 40 N. by E. of Truro, 80 N. E. by E. of Annapolis on the bay of Fundy, and 157 fouth-east of st. Ann, in New-Bruntwick, measuring in a ftraight line. N. lat. 44. 40. W. long. 63. 15.

HALIFAX, a fort in the town of Winflow, in Lincoln county, Maine, erected by order of Governor Shirley in 1754. It ftands on the point of land formed by the confluence of the Sebaltacook with the Kennebeck, 30 miles below Sandy river.

HALIFAX, a township in Windham county, Vermont, 23 miles E: by S. of Bennington, has Marlborough on the north, and the Maffachufetts line fouth. It contains 1300 inhabitants.

HALIFAX, a township in Plymouth county, Maffachufetts, fituated 35 miles fouth-east of Boston. It was incorpo rated in 1734, and contains 664 inhabit ants.

HALIFAX, a village or fettlement on the east fide of Sulquehannah river in Dauphin county, Pennfylvania, 13 miles

north of Harrifburg. HALIFAX, one of the middle diffricts of North-Carolina, bounded north by the State of Virginia, east by Edenton district, welt by Hillfborough, and fouth by Newbern. It is divided into 7 counties, viz. Northampton, Halifax, Mar-tin, Edgcomb, Warren, Franklin, and Nafh, which contain 64,630 inhabitants, including 2 5,402 flaves. Befides fmaller ftreams, the Roanoke paffes through this district in a fouth-east course, and the Pamplico has its fource in it. Chief town, Halifax.

HALIFAX, a county of the above diftrict, bounded north by Northampton, fouth by Edgcomb, eaft by Bertie, and welt by Warren. It contains 7459 inhabitants, and 6506 flaves. Chief town, Halifax.

HALIFAX, the chief town of the 3 63

name in North-Carolina, is a post-town, pleafantly fituated on the weftern bank of the Roanoke, about fix miles below the falls, regularly laid out, and belides dwelling houses, has a court-house and gaol. It is 36 miles north of Tarborough, 28 miles from Grenville courthonie, 147 north-eaft of Fayetteville, 75 S. by W. of Petersburg, Virginia, and 383 S. W. by S. of Philadelphia. N. lat. 36. 13.

HALIFAX, a county in Virginia, bordering on the State of North-Carolina, It is about 42 miles long, and 39 broad. and contains 14,722 inhabitants, including \$ 56 5 flaves.

HALLAM, a township in York county, Pennfylvania.

HALLOWELL, a flourishing post-town in the District of Maine, and the shire town of Lincoln county, fituated in N. lat. 44. 16. at the head of the tide waters on the weft fide of Kennebeck river. An academy is established here with a confiderable fund in lands. The court-houfe here is 12 miles S. by W. of Vaffal-borough, 30 N. by W. of Wilcaffet, 40 north-east of New-Gloucester, and 195 N. by E. of Bolton, Hallowell Hook lies on the fame fide of the river. three miles below the town, and five north of Pittfton. The whole township contains 1194 inhabitants.

HAMBATO, a principal affiento, or jurifdiction in the province of Quito, in Peru. It is fituated in 1.41. S. lat. and 12 miles weft of the city of Quito; and has 6 finall villages in its dependence. It contains about 18,000 inhabitants, who are mostly employed in weaving fluffs, and in knitting.

HAMBDEN, or Hamden, a township in New-York State, bounded north by land ceded to Maffachufetts, fouth by the north line of Pennfylvania, and east by Sidney. Sufquehannah river paffes in a welt courie through both towns. The centre of the town lies 13 miles W. by S. of the mouth of Chenengo river.

HAMBURG, a fmall post-town of New-Jerley, 18 miles from Gofhen in New-York, and 20 from Newtown or Suffex court-houfe.

HAMBURG, a handfome town in Burke's county, Pennfylvania, feated on the east fide of Schuylkill. Here are about 50 or 60 houses, a German Lutheran

theran and Calvinist church, united. It is 18 miles N. by W. of Reading, and 70 north-north-west of Philadelphia. North lat. 40. 34. W. long. 76.

HAMDEN, a township in New Haven county, Connecticut, about eight miles north of New-Haven city.

HAMDEN, a township of the District of Maine, in Hancock county, on the west fide of Penobleot river; opposite Orrington; having about 50 families in 1796.

HAMILTON, a cape on the north end of Newfoundland Island.

HAMILTON. There are three townfhips of this name in Pennfylvania; one in each of the counties of York, Franklin, and Northampton.

HAMILTON, a fettlement in Vermont on the Canada line.

HAMILTON, in Herkemer county, New-York, a township 12 miles square, 20 south of old Fort Schuyler, a level township of good land, fast settling.... Oriske or Othiske creek, a water of Mohawk, and Chemung, a water of Susguehannah, rife in this township. In 1796 there were 1202 inhabitants, of whom 196 were electors.

HAMILTON, a town or fettlement lately laid out in Albany county, New-York, in the extensive township of Water Vliet, formerly called the Glass Factory; and has its prefent name in honour of that great patron of American manufactures, the late fecretary of the treafury of the United States of America. It lies 10 miles welt of Albany, two miles from the Scheneclady road; and is one of the most decisive efforts of private enterprife in the manufacturing line, as yet exhibited in the United States. The glafs manufactory is now fo well eftablifhed, and fo happily fituated for the fupply of the northern and weftern parts of the States of New-York, as well as Vermont and Canada, that it is to be expected the proprietors will be amply rewarded for their great and expensive exertions. The glass is in good repu-tation. Here are two glass-houses, and rarious other buildings, curious hydraulic works to fave manual labour, by the help of machinery. A copious ftream runs through the heart of the fettlement which lies high; and being forrounded by pine plains, the air is highly falubrious. The great Schoharie road tra-veries the fettlement. A fpacious

fchool-houfe, and a church of an octagon form are foon to be erected.

The enterprising proprietors of the Glass and other works in this thriving fettlement, were incorporated by the Legislature of New York in the spring of 1797; by the name of "The Hamilton Manufacturing Society, which act, has given a spring to the works here; and authorifes a hope that Ame ican manufactures may not only subserve the interests of our country but that also of the proprietors.

In the neighbourhood of these glass works, a block was cut out of an ancient tree, not many years ago, nontaining evident marks of an axe or some edge tool, made i85 years ago, determined according to the usual and certain mode of alcertaining the age of trees. The block is preferved in Albany as a curiosity. Henry Hudson alcended the river which bears his name, as high as Albany, in the autumn of 1609, 187years ago, and these marks were probably made by some of his men.

HAMILTON, on Chaleur Bay; fee Bonaventure.

HAMILTON FORD lies near the mouth of Bullock's Creek in North-Carolina. This was the route purfued by Tarleton, after his defeat at Cowpens, in January, 1781.

HAMILTON, a diffrict in the State of Tennefice, fituated on the waters of the Holfton and Clinch; bounded fouth by Tennefice river, and feparated from Mero diffrict on the weft by an uninhabited country. It contains the counties of Knox, Jefferfon, Blount, Sevier, and Grainger.

HAMILTON, a county of the N. W. Territory, erected Jan. 2, 1790. " beginning on the bank of the Ohio river at the confluence of the Little Miami ; and down the faid Ohio river, to the mouth of the Big Miami, and up faid Miami to the ftanding Stone, Forks, or branch of faid river ; and thence with a line to be drawn due E. to the Little Miami, and down faid Little Miami river to the place of beginning."

HAMILTON, FORT, ftands on the eaft fide of the Great Miami, in the N. W. Territory; 25 miles fouth of Fort St Clair, and 25 north of Cincinnati. It is a flockaded fort, capable of containing 200 men. The fituation is as advantageous for defence as pleafing to the

the eye. It is built upon a narrow neck of land, commanding the Miami on the north-weft, and a prairie and fheet of water on the north eaft, about a mile wide, and a miles long. The foil near it is rich and fertile; and forage may be got by repeated mowings of natural grafs. HAMILTON, a port in the Bermuda Islands.

HAMMEL'S TOWN, a town in Dauphine county, Penníylvania, five miles from Sulquehannah river, and 85 from Philadelphia. It contains a German church, and about 35 dwelling houses.

HAMPDEN SYDNEY COLLEGE. See Prince Edward County, Virginia.

HAMPSHIRE, an extensive, populous and wealthy county in Maffachufetts, made a fhire in 1662. It is in many parts mountainous and hilly, and extends acrofs the state from north to fouth ; bounded north by the States of New-Hampfhire and Vermont, fouth by the State of Connecticut, east by Worcefter county, and weft by Berkshire. It contains 60 townships, 9181 houses, 9617 families, and 59,681 inhabitants. Its principal towns lie on both fides of Connecticut river, which interfects it from north to fouth. Thefe are Springfield, Weft-Springfield, Northampton, Hadley, Hatfield, Deerfield, and Northfield. It is generally of a fertile toil, and produces the necessaries of life, and fome of its luxuries in great plenty.

HAMPSHIRE, a county in Virginia, bounded N. and N. W. by the Patowmack river, which divides it from the State of Maryland. It is about 60 miles long and 50 broad, and contains 7346 inhabitants, including 454 flaves. It is well watered by Patowmack and its fouth branch. Iron ore and coals have been difcovered on the banks of this river. Chief town, Romney.

HAMPSTEAD, a town in Rockingham county, New-Hampshire, about 30 miles westerly of Portsmouth. It was incorporated in 1749, and contained in 1775, 268 inhabitants; in 1790, 724.

HAMPSTEAD, a town on Long Island, New-York, nine miles easterly of Jamaica, and 23 miles eastward of New-York city. In this town is an extensive and remarkable plain, called Hambshead Plain. See Long Island.

Hampflead Plain. See Long Ifland. HAMPSTEAD, a village in Georgia, about four miles from Savannah, and about a mile from another village called

Highgate. The inhabitants are gardeners, and fupply the town with greens,

HAM

pot herbs, roots, &c. HAMPTON, a township in Windham county, Connecticut, three miles northeast of Windham, of which it was formerly a parish, but lately incorporated.

HAMPTON, EAST, a township in Hampshire county, Massachusetts, containing 457 inhabitants, and situated 105 miles welt of Boston. It was incorporated in 1785.

HAMPTON, EAST, on the east end of Long-Ifland, (New-York) a half fhire town of Suffolk county. It has 3260 inhabitants, and in it is Clinton Academy, which in 1795 had 92 ftudents.

HAMPTON, a township on the feacoast of New Hampshire, on the eastern fide of Rockingham county, and called *Winicumet* by the Indians. It was fettled under Massachusetts, and incorporated in 1638. In 1775 it contained 862 inhabitants, and in 1790, 853. It is 12 or 14 miles S. by W. of Portsmouth, and eight S. E. of Exeter. In 1791, a canad was cut through the marshes in this town, which opens an inland navigation from Hampton through Salisbury into Merrimack river, for about eight miles; loaded boats may pass through it with east and fasty.

HAMPTON FALLS, a finall town taken from the above town, lying on the road which leads from Exeter to Newbury-Port, fix miles fouth-eafterly of the former, and eight northerly of the latter. In 1775 it contained 645, and in 1790, 541 inhabitants. It was incorporated in 1712.

HAMPTON, a township in the northern part of Washington county, New-York, having Skeensborough on the west. It has 463 inhabitants, of whom 107 are electors.

HAMPTON, the capital of Elizabeth county, in Virginia, alfo a port of entry and polt-town, fituated at the head of a bay which runs up north from the mouth of James river, called Hampton Road, 5 miles north-welf of Point Comfort. It contains about 30 houfes, an epifcopal church, a court-houfe and gaol. The value of its exports of grain, lumber, flaves, &c. amounted to 41,997 dollars in one year, ending September 30, 1794. This town was anciently called Kecoughtom by the Indians. It is 18 miles N. of Norfolk, 22 S. E. of York-Town,

an octa-

of the

thriving

by the le fpring Hamilich act. ks here melican fublerve but that efe glafs f an an-Pontainor tome >, deterand cerof trees. any as à ided the high as 9, 187 proba-

ay; fee

ear the Northpurfued at Cow-

State of s of the outh by om Mehabited nties of ier, and

N. W. . " beio river Viami ; to the up faid rks, or ; with a Little ami ri-

on the the N. of Fort cinnati. of conon is as thing to the 93 E. S. E. of Richmond, and 205 W. by S. of Philadelphia.

HANCOCK'S HARBOUR, called by the Indians Cliequot, is fituated about 20 leagues E. S. E. of Nootka, in N. lat. 481 30, weft long. from Greenwich 125. 26. The entrance of this harbour is about 5 miles in length, and has good anchorage; about it are feattered a number of islands, and feveral fand banks or fpits. It has alfo a number of fine coves. The land round the harbour is generally uneven, rocky and mountainous; covered however with pine, fir, fpruce, cedar, hemlock, cyprefs and other trees of a remarkable fize. The climate here is much milder than in the fame latitude on the eastern fide of the continent; the frost in winter being feldom fo fevere as to prevent vegetation. An eafterly wind is confidered here as a prognoftic of a ftorm, and weft winds bring fair, weather. Deer, racoons, wolves, bears, fquirrels, martins, land otters, beaver and wild-cats are the animals which inhabit the forefts. The amphibious animals are the common feal, and the fea-otter. The fkin of the latter is very valuable. The inhabitants are faid to be cannibals. This and other places of the fame name have their appellation in honour of the late Governor Hancock, of Maffachufetts.

HANCOCK, a river of Washington ifland, on the N. W. coaft of North-America, called Masheet by the Indians, discovered by Captain Crowell in 1791. It empties into the fea from the north end of the largest island. At its mouth it is nearly two and an half nantical miles wide; and a confiderable fize 10 miles up. It has at its mouth five fathoms water, gradually increasing in breadth; and for 71 miles up, to Goole Island, has not less than ten fathôms. Captain Ingraham examined it about iz miles; but by the information of the natives, he judged that it communicates with Skitikifs Bay, or near it, on the eaft fide of the iflands. It is by far the most eligible for a new fettlement, of any place the Captain had feen on the coaft. The land is low and apparently very fertile; and the river abounds with falmon. Were a good house erected on fome of the pleafant fpots it would have every appearance of being long fettled. Beautiful bufhes and grafs occupy the fkirts of the woods. The mouth of the river is in north lat. 54. 7. weft long. 131. 54.

HANCOCK, a township in Addison county, Vermont.

HANCOCK, a large maritime county of the Diffrict of Maine, bounded N. by Lower Canada, S. by the ogean, E. by Washington county, and W. by Lincoln county. It is 190 miles long from north to fouth, and nearly 60 broad. It contains 24 townships and plantations; of which Penobfcot and Caftine are the chief. The number of inhabitants is greatly increased fince. 1790. At that time there were 9549 fouls. It is remarkably well watered by Penoblcot river and its branches, Union river, and other fmall streams. The northern part of the county fends its waters in one ftream from numerous branches, in a N. E. courfe to St. John's river. On the fea-coaft are many harbours and in'ets, hid by a multitude of fertile islands; the largest of these in a S. W. direction from Gold/borough, are Mount Defart, SwanIfles, Vinal Haven, Haut Ifle, Deer, and Iflefborough ; all fituated in Penobicot Bay. Great part of the country is yet unfettled. The towns along the fea-coaft, and on the banks of Penobicot and Union rivers, are the most fertile and populous. Caltine is the fhire town. See Maine and Penobscot.

HANCOCK, a township in Lincoln county, Maine, embosomed by the Kennebeck and Sebasticook rivers, bounded N. W. by Canaan, and 7 miles north of the confluence of the two rivers. It contains 278 inhabitants,

HANCOCK, a township in Hillsborough county, New-Hampshire, situated between two western branches of Contoocook river, 14 miles east of Keene, and between 60 and 70 W. by S. of Portsmouth. It was incorporated in 1779, and contains 634 inhabitants.

HANCOCK, a long, narrow and mountainous township on the New-York-line, in Berkshire county, Maslachusetts, having the towns of Lanesborough and Partridgesield on the northward, and Pittsfield on the S. It was incorporated in 1776, has 1211 inhabitants, and lies 20 miles N. by W. of Lenox, and 150 W. of Boston.

HANCOCK, a fmall poft-town of Maryland, fituated in Wafhington county, on the N. bank of Patowinack river, between

betwe creek in Per in M more. HA per di HA Hudfe end o and c river, and I HA count of Gi Bedfo by W latter. HA the St rio, 1 HAT ras, fi fula o the w tract and th nifh k at the of cul See B. HA count in Wa Hanoy count HA poft-te nia, i and a flows tains 1 Germ miles miles S. of HA count from] and co HA Hamp Conne Darin fituate half a N. lat Green

between Conolowy and Little Conolowy creeks, about 25 miles S. E. of Bedford in Pennfylvania, 34 N.E. of Old Town in Maryland, and 119 N.W. of Baltimore.

HANCOCK, a new county in the upper district of Georgia.

HANNAH BAY House, a factory of the Hudson's Bay Company, at the fouth end of James' Bay in North-America, and on the eastern fide of Harricanaw river, 45 miles E. by S. of Moofe Fort, and 18 below a house on the fame river. HANNAH's-TOWN, in Weltmoreland county, Pennfylvania, 4 miles N. N. E. of Greenburg; and on the road from Bedford to Pittfburgh; 54 miles N.W. by W. of the former, and 26 east of the latter.

HANNIBAL, a military township in the State of New-York, on Lake Ontario, 10 miles S. by W. of Fort Ofwego. HANOVER, a bay in the fea of Honduras, fituated on the E. fide of the peninfula of Yucatan, from which it receives the waters of the Rio Honde. The tract of land between the river Honde and the Balize was ceded by the Spaailh king to the king of Great-Britain, at the peace of 1783, for the purpole of cutting and carrying away logwood. See Bahia de Chetumal.

HANOVER, a township in Luzerne county, Pennfylvania. Alfo a township in Washington county. East and West Hanover, are 2 townships in Dauphine county in the fame State.

HANOVER, or M'Allifter's-Town, a post-town in York county, Pennfylvania, fituated between Cadorus creek, and a branch of Little Conewago, which flows into the Sufquehannah. It contains nearly 300 dwelling houfes, and a German and Lutheran church. It is 7 miles north of the Maryland line, 18 miles S. W. of York, and 106 W. by S. of Philadelphia.

HANOVER, a township in Plymouth county, Maffachufetts, 25 miles S. E. from Bofton; was incorporated in 1727, and contains 1083 inhabitants.

HANOVER, a post-town of New-Hampfhire, fituated on the east fide of Connecticut river in Grafton county. Dartmouth College, in this town, is fituated on a beautiful plain, about half a mile, from the river, in 43. 43. N. lat. and in 72. 14. W. long. from Greenwich. It derives it's name from abounds with lime-ftone. 221

William, Earl of Dartmouth, one of its principal benefactors, and was founded in the year 1769 by the late Dr. Eleazer Wheelock. The funds of the college confift chiefly of lands, amounting to about 80,000 acres, which are increasing in value in proportion to the growth of the country; 1,200 acres lie contiguous to the college; and are capable of the best improvement; 12,000 lie in Vermont. A tract of 8 miles square was granted by the affembly of New Hampthire in 1789. The revenue of the college, ariting from the lands, in 1793, amounted annually to f. 140. By contracts then made, they would amount, in four years after, to £.450; and in 12 years to £.650. The income from tui-tion is about £ 600 per annum. The number of under-graduates is, on an average, from 150 to 180. A grammar fchool of about 50 or 60 fcholars is annexed to the college. The ftudents are under the immediate government and inftruction of a prefident, who is alfo protefior of hiftory, a professor of mathematics and natural philofophy, a proteffor of languages, and two tutors. The college is furnished with a handfome library and a philosophical apparatus to-lerably complete. A new college edifice of wood, 1 50 by 50 feet, and three flories high, was created in 1786, containing 36 rooms for students. Its situation is elevated, healthful and pleafant, commanding an extensive prospect to the west. There are three other public buildings, belonging to the college, and a handfome congregational meeting houfe has lately been erected, in which the commencement exercifes are exhibited. It is 32 miles N. of Charlestown, 115 N. W. by W. of Portfmouth, 138 N. W. of Bolton, and 378 N.E. by N. of Philadelphia.

HANOVER, a township in Morris county, New-Jerfey. In a ridge of hills in this township are a number of wells; 40 miles from the fea in a ftraight line, which regularly ebb and flow about 6 feet twice in every 24 hours. It is about 16 miles N.W. of Elizabeth-Town, and joins upon Morriftown.

HANOVER, a county of Virginia, lying between Pamunky and Chickahominy rivers. Its length is about 48 miles, and its breadth 22; and contains 14,754 inhabitants, including 8,223 flaves. It

HANOVER,

7. weft Addifon e county ided N. e ogean, und W. iles long early 60 nips and fcot and mber of ed fince ere 9549 watered ranches, Areams. ity fends umerous . John's any hartitude of thefe in borough, inal Haorough ; Great ed. The 1 on the n rivers, s. Calaine and

> Lincoln he Kenbounded north of It con-

borough ted be-Contooene, and f Portfin 1779, distance.

d mounwrk-line, chufetts, ugh and d, and incorpoibitants, Lenox, of Macounty, k river,

between

HANOVER, a finall town of Virginia, of the above county, fituated on the W. fide of the Pamunky, in which is an academy. It is fix miles from New-Caftle, 22 N. E. by E. of Richmond, and 110 N.N.W. of Washington city. HANTS, a county of Nova-Scotia, be-

ginning about 30 miles from Halifax, contains the townfhips of Windfor, Falmouth, and Newport; feveral valuable tracks remain unfettled. The road from Halifax runs part of the way between Windfor and Newport, and has fettlements on it at fmall diftances. The county is about 20 miles fquare, and is well watered. The rivers St. Croix, Kenetcoot, and Cocmiguen empty into the Avon, and are all navigable except the laft. The Cacaguet and Cobeguit are navigable 40 miles for veffels of 60 tons.

HAPAEE, 4 fmall islands among the Friendly Isles, in the South fea.

HARDIN, a new county in the State of Kentucky, bounded N.E. by Walhington and Lincoln, N. W. and W. by Nelfon and Greene, and S. E. by Logan counties.

HARDWICK, a township in Caledonia county, in Vermont.

HARDWICK, a township in Worcester county, Massachusetts, 25 miles N. W. of Worcester, and 70 S. W. of Boston. It is separated from New-Braintree and Ware by Ware river. There are within this town 245 houses, 1725 inhabitants, 5 corn and 4 faw mills, and two clothiers' works.

HARDWICK, a township in Suffex county, New-Jersey, nearly 10 miles S.W. of Newton.

HARDWICK, a fmall town of Georgia, at the mouth of Ogeechee river, and about 18 miles S. by W. of Savaanah. It has lately been made a port of entry.

HARDY, a county of Virginia, bounded north by Hampshire. It is about 60 miles long, and 40 in breadth, and contains 7336 inhabitants, including 369 flaves. Chief town, Moorfield.

HANDYSTON, a township in Suffex county, New-Jetsey, containing 2393 inhabitants, including 26 flaves.

HARE Bay, a large bay on the eaft coast of Newtoundland,

HARE Indians inhabit near M'Kenzie's river in the N.W. part of North-America.

HARFORD County, in Maryland, is bounded N. by York county in Pennfylvania; E. by Su quehannah river and Chefapeak Bay. The chief waters within the county are Buth river and Deer ceeek; on which are 16 mills of different kinds. On the former and its branches are the towns of Harford, Abington, Coopftown, and Belle-Air. The other towns are Hawre de Gras at the mouth of Sufquehannah, and Joppa below the forks of Gunpowder.

It contains 14,976 inhabitants, including 3417 flaves. Chief town, Belle-Air.

HARFORD, or Bufb-town, in Harford county, Maryland, lies at the head of the tide waters of Bufh river, between Binam's and James's runs; the former feparating it from Abington. It has few houfes, and is falling to decay fince the courts of juffice have been removed to Belle-Air. It is nine miles S. E. of Belle-Air. and 25 N.E. by E. of Baltimore.

HARLEM, a township in Lincoln county, Maine, incorporated in 1766. It was formerly called *Jones's Plantation*.

HARLEM, or East River, a river which connects Long-Ifland Sound with North, or Hudson River, and forms York-Ifland.

HARLEM, a division of New-York county in the northern part of York-Island, which contains 803 inhabitants, including 189 flaves. The village of its name stands 9 miles northerly of New-York city, and 4 S.W. of West-Chester. It is opposite to the west end of Hell Gate.

HARMAN's Station, in Kentucky, is a fort on the east fide of the west branch of Big Sandy river. On the opposite fide of this branch is the Great Salt. Spring. Harman's Station is about 20 miles S. of Vancouver's fort.

HARMAR, a well confiructed fort in the N. W. Territory, fituated at the mouth of the Mufkingum. It has 5 baftions, and 3 cannon mounted, and is garrifoned by 4 companies. It is conveniently fituated to reinforce any of the pofts up or down the river Ohio. The place is remarkably healthy.

HARMONY, a village in Luzerne county, Pennfylvania, clofe on the line of New-York, on the north fide of Starucca creek, a water of the E. branch of Sufquehannah river. Between this and Stockport on Delaware river, diftant 18 miles E.S.E. there is a portage. It is about

about 140 miles N. by W. of Philadelphia, and 130 N.W of New-York. N. lat. 41. 58.

HARPATH, a finall boatable river in Tennefice, which, after a N. N. W. courfe of about 40 miles, falls into Cumberland river, 19 miles N. W. of Nafhville.

HARPERSFIELD, a township in Otsego county, in New-York, bounded S. W. by Unadilla township, and 3.2 miles S. E. of Cooperstown; 155 of its inhabitants are electors. Through this town runs the great post-road from Hudson to Williamsburgh, 62 miles west of Hudson city.

HARPLE, a township in Delaware, county, Pennsylvania.

HARPSWELL, a township in Cumberland county, diffrict of Maine, incorporated in 1758, and contains 1071 inhabitants. It is bounded eafterly by Georgetown; from which it is feparated by a navigable river. The people here are opening a communication by a canal between the waters of Kennebeck river and those of Casco Bay, through the arm of the fea called Stevens's river. The point called Merryconeag, projecting itself into the bay together with the ifland Sebascodeagan, and several other fmall iflands, are incorporated and form this township. The waters round this ifland extend to within two miles of the waters of the Kennebeck, and thus form what is called Small Point.

HARRINGTON, a township in Bergen county, New-Jersey.

HARRINGTON, a thriving town in Lincoln co. district of Maine, at the head of the tide waters on the Kennebeck river, three miles N. of Hallowell, of which, till its incorporation in 1797, it was a part, and known by the name of For: Western. Vessels of 100 tons alcend the river to this town. The judicial courts for the county are held alternately in this town, and at Pownalborough. There is here a court-houfe, and goal. A bridge is about to be crected upon the Kennebeck, opposite old Fort Western. Several merchants and traders are fettled here, and carry on a brifk commerce with the back country. The township contains 36,000 acres of land, and about 1000 inhabitants. N. lat. 44. 25.

HARRISBURG, a post-town, and the capital of Dauphine county, Pennfylva-

nia, is fituated on the N. E. hank of Sulquehannah river. It is laid out regularly, and contains about 300 houles; of which feveral are neat and convenient; fome of brick and others of fione. In 1789, it contained 130 houfes, a fione gaol, and a German church. At that period it had been fettled about 3 years. It is 107 miles W. N. W. of Philadelphia, 53 W. S. W. of Reading, and ry E. N. E. of Carlifle. N. lat. 40. 16.

HARRISON, a township in West- Chefter county, New-York, containing 1004 inhabitants; of whom 115 are electors, and 54 flaves.

HARRISON, a county in the weftern part of Virginia, bounded N. by Ohio county, N. E. by Monongalia, S. by Greenbriar, and S. W. by Kenhawa. Its length is about 120 miles, its breadth 80; and the number of inhabitants 2,080, including 67 flaves. Chief town, Clarkfburg.

HARRISON, a new county in the N. E. part of the State of Kentucky, N. of Bourbon.

HARRODSBURG, or Harrodflown, a post-town in Mercer county, Kentucky, at the head of Salt river, which contains about 20 houses, and is 10 miles S. W. of Danville, 30 S. by W. of Frankfort, and 825 S. W. of Philadelphia.

HARTFORD, a township in Windfor county Vermont, on Connecticut river, opposite the town of Lebanon, in New-Hampshire. It contains 988 inhabitants.

HARTFORD, a township on the east bank of Geneffee river, in New-York. State, 40 miles W. of Geneva, and 67 S. E. by E. of Fort Niagara.

HARTFORD, a fertile and populous, though hilly county, in Connecticut, bounded N. by the State of Maffachufetts; S. by part of Middlefex and New-Haven counties; E. by Tolland, and W. by Litchfield county. It is about 34 miles from N. to S. and its greateft breadth from E. to W. is 30 miles. It is divided into 15 townfhips, and contains 28,029 inhabitants, including 263 flaves. Chief town, Hartford city.

HARTFORD City, the capital of Connecticut, lies on the weft bank, of Connecticut river, in the county and townfhip of its own name, 50 miles northwefterly from the mouth of the river, at Saybrook Bar, in Long Ifland Sound 3 and thus far the tide flows. The town-

thip

waters rer and nills of and its d, Abr. The at the

ver and

, inclu-Belle-

Harford

read of

ppa be-

etween former It has uy fince emoved . E. of Baltin coun-It was t. r which North,

York-

-Vork Yorknitants, age of erly of Weftreft end Acres cky, is branch ppofite at Salt. out 20 fort in at the s bafand is is conany of Ohio. e counline of of Stainch of uis and ant 18 It is

about

HAR

thip is 6 miles fquare, bounded N. by Windfor, N. E. by Eaft-Windfor, W. by Farmington, E. by Eaft-Hartford, S. E. by Glaffenbury, and S. by Wethersfield. The town is divided by a fmall itream called Little River, with high romantic banks, over which is a bridge connecting the two divisions of the town. The city is regularly laid out, the fireets interlecting each other at right angles. Its buildings arean elegant ftate-houfe, lately built, 2 churches for Congregationalifts, I for Episcopalians, and between 400 and 500 dwelling-houfes; a number of which are handfomely built with brick. The inhabitants amount to upwards of 4,000. A bank was incorporated in 1792, with 100,000 dollars capital, num. ber of fhares 2 50. The corporation have the power to extend their capital to 500,000 dollars. A woollen manufactory was established here and encouraged by the State, but has not fucceeded. The town is advantageoufly fituated for trade, has a fine back country, enters largely into the manufacturing bufinefs, and is a rich, flourifhing, commercial town.

This town was first fettled in the year 1636, by Mr. Haynes and Mr. Hooker, who, with their adherents, removed from Maffachufetts. The Dutch had then a trading house at the confluence of Mill and Connecticut rivers. They foon relinguished the fettlement, and their lands were confilcated by a commission from the Commonwealth of England in 1653. A point of land, which formed part of their poffessions, is still called Dutch Point. It is 40 miles N. E. by N. of New-Haven, 55 N. W. of New-Lon-don, 124 S. W. of Boston, 128 N. E. of New-York, 223 N. E. of Philadelphia, 502 from Richmond, 376 from Wafhington city, 1044 from Augusta, and 1018 from Frankfort in Kentucky. N. lat. 41. 44. W. long. 70. 4.

HARTLAND, a township of Connecticut, the north-easternmost in Litchfield county.

HARTLAND, a township in Windsor county, Vermont, fituated on the west bank of Connecticut fiver, it miles below the 15 mile Falls.

HARVARD, a township in the eastern part of Worcester county, Massachusets, which is remarkable for sudden squalls of wind, and for the most severe storms of thunder, lightning, and rain, which happen almost every day, during one porated in 1732, by this name, in honour

HAT

of the founder of Harvard University in Cambridge. It has 1400 inhabitants. HARVARD UNIVERSITY. See Cam-

bridge. To deterri Domen . It a the li

HARWICH, a township on Cape Cod, in Barnstable co. Massachust, lying between Yarmouth and Chatham, about 88 miles S. E. of Boston, containing 2392 inhabitants. It extends quite across the cape, which is here about 6 miles over. Their marine business lies chiefly in the fishery. The remains of the Indians of this township are only 6 or 7 fouls. The live at Potanumaquut.

HARWICH, a township in Rutland county, Vermont, containing 165 inhabitants.

HARWINGTON, a post-town of Connecticut, in Litchfield county, 8 miles E. of Litchfield, and 24 W. by N. of Hartford.

HATBOROUGH, a finall town in Montgomery county, Pennfylvania, fituated on the N. E. fide of Pannepack Creek, which runs into Delaware river about 5 miles above Frankfort. It contains about 20 houses.

HATCHA CONES. See Pearl River. HATCHI. See Pearl River.

HATCHY, a navigable river in the State of Tenneffee, runs westerly into the Miffisippi, about 19 miles N. of Wolf river, and is about 80 yards wide 7 miles from its mouth.

HATFIELD, a very pleafant town in Hampfhire county, Maffachufetts, fituated on the weft bank of a bend of Connecticut river where it is 80 rods wide, 5 miles north of Northampton, and 100 weft of Bofton. It lies chiefly on one ftreet, and contains 103 houfes, and 703 inhabitants. Here are two ferries on Connecticut river; the one to Hadley, the other to Amherft. North of the ferry to Amherft, the river meets with a bed of rocks, which leffens its breadth 20 or 30 rods—no fall, but a large eddy at high water.

HATTERAS is the molt remarkable and dangerous cape on the coaft of N. America. This point extends far into the ocean, from the coaft of N. Carolina, in 35. 15. N. lat. The water is very fhoal at a great diffance from the cape, which is remarkable for fudden fqualls of wind, and for the moft fevere florms of thunder, lightning, and rain, which happen almost every day, during one half the year. At the time of Sir Wal-

ter Rai the fho were fo and fo f with n that no within At p about n but of . they an moderat extent. is about here, at tremend to the cl of the G eaftern e the decli from 10 the fpot firm fand good vef and go to however, over, if much d: ing more From thi tent, and ridge ru cape abor half a mi generally There an fording c water. bout a m and is a wide, an paffed by ly used ex may be breakers : and a bre ern fide ; conftant. is confider of the cap fathoms ; ward, a even brin plenty of where on or two, a fand. HATTO ver, a vill

verfity in habitants. See Cam-

Jape Cod, tts, lying am, about ining 2392 acrofs the niles over. efly in the Indians of r 7 fouls.

n Rutland 165 inha-

vn of Cony, 8 miles by N. of

town in vania, fitu-Pannepack aware river t. It con-

earl River. ver. iver in the refterly into niles N. of yards wide

lant town in fetts, fituatnd of Conrods wide, mpton, and lies chiefly 103 houfes, ere are two ; the one to erft. North e river meets h leffens its fall, but a

remarkable coaft of N. tends far into N. Carolina, water is very om the cape, udden fqualls fevere ftorms d rain, which , during one ne of Sir Walter

ter Raleigh's approaching this coaft, | court-houfe, in S. Carolina, and 17 from the fhoals in the vicinity of Hatteras were found fo dangerous, fo extensive, and fo fhallow, many of them covered with not more than 5 or 6 feet water, that no veffels, in that latitude, ventured

HAT

within 7 leagues of the land. At prefent the out-fhoals, which lie about 14 miles S. W. of the cape, are but of 5 or 6 acres extent, and where they are really dangerous to veffels of moderate draught, not above half that extent. On the fhoaleft part of these is about to feet at low water; and here, at times, the ocean breaks in a tremendous manner, fpouting, as it were, to the clouds, from the violent agitation of the Gulf Stream, which touches the eaftern edge of the banks, from which the declivity is fudden, that is to fay, from 10 fathoms to no foundings. On the fpot above mentioned, which is firm fand, it has been the lot of many a good veffel to ftrike, in a gale of wind, and go to pieces. In moderate weather, however, these shoals may be passed over, if neceffary, at full tide, without much danger, by veffels not drawing more than 8, 9, or 10 feet water. From this bank, formerly of vaft extent, and called the Full Moon Shoal, a ridge runs the whole diffance to the cape about a N. W. course, is about half a mile wide, and at low water has generally, 10, 11 and 12 feet water. There are gaps at equal intervals, affording channels of about 15 or 16 feet water. The most noted of these is about a mile and a half from the land, and is at leaft two miles and a half wide, and might at full fea be fafely paffed by the largest ships ; but is rarely used except by coasting veffels. It may be eafily known by a range of breakers always feen on the weft fide, and a breaker head or two on the eastern fide; which, however, are not fo conftant, only appearing when the fea is confiderably agitated. A little north of the cape is good anchoring in 4 or 5 fathoms; and with the wind to the weftward, a boat may land in fafety, and even bring off cafks of fresh water, plenty of which is to be found every where on the beach, by digging a foot or two, and putting a barrel into the fand.

HATTON'S FORD, on Tugelo river, a village 16 miles from Pendleton Franklin court-houfe, in Georgia. 6.188

HAUT ISLE is the fouthernmoft of the large islands in Penebscot Bay, in Lincoln county, diffrict of Maine. HAVANNAH, a ftrongly fortified fea-

port town, on the northern fide of the island of Cuba, capital of the island, 191 miles almost directly S. of Cape Florida, and confequently commands the gulf of that name. Its great frength, importance, and happy fituation, occasion it to be called the key of the Weft-Indies. It is famous for its harbour, which is to large that it may hold 1000 veffels, and yet the mouth is fo narrow that only one fhip can enter at a time. This is the place where all the fhips that come from the Spanish settlements rendezvous on their return to Spain. The entrance into the harbour is well defended by forts and platforms of great The town, fituated on the weftguns. fide of the harbour, contains above 2000 houses with a great number of rich churches and convents. It is a place of great commerce; the refidence of the governor of the ifland, and other royal officers, the bilhop of St. Jago, and moft men of fortune belonging to the ifland. It was taken by the British in 1762, but reftored to the Spaniards by the treaty of peace in 1763. It is 30 miles W. of the town of Santa Cruz, and 54 miles. from Cape Sed. N. lat. 23. II. W. long. 82. 13.

HAVERFORD, a township in Delaware county, Pennfylvania.

HAVERHILL, a post-town of New-Hampfhire, and the capital of Grafton county, fituated on the caft fide of Connecticut river, in Lower Coos. It has between 40 and 50 compact houses, a well constructed court-house, and a congregational church. This townfhip was incorporated in 1763, and contains 552 inhabitants. In it is a bed of iron ore, which has yielded fome profit to the proprietor, also a quarry of free-ftone, fit for hearths and chimney pieces. It has alfo a fulling-mill, an oil-mill, and many other excellent mill-feats. It is ? opposite to Newbury in Vermont, 35 miles above Dartmouth college, 119 miles N. W. of Portfmouth.

HAVERHILL, a handiome post-town. of Maffachufetts, in Effex county, fituated on the N. fide of Marrimack river, across which is an elegant bridge, connecting

arches, of 280 feet each, fupported by 3 handfome from piers, 40 feet fquare ; alfo a draw of 30 feet, over the channel of the river. Haverhill has a confiderable inland trade, lying about 32 miles N. by W. of Bofton, and 12 miles from Newburyport, at the mouth of the river, and about 28 S. W. of Portimouth in New-Hampshire. It lies chiefly upon two freets; the principal of which runs parallel with the river. Veffels of see tons burthen can go up to it. Travellers are firuck with the pleafantness of the fituation; and a number of neat and well finished houses give it an air of ele. ince. Here are two churches, one for Congregationalifts, and one for Bap-tifts; 3 diffilleries, one of which has lately undergone a laudable transmutation into a brewery. Some veffels are annually built here, and feveral are employed in the West-India trade. A anufactory of fail-cloth was begun here in 1789, and is faid to be in a promifing way. The trade of this place, however, is confiderably lefs than before the revolution. The whole township contains 330 houfes, and 2,408 inhabitants.

HAVERSTRAW BAY, called by fome Haver bann, in Hudson's river, 38 miles above New-York city, fpreads S. of Stony Point, and before the town of its own name, is 10 miles long and about 3 wide.

HAVERSTRAW, a township in Orange county, New-York, fituated on the W fide of the above bay, 35 miles N. of New-York city. It contains 4,826 inhabitants, of whom 98 are qualified electors, and 238 flaves.

HAVRE DE GRACE, or GRAS, a pofttown and port of entry in Harford county, Maryland, on the W. fide of Sulquehannah river, at its mouth in Chelapeak Bay. It contains about 40 houles, 250 inhabitants, and is the port of entry for all the thores of Chefapeak Bay above Turkey Point. It is 6 miles W. by S. of Charleftown in Cecil county, 37 N.E. of Baltimore, and 65 W.S.W. of Philadelphia. N. lat. 39. 39.

HAW, a water of Cape Fear which emites with Deep river. It may be rendered navigable for so miles. See Saxspabar River.

HEB Gooneffing this town with Bradford, county, New-Hampthire, diffant 27 miles arches, of 250 fort arch. fr. It has 3 from Portfmouth, was incorrectly the 1760, and contained in 1775, 504, and in 1790, 410 inhabitants.

lorth given

an tr It lies

bury,

and P

Pennfy

is 70

This f

State o

Seneca having townfh

by W.

in Pem

ed 24 Warwi

HEI

Dauphi taining

man c

vinifts

fome fto

by N. of

other t State, t

in that

tains w

N. E.

Maine f to many

rence riv

the At

growth

and St. birch, he

pines, a

of the riv

north, f

trance, a

Beaufort

illands, o

Ifland, c

Port Roy

are St. H

ing Ifland

s or 6 i

ocean, fo and other

thele iflan

HELEN trict, S.

HELE S. Carol

HEIC

HEI

HEC

HE

HAWKINS, a county in Washington diffrict, in Tennefice, having 6,970 inhabitants, inclusive of 807 flaves. Chief town, Rogersville.

HAWKINS Court-boufe, in Tenneffee, is 25 miles from Free-stone Gap, 72 from Abingdon, and 178 from Danville in Kentucky.

HAWK'S BAY, on the coaft of Weft-Florida, weftward of the mouth of Mobile Bay, is between Pelican and Dauphin islands. There is a broad channel of 11 and 12 feet water, afterwards fafe anchorage in 4 fathoms, good holding ground, and fheltered from most winds; on which account it is very convenient for fmall veffels.

HAWKE's HARBOUR is an arm of Igornachoix Bay, Newfoundland Ifland.

HAWLEY, a township in Hampshire county, Maffachufetts, 120 miles wefterly of Botton. Previous to its incorporation in 1792, it was called Plantation No. 7, and had 539 inhabitants. It is composed of parts of feveral adjoining towns, and is about zo miles N. W. of Northampton.

HAYCOCKS, a fmall ifle in Delaware river, about 7 miles below Eafton in Northampton county, Pennfylvania.

HAYE's ISLAND, a fmall ifland of New South Wales formed by the rivers Nelfon and Hayes. At the mouth of Nelfon river ftands Fort York ; which, as well as Nelfon river, is called Bourbon by the French.

HAYNE'S FORT, COLONEL, is fituate ed in Nelfon county, Kentucky, on the north fide of Green river, 25 miles weft of Craig's Fort, and 53 from the Ohio,

HEATH, a township in Hampshire county, Maffachuletts, containing 379 inhabitants. It was incorporated in 1785, and is 125 miles N. W. of Botton, and about 18 milesN.N.W. of Northampton.

HEBRON, a town in Cumberland county, Maine, fituated on the N. E. fide of Little Androfcoggin, was incorporated in 1792. It is 35 miles N. by W. of Portland.

HEBRON, a township in Washington county, New-York, containing 1703 inhabitants, of whom 414 are electors. HEBRON, a township in Tolland coun-HAWKE, a township in Rocking am ty, Connecticut, fettled in 1704 from Northampton.

t 27 miles orated in 504, and

afhington 6,970 in-res. Chief

Tenneffee, P. 72 from anville in

t of Weftth of Moand Dauad channel rwards fafe od holding oft winds; convenient

an arm of and Ifland. Hampfhire iles wefterincorpora-Plantation ents. It is adjoining s N. W. of

in Delaware Eafton in vivania. land of New rivers Nel-uth of Nelwhich, as ed Bourbon

st, is fituate sky, on the miles weft n the Ohio. Hampfhire ning 379 in-Botton, and orthampton. erland coun-N. E. fide of w, of Port-

Washington electors. 'olland coun-1704 from orthampton.

粮臣臣

given by Joshua, fachem of the Mohean tribe, in his laft will and teftament. It lies between Lebanon and Glaftenbury, about 18 miles S. E. of Hartford, and r6 fouth of Tolland.

HEBRON, a Moravian fettlement in Pennfylvania, 16 miles from Litiz, which is 70 miles northerly of Philadelphia.

This fettlement began in \$7 57. HECTOR, a military township in the State of New-York, on the east fide of Seneca Lake towards the fouth end, having Ovid on the north and Newtown township on the fouth, and 29 miles S.

by W. of the ferry on Cayuga Lake. HEIDELBERG, a Moravian fettlement in Pennfylvania, begun in 1743; fituat-ed 24 miles from Litiz, which is in Warwick township, Lancaster county.

HEIDELBERG, a handfome town in Dauphine county, Pennfylvania, containing about 100 houses and two German churches for Lutherans and Calvinifts; one of the churches is a handfome ftone building. It is 33 miles E. by N. of Harrifburg, and 74 N. W. by W. of Philadelphia. There are two other townships of this name in the State, the one in York county, the other in that of Northampton.

HEIGHT OF LAND, a range of mountains which extend from S. W. to the N. E. and feparates the diffrict of Maine from Lower Canada, giving rife to many rivers which fall into St. Lawrence river, and others which fall into the Atlantic Ocean. The principal growth between the Height of Land and St. Francis river is beech, maple, birch, hemlock, and fir, very few white pines, and no oak of any fort. Some of the rivers have fine intervales.

HELENA ISLAND, ST. on the coaft of S. Carolina, with the continent on the north, forms St. Helena Sound or En trance, and gives name to a parish in Beaufort diftrict.

HELENA PARISH, ST. in Beaufort diftrict, S. Carolina, confifts of a cluster of illands, on the S. W. fide of St. Helena Ifland, one of the largest of which is Port Royal. Adjacent to Port Royal are St. Helena, Ladies, Paris, and Hunting Iflands. The Hunting Iflands are 5 or 6 in number, bordering on the ocean, to called from the number of deet and other game found upon them. All theie islands, and fome others of lefs note | and Cape May the N. E. fide, a8 miles

Northamptons Mothof the lands were | belong to this parify The produce of the iflands is rice, indigo, cotton, corn, and fweet potatoes ; the cultivation of which, as well as in other parts of the State, is entirely carried on by flaves. Taxes paid by St. Helena parifh 1,1441. 138. ad. Chief town, Beaufort, on Port

Royal Ifland. HELENA ST. a town on the coaft of Florida, built by the Spaniards, and

burnt by Sir Francis Drake in 1585. HELL GATE, this celebrated frait is near the weft end of Long Illand Sound, oppofite to Harlern in York Illand, and about 8 miles north-eaft of New-York city, and is remarkable for its whirl-pools, which make a tremendous roaring at certain times of the tide. Then whirlpools are occasioned by the narrowness and crookedness of the patfage, and a bed of rocks which extend quite acrofs it; and not by the meeting of the tides from east to welt, as has been conjectured, becaufe they meet at Frog's Point, feveral miles above. A fkilful pilot may conduct a fhip of any burden, with fafety, through this firait, at high water with the tide, or at low water with a fair wind. There is a tradition among the Indians, that in fome diftant period, in former times, their anceftors could ftep from rock to rock, and crois this arm of the fea on foot to Hell Gate.

HEMLOCK, a lake in New-York State, 12 miles long, and 1 broad, in the Geneffee country.

HEMPFIELD, the name of two townthips in Pennfylvania, the one in Lancafter county, the other in that of Weftmoreland.

HENDERSON'S GRANT, a tract 15 miles square, on the peninsula formed by the junction of Green river with the Ohio, in the State of Kentucky.

HENLEY HOUSE, a flation of the Hudion's Bay Company, on the north bank of Albany river, in New S. Wales, 150 miles S. W. of Albany Fort, and 110. N. W. by W. of Bruniwick Houfe. N. lat. 51. 14. 27. W. long. 85. 5. 54.

HENNIKER, a township in Hillsborough county, New-Hampshire; about 12 miles welt of Concord. In 1775, it contained 367, and in 1790, 1127 inhabitants.

HENLOPEN, CAPE, forms the S. W. fide of the entrance of Delaware Bay, P'a apart. 228

apart. Cape Henlopen lies in N. lat. 8. 50. and in W. long. 75. 26. There is a light-house here, a few miles below the town of Lewis, of an octagon form, handfomely built of ftone 115 feet high, and its foundation is nearly as much above the level of the fea. The lantern is between 7 and 8 feet fquare, lighted with 8 lamps, and may be feen in the night 10 leagues off at fea. Its annual expense is about £.650. There is a ftrong iron net-work, in order to prevent birds from breaking the glafs at night. Yet fo attractive is the light to the winged tribe, that fhortly after its erection, 110 birds of different kinds were found dead one morning, and a duck, in particular flew against it with fuch force, as to penetrate through both the wire and glais, and was found dead in the lantern. Since the above accident, few fimilar ones have occurred, and the birds have become more wary. Veffels off the Delaware, upon difplaying a jack at the foretopmast-head, will be immediately furnished with a pilot. None, however, are to be depended upon, unle's they are furnished with branches, and with a certificate from the board of wardens of Philadelphia.

HENRICO, a county of Virginia, about 30 miles long, and 7 broad, contains 12000 inhabitants, including 5819 flaves. It is furrounded by Hanover, Charles City, and Goochland counties, and James river. A number of coal mines are in the county, and pits have been opened by many of the proprietors, and worked to confiderable profit. The coals in feveral of the pits are found nearly 200 feet above the level of the river, and 3 or 4 feet below the furface of the ground. It is fuppofed that 500,000 buthels might be raifed from one of these in a year. Chief town, Richmond.

HENRIQUELLE, a remarkable faltpond in the Spanish part of the island of St. Domingo, about 22 leagues in circuit. It is inhabited by lizards and alligators, and land tortoises, all of a large fize. The water is deep, clear, buter and falt, and has a difagreeable fanell. Near the middle of this pond is an island about 2 leagues long, and a league wide, in which is a spring of fresh water, well stocked with cabrines, and thence called *Cabrito island*. This pond is about 11 leagues E. of Port au Prince.

HENRY, a cape, the north-eaftern extremity of Princels Ann county, in Virginia, 12 miles S. by W. of Cape Charles in Northampton county. These capes form the entrance of Chelapeak Bay. Cape Henry lies in N. lat. 37. W. long, 76. 16.

HENRY, a fort in Penn(ylvania, 3 miles N. by W. of Myer's Town, at the head of Tulpehocken creek, 32 N. of Lancafter, and nearly 37 S. E. of Sunbury. HENRY, a mountainous and hilly county of Virginia, bounded N. by Franklin, S. and S.E. by Patrick, S.W. by Grifon, and N. W. and W. by Montgomery. It is about 40 miles long, 15 broad, and contains 6928 inhabitants, including 1551 flaves. HENTIONITAN, an ifland in the N.

E. part of Lake Huron.

HERKEMER, a new county of New-York, divided into 20 townships, viz. German Flats, Warren, Frankfort, and Litchfield, formed out of German flate in Feb. 1796. Herkemer, Fairfield and Norway, formed out of Fairfield, Feb. 1796.—Schuyler. The following were comprehended originally in Whiteflown, viz. Paris, Sangerfield, Hamilton, Sherburn, Brookfield, Cazenovia, Weftmoreland, Mexico, Rome, Steuben and Floyd. By the flate centus of 1796 this county contains 25,573 inhabitants, of whom 4161 are electors. It is bounded N. by part of Lower Canada and the river St. Lawrence, N. W. by the E. end of Lake Ontario, and the river St. Lawrence; S. by Otfego county; E. by Clinton and part of Washington county.

HERKEMER TOWN, in the above county, is fituated on the north fide of Mohawk river. The township includes the village called Little German Flats, and the celebrated plain called German Flats. The village contains a courthoufe, gaol, a Dutch church, and about 40 dwelling houfes, which laft are very indifferent buildings. It is 80 miles N.W. by W. of Albany, 16 S.E. of old Fort Schuyler, and 20 in a like direction from Whiteftown. In the midft of the flats is a fhrub oak plain of 80 or 100 acres, barren and ftoney, of no use but for building lots. The township is named in honour of general Herkemer, who was mortally wounded in the late war. It contained in 1796, by the State cenfus.

cenfus were e He Cham Chitte contair in leng HER lake, Vermon try, an 14 mile ous fma illand and oth bluifh g pearanc lops, a vicinity commo a marle HER bile, in Palcago and from on the H N. lat. HERE Chefape of Anna the fifh HER Sanducic HERT diffrict. the State E. by Cl ton, and whom 2 Wynton. HERT rolina, in of Gates/ of Perqui 20 houfes is 18 mile N. N. E. W. of Su HERVI covered if ed by Cap 18. W. lo HEVE, cape on Here the was taken of men 17 HIATST county, N south reib

hip includes rman Flats, led German n's a courthurch, and which laft zs. It is So my, 16 S.E. o in a likedi-In the midft plain of 80 toney, of no The township

al Herkemer, d in the late by the State cenfus, HIA

cenfus, 2073 inhabitants ; of whom 338 were electors.

HERO, NORTH, an island in Lake Champlain, is a township annexed to Chittenden county in Vermont, and contains 129 inhabitants. It is 13 miles in length; and 2 in breadth.

HERO, SOUTH, an island in the fame lake, belonging to Chittenden county, Vermont, is a township and port of entry, and contains 537 inhabitants. It is 14 miles long, and 31 broad. Numerous fmall ifles furround the Heros. This island produces good crops of wheat and other grain. In it is a quarry of bluish grey marble, which has the ap-pearance of being a petrifaction of scallops, a ipecies of fhell common in the vicinity of the lake, together with the common earth of the fhore, which is of a marley fubftance.

HERON, PASS AU, at the bay of Mobile, in W. Florida, is 18 miles E. of Pafcagoula river, and has 4 feet water; and from thence to the point which is on the E. fide of the Bay of Mobile, in N. lat. 30. 17. is nearly 6 miles.

HERRING BAY, lies on the W. fide of Chefapeak Bay, Maryland, 26 miles S. of Annapolis, and derives its name from the fifh of its name which frequent it. HERRING POND INDIANS. See Sandwich.

HERTFORD, a county of Edenton diffrict, N. Carolina; bounded N. by the State of Virginia, S. by Bertie co. E. by Chowan, and W. by Northampton, and contains 5828 inhabitants, of whom 2442 are flaves. Chief town, Wynton.

HERTFORD, 'a post-town of N. Carolina, in Edenton diffrict, and capital of Gates/county, fituated on the W. fide of Perquimin's river. It contains about so houfes, a court-houfe, and gaol, and is 18 miles N. N. E. of Edenton, 208 N. N. E. of Wilmington, and 38 S. by W. of Suffolk in Virginia,

HERVEY's ISLE, one of the new difcovered islands, in the South Sea, vilited by Capt. Cook in 1778. S. lat. 19. 18. W. long. 159. 6.

HEVE, or La Haive, a port and cape on the S. coaft of Nova-Scotia. Here the French built a fort, which was taken by the British with some loss of men 1712.

HIATSTOWN, a village in Middlefex county, New-Jerley ; 13 miles N. eaftand rich

HIL

220

erly of Trenton, and 17 S. by W. of New-Brunfwick.

HICKMAN's, a settlement in Fayette county, Kentucky, on the N. fide of Kentucky river, 10 miles N. of Danville, and 2's S, of Lexington.

HID ISLAND is fituated on the N.W. Territory; in Plein river, the northern head water of the Illinois.

HIGHGATE, a village in Georgia, bout 4 miles from Savannah. See Hampflead.

HIGHGATE, the north-westernmost township except Alburgh, in Vermont, in Franklin county, contains 103 inhabitants.

HIGHLANDS, a mountainous tract of country on the banks of Hudion's river. in the State of New-York, between 40 and 60 miles N. of New-York city. The paffage on the river through these highlands, for the diffance of about 18 miles, is grand and romantic in a high degree. The opening feems to have been formed on purpose for the passage of this noble river. In these highlands are fituated the important and famous fortrefies of Weft Point, Fort Montgomery, and Stoney Point. The most noted peaks are, as you afcend the river, Thunder Hill, St. Anthony's Noie, Sugar Loaf, Butter Hill, and Break Neck Hill. After paffing the two last, the country opens delightfully, and prefents to the eye the pleafant villages of New-Windfor and Newburgh. These mountains abound with iron ore.

HIGHWASSEE. See Highwaffee Riven.

HIGUEY, or Alta Gracia, a city in the S.E. part of the Spanish division of St. Domingo, the eafternmost of all the fettlements in the ifland, cerebrated formerly for its fertility, and the quantity of fugar it produced. It was formerly the feat of Cayacoa, the most powerful cacique of the ifland. It has now only about 500 inhabitants, and is diffant about 40 leagues to the eastward of St. Domingo, between which and Higuey are 3 roads, the circuitous and northernmost of which leads by Bayaguana. N. lat. 18. 30.

HILLS, a river in New South Wales, which rifes from Pathapoowinepee Lake, and empties into Hudion's Bay at York Fort.

HILLSDALE, a township in Columbia county, New York', 18 miles from Hud-P 3 fon

fon city, containing 4556 inhabitants, including 31 flaves. By the State cenfus of 1796, 622 of the inhabitants are electors.

HILLSBOROUGH, an ifland on the Labrador coaft, on a bay at the head of which is Nain. See Nain.

HILLSPORDUCH, a county of New-Hampfhire, bounded N. by Grafton county, S. by the State of Maffachufetts, W. by Chefhire, and E. by Rockingham county.

It is divided into 37 townships and 4 gores of land, which contain 32,874 inhabitants, all free people, who chiefly follow agriculture. The academy at Amherit, has £ 800 funds, and another at New-Ipswich of £.1000, Chief towns, Amherit and Hopkinton.

HILLSBOROUGH, a township in the above county, fituated on the north rn head branches of Contocook river, about \$8 or 20 miles W. of Concord, was incorporated in 1772, and contains 798 inhabitants.

HILLSBOROUGH, a township in Somerset county, New-Jersey, containing soor inhabitants, including 386 flaves. It is about 15 miles W, of Brunswick, and 18 northerly of Trenton.

HILLSBOROUGH, a village on the eastern fide of Chefapeak Bay, in Caroline county, Maryland; feated on the E. fide of Tuckahock Creek, one of the chief branches of Choptank river, 7 miles S. E. by E. of Denton, 9 N. W. of Green(borough, and 27 S. S. W. of Chefter.

HILLSBONDUGH, one of the middle diftricts of North Carolina, bounded N. by the State of Virginia, S. by Fayetteville diffrict, E. by Halifax, and W. by Salifbury. It comprehends the counties of Granville, Perfon, Cafwell, Orange, Wake, Chatham, and Randolph; and contains 59,983 inhabitants, of whom 13,506 are flaves. Chief town, Hillfborough.

HILLSBOROUGH, a poft-town of North-Carolina, and capital of the diftrict of its name, is fituated in Orange county, on the N fide of Eno river, in a high, healthy and fertile country. It contains about 80 houfes, a court-houfe and gaol; and had in 1788 an academy of 60 of 80 fludents, patronized by the principal gentlemen of the State. The Eno emites with Little and Flat tivers, and forms the Neus, about 17

miles below the town. It is a somiles W. N. W. of Newbern, 26 S. by W. of Perfor court-houfe, 103 W. by S. of Halifax, 110 E.N.E. of Salifbury, and 452 S. W. by S. of Philadelphia.

HILLSDALE, a township in Columbia county, New-York, having Claverack on the W. and Great-Barrington in Berkshire county, Maffachusetts, on the E. It contains 4556 inhabitants, of whom 31 are flaves.

HILLTOWN, a finall town near the centre of Chetter county, Pennfylvania; 28 miles W. of Philadelphia, and 21 N. W. of Chefter. Alfo the name of a township in Bucks county in the fame State.

HILTON HEAD is the moft fouthern fea land in S. Carolina. W. and S. W., of Hilton Head lie Pinckney's, Bulls, Dawfufkies and fome fimaller iflands, between which and Hilton Head, are Calibogie river and found, which form the outlet of May and New rivers.

HILTON'S POINT, in Pifcataquariwer, in New-Hamphire, is the foot where the united fiream of Newichawannock and Cochechorivers, which comes from Dover, meets the weftern branch and forms the Pifcataqua: From thence to the fea is 7 miles, the courfe generally S. to S.E. and the river is fo rapid that it never freezes.

HINCHE, a territory and town in the Spanish part of St. Domingo. The canton of Hinche is bounded W. by the French parishes of Gonaives, Petit Riviere and Mirebalais—and contains with tome appendages about 12,000 fouls. The town contains about 500 houfes, and, together with its dependencies, 4,500 fouls, 500 of whom are capable of bearing arms. It is situated on the E., fide of the mouth of the river Guayamuco, 64 miles N. W. of St. Domingo, N. lat. 19. 3.

HINESBURGH, a township in Chittenden county, in Vermont, lies E. of and joins Charlotte on Lake Champlain. It contains 454 inhabitants.

HINGHAM, a post-town in Suffolk county, Massachuletts, fituated on a small bay which fets up fouth from Boston Bay. It contains a number of houses compactly built, two Congregational churches, and a well endowed school, called, in honour of its principal donor and founder, Derby School. It is 19 miles S. E. of Boston, and 22 in a like direction

s a somiles 6 S. by W. W. by S. of ifbury, and phia. in Columring Clave--Rarrington chufetts, on abitants, of

wn near the nnfylvania; a, and 21 N. name of a in the fame

noft fouthern , and S. W. iey's, Bulls, iller iflands, n Head, are which form r rivers. ataquariver, : fpot owhere ichawannock h comes from branch and rom thence to rife generally fo rapid that

d town in the mingo. The ed W. by the s, Petit Rivicontains with 12,000 fouls. t 500 houfes, dependencies, are capable of ated on the E. river Guaya-f St. Domin-

thip in Chitnt, lies E. of ce Champlain. its.

wn in Suffolk nated on a fmall from Bofton nber of houses Congregational adowed fchool, principal donor. pol. It is 19 nd az in a like direction

HOB

direction from Plymouth. The town- | and Fort Lee, about 7 miles above New fhip is about 4 miles fquare, confifts of two parifhes, was incorporated in 1635, and contains 2085 inhabitants. Here are 6 grift-mills, 3 faw-mills, and a fulling-mill; four of which are tide mills. Two hills in this town, one of which is called Baker's Hill, prefent extensive and delightful prospects of Bolton Bay Bofton Bay, its islands, and the adjacent country.

HINSDALE, the S. eafternmoft townthip in Vermont, and in Windham co. It contains 482 inhabitants.

HINSDALE, a township in Cheshire county, New-Hampfhire, on the east bank of Connecticut river, where the fouth line of the State firikes the river in 42. 43. 59. N. lat. and is opposite to Hinfdale in Vermont. It was incorporated in 1753, and contains 522 inhabitants. It is about 38 miles above Northampton, and 114 from Portfmouth.

HIRAM, a fmall fettlement in York county, Maine. See New Andover. HISPANIOLA, or St. Domingo. See St. Domingo.

HITCHELAGA, or Hochelaga, an Indian village in Lower Canada, fituated in the ifland of Montreal, and at the foot of the mountain fo called. It is fortified after the Indian manner, and the inhabitants fpeak the Huron language.

HITTEN, a fmall village in Ann Arundel county, Maryland, 13 miles W. by S. of Baltimore.

HIWASSEE is the only river of any confequence which empties into the Tenneffee from the fouth. It is a bold river, paffing through the Cherokee towns, and empties into the Tenneffee about 40 miles helow the mouth of the Clinch, and 46 above the Whirl or Suck, by land, but 60 by water. It is navigable till it penetrates the mountains on its S. fide. Ore was found in these mountains, when in poffession of the British, from which gold was extracted. The Indians know the fpot; but are very anxious to keep it a fecret. A branch of the Hiwaffee, called Amoia, almost interlocks a branch of the Mobile. The portage between them is thort, and the road firm and level.

HOBBSHOLE. See Tappabaunock. HOBOKEN, a tract of land in Bergen county, New-Jerfey, fituated on the W. bank of the Hudson, in the mountainous HOL

York city.

HOCHELAGA, the ancient name of the river St. Lawrence.

HOCKHOCKING, a river in the north-weft Territory, about twenty-eight miles below the Mufkingum, which it refembles, but is inferior to it in fize. It rifes near a branch of the Sciota, and taking a fouth-weft courfe enters the Ohio at Bellpree, in N. lat. 38. 57. It is navigable for large flat-bottomed boats, between 70 and 80 miles; has fine meadows with high banks, which are feldom overflowed, and rich uplands on its borders. On the banks of this fine river are inex-hauftible quarries of free flore, large beds of iron ore, rich mines of lead, and coal pits. There are also productive falt fprings, beds of white and blue clay of an excellent quality. Red bole, and many other useful foffils have been found on the banks of this river.

HOCKQUAR, or Hockquart, an ifland of Upper-Canada, on the E. fide of Lake Superior.

Hoo, an island on the E. fide of Lake Champlain, in Franklin county, Vermont, 9 miles long, and generally about a broad.

Hoc, an ifland in Naraganfet Bay, in the State of Rhode Ifland, about a miles in circumference, 2 miles from Briftol.

HOGOHEGE, CALLANANCO, and CHEROKEE; names formerly applied to Tenneffee river.

HOLDEN, a township in Worcester county, Maffachufetts, was formerly the north-western part of Worcester, from which it is diftant 7 miles, and 52 miles W. of Bofton. It contains 1050 inhabitants. It was incorporated in 1740. In the earthquake in 1755, there were feveral acres of land, in an obfcure place in the N. E. corner of the townthip, quite furrounded by a visible fracture in the earth, of a circular form, and of various width and depth. The fmall river there had its bed raifed fo as to occasion a confiderable fall of water, where there was little or none before. The flump of a tree, that flood directly over the chaim, on the E. was divided into two equal parts, one flanding on the outfide of the chaim, the other upon the infide ; but not opposite sountry between the town of Bergen to each other; the half within the chaim

chaim, being carried five feet forward, towards the river.

HOLDERNESS, a township in Grafton county, New-Hampshire, situated on the eastern fide of Pemigewasset river, was incorporated in 1761, and contains 329 inhabitants. A corner of Squam Lake is in this township; and Rattlefnake Mountain lies partly in this and Sandwich the adjoining township on the N. E. It is 64 miles N. N. W. of Portsmouth.

HOLD-WITH-HOPE, the first land difcovered by Hudson on the eastern coast of Greenland, in 1607. N. lat. 73. HOLE-IN-THE-WALL, a village in Talbot county, Maryland, on the E. fide of Chelapeak Bay; 7 miles easterly of Oxford, and a like distance S. of Easton.

HOLLAND, a township in Hampshire county, Maffachusetts, which, until incorporated in 1785, was the E. parish of South-Brimsfield, and is bounded S. by Tolland county, in Connecticut, E. by Worcester county, and northward by Brimsfield. It contains 428 inhabitants and is 75 miles S. W. by W. of Boston.

HOLLAND Company Lands, are fituated in Pennfylvania, on the navigable waters of Alleghany river and French Creek.

HOLLAND'S Iflands' are near to, and fouth of Hooper's Ifland and Straits in Chefapeak Bay.

HOLLAND'S Point, on the weft fide of Chefapeak Bay, together with Parker's Ifland, form the mouth of Herring Bay.

HOLLIS, the Nifulfet of the Indians, a township in Hilfborough county, New-Hampshire, fituated on the Maffachufetts line, incorporated in 1746, and contains 1441 inhabitants. It is about 70 miles S. W. of Portsmouth, and 45 N. W. of Boston.

HOLLIDAYS Ifland lies 15 miles up Chowan river in North-Carolina: thus far the river is three miles wide.

HOLLISTON, the moft fouthern townfhip in Middlefex county, Maffachufetts, has Hopkinton on the N. Wrentham on the E. and is 24 miles S. by W. of Bolton. The first fettlements were made here in 1710, and in 1724 the town was incorporated by its prefent name, in honour of Thomas Hollis of London, one of the patrons of Cambridge University; and it now contains 875 inhabitants.

HOLSTON, the largeft branch of Tenneffee river, rifes in Virginia, and joins that river 22 miles below Knoxville. It is a large, bold river, upwards of 300 yards wide at that town, is about 200 miles in length, and receives in its courfe feveral confiderable rivers, viz. from its head downwards, Watauga, French Broad, (which includes Limeftone . Creek, Nolachucky, Swanano, Big Laurel, and Big and Little Pigeon) and Little rivers. The ftreams on the northern fide are creeks of no great fize or length of courfe. Holfton is navigable for boats of 25 tons upwards of 100 miles, as high as the mouth of the North Fork; at which place Mr. David Rofs has erected iron works upon a large icale. At the mouth of this river, on the north fide, ftands Fort Grainger. The river is 150 yards wide, 16 miles above the North Fork at Rofs's iron works, and nearly 5 above Long-Ifland, and in N. lat. 36, 27. W. long. 83. 8. See Tenneffee and Long-Ifland.

HOLSTON, a fettlement on the river above mentioned, in the State of Tenneffee, containing 28,649 inhabitants, though in the year 1775 it had hardly 2200; yet its importance during the revolution may be conceived, when it is known that a great part of thofe volunteer troops who attacked and defeated the British and tories on King's Mountain, who were commanded by Colonel Ferguion, came from this country.

The land is generally fertile, but the face of the country is much broken. Placed between two large mountains, it feldom fuffers for want of rain. It. abounds with iron ore. A capital furnace and forge have lately been erected in Holston near the Virginia line, a bloomery below the mouth of Watawga, and another 25 miles above the mouth of the French Broad, There are fundry lead mines in the fettlement, one in particular on the French Broad, that produces 75 per cent. pure lead. Long Island on Holfton river is 340 miles S. W. by W, of Richmond in Virginia.

HOLY ROOD, a bay and pond in Newfoundland Ifland. The bay is at the head of Conception Bay.

HOMER, a military township in Onondaga county, New-York, on the head waters

waters go rive tors. Ho in Ge Pearl fouther Manca from it river. Hot which ras. was the fouthw the Spa carry a HON the iflar vannah. HON Spain, the Nor on the Shore or Guatim on the v long and honey, in partic ver mine the Nile is good, low gro bears In vineyard diately a again; a before (chief tow thop refic and very is ftrong claim th have been wood trai ing large the Moli this prov with the their cou vices. I forts in 1 the Mofq HOND of the No. land of C S. W. by

of Tennd joins ville. It s of 300 out 200 ts courfe from its French imeftone . Big Lauand Lite northt fize or avigable of 100 ie North vid Rofs a large iver, on rainger. 16 miles is's iron 5-Ifland, . 83. 8. he river of Tenibitants, hardly ring the hen it is le volundefeated s Moun-Colonel try. but the broken. tains, it ain. It. vital furn erected line, a Watawyove the There tlement. 1 Broad, ure lead. is 340 nond in pond in ay is at in Ononthe head

waters

waters of the N. W. branch of Chenengo river; 56 of its inhabitants are electors.

HONA CHITTO, a river which rifes in Georgia, in N. lat. 32. between Pearl and Loofa Chitto rivers, runs foutherly 125 miles, and at the town of Manca in Weft Florida, a few miles from its mouth, runs W. to Miffifippi river. N. lat. 30. 25.

HONDO, RIO, a river of Yucatan, which empties into the bay of Honduras. This river, by the peace of 1783, was the northern boundary of the tract fouthward of Balleffe river, granted by the Spaniards to the British, to cut and carry away logwood.

HONDE, a bay on the north fide of the island of Cuba, westward of the Havannah.

HONDURAS, a province of New Spain, having the bay of its name and the North Sea on the north; Yucatan on the north-weft; and the Mofquito Shore on the north-eaft; Nicaragua and Guatimala on the fouth, and Vera Paz on the welt. It is about 100 leagues long and 80 broad. It abounds with honey, cotton, fine wool, dye woods in particular, and has fome gold and filver mines. The rivers overflow like the Nile, and enrich the land. The air is good, except near the lagoons and low grounds. The foil in many parts bears Indian corn thrice a year; and the vineyards bear twice a year; for immediately after the vintage they cut them again; and the fecond grapes are ripe before Chriftmas. Valladolid is the chief town, where the governor and bi-fhop refide. Truxillo is also a fine town, and very strong by nature; and Omoah is ftrongly fortified. The Spanlards claim this country; but the English have been long in poffeffion of the log-wood tract in the Bay of Honduras, cuting large quantities of it every year. And the Molquito Indians to the east of this province have entered into treaties with the English, received them into their country, and done them feveral fervices. Befides, the Spaniards have no forts in this bay, or in the country of the Mosquitos, only two forall towns.

HONDURAS, SEA OF, is that part of the North Sea bounded N. by the Ifland of Cuba, S. by the Molquito Shore, S. W. by the bay of Honduras, W. by the peninfula of Yucatan, N. W. by the gult of Mexico, E. N. E. by Jamaica, and the Caribbean Sea.

HONDURAS, BAY OF, noted for cutting of logwood, as that of Campeachy formerly was. It lies in the province of the fame name, and opens betwixt Cape Honduras in N. lat. 13. 30. and Cape Catoche, the easternmost point of Yucatan in N. lat. 21. 30. The diftance between these capes is 270 miles. The great lake of Nicaragua has an outlet into it by the river Anuzelos, or Angelos, only navigable by imall craft. In this bay are feveral finall iflands, particularly the Pearl Iflands, a little to the north, but the pearls fifhed up are not in fuch quantities as formerly, nor fo large. Sugar river alfo, a fmall river from Veraguas, falls into it. It has its name from the quantity of fugar works, with which the country abounds. The part of the country where the English cut their logwood is all a flat, and a great part of it a morals, with feveral lagoons, which are very often overflown. The cutters amount to 15 or 1600 men; but form no regular colony ; yet they choose a chief, who cannot have lefs authority, luxury, or emolument, or whole fubjects are more difobedient. The quantity of wood annually furnished by the bay has been valued at 20,000 tons. The English export only about 6,000; but the principal branch of the trade was lately carried on by the Dutch, whole annual clear profit used to amount to The bay is above 90,000l. fterling. sprinkled with an infinity of thoals, rocks and clusters of drowned illands, which abound with great numbers of green turtle. There are feveral channels between them, among which a thip thould not venture without an experienced pilot. The manati is frequently met with here, and that called the Jew-fifh, which is fomething like the cod, but thicker in proportion, and much better eating. They have very broad icales, and fome of them weigh 8olbs.

HONEYYOE, a lake in the Genneffee country in New York State, weftward of Canandargua Lake, 5 miles long and 3 broad.

HONOMINIES, a river in the N. W. Territory which runs S. S. eafterly into Puan Bay. Between the head of this river and Lake Superior is a flort portage. HOOD'S HOOD'S ISLAND, one of the Marquefas Illands in the South Sea, fo called by its diffeoverer Captain Cook. It lies in g. 26. S. lat. 5 or 6 leagues N. by W. of the eaft point of Dominica.

HOOK ISLAND. See Bombay Hook. HOOKSET FALLS, or Hook fet Ifle Falls in Merrimack river, just below the mouth of Suncook, 7 miles above Amufkerg Falls, and 3 miles below Concord, in New-Hampfhire.

HOOKSTOWS, a village on the weft fide of Chefapeak Bay in Maryland, in Baltimore county, 6 miles N, W. of the town of Baltimore.

HOOKTOWN, a village on the eaft fide of Chefapeak Bay, in Talbot county, Maryland, lies north of Eafton, and S. W. of Williamfburg, nearly 3 miles from each.

HOOPER'S ISLAND and STRAITS lie on the eaft fide of Chefapeak Bay. and on the S. W. coaft of Dorchefter county, Maryland. The ifland is 7 miles long, and 24 broad.

HOOSACK, a river of New-York which falls into the Hudfon from the saft, about 8 miles above the city of Lanfinburgh. It rifes in Berkfhire county, Maffachufetts, runs north-wefferly through Pownal in Vermont, thence into New-York State. Its length is about 40 miles. The curious mill fiream called Hudfon's Brook, which falls into a north branch of Hoofack, is defcribed in the account of Adams, in Maffachufetts.

HOPE, a village in Suffex county, New-Jeriey, on the poft-road from Newtown to Eafton in Pennfylvania, 16 miles S. W. of the former, and 20 N. E. of the latter. It is inhabited by about 100 of the Moravian United Brethren.

HOPE, a bay on the N. W. coaft of N. America, io named by Capt. Cook. The entrance of Nootka, or Si. George's Sound, is fituated in the east corner of Hope Bay, in N. lat. 49. 33. E. long. 33. 12.

Hope, a Moravian fettlement in Wachovia, in N. Carolina, in Surry county, where is a meeting-house of the United Brethren.

HOPE, a fmall island in Narraganset Bay, State of Rhode Island.

HOFKANS, or Hopkinfaille, a township in Caledonia county, in Vermont, was granted to Dr. Hopkins; 11 miles northwest of the upper bar of the Fisteen Mile Falls in Connecticut river.

HOR

HOFRINTON, a township in Hillsorough county, New-Hampshire, on Contoocook river, 9 miles S. W. from its confluence with the Merrimack, and divided from Concord on the east, by the Rockingham county line. It was first granted by Maffachufetts, was incorporated in 2765, and contains 1,715 inhabitants, who are chiefly farmers. It is 45 miles E. by S. of Charlestown on Connecticut river, and about 64 W, by N. of Portfimouth.

Wir

blu

this

Nev

nor

Ho

cou

dia

It l

Che

blo

the

Du

via

bot

this

Ha

Nev

faic

S.V

mer

Not

Ho

with

Rer

on

con

are

101

part

iflar

. I

Jeag

iflar

gin

mou

or a

Bay

leag

Nev

ing

dife

176

it,

æd.

Ifa

44.

H

H

F

ł

Ł

đ

1

1

HOPKINTON. a township in Middlefex county, Massachus It was incorporated in 1715, and contains 1317 inhabitants. The rivers Concord, Providence and Charles receive each of them a branch from this town : These streams furnish seats for 7 or 8 gristmills; a number of faw-mills, iron-works. &cc.

HOPRINTON, a township in Washington county, Rhode-Island, situated on the west line of the State, on several branches of Pawcatuck river. It contains 2462 inhabitants, including 7 flaves.

HOPEWELL, a township in Cumberland county, in the Province of New-Brunswick, fituated on Chepodie river, which runs easterly into a northern arm of the Bay of Fundy, and is navigable 4 or 5 miles.

HOPEWELL, the name of 3 townships in Pennsylvania, viz. in York, Huntingdon, and Washington counties.

HOPEWELL, a township in Hunterdon county, New-Jersey, fituated on Delaware river, 14 miles W. of Princetown, 31 above Trenton and 30 southwesseries of New-Brunswick. It contains 2320 inhabitants, including 233 flaves. Another township of this name lies in Cumberland county, in New-Jersey.

HORN, Cape, the fouthern extremity of Terra del Fuego, and of South-America, was first failed round in 1616, and the straits were discovered in 1643. S. lat. 55. 58. W. long. 67. 21.

HORN, an ifland on the coaft of Weft Florida, between Ship and Maffacre iflands. Horn ifland is nearly 17 miles long and about half a mile wide. There are more trees on the middle of the ifland than in any other part of it; and for about 2 miles from the caft end there are no trees at all; but there are a number of fandy hillocks.

HORN-TOWN, a village in Maryland, 31 miles from Snowhill, 26 from Druinmond.

#34

in Hillingire, on Con-V. from its ck, and dieaft, by the It was firft as incorpo-715 inhabners. It is W. by N.

in Middle-It was inntains 1317 ncord, Proach of them hefe ftreams ills; a nums. &c. in Washingfituated on , on feveral er. It conling 7 flaves. in Cumberce of Newpodie river, orthern arm is navigable

3 townships ork, Huntunties. in Hunterfituated on 1. of Princekl 30 fouthk. It concluding 233 of this name y, in New-

rn extremity South-Amen 1616, and in 1643. S. LZ.

oaft of West nd Maffacre arly 17 miles wide. There iddle of the rt of it; and eaft end there e are a num-

n Maryland, from Druinmond.

HOU

mond, or Accomack court-houle, in Wirginia, and 168 from Philadelphia. HORSENECK-FIELD-POINT, a round bluff on the coaft of Greenwich townthip in Connecticut. 2 miles E. of the New-York line at Byram river.

HORSENECK, a point of land, on the north fide of Long-Ifland, between Hog's Neck and Eafton's Neck.

HORSENECK, a town in Fairfield county, Connecticut, called by the In-dians Pai bom fing, was fettled in 1680. It lies 6 miles N. E. of Rye, in Weft-Chefter county, New-York State. A bloody battle was fought here between the Dutch and the Indians, in 1646. The Dutch with great difficulty obtained the victory. Great numbers were flain on both fides; and their graves appear to this day. It is 53 miles 3. W. of New-Haven, and 37 N.E. of New-York city. HORSENECK, a village in Effex co. New-Jerley, on the fouthern bank of Paffaic river above the Little Falls, 4 miles S.W. by S. of the town of Patterion.

HORSHAM, a township in Montgo-mery county, Pennsylvania.

HORTON, a township in King's co. Nova-Scotia.' Salmon river runs thro' Horton, and fupplies the inhabitants with excellent falmon.

HOSACK, or Hoofack, a township in Rensfelaer county, New-York, fituated on the eastern boundary of the State, contains 3035 inhabitants, 419 of whom are electors.

HOTTE, a mountain in the western part of the fouthern peninfula of the ifland of St. Domingo.

HOT SPRING. See Virginia.

HOUGUE, LA, a little fort fituated a leagues beyond the Havannah, in the ifland of Cuba. From hence veffels begin to discover La Pain de Matance, a mountain whole top refembles an oven or a loaf. It ferves failors to know the Bay of Matance by, which is about 14 leagues from the Havannah.

HOWE, Fort, on St. John's river in New-Brunswick, is capable of containing too men.

HOWE's Island, in the South Sea, was difcovered by Captain Wallis, July 30, 1767. Smoke was feen to arife from it, but no inhabitants could be difcerned. S. lat. 16. 46. W. long. 154. 8. HOUAHEINE, one of the Society

Islands, in the South Sea. S. lat, 16. 44. W. long. 151. 1.

HOWLAND's Ferry, is the narrow part of the waters that feparate Rhode-Island from the main land. It is about a quarter of a mile wide. The bridge built acrofs this firait coft 30,000 dollars, and was carried away by a form in January, 1796. It is rebuilt.

HOUSATONICK, a river of Connec. ticut, in the Indian language fignifying over the mountain, rifes by two fources; the one in Lanefborough, the other in Windfor, both in Berkshire county, Mafiachufetts., Thefe branches form a junction near Salifbury, and the river after paffing through a number of towns, empties atfelf into Long-Island Sound, between Stratford and Milford in Connecticut. It is navigable about 1 2 miles. to Derby. A bar of fhells, however, at its mouth, obstructs the navigation of large veffels. In this river, between Salifbury and Canaan, is a cataract, where the water of the whole river, which is 150 yards wide, falls perpendicularly 60 feet.

HOUSE OF THE DEVIL. See Lake Ontario.

HOUAKILA, a name by fome applied to the N. E. branch of Illinois river. See Theakiki.

HUBBARDSTON, a township in Worcefter county, Maffachuletts, and formed the N. E. quarter of Rutland, until incorporated in 1767. It borders on the weftern part of Wachufet Hill, and contains 933 inhabitants. It is 20 miles N. W. of Worcefter, and 60 W. of Bofton.

HUBBARDTON, a small river rifing in the N. part of this township, noticeable only for its 5 falls which furnish excellent mill-feats.

HUBBERTON, a township in Rutland county, Vermont. It contains 404 inhabitants, and lies so miles N. of Bennington.

HUDSON'S BAY took its name from Henry Hudson, who discovered it in 1610. It lies between 55 and 65 degrees of N. latitude. The eaftern boundary of the Bay is Terra de Labrador; the northern part has a ftraight coaft, facing the bay, guarded with a line of illes innumerable. A vaft bay, called the Archiwinnipy Sea, lies within it, and opens into Hudfon's Bay, by means of Gulf Hazard, through which the Beluga whales pafs in great numbers. The entrance of the bay from the Atlantic

lantic Ocean, after leaving, to the N. Cape Farewell and Davis's Straits, is between Refolution Ifles on the north, and Button's Iffes, on the Labrador coaft, to the fouth, forming the eaftern extremity of Hudson's Straits. The coafts are very high, rocky and rugged at top; in fome places precipitous, but fometimes exhibit extensive beaches. The islands of Salisbury, Nottingham, and Digges are very lotty and naked. The depth of water in the middle of the bay is 140 fathoms. From Cape Churchill to the fouth end of the bay, are regular foundings; near the fhore, fhallow, with muddy or fandy bottom. To the northward of Churchill, the foundings are irregular, the bottom rocky, and in fome parts the rocks appear above the furface at low water. Hudfon's Bay is reckoned about 300 leagues wide, from north to fouth. Its breadth is unequal, being about 130 leagues where broadeft; but it grows narrower at both extremities, being not much above 35 leagues in fome places. In the account of New-Britain, we have given a general account of the Hudfon's Bay Companies fettlements on both fides of James's Bay. The commerce in the countries adjacent to this inland fea is in the hands of an exclusive British Company of its name, who employ only four fhips, and \$30 feamen. The forts, Prince of Wates, Churchill river, Nelfon, New Severn, and Albany, are garrifoned by 186 men. The French, in 1782, took and deftroyed these fettlements, &c. faid to amount to the value of f 500,000 fterling. The Company's exports are to the amount of f. 16,000, mostly the drugs of the market, which produce returns, chieffy in beaver fkins and rich furs, to the value of £.29,000 ; yielding government a clear revenue of 6.3734. This includes the fifthery in Hudfon's Bay. The fkins and furs procured by this trade, when manutactured, afford articles for trading with many nations of Europe to great advantage.

HUDSON'S STRAIT, or Frobifier's, Miflaken Strait, which leads into Hudfon's Bay, in a wefterly courfe is 76 miles wide, between Cape Chidley and the S. point of Refolution Ifland.

HUDSON'S HOUSE, one of the Hudfon's Bay Company's factories in N. America, lies on the S. W. fide of Sufkafhawan river, 100 miles eaft of Manchefter Houfe, and 167 S. E. by E. of Buckingham Houfe. N. lat 53. 0. 32. W. long, 106. 27. 20.

HUDSON RIVER paffes its whole courfe in the State of New-York, and is one of the largest and finest rivers in the United States. It rifes in a mountainous country, between the lakes Ontario and Champlain. In its course foutheasterly it approaches within 6 or 8 miles of lake George ; then, after a thort courfe E, turns foutherly, and receives the Sacondaga from the S. W. which heads in the neighbourhood of Mohawk river. The course of the river thence to New-York, where it empties into York Bay, is very uniformly S. 12. or 15 W. Its whole length is about 250 miles. From Albany to lake George is 65 miles. This diffance, the river is navigable only for batteaux, and has two portages, occafioned by falls, of half a mile each. The banks of Hudfon's river, especially on the western fide, as far as the highlands extend, are chiefly rocky cliffs. The paffage thro? the highlands, which is 16 or 18 miles, affords a wild romantic scene. In this narrow pais, on each fide of which the mountains tower to a great height, the wind, if there be any, is collected and comprefied, and blows continually as through a bellows; veffels, in paffing through it are often obliged to lower their fails. The bed of this river, which is deep and fmooth to an altonishing diftance, through a hilly, rocky country, and even through ridges of fome of the highest mountains in the United States, must undoubtedly have been produced by fome mighty convultion in uzture. The tide flows a few miles above Albany, which is 160 miles from New-York. It is navigable for floops of 80 tons to Albany, and for thips to Hudfon. Ship navigation to Albany is interrupted by a number of iflands, and thoals 6 or 8 miles below the city, called the Overflaugh. It has been in contemplation to confine the river to one channel, by which means it will be deepened, and the difficulty of approaching Albany with veffels of a larger fize, be removed. About 60 miles above New-York the water becomes fresh. The river is flored with a variety of fifh, which renders a fummer paffage to Albany, delightful and amufing to those whe

who tages fur ti lakes for a happy farms a cert the I New. of Ph the pi to ma tent o hence with driver done i duce o ket b parad vantag ral de of the branch increal veyed northe pleted to the HU river el Dorche Point, mouth Hu poft-to New-Y river 3 132 110 limits o mile, a try ext of 1781 kins, fi Rhodefpot, v town, t veffels o into la river, a adventu tions, **Iquares** croffing Each fo divided 50 feet In the f

of Manby E. of 3. 0. 32. whole k, and is rivers in iountain-Ontario le fouth-6 or 8 er a thort receives '. which Mohawk er thence ties into . 12. OF out 2 50 Jeorge is river is and has falls, of of Hudweftern end, are ge thro? 8 miles, In this hich the ght; the ted and nally as paffing to lower r, which onifhing y counfome of United een pron in uaes above m News of 80 o Hudly is inds, and ty, callin conr to one be deepoaching fize, be ve New-The of fifh, to Al-

o thefe whe ·HUD

who are fond of angling. The advantages of this river for carrying on the fur trade with Canada, by means of the lakes, are very great. Its conveniences for internal commerce are fingularly happy. The produce of the remotest farms is eafily and fpeedily conveyed to a certain and profitable market, and at the lowest expense. In this respect, New-York has greatly the advantage of Philadelphia. A great proportion of the produce of Penntylvania, is carried to market in waggons, over a great extent of country, fome of which is rough ; hence it is that Philadelphia is crowded with waggons, carts, horfes and their drivers, to do the fame business that is done in New-York, where all the produce of the country is brought to mar-ket by water, with much lefs fhew and parade. But Philadelphia has other advantages, to compensate for this natural defect. The increasing population of the fertile lands upon the northern branches of the Hudson, must annually increase the amazing wealth that is conveyed by its waters to New York. The northern and weftern canals, when completed will be of incalculable advantage to the trade of this State.

HUDSON'S RIVER, a broad but fhort river emptying into Chefapeak Bay, in Dorchefter county, Maryland. Hill's Point, N. E. of it, fhapes the broad mouth of the river.

HUDSON CITY, a port of entry and post-town, fituated in Columbia county, New-York, on the east nide of Hudson's river 30 miles S. by E. of Albany, and 132 north of New-York city. The limits of the corporation include a fquare mile, and its privileges as a port of entry extend no farther. In the autumn of 1783, Meffrs. Seth and Thomas Jenkins, from Providence, in the State of Rhode-Illand, fixed on the unfettled fpot, whereon this city stands, for a town, to which the city is navigable for veffels of any fize. The city is laid out into large squares, bordering on the river, and divided into 30 lots. Other adventurers were admitted to proportions, and the town was laid out in fquares, formed by fpacious ftreets, croffing each other at right angles, Each iquare contains 30 lots, two deep, divided by a 20 feet alley. Each lot is 50 feet in front, and 120 feet in depth. In the fpring of 1784, feveral houfes and

1.5.26

fores were erected. The increase of the town from this period to the spring of 1786, two years only, was aftonithingly rapid, and reflects great honour upon the enterprising and perfevering fpirit of the original founders. In the space of time just mentioned no lefs than 1 50 dwelling-houfes befides fhops, barns and other buildings, four ware-houles, feveral wharves, fpermaceti works, a covered rope-walk, and one of the beft diftilleries in America, were erected, and 1,500 fouls collected on a fpot, which three years before, was improved as a farm, and but two years before began to be built. Its increals fince has been very rapid; a printing-office has been effablished, and feveral public buildings have been creeted, be-fides dwelling houfes, ftores, &c. The inhabitants are plentifully, and conve-niently fupplied with water, brought to their cellars in wooden pipes, from a fpring two miles from the town. It has a large bay to the fouthward, and ftands on an eminence from which are extensive and delightful views to the N. W. N. and round that way to the S. E. confifting of hills and vallies, variegated with woods and orchards, corn-fields and meadows, with the river, which is in most places a mile over. and may be feen a confiderable diffance to the northward, forming a number of bays and creeks. From the S. E. to the S.W. the city is fcreened with hills, at different distances, and west afar off over the river and a large valley, the profpect is bounded by a chain of flupendous mountains, called the Katts Kill, running to the W. N. W. which add magnificence and fublimity to the. whole scene. Upwards of 1200 fleighs entered the city daily, for feveral days together, in February, 1786, loaded with grain of various kinds, boards thingles, staves, hoops, iron ware, stone for building, fire-wood, and fundry articles of provision for the market, from which fome idea may be formed of the advantage of its fituation, with respect to the country adjacent, which is every way extensive and fertile, particularly west-ward. The original proprietors of Hudson, offered to purchase a tract of land adjoining the south part of the city of Albany, and were configured, by a refutal of the propolition, to become competitors for the commerce of the northern northern country, when otherwife they would have added great wealth and confequence to Albany. There is a bank here, called Bank of Columbia, whole capital may not exceed r60,000 dollars. It is composed of 400 shares, at 400 dollars each. Hudson city is governed by a mayor, recorder, 4 aldermen, 4 affitants, and a number of other officers. The number of inhabitants in Hudson Torumsbip, by the census of 1790, amounted to 2,584, including 193 flaves; and it appears by the State census of 1796 that 338 of the inhabitants are electors. Hudson city is 4 miles S. W. of Claverack; 47 north of Poughkeepsie; and 43 south of Laminburg.

HUGHESBURG, a town in Northumberland county, Pennfylvania, called alfo *Cataweffy*, being fituated at the mouth of Cataweffy creek, 25 miles N. E. of Sunbury. It contains about 60 handfome houses, and a meeting-house for Friends. It is 144 miles N. W. of Philadelphia. N. lat. 40. 54-

HULL, an inconfiderable town in Suffolk county, on the fouth fide of Bofton harbour, Maffachufetts, containing 120 inhabitants. On the fort on the eaft hill there is a well funk 90 feet, which commonly has 80 odd feet of water.

HUMAS, an Indian village on the east fide of Miffifippi river in Louisiana, 60 miles above New-Orleans. The Humas were formerly a confiderable nation, but about 1770 were reduced to about 25 warriors. The Alabamas, whofe villages are near those of the Humas, had, at the above period, about 30 warriors, and followed the French here when they abandoned the post on Alabama river in 1762. The Chetimachas have about 27 warriors.

HUMBER, a river of Newfoundland Island, which empties into the gulf of St. Lawrence through the bay of Islands.

HUMMEL'S TOWN, a thriving town in Dauphine county, Pennfylvania, containing a German Lutheran church and about 90 houfes; fituated on the fouth fide of Swetara creek, 6 miles north of Middletown, 10 E. by N. of Harrifburg, and 100 weft north-weft of Philadelphia.

HUNGERFORD, a township in Frankfin county, Vermont, containing 40 inhabitants, 7 miles south of the Canada line and 14 east of Lake Champlain.

HUNGER CREEK, a fream which ear-

HUN

ries the various water machinery, in the new and thriving manufacturing town of Hamilton, between Albany and Schenectady, New-York.

HUNTER, FORT, 21 miles weft of Schenectady, on the fouth fide of Mohawk river, at the mouth of Schohary" Creek, over which a bridge is about to be built. Here is an old church built in the reign of Queen Ann, and 3 or 4: houses. At this place was the Old Mohawk town, which was abandoned by that nation as late as the fpring of 1780. These Indians had made confiderable advances in civilization-could generally fpeak the English language, and num-bers of them made profession of their faith in the Christian religion. In the church which is now flanding, they ufed' to attend public worfhip in the Epifcopal form. Thefe Indians are now fettled, a part of them on Grand river, a northern water of Lake Erie, and a part of them in another part of Upper Canada. None of this nation now remain in the United States. The father of the only remaining family was drowned in 1788.

HUNTERDON County, in New-Jerfey, is bounded N. by that of Morris, E. by Somerfet, S. E. by Burlington, S. W. and W. by Delaware river, which feparates it from the State of Pennfylvania, and N. W. by Suffex county. It is about 40 miles long, and 32 broad, is divided into 10 townships, and contains 20,253 inhabitants, including 1,301 flaves. On the top of Mufkonetcong mountain in this county, is a noted medicinal fpring, much reforted to. It iffues from the fide of a mountain into an artificial refervoir, for the accomodation of those who wish to bathe in, as well as to drink, the waters. It is a ftrong chalybeate. Trenton is the chief town.

HUNTERSTOWN, a village of Pennfylvania, fituated in York county, 25 miles W. by S. of York-Town.

HUNTING-CREEK, in Virginia, runs east into Patowmack river, at the fourth corner of the territory of Columbia.

HUNTING-CREEK-TOWN, a village in the northern part of Dorchefter county, Maryland; 14 miles N. N. W. of Vienna, 16 S. by W. of Denton, and 18 N. E. of Cambridge.

HUNTINGDON, College: See Georgia. HUNTINGDON, an extensive and mountainous

mounta bounde county, by Fra and So land. broad : land, d contain iron or furnace confide iron, ; have a turing don. HU above fide of of Star the me 90 hou is abou Town, delphia Ĥυ north (fituate county found, byteris 38 mil It is o cut, an thefe, Hu county HU field from 1 ford ri Hu welt fi land, ing Cr N. by E. N. Hu lin cou on the ants. Hu Caroli 16 fro Ηu ty, Ne ants ; 245 1 tains ;

s weft of

e of Mo-Schohary about to rch built nd 3 or 4 Old Mondoned by onfiderable d generaland numn of their In the 1. they used' he Epifcoe now fetnd river, a and a part Upper Can now re-The father was drown-

lew-Jerfey, rris, E. by ton, S. W. which fepannfylvania, nty. It is a broad, is nd contains ling 1,301 ufkonetcong a noted meto. It ifitain into an accomodabathe in, as rs. It is a is the chief

ge of Penncounty, 25 'own. irginia, runs at the fouth olumbia. vn, a village thefter connl. N. W. of nton, and 18

see Georgia. tenfive and mountainous HUR

mountainous county in Pennfylvania, bounded N. and N. W. by Lycoming county, E. and N. E. by Mifflin, S. E. by Franklin, S. and S. W. by Bedford and Somerfet, and weft by Weffmoreland, It is about 75 miles long and 39 broad; contains 1,432,960 acres of land, divided into 7 townships, which contain 7,565 inhabitants. Limeflone, iron ore and lead are found here. A furnace and two forges manufacture confiderable quantities of pig and bar iron, and hollow ware; large works have alfo been eftablished for manufacturing of lead. Chief town, Huntingdop.

HUNTINGDON, the capital of the above county, fituated on the N. E. fide of Juniatta river, and at the mouth of Standing Stone creek, 50 miles from the mouth of Juniatta, contains about 90 houfes, a court-houfe, and gaol. It is about 23 miles W. S. W. of Lewis Town, and 184 W. N. W. of Philadelphia.

HUNTINGBON, a post-town on the north fide of Long Island, New-York, fituated at the head of a bay in Suffolk county, which fets up fouth from the found, contains about 70 houfes, a Prefbyterian and Episcopal church. It is 38 miles E. by N. of New-York city. It is opposite to Norwalk in Connecticut, and contains 3,260 inhabitants; of these, 552 are electors, 213 flaves.

HUNTINGDON, a township in York county, Pennsylvania.

HUNTINGTON, a township in Fairfield county, Connecticut, separated from Derby on the north-cast by Stratford river.

HUNTING-TOWN, a village on the west fide of Chefapeak bay in Maryland, fituated on the S. E. fide of Hunting Creek, in Calvert county, 3 miles N. by W. of Prince Frederick, and 22 E. N. E. of Port Tobacco.

HUNTSBURG, a township in Franklin county, in Vermont. It is fituated on the Canada line, having 46 inhabitants.

HUNTSVILLE, a post-town in North-Carolina, 10 miles from Bethania, and 16 from Rockford.

HURBRY, a township in Ulfter county, New-York, containing \$47 inhabitants; of whom 116 are electors, and 245 flaves. The compact part contains about 30 houses, fituated on Ele-

pus Kill, about 5 miles from the well bank of Hudfon's river, and not norths of New-York. The lands around it are low and fertile, but infetted with wild onions.

HURON, one of the five principal northern lakes. It lies between 43. 30. and 47. 30. N. lat. and between 80. 45. and 84. 45. W. long. and is reckoned to be upwards of rooo miles in circur ference. The fifth are of the fame kind as in Lake Superior, and it communicates with that lake through the firaits of St. Marie on the N. W. with Michie an on the W. and with Erie on the S. It is of a triangular fhape, and on the S. W. part is Saguinum or Sagana bay, 80 miles in length, and about 18 or 20 in breadth; the other most remarkable bay is Thunder Bay; which fee-alfo fee Manataulin Island, and Michillimakkinack. On the banks of the lake are found amazing quantities of fand cherries. The land bordering on the weftern fhore of the lake is greatly inferior in quality to that on Lake Erie. It is mixed with fand and fmall ftones, and is principally covered with pines, birch, and fome oaks; but a little distance from the lake the foil is very luxuriant. Twenty years ago, part of the Indian nations, called Chepaways and Ottawas, who inhabited round Saguinum, hay and on the banks of the lake could furnifie 200 warriors; and those of the latter nation, who lived on the E. fide of Lake Michigan, 21 miles from Michillimakkinack could furnish 200 warriors.

HURON, a finall river of the N. W. territory, which, after a courfe of 30 miles, falls into Lake St. Clair from the N. W. Gnadenhuetten lies on this river. Alfo the name of another finall river in the fame territory, which rung N. eaftward into lake Erie, 40 miles weftward of Cayahoga, and 15 S. E. of the mouth of Sandufky Lake.

HYANIS ROAD. See Barnftable, in Maffachufetts.

HYDE, a maritime county in Newbern diffrict, North Carolina; bounded E. by the ocean, W, by Beaufort coanty, N. by Tyrrel, and S. by Carterers It contains 4120 inhabitants, of whome 1048 are flaves.

HYCO-OTEE, or Hycee, a final river which empties into the Dan, about 4 miles above the mouth of Staunton river,

HYDESPARE,

hel in our raided

HYDESPARK, a township in Orleans county, in Vermont, containing 43 in-habitants. It is 5 miles S. of the Canada line, and a6 north by east of Bennington. real antima bit

itugers, one of the fire mineters!

ing her commend and it is an interest of the

AGO. See Jage, or Yage.

ALL CAR ENERGY A

IATA, a bay on the coalt of Chili. IBBERVILLE, a river or rather a fort of natural canal, of W. Florida, which, when the Miffifippi overflows, and is high enough to run into it, (which is generally in the months of May, June, and July) forms a communication for veffels drawing three or four feet, from the Miffifippi to the gulph of Mexico, eaftward, through the lakes Mauripas and Pontchartrain. This canal, which has been dignified with the name of river, is dry all the reft of the year. It is a mile below a village of Alabama Indians, 35 miles from the fettlements of Point Coupeé, 99 W. by N. of New-Orleans, 204 N. W. of the Balize, and 270 W. of Penfacola, by the above lakes. It receives the river Amit, or Amite, from the northward, which is navigable for batteaux to a confiderable diftance.

ICAQUE POINT, on the E. end of the ifland of St. Domingo, lat. 19. 9.

ICHUA-TOWN, in the Geneffee country in the State of New-York, is an Indian village at the mouth of Ichua Creek, a north-eaftern head water of Alleghany river. It is 60 miles eafterly of Fort Erie, 70 E. by S. of La Boeuf, and 67 S. W. by S. of Hartford on Geneffec river.

ICUNADA DE BARRUGAN, a town on e river La Plata, in S. America. See

luenes Ayres. ICY CAPE is the north-westernmost head land of N. America, fituated in the Northern ocean. Between this cape and Cape North in Afia, is the opening into Behring's Straits, which lead from the Northern into the Pacific occan.

IONACIO, ST. a town in the eaftern art of Peru, and on the N. fide of Aazon river.

IGORNACHOIX, a bay in the ifland Newfoundland, fouthward of St.

John's Bay. ILEIGNES, or St. Charles, a town n'the S. fide of the ifland of St, Do-Breas and

I-L-Let

mingo, and 200 fathoms from the city of St. Domingo. It is inhabited by emigrants from the Canary Iflands, and has a few freets which run from the four cardinal points, and cut each other at right angles. The initabitants are the most industrious people in the Spanifh part of the ifland

ILHEOS, a'captainfhip S. of that called Bay of All-Saints, and in the middle division of B azil. Chief town, Paya. Ilheos, the capital of the above province. ftands about to leagues N. E. of Porto Seguro, and as far S. W. of the Bay of All-Saints. It is watered by a river of the fame name, and contains about . 200 families. S. lat. 15. 40. W. lon. 34. 28.

ILLINOIS, a large navigable river of the N. W. Territory, formed by the confluence of the rivers Plein, and Theakiki, in 41. 48. N. lat. and in 88. 42. W. longitude. This noble branch of the Millifippi, after running a ferpentine S. W. courfe, through an extensive country of rich, fertile land, and receiving a vaft number of rivers from 20 to 100 yards wide, which are navigable for boats from 15 to 180 miles, approaches within 5 miles of the Miffifippi; from thence running eaftward about 12 miles. it pays its tribute by a mouth 400 yards wide, in 38. 40. N. lat. and in 91. 12. W. longitude; opposite the large cave, 176 miles above the Ohio and 18 above. the Miffouri. The lands on the banks of the Illinois, particularly those on the S. E. fide, are perhaps as fertile as any part of North-America. They produce in the most luxuriant plenty, wheat, rye, Indiau corn, peas, beans, flax, hemp, tobacco, hops, grapes, apples, pears, peaches, dying roots, medicinal plants, &c. Here alfo grow large forefts, of hickory, oak, cedar, mulberry trees, &c. Savannas, or natural meadows are both numerous and extensive. In the forefts are great variety of animals, as buffaloes, deer, &c. and in the rivers are plenty of fifh, particularly cat, carp, and perch, of an enormous fize. Such is the abundance of wild grapes in this country, that in the year 1769, the French planters upon this river made above 110 hhds. of ftrong wine, from thefe grapes. On the north-western fide of this river is a coal mine, which extends for half a mile along the middle of its banks, and about the fame diftance

fance ponds. feveral ftagnai the Fri from i munici Chicag Illinoi which whole I of The tance fi fite to 1 480 mil the Un Greenv miles fe the Illin at the O the fout lake is c is fituate fource of Salt Por miles bre ILLIN kia on th

IMPE America having ti and anoth vigable. neck of h 1600, it v a year's fi having 1 burnt the Soforno. Sancta Ci were taker fo confidei fought the fome mea they had c men. Th a town he fee. S. la INAGUA iflands in th of the iffand

INATTE Ifland of C ville, lies on of Arfacide

of the idan

INCAL, a river in S. / INDEPE:

m the city habited by flands, and n from the cach other pitants are m the Spa-

Ethat called the middle non, Paya. e province, E. of Porto the Bay of by a river tains about o. W. lon.

ble river of by the cond Theaki-88.42.W. nch of the ferpentine n extentive and receiv+ rom 20 to navigable , approachippi; from t 12 miles, 1 400 yards in 91. 12. large cave, d 18 above the banks hofe on the tile as any ey produce wheat, rye, lax, hemp, des, pears, inal plants, ge forefts, berry trees, meadows enfive. In of animals, a the rivers. cat, carp, fize. Such pes in this 1769, the river made wine, from rth-weftern ine, which the midle fame difIND

fance below the coal mine are two falt ponds, 100 yards in circumference, and feveral feet in depth. The water is ftagnant and of a yellowifh colour ; but the French and natives make a good falt from it. The Illinois furnishes a communication with lake Michigan, by Chicago river, between which and the Illinois are two portages, the length of which do not exceed 4 miles. The whole length of the river from the fource. of Theakiki, which is but a mort diftance from the river St. Joleph, oppofite to Fort St. Joseph on the north, is 480 miles. The Indians have ceded to the United States, by the treaty of Greenville, in 1794, a tract of land 12 miles fquare, at or near the mouth of the Illinois ; alfo a tract 6 miles fquare, at the Old Piarias fort and village near the fouth end of Illinois Lake. That lake is only a dilatation of the river, and is fituated about 240 miles below the fource of Theakiki, and 43 below the Salt Ponds. It is 20 miles long and 5 miles broad in the middle.

ILLINOIS Indians inhabit near Cahokia on the Miffifippi. Warriors 260.

IMPERIALE, a city of Chili in South-America, 6 leagues from the South Sea, having the river Cauten to the fouth and another river to the welt, both navigable. It is fituated on a rifing fleep neck of land, hard to be afcended. In 1600, it was taken by the Indians, after a year's fiege; most of the inhabitants having perifhed by famine. They barnt the town, and then laid fiege to Soforno. In this war Valdivia, Argol, Sancta Croz, Chilla, and Villa Rica were taken. After which they became fo confident of their strength, that they fought the Spaniards bravely, and in fome measure revenged the crucities they had committed upon their countrymen. The Spaniards afterwards built a town here called Conception ; which fee. S. lat. 38. 42. W. long. 73. 25.

INWOWN, Great and Little, two fmill islands in the Windward Paffige. N. W. of the island of St. Domiugo, and N. E. of the island of Caba.

INATTENDUE Island, (the Gower Island of Carteret) to named by Surville, lies of the north fide of the islands of Arfacides, 2°. 4'. east of Port Prassin. INCAI, a southern branch of Amazon

river in S. America.

INDEPENDENCE MOUNT, is fituated

on the firait through which the waters of Lake George and East Bay flow into Lake Champlain, in the N. W. part of the town of Orwell in Rutland county, Vermont, and oppofite to Ticonderoga.

INDIAN BAY lies on the weft fide of Bonavista Bay, in Newfoundland Island.

INDIAN OLD TOWN, a town in Lincoln county, in the District of Maine, fituated on an ifland in Penobleot river. just above the Great Falls, and about 60 below the Forks. Here are about 100 families, who are Roman Catholics, the remains of the Penoblcot tribe, and the only Indians who refide in the Diftrist of Maine. They live together in a regular fociety, and are increasing in number; the Sachems having laid an injunction on the young people to marry early. In a former war, this tribe had their lands taken from them ; but at the commencement of the American revolution, the Provincial Congress grants ed them a tract of land, 12 miles wide, interfected in the middle by the river. They have a right, in preference to any other tribe, to hunt and filh as far as the mouth of the bay of Penoblcot extends. In their town is a decent church with a bell ; and a prieft refides among them to administer the ordinances.

UNDIAN ORCHARD, a tract of land in Northampton county, Pennsylvania, on the W. fide of Delaware river, on the river Lexawacsein.

INDIANA, a territory in Virginia, lying between Ohio river and the Laurel Mountain, containing about 31 millions of acres. It is nearly of a triangular form, and extends in length from the Pennfylvania line to the waters of the Little Kanhaway. It was granted to Samuel Wharton, William Trent, and George Morgan, elquires, and a few other perfons, in the year 1768, by the Shawanefe, Delaware and Huron tribes of Indians, as a compensation for loss to the amount of 8 5,9161. ros. Sd. currency, which thefe people had fuftained by the depredations of the Indians, in the year 1767. It is a valuable tract of land; but the title of the proprietors, the' pronounced good by a Committee of Congress in 1782, is at prefent embarraffed in confequence of the revolution.

INDIANE, a small harbour in the ifland of Cape Breton.

INDIAN RIVER, or Cyprefs Swamp, lies partly in the States of Maryland and Q Delaware.

Sec. 1

Delaware. This morafs extends 6 miles from eaft to weft, and nearly 12 from north to fouth, including an area of nearly 50,000 acres of land. The whole of this fwamp is a high and level bafon, very wet, though undoubtedly the higheft land on that part of the coaft. Falfe Cape, at the mouth of Indian river, and the N. E. part of Cedar Neck is in 38. 35. 15. N. lat. and 114 miles fouth of the light-houfe at Cape Henlopen. Cedar Swamp contains a great variety of plants, trees, wild beafts, birds, and reptiles.

INDIAN RIVER, on the eaft coaft of the peninfula of E. Florida, rifes a flort diffance from the fea-boaft, and runs from north to fouth, forming a kind of inland paffage for many miles along the coaft. It is alfo called Rio Ays, and has on the north fide of its mouth the point El Palmer, on the fouth that of the Leech. N. lat. 27. 30. W. long. 80. 40.

INDIAN River, Diftriet of Maine, a finall arm of the fea, between Chandler's and Pleafant river.

INDIAN ISLAND. See Penobfcot River. INDIANS. The amount of Indian population, in America can only be gueffed at. The new discovered islands in the South Sea, and part of the N. W. coaft are probably the most populous. The beft informed have conjectured the number of aboriginal inhabitants, or Indians, in America, to be under two millions and a half. The decrease fince the difcovery of America, has been amazing: At that period, the ifland of Hilpaniola alone contained at leaft a million of inhabitants; Bartholomew de las Cafas estimated the number at three millions. Millions were buried in the mines or hunted to death by the Spaniards, both on the iflands and continent. In the northern parts of Ame. rica, numbers were doubtlefs deftroyed in forming the English, Dutch, and French colonies; but notwithftanding the ruptures between the colonifts and the Indians, very few comparatively perifhed by war. Famine, and its companion the peftilence, frequently deftroy whole tribes. The difeafes allo introduced by the Europeans, have made great havock; the fpiritous liquors in the use of which they have been initiat. ed by the whites, prove perhaps moft of all repugnant to population. They wafte as the Europeans advance; they

moulder away, and disappear. The most numerous tribes are at the greatest diftance from the fettlements of the whites, and it is very certain that in proportion to their diffance they are unacquainted with the use of fire-arms. All the nations north of lake Superior, and those beyond the Miffifippi, use only bows and arrows, to that when their feattered fituation is confidered, the various cultoms and fuperstitions which it/would be neceffary to reconcile, in order to produce unity of action, and what a fmall proportion of them have the apparatus, or understand the use of mulquetry, or poffels refources to enable them to carry on lafting hoftilities against the power of the United States, it must be obvious that even partial defeats of the federal troops will haften their ruin, notwithstanding the wonderful dexterity and intrepidity which they exhibited in feveral actions with the regular troops in the late war. But this neither is nor ought to be the wifh of the inhabitants of the United States; they ought to teach them the bleffings of peace, and curb the exorbitant luft of farther extent of territory.

A lift of Indian tribes, in Imlay's Hiftory of Kentucky, makes the aggregate number lefs than 60,000 who inhabit the country from the gulf of Mexico on both fides of the Mifflifippi, to the gulph of St. Lawrence, and as far welt as the country has been generally explored, that is, to the head water of the Mifflifippi, and from thence a good way up the Miffouri, and between that river and Santa Fe. To give any account of the nations farther fouth, far lefs in S. America, would be a tafk beyond all bounds; the chief of thefe are noticed under their refpective names:

The population of the Indian nations in the jouthern parts of the United States, fomewhat different from Imlay, is, according to Mr. Purcell, who refided among them in 1780, as follows:

- 17 J	hoos		Gun-mer	. Total.
Mufcogees, co called Cree	omm ks	only	5,860	17,280
Chactaws	-		4,131	13,423
Chickafaws		•	575	2,290
Cherokees	-		2,800	8,550
Catabaws	•	1	3 50	490
1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1			13,516	42,033 The

The in a fi eftabl white few in life, g reftlefi creafe checke ed and the ve mong Maj end to dians b conclud which the Ur The In the foll wares, Ottawa St. Joie Miamie. River Kaskaski and for Sandufk United S 2 to 12 1 polts in United (tribes ab lue of 20 deliver ir dollars a which ea feen in t nation or Little i

the interi In 1792, employ o from fou hitherto u ward. T westerly f he penetra ri, and fro 500 miles ocean. H in feveral l dians, all 1 ject, the p might exp to fea; a nearly by t fued in goin ii, Mr. Ste pear. The the greateft ints of the that in proy are unac--arms. All aperior, and i, ule only when their ared, the vaitions which reconcile, in action, and f them have d the use of ces to enable lities againft ates, it must l defeats of n their ruin, rful dexteriey exhibited egular troops neither is nor : inhabitante ey ought to peace, and farther ex-

> in Imlay's is the aggre-60,000 who the gulf of e Miffifippi, ence, and as ias been geto the head from thence and between To give any er fouth, far be a talk beof these are ve names : idian nations the United it from Im-Purcell, who 780, as fol-

-men. Total.

160	17,280
138	13,423
575	2,290
100	8,550
1 50	490
-	
516	42,033 The

IND

The above red nations have increased in a small degree fince the general peace eftablished among them in 1777. The whites incorporated among them are few in number, and lead a vagabond life, going from tribe to tribe as their reftlets disposition leads them. The increase of population is confiderably checked by the quantities of adulterated and poisonous spirituous liquors, and the venereal difference introduced among them by the whites.

Major-Gen. Anthony Wayne, put an end to the deftructive war with the Indians by a treaty of peace and friendship concluded at Greenville Aug. 3, 1795, which was ratified by the Prefident of the United States, Dec. 22, 1795, The Indian tribes figned the treaty in the following order: Wyandots, Delawares, Shawanoes, Ottawas, Chipawas, Ottawa, Patawatames of the river of St. Joleph, Patawatames of Huron, Miamies, Miamis and Eel River, Eel River tribe, Miamis, Kickapoos and Kaskaskias, Delawares of Sandusky, and tome of the Six Nations living at Sandufky. Thefe Indians ceded to the United States various tracts of land from 2 to 12 miles fquare near the different polts in the N. W. Territory. The United States delivered to the Indian tribes above named in goods to the value of 20,000 dollars; and agreed to deliver in goods to the value of 9,500 dollars annually, for ever. The portion which each tribe is to receive will be feen in the account of the particular nation or tribe.

Little is yet known of the Indians in the interior parts of North-America. In 1792, Mr. Stewart, faid to be in the employ of the British court, returned from four years travels through the hitherto unexplored regions to the weftward. Taking his courfe welt-fouthwesterly from the posts on the lakes, he penetrated to the head of the Miffouri, and from thence due W. to within 500 miles of the thores of the Pacific ocean. He joined the interior Indians in feveral battles against the fhore Indians, all which coming fhort of his object, the procuring a peace, fo that he might explore the continent from fea to fea; after fome ftay, he returned nearly by the fame route he had purfued in going out. Beyond the Miffouri, Mr. Stewart met with many power-

ful nations, in general hospitable and courteous. The Indian nations he vifited weftward, appeared to be a polified and civilized people, having towns regularly built, and being in a state of fociety not far removed from that of the Europeans, and only wanting the use of iron and steel to be perfectly for They are always clod in fkins cut in an elegant manner, and in many respects preferable to the garments in use among the whites. Adjacent to these nations is a vaft ridge of mountains, which may be called the Alleghany of the western parts of America, and ferves as a barrier against the too frequent incursions of the coaft Indians, who entertain a mortal antipathy to the nations and tribes. inhabiting the country eaftward of the mountains.

INDIAN-TOWN, in Maryland, a village fituated on Indian Creek, on the S. E. bank of Choptank river, and in Dorehefter county, 3 miles S. W. of New-market.

INDIAN-TOWN, a fmall post-town of N. Carolina, 10 miles from Sawyer's Ferry, and 52 from Edenton.

INDIES. See Weft-Indies.

INGRAHAM, Port, on the weffern fide of Washington Island, on the N. W. coast of N. America, is divided into two parts by Young Frederick's Island. It is a fine harbour for wintering in, being near the fea, and having deep water. N. lat. 52. 37. W. long. 133. 18.

INGRAHAM Ifles, in the South Pacific ocean, lie N. N. W. of the Marquefas Islands, from 35 to 50 leagues distant, and are 7 in number, viz. Ochoona, or Washington ; Wooapoo, or Adams ; Lincoln ; Noobeeva, or Federal ; Tatoo-e-tee, or Franklin; Hancock, and Knox. The names in Italic are those by which they are known to the natives. The others were given them by Captain Joseph Ingraham, of Boston in Maffachusetts, commander of the brigantine Hope of Bofton, who difcovered them on the 19th of April, 1791, a day remarkable in the annals of America, the revolutionary war having commenced on that day in 1775, and the first discoveries made under the flag of the United States marked its 16th anniverfary. There islands, lying between 8. 3. and 9. 24. S. lat. and between 140, 19, and 141. 18. W. long. from Greenwich, are moftly inhabited, and Q 2 appear

pear to be generally variegated with hills and vallies abounding with timber, and very pleasant. Nooheeroa, or Federal ifland, is represented by the natives to be the largest, most populous and productive of the whole; which, they fay, are to in number. The people refemble those of the Marquelas Islands; as do their canoes, which are carved at each end. Cotton of a superior quality grows here. The natives were friend-. Before Ingraham's difcovery was known, Captain Johah Roberts, of Bofton, failed in the ship Jefferion for the N. W. coaft, and likewife difcovered thefe islands. He gave them different names; but to avoid confusion the reader is referred to each island under the Indian name when it is known. As these iflands lie in that part of the Pacific Oeean, through which veffels from Europe or America, bound to the N. W. coalt, must pais, and are not far out of their usual track, they may be visited for refrefliment in cale of need. See Noobeewa, and Marquefas Iflands, &c.

IOW

INTRCHAR RIVER, or Caguela, the name of Orinoco river, at its fource in the mountains, weftward, between New Granada and Peru, not far from the South Sea.

INNA-QUITO, one of the fpacious plains upon the N. tide of Quito, in Peru. INSCUA RIVER, is laid down in fome maps as the north-weltern and main branch of St. Croix river, an eaftern water of the Millifippi, rifing in the 48th degree of north latitude.

INVERNESS, NEW, atown on the river Alatamaha, in Georgia, built by a company of emigrants from the Highlands of Scotland, 130 of whom were brought over by Gen. Oglethorpe in 1734. It is about 20 miles from Frederica. These fettlers prefented a most pathetic and prophetic remonstrance to Gen. Oglethorpe in January, 1738, against the introduction of flaves into the colony.

Iowa, a river of Louisiana, which runs fouth eastward into the Millifippi, in N. lat. 41. 5. 61 miles above the lowa Rapids, where on the E. fide of the river is the Lower Iowa Town, which so years ago could furnish 300 warriors. The Upper Iowa Town is about 15 miles below the mouth of the river, allo on the E. fide of the Millifippi, and could formerly furnish 400 wartiors. See Riviere du Moins. IRE

IPSWICH, the Agawam of the In. diane, is a post-town and port of entry on both fides of lpfwich river, in Effex county, Maffachutetts, 12 miles fouth of Newburyport, to north-eaft of Beverly, 32 N. E. by N. of Bofton, and about a mile from the fea. The township of Ipfwich is divided into g parifhes, and contains for houses, and 4502 inhabitants. There is an excellent ftone bridge acrois Ipfwich river, composed of two arches, with one folid pier in the bed of the river, which connects the two parts of the town, executed under the direction of the late Hon. Judge Choate. This was heretofore a place of much more confideration than at prefent. Its decline is attributed to a barred harbour and fhoals in the river. Its natural fituation is pleafant, and on all accounts exceedingly well calculated to be a large manufacturing town. The supreme judicial court, the courts of common pleas and feffions are held here once a year, on the rit Tuesday of April; and from its central fituation, it appears to be the most convenient place for all the courts and public offices of the county. The inhabitants are chiefly farmers, except those in the compact part of the townfhip. A few vefiels are employed in the filhery, and a few trade to the West Indies. Silk and thread lace, of an elegant texture, are manufactured here by women and children, in large quantities, and fold for use and exportation in Boston, and other mercantile towns. In 1790, no lefs than 41,979 yards were made here, and the manufacture is rather increasing. Ipiwich township was incorporated in 1634, and is 378 miles N. E. of Philadelphia. N. lat. 42. 43. long. 70. 50.

IPSWICH, NEW, a township in Hillfborough county, New-Hampshire, containing 1241 inhabitants, fituated on the welf fide of Souheagan river, and separated from Whatohook Mountain by the north line of Maffachusetts, 56 miles N. W. of Boston, and about 77 west of Portsmouth. It was incorporated in 1762, and has in it a shourishing academy.

IRASBURG, a township in Orleans county, in Vermont, fituated on Black river, 17 miles N. of Hazen Block-houseand 12 S. of the Canada line.

IREDELL COUNTY, in Salifbury diftrict, N. Carolina, is furrounded by Surry, Rowan, and Burke. The climate is agreeable

fully rich. 858 a poft-o and 2 IRI in the extend about narrov 146. 3 The in is cove pigeon and N. wich, miralty by Ca tracks 1616, 0 gainvit IROI village St. Dor IRON E. fide (of the O IRON Porto B miral V 1739. de todo IRON Ge Runa fide of th Walker' IRON State of 7 Tenneffe 6. W. to range has and beyo Iron Mot feems to to the wh boundary fee, and th tends from Kanhawa try, to th nates nea The cav mountain IROQU IROQU FRYIN of the Neu ISABEL

n'eea

e climate is a-

greeable

ISA

greeable and healthy; the lands beauti-fully variegated with hills, and the foil is rich. It contains 5435 inhabs. of whom 8 58 are flaves. At Iredell court-house is a poft-office. It is 25 miles from Salifbury, and 15 from Charlotte court-houfe.

IRELAND, NEW, a long narrow ifland in the Pacific ocean, N. of New Britain, extending from the N. W. to the S. E. about 270 miles, and in general very narrow ; between 3. and 5. S. lat. and 146. 30. and 151. E. long. from Paris. The inhabitants are negroes. The illand is covered with wood, and abounds with pigeons, parrots, and other birds. Weft and N. W. of New Ireland, lie Sandwich, Portland, New Hanover, and Admiralty Islands, differented and named by Captain Carteret, in 1767. The tracks of Le Maire and Schouten in 1616, of Roggewin in 1722, and of Bougainville in 1768, pais thefe iflands.

IROIS, POINTE DE, or Irifb Point, a village on the W. end of the island of St. Domingo.

IRON BANKS, a tract of land on the E. fide of the Miffifippi, below the mouth of the Ohio.

IRON-CASTLE, one of the forts of Porto Bello, in S. America, which Admiral Vernon took and deftroyed in 1739. The Spaniards call it St. Philip de todo Fierra.

IRONDEQUAT, called in fome maps Ge Rundegut, a gulf or bay on the S. fide of the Lake Ontario, 4 miles E. of Walker's at the mouth of Genefice river.

IRON MOUNTAINS, GREAT, in the State of Tenneffee, extend from the river Tenneffee to that of French Broad from 6. W. to N. E. ; farther to the N.E. the range has the name of Bald Mountain, and beyond the Nolachucky, that of Iron Mountains. The Iron Mountains, feems to be the name generally applied to the whole range. It conftitutes the boundary between the State of Tenneffee, and that of North-Carolina, and extends from near the lead mines, on the Kanhaway, through the Cherokee country, to the fouth of Chota, and terminates near the fources of the Mobile. The caverns and cafcades in thefe mountains are innumerable.

IROQUOIS. See Six Nations.

IROQUOIS River. See Sorrel. ERVIN River is a weffern head water of the Neus, in N. Carolina.

ISABEL, ST. one of the Mands of

ISC

Solomon, 200 miles in circumference in the Pacific Ocean, 7. 30. S. lat about 160 leagues W. of Lima, discovered by Mendana, 1567, whofe inhabitants are cannibals, and worfhip ferpents, toads, and other animals. Their complexion is bronze, their hair woolly,' and they wear no covering but round the wailt. The people are divided into tribes, and are constantly at war with each other. Bats were teen here, which from one extremity of their wings to the other, meafived 5 feet. Dampier, who has the reputation of exactness, fays that he faw, in the finall ifland of Sabuda, on the W. coaft of Papua, bats as large as young rabbits, having wings 4 feet in extent from one tip to the other.

ISABELLA River. See Ozama. ISABELLA Point, lies on the N. fide of the ifland of St. Domingo, and forms the N. E. fide of the bay of its name. N. lat. 19. 59 10. This is the port where Columbus formed the first Spawith fettlement on the ifland, and named both it and the point after his patronels Queen Habelia. He entered it in the night, driven by a tempelt. It is overlooked by a very high mountain flat at the top, and furrounded with rocks, but is a little expoled to the N. W. wind. The river Itabella which falls into it, is confiderable. There are 14 fathoms of water to anchor in. The fettlement was begun in 1493, was given up in 1496, when its inhabitants were carried to the city of St. Domingo, which originally was called New Mabella. The bay is faid to have good anchorage for thins of war. It is about 29 leagues eaft by north of Cape Franceis, measuring in a straight line,

Isca, or rather Ica, with Pifco and Nalca, three towns from which a jurifdiction of Lima in Peru, S. America, has its name. Great quantities of wine are made here and exported to Calao. It a fo produces excellent olives, either for eating or for oil. The fields which are watered by trenches, yield an uncommon plenty of wheat, maize, and fruits. This jurifdiction is remarkable for lpacious woods of carob trees, with the truit of which the inhabitants feed numbers of affes, for the uses of agriculture, to this and the neighbouring jurifdictions. The Indians who live near the fea apply themfelves to fifting, and after falting the fifb carry them to a good Q3 market

market in the towns among the mountains.

246

ISLANDS, Bay of, on the fouth coaft of Nova-Scotia.

ISLE OF WIGHT, a county of Virginia, on the fouth fide of James's river, weft of Norfolk county, being about 40 miles long and 15 broad, and contains 9,028 inhabitants, including 3,867 flaves. A mineral fpring has been difcovered near the head of the weft branch of Nanfemond river, about 10 miles from Smithfield, and 12 from Suffolk. It is much seforted to, and famed for its medicinal qualities.

ISLE ROYAL, on the north-weft fide of Lake Superior, lies within the territory of the United States north-weft of the Ohio, is about 100 miles long, and many places about 40 broad. The satives fuppofe that this and the other islands in the lake are the refidence of the Great Spirit.

ISLESBOROUGH, a township in Hancock county, Maine, formed by Long-Island, in the centre of Penobscot Bay, 15 miles in length, and from 2 to 3 in breadth. It was incorporated in 1789, contains 382 inhabitants, and is 260 miles N. E. by N. of Boston.

ISLES DE MADAME lie at the fouth end of Sydney, or Cape Breton Island, on which they are dependant. The largeft of these, with Cape Canso, the east point of Nova-Scotia, form the entrance of the Gut of Canso from the Atlantic ocean. See Cape Breton.

ISLIP, a township of New-York, situated in Suffolk co. Long-Island, east of Huntington, and contains 609 inhabitants; of these 93 are electors, and 35 slaves.

IWANEE, a little town near St. Jago de Cuba, where a finall remnant of the ancient Indians live, who have adopted the manners and language of the Spaniards.

J

JACKSON's *River*, a head water of James's river in Virginia, rifes in the Warm Spring Mountains, about 20 miles fouth-weft of the Warm Spring Mountains, and runs fouth-weft through the valley until Carpenter's creek joins it from that quarter, when the river affumes the name of Fluvanna, and flows fouth eaft. About three-quarters of a mile from its fource it falls over a rock

200 feet into the valley below. The fheet of water is broken in its breadth by the rock in two or three places, but not in its height. Between the fheet and the rock at the bottom you may walk acrofs dry. It is near half as high again as Niagara, but is only 12 or 15 feet wide.

JACKSON, a new county of Georgia.

JACKSONSBOROUGH, a finall polttown of South-Carolina, on the east fide of Edifto river, about 35 miles weft of Charleftown.

JACMEL, a jurifdiction and fea-port town on the fouth lide of the illand of St. Domingo. This jurifdiction, in the French part of the island, contains 3 parifhes, is remarkable for the goodnefs of its foil, and the abundant crops of coffee; and is fusceptible of a great augmentation. Its exports from January 1, 1789 to Dec. 31, of the fame year, were 27,350 lb. white fugar ; 55,624 lb. brown ingar; 4,072,702 lb. of coffee; 406,832lb. cotton, and 10,046lb. indigo. The duties on exportation of the above amounted to 15,619 dollars, 26 cents. The town is fituated on the fouth fide of the neck of the fouth peninfula. The town is 6 leagues weftward of Cayes de Jacmel, 71 east of the bay and town of Baynet, as far fouth of Leogane on the north fide of the peninfula, 13 fouth-weft of Port au Prince, and 53 east of Cape Tiburon. N. lat. 18. 21. W. long. from Paris 75. 2.

JACMEL, CAYES DE, a town and parifh on the eaft fide of the fiream of its name, 6 leagues eaft of the above town of Jacmel. This parifh is bounded eaft by the plain on the Spanish part, at the foot of the mountains of Bahoruco, 80 leagues square, fit for any kind of cultivation. On the neighbouring mountains coffee would fucceed well.

JACOB'S CREEK, an eaftern water of Youghiogany river in Weftmoreland county, Pennfylvania. There is a carrying p ace 6 miles weft to Monongahela river, from the Youghiogany, opposite the mouth of this creek.

JADAGHQUE. See Chataughque.

JAFFREY, a township in Cheshire county, New Hampshire, on the fouth fide of the Great Monadnock, 6 miles north of the Massachusetts line, 19 east of Connecticut river, and about 56 W. S. W. of Portsmouth. It was incorporated in 1773, and contains 1,235 inhabitants. Here are found red and yellow ochre. ochre, great q anthes Hampi cine, is Monad

JAG

Chiame faid ril empties by a m feet dee JAGO which r Peru. country JAGO ble town with a s and a ro large be the nece Cordille Mapoch to W. the inhal

ants accc ries on a Ayres, 1 Althougi are amid the Cord cheaper t by fea. long. 69.

Spaniard

JAGO Guatimal. JAGO ern coaft

good hart

a bay, ai name. I the ifland well fortil ward paffa ing aipect of its for noble, fafe rior to the tion. Wi very, is a road from are a grea various fiz ferve for c

a cathedra and had on moved to low. The breadth by s, but not in eet and the walk acrofs h again as s feet wide. f Georgia. fmall pofthe eatr fide iles weft of

nd fea-port e ifland of ion, in the contains 3 he goodnefs rops of cofgreat augm January fame year, 55,624 lb. of coffee ; 6lb. indigo, f the above 26 cents. iouth fide of fula. The of Cayes de nd town of rane on the 3 fouth-weft ift of Cape . long. from

> town and e stream of f the above h is boundpanifh part, of Bahorur any kind eighbouring eed well. ern water of eftmoreland re is a carry-Ionongahela ny, opposite

rughque. in Chefhire in the fouth ck, 6 miles ne, 19 eaft out 56 W. vas incorpo-,235 inhabiand yellow ochre, IAG

ochre, allum, vitriol, and black lead in great quantities. The buck-bean (menyanthes) faid to be a rare plant in New-Hampshire, and of fingular use in medicine, is found at Jaffrey, near the Great Monadnock.

JAGO, ST. a river in the province of Chiametlan, in New Spain, which it is faid rifes in the lake Guadalajara, and empties into the North Pacific Ocean, by a mouth half a mile broad, and io feet deep attlow water.

IAGO, ST. a large river of S. America, which rifes in the audience of Quito, in Peru. It is navigable, waters a fertile country, and falls into the South Sea.

JAGO, ST. a handfome and confiderable town of S. America, capital of Chili, with a good harbour, and a bifhop's fee, and a royal audience. It is feated on a large beautiful plain, abounding in all the neceffaries of life, at the foot of the Cordillera de los Andes, on the river Mapocho, which runs acrofs it from E. to W. It is fubject to earthquakes, and the inhabitants are native Americans and Spaniards. It contains 40,000 inhabitants according to Abbé Raynal, and carries on a confiderable trade with Buenos Ayres, by land, 354 leagues diftant. Although above 40 leagues of the way are amidst the mows and precipices of the Cordilleras, yet it is found fafer and cheaper to fend goods by this road than by fea. See Chili. S. lat. 33. 40. W. long. 69. 35.

JAGO DE GUATIMALA, ST. See Guatimala.

IAGO DE CUBA, a town on the fouthern coaft of the ifland of Cuba, with a good harbour, feated at the bottom of a bay, and on the river of the fame name. It was formerly the capital of the ifland, and was built in 1514, is well fortified, and commands the windward paffage. This place has a declining afpect, and prefents only the ruins of its former greatnefs. Yet it has a noble, fafe, and commodious port, inferior to the Havannah only in its fituation. Within 3 leagues of it, at Covery, is a rich copper mine. In the road from St. Jago to St. Salvadore are a great quantity of flint-flones, of various fizes, fo round that they might ferve for cannon bullets. St. Jago has a cathedral with canons refidentiary, and had once a good trade, but it is removed to the Havannah, where its

bishop also refides. Sir Francis Drake took and burnt this city in 1585. It is about 22 leagues to the eaftward of the Copper Hills, 12 or 13 weft of Cumberland harbour, and 41 S. 6 W. of the eaft end of the ifland of Jamaica. N. lat. 20. 15. W. long. 76. 40.

JAGO DE LEON, ST. a town of Venezuela, a province of Terra Firma, in S. America, 18 miles from the fea-coaft, and fituated on a plain, amongst high mountains extremely difficult of accels. It was taken by the English in 15995 but afterwards reftored to Spain.

JAGO DE NEXAPHA, ST. a town of Guaxaca, in the aud.ence of Mexico, fituated in the valley of Nexapha, on a river which falls into the river Alvarado. It has a rich convent of Dominicans.

JAGO DEL ESTERO, ST. a town of S. America, one of the most confiderable of Tucuman, and the refidence of the inquifitor of the province, and is a bishop's fee. It is fituated on the banks of the Dolee, which is here pretty large and navigable for veffels of burden. It is 160 leagues eaft of Potofi. S. lat. 24. 40. W. long. 64. 55. JAGO DE LAS VALLES, ST. 2 town

of N. America, in the audience of Mexico, feated on a plain, on the river Pa-nuco. N. lat. 23. W. long. 71. 10.

JAGO DE LA VEGA, or Spanifs Town, is the capital of the ifland of Jamaica ; fituated in Middlefex county, on the banks of the river Cobre, about 6 miles from the fea, and contains between 5 and 600 houfes, and about 5,000 inhabitants, including people of colour. It is the refidence of the governor or commander in chief, whom is accommodated with a fuperb palace. Here the legiflature is convened, and the court of chancery, and the fupreme court of judicature are held. It was greatly damaged by a ftorm in 1772. It lies in the S. E. part of the island, about 7 miles N. W. of Port-Paffage, on the bay of Port-Royal. N. lat. 18. 6. W. long. 76. 49.

JAGO, ST. in the island of St. Domingo. See Yago.

JAMAICA, a township in Windham county, Vermont, watered by feveral branches of Weft river, and containing 263 inhabitants.

JAMAICA, a post and chief town of Queen's county, New-York, in the weft part of Long-Ifland, and contains a Prefbyterian, an Episcopalian, and a Dutch Q4

Dutch church, an academy, and nearly zoo dwelling-houfes. It is 12 miles eath of New-York city. The whole townthip contains 1,657 inhabitants, of whom 237 are electors, 222 flaves.

JAMAICA, an ifland fituated in the Atlantic ocean, about 4000 miles S. W. of Great-Britain, and forms one of the most valuable appendages to that crown. It is 30 leagues E. of the island of St. Domingo ; about the fame diffance N. of the ifland of Cuba; having the gulf of Honduras on the W, and Carthagena on the continent of S. America to the S. diftant 145 leagues. The centre of Jamaica lies in about 18. 12. N. lat. and about 76.45. W. long. from London. It is 1 50 miles in length, and on a medium about 40 miles in breadth, containing 4,080,000 acres; of which 900,000 acres were planted in 1675; and in November, 1789, there were no more than 1,907,589 acres located or taken up, by grants from the crown. This ifland is interfected with a ridge of fteep rocks, from which iffue a vaft number of fmall rivers of pure wholefome water, which fall down in cataracts, and together with the flupendous height of the mountains, and the bright verdure of the trees, through which they flow with rapidity to the fea on both fides of the illand, form a most delightful landfcape; but none are navigable by marine veffels. Black river is the deepeft, and is navigable for flat bottomed boats and canoes 30 miles. Sugar is the greatest and most valuable production of this ifland. Of this article was exported to Great Britain in 1787, \$24,706 cwt. in 1790, 1,185,519 cwt. It produces alfo cocoa, ginger, pimento, or as it is called, Jamaica pepper, and vulgarly allipice; the wild cinnamon, the machineel, whole fruit though uncommonly delightful to the eye, contains one of the worft poifons in nature; the cabbage tree, remarkable for its height, and for the hardness of its wood, which, when dry, is incorruptible, and hardly yields to any kind of tool; the palma, affording oil, much effeemed by the negroes, both as food and medicine; the foap tree, whole berries answer all the purpoles of washing ; the mangrove and olive bark, ufeful to tanners ; the fuffic and redwood, to the dyers; and lately the logwood. The indigo plant was formerly much cultivated, and the

cotton tree is ftill fo. Here they have maize, or Indian corn, Guinea corn, peas of various kinds, with a variety of roots. Fruits grow in great plenty, as citrons, Seville and China oranges, common and fweet lemons, limes, fhaddocks, p megranates, mamees, lourlops, papas, pine apples, prickly pears, allicada pears, melons, guavas, feveral kinds of berries, and kitchen, vegetables in great variety. Admiral Rodney enriched this beautiful ifland with many of the rare productions of the Eaft, which fell into his hands by the fortune of war ; particularly the bread-fruit tree, the true Ceylon cinnamon tree, and the mango tree. Jamaica can boaft of a botanical garden containing the rareft collection of curious trees and plants perhaps in the world; of which a catalogue has been published. The botanical garden contains, among other valuable productions, the Chinete hemp, palm, Otaheite plum, tallow-tree, gum-arabic, papermulberry, from which paper and cloth are made, tea plant, and Chinefe olive, The other productions, both animal and vegetable, are fuch as are common to the other iflands in the West Indies; but mahogany is now become fearce. In many parts of Jamaica there is a great appearance of metals; and it is believed that the Spaniards had mines both of filver and copper. A lead mine was indeed opened fome years ago, near to the Hope eftate, in St. Andrew's parish; but the poffeffors find more profit in cultivating the furface of the earth than digging into its bowels. Jamaica is divided into 3 counties, Middlefex, Surry, and Cornwall ; fubdivided into 20 parishes, as follows r Middlejex contains those of St. Mary, St. Ann, St. John, St. Dorothy, St. Thomas in the Vale, Clarendon, Vere, Sr. Catherine, the town of St. Jago de la Vega, the capital, and 13 villages; 244 fugar plantations, and 43,626 negroes. Surry contains the parifies of St. Andrew, St. George, Portland, Port Royal, St. David, St. Thomas in the Eaft, Kingfton, the towns of Kingfton and Port Royal, & villages, 159 fugar plantations, and 27,337 negroes. Cornwall contains the parifhes of Trelawney. St. James, Hanover, Weftmoreland, St. Elizabeth, the towns of Savanna-la-Mar, Montego Bay, and Falmouth, 109 fugar plantations, and 57,835 negroes. The whole 20 parifhes contain 18 churches and

they have uinea corn, a variety of t plenty, as a oranges, imes, had_ s, iourlops, pears, allieveral kinds getables in ney enrichth many of Eaft, which une of war ; ree, the true the mango a botanical t collection perhaps in alogue has ical garden ple producn. Otaheite bic, paperand cloth inefe olive. animal and ommon to eft Indies ; me fearce. e is a great is believed es both of ine was innear to the parifh; but it in cultithan digis divided Surry, and o parifices, ns those of St. Doro-Clarendon, of St. Jago 3 villages; 13,626 neparifies of land, Port nas in the Kingfton 159 fugar es. Cornrelawney. reland, St. a-la-Mar, 309 fugar pes. The churches and

JAM

and chapels; and each parish has a rector and other church officers. Prefentations to livings are made by the commander in chief. The number of white inhabitants in 1787, was 30,000; freed negroes 10,000; marcons 1400; and flaves 250,000; in ally 304,000. The value of this island as British property, is effimated as follows: 250,000 negroes at f. 50 fterling each, 121 millions; the landed and perfonal property and buildings to which they are appurtenant, 25 millions more; the houfes and property in the towns, and the veifels employed in trade, 11 millions; in all 39 millions. The exports of Jamaica for one year, ending the 5th of January, 1788, amounted in fterling money to 2,136,4421. 178. 3d. In 1787 the exports to the United States amounted to 60,00 sl. 18s. and importations from the United States to the value of f. 90,000. This ifland was originally a part of the Spanish empire in America. It was reduced under the British dominion by Penn and Venables in 1656, and ever fince has been fubject to Great-Britain. The government of it is one of the richeft places next to that of Ireland, in the difpofal of the crown, the standing falary being £.2500 per annum, and the affembly commonly vote as much more to the governor; which, with other perquifites, make it on the whole little less than £.10,000 a year. This fine itland is subject to earthquakes and hurricanes, which have done it incredible damage. See Weft-Indies and Cold Spring.

JAMES'S BAY lies at the bottom or most fouthern part of Hudion's Bay, with which it communicates, and divides New-Britain from South Wales. It contains feveral iflands, among which are Bear, Viners, Charleton, and Agomitca iflands. Michipicaton river, which falls into Lake Superior, has its fource towards this bay, from whence there is faid to be but a flort portage to Moofe river, which falls into James's Bay.

JAMES, Cape St. is the fouthernmost extremity of Washington Isles, on the north-west coast of North-America.

JAMES'S ISLAND lies on the fouth fide of Charleftown harbour, in South-Carolina, opposite to Charleftown, and contains about 50 families. It is feparated from John's Ifland on the weftward by Stono river. JAM

JAMES, a navigable river of Virginia, called anciently Powbatan by the Indians, affords harbour for veffels of any fize in Hampton Road, but not in fafety through the whole winter; and there is navigable water for them as far as Mulberry Itland. A 40 gun thip goes to Jameflown, and, lightening herfelf, may pais to Harrifon's Bar, on which there is only 15 feet water. Veffels of 250 tons may go to Warwick ; those of 125 go to Rockets's, a mile below Richmond, from thence is about 7 feet water to Richmond; and about the centre of the town 41 feet, where the navigation is interrupted by falls, which in a courfe of 6 miles, delcend about 80 feet perpendicular. A canal is nearly or quite completed for the paffing of boats by these falls. Above these the river is navigable for batteaux and canoes to within 10 miles of the Blue Ridge and even through the Blue Ridge a ton weight has been brought; and the expense would not be great, when compared with its object, to open a tolerable navigation up Jackfon's river and Carpenter's Creek, to within 25 miles of Howard's Creek of Green Briar, both of which have then water enough to float veffels into the Great Kanhaway. In fome future fate of population, it is poffible that its navigation may also be made to interlock with that of the Patowmac; and thro" that to communicate by a flort portage with the Ohio.

JAMES CITY, a county of Virginia, to miles long and 12 broad, lying between Chickahominy and James's rivers. It contains 4070 inhabitants, including 2405 flaves.

JAMES, a fort on the north fide of Loblollo Bay, in the ifland of Antigua, in the head of which is St. John's harbour.

JAMES, a creek in Delaware which empties into Delaware Bay, 11 miles below Hook Ifland. Dover, the feat of government, flands on this creek, 5 miles from its mouth.

JAMES Dartmouth Fort, a fortrels at the confluence of Broad with Savannah river. It was crected under the British government, and defigned as a defence of a commercial and political intercourfe with the Indians.

JAMES's, ST. a town of Maryland, fituated in Kent county, four miles fouthfonth-weiterly of the town of Chef-

250

JAMES, GOOSE CREEK, ST. a parifh in Charlestown district, S. Carolina, containing 2787 inhabitants; of whom 2333 are flaves.

JAMES SANTEE, Sr. a parish in the above diffrict containing 3797 inhabitants; of whom 437 are whites, and 3345 flaves.

JAMESTOWN, formerly the metropolis of Virginia, and county-town of James City county. In 1777 it had but one family. The church and other buildings are mouldering to ruins. It is the oldeft town in the fettlements formed by the English in North-America. It is fituated on a peninfula, on the N. fide of James's river, 32 miles from Point Comfort, at the mouth of the river in Chefapeak Bay. It is 8 miles S. S. W. of Williamfburgh, and es S. E. by E. of Richmoud. N. lat. 37. 9.

JAMES, GREAT and LITTLE, ST. two of the finaller Virgin Ifles, fituated in the King's Channel eaft of Tortula, and weft of St. Thomas, between which and them is St. James's Paffage. JAMES's Torwn, in the ifland of Barbadoes, in the Weft-Indies, is fituated in St. James's parifin, on the weft fide of the ifland.

JANEIRA, RIO DE. See Rio de Janeira.

JAQUEMEL. See Jacmel.

JAQUET, a river on the fouthern fide of Chaleur Bay, called by the Indians *Boocumkick*, is about 3 leagues weft of Billi Down. Here is a finall falmon fifthery.

JARDINE DEL REYNA, a vaft clufter of ifles and rocks on the fouth fide of the ifland of Cuba. These furnish immenie numbers of large and fine turtle.

JAUPTIONI, a river in Louifiana which runs a S. E. course and empties into the Miffisippi in N. lat. 39. 15. about 16 miles south of the mouth of Fabiani river, and 13. N. of that of Oahaha river.

JAY, a township in Cumberland county, district of Maine, lately incorporated; and thus named in honour of John Jay, governor of the State of New-York.

JAX's Valley, a fettlement in the but it is not fafe, as the water fhoals town of Kattikill, State of New-York, fuddenly, and the ground is not fo clean infide.

JEA

formerly called *Minor Kill*. This name was changed in honour of the prefent governor of New-York.

JAYNA, a canton, parifh, and river on the fouth fide of the island of St. Domingo. The rivers Nigua and Jayna are about a leagues apart ; and between them lies an extensive and fertile plain, which was originally an abundant fource of riches to the colonist. The quantity of pure gold, that was dug from its cavities, its fugar, cocoa, indigo, and other plantations paid duties to a greater amount than those now paid by all the Spanish part of the island put together. It was in this territory, and on the river Jayna, that the famous lump of gold was found, which the Spanish writers fay weighed 3600 Spanish dollars; without mentioning many others of a remarkable fize. The fettlements Gamboa, Guayabal, Bonaventura and Cagnabola, which laft was formerly called the Whale, are very inconfiderable : the whole employment of the people is breeding of cattle, or the washing of gold fand. Indigo grows wild here. The river Jayna is not fordable ; it is croffed in canoes and fkins at 2 50 fathoms from its mouth ; and the animals are obliged to fwim aerofs it. The coaft lying between Jayna and St. Domingo is of rock, almost perpendicular, in general from 6 to 15 feet high. Opposite this coast are a number of floals, each of about 40 fathoms wide. Towards the fource of this river were the celebrated gold mines of St. Chriftopher's, near which Columbus erected the fort of that name. There are also rich filver mines on this river. The eftablishments in the plain of St. Rofe, and those on the Javna ought to be locked upon as depending on the city of St. Domingo. They are reckoned to contain 2000 perfons; for the moft part people of colour, free and flaves.

JEAN RABEL, a town on the N. W. part of the north peninfula of the island of Domingo, in 19. 55. N. tat. and in 75. 42. W. long. from Paris. It is 4 leagues eaft of the Mole, and 32 well of Cape Francois. Jean Rabel Point forms the anchorage of that name, which is good, fafe, and eafy to fetch. You can anchor in 15 fathoms. You may go farther in as far as 8 fathoms; but it is not fafe, as the water thoals fuddenly, and the ground is not for clean infide. infide. place, thould which makes enemy the or N.W JEF Territ which tains of For JEF of the line of IEF ated o 19 mil N. lat. JEF bound fouth | E. by bitants town. Ohio. lies on er, abc is fepa fpring JEF and in tained 7840 flaves. JEF gia, er of Bu Ogeecl creeks. at Los houfe r JEF the co Cape from t weftwa 30. N. 69.45 JEK river A afford 40 gu JEN gomer north o JEN in Per l river on

St. Dond Jayna between ile plain, int fource he quanug from ligo, and a greatid by all put toory, and ous lump : Spanifh nifh dolw others ttlements tura and erly callderable : people is afhing of ild here. de ; it is t 250 fa-: animals it. The St. Dopendicuet high. mber of ms wide. ver were t. Chrifs erected are alfo The ef-St. Rofe, ht to be the city reckoned the moft flaves. eN.W. he ifland lat. and s. It is 1 32 wet el Point name, to fetch. s. You fathoms; er fhoals fo clean infide. infide. The Debarcadaire, or landing place, is a very good one, even if there thould be a fwell; it is under the fort, which is exceedingly well placed, and makes it a very good retreat from an enemy. The grounds hold well, and the only winds to fear are the N. and N. W.

IEN

JEFFERSON, Fort, in the N. W. Territory, is fituated on a finall thream which falls into the Great Miami; contains about 100 men; 21 miles north of Fort St. Clair. N. lat. 40. 4.

JEFFERSON, a fort on the east bank of the Miffifippi, in Kentucky, near the line of the State of Tenneffee.

JEFFERSON, a town of Virginia, fituated on the N. fide of Roanoke river, 19 miles below the Occoneachey islands. N. lat. 36. 32.

JEFFERSON, a county of Kentucky, bounded north and weft by Ohio river, fouth by Nelfon county, and S. E. and E. by Shelby. It contains 4565 inhabitants; of whom 876 are flaves. Chief town, Louigeille, at the Rapids of the Ohio. Drinnon's Lick, in this county, lies on the S. W. fide of Kentucky river, about 15 miles from its mouth; and is feparated from the famous medicinal foring by a fmall rivulet.

JEFFERSON, a county in Tennessee, and in Hamilton district, which contained by the State census of 1795, 7840 inhabitants, of whom 776 were flaves.

JEFFERSON, a new county of Georgia, erected in 1796, from the counties of Burke and Warren, bordering on Ogcechee river, and Briar and Big creeks. Courts and elections are held at Louifville for this county, a courthouse not being yet erected.

JEFFREY'S LEDGE, a fand-bank off the coaft of New-England, between Cape Ann and Calco Bay, extending from the north eaftward to the fouthwestward; between 42. 40. and 43. 37. 30. N. lat. and between 68. 52. 30. and 69. 45. W. long.

JEKYL SOUND, in the mouth of the river Alatamaha, in Georgia, which will afford fafe riding for a dozen thips of 40 guns.

JENKINTOWN, a village in Montgomery county, Pennfylvatha, 10 miles north of Philadelphia.

JENUCHSHADEGA, an Indian village in Pennfylvania, fituated on the W.

bank of Alleghany river, 8 miles S. S. W. from that of Teufhanufhfong-goghta, and 14 S. E. from the outlet of Chataughque Lake.

JEREMIE, a jurifdiction, town, and cape, within the bite or bay of Leo. gane, and on the fouthern peninfula of the island of St. Domingo. This is the westernmost juri/diction of the island, contains 2 parifhes, and is celebrated for the excellency of its foil, but particularly for the culture of coffee. Its exports from Jan. 1, 1789, to Dec. 31, of the fame year, were as follow : 1420lb. white fugar-247,760 lb. brown fugar-5,440,646 lb. coffee-54,786 lb. cotton-598 lb. indigo; and various articles to the value of 297 livres. The exportation duty on these productions amounted to 13,328 dollars 6 cents. The town ftands on the welt fide of the bay and at the month of a brook, a league S. by W. of Point Jeremie, 11 due N. of Port a Piment on the fouth fide of the peninfula, and nearly 8 leagues east of Cape Dame Marie. Point Jeremie lies in N. lat. 18. 42. 30. W. long. from Paris 76. 12.

JEREMYSQUAM, an island in Lincoln co. District of Maine, which, with Folly Island, form the mouth of Sheepscott river in Wiscasset Bay.

JERICO, a township in Chittenden county, Vermont, lies S. E. of Effex, and N. E. of Williston, and separated from the latter by Onion river, and contains 381 inhabitants.

JERICO, a post town of New-York, fituated in Tioga county, between Chenengo river and the east branch of Sufquehannah.

JEROM, FORT, ST, a fort on the fouth fide of the illand of St. Domingo, on the lea fide, and near the road from the city of St. Domingo, and in the canton of Jayna. It is no more than a fortified redoubt in mafonry; but it is confuncted with art.

JERSEY Field, a fettlement in Norway township, in Herkemer county, New-York, on the fouth-eastern fide of Canada creek.

JERSEY. See New Jerfey.

JER USALEM, a township in Ontario county, New-York. Of its inhabitants, 113 are electors. The compact part of it forms a hansome town, fituated on the W. fide of Seneca Lake, and contains about 30 families, the followers of lemima Jemima Wilkinfon. It is to miles N. Jer, which forms a convenient and fafe E. by N. of Bath, and 16 S. S. W. of Geneva. which will mark ' a start, ' the

JERUSALEM, or Funks Town, a town of Maryland, fituated in Walhington county on Antietana creek, about 21 miles S. W. of Elizabeth-Town. It contains about 50 dwellings, and a German church Sec.

JERUSALEM, OLD. See Fallen City. ERUYO, a mountain fituated in the valley of Urecho, in Mexico or New-Spain, is a great curiofity. Before the year 1760, there was nothing of it but a finall hill, where there was a fugar plantation. But on the 29th of Septem. ber, 1760, it burlt with furious shocks, and entirely ruined the fugar-works and the neighbouring village of Guacana; and from that time has continued to emit fire and burning rocks, which have formed themfelves into three high mountains, whole circumference was nearly 6 miles in 1766. The aftes at the irruption were forced to the diftance of 1 50 miles. In the city of Valadolid, 60 miles diftant, it rained afhes in fuch abundance, that they were obliged to fweep the yards of their honies two or three times during the day.

JESUS, ISLE DE, a finall ifland lying 8 degrees due north of the New Hebrides Island, and 1450 leagues welt of the coaft of Peru, in S. lat. 6. 50. E. long. from Paris 165. discovered by Mendana, Jan. 10th, 1567, inhabited by a coppered coloured and inulatto race of men.

JOHN, BAYOUK OF, ST. a little creek which furnishes a very easy communication from New Orleans to Weft-Florida. It is natigable for veficis drawing about 4 feet water 6 miles up from the Lake Ponchartrain, where there is a landing place, at which veftels lead and unload : this is about two miles from the town. The entrance of the Bayouk of St. John is defended by a battery of five or fix cannon. There are fome plantations on the Bayouk, and on the road from thence to New-Orleans.

JOHN DE FRONTIERA, ST. is the chief town of the province of Cayo in Peru.

JOHN'S ISLAND, in South-Carolina, lies S. W. of Charlestown harbour, diwided from James' Island by Stone riv-

JOH

harbour. men gang being with mak State

IOHN'S COLLEGE, ST. in Maryland. is fituat.d in the city of Annapolis, was inftituted in 1784, to have 24 truffees, with power to keep up the increffion by lupplying vacancies, and to receive an annual income of £.9000. It has a permanent fund of £11750 a year, out of the monies arifing from marriage licenfes, fines and forfeitures on the Weftem Shore. This college, with Wafhington college at Cheftertown, conftitute one university, named "The Univerfity of Maryland," The convocation of the University of Maryland, who are to frame the laws, preferve uniformity of manners and literature in the colleges, confer the higher degrees, determine appeals, &c.

JOHN's, ST. one of the chief towns of Newfoundland ifland, fitnated on the eaft coaft, 6 miles north-welt of Cape Spear, and 18 fouth-ealt of Cape St. Francis. N. lat. 47. 32. W. long. 52. 21. It lies on the bay of the fame name. Its harbour is one of the beft in the ifland, and has from ro to 17 fathoms water up to King's wharf, which is a lit le to the N. W. of the Old Fort, at the bottom of the town, and is a mile from the month of the harbour. A mile further is the mouth of Callor river, in which diffance there is from 14 to 4 fathoms of water. On the S. fide of the river is King's wharf, an hofpital, and a watering place. Near these are the hills called the High Lands of Sr. John's. N. lat. 47. 32. W. long. 52. 20

JOHN's, ST. a bay and ifland on the wett coaft of Newtoundland ifland, in the gulf of St. Lawrence, at the fouthwelt end of the Straits of Bellifle.

JOHN'S RIVER, ST. in Eaft-Florida rifes in or near a large fwamp in the heart of Eaft-Florida, and purfues a northern courfe, in a broad navigable ftream, which in feveral places fpreads into broad bays or lakes; of which Lake George is the chief. Veffels that draw 9 or 10 feet water, may navigate fafely through the welt channel into St. John's river as far as Lake George; which fee. The bar at the mouth is liable to fhift. It is 101 leagues N. of St. Augustine.

JOHN'S RIVER, Little St. in Weft-Florida, falls into Apalache Bay, about 10

10 mi It is f any in broad. the to called its fou from windir Indian branch it: bu which JOR the Br From Bay o compu flows \$ is nav miles. courfe furnich bals, a route t the cit trance or 100 in leng It bein running nel, on water, difchar above. about 2 low wi than the ter, the feet his that in one out only tin time w level wi is twice more th other til tremely fage of The ba the ann About mences tervale : with th beech, e many tr it on en

nt and fafe 的最高级和自己的 Maryland, apolis, was 14 truffees, increffion to receive It has a year, out arriage lithe Weftith Wathn, confti-The Uniconvocaland, who uniformi-

in the col-

es, deter-

hief towns ted on the t of Cape Cape St. long. 52. the fame the beft in to 17 fauf, which Did Fort, l is a mile . A mile r river, in 14 to 4 5. fide of hofpital, these are Is of Sr. long. 52. id on the fland, in he fouthfle. t-Florida ip in the urfues a

avigable s ipreads f which ffels that navigate into St. George ; uth is liis N. of

in Weftry, about 10 JOH

to miles eaftward of Apalache river. It is faid to be the clearest and purest of any in America, is about 200 yards broad, and about 15 or 20 feet deep at the town of Talahafochte. The fwamp called Ouaquaphenogaw is faid to be its fource, which is 100 miles by land from Talahalochte, and, following its windings, from the fea 200 miles. The Indians and traders fay it has no branches, or tributaries, which fall into it; but that it is fed by great fprings which break out through the banks.

JOHN's, ST. is the largeft river in the British province of New-Brunswick. From its mouth on the north fide of the Bay of Fundy, to its main fource is computed to be 350 miles. The tide flows So or 90 miles up this river. It is navigable for floops of 50 tons 60 miles, and for boats 200. Its general courfe from its fource is E.S.E. It furnishes the greateft plenty of falmon, bais, and flurgeon; and is the common route to Quebec. About a mile above the city of St. John's is the only entrance into this river. It is about 80 or 100 yards wide, and about 400 yards in length; called the falls of the river. It being narrow, and a ridge of rocks running across the bottom of the channel, on which are not above 17 feet of water, it is not fufficiently fpacious to discharge the fresh waters of the river above. The common tides flowing here about 20 feet, the waters of the river, at low water, are about 12 feet higher than the waters of the fea; at high water, the waters of the feature about five feet higher than those of the tiver; fo that in every tide there are two falls, one outwards and one inwards. The only time of paffing with fafety is at the time when the waters of the river are level with the waters of the fea, which is twice in a tide, and continues not more than 20 minutes each time. At other times it is either impaffable or extremely dangerous; refembling the paffage of Hell Gate near New-York, The banks of this river, enriched by the annual freshets, are excellent land. About 30 miles from its mouth commences a fine level country of rich intervale and meadow lands, well clothed with timber and wood, fuch as pine, heech, elm, maple, and walnut. It has many tributary freams, which fall into IOH

253

Oromocto river, by which the Indiana have a communication with Paffamaquoddy; the Nafhwach and Madamkifwick, on which are rich intervales that produce all kinds of grain in the higheft perfection. This noble river, in its numerous and extensive branches, waters and enriches a large tract of excellent country, a great part of which is fettled and under improvement. The up-lands, in general, are covered with a fine growth of timber, fuch as pine and fpruce, hemlock and hard wood, principally beech, birch, maple, and fome afh. The pines on this river are the largeft to be met with in Britifla America, and afford a confiderable fupply of mafts, fome from 20 to 30 inches in diameter, for the British navy.

JOHN'S, ST. one of the Virgin Iflands, about 12 leagues eaft of Ports Rico. It is about 5 miles long and one broad and 2 leagues fouth of St. Thomas. It is the best watered of all the Virgin Isles; and its harbour, called Crawl Bay, is reckoned better than that of St. Thomas, and paffes for the beft to the leeward of Antigua. There is, however, little good land in the ifland, and its exportations are triffing.

JOHN's, ST. an island in the gulf of St. Lawrence, near the northern coak of Nova Scotia, to which government it is annexed. It is 117 miles in length from N. E. to S. W. The medium breadth is 20 miles; but between Richmond Bay on the north, and Halifax Bay on the fouth, it is not above 3 miles broad. The other bays on the north fide are London Harbour, Grand Raftied, and St. Peter's; those on the fouth fide, Egmont, Halifax, and Hillfborough. On the east fide, Three River Harbour, and Murray Harbour. It has feveral fine rivers, a rich foil, and is pleafantly fituated. Its capital is Charlotte-Town, the refidence of the lieutenant-governor, who is the chief officer on the ifland. The number of inhabitan's are effimated at about 5000. Upon the reduction of Cape Breton in 1745, the inhabitants quietly submitted to the British arms. While the French poffeffed this island, they improved it to for much advantage, as that it was called the granary of Canada, which it furnished with great plenty of corn, as well as beef and pork. When taken, it had it on each fide, among which are the 10,000 head of black cattle upon it, and

buffiels of corn annually. Its rivers abound with falmon, trout, and cels, and the furrounding fea affords plenty of furgeon, plaice, and most kinds of shellfift. The ifland is divided into three counties, viz. King's, Queen's, and Prince's counties; which are fubdivided into 14 parifhes, confifting of 17 townthips, which in all make 1,363,400 acres, the contents of the island. The chief towns, befides the capital, are Georgetown, Prince's-Town; befides which are Hillfborough-Town, Pownal-Town, Maryborough-Town, &c. It lies between 45. 46. and 47. 10. N. lat. and between 44. 22. and 46. 32. W. long.

JOHN'S, ST. the north-westernmost town in Sustex county, Delaware, is fituated at the head of the middle branch of Nanticoke river, about 27 miles N. E. of Vienna in Maryland, and 22 S. by W. of Dover.

JOHN'S, ST. a town and fort in Lower Canada, fituated on the weft bank of Sorrel river, at the north end of Lake Champlain, a few miles fouthward of Chamblee, 28 miles fouthward of Montreal. It has been established as the fole port of entry and clearance for all goods imported from the interior of the United States into Canada, by an ordinance published by the executive council of Lower Canada, the 7th of July, 1796. It is 145 miles northward of Ticonderoga, and was taken by General Montgomery in Nov. 1775. N. lat. 45. 9. W. long. 72. 18.

JOHN, ST. a lake in Lower-Canada, which receives rivers from every direction, and fends its waters through Saguenai river into the St. Lawrence, at Tadoufac. It is about 25 miles each way.

JOHN'S BERKLEY, ST. a parifh of S. Carolina, in Charlestown district, containing 5922 inhabitants; of whom 692 are whites, and 5170 are flaves.

JOHN'S, ST. a fmall island in the West-Indics belonging to Denmark, north of St. Croix, and fouth of Tortola, to which last it is very near. It is noted only for its fine harbour, which is faid to be fufficient to contain in fafety the whole British navy. It has a number of falt ponds, which, however, are no evidence of its fertility.

JOHN'S COLLETON, ST. a parish of S. Carolina, in Charlestown district, con-

and leveral of the farmers raifed 22,000 taining 53.12 inhabitants ; of whom 58 5 buffiels of corn annually. Its rivers are whites; and 4705 flaves.

JOHN's, ST. the capital of the island of Antigua in the Weft-Indies. It is a regularly built town, with a harbour of the same name, situated on the weft shore, and on the north-call fide of Loblollo Bay. The entrance of the harbour is defended by Fort James. This town is the refidence of the governor general of the leeward Charaibe Islands, and where the affembly is held, and the port where the greatest trade is carried on. It was so flourishing as to receive a loss by a storm, to the value of £.400,000 sterling. N. lat. 17. 4. W. long. 62. 4.

JOHN, ST. or Juan de Porto Rico, the capital of the ifland of Porto Rico, in the Weft-Indies. See Porto Rico.

JOHNSBURY, ST. a township in Caledonia county, in Vermont, bounded S. W. by Danville, and has 143 inhabitants.

JOHNSON FORT, in S. Carolina, lies on the N. E. fide of James's Island, and S. of the city of Charlestown. It ftands at the entrance of the harbour, and by which no veffel can pass unless the maiter or mate make oath that no malignant diffemper is on board. It is guarded by 120 men.

JOHNSTON FORT, or Johnson Fort, in N. Carolina, ftands on the weftern bank of Gape Fear river, opposite to the island on the fea-coast whole southern point is Cape Fear.

JOHNSONSBOROUGH, a post-town of New-Jerley, 10 miles from Suffex-courthouse.

JOHNSON'S LANDING-PLACE, is on O-yongwongych Creek, about 4 miles eaftward of Fort Niagara.

JOHNSON, a county of N. Carolina, in Newbern diffrict, bounded S. E. by Glafgow, N. by Franklin and Wayne counties, and S. by Sampfon. It contains 5634 inhabitants, of whom 1329 are flaves.

JOHNSTOWN, a poft town and the capital of Montgomery county, New-York, fituated on the N. bank of Mohawk river, 24 miles W. of Schene Clady. The compact part of the town is a little back from the river, and contains about 70 houfes, a Prefbyterian and an Epifcopal church, a court-houfe and gaal. In the township 593 of the inhabitants are electors. Caghnawaga is a parish or diffrict of Johnstown, 26 miles above

above S ments So yes houle, l formerl fon. 1 ftroyed who we and oth Williar afferted. want o graced in this bours, ed in th tate was tants ha friend. feeing t fumed, walk, i could no and fcal JOHN dence co the tow inhabita JOHN county, habitant JOLY Scotia. JONA inlet on (Smith's cle, in la JONE Newberr ven. It e and 168 Trent ri Chief to JONES chief to Tenneffe county c having t is 26 m Knoxvill ginia, an JONES Camden Carolina. and a few JONE' Williamfb JONES JONES

whom 585

the ifland es. It is a harbour of t the weft de of Lobhe harbour This town lor general ands, and nd the port arried on, ceive a lofs 6.400,000 mg. 62.4. Porto Rico. orto Rico. to Rico. hip in Caounded S. 41 inhabi-

rolina, lies Ifland, and It ftands r, and by s the maino maligt is guard-

nfon Fort, ne weltern fite to the fouthern

ft-town of

CE, is on t 4 miles

Carolina, S. E. by d Wayne It coniom 1329

a) and the ty, Newc of Moenectady, is a little ins about an Epifand gaol, b inhabij aga is a 26 miles above JON

ments have been made here for about So years. Here ftand the dwelling houfe, barn, and out-houfes (all of ftone) formerly occupied by Sir William Johnfon. This fettlement was mostly deftroyed by the British in the year 1780, who were joined by a party of Indians and others, under the command of Sir-William Johnson. In this action it is afierted, that Sir William evinced a want of feeling which would have difgraced a favage. The people deftroyed in this expedition were his old neighbours, with whom he had formerly lived in the habits of friendship. His eftate was among them; and the inhabitants had always confidered him as their friend. These unfortunate people, after feeing their houfes and property confumed, were hurried, fuch as could walk, into cruel captivity; those who could not, fell victims to the tomahawk and fcalping knife.

JOHNSTON, a township in Providence county, Rhode-Island, westerly of the town of Providence, having 1320 inhabitants.

JOHNSTON, a township in Franklin county, in Vermont; it contains 93 inhabitants.

JOLY, a port on the S. coast of Nova-Scotia.

JONAS'S SOUND, the most northern inlet on the western coast of Sir Thomas Smith's Bay, lying near the arctic circle, in latitude 76.

JONES, a county of N. Carolina, in Newbern diffrict, bounded N. by Craven. It contains 3141 free inhabitants, and 1681 flaves. It is well watered by Trent river, and its tributary ftreams. Chief town, Trenton.

JONESBOROUGH, a post-town, and chief town of Washington district in Tennessive, is the seat of the district and county courts. It has but few houses, having been but lately established. It is 26 miles from Greenville, 101 from Knoxville, 40 from Abingdon in Virginia, and 627 from Philadelphia.

JONESBOROUGH, the chief town of Camden county in Edenton district, N. Carolina. It contains a court-house and a few dwelling-houses.

JONE's-TOWN, in Pennfylvania. See William fburg.

JONES, CAPE. See Lopkout Cape. JONES'S PLANTATION, in Lincoln JOS

above Schene Stady on the river. Settlements have been made here for about so years. Here fand the dwelling houfe, barn, and out-houfes (all of flone) formerly occupied by Sir William Johnfon. This fettlement was moftly de-

> JONES'S FORD, on Brandywine creek, is 5 or 6 miles above Chad's Ford, in Pennfylvania.

> JOPPA, a finall town in Harford co. Maryland, 20 miles E. by N, of Baltimore, and 82 S. W. of Philadelphia.

JORDAN'S *River* paffes thro' Trenton, in the Diffrict of Maine, 3 miles from Union river.

JORE, a village and mountain in the Cherokee country. The mountain is faid to be the highest in the Cherokee. country, and through which the Tenneffee river forces its waters. The Indian village, called Jore, is fituated in a beautiful lawn, many thousand feet higher than the adjacent country. Here is a little grove of the Cafine Yapon, called by the Indians the beloved tree. They are very careful to keep this tree pruned and cultivated, and drink very ftrong infusion of the leaves, buds, and tender branches of this plant. It is venerated by the Creeks, and all the fouthern maritime nations of Indians.

JOSEPH, LAKE ST. in N. America, lies E. of Lake Sal, and fends its waters by Cat Lake river into Cat Lake, and afterwards forms the S. E. branch of Severn river. The lake is 35 miles long and 15 broad. Ofnaburg Houfe is on the N. E. part of the lake; which fee.

JOSEPH, Ilet à Pierre, a village on the westernmost coast of the island of St. Domingo; about 3 leagues N. W. of the village of Tiburon.

JOSEPH'S, ST. in the province of California, in Mexico, N. America. N. lat 23. 3.

JOSEPH'S BAY, ST. on the coaft of Weft-Florida, is of the figure of a horfe fhoe, being about 13 miles in length, and 7 acrofs where broadeft. The bar is narrow, and immediately within it there is from 4 to 61 fathoms foft ground. The beft place to anchor, is just within the peninfula, opposite to fome ruins that ftill remain of the village of St. Jofeph's and Cape Blaize is a narrow flip of land, in fome places not above a quarter of a mile broad. A very good establishment might be made here

here for a fifhery, as the fettlers might make falt on the fpot to cure the bafs, rock, cod, grouper, red mullet, &c. which are here in abundance.

JOSEPH, ST. a water which runs N. W. into the S. E. part of Lake Michigan. It fprings from a number of small lakes, a little to the N. W. of the Miami village. The Pawtewatemie Indians refide on this river, opposite Fort St. Joseph. They can raise 200 warriors. At or near the confluence of the rivers St. Mary's and St. Joleph's, where Fort Wayne now ftands, the Indians have ceded to the United States a tract of 6 miles square.

JOSEPH, Fort St. is fituated on the eaftern fide of the above river in N. lat. 42. 14. W. long. 86. 10. It is about 175 miles S.W. by W. of Detroit, to which place there is a ftraight road.

JOSEPH, ST. a port on the W. fide of the ifland of Trinidad, near the coaft of Terra Firma.

JOSEPH, ST. a fmall town and port on the W. point of the N. penin ula of the ifland of Trinidad, in the West-Indies.

JOSEPH, ST. a bay on the weft fide of the island of Trinidad, defended by a finall battery. It has a few houfes on it, and lics S. E. of Port of Spain, the capital of the ifland. Near it is a mountain having mineral pitch.

JUAN, ST. the capital of California in N. America. N. lat. 26. 25. W. long. 114. 9.

JUAN, Fort St. flands in the province of New Leon, in N. America, on the S.W. fide of the Rio Bravo, in the 29th degree of N. latitude and 101ft of W. longitude.

JUAN DE LA FRONTERA, ST. a town of Chili in S. America. In its neighbourhood are gold mines. S. lat. 33. 25. W. long. 68. 55.

JUAN DE PORTO RICO. See Porto Rico.

JUAN DE FUCA, Entrance of. See Fuco.

JUAN FERNANDES, an ifland in the South Pacific ocean, 38 leagues east-ward of the ifland of Maffatuero, and \$90 weft of the continent. S. lat. 33. 32. W. long. 79. 50. from Greenwich. It is fuppofed to have been inhabited by a Spaniard, whole name it retains; although it was long abandoned by him and his nation; but is more remarkable locks with the weftern waters of Mo-

for having been the refidence of Alexander Selkirk, a Scotchman, whofe life and adventures furnished De Foe with the ground-work of that admirable novel Robinfon Crufoe. The harbour lies in Cumberland Bay, on the north fide of the ifland. Since the fhip Columbia was there, no foreigners are allowed to anchor in the road. Maffa Fuero Island lies 22 leagues W. by S. of this illand. Juan Fernandes, which is reprefented as an earthly paradife, furnished refreshment to Lord Anfon's fquadron in his voyage round the world. Its greateft length is 5 leagues ; its breadth lefs than two. On the fouth-weft is a fmall ifle called Goat Ifland, and a rock called Monkey Key, almost contiguous to it. On the north fide are three bays; but the middlemost called Cumberland Bay, where Commodore Anion anchored with his fhips, is the beft. Thefe bays, and the whole coaff abound with great variety of fifh in abundance. Admiral Anfon fowed here a great variety of vegetables, and planted plum, apricot and peach ftones, which the Spaniards fay are now thriving trees.

IUCATAN. See Yucatan.

JUDITH, POINT, the fouth-eafternmoft point of Rhode-Island State, fituated on the fea-coaft of Washington co. in South-Kingfton townfhip.

JUDOSA BAY, in Louisiana, lies in the N. W. corner of the gulf of Mexico. 4 A chain of iflands form a communication between it fouth-weftward of St. Bernard's Bay.

JULIAN, ST. a harbour on the coaft of Patagonia, in South-America, where thips bound to the Pacific ocean utually touch for refreshment. S. lat. 48. 51. W. long. 65. 10.

JULIENNE. See Neybe.

JULIET, MOUNT, in North-America, lies on the north fide of Illinois river, oppofite the place where that river is formed by the junction of Theakiki and Plein rivers. The middle of Mount Juliet is in N. lat. 42. 5. W. long. 88. 44.

JUMPING POINT. See Navefink Harbour.

JUNIUS, a military township in New-York State, bounded north by Galen, and fouth by Romulus.

JUNIUS CREEK, a northern branch of the Little Kanhaway, which internongahela

nongahel day adm latter inte way. JURUY

KAA Stat Hudfon's from Kaal from Efop

KAATS village of in the Stat the weft fic 100 rods fi of Hudfon York. It 1 ing place, erect build the margin tage of de which the fhallow. contains 19 are electors,

KAATS' ftands the a

KAATS' cinity of th bank of H a majeftic a first part o called the 1 mountains. KAHNON

village of th is Oneida Ca W. from W Paris. The in this villag but a fmall cient wigw fparfely throu veral miles which they and fwine, an and fow their

KAHOKIA KAMTSCH

the continents 66. N. lat. the only 18 miles his laft voyage tainty of this continents, be KAM

nongahela river; and which may one day admit a fhorter paffage from the latter into the Ohio, See Little Kanbaway.

JURUYO. See Mexico.

K

K AATS' BAAN, in New-York State, lies on the weft bank of Hudfon's river, feven miles foutherly from Kaats' Kill, and 11 N.E. by N. from Efopus.

KAATS' KILL, or Catfkill, a fmall village of 30 or 40 houles and ftores, in the State of New-York, fituated on the welf fide of Hudfon's river, about 100 rods from its bank; 5 miles fouth of Hudfon city, and 125 north of New-York. It has the appearance of a thriving place, and it is in contemplation to erect buildings on a marfhy point, on the margin of the river, for the advantage of deeper water, the creek on which the ftores now ftand being too fhallow. The townfhip of this name contains 1980 inhabitants, of whom 343 are electors, and 305 flaves.

KAATS' KILL, a creek on which ftands the above town.

KAATS' KILL Mountains, in the vicinity of the above town on the weft bank of Hudfon's river, which make a majeftic appearance. These are the first part of the chain of mountains called the Alleghany, or Appalachian mountains.

KAHNONWOLOHALE, the principal village of the Oneida Indians, in which is Oneida Caftle, about 20 miles S. of W. from Whiteflown, and 12 W. of Paris. There is but one framed house in this village. Their habitations are but a fmall improvement upon the ancient wigwams; and are fcattered sparfely throughout an enclosure of feveral miles in circumference, within which they keep their cattle, horses, and fwine, and without, plant their corn and fow their grain.

KAHOKIA. See Cabokia.

KAMTSCHATKA SEA lies between the continents of Afia and America. In 66. N. lat. they are feparated by a ftrait only 18 miles wide. Captain Cook, in his laft voyage, has eftablished the certainty of this near approximation of the continents, beyond a doubt; and that

the inhabitants of each continent are fimilar, and frequently pais and repais in cances from one continent to the other. From these and other circumflances it is rendered highly probable that America was first peopled from the N. E. parts of Asia. But fince the Efquimaux Indians are manifestly a separate species of men, and bear a near refemblance to the northern Europeans, it is believed that the Esquimaux Indians emigrated from the north-west parts of Europe.

KANAWA, or Kanhawa, a large mountainous county on the weftern line. of Virginia, having the Ohio river on the north-welt, and Kentucky weft. The population of this county is included in Green Briar, being 6015 inhabitants, including 319 flaves. About 7 miles from the mouth of Elk river in this. county, is a burning fpring, capacious enough to hold 40 gallons. A bituminous vapour constantly issues from it, which agitating the fand around it, gives it the appearance of a boiling fpring. On prefenting a torch within 18 or 20 inches of the mouth, it flames up in a column, 4 or 5 feet in height, and about 18 inches diameter, and which fometimes burns 20 minutes, and at other. times has continued 3 days. General Clarke kindled the vapour, ftaid about an hour, and left it burning.

KANAWAGERES, an Indian village on the weft fide of Genefice river, 4 miles weft-fouth-weft of Hartford in the Genefice country in New-York.

KANHAWAY, GREAT, a riverof Vir . ginia of confiderable note for the fertility of its lands, and still more as leading towards the head waters of James's river. But it is doubtful whether its great and numerous rapids will admit a navigation, but at an expense to which it will require ages to render its inhabi-tants equal. The great obstacles begin at what are called the Great Falls, 90 miles above the mouth, below which are only 5 or 6 rapids, and these passable with fome difficulty even at low water. From the falls to the mouth of Green Briar is 100 miles. It is 280 yards wide at its mouth. The head waters of this river are in the western part of North-Carolina, in the most easterly ridge of the Alleghany or Appalachian mountains, and fouth of the 36th degree of latitude. Its head branches encircle theie R

257

of Alexwhofe life Foe with rable novel our lies in rth fide of Columbia llowed to tero IRand his ifland. refented as d refreshon in his s greateft h lefs than fmall ifle ock called ous to it. bays; but land Bay, anchored hefe bays, with great Admiral variety of n, apricot Spaniards.

> h-eafternite, fituatington co.

ia, lies in if Mexico. 4 mmunicaird of St.

the coaft ica, where an ulually t. 48. 51.

h-Ameriof Illinois that rivf Theakimiddle of 2.5.W.

Navefink

p in Newby Galen,

rn branch tich interrs of Monongahela those of the Holfton, from which they are feparated by the Iron Mountain, through which it paffes to miles above the lead mines. About 60 miles from Little river it receives Green Briar river from the eaft, which is the only confiderable tributary ftream in all that diftance. About forty miles below the mouth of Green Briar river, in Virginia, in the Kanhaway, is a remarkable cata. ract. A large rock, a little elevated in the middle, croffes the bed of the river, over which the water fhoots, and falls about 50 feet perpendicularly, except at one fide where the defcent is more gradual. The great Kanhaway is 196 miles below Pittfburg, and is navigable moft of the year; and a waggon road may be made through the mountain which occafions the falls, and by a portage of a few miles only, a communication may be had between the waters of Great Kanhaway and Ohio, and thofe of James's river in Virginia. Down this river great quantities of goods are conveyed up the Kentucky river, others on horfeback or in waggons to the fettled part, and fold on an average, at 100 per cent. advance. See Sulphur Spring.

KAS

KANHAWAY, LITTLE, a finall navigable river of Virginia, which is 150 yards wide at its mouth, and is navigable 10 miles only. Perhaps its northerly branch, called Junius Creek, which interlocks with the weftern waters of Monongahela, may one day admit a fhorter paffage from the latter into the Ohio.

KAPPAS, a tribe of Illinois Indians, in Louifiana: they lie a little above the Sothouis. This nation was formerly very numerous before the difcovery of the Miffifippi. The country they inhabit has good paffurage.

KAPPAS, Old Fort, in Louisiana, stands on the Missippi, at the mouth of the river St. Francis. It was built by the French principally for a magazine of stores and provisions, during the wars with the Chickasaws; by whom their Illinois convoys were constantly attacked and frequently destroyed.

KARATUNK, or *Carytunk*, a plantation in Lincoln co. Diffriet of Maine, confifting of about 20 families or 103 inhabitants. It is the uppermoft on Kennebeck river, 14 miles north of Brookfield.

KAGKASKIAS Village lies on the S.

KAT

W. bank of the river of the fame name, a water of the Miffifippi, in the N. W. Territory, opposite Old Fort, and 12 miles from the mouth of the river, but not half that diffance from the Miffifippi. It contains 80 houfes, many of them well built; feveral of ftone, with gardens, and large lots adjoining. About 20 years ago it contained about 500 whites, and between 4 and 500 negroes. The former have large ftocks of black cattle, fwine, &c.

KASKASKIAS, an Indian nation near the river of that name in the N. W. Territory. They can furnifh 250 warriors. Three miles northerly of Kafkafkias is a village of Illinois Indians, of the Kafkafkias tribe, containing about 210 perfons, and 60 warriors. They were formerly brave and warlike, but are now degenerated and debauched. At the late peace the United States granted them a fum of money in hand, and became bound to pay them 500 dollars a year for ever.

KASKASKIAS, a river on the N. W. Territory, which is navigable for boats 130 miles. Its courfe is S. S. W. and near its mouth it turns to the S. S. E. and flows into the Miffifippi river, 84. miles from the Illinois. It runs through a rich country, abounding in extensive natural meadows, and numberlefs herds of buffaloe, deer, &c. High grounds lie along the eaft fide of the river, the banks being composed of lime-ftone and free-frone, and are from 100 to 130 feet high, divided in many places by deep cavities, thro' which many fmall rivulets pass before they fall into the Miffifippi. The fides of these hills, fronting the river, are in many places perpendicular, and appear like folid pieces of mafonry, of various colours, figures and fires.

KASKASKUNK, a town of the Delawares, between Great Bever creek and Alleghany river, in Penníylvania. Here the Moravian miffionaries had a fettlement. It is 40 miles north of Pittfburg.

KASKINOMPA, a fmall river which runs weft, into the Miffifippi, from the State of Tenneffee, in N. lat. 36. 28. On the N. fide of its mouth is an iron mine/ See Reelfoot.

Kaats' Kill, in New-York State.

RATHTIPPACAMUNCK, an Indian village fituated on the north fide of Wabash both riv creek, a er Wea itruction fon, it c were fh belonges delightf cellars, and the of order KAW

the Diffr maps as er. N. KAYA

York St: confluence river. toga, 8 c the mary branch o Alío the ratoga co

the town Kar's of Ameri east long. hood of i covered fe

KEENI fhire, and Chefhire c in 1753, i and in 175 miles fron mouth, an lat. 42. 53 KELLY

of the north KENAP lage on the branch of t KENDRI

tenden con

fide of Noo may enter fetts Sound the ifland.

259 · KENNEE the fineft ri Three mile Ifland, 7 mi the river. it are navigeaft fide of eight miles Nahunkeag,

fame name, i the N. W. mt, and 32 e river, but the Miffifipuany of them t, with garng. About about 500 500 negroes. ks of black

nation near the N. W. iffh 250 warerly of Kafs Indians, of aining about iors. They warlike, but debauched. Inited States ney in hand, ay them 500

n the N. W. ble for boats i. S. W. and the S. S. E. pi river, 84 runs through in extensive berleis herds ligh grounds he river, the of lime-ftone n 100 to 130 ny places by 1 many fmall fall into the f thefe hills, many places ir like folid ious colours,

of the Delay ver creek and rlvania. Here had a fettleof Pittfburg. 1 river which ippi, from the lat. 36. 28. th is an iron

tern branch of k State. k, an Indian th fide of Wabash KEN

befn river, at the mouth of Rippacanoe creek, and about 20 miles above the Lower Weau towns. In 1791, before its deftruction by Generals Scott and Wilkinfon, it contained 120 houfes, 80 of which were fhingle roofed. The beft houfes belonged to the French traders. The gardens and improvements round were delightful. There was a tavern with cellars, bar, public and private rooms; and the whole. marked no fmall degree of order and civilization.

KAWAKUSICA, or Kowfaki, a lake in the Diffrict of Maine, laid down in late maps as the head of Paffamaquoddy river. N. lat. 46. 3.

KAYADAROSSORA CREEK, in New-York State, about 12 miles weft of the confluence of Fifh-creek and Hudion's river. The celebrated fprings of Saratoga, 8 or 9 in number, are fituated on the margin of a marfh formed by a branch of this creek. See Saratoga. Alio the name of a tract of land in Saratoga county, New-York, bounded by the town of Shenectady.

KAY'S ISLAND, on the N.W. coaft of America, lies in north lat. 59. 49. eaft long. 216. 58. In the neighbourhood of this island; Captain Cook difcovered feveral other islands.

KEENE, a post-town of New-Hampfhire; and one of the most flourishing in Cheshire county. It was incorporated in 1753, and contained in 1775, 756, and in 1790, 1314 inhabitants. It is 14 miles from Walpole, 95 west of Portsmouth, and 86 N.W. from Boston. N. lat. 42. 53.

KELLYSBURGH, a township in Chittenden county, Vermont, at the head of the north branch of La Moille river.

KENAPACOMAQUA, an Indian village on the north bank of Eel river, a branch of the Wabah. See Longuille.

KENDRICK'S *Ifland* forms the weft fide of Nootka Sound, into which you may enter from the weft by Maffachufetts Sound, along the northern fide of the ifland.

259. KENNEBECK, next to Penobicot is the fineft river in the Diftrict of Maine. Three miles from the Chops, Swan Ifland, 7 miles long, divides the waters of the river. The waters on both fides of it are navigable; but the channel on the east fide of it is mostly used. Thirtyeight miles from the sea is the island Nahunkeag, which fignifies the land 250

where eels are taken. Within 3 miles of this island, a finall river coming weft from ponds which are in the town of Winthrop, runs into the Kennebeck, and is known by the name of Cobbefeconte, called by the Indians Cobbiffeconteag, which in their language fignifies the place where flurgeon are taken. Six miles further up the river we find the head of the navigable waters. This is a balon 46 miles from the fea, and very commodious for the anchoring of vefiels; On the east bank of the small fall which terminates the navigation of the Kennebeck, is Fort Weftern, which was crected in the year 1752. From that fort to Taconnet Fall is 18 miles. This is a great fall of water, and on the bank of it, on the eaftern fide of the river, is Fort Halifax, erected in 1754, and fituated on the point of land formed by the confluence of the Sebaftacook with the Kennebeck, by which the latter is increafed one third in fize. The Sebaftacook comes from lakes nearly north from its mouth; and in its windings receives brooks and fmall rivers, for the fpace of 1 50 miles. Thirty miles above Fort Halifax; as the river runs; the ftream called Sandy river flows into the Kennebeck, at the point where the ancient town of Norridgewock flood; 40 miles or more further up; the Kennebeck takes a fouth-weftward courfe. The Kennebeck turning again weftward, receives the eaftern branch 50 miles from Norridgewock. The main branch of the Kennebeck, winding into the wilderness, forms feveral carrying-places, one of which; called the Great Carrying-place, is 5 miles acrofs, and the river's course gives a distance of 35 miles, for that which is gained by 5 on the dry land. At about 100 miles diftance from the mouth of the eaftern branch; the fource of the main or weftern branch of the Kennebeck is found extended a great distance along the fide of the Chaudiere, which carries the waters from the high lands into the St. Lawrence. There are no lakes, but a few finall ponds and moraffes at the fource of this branch. The carrying-place from boatable waters in it; to boatable waters in the river Chaudiere, is only 5 miles over. The eaftern branch of the Kennebeck, which unites with the other above Norridgewock, iffues from a body of waters which lie N. R 2 about

about 20 miles from the confluence of | the two branches. These waters are called Moofe Pond or Moofe Lake. The fides of the lake are fo crooked, that the body of waters has an irregular figure; but the lake contains 3 times as much water as is found in Lake George. There are very high mountains to the north and weft of the lake, and from these the waters run by many channels to the St. Lawrence. The Kennebeck affords great quantities of lumber, and is inhabited at different feafons by feveral fpecies of valuable fifh. Salmon and flurgeon are taken here in great abundance, and fhad and alewives relieve the wants of the necessitous part of the inhabitants. This river forms the nearest fea-port for the people on the upper part of the river Connecticut. From the Upper Cohos, or Coos, on the latter river to the tide-water in Kennebeck, is go measured miles.

KENNEBUNK, the Indian name of the place fince called Wells, Diffrict of Maine, about 33 miles below Portfmouth, New-Hampfhire.

KENNEBUNK, a river of the Diffrict of Maine, having a good harbour at its mouth, from whence great quantities of lumber are thipped for a market. There the lumber of Moufom is thipped at prefent. This river divides the townfhips of Wells and Arundel. It runs a thort courfe, and empties into the fea between Cape Porpoife and Cape Neddick. See Kennebunk and Wells.

KENNET, a township in Chefter co. Pennsylvania.

KENNOMICK, GREAT, a navigable river of the N.W. Tervitory, emptying into the fouth end of Lake Michigan, about N. lat. 42. 11. The waters of this river communicate, by a portage of thirty yards, with Little Kennomick, a fhort river which runs north easterly into the lake.

KENSINGTON, a townfhip in Rockingham county, New-Hampfhire, about 6 miles foutherly of Exeter, 8 northerly of Newbury-Port, and 20 from Portimouth. It was incorporated in 1737. In 1775 it contained 797, and in 1790, 800 inhabitants.

ENT, a county of Maryland on the eastern fhore of Chefapeak Bay, bounded E. by Newcafile, and part of Kentcounty, Delaware, and W. by Chefapeak Bay. It is about 32 miles long and 13

broad, and contains 12,836 inhabitants, including 5433 flaves. Chief town, Chefter.

KENT, a county of Rhode-Ifland, lying S. of Providence county, on the W. fide of Narraganfet Bay. It is 20 miles in length, and 10 in breadth, and is divided into four townships. It contains 8785 inhabitants, including 63 flaves.

KENT, the middle of the three counties of Delaware. It is 40 miles from north to fouth, and 26 from eaft to weft, and contains 18,920 inhabitants, including 2300 flaves. The lands in Kent county are efteemed the richeft in the State. It is well watered by feveral finall freams that empty into the Delaware. Chief town, Dover.

KENT, an island in Queen Ann's co. Maryland, and the largeft in Chefapeak Bay. It is 12 miles from north to fouth, and 6 in breadth.

KENT, a township in Litchfield co. Connecticut, bordering on the State of New-York, and 8 or 10 miles weft of Litchfield.

KENTUCKY, a very crooked river in the State of its name, which after a general N. W. courfe of 200 miles, falls into the Ohio in N. lat. 39. It is formetimes called *Cuttawa*. Its fource is in the Laurel Mountains, and it interlocks with Licking river. Its mouth is 77 miles above the Rapids, and 626 below Pittfburg. Its mouth is 250 yards wide, and the river is navigable 130 miles; the current is confiderably rapid, the banks being high and rocky. It is faid black lead mines have been found on the head waters of this river. *Little Kentucky River* is 25 yards wide, and 3 miles weft of Kentucky river.

KENTUCKY, one of the United States of America, bounded N. W. by the river Ohio; W. byCumberland river; S. by Tenneffee State; E. by Sandy river, and a line drawn due S. from its fource, till it firikes the northern boundary of Tenneffee. It lies between 36. 30. and 39. 30. N. lat. and between 81. and . 89. W. long. about 250 miles long, and 200 broad, and contains about 50,000 fquare miles. It is divided into 14 counties, viz. Jefferson, Fayette, Bourbon, Mercer, Nelfon, Maddison, Lincoln, Woodford, Mason, Washington, Clark, Scott, Logan, and Franklin. It contains 73,677 inhabitants, of whom 12,430 are flaves. The river Ohio wafhes

wafhes t in its wh es which try, are § Green, again br rivulets zing the fprings a continue til Nover fwell the country thefe was which is pears of a is exposed it looks] banks of ftone has being of in the g rains, th tween th 10 to 30 fprings of higher an Bone Lic let's Lick licks ha Cumberla a bufhel, Illinois ci curing w finking w which yi pregnated the fea. This w been difco

below the where the of about 2 of the Ohi fperfed wi reft of the gently afc great difta are from times more very narrow thin, and that along quently no you fee a roots cling rock. Th cents (for

ftone, whi

habitants, wn, Chef-

Ifland, lyon the W. s 20 miles and is di-It contains 53 flaves. hree counmiles from aft to weft, its, includs in Kent heft in the by fleveral o the Dela-

Ann's co. in Chefa-

tchfield co. he State of iles weft of

ked river in after a gemiles, falls It is fomefource is in it interlocks wouth is 77 626 below yards wide, p miles; the l, the banks s faid black on the head, the Kentucky and 3 miles

the United d N. W. by verland river; Sandy river, m its fource, boundary of 36. 30. and en 81. and . miles long, itains about divided into m, Fayette, , Maddifon, n, Washingnd Franklin. ats, of whom river Ohio wafhes

wafhes the N. weftern fide of Kentucky; in its whole extent. Its principal branches which water this fertile tract of country, are Sandy, Licking, Kentucky, Salt, Green, and Cumberland rivers. These again branch in various directions, into rivulets of different magnitudes, fertilizing the country in all its parts. The fprings and ftreams leffen in June, and continue low, hindering navigation, until November, when the autumnal rains fwell the rivers, and replenish the whole country with water. At the bottoms of these water-courses the lime-ftone rock, which is common in this country, appears of a greyish colour; and where it is exposed to the air, in its natural state, it looks like brown free-ftone. On the banks of these rivers and rivulets, this stone has the appearance of fine marble, being of the fame texture, and is found in the greatest plenty. After heavy rains, the waters in the rivers rife between the high lime-ftone banks from 10 to 30 feet. There are 5 noted faltfprings or licks, in this country, viz. the higher and lower Blue Springs, the Big Bone Lick, Drinnon's Lick, and Bullet's Lick at Saltfburg. The laft of thefe licks has fupplied this country and Cumberland with falt, at 3 dolls. 33 cents a bufhel, and fome is exported to the Illinois country. The method of procuring water from these licks, is by finking wells from 30 to 40 feet deep, which yield water more ftrongly impregnated with falt, than the water from the fea.

This whole country, as far as has yet been discovered, lies upon a bed of limeftone, which in general is about fix feet below the furface, except in the vallies, where the foil is much thinner. A tract of about 20 miles wide, along the banks of the Ohio, is hilly, broken land, interfperfed with many fertile fpots. The reft of the country is agreeably uneven, gently afcending and defcending at no great distances. The angles of ascent are from 8 to 24 degrees, and fometimes more. The vallies in common are very narrow, and the foil in them is very thin, and of an inferior quality; and that along the afcending ground, is frequently not much better; for where you fee a tree blown up, you find the roots clinging to the upper parts of the rock. The foil on these agreeable afcents (for they cannot be called hills)

is fufficiently deep, as is evident from the fize of the trees. The foil is either black, or tinged with a lighter or deeper vermilion, or is of the colour of dark afhes. In many places there are appearances of potter's clay, and coal in abun-dance. The country promifes to be well fupplied with wholefome, well tafted water. In Nelfon county, N. W. of Rolling Fork, a branch of Salt river, is a tract of about 40 miles fquare, moftly barren, interfperfed with plains and ftrips of good land, which are advantageous fituations for raifing cattle, as the neighbouring barrens, as they are improperly ftyled, are covered with grafs, and afford good pasturage. The lands eaft of Nolin creek, a branch of Green river, are in general of an inferior quality; but the banks of Green river afford many defirable fituations.

Toward the head waters of Kentucky river, which interlock with the waters of Cumberland and Sandy rivers, and the whole country eaftward and fouthward as far as the Holfton river, is broken and mountainous; and from the defcription given by hunters, it has been much doubted whether it would ever be practicable to make a paffable road from Kentucky across to Winchefter, in Virginia, on the east fide of the mountains, which, on a ftraight line, is not perhaps more than 400 miles, and the way now travelled is 600. This doubt, however, is now removed, and a company have lately undertaken to cut a road (it is thought a waggon road may be made) from Kentucky, to pais by the Sweet Springs in Virginia; thence to Winchefter. This new road, it is supposed, will be nearly 200 miles fhorter than the one now travelled.

This country in general is well timbered. Of the natural growth which is peculiar to this country, we may reckon the fugar, the coffee, the papaw, the hackberry, and the cucumber trees. The two laft are foft wood, and bear a fruit of the fhape and fize of a cucum-The coffee tree refembles the ber. black oak, and bears a pod, which encloses a feed, of which a drink is made not unlike coffee. Befides thefe, there is the honey-locuft, black mulberry, wild cherry, of a large fize. The buckeye, an exceedingly foft wood, is the horfe chefnut of Europe. The magnolia bears a beautiful bloffom of a rich

R₃

and

and exquisite fragrance. Such is the variety and beauty of the flowering fhrubs and plants which grow fpontaneoufly in this country, that in the proper feason the wilderness appears in bloffom. The accounts of the fertility of the foil in this country, have, in fome inftances, exceeded belief, and probably That fome have been exaggerated. parts of Kentucky, particularly the high grounds, are remarkably good, all accounts agree. The lands of the first rate are too rich for wheat, and will produce 50 and 60, and in some instances, it is affirmed, 100 bufhels of good com an acre. In common, the land will produce 30 bufhels of wheat or rye an acre. Barley, oats, flax, hemp, and vegetables of all kinds common in this climate, yield abundantly. Cotton is feldom and with difficulty brought to perfection. Irifh potatoes produce in abundance, fweet potatoes are raifed

KEN

with difficulty. The old Virginia planters fay, that if the climate does not prove too moift, few foils known will yield more or better tobacco. Experience has proved, that the climate is not too moift. Great quantities of this article have been exported to France and Spain, through New-Orleans; and it is a well known fact that Philadelphia is a profitable market for the Kentucky planters, notwithftanding all the inconveniences and expenses of refhipment at New-Orleans, under a Spanish government. What advantages then may not this country expect fince the free navigation of the Miffifippi is now enjoyed?

In the rivers are plenty of buffaloe, pike and catfifh of uncommon fize, falmon, mullet, rock, perch, garfifh, eel, fuckers, funfifh, &c. Shad have not been caught in the weftern waters.

Swamps are rare in Kentucky; and of courie the reptiles which they produce, fuch as makes, frogs, &cc. are not numerous. The honey bee may be called a domeftic infect, as it is faid not to be found but in civilized countries. This is confirmed by a faying which is common among the Indians, when they fee a fwarm of bees in the woods, "Well, brothers, it is time for us to decamp, for the white people are coming." Neverthelefs, bees, of late years, have abounded, to their amazement, even 200 miles N. and N. W. of the Ohio. The qua-

drupedes, except the buffaloe, are the fame as in Virginia and the Carolinas.

The climate is healthy and delightful, fome few places in the neighbourhood of ponds and low grounds excepted. The inhabitants do not experience the extremes of heat and cold. Snow feldom falls deep, or lies long. The winter, which begins about Chriftmas, is never longer than three months, and is commonly but two, and is fo mild as that cattle can fubfit without fodder.

Kentucky experiences a greater degree of temperature than any of the neighbouring States: Fahrenheit's thermometer feldom falling below 35° in winter, nor rifing above 80° in fummer. The approach of the featons is gradual. The fummer continues mostly to the middle of October. The autumn or mild weather, generally continues until Chriftmas, when there is fome cold and froft until February, when the fpring approaches; and by the beginning of March leveral fhrubs and trees begin to fhooth forth their buds; by the middle of the month the buck-eye or horfe-chefnut is clad in fummer's array; and by the middle of April the foliage of the forefts is completely expanded; which is a fortnight earlier than the leaves are fhot forth in Virginia and Maryland : and Cumberland is proportionally more temperate than N. Carolina, as Kentucky is to Virginia. Malt-liquor, fpirits diftilled from corn and rye, and the juice of the fugar-tree mixed with water, conftitute the ordinary beverage of the country. Here are various mineruls; as iron, copper, lead, fulphur, nitre, &c. Iron-works are in fuch forwardness, as to furnish large quantities of caftings.

The legislature of Virginia, while Kentucky belonged to that State, made provision for a college in it, and endowed it with very confiderable landed funds. The Rev. John Todd collected, chiefly from a number of liberal gentlemen in England, a very handfome library for its ule. This college, of late, has not flourished; and another has been eftablifhed, and confiderable funds collected for its fupport. Schools are established in the feveral towns, and, in general, regularly and handfomely fupported. In this State are two printing offices, and two weekly gazettes published. There are crected a paper mill, oil mills, fulling fulling r ber of v luable t differen falt wo fupply price. tities of

The Kentuc reckone of this eye beh pendicu lime-fto white m frata of rivers h tificial o are cove Caves country a fine lin rious ar emit ful in fevera near a fa of Boa fprings o river, w empty th voir, and the purp and allu Kentuck curious tons. | I in or ne or fix f ground, which w regularly Thedi to Kentu miles; nearly 60 wards of the Rapi 1000 mil of Mexic KEOW to Savan: with the KEOV and territ on the riv ernmoft | foil is v heights 1

e quantities rinia, while State, made and endowanded funds. Sted, chiefly gentlemen in library for late, has not s been eftands collected re eftablished in general, fupported. ting offices, published. ill, oil mills, fulling

KEO fulling mills, faw mills, and a great number of valuable grift mills. Several valuable tanneries have been eftablished in different parts of the country. Their

falt works are more than fufficient to fupply all their inhabitants, at a low price. They make confiderable quantities of fugar from the fugar-trees.

The banks, or rather precipices, of Kentucky and Dick's river, are to be reckoned among the natural curiofities of this country. Here the altonished eve beholds 300 or 400 feet of folid perpendicular rock, in fome parts of the lime-ftone kind, and in others of fine white marble, curioufly checkered with frata of aftonifhing regularity. Thefe rivers have the appearance of 'deep artificial canals. Their high rocky banks are covered with red cedar groves.

Caves have been difcovered in this country of feveral miles in length, under a fine lime-ftone rock, fupported by curious arches and pillars. Springs that emit fulphureous matter have been found in feveral parts of the country. One is near a falt fpring, in the neighbourhood There are three of Boonfborough. fprings or ponds of bitumen near Green river, which do not form a ftream, but empty themfelves into a common refervoir, and when ufed in lamps, answer all the purpoles of the best oil. Copperas and allium are among the minerals of Kentucky. Near Lexington are found curious fepulchres full of human fkeletons.) It has been afferted that a man in or near Lexington, having dug five or fix feet below the furface of the ground, came to a large flat ftone, under which was a well of common depth, regularly and artificially froned.

The diftance of Philadelphia, by land, to Kentucky is between 700 and 800 miles; from Baltimore nearly 700; nearly 600 from Alexandria, and upwards of 500 from Richmond. From the Rapids of the Ohio to Santa Fe, is 1000 miles, and from thence to the city of Mexico, 1 500.

KEOWE, or Keowee, the name given to Savannah river, above its confluence with the Tugulo, the weft main branch.

KEOWE, anciently a populous town and territory of the Cherokee Indians, on the river of that name, the N. eafternmoft branch of Savannah river. The foil is very fertile, and the adjacent heights might, with little expense, be

rendered almost impregnable. The fruitful vale of Keowe is 7 or 8 miles in extent, when a high ridge of hills terminates the vale, but opens again below the ridge, and continues 10 or 12 miles down to Sinica, and in width 1 or 2 miles. This was formerly one continued and thickly inhabited fettlement. well cultivated and planted. It now exhibits a very different spectacle to the feeble remains of the once potent Che-Fort George formerly flood rokees. near the old feite of Keowe.

KEPLERS, a village in Berks county, Pennfylvania, on Little Schuylkill river, the N. branch of Schuylkill river; 21 miles N. N. W. of Reading, and 32 W. of Bethlchem.

KERISONGAR, a lake in the Diffrict of Maine, which fends its waters to Penobicot river.

KERSHAW, a county of Camden diftrict, S. Carolina, on Wateree river, which feparates it from Richland county. It is 35 miles in length and 30 in breadth.

KESIAH. See Culbai River.

KEYWAWA, a fmall ifle in Charleftown harbour, S. Carolina.

KAIRSERGE GORE, in Hil forough county, New-Hampfhire, contains 103 nhabitants.

KICKAPOUS, an Indian nation whole different tribes inhabit near the entrance of Lake Superior, where 20 years ago they had 400 warriors; part relide at Lake Michigan, and between that and the Miffifippi, near the Outtagomies, &c. and another tribe near the Piankeshaws, and on the Wabash and its branches.

The Kickapous and Kaskaskias, two Indian nations lately hoftile, ceded lands to the United States at the treaty of Greenville, August 3, 1795. The United States, on the other hand, paid them a fum of money in hand, and engaged to pay them in goods, annually, to the value of 500 dollars for ever.

KICKEMUIT River is a N. western arm of Mount Hope Bay. It is about 2 miles long, and half a mile broad. The town of Warren, in Briftol county, in the State of Rhode-Island, lies N.W. of it.

RIGLAPYED, on the coaft of Labrador, in Davis's Strait, N. from and near Nain; which fee.

KIKEIONEC Point. See Kieanon. R 4 KILLINGLY,

KILLINGLY, a town in Windham county, Connecticut, in the north-eaftern part of the State, bordering on Rhodefiland, and feparated from Pomfret by Quinebaug river. It lies about 18 miles eaftward of Windham, and has a Congregational church. The original fettlers were from Maliachufetts. The town was incorporated in May, 1708. In 1728 it was divided into two parifies; one of which is now incorporated by the name of Thompson.

KILLINGTON, a mountainous town thip in Rutland county, Vermont, having Medway on the W. Barnard N. E. and Saltafh on the S. E. and contains 32 inhabitants. Waterquechee river has its fource in a pond in this town.

KILLINGWORTH, a post-town in Middlefex county, Connecticut, fituated on Long-Island Sound, 9 miles E. of Guilford and 27 W. of New-London. The Indian name of the township was Mammonaffet; and a stream of that name runs on the W. fide of the town, and divides it from Guilford. It was fettled in 1663, by 12 planters from Hartford, Guilford, and Windfor. The English name defigned to have been given this town was Kennelworth, but by mistake it was recorded Killingworth. It was incorporated in 1703.

KILLISTINOES, Indians who inhabit on Lake Superior; and can furnish 250 warriors.

KILKENNY, a town in Grafton county, New-Hampshire, incorporated in 1774, but not inhabited.

KIMBECK, a place on the east bank of Hudson's river; 17 or 18 miles north of Poughkeepsie.

KINDERHOOK, a post-town in Columbia county, New-York, on the east fide of Hudion's river: 13 miles north of Hudion city, 29 S. by E. of Albany, 145 north of New-York, and 25 W. by N. of Stotkbridge in Massachusetts. The township contains 4,661 inhabiants; of whom 411 are electors, and 638 flaves.

KINDERHOOK Landing, in the above township, is situated under the bank of the river, surrounded with an uncleared barren country, has about 15 or 20 houses, and nearly as many stores and other buildings; 20 niles S. of Albany. The town, through which the stage to New-York runs, is about 5 miles east of the Landing. KINGLESS, a township in Philadelphia county, Pennsylvania.

KING AND QUEEN, a county of Virginia, on Mattapany river, which feparates it from King William's county. It is about 25 miles long and 20 broad, and contains 9,377 inhabitants, including 5,143 flaves.

KING GEORGE, an ancient fort on the borders of Eaft-Florida, near St. Mary's river.

KING GEORGE'S SOUND, or Nogtka, lies on the N. W. coaft of N. America, in north lat. 49. 36. See Nootka.

KING GEORGE, a county of Virginia, lying between the Patowmac, and Rappahannock rivers. It is 22 miles long, and 14 broad, and contains 7,366 inhabitants, of whom 4,157 are flaves.

KINGS, a maritime county of New-York, " containing all that part of the State, bounded eafterly by Queen's county; northerly, by New-York county; wefterly, partly by Hudíon's river, partly by the ocean; and foutherly by the Atlantic Ocean, including Coney Iflands." This fertile tract of land, fituated on the W. end of Long-Ifland, and feparated from Staten-Ifland by the Narrows, contributes largely to the fupply of the New-York market with vegetables, roots, fruits, butter, &c. It is divided into 6 townfhips, and contains 4,495 inhabits. including 1,432 flaves. Chief towns, Brooklyn and Flatbufh.

KING's, a county of Nova-Scotia, comprehending the lands on the S. W. and S. fides of the Bafin of Minas. The Habitant is navigable for veffels of 40 tons a little way up. The Canaid for veffels of 160 tons, 4 or 5 miles; and the Cornwallis is navigable for veffels of 100 tons 5 miles, for those of 50 tons 10 miles farther. There are confiderable fettlements on these rivers, and they afford a good portion of fine lands for tillage, and for herbage, and fome excellent meadows. In the rivers are found a great abundance of fhad of an excellent kind; and in the Bafin of Minas are fine cod-fish, haddock, bafs, and flat fish of different kinds.

Ktyc's BRIDGE, a post-town of New-York, 1 5 miles north of New-York city, and 29 S.W of Stamford in Connecticut. The bridge here connects New-York island with the main land. It was strongly fortified during the war. The heights about it are commanding.

KINGSBURY,

KING ton cou erly by incial bitants. KIN ifland in to Spain ery; an 81. 36. KIN of New on the miles V fide of deftroy by orde mandin Hudfor were co gular 1 houfes, formed moft pl rounded miles S York. 56. .7 bitants. 302 fla KING Vermon KIN co. Ma of Plyn Duxbo bitants ing mil in 170; ton. KINC county road wl hill, in former, Portfm 1694. bitants KIN three m S. W. pleafan KIN county It is a plain o contain 30 hou bern, a

KINGSBURY, a township in Washington county, New-York, bounded easterly by the tract of land called the Proyincial Patent. It contains 1120 inhabitants.

adel

y of

which

unty

road

clud-

ort on

r St.

oatka,

erica,

ginia,

Rap-

long,

inha-

New-

of the

coun-

part-

by the

In-

fitu-

d, and

y the

e fup-

th ve-

It is

ntains

laves.

icotia.

S. W. The

of 40

id for

; and

tons

idera-

d they

ds for

né ex-

of Mi-

s, and

New-

k city,

cticut.

York

was

The

URY,

s are of an

ufh.

KING'S, or PEARL ISLAND, a finall ifland in the Bay of Panama. It belongs to Spain, and is famous for its pearl fichery; and lies in N. lat. 7. 12. W. long. 81. 36.

KINGSTON, or ESOPUS, a post-town of New-York, fituated in Ulfter county, on the W. fide of Hudson's river, fix miles W. of Rhinebeck, and on the E. fide of Efopus Kill, or Creek. It was deftroyed on the 1 sth of October, 1777; by order of General Vaughan, commanding a fleet which failed up the Hudson, when large quantities of ftores were confumed. It is rebuilt on a regular plan, and contains about 150 houfes, a court-houfe, jail, a Dutch reformed church, and an academy. It is most pleafantly fituated upon, and furrounded by a spacious plain. It is 56 miles S. of Albany, and 109 N. of New-N. lat. 41. 56. W. long. 73. York. 6. . The township contains 3929 inhabitants, of whom 556 are electors, and 302 flaves.

KINGSTON, a township in Addison co. Vermont, containing 101 inhabitants.

KINGSTON, a township in Plymouth co. Massachuletts, on the western part of Plymouth Bay, bounded northerly by Duxborough, and contains 1004 inhabitants. There is here a slitting and rolling mill. The town was incorporated in 1707. It is 38 miles S. E. of Boston.

KINGSTON, a townflip in Rockingham county, New-Hampfhire, lying on the road which leads from Exeter to Haverhill, in Maffachufetts, 6 miles from the former, 12 from Haverhill, and 20 from Portfimouth. It was incorporated in 1694. In 1775 it contained 961 inhabitants; and in 1790, 906.

KINGSTON, a village in New Jerfey, three miles N. E. of Princeton, and 15 S. W. of Bruniwick; an elevated and pleafant fpot.

KINGSTON, the chief town of Lenoir county, Newbern diffrict, N. Carolina. It is a poft-town, fituated in a beautiful plain on the N. fide of Neus river, and contains a court-house, jail, and about 30 houses. It is 40 miles W. of Newbern, and 24 from Waynesborough, KINGSTON, a township in Luzerne county, Pennsylvania.

KINGSTON, a town of Georgetown diffrict, S. Carolina. It is fituated on the W. fide of Wakkamau river, and contains an Epifcopal church, and about 30 houfes. It is 41 miles N. by E. of Georgetown, and 103 N. N. E. of Charleftown. N. lat. 33. 51. W. long. 79.1.

KINGSTON, a village in Talbot co. Maryland, fituated on the eaftern fide of Choptank river, 4 miles below the Forks. KINGSTON, formerly called Frontinac, is fituated on the northern part of Lake Ontario, at the mouth of its outlet Iroquois river; 200 miles fouthward of Montreal, and 150 northward of Niagara. Here the King's flores are kept and guarded by one company of men. Part of Old Fort Frontinac is now standing, the best part of which is the magazine. Kingfton contains about 100 houfes. Large veffels go no farther than this place ; thence to Niagara, &c. ftores and merchandize are conveyed in boats.

KINGSTON, the capital of the island of St. Vincents, in the West-Indies, and the seat of government, lies at the head of a bay of the same name, on the southwestern shore of the island, in St. George's parish.

KINGSTON, the capital of the ifland of Jamaica, in the Weft-Indies, is fituated on the N. fide of a beautiful harbour, having Port-Royal on the N.E. and Spanish-Town on the S. W. and was founded in 1693; when repeated defolations by earthquakes and fire had driven the inhabitants from Port-Royal. It contains 1665 houfes, befides negro huts and ware-houfes. In 1788; the white inhabitants amounted to 6,539; free people of colour 3,280; and flaves 16,659; in all 26,478. It is a place of great trade and opulence. Many of the houses in the upper part of the town are extremely magnificent; and the markets for butchers' meat, turtle, fifh, poultry, fruits, and vegetables, inferior to none. It is the refidence of the moft confiderable merchants, whole thips load and unload here. Upon an average of 20 years, the fhips that go out aunually from this port amount to 400. N. lat. 17. 57. 30. W. long. 76. 33.

KING WILLIAM, a county of Virginia, between Mattapony and Pamunky rivers, It is 47 miles long and 15 broad,

and contains 3,128 inhabitants; of whom | plenty of that fift, in the mouth of the 5,151 are flaves.

KINGWOOD, a township in Huntingdon county, New-Jersey, containing 2,446 inhabitants, including 104 slaves. It is about 5 miles below Alexandria, and 15 S. W. of Lebanon. Also the name of a small river of New-Jersey.

KINSALE, a post-town of Virginia, 16 miles from Westmoreland court-house, and 12 from Northumberland courthouse.

KtOANON POINT, called in fome maps Kikeionee, is the extremity of a large peninfula which projects far into the fouth fide of Lake Superior.

KIONTONA, an Indian town on Conewango river, in Pennfylvania, and 11 miles northerly from its mouth in Alleghany river.

KISHTAC, an ifland on the N. W. coath of North-America, lies eaftward of Foggy Cape, on the fouth-eaft fide of the peninfula of Alafka, and on that part of it opposite the head of Briftol Bay, on the N. W. fide of the peninfula. It is also opposite the mouth of Cook's river.

KISKEMANITAS *River*, is a branch of Alleghany river, into which it empties in N. lat. 40. 40. in Weftmoreland county, Pennfylvania. Its head waters are Little Conemaugh and Stone creek. After their junction it is called Conemaugh river. It then receives Black Lick from the N. E. and 17 miles from its mouth Loyalhannon Creek enters from the S. S. E. after which it is called Kifkemanitas river. It is navigable for batteaux 40 or 50 miles, and good portages are found between it and Juniatta and Potowmac rivers. Coal and falt are difcovered in the vicinity of thefe rivers.

KITTANING, a fettlement in Pennfylvania, on the caft fide of Alleghany river, 36 miles northward of Pittfburg.

KITTATINNY Mountains, a ridge of the Alleghany Mountains, which suns through the northern parts of New-Jerfey and Pennfylvania.

KITTERY, a township in York county, diffrict of Maine, incorporated in 2653, and confists of 3 parishes, containing 3,250 inhabitants. It is fituated between Pifcataqua and York rivers, 67 miles northerly of Boston. In this town is Sturgeon Creck, called fo from the plenty of that fifh, in the mouth of the creek at the first settlement of the country; but there have been none found for these many years past. This creek is famous in the history of the first settlers.

KATTS, ST. See St. Chriftophers.

KNOB LICK, in Mercer county, Kentucky, lies 15 miles S. E. of Harrodftown, and about 12 foutherly, of Danville.

KNOWLTON, a township in Suffex county, New-Jersey, containing 1,937 inhabitants, of whom 13 are flaves.

KNOULTON, a grant in Chittenden county, Vermont, lies E. of Smithfield, and W. of Kellyfburgh, and contains 10,000 acres of land.

KNOX, a county in the State of Tenneffee, in Hamilton diffrict, contained in 1795, according to the State cenfus, 11,573 inhabitants, of whom 2,365 were flaves.

KNox, a county in the N. W. territory, crected June 20, 1790. " Beginning at the Standing Stone Forks of the Great Miami river, and down the faid river to its confluence with the Ohio river; thence with the Ohio to the finall rivulet above fort Maffac ; thence with the eaftern boundary line of St. Clair county, to the mouth of the little Michilimackinack; thence up the Illinois river to the forks or confluence of the Theakiki and Chikago; thence by a line to be drawn due north to the boundary line of the territory of the United States, and fo far eafterly upon faid boundary, as that a due fouth line may be drawn to the place of beginning. Also the name of a fort in the same territory.

KNox, one of Ingraham's iflands. Captain Ingraham difcovered two iflands, which he called *Knox* and *Han*. cock, which Captain Roberts foon after difcovering, called *Freeman* and *Langdon*. Thefe iflands had every appearance of fertility. Their latitude is from 8. 3. to 8. 5. S. and their longitude very nearly 141. W. from Greenwich.

KNOXVILLE, the metropolis of the ftate of Tenneffee, is fituated in Knox county, on the north fide of Holfton river, on a beautiful fpot of ground, az miles above the junction of Holfton river with the Tenneffee, and 4 below the mouth of French Broad river. It is in a flourishing the N.

Robert

50. W

A

Ath

called hended by Hu Lower rence, by the E. by Gulf o rocky ifles. Labra the fi which fterl. is unl The comm

=66

LAB

f the

coun-

found

creek

ft fet-

rs.

Ken-

rrodf-

Dan-

Suffex

1,937

enden

hfield,

ntains

Ten-

tained

enfus,

2,365

terri-

Begin-

of the

he faid

Ohio

finall

e with

Michi-

Illinois

of the

by a

boun-

United

on faid

ie may

me ter-

iflands.

d Han.

oon af-

an and

ery ap-

latitude

teir lon-

Green-

of the

n Knox

Holfton

and, 22

lfton ri-

low the

It is in

urifhing

two

ming.

Clair

a flourishing fituation, and enjoys a communication with every part of the Unit-ed States by poft. It is regularly laid out, and contains about 130 houses, a court-houfe, gaol, and barreks large enough to contain 700 men. The fupreme courts of law and equity for the district of Hamilton are held here half yearly, and the courts of pleas and quarter feffions for Knox county are held here. A college has been eftablished here by government, called Blount College. It is 32 miles N. of Tellico Blockhoule; 200 S. E. by S. of Frankfort, in Kentucky ; 485 W. by S. of Richmond, in Virginia; and 728 fouth-wefterly of Philadelphia.

KODIAC, an ifland on the fouthern fhore of the peninfula of Alaska, on the N. W. coast; which fee,

KORTRIGHT, a township in Otsego county, New-York; 122 of its inhabitants are electors.

KOYAHT, a fmall ifle at the S. end of Washington Ifle, at the entrance of a strait separating a small isse from the largest.

KRIS, Indians inhabiting the banks of Lake Christineaux. They can raife 1,200 warriors.

KULSAGE, or Sugar Town, a little Cherokee town in the vale of Keowe.

KYUQUOT, a large found or bay on the N. W. coaft of N. America, having Roberts Ifland on the one fide. N. lat. 50. W. long. 127. 20.

L

ABRADOR, TERRA DE, one of LA the northern counties of America, called also Efquimaux, and is comprehended in New-Britain; bounded north by Hudson's Strait, fouth by part of Lower Canada and the river St. Lawrence, weft by Hufon's Bay, north-eaft by the Ocean and Davis's Straits, and E. by the Straits of Bellifle and the Gulf of St. Lawrence. The coaft is rocky and interfperfed with innumerable ifles. The only attempt to trade with Labrador, has been directed towards the fifthery; the annual produce of which, amounts to upwards of £49,000 fterl. The inhabitants, whole number is unknown, hunt for furs and fkins. The Moravian Brethren maintain a communication with their miffion on

the coaft of Labrador. The property of their fhip is divided into thates of L_{10} only, with the fupply intended for the brethren; articles are fent for traffic with the natives, enabling them to bring back cargoes that have afforded them not always a dividend of more than the intereft of the capital employed. See New-Britain.

LABRADOR, a large lake which by its numerous branches forms a water communication through great part of the ifland of Cape Breton. In fome maps it is called St. Peter's Lake.

LACHAWANNOCK, a mountain in the north-western part of Pennsylvania.

LACHAWANNOCK, a township in Luzerne county, Pennsylvania

LACE, a township in Mifflin county, Pennsylvania.

LA COLE, a river which falls into Lake Champlain from the W. 5 miles S: S. W. of Nyt-Ifland, after a fhort courfe.

LACOMIC, a finall creek which empties through the weft bank of Alleghany river in Pennfylvania, oppofite Licking Creek, a fhort diftance below fort Franklin.

LACONIA. The tract of land extending from the river Merrimack to Sagadahock, and from the ocean to the lakes and rivers of Canada, went under this name, in the grant of lands in 1622, from the council of Plymouth to Capt. Maion and Sir Ferdinand Gorges.

Mafon and Sir Ferdinand Gorges. LADIES *Ifland*, a fmall ifland of S. Carolina, near Port-Royal.

LAGOON, one of the new difcovered islands in the South Sea. Captain Cook visited it in 1769. S. lat. 18. 47. W. long. from Greenwich 139. 28.

LAGUNA, a town of Peru, fituated on Amazon river. S. E. of the town of Borja.

LA GUAYRA, a maritime fortified town in Caraccas, a province of Terra Firma. This town, and Puerto Cabela are the chief in the province. LAKE OF THE WOODS. See Woods.

LAKE OF THE WOODS. See Woods. LA MOELLE, a large river in the N. W. part of Vermont. Its general course is wefterly 1 after running about 75 miles, and receiving 14 lefter ftreams, it falls into Lake Champlain at Colchetter, 5 miles north of the mouth of Onion river, and is of about the fame magnitude.

LAMBAYEQUE, a town on the road from Guayaquil to Lima in Peru, four leagues from Morrope. It confits of about 1,500 houfes, built of different materials. materials, but in general of bajareques, or mburnt bricks. The meaneft of the boufes are the habitations of the Indians, which conflit entirely of canes. The number of its inhabitants amounts to above 30,000, fome of whom are opulent; but the generality are poor Spaniards, Mulattors, Meftizoes, and Indians. It has a large and elegant flone church. It is the relidence of a corregidor, having under his jurifdiction, befides many other towns, that of Morrope. One of the two officers of the revenue appointed for Truxillo, alfo rendes here. S. lat. 6, 47. 37. W. long. 76. 15.

LAMPA, a jurifdiction of Cufco, in Peru, in S. America. It hegins about 30 leagues fouth of the city of Cufco; and is the principal province included under the name of Cuflao. Here are excellent paftures and filver mines. The air is very cold.

LAMPETER, a township in Lancaster county, Pennsylvania.

LAMPREY River, a water of Great Bay, in New Hampfhire.

LANCASTER, a bay or found on the western coast of Sir Thomas Smith's bay. The southernmost part lies in N. lat. 74. 20. The most northerly is called Akderman Jonas's Sound, and his in N. lat. 76.

LANCASTER, a populous and wealthy county in the interior part of Pennfy vania, extending fouth to the Mary-Im id line. It is about 42 miles fquare, is divided into 25 townships, and contains 566,240 acres of land, and 35,147 inhabitants, including 348 flaves. The lands in this county are rich and well cultivated. The hills in the northera parts abound with iron ore; for the man ufacturing which, 2 furnaces and 8 for es have been credted. The furnaces mannfacture about 1,200 tons of pigs and nearly that number of bar-iron ana ually. Copper and lead have alio been found here. Chief town, Lancafter.

LANCASTER, a county of Virginia, bo unded eaft by Chefapeak Bay, and S. W. by Rappahannock river. It is about 40 miles long, and 15 broad, and contains 5,638 inhabitants, of whom 3, 336 are flaves.

LANCASTER, a county of Camden di ftriet, S. Carolina, lying on Lynche's c cek, and Waterce river. It contains (,302 inhabitants, of whom 4,684 are 1, hites, and 1,370 flayes.

LANCASTER, Borough of, a handfome and flourishing post-town, the capital of Lancaster county, Pennfylvania, and the largest inland town in the United States. It is pleafantly fituated upon the defcent of a hill, a mile and a half weft of Coneftoga creek, which falls into Sulquehannah river 9 miles S. by W. of the town. Its trade is already great, and mult increase in proportion as the furrounding country populates. It contains about 7 or 800 houses and about 5,000 people. The legislature is to meet here in future, till a permanent feat of government shall be eftablifhed. The public buildings are a handfome court-house of brick, a market-house of the same materials, and a strong stone gaol. Here are fix places of worthip, for as many different perfuafions, viz. German Lutherans, German Calvinifts, Prefbyterians, Epifcopalians, Moravians, and Roman Catholics. The German Lutheran church is a large brick building, having an organ, and a handfome fpire; the others are of brick, and are neat and commodious buildings. The only manufactures here are carried on by individuals. There are 3 breweries and 2 or 3 valuable tanneries. Franklin College is eftablished here for the Germans. Its endowments are nearly the fame as those of Dickinson college at Carlisle. Its truftees confift of Lutherans, Calvinifts, Prefbyterians, and Episcopalians; of each an equal number. The principal is a Lutheran, and the vice-prefident a Calvinist. It is 58 miles as the new turnpike road runs, W. by N. of Philadelphia, and 31 from Reading. N. lat. 40. 3. W. long. 76. 20.

LANCASTER, a post-town of S. Carolina, 36 miles from Camden, and 47 from Charlotte, N. Carolina.

LANCASTER, a very pleafant pofttown in Worcefter county, Maffachufetts, the oldeft in the county, having been fettled in 1645, and incorporated in 1653. It is fituated on a branch of Nafhua river, which empties into the Merrimack. It is 35 miles W. N. W. of Bofton, 4 miles W. of Bolton, and 14 N. by E. of Worcefter. The lands of the townfhip of Lancafter, and thofe of Sterling on the S. W. are part of the tract called *Nafbawogg* by the Indians. The pleafantnefs of this town has invited many perfons of education and

-61

and fortune to relide here. In the N. It is avery flourishing place, fituated on eafterly part of Lancaster there is a valuable, and perhaps inexhauftible flate pit, furnishing flates for houses, and excellent ftones for tombs and graves. No flates equal to these have yet been difcovered in the United States. Thefe are fent to Bofton, and exported to New-York, Virginia, &c. Two principal branches of Nafhua river, over which are 9 large bridges, water this town, and have on their banks excellent intervale land. Cumbery pond in this town is obferved to rife as much as two feet, just before a storm; and Sandy pond rifes in a dry feafon.

LANCASTER, a township in Grafton county, New-Hampfhire, on the eaft, bank of Connecticut river, about 41 miles above Hanover. It was incorporated in 1763. In 1775 it contained

61 inhabitants, and in 1790-161. LANCE ISLES, on the N. W. coaft of N. America, lie off Cape Scott, which is the fouthern point at the mouth of Pintard's Sound, opposite to Point Difappointment. There is a narrow channel between the largeft ifle and the cape. See Pintard's Sound.

LANDAFF, a township in Grafton county, New-Hampfhire. It was incorporated in 1774, and contains 292 inhabitants.

LAND'S HEIGHT, in North-America, is the high ground on the chain of lakes between Lake la Plue and Lake Superior, where there is a portage of 7 miles. It is 80 miles east of the grand portage from the weft end of Lake Superior.

LANGDON, a township in Cheshire county, New-Hampfhire, incorporated in 1787, and contains 244 inhabitants.

LANESBOROUGH, a township in Berkshire county, Massachufetts, N. by E. of Hancock, 12 miles N. by W. of Lenox, and 144 W. by N. of Bofton. It affords a quarry of good marble, and contains 2,142 inhabitants.

LANSINBURGH, (city) in the townthip of Troy, Renffalaer county, New-York, is very pleafantly fituated on the E, bank of Hudson's river, opposite one. of the mouths of the Mohawk, and contains about 200 dwelling-houfes, a brick church, the joint property of the Dutch and Prefbyterian congregation, a court-houfe, gaol, and an academy, incorpo-rated in 1796. Here is a library company which was incorporated in 1775.

a plain at the foot of a hill, from the top of which is a most delightful profpect. A few years ago there was hur one ftage between this town and Albany; now (1796) zo ftages daily pals and repais between the neighbouring towns of Lanfinburgh, Troy, Waterford, and Albany; and the average number of paffengers is faid to exceed 150. It is 9 miles north of Albany, 3 above Troy, 175 north of New-York, and 270 N. N. E. of Philadelphia.

LAPIS LAZULI, a fmall rock fur rounded with and almost covered by the fea on the coaft of Nova-Scotia. is about 2 miles from Monano Island, and thews the paffage into St. John's river.

LA PLATE. See Paraguay.

LARGE ROCK lis on the S. bank of. Ohio river, in the track called Indiana, and nearly opposite the mouth of Mufkingum river.

LARGE ISLAND, one of the largest iflands on the Labrador coaft, due welt

of the mouth of Shecatica Bay. LARICAXAS, a province of La Paz, and audience of Charcas, in Peru. It lies adjacent to the territories of the jurifdiction of La Paz, and to the north of that city, extending 118 leagues from E. to W. and about 30 from N. to S. It abounds in gold mines, the metal of which is of fo fine a quality, that its ftandard is 23 carats and 3 grains.

LATACUNGA, Affiente of, the first jurifdiction to the fouthward of that of Quito, in Peru. The word affients implies a place lefs than a town, but larger, than a village. It ftands on a wide plain, having on its east fide the eastern cordillera of the Andes, from which, projects a very high mountain; and at a fmall diftance from its foot is fituated Latacunga, in 55. 14. 30. S. lat. On its W. fide is a river, which is fometimes fordable, but generally paffed over a bridge. This affiento is large and regular, the fircets broad and firaight, the houses of stone, arched, and well con-trived, one story high. This precaution the inhabitants were taught to obferve by a dreadful deftruction of all the buildings, on the 20th of June, 1699. Out of 600 ftone houses, which the affiento then contained, only a part of one, and the Jesuit's church, were left standing, and most of the inhabitants were buried

n, and e lands d those part of the In-

s town

ucation and

fome

capi-

ania,

Uni-

d up-

nd a

which

miles is al-

pro-

y po-

800

The

e, till all be

s are

mar-

and a

places

per-

Ger-

pilco-

atho-

rch is

organ,

are of

odious

Aures

duals.

valu-

t is ef-

Its

ne as

arlifle.

Calvin-

lians ;

princiefident

he new

of Phi-

. N.

S. Ca-

and 47

t poft-flachu-

having

porated

anch of

nto the

N. W.

8-

in the ruins. The ftone of which the houses and churches are built, is a kind of pumice, or spongy stone, ejected from volcanoes; which have formed inexhauftible quarries in the neighbourhood. It is fo light; that it will fwim in the water, and from its great porofity; the lime cements the different pieces very ftrongly together. This jurifdiction contains 17 principal villages. The air of the affiento is colder from the place being only 6 leagues from the mountain of Cotopaxi; which as it is not lefs in height or extent than those of Chimborazo and Caymburo, fo like them, it is covered with ice and fnow. The villages are populous; fuch as are feated in the vallies are hot, those in the plains temperate, whilft those which border on the mountains, like that of the affiento, are cold, and fometimes to an exceffive degree. The inhabitants amount to about 12,000, chiefly Spaniards and Meftizoes. Great quantities of pork are falted here and fent to Quito, Guayaquil, and Riobamha, being highly valued for the peculiar flavour given it in the pickling. The manufac-tures are those of cloth, bays, and rucu-yos. The inhabitants of Pugili, and Saquifili, are noted for making earthen ware, highly valued all over the province of Quito. The clay of which they are made is of a lively red, remarkably fine, emitting a kind of fragrancy, and the workmanship very neat and ingenious.

LAUREL MOUNTAIN, a range of mountains weftward of the Alleghany ridge, and a part of what is called the Alleghany Mountains. It extends from Pennfylvania to N. Carolina, and gives rife to feveral branches of the Ohio river. The great Kanhaway breaks through the Laurel Ridge in its way to the Ohio, in N. lat. 38. 30. W. long. 81. 19. In a fpur of this mountain, about lat. 36. is a fpring of water, 50 feet deep, very cold, and, it is faid, as blue as indigo. The lands within a fmall diffance of the Laurel Mountain, through which the Youghiogany runs, are in many places broken and ftoney, but rich and well timbered ; and in fome places, and particularly on Laurel Creek, they are rocky and mountainous. From the Laurel Mountain to Monongahela, the first 7 miles are good, level farming lands, with fine meadows; the timber, white-oak, cheinut, hickory; &c.

LAWRENCE River and Gulf. St. St. Lawrence is one of the largest rivers in N. America: It iffues from Lake Ontario; forming the outlet of the long chain of great lakes; which feparate Upper-Canada from the United States. From Lake Ontario to Montreal it has the name of Iroquois; and taking a northeaft courfe embofoms the ifland of Montreal; just above which it receivesOttawas from the weft; and forms many fertile iflands. From Montreal it affumes the name of St. Lawrence, and continuing the fame courfe paffes by Quebec, and meets the tide upwards of 400 miles from the fea, and is fo far navigable for large veffels. Having received in its courfe befides Ottawas, St. John's, Seguina, Desprainles, Trois Rivieres, and innumerable other finaller ftreams, it falls into the ocean at Cape Rofieres, by a mouth about 90 miles broad. In its courie it forms a great variety of bays, harbours and iflands, many of them fruitful and extremely pleafant. See Quebec, Montreal, &c. The main entrance into the gulf of Sta Lawrence from the Atlantic ocean, is on the eaftward between Cape Ray, the fouth point of Newfoundland Ifland, and the north cape of Cape Breton; the Gut of Canfo leads into it from the S. E. between Nova-Scotia and the S. end of Cape Breton ; and the Straits of Bellifle lead into it from the north between Newfoundland Ifland and the coaft of Labrador. It contains a num-ber of iflands, viz. St. John's, at its fouthern extremity, on the coaft of New-Brunfwick and Nova-Scotia; An= ticofti, at the mouth of the St. Lawrence; befides a number of fimall iflands:

LAURENS, a county in Ninety-Six diffrict, S. Carolina, lying between Enoree and Saluda rivers. It is about 3r miles long, and 22 broad, and contains 8,217 free inhabitants, and 1,120 flaves.

LAURENS Court House, in the above county, is 20 miles from Bush river, 32 from Newbury court-house, and 40 from Greenville.

LAWRENCE, Fort, is a little above the croffing place of Julearawas, a branch of Murkingum river.

LAWRENCE-TOWN, a thinly fettled agricultural township, a few miles to the caftward of Halifax in Nova-Scotia. LAURENT

LAUR ment in t the Spani ftands in first foun Ozama, a from its o can only on St. D habitants cure. I run-away fent dow fhipped efcort, a maintain LAW fettleme on Alle eaft of I LAZA De Fonte LEAC county, LEAS well con a court-LEB/ ty, Diff east fide north c in 1767 A fpeci yields c LEB. New-Y Maffacl and pa The m celebrit pool is nence, rounde tolerab LEB county 1697. in the nerally wealth town houfes each been p 80 yes by th Moun tween

LAURENT of the Mine, St. a fettlement in the ifland of St. Domingo, near the Spanish capital, St. Domingo. It ftands in the place where the capital was first founded, on the east fide of the Ozama, and about a quarter of a league from its confluence with the Ifabella. It can only be confidered as a dependency on St. Domingo, and contains 300 in. habitants, all free negroes, forming a cure. It was formed in 1723, by 128 run-away French negroes who being fent down to the bay of Occa to be fhipped off, the Spaniards attacked the efcort, and gave arms to the fugitives, maintaining that they were free men.

LAWUNAK HANNOCK, a Moravian fettlement nearly opposite Gofhgoshink, on Alleghany river, and 20 miles northeast of Fort Franklin.

LAZARUS, Archipelago of, St. See De Fonte.

LEACOCK, a township in Lancaster county, Pennsylvania.

LEASBURGH, the chief town of Cafwell county, N. Carolina. It contains a court-houle, gaol, and a few houfes.

LEBANON, a township in York county, Diffrict of Maine, fituated on the east fide of Salmon Fall river, 100 miles north of Boston. It was incorporated in 1767, and contains 1275 inhabitants. A species of stone is found here which yields copperas and sulphur.

LEBANON, New, a pleafant village in New-York State, bordering on Pittsfield, Maffachufetts, fituated partly in a vale, and partly on the declivity of hills. The medicinal firings here are next in celebrity to these of Saratoga. The pool is fituated on a commanding eminence, overlooking the valley, and furrounded with a few houses which afford tolerable accomodations to invalids.

LEBANON, a township in Windham county, Connecticut, was settled in 1697. The foil is equal to almost any in the State, and the inhabitants are generally farmers, many of whom are wealthy. The thick settled part of the town forms a very wide firet, and the houses are at confiderable diffances from each other. Academic education has been patronized in this place for above 80 years, greatly to the honour of the people. The river Shetucket is formed by the junction of Willamantic and Mount Hope rivers, which unite between this town and Windham. It lies

9 miles north of Norwich, and 30 fouth-, east of Hartford.

LEBANON, a township in Grafton county, New Hampshire, fituated on Mulcomy river, and on the east fide of the Connecticut, z miles below Dartmouth College. It was incorporated in 1761. In 1775 it contained 347 inhabitants, and in 1790—1180. It is in contemplation to build a bridge on Connecticut river at the middle bar of Agar's falls in this town, where the diftance between the rocks is 110 feet. It is 35 miles above the bridge built by Col. Hale at Bellows's Falls at Walpole. See Mafcomy Pond.

LEBANON, a post-town of Pennfylvania, fituated on the fouth fide of Quitapahilla creek, in Dauphin county. About a mile from the town is the Sufquehannah, and Schuylkill canal, which connects this creek with the Tulpehocken, a branch of the Schuylkill. Lebanon contains about 300 houfes regularly built, many of which are of brick and ftone; a German Lutheran and a Calvinift church. It is 25 miles E. by N. of Harrifburg, 43 E. by S. of Carlifle, and 82 N. W. by W. of Philadelphia.

LEE, a finall town in Strafford county, New-Hampfhire, about 12 miles north of Exeter. It was formerly part of Dover and Durham, and was incorporated in 1766. In 1775 it contained 954 inhabitants, in 1790-1029.

LEE, Fort, was erected by the Americans during the late war, on the weft bank of North river, having the track called the English Neighbourhood on the north, and that called Heboken on the fouthward, in N. lat. 40. 56. and about 9 miles above the town of Bergen. The Americans had 2,000 men in garrison here in the late wor, but evacuated it in November, 1776, with the loss of their artillery and ftores.

LEE, a county of Virginia, lately taken from Ruffel, in the S. W. corner of the State, bounded fouth by the State of N. Carolina, and weft by Kentucky.

LEE, a township in Berkshire county, Massiachusetts, 5 miles southerly of Lenox, 4 east of Stockbridge, and 140 west of Boston; was incorporated in 1777, and contains 1, 170 inhabitants. Housatonick river runs southerly through this town.

LEEDS, a town in the eaftern part of Gloucefter

ckory;

t. St.

vers in

Ontachain Upper-From as the north-MonvesOtmany it afe, and fies by ards of fo far ing revas, St. ois Rifmaller t Cape miles a great iflands, tremely f of Sta ean, is ay, the Ifland, Breton ; om the the S. raits of orth bend the a num-, at its oaft of a; An= Lawen Enobout 31 contains o flaves. e above iver, 32 40 from

e above

was, a

y fettled

es to the otia:

URENT

Gloucefter county, New-Jerfey, 4 miles about 75 miles, and is navigable 38 weft of the mouth of Mullicus river, miles. and 8 north-westerly of Brigantine Inlet. LEEDS, a village of Richtmond coun-

272

ty, Virginia, fituated on the north bank of Rappahannock river; 14 miles E. by S. of Port Royal, 40 S. E. of Frede-rickfburg, and 70 N. E. of Richmond. Near Leedstown is a famous course for horfe-racing.

LEEFOOGA, one of the Friendly iflands, in the South Sea. It was vifited by Captain Cook in 1776, who confiders it, in fome respects, superior to Anamooka. The ifland is fituated near Hapace, and is about 7 miles long and 3 broad.

LEESBURG. See Leasburg.

LEESBURG, a post-town of Maryland, 25 miles from Frederickstown.

LEESBURG, a post-town of Virginia, and capital of Loudon county. It is fi-tuated 6 miles S.W. of the Patowmac, and 4 S. of Goofe Creek, a branch of that river on the great road leading from Philadelphia to the fouthward, and on the road leading from Alexan. dria to Bath. It contains about fixty houses, a court-house and gaol. It is 20 miles from Salifbury, 32 from Shepherdftown, 20 miles from Frederickftown in Maryland, 46 north-weft of Alexandria, and 64 E. S. E. of Winchefter.

LEESBURG, or Leeflown, a settlement in Kentucky, on the banks of Kentucky river, 20 miles from Lexington, and about 30 from the Upper Blue Lick. It was deftroyed by the Indians and abandoned. The country for many miles round is first rate land. Great plenty of marble is found on the banks of Kentucky, particularly at this place.

LEE's ISLAND, in Patowmac river, in Fairfax co. Virginia, about 2 miles fouth-eastward of Thorp, which is on the north fide of Goofe Creek.

LEEK, a fmall ifland of Pennfylvania, in Delaware river.

LEEWARD ISLANDS. See Weft-Inhes.

LEHIGH, or Lecha, a river which rifes in Northampton co. Pennfylvania, about 21 miles eaft of Wyoming Falls, in Sulquehannah river, and taking a circular courfe, paffing through the Blue Mountains, empties into Dela-ware river on the fouth fide of Easton, 15 miles N. E. of Bethlehem. It runs. LEN

LE GRAND, a confiderable river of the N.W. Territory, which rifes with-in a few miles of the weft extremity of Lake Erie, and purfuing a N. N. W. course for nearly 100 miles, thence turning to the weft, empties into Lake Michigan. It is about 250 yards wide at its confluence with the lake.

LEICESTER, a township in Addison, county, Vermont, fituated on the eaft fide of Otter Creek, having 343 inhabi-tants. Great Trout Pond, or Lake, is partly in this town, and partly in Salif-bury, on the north. This town was

granted Oct. 20, 1761. LEICESTER, called by the Indian na-tives Towtaid, is a confiderable town in Worcefter co. Maffachufetts, containing 1076 inhabitants. It is fituated upon the poft-road from Bofton to Hartford, New-York and Philadelphia, 6 miles wefterly of Worcefter, and 54 W. by S. of Bol-ton; bounded N. by Paxton and S. by Oxford. It was fettled in 1713, and incorporated in 1720 or 1721. There are three meeting-houses here for Congregationalifts, Anabaptifts, and Quakers; who live in harmony to-gether. The Leicefler Academy was incorporated in 1784, and is well endowed. | Wool cards are manufactured here to the annual amount of 15,000 pairs.

LEMINGTON, a township in Effex county, Vermont, on the weft bank of Connecticut river, and near the N.E. corner of the State. The Great Monadnock Mountain is in this town. It contains 31 inhabitants.

LE MAIRE. See Maire.

LEMPSTER, an inconfiderable townthip in Chefter county, New-Hampfhire. It was incorporated in 1761. In 1775, it contained 128, and in 1790, 414 inhabitants.

LENOIR, a county of Newbern diftrict, N. Carolina, furrounded by Glafgow, Crayen, Jones, and Dauphin. It contains 2484 free inhabitants, and 957 flaves. Chief town, Kingfton.

LENOX, the fhire town of Berkfhire county, Maffachufetts, It is a pleafant and thriving town, and has a court-houfe and gaol. Houfatonick river paffes through the town. It lies eaft of Washington, fouth of Pittsfield, 17 miles fouth-westerly of Chefter, and 145 miles north of Bofton.

LEOGANE,

FOCI or Bite of Leogane, of St. Dor ninfulas. Nicholas a peninfula, N. W. poi leagues ap bay are th north fide ifles Reffif a vaft num bays, town Nicholas r are La Pl Gonaives, haye, Port Miragoane daires, Bà Dame Mar head of w the extren éaftward, Dame Mar Nicholas. LEOGAN French par go, fituate of the fout! of Leogan which fets Goave, 4 l that name, of Cayes de au Prince, : Gonave If long. from able, pleafi The export 31, of the i white fugar gar-1,932 cotton-an ties on the

26,103 dol

LEOMIN

ter county,

by W. of

chendon, 4

of Worceff

rough, in N

ing-office a

Thistownfl

incorporate

1189 inha

ftreams whi 2 grift mil

and clothie

LEO

c 30

er of

with-

w.

turn-

Mi-

de at

difon

e east

habia

ke, is Salif-

was

n nawn in ining

on the Newfterly

Boi-

nd S. 1713,

1721. here

s, and

y to-

as in-

ndow-

d here

Effex

ank of

N.E.

t Mo-

n. It

town-

Hamp-

1761.

1790,

rn dif-Glaf-

n. It

nd 957

rkfhire

leafant

court

river

ies eaft

eld, 17

and 145

GANE,

airs.

LEOGANE, Bay of, called alfo Bight, or Bite of Leogane, also Cul de Sac of Leogane, at the welt end of the island. of St. Domingo, is formed by two peninfulas. It opens between Cape St. Nicholas at the weft end of the north peninfula, and Cape Dame Marie, the N. W. point of the fouth peninfula, 45 leagues apart. At the bottom of the bay are the iflands Gonave, and on the north fide of the fouth peninfula the ifles Reffif and Caymite. It embofoms a vaft number of fine bays. The chief bays, towns and ports from Cape St. Nicholas round to Cape Dame Marie are La Plate Forme, or the Platform, Gonaives, St. Marc, Montrouis, Archahaye, Port au Prince, Leogane, Goave, Miragoane, Petit, Trou, Bay of Bara-daires, Bay of Durot, Jeremie, Cape Dame Marie, &c. Trou Bordet, at the head of which is Port au Prince, is at the extremity of the Bay of Leogane eaftward, 60 leagues eaft of Cape Dame Marie, and 51 S. E. of Cape St. Nicholas.

LEOGANE, a fea-port town in the French part of the ifland of St. Domingo, fituated on the N. fide of the neck of the fouth peninfula in the bay or bite of Leogane, at the head of a small bay which fets up E. from the bay of Grand Goave, 4 leagues N. E. of the town of that name, 6¹/₂ N. of Jackmel, 8 N. W. of Cayes de Jacmel, 9 W. by S. of Port au Prince, and 61 leagues S. E. of Petite Gonave Ifland. N. lat. 18. 30. W. long. from Paris 75. 2. It is an agree-able, pleafant, and commercial place. The exports from Jan. 1, 1789, to Dec. 31, of the fame year, were 895,871 lbs. white fugar-7,079,205lbs. brown fugar-1,932,952lbs.coffee-139,887lbs. cotton-and 4,960lbs. indigo. The duties on the exportation of the above, 26,103 dollars 70 cents.

LEOMINSTER, a polt-town in Worcefter county, Massachusetts, 7 miles N. by W. of Lancaster, 20 S. E. of Winchendon, 46 weftward of Bofton, 19 N. of Worcefter, and 20 S. of Mariborough, in New-Hampfhire, has a printing-office and feveral neat buildings. This township was taken from Lancaster, incorporated in 1740, and contains 1189 inhabitants. On the different ftreams which pais through the town are

271

About 200,000 bricks are annually made here. The manufacture of combs is alfo carried on to great perfection and profit. Leominfler Gore, adjoining, contains 27 inhabitants.

LEON, a river which falls into the Gulf of Mexico from the N. W. at the bay of St. Bernard.

LEON, New, a populous kingdom of New-Spain, in N. America, in which are feveral filver mines.

LEON, a town of the province of Panuco, in Mexico. It has rich mines, and lies 30 leagues N. of Mechoacan, and 55 N.W. of the city of Mexico.

LEON DE CARACAS, ST. a city, the capital of the province of the Caracas, fituated on a river, about 6 leagues S. from the coaft, enclosed by mountains. The valley in which it fands is a favannah, well watered and very healthy, about 3 leagues long and 1 broad in the middle, the only entrance into which is through a crooked and fteep road. The city is near a mile long; the houses handfome and well furnished; the ftreets regular, straight and broad, cutting each other at right angles, and terminating in a magnificent square in the centre. It contains about 4 or 5000 inhabitants; most of whom are owners of cocoa plantations, which 12 or 13,000 negroes cultivate in the rich vallies, which is almost the only cultivation they have.

LEON DE NICARAGUA, a town of N. America in New-Spain, and in the province of Nicaragua; the refidence of a governor, and a bifhop's fee. It was taken by the buccaneers in 1685, in fight of a Spanish army who were 6 to r; is feated at the foot of a mountain, which is a volcano, and occafions earth-It confifts of about 1000 quakes. houfes, and has feveral monasteries and nunneries belonging to it. At one end of the town is a lake which ebbs and flows like the fea. It is 30 miles from the South Sea. N. lat. 12. 25. W. long. 88. 10.

LEONARDSTOWN, a post-town of Maryland, and the capital of St. Mary's county, is fituated on the east fide of Britton's Brook, just where it falls into Britton's Bay, 5 miles from its mouth in the Patowmac, and contains about 50 houses, a court-house, and gaol. It is 113 miles fouth of Baltimore, 62 fouth 2 grift mills, 5 faw mills, an oil mill, by east of Upper-Marlborough, 30 and clothiers works, very excellent. fouth-east of Port Tobacco, and 217 fouth-

LEFEE's Uland, one of the New He-brides. The inhabitants of this ifland, according to Bougainville's account of them, " are of two colours, black and mutatto. Their lips are thick, their hair frizzled, and fome have a kind of wellow word, they are fault of yellow wool; they are fmall, ugly, ill-made, and in general devoured by the *leprofy*, which occafioned the diffeoverer Bougainville to call it the *Ifle of Lepers*: few women were feen, but they were altogether as difguiting as the men. They go naked, hardly covering their waifts with a mat." They carry their children on their backs in a kind of fearf. They wear ornaments in their noftrils; and have no beards. LE ROACH Ifland, is near Falk-Iand's Iflands; difcovered in 1657.

LES CAYES, a jurifdiction on the S. fide of the French part of the ifland of St. Domingo, contains 4 parifhes and yields abundance of fugar, cotton, and coffee. Its exports from the town Les Cayes from January 1, 1789, to Dec. 31, of the fame year, were 2, 597,666lb.white fugar ; 24,526,050 lb, brown fingar ; 5,025,604lb.coffee ; 855,447lb. cotton ; 169, 105lb. indigo; and fmall articles to the value of 8256 livres. The value of duties paid on the above on exportation 207,528 dollars, 85 cents. The town Les Cayes, lies between the villages Torbeck and Cavaillon, on the large bay which fets up to the island Avache; from which it is about 3 leagues diffant, and 5 leagues northerly of Point Aba-con. N. lat. 18, 12. W. long. from Paris 76. 8.

LETTERKENNY, a township in Franklin county, Pennfylvania.

LEVERETT, a township in Hamp-faire county, Maffachusetts, near Connecticut river, and 95 miles weft of Bofton. It was incorporated in 1774, and contains 524 inhabitants. A copper mine has been found in this townthip

LEVI, a point of land in the river St. Lawrence, opposite to the city of Quebec.

LEWIS, a town in Effex county, S. W. of Lemington, adjoining, in Ver-It is about 8 miles fouth of the nont Canada line.

LEWIS CREEK, in Vermont, a fmall ftream which falls into Lake Champlain

outh-weft of Philadelphia. N. lat. 18. | at Ferrifburg, a little north of the mouth of Little Otter Creek.

LEWIS'S BAY. See Barnftable Coun-ty, Maffachuletts.

LEWISBURG. See Louifbourg. LEWISBURG, a county in Orange-

burgh diffrict, S. Carolina,

LEWISBURGH, a poft- town of N. Carolina, and capital of Franklin county. The second secon tadelphia.

LEWISBURGH, a post-town, and the chief town of Greenbriar county, Virginia; fituated on the N. fide of Greenbriar river, contains about 60 houfes, a court-house and gaol. It is \$50 miles W. by N. of Richmond, and 486 W. by S. of Philadelphia. N. lat. 38. 8.

LEWISBURG for Tarflown, a town of Northumberland county, Pennfylvania; fituated on the weft fide of the Sulquehannah, 7 miles above Northumberland. It contains about 60 houles, and is well fituated for carrying on a brifk trade with the N. W. part of the State. It is 30 miles E. by N. of Aaronfburg.

LEWISTOWN, a plantation in Lincoln county, Diffrict of Maine, fituated on the eaft fide of Androfcoggin river, and bounded S.W. by Bowdoin. Lewiftown and Gore contain 532 inhabitants. It is 36 miles N. E. of Portland.

LEWISTOWN, or Lewes, a town in Suffex county, Delaware, is pleafantly fituated on Lewes creek, 3 miles above its mouth in Delaware Bay, and as far W. by N. of the light-house on Cape Henlopen. It contains a Prefbyterian and Methodift church, and about 150 houfes, built chiefly on a ftreet which is more than three miles in length, and extending along a creek, which feparates the town from the pitch of the cape. The fituation is high, and commands a full profpect of the light-house, and the fea. The court-house, and the gaol are commodious buildings, and give an air of importance to the town. The fitua-tion of this place must at fome future time render it of confiderable imporance. Placed at the entrance of a bay, which is crowded with veffels from all parts of the world, and which is frequently

It is fituate

ladelphia t

wildnernefs

the N. bra

contains a (

100 houfes.

nouth

Coun-

N. Caounty. mtains court-N. of m, 56 n Phi-

is 250 d, and N. lat.

a town of the orthumhoules, g on a t of the of Aa-

Lincoln ated on ver, and wiftown nts. It

town in leafantly es above nd as far on Cape byterian out 150 which is and ex*feparates* he cape. mands a , and the gaol are ve an air he fituae future e imporof a bay, from all a is frequently

LEX

quently clofed with ite a part of the winter feafon, neceffity feems to require, and nature feems to fuggeft, the forming this port into a harbour for fhipping. The deficiency of water in the creek, may be cheaply and eafily fupplied by a fmall canal to as to afford a paffage for the waters of Rehoboth into Lewes creek, which would enfure an adequate fupply. The circumjacent country is beautifully diverified with hills, woods, freams, and lakes, forming an agreeable contraft to the naked fandy beach, which terminates in the cape; but it is greatly infefted with mufketoes and fand-flies. It carries on a fmall trade with Philadelphia in the productions of the country. A manufacture of marine and glauber falts, and magnefia, has been lately eftablifhed here, which is managed by a gentleman fkilled in the practical knowledge of chemiftry. It is 113 miles fouth of Philadelphia. N. lat. 38. 6. W. long, 75, 18.

lat. 38. 6. W. long. 75. 18. LEWISTOWN, the chief town of Mifflin county, Pennfylvania, fituated on the northern fide of Juniatta river, on the W. fide, and at the mouth of Cifhicoquilis creek; a fhort way weft of the Long Narrows in Juniatta river, and about 23 miles north-cafterly of Huntingdon. It is regularly laid out, and contains about 120 dwelling-houfes, a court-houfe and gaol. It was incorporated in 1795, and is governed by two burgefies, one high conftable, a townelerk, and two affiftants. It is 150 miles W. N. W. of Philadelphia. N. lat. 40. 33. W. long. 77. 23.

LEWÜNAKHANNEK, a town on the Ohio, where Chriftian Indians fettled under the care of the Moravian miffionaries.

LEXAWACSEIN, a finall river of Pennfylvania, which rifes by feveral branches in Northampton county, Pennfylvania, on the east fide of Mount Ararat; these unite about 10 miles from its mouth in Delaware river. Its course is S. E. and east. It joins the Delaware about 174 miles above Philadelphia.

LEXINGTON, a post-town of Virginia, and capital of Rockbridge county. It is fituated on the post-road from Philadelphia to Kentucky, by way of the wildnernes, and about a mile fouth of the N. branch of "James's river. It contains a court-houle, gaol, and aboutsoo houses. The fituation of the town is healthy and agreeable, and the comtry round highly cultivated. It is 159 miles W. by N. of Richmond, 398 from Philadelphia, and 465 from Danville in Kentucky.

LEXINGTON, a post-town of Ken-tucky, and formerly the metropolis of that State. It is fituated on a rich extenfive plain, in Fayette county, on the north fide of Town Fork, a fmall ftream which falls into the fouth branch of Elkhorn river. It is built on a regular plan, and contains about 250 houles, 3 places of public worfhip, a court-houle and gaol. It contains 2 printing-offices, which publish 2 weekly gazettes; has feveral flores of goods well afforted, and is a flourishing, agreeable place. It is fituated in the midit of a fine tract of country, on the head waters of Elkhorn river, 24 miles east of Frankfort, and 774 S.W. by W. of Philadelphia. Its inhabitants are supposed to amount now (1796) to 2000; among whom are a number of very genteel families, af-fording very agreeable fociety. N. lat. 38. 6. W. long. \$5. 8. Near this town are found curious fepulchres full of human skeletons. It has been afferted that a man in or near the town, having dug 5 or 6 feet below the furface of the ground, came to large flat ftone, under which was a well of common depth, regularly and artificially ftoned. In the vicinity of Lexington are found the remains of two ancient fortifications, furnished with ditches and bastions, overgrown with large trees.

LEXINGTON, a county in Orangeburgh diffrict, S. Carolina.

LEXINGTON, formerly called the Great Falls, a fmall town of Georgia, fituated on the fouth fide of Ogeechee river, on a beautiful eminence which overlooks the falls of the river. It is z miles from Georgetown, and 30 from Greenfborough.

LEXINGTON, a town in Middlefex county, Maffachufetts, 10 miles N. W. of Bolton, having a neat Congregational church, and a number of compact houfes. It has been rendered famous by the battle fought in it, April 19, 1775, which may be confidered as the commencement of the American revolution. This townfhip contains 94 t inhabitants, and was incorporated in 1712.

LEYDEN, a township in Hampshire county, Massachusetts, between Colerain S 2 and and Bernardflon, 29 miles from Northampton, the fhire town, and 117 N. W. of Bofton. It was incorporated in 1784, and contains 989 inhabitants.

LEZARS, an Indian nation, who inhabit between the mouth of the Ohio and Wabash rivers. They can furnish yoo warriors.

LIBERTY, a post-town of Virginia, 15 miles from New London, 35 from Fincastle, 40 from Franklin court-house, and 65 from Martinsburg.

and 65 from Martinfburg. LIBERTY-TOWN, a village of Maryland, fituated in Frederick county, 10 miles north-eaft of Frederick flown, and about 44 N.N.W. of the Federal City. Copper mines have been found near this town, and have been worked; but to no great extent as yet. LICHTENAU, a Moravian fettlement

LICHTENAU, a Moravian fettlement on the eaft fide of Mulkingum river, 3 miles below Goschachguenk; but as the, warriors passed constantly through this place, it was forsaken, and they removed to Salem, 5 miles below Gnadenhuetten.

LICE, a name by which falt fprings are called in the weftern parts of the United States. See Big Bone Lick.

LICKING, a navigable river of Kentucky, which rifes on the weftern confines of Virginia; interlocks with the head waters of Kentucky river; runs in a N. W. direction upwards of 180 miles, and by a mouth 150 yards wide flows through the fouth bank of Ohio river, opposite fort Washington. Upon this river are iron-works, and numerous falt fprings. Its principal branch is navigable nearly 70 miles. From Limeflone to this river, the country is very rich, and covered with cane, rye-grafs, and natural clover.

LIGONIER, Fort, lies on the road from Philadelphia to Pittfburg; 266 miles from the former, and 54 from the latter, and 9 miles from the E. fide of Laurel Hill.

LIGUANEA, mountains in the island of Jamaica. At the foot of thefe in St. Andrew's parish, about fix miles from Kingston, is the most magnificent botanical garden in the world. It was eftablished in 1773, under the fanction of the affembly. The fortune of war having thrown into Lord Rodney's hands many rare plants, he prefented to his favoured island plants of the genuine cinnamon, the mango, bread-fruit, and

other oriental productions; which are now become common in the ifland. See Cold Spring.

See Cold String. LILLIE, a citadel at Cape Ann, in the townfhip of Gloucester, Massachufetts.

LIMA, the middle division of Peru, in South America. It has Quito on the north, the mountains called the Andes on the east, the audience of Los Charcos on the fouth, and the Pacific ocean on the west. There are many wild beasts in the audience.

LIMA, the capital of Peru, in S. America, is also called Los Reyes, or the City of Kings, and is the emporium of this part of the world. It was founded by Don Francisco Pizarro, on the 18th of January, 1535; is fituated in a large, spacious, and fertile plain, called the valley of Rimac, on the fouth fide of the river Rimac, which runs weftward. The name of Lima being only a corrupt pronunciation of the Indian word, which is derived from an idol to which the Indians and their Yncas used to facrifice, This idol being supposed to return anfwers to the prayers offered to it, they called it, by way of diffinction, Rimac, i. e. the fpeaker.

It is fo well watered by the river Rimac, that the inhabitants command a ftream, each for his own use. The N. fide of the town runs nearly close to the river for the length of about 10 furlongs. At about 4 of this space, from the western extent, an elegant ftone bridge of 4 or 5 arches is built across the river leading fouth, about 200 yards to the great fquare, of which the fide is about 140 vards. The ftreet continues fouth from the bridge, for near a mile, having parallel ftreets, 8 to the weft, and 6 to the eaft, belides other freets which run obliquely fouth-eastward. The fifteen ftreets, running north and fouth, are croffed by eight others running eaft and weft, befides feveral to the fouthward, not parallel to the former, and others in the eaftern parts, which have different directions. The figure of the town is nearly quadrilateral. A diagonal line running east and weft, would be 18 fur-longs in length; and the fouthern perpendicular, about 7 furlongs, and the northern about 4 furlongs; fo that the city flands on a fpace of ground nearly equal to a mile and a quarter fquare. The northern fide for about three quarters

ers of a m moftly by cuit is incl and their whole is f furrounded vered way, gates, befid a commu country. from Calls Lima, and The white at about 1 of inhabita remarkable ftrate the the viceroy his entry in bitants, to freets to b amounting travellers f decoration filver, and and ornam only thing counts, is 1 five comm merchants with all th that both (factors for ductions o conveyed, the harbou the inhabit The fleet ! dies land a commoditi America, other. Bu tants, all (the fertilit infufficient ter which actually be very frequ Since th pened abo that on th half an ho and three moon; wh that in li the greated great and deftroyed those inha

、火力性活动

ifland. nn, in flachu-Peru, on the Andes Charc ocean y wild h S. A. or the rium of founded the 18th a large, lled the le of the eftward. corrupt d, which the Inacrifice, turn anit, they Rimac, iver Rinmand a The N. furlongs. the weftdge of 4 ver leadthe great bout 140 s fouth e, having and 6 to hich run he fifteen

outh, are

east and

uthward,

others in

different

e town is

gonal line

ne 18 fur-

hern per-

, and the

o that the

and nearly

r square.

hree quar-

ters

ch are

moftly by redans; the reft of the circuit is inclosed with 34 hollow baftions and their intermediate curtains. The whole is faced with a brick wall, and furrounded with a ditch, but has no covered way, glacis, nor outworks. Eight gates, befides that at the bridge, furnifh a communication with the adjacent country. The city ftands about 6 miles from Callao, which is the fea-port to Lima, and 180 north weft of Guamanga. The white people in Lima are estimated at about 15,000, and the whole number of inhabitants are about 60,000. One remarkable fact is fufficient to demonftrate the wealth of this city. When the viceroy, the Duke de la Palada, made his entry into Lima, in 1682, the inhabitants, to do him honour, cauled the ftreets to be paved with ingots of filver, amounting to 17 millions fterling. All travellers speak with amazement of the decorations of the churches with gold, filver, and precious stones, which load and ornament even the walls. The only thing that could juftify these accounts, is the immense riches and extenfive commerce of the inhabitants. The merchants of Lima may be faid to deal with all the quarters of the world ; and that both on their own account, and as factors for others. Here all the productions of the fouthern provinces are conveyed, in order to be exchanged at the harbour of Lima, for fuch articles as the inhabitants of Peru ftand in need of. The fleet from Europe and the East-Indies land at the fame harbour; and the commodities of Afia, Europe, and America, are there bartered for each other. But all the wealth of the inhabitants, all the heauty of the fituation, and the fertility of the climate of Lima, are infufficient to compensate for the difafter which threatens, and has fometimes actually befallen them. Earthquakes are very frequent.

LIM

ters of a mile next the river, is fortified

Since the year 1582, there have happened about fifteen concuffions, befides that on the 28th of October, 1746, at half an hour after 10 at night, five hours and three quarters before the full of the moon; which began with fuch violence, that in little more than three minutes, the greateft part, if not all the buildings, great and fimall, in the whole city, were deftroyed; burying under their ruins thole inhabitants who had not made fuf-

STYRINGS .

LIM

277

ficient hafte into the fireets and fouares. the only probable places of fatety in those terrible convulsions of nature. At length the dreadful effects of the first flock ceafed, but the tranquillity was of flort duration ; concuffions returning fo repeatedly, that the inhabitants, according to the account fent of it, computed 200 in the first 24 hours; and to the 24th of February, the following year, 1747, when the narrative was dated, no lefs than 450 flocks were observed a lome of which, if lefs permanent, were equal to the first in violence. The fort of Callao, at the very fame hour, tumbled into ruins. But what it fuffered from the earthquake in its buildings, was inconfiderable, when compared with the terrible cataftrophe which followed. For the fea, as is usual on fuch occafions, receding to a confiderable diffance, returned in mountainous waves, foaming with the violence of the agitation, and fuddenly overwhelm-ed Callao and the neighbouring country. This was not, however, perform-ed by the first fwelling of the waves : For the fea retiring further, returned with ftill greater impetuofity, the flu-pendous water covering both the walls and other buildings of the place; fo that whatever had efcaped the firff, was now totally overwhelmed by those terrible mountains of waves; and no thing remained, except a piece of the wall of the fort of Santa Cruz, as a memorial of this terrible devastation. Here were then 23 fhips and veffels, great and finall, in the harbour, of which 19 were funk, and the other four, among which was a frigate called St. Fermin, carried by the force of the waves to a confiderable diffance up the country. See Callao. This terrible inundation extended to other parts of the coaft, as Cavallos and Guanape; the towns of Chancay, Guaura, and the vallies Della Baranco, Sape, and Pativilca, underwent the fame fate as the city of Lima. According to an account fent to Lima after this accident, a volcano in Lucanos burft forth the fame night, and ejected fuch quantities of water, that the whole country was overflown; and in the mountain near Patas, called Converfiones de Caxamarquilla, three other volcanoes burft, discharging frightful torrents of water; and in the fame manner as that of Carguayraffo. Lima \$ 3

is the lee of an archbishop, and the feat of an university. The inhabitants are very debauched; and the monks nd nuns, of whom there are great numbers, are no more chafte than the reft of the inhabitants. If any one happens to rival a monk, he is in danger of his life, for they always carry daggers con-cealed. Lima, according to feveral obfervations made for that purpole, flands in lat. 12. 2. 31. S. and its long. is 75. 52. W. The variation of the needle is 9. 2. 30. eafterly.

LIMBE, a village in the N. W. part of the illand of St. Domingo, 7 leagues weft by fouth of Cape Francois.

LIMERICE, a township in York co. Maine, fituated near the confluence of Little Offipee river with Saco, and oppolite Gorham in Cumberland county. It was incorporated in 1787, contains 411 inhabitants, and is 114 miles northcrly of Bofton.

LIMERICK, a township in Montgomery county, Pennfylvania.

LIMESTONE CREEK, in Tenneffee, is the north-eaftern branch of Nolachucky river. It rifes 22 miles fouth of Long-Island in Holfton river.

LIMESTONE, a post town in Kentucky, fituated on the fouth fide of Ohio river, and on the weft fide of the mouth of a finall creek of its name. It ftands on a lofty and uneven bank, and is not feen from the river until one is within 2 miles of it. This is the ufual landing-place for people coming down in boats, who mean to fettle in the upper parts of the State; and here the champaign country on the eaftern fide of the river begins. It is 4-miles northeast of the town of Washington, 45 fouth-west of Fort Washington, 44 S. W. by S. of Bourbontown, and 500 miles below Pittfburg. N. lat. 38. 40. W. long. 84. 17.

LIMONADE, a village on the north fide of the French part of the island of St. Domingo, 4 leagues fouth-west of Fort Dauphine, and 71 measuring in a ftraight line fouth-east of Cape Francois. N. lat. 19. 37.

LINCOLN, a large maritime county of the Diffrict of Maine; bounded northby Canada, fouth by the ocean, east by Hancock county, and well by that of Cumberland. Its fea-coaft extends from that part of Penobicot Bay opposite to Deer Ifiand eaftward, to Cape Small | Crab-Orchard.

Point weftward. It is 200 miles long and 54 broad, and comprehends 4 towns and plantations; but there are large tracts yet unfettled. The population amounts to 29,962 free perfons. The fea-coaft of the counties of Cumberland and Lincoln is 100 miles in extent, measured, in a straight line, but is faid to be above 200 by the course of the waters. It abounds with fafe and commodious harbours; and the whole fhore is covered by a line of iflands, among which veffels may generally anchor in fafety. There are in these counties many large rivers, fome of them navigable far up the country; and although navigation for large veffels is interrupted by falls, when far up the rivers, yet above the falls, there is plenty of water for boats, nearly to the fource of the rivers; and by the lakes and ponds and branches of the rivers, there is a water communication, with few interruptions, from the weftern to the caltern bounds, acrois the country, above the centre of it. By this route its productions may, at a imall expense, be transported to the different fea-ports. The fupreme judicial court held in Lincoln county, has civil and criminal jurifdiction in caufes ariling in Hancock and Washington counties. Chief towns, Pownalborough, Hallowell and Waldoborough.

LINCOLN, a county of Morgan diftrict, North-Carolina bounded N. E. by Iredell, N. W. by Burke, weft by Rutherford, and eaft by Cabarras. It contains 9224 inhabitants, of whom 935 are flaves. Here are mineral fprings and mines of iron. A furnace and forge have been erected, which carry on the manufacture of pig, bar iron, &c. Chief town, Lincolntown.

LINCOLN, a county of Kentucky, bounded N. by Mercer, N. W. by Washington, N. E. by Maddison, and S. by Logan. By the cenfus of 1790, it contained 6548 inhabitants, of whom 1094 were flaves. The road from Danville on Kentucky river paffes thro' it fouth-wefterly, and over Cumberland mountain to Virginia.

LINCOLN, a town in Mercer county, Kentucky, fituated on the east fide of Dick's river, on the road from Danville to Virginia. It ftands 12 miles foutheast of Danville, and 11 north-west of

LINCOL county, N in 1764, c LINCON ern part o granted N LINCO county, M 1754. It is 16 mile LINCO laid out in Savannah tle rivers. LINCO Carolina, It contain house, an Morganto fouth by LINDL of the Ca er, in Ne Pennfylva Painted I on the ros LINN, county, F

LINNE LISBO

county, Norwich, Norwich. having a on the we eaft of FI LISBO Pennfylv fide of 1 falls into about 15

> York. LITCH county, J

Hallowel LITCH rough co ed on the about 50 It was fo contained bitants.

LITC county o by the S New Ha by Hart New-Yo thips, co

\$ 78

LINCOLN, a township in Grafton county, New-Hampshire, incorporated in 1764, contains 22 inhabitants.

les long

nds 46

nere are

popula-perfons. Cum-s in ex-, but is purfe of afe and iflands, ally an-n thefe fome of ountry;

rge vef-hen far

e falls,

s, nearand by is of the lication,

he weft-rols the

By this

a fmall

different

al court

wil and

rifing in ounties.

Hallo-

gan dif-

N. E.

weft by

ras. It

nom 935

fprings

nd forge

on the

. Chief

ntucky,

W. by ion, and of 1790, of whom d from fes thro' nberland

county,

fide of

Danville s fouth-

-west of

NCOLN,

LINCOLN, a township in the northern part of Addison county, Vermont, granted Nov. 7, 1780.

LINCOLN, a township in Middlefex county, Maffachufetts, incorporated in 1754. It contains 740 inhabitants, and is 16 miles north-weft of Bofton.

LINCOLN, a new co. of Georgia, laid out in 1796, from Wilkes co. on Savannah river, between Broad and Little rivers.

LINCOLNTOWN, a post-town of N. Carolina, and capital of Lincoln county. It contains about 20 houfes, a courthouse, and gaol. It is 46 miles from Morgantown, 159 from Salem, and 718 fouth by weft of Philadelphia.

LINDLEY, a village on the west fide of the Canawifque branch of Tioga river, in New-York, 2 miles north of the Pennfylvania line, 8 S.W. by S. of the Painted Poft, 64 fouth-east of Hartford, on the road to Niagara.

LINN, a township in Northampton county, Pennfylvania.

LINNELINOPIES. See Delaquares. LISBON, a town in New-London county, Connecticut, lately a part of Norwich, about 7 miles northerly of Norwich. It contains 2 parifies, each having a congregational church. It lies on the weft fide of Quinebaug river, and eaft of Franklin.

LISBON, a village of York county, Pennfylvania, fituated near the fouth fide of Yellow Breeches creek, which falls into the Sufquehannah. It contains about 15 houfes, and lies 18 miles from York.

LITCHFIELD, a township in Lincoln county, District of Maine, 45 miles from Hallowell, and 220 N.E. of Bofton.

LITCHFIELD, a township in Hillsborough county, New Hampfhire, fituated on the east fide of Merrimack river, about so miles wefterly of Portfmouth. It was fettled in 1749, and in 1775 it contained 284, and in 1790, 357 inhabitants.

LITCHFIELD, a popoulous and hilly county of Connecticut; bounded north by the State of Maffachufetts, fouth by New Haven and Fairfield counties, eaft by Hartford, and weft by the State of New-York. It is divided into 20 townthips, containing 38,755 inhabitants, inLIT

tirely from maritime commerce and the inhabitants are almost universally farmers.

LITCHFIELD, the chief town of the above county, fituated upon an elevated plain, and much exposed to the cold winds of winter, but enjoys alfo a large fhare of the refreshing breezes of fummer. It is a handsome fituation, containing about 60 or 70 dwelling-houfes, a court-house and meeting-house. It is 32 miles weft of Hartford, and 42 N.N. W. of New-Haven. N. lat. 41. 46. W. long. 73. 37. In the S. W. cor-mer of the township stands an high hill called Mount Tom. On feveral finall ftreams, fome of which fall into Great Pond, are 3 iron works, an oil mill and a number of faw and grift mills.

LITCHFIELD, a township in Herke-mer county, New-York taken from German Flats, and incorporated in 1796.

LITIZ, or Leditz, a village or town in Lancaster county, Pennsylvania, situated in Warwick township, on the fouth fide of a fmall stream, which fends its waters through Coneftoga creek into the Sufquehannah. It contains about so houses chiefly of stone, a stone tavern, and an elegant church with a flee-ple and bell. The fettlement was begun in 1757. It is inhabited by the United Brethren, whole mode of life and cuftoms are fimilar to these of Bethlehem. There is also a good farm and feveral mill works belonging to the place. The number of inhabitants, including those that belong to Litiz congregation, living on their farms in the neighbourhood, amounted, in 1787, to upwards of 300. It is 8 miles north of Lancaster, and 66 W. by N. of Philadelphia.

LITTLE EGG HARBOUR, a port of entry on the east coast of New-Jerfey, comprehending all the fhores, bays and creeks from Barnegat Inlet to Brigantine Inlet, both inclusive. The town of Tuckerton is the port of entry for this district. See Egg.

LITTLE ALGOMQUINS, Indians who inhabit near the Three Rivers, and can raife about 100 warriors.

S 4

LITTLE-

LITTLEBOROUGH, a plantation in | Lake Ontario, about 1 5 miles fouthward Lincoln county, District of Maine, having 263 inhabitants.

LITTLE BRITAIN, a township in Lancaster county, Pennfylvania. Also a township in Chefter county, in the fame State.

LITTLE-COMPTON, a township in Newport county, Rhode-Ifland, bound-ed N. by Tiverton; S. by the Atlantic ocean, where are Seakonnet rocks; W. by the caft paffage into Mount Hope Bay; and E. by the State of Maffachufetts. It contains 1542 inhabitants, of whom 23 are flaves. It was called Seconnet or Seakonnet by the Indians, and is faid to be the best cultivated township in the State, and affords greater quan-tities of meat, butter, cheele, vegetables, &c. than any other town of its fize. The inhabitants are very industrious, and manufacture linen and tow cloth, flannels, &c. of an excellent quality, and in confiderable quantities for fale.

LITTLE FORT, in the N. W. Ter-ritory, flands on the fouth-western bank of Lake Michigan, and on the south fide of Old Fort river, which runs a northeastern courfe into the lake. See Chi

LITTLE HARBOUR. See Pascataqua. It is near the mouth of Palcataqua river, about a mile from Portf-mouth, in New-Hampshire. A settlement was attempted here in 1623.

LITTLE MECATINA. See Mecatina. LITTLE PELICAN. See Pelican. LITTLE RIVER, in Georgia, is a beautiful and rapid river, and at its confluence with Savannah river, is about 50 yards wide. On a branch of Little river is the town of Wrightsborough. Also a river which feparates, in part, N. and S. Carolina.

LITTTLE RIVER, a plantation in Lincoln county, District of Maine, containing 64 inhabitants.

LITTLE ROCKS, on the N.W. bank of Hlinois river, are fituated 60 miles from the Forks, 270 from the Miffifippi river, and 43 S.W. of For river. The S.W. end of these rocks lies nearly oppolite to the mouth of Vermilion river, and the two finall ponds where the French and Indians have made good falt, lie opposite to the N.E. end. A coal mine half a mile long extends along the bank of the river above these rocks.

of Ofwego.

LITTLETON, a township in Middlefex county, Maffachufetts, 30 miles N. W. of Bofton.

LITTLETON, a township in Grafton county, New Hampfhire, (1 part of Ap-thorpe) was incorporated in 1784, and contains 96 inhabitants. It lies on Connecticut river, below the 15 mile Falls, and nearly opposite Concord in Vermont.

LITTLETON, a township in Caledonia county, Vermont, on the W. fide of Connecticut river, opposite the 15 mile Falls, and contains 63 inhabitants.

LITTLETON, a township of Massa-chusetts, in Middlefex co. 28 miles N.W. of Bofton. It was incorporated in 1715, and contains 554 inhabitants.

LITTLETON, FORT, in Pennfylva-nia, is 27 miles E. of Bedford, 39 S.W., by W. of Carlifle, and 34 N. by E. of Fort Frederick, in Washington county, Maryland.

LIVERMORE, a plantation in Cum-berland county, Diffrict of Maine, fi-tuated on Andro/coggin river, 19 miles N.W. of Hallowell.

LIVERPOOL, a town on the S. fide of the Bay of Fundy, in Queen's county, Nova-Scotia, fettled by New-England-ers. Roffignol, a confiderable lake, lies between this town and Annapolis. It is 32 miles N. E. of Shelburne, and 58 N. W. of Halifax. It was formerly called *Port Roffignole*.

LIVINGSTON, a township in Colum-bia county, New York, fituated on the eaft bank of Hudson's river, 4 miles northerly of Palatine town, 11 fouth of Hudson, and 9 south-eaft of Claverack. It contains 4594 inhabitants ; of whom 659 are electors, and 233 flaves.

LIVINGSTON's Creek, a confiderable branch of North-Weft, an arm of Cape Fear river. This creek heads in vaft fwamps in the vicinity of the beautiful lake Waukama.

LOBOS, iflands on the coaft of Brazil. The fouthernmost island is in S. latitude 6. 27. One of these islands obtains the name of Lobos de la mer; the other, which lies to the north of it, and very like it in fhape and appearance, is called Lobos de tierra.

LOCKE, a military township in New-York State, adjoining to Milton on the LITTLE SODUS, a fmall harbour of | eaft, fituated in Onondago county. The centre

centre of th the S. end .

LOCKAR county, P fthmus for the Sulque bout a mile are as yet mifes to l both the r miles into is 4 miles nearly 48 above Wil LOGAN Kentucky LOGST the Ohio, and 18 mi LOGW of the Mo the Bay of Vera Paz 181 N. la fpread wit the navig LOND oounty, I Annapoli LOND Long-Ifa into the miles we river. M another acrofs w with a di LOND Rocking fituated which e at Pawtu by W. was fett 1722, a The peo of emig Uliter c from Sc manufad and ma fale. Them for LON lifax co the N.

river, a the baf the Nor hward

iddle

les N.

rafton

of Ap.

, and

Falls,

Ver-

edonia

ide of

5 mile

Maffa.

N.W.

1715,

nfylva-

S.W.

E. of

ounty,

Cum

ne, fi-

miles

fide of

ounty

gland-

ce, lies

. It is

and 58

rmerly

Colum-

on the miles

outh of

erack.

whom

lerable

f Cape in vaft

autiful

f Bra-

in S.

iflands

a mer;

arance,

New-

on the

centre

centre of the town is 13 miles N. E. of the S. end of Cayuga lake. See Milton. LOCKARTSBURG, a town in Luzerne county, Pennfylvania, fituated on an ifthmus formed by the confluence of the Sufquehannah and Tioga rivers, ahout a mile above their junction. There are as yet few houfes built, but it promifes to be a place of importance, as both the rivers are navigable for many miles into the State of New York. It is 4 miles fouth of the New-York line, nearly 48 wefterly of Harmony, and 90 above Wilkfbarre.

LOGAN, a new county in the State of Kentucky.

LOGSTOWN on the western fide of the Ohio, lies fouth of Butler's Town, and 18 miles from Pittsburg.

LOGWOOD COUNTRY, lies N. W. of the Molquito Shore, at the head of the Bay of Honduras, and extends from Vera Paz to Yucatan from 15¹/₂ to 18¹/₂ N. lat. The whole coaft is overfpread with iflots, keys and fhoals, and the navigation is intricate.

LONDON, a town in Aun Arundel county, Maryland, 5 m'les S. W. of Annapolis.

LONDON COVE, a narrow water of Long-Ifland Sound, which fets up north into the township of New-London, 4 miles west of the mouth of Thames river. Millstone Point separates it from another much broader on the west, across which is a handsome bridge, with a draw at Rope Ferry.

LONDONDERRY, a post-town in Rockingham county, New-Hampshire, fituated near the head of Beaver river, which empties into Merrimack river, at Pawtucket Falls. It is 38 miles S. W. by W. of Portimouth. Londonderry was fettled in 1718, and incorporated 1722, and contains 2590 inhabitants. The people are mostly the descendants of emigrants from it, came chiefly from Ulfter county in Ireland, or originally from Scotland, and attend largely to the manufacture of linen cloth and thread, and make confiderable quantities for fale. The town is much indebted to them for its wealth and confequence. LONDONDERRY, a township in Halifax county, Nova-Scotia, fituated on the N. fide of Cohequid or Colchefter river, about 30 miles from its mouth, at the bafin of Minas. It was fettled by the North Irifh and Scotch.

LONDONDERRY, a township, and the north-westernmost of Windham county, Vermont, on the head waters of West river, about 33 miles N. E. of Bennington. It was granted March 15, 1780. Moofe Mountain extends into the eastern part of this town. LONDONDERRY, the name of two townships in Pennfylvania, the one in Chelter county, the other in that of Dauphine.

LONDONGROVE, a township in Dauphine county, Pennfylvania.

LONG Bay, extends along the flore of N. and S. Carolina, from Cape Fear to the mouth of Pedee river.

LONG Bay, on the fouth fide of the ifland of Jamaica, extends from Gutt to Swift river, and affords anchorage for fmall veffels.

LONG Bay, in the island of Barbadoes, in the West-Indies, lies on the west fide of the island, having St. Jofeph's river fouth-easterly, and Pico Tenerisfe north-westerly. Another bay of the fame name lies on the fouth end of the island, about a miles easterly of the fouth point.

the fouth point. LONG Ifland, in Penoblecot bay. See Iflefborough.

Idefborough. LONG, or Eighteen mile Beach, on the coaft of New-Jerfey, lies between Little Egg harbour inlet and that of Barnegat.

LONG Island, formerly called Manbattan, afterwards Naffau Ifland, be-longs to the State of New-York. It extends from Hudson's river opposite to Staten-Island, almost to the western bounds of the coast of Rhode-Island, terminating with Montauk Point. Its length is about 140 miles, and its medium breadth not above 10 miles; and feparated from Connecticut by Long-Ifland Sound. It contains 1,400 fquare miles; and is divided into 3 counties, King's, Queen's and Suffolk, and thefe again into 19 townships. The N. fide of the island is rough and hilly. A fingle range of these hills extends from Jamaica to Southhold. The foil is here well calculated for raifing grain, hay, and fruit. The fouth fide of the ifland lies low, with a light fandy foil. On the fea-coaft are extensive tracts of fait meadow, which extend from Southampton to the west end of the fland. The foil, notwithstanding, is well adapted to the culture of grain, particularly Indian corn. Near the middle of the ifland is Hampftead LON

Hampflead Plain, in Queen's county. It is 16 miles long, and about \$ broad. This plain was never known to have any natural growth, except a particular kind of wild grafs, and a few fhrubs, although the foil is black, and to appearance rich. It produces fome rye, and large herds of cattle are fed upon it, as well as on the fait marfles. On the E. part of the ifland, E. of Hampflead Plain, is a large ifland, E. of Hampstead Plain, is a large barren heath, called Brushy Plain: It is overgrown with thrub-oak, intermixed with a few pine trees, where a number of wild deer, and groufe harbour. The largeft river, or fiream in the island is Peakonok, an inconfiderable ftream. It runs E. and empties into a large bay, that feparates Southhold from Southampton. In this bay are Robbin and Shelter iflands. Rockonkama pond lies about the centre of the island, between Smith-Town and Islip, and is about a mile in circumference, and has been found, by observation, to rise gradually for several years, until it had arrived to a certain height, and then to fall more rapidly to its loweft bed; and thus is continually ebbing and flowing : The caufe has never been inveftigated. Two miles to the fouthward of the pond, is a fream called Connecticut river, which empties into the bay. The produce of the middle and western parts of the island is carried to New-York. The ifland contained, in 1790, 41,782 inhabitants, of whom 4,839 were flaves.

LONG-ISLAND Sound is a kind of inland fea, from 3 to 25 miles broad, and about 140 miles long, extending the whole length of the ifland, and dividing it from Connecticut. It communia cates with the ocean at both ends of Long-Ifland; and affords a very fafe and convenient inland navigation.

LONG-ISLAND, an ifland in Sulquehannah river.

LONG-ISLAND, in Holfton river, in the State of Tenneffee, is 3 miles long. Numbers of boats are built here every year, and loaded with the produce of the State for New-Orleans. Long-Island is so miles W. of the mouth of Wataugo river, 43 from Abingdon, 100 above Knoxville, 283 from Nafhville, and 1000 from the mouth of the Tenneffee. It is 340 miles S. W. by W. of Richmond, in Virginia, and to which there is a good waggon road.

LONG ISLE, or Ifte River Indians,

38. 58. W. long. 90. 7. LONG LAKE, in the Geneffee country in New-York. See Honeyyog Lake. LONG-MEADOW, a town in Hamp-thire county, Maflachufetts, fituated on the E. bank of Connecticut river, about 4 miles S. of Springfield, and 23 N. of Hartford. It was incorporated in 1788.

Hartford. It was incorporated in 1783; contains a Congregational church, and about 70 dwelling houses, which lie upon one wide street, running parallel with the river. The township contains 744 inhabitants. It is 97 miles S. W. by W. of Bofton.

LONG POINT, a peninfula on the N. fide of Lake Eric, and towards the eaftern end of the lake. It is compoled of fand, and is very convenient to haul boats out of the furf upon, when the lake is too rough for rowing or failing. Vermilion Point, between Puan Bay and Lake Michigan, is alfo called Long Point in fome maps.

LONG POND, in the Diffrict of Maine, lies mostly in Bridgton, and is 10 miles long from N. W. to S. E. and about a mile broad. On each fide of this pond are large fwells of excellent land, with a gradual defcent to the margin of the pond, and furnish a variety of romantic prospects. See Bridgton and Sebago.

LONGUILLE, or as the Indians call it, Kenapacomaqua, an Indian village on the N. bank of Eel river, in the N. W. Territory. It was deftroyed by Gen. Scott in 1791, with 200 acres of corn in its neighbourhood.

LOOKOUT, Cape, on the coaft of N. Carolina, is the fouthern point of a long infulated and narrow flip of land, eaftward of Core Sound. Its N. point forms the S. fide of Ocrecock inlet, which leads into Pamlico Sound, It lies N. E. of Cape Fear, and S. of Cape Hatteras, in about latitude 34. 50. It had an ex-cellent harbour, which has been filled up with fand fince the year 1777.

LOOKOUT, Cape, on the fouthern coaft of Hudson's Bay, in New South Wales, E. S. E. of the mouth of Severn river. N. lat. 56. W. long. 84. LOOSA CHITTO. See Loufa Chitto. LOREMBEC. See Louistourg. It is

a cape near the N. fide of Louisbourg harbour, and may be feen 12 leagues off at fea.

LORENZO,

LOREN Peru, S. A of Quito, S. lat. 0.2 LORET tian India

bec, in Ca a chapel b the Santa

from whe Virgin ha here, refe Italian iat of the Hu LORET diffrict of California Here is a fionaries, furrounde LOROI N. W. c from For fork of a river wh this spot line, the to the Ur the treaty the port Miami o ver, whi Los I Los F province of Parag Los fouthern cities an Loui country Block-H

Loui the rive Berkley about 5 contains 4,030 1 Lou county, Cantert in 1773

Merrim mouth, Lou county of Len 124 W ed in a 1.14

LOREWZO, Cape St. on the coaft of Peru, S. America, hies in the province of Quito, W. of the city of that name. LOUGHABER, or Lochaber, a fmall

S. lat. 0.20. W. long. 80. 20. LORETTO, a fmall village of Chrif-tian Indians, 3 leagues N. E. of Que-bee, in Canada. It has its name from a chapel built according to the model of the Santa Cafa at Loretto, in Italy; from whence an image of the Holy Virgin has been fent to the converts here, refembling that in the famous Italian fanctuary. These convents are of the Huron tribe.

LORETTO, Lady of, a place in the diftrict of St. Dennis, on the ifthmus of California; the Indians call it Cancho. Here is a fmall fort erected by the miffionaries, confifting of four baftions, and furrounded by a deep ditch. LOROMIE'S STORE, in the territory

N. W. of the Ohio, a place westerly from Fort Lawrence, and at or near a fork of a branch of the Great Miami river which falls into the Ohio. At this spot, bounded W. by the Indian line, the Indians ceded a tract of land to the United States, 6 miles iquare, by the treaty figned August 3, 1795. Here the portage commences between the Miami of the Ohio, and St. Mary's river, which runs into Lake Erie.

LOS REYES. See Lima.

LOS REYES, the chief town of the province of Uragua, in the E, division of Paraguay, in S. America.

LOS CHARCOS, a province in the fouthern division of Peru, whole chief cities are Potofi and Porco.

LOUDON, Fort, a fort creeted in the country of the Cherokees. See Tellico Block-Houfe.

LOUDON, a county of Virginia, on the river Potowmac, adjoining Fairfax, Berkley, and Faquier counties. It's about 50 miles long, and 20 broad, and contains 18,962 inhabitants, including 4,030 flaves. Chief town, Lechburgh.

LOUDON, a township in Rockingham county, New-Hampfhire, taken from Canterbury township and incorporated in 1773. It is fituated on the E. fide of Merrimack river, 40 miles from Portfmouth, and contains 1084 inhabitants. LOUDON, a township in Berkshire county, Maffachusetts, 21 miles S. E. of Lenox, 24 W. of Springfield, and 124 W. of Bofton. It was incorporated in 1673, and contains 344 inhabit-40.265 .

which, 2,944 are ponds. LOUGHABER, or Lochaber, a finall fettlement in Georgia, on a branch of Savannah river, above its confluence with the Tugulo, the W. main branch, LOUIS, Fort, a fettlement formed by the French near the mouth of the river

Coza, in Florida, about 20 leagues N. E. of the nearest mouth of the Miffifippi, and until the peace of 1763, was the ufual refidence of the principal governor of Louifiana.

Louis, St. the capital town of Guadaloupe, Grand-Terre. It has a for-trefs 3 leagues to the S. E. of the Salt river. See Guadaloupe.

LOUIS DE MARANHAM, ST. a town on the northern coaft of Brazil, and on the Atlantic ocean, fituated on the eaft fide of Mearim river; about half way between point Mocoripe, and the mouth of the river Para.

Louis, ST. a jurifdiction and town on the fouth fide of the ifland of St. Demingo. The jurifdiction contains 3 parifhes. Its exports fhipped from the town of St. Louis from Jan. 1, 1789 to Dec. 31, of the fame year, were 120,665 lb. coffee; 19,253 lb. cotton; 5,751 lb. indigo. Total value of duties on exportation, 904 dollars 13 cents. St. Louis is rather a borough than a town. It is fituated on the head of the bay of its name, opposite a number of fmall ifles which thetter the bay on the fouth towards the ocean, and on the S. fide of the fouth peninfula, 8 leagues N. E. of Les Cayes, a little more than 3 S. W. of Aquin, and 36 leagues S. W. by W. of Port au Prince: from which last are two roads leading to it : the one by Jacmel, the other by Leogane, and of much the fame length; both join at Aquin. N. lat. 18. 18. W. long. from Paris 75. 52.

Louis, ST. a imall, compact, beautiful bay in W. Florida, having about 7 feet water. It is 18 miles from the Regolets, and 26 from the bay of Biloxi. The land near it is of a light foil, and good for patture. There were feveral fettlers formerly on it, but in the year 1767, the Chactaw Indians killed their cattle and obliged them to remove."

Louis, ST. a Spanish village on the W. fide of the river Miffifippi, about 13. miles below the mouth of the Miffouri. Its feite is on a high piece of ground, the

ies off ENZO,

which

abat N. lat.

ountry Hamp ted on

about N. of

1783 h, and lie up-

arallel

ontains

S. W.

the N.

le caftofed of

b haul

en the ailing.

ay and

Long

Maine.

miles bout a

s pond, with

of the

mantic

ebago. ns call

village

the N.

ed by

cres of

of N.

a long

eaft-

forms

h leads

E. of

ras, in

an ex-

filled

athern

South

Severn

Chitto.

It is

bourg

the most healthy and pleafurable of any known in this part of the country. Here the Spanish commandant and the principal Indian traders refide; who, y conciliating the affections of the natives, have drawn all the Indian trade of the Miffouri ; part of that of the Mifflippi (northwards) and of the tribes of Indians refiding near the Ouifconfing, and Illinois rivers, to this village. About 20 years ago there were here 120 large and commodious houses, mostly built of ftone, and 800 inhabitants, chiefly French. Some of them have had a liberal education, and were polite and hospitable. They had about 1 50 negroes, and large flocks of cattle, &c. It is 4 or 5 miles N. by W. of Caho-kia, on the east fide of the Missippi, and about 150 miles W. by S. of Poft St. Vincent's, on Wabash river. N. lat. 38. 24. W. long. 92. 32.

LOUISA, a county of Virginia, adoining Orange, Albemarle, Fluvanna, pottfylvania, and Goochland counties. It is about 35 miles long, and 20 broad, and contains 8,467 inhabitants, including 4,573 flaves. There are here fome medicinal fprings, on the head vaters of South Anna, a branch of York river; but they are little frequented.

LOUISA, a river of Virginia, the head vater of Cole river, a S. W. branch of the Great Kanhaway.

LOUSA CHITTO, or Loofa Chitte, a river which rifes on the borders of S. Carolina, and runs a S. westerly course through the Georgia weftern lands, and joins the Miffifippi just below the Walnut Hills, and 10 miles from Stoney river. It is 30 yards wide at its mouth, but after you enter it, is from 30 to 40 yards, and is faid to he navigable for canoes 30 or 40 leagues. It is 39‡ miles below the Yazoo cliffs.

LOUISBOURG, the capital of Sydney, or Cape Breton ifland, in North-America. Its harbour is one of the fineft in that country, being almost 4 leagues in circuit, and 6 or 7 fathoms water in every part of it. The anchorage or mooring, is good, and thips may run aground without any danger. Its en-trance is not above 300 toiles in breadth, formed by two fmall iflands, and is known 12 leagues off at fea, by Cape Lorember, fituated near the N. E. fide

fiftery may be continued from April to the close of November. The harbour is more than half a mile in breadth, from N. W. to S. E. in the narrowell part ; and 6 miles in length, from N. E. to S. W. In the N. E. part of the harbour is a fine careening wharf to heave down, and very fecure from all winds : On the opposite fide are the fifting stages, and room for 2000 hoats to cure their fifh. In winter the harbour is entirely frozen up, fo as to be walked over, which feafon begins here at the close of November, and lafts till May or June : fometimes the frosts fet in fooner, and are more intenfe; as particularly in 1745, when by the middle of October a great part of the harbour was already frozen. The town of Louisbourg stands on a point of land, on the S. E. fide of the island; its streets are regular and broad, confifting for the most part of ftone houses, with a large parade at a little diffance from the citadel; the infide of which is a fine fquare, near 200 feet every way. On its N. fide, while poffeffed by the French, flood the governor's house and the church; the other fides were taken up with barracks, bomb proof; in which the French fecured their women and children during the fiege. The town is near half a mile in length, and a in circuit. The principal trade of Louisbourg is the cod fishery, from which valt profits accrue to the inhabitants; the plenty of fifh being remarkable, and at the fame time better than any about Newfoundland. See Breton Cape. N. latitude 45. 54. weft longitude 59. 55.

LOUISBURGH, in Pennfylvania. See Harrifburg.

LOUISIADE, Land of, difcovered and named by Bougainville in 1769, is probably a chain of iflands, forming a foutheastern continuation of New-Guinea. The coaft feen by the Dutch Geelwink. Yacht in 1705, is a small distance north of Louisiade.

LOUISIANA, a Spanish province of North-America, bounded E. by the Miffifippi, S. by the gulph of Mexico, W. by New-Mexico, and N. by undefined boundaries. Both fides of the Mifnifipi were under the French government till the peace of 1762; when the eastern fide was ceded to the king of Great-Britain; and the day before the preliof it. Here is plenty of cod, and the minaries of peace were figned, his Chriftian

cian Majef ritories to pi, togethe leans; with laws and u this precativards of Louifia ber of fin Francis, t or Mexica Noir, and fcribed u The grea tants are governed The num The qua fifippi and Mexico 1 nearly 10 that in th ez, and c of it all. tations o crop to 1 has fom that plai portation myrtle, The o for heal! various den veg and falt in fuch fupply (banks c in exter above t nued ct of high N.W. wide, Francis Whi ed in 1 land, tl ed the and fet the Ibl cludin virtue pled a grees 1 bound gation been a 1796. tian Majefty ceded to Spain all his territories to the weftward of the Miffifippi, together with the town of New Orleans; with a flipulation that the French laws and ufuages fhould not be altered; this precaution, however, proved afterwards of no avail.

sril to

rbour

eadth.

rowelt

N.E.

e har-

heave

vinds :

fithing

o cure

is en-

over.

ofe of

Iune :

, and

rly in ober a

lready

ftands

fide of

Ir and

art of

a lit-

infide

o feet

e pof-

mor's

bomb

cured

g the

nile in

neipal

thery,

he in-

ng re-

better

. weft

. See

d and

pro-

outh-

ninea.

wink

north

ace of

y the

exico,

unde-

Mif-

ment

eaft_

preli-

Chrif-

tian

See

fides

Louisiana is interfected by a number of fine rivers, among which are St. Francis, the Natchitoches, the Adayes, or Mexicano river, the Miff uri, Rouge, Noir, and many others which are defcribed under their respective names. The greater part of the white inhabitants are Roman Catholics. They are governed by a viceroy from Spain. The number of inhabitants is unknown. The quantity of good land on the Miffifippi and its branches, from the bay of Mexico to Ohio river, a diftance of nearly 1000 miles, is very great; but that in the neighbourhood of the Natchez. and of the river Yazoo, is the flower of it all. There have been fome plantations of fugar-canes; but it is not a crop to be depended upon, as the froft has fometimes been too powerful for that plant. The chief articles of exportation are indigo, cotton, rice, beans, myrtle, wax, and lumber.

The climate is faid to be favourable for health and to the culture of fruits of various kinds, and particularly for garden vegetables. Iron and lead mines and falt forings, it is afferted, are found in fuch plenty as to afford an abundant fupply of thefe neceflary articles. The banks of the Miffifippi, for many leagues in extent, commencing about 20 miles above the mouth of Ohio, are a continued chain of lime-flone. A fine track of high, rich, level land, S.W. W. and N.W. of New-Madrid, about 25 miles wide, extends quite to the river St. Francis.

While the United States were engaged in the revolution war againft England, the Spaniards attacked and poffeffed themfelves of all the English pofts and fettlements on the Miffisppi, from the Ibberville up to the Yazoo river, including the Natchez country; and by virtue of this conquest have fince peopled and governed an extent three degrees north of the United States' fouth boundary, claiming the exclusive navigation of the other. This business has been amicably fettled by the treaty of \$796. 280

The Miffifippi, on which the fine country of Louifiana is fituated, was first discovered by Ferdinand de Soto, in 1541. Monfieur de la Salle was the first who traveried it. He, in the year 1682, having paffed down to the mouth of the Miffifippi, and furveyed the adjacent country, returned to Canada, from whence he took paffage to France. From the flattering accounts which he gave of the country, and the confequent advantages that would accrue from fettling a colony in those parts, Louis XIV. was induced to establish a company for the purpole. Accordingly, a fquadron of four veffels, amply provid-ed with men and provisions, under the command of Monfieur de la Salle, embarked with an intention to fettle near the mouth of the Miffifippi. But he unintentionally failed a hundred leagues to the weltward of it, where he attempted to eftablish a colony; but, through the unfavourableneis of the climate, most of his men miferably perifhed, and he himfelf was villainoufly murdered, not long after, by two of his own men. Mon fieur Ibberville fucceeded him in his laudable attempts. He, after two fuccefsful voyages, died while preparing for a third. Crozat fucceeded him ; and, in 1712, the king gave him Louisiana. This grant continued but a fort time after the death of Louis XIV. In 1763, Louisiana was ceded to the king of Spain, to whom it now belongs.

The following is Melford's account of the Spanish firength in the Floridas and Louisiana, in 1790:

Provincial levies and troops at St.

Augustine, and on St. John's river,	400
The garrifon at St. Mark's,	100
do. at Penfacola,	350
do. Mobile and Tombigbee,	\$ 50
do, at the Natchez,	200
do. Red river, W. of Miffifippi,	100
do. in the Illinois country,	300

1600

men, called the Orleans or Louisiana regiment. The number of American families that have been Spanish subjects fince 1783, amount to 1720, viz.

At Tenfau, near Mobile Bay, 90 On Tombigbee river, 130 At the Natcher, on the Miffinppi, 1500

12 X 1 1 1 1 1 1

All

All the fattlers in thefe diffricts are under the immediate orders of the militacommandants, and fubject to martial by commandants, and fubject to martial law, with an appeal from ftage to ftage, up to the viceroy of Mexico. The property of the fubject, at his decease, is to be managed by the Commandant, whole fees are fettled by law, and a-

LOUISTOWN, in Talbot county, Maland, lies on the weft fide of Tucka-be creek, about 4 miles north of King's Town, and 7 or 8 north call of Eafton. LOUISVILLE, a port of entry, and post-town of Kentucky, and chief of Jefferion county, pleasantly fituated on the east fide of the Ohio, on an elevated lain, at the Rapids, nearly opposite Fort enny. It commands a delightful profpect of the river and the adjacent country, and promifes to be a place of great trade; but its unhealthines, owing to ftaguated waters back of the town, has confiderably retarded its growth. It confilts of 3 principal ftreets, and contains about 100 houfes, a court-houfe and gaol. It is 38 miles from Bairdstown, 83 from Danville, and 40 W. of Frankfort. See Ohio.

LOUISVILLE, the prefent feat of overnment of Georgia, fituated in Burke county, in the lower district of the State, on the N. E. bank of the Great Ogeechee river, 70 miles from its mouth. It has been lately laid out, and contains a state-house, a tobacco warehouse, and about 30 dwelling-houfes. Large quantities of tobacco are inspected here, and boated down to Savannah. The convention for the revifal of the conftitution fat in this town in May, 1795, and appointed the records to be removed, and he legiflature to meet here in future : a college, with ample and liberal endowments, is inftituted here. It is 52 miles S. E. of Augusta, and 100 N. W. of Savannah.

LOVE-COVE, a fine opening to the veftward of Whale Cove, in New North Wales.

LOVELL'S POND, in New. Hampfhire, lies at the head of the eaftern branch of Salmon Fall river.

LOWER ALLOWAY's Creek, a townthip in Salem county, New-Jerfey.

LOWER DUBLIN, a township in Phiadelphia county, Penniylvania. Buck's county, Pennfylvania.

LOWER MARLBOROUGH, & poft. town in Maryland, 30 miles from An-napolis, and 12 from Calvert court-house.

LOWER PENN's Neck, a township in Salem county, New-Jersey. . LOWER WEAU Towns, in the Terri-tory N. W. of the Ohio, lie so miles below Rippacanoe creek, at its mouth in Wabath river.

LOWHILL, a township in Northamp-ton county, Pennsylvania.

LoxA, a town of Quito in Peru, at the head of a N. W. branch of Amazon river, 215 miles north-east of Paita, and north-westerly of Borja. It is the capi-tal of a jurifdiction of the fame name, and lies in lat. 5. 10. S. long. 77. 10. W. Befides 2 churches, it has feveral religious foundations; as; a college in. ftituted by the Jefuits, an hospital, with 14 villages in its diffrict.

The jurifdiction of the fame name produces the famous specific for intermittent fevers, called Cafcarilla de Logo Quinquina, or Jefuit's bark. Of it there are feveral kinds, but one more efficacious than the others. Here also they are employed in breeding cochineal. The inhabitants of Loja, called alfo Lojanus, do not exceed 10,000 fouls, though formerly far more numerous. Large droves of horned cattle and mules are bred here. Carpets are alfo manufactured here of remarkable finenefs.

LOYALSOCK Creek, in Northumberland county, Pennfylvania, empties into the W. fide of the branch of Sufquehannah river, from the north-eaft, a few miles E. of Lycoming Creek, 26 from Sunbury, measuring in a ftraight line, and about 170 from Philadelphia. The lands from this to Sunbury are among the highest and of the best quality, and in the healthieft fituation in the State. It is navigable 20 or 30 miles up for batteaux of 10 tons.

LUCANAS, a jurifdiction in the diocefe of Guamanga, in Peru. It begins about 25 or 30 leagues S. W. of Guas manga. Its temperature is cold and moderate. It abounds with cattle, grain and fruit; and has also filver mines; and is the centre of a very large commorce.

LUCAR, Font, St. lies on the northeast coast of Brazil; about half way be-LOWER MILFORD, a township in | tween thecity of Scara and Rio Grande. LUCAR, CAPE ST, or Lucas. The S. E.

S. E. end is fo name LUCAY Babama. LUCAT about 70

Florida, a is about

and gives

lat. 27. 2

LUCAT hama ille further length is lies north LUCE oftheilla nover pa

Molquito has excel north-eat LUCI runs fou of the inland w wateras hilly kn the fout

LUCI Sainte A covered Caribbe tinico, a is about fouth, a hills, 2 fteep, ar Lucy, an of them foil, and trees, w planters build Here is The air not bei trade-w the eaft, climate agreeab In St bays a

age, pa one of the Fre neutral noted a depth e bottom

is fo named.

LUCAYA, or Babama Mands. See Babama.

LUCAYA, one of the Bahama Iflands, about 70 leagues east of the coast of Florida, and 6 from Bahama Ifle. It is about 9 leagues long and 2 broad, and gives name to the whole range. N. lat. 27. 27. W. long. 78. 5.

LUCAYONEQUE, another of the Bahama illes, which lies about 9 leagues further east than the former; whole length is 28 leagues and breadth 3, and lies north and fouth.

LUCEA, a harbour on the north fide of the illand of Jamaica, fituated in Hanover parifh, between Great Cove and Mofquito Cove. It is land locked and has excellent anchorage; 15 or 16 miles north-eastward of Negril.

LUCIA, ST. a river of Eaft-Florida, runs fouth-easterly along the east fide of the peninfula; and communicates inland with Indian river. It has 6 feet water as far as the Tortolas, where are hilly knowls. A branch joins it from the fouth.

LUCIA, ST. called by the French, Sainte Aloufie, from its having been difcovered on St. Lucia's Day; one of the Caribbee Iflands, 6 leagues fouth of Martinico, and 21 N. W. of Barbadoes. It is about 27 miles long from north to fouth, and 12 broad. Here are feveral hills, 2 of which being very round and freep, are called the Pins' heads of St. Lucy, and were volcanoes. At the foot of them are fine vallies, having a good foil, and well watered. In these are tall trees, with the timber of which the planters of Martinico and Barbadoes build their houfes and wind-mills. Here is alfo plenty of cocoa and fuffic. The air is reckoned healthy, the hills not being fo high as to intercept the trade-winds, which always fan it from the eaft, by which means the heat of the climate is moderated and rendered agreeable.

In St., Lucia are feveral commodious bays and harbours with good anchorage, particularly the Little Careenage, one of the principal inducements for the French to prefer it to the other neutral islands. This port has feveral noted advantages; there is every where depth enough, and the quality of the bottom is excellent. Nature has form-

1000

S. E. end of the peninfula of California | ed there three careening places, which do not want a key, and require nothing but a capftern to turn the keel abov ground. Thirty flips of the line migh lie there sheltered from hurricanes, with out the trouble of being moored. The boats of the country, which have bee kept a long time in this harbour, have never been eaten by the worms ; however, they do not expect that this advantage will laft, whatever be the caufe. For the other harbours, the winds are always good to go out with, and the largeft fquadron might be in the offing in lefs than an hour. There are 9 parifles in the ifland, 8 to the leeward, and only one to the windward. This preference given to one part of the ifland more than another, does not proceed from the fuperiority of the foil, but from the greater or lefs conveniency in fending out or receiving thips. A high road is made round the ifland, and two others which crofs it from east to welt, afford all manner of facilities to carry the commodities of the plantations to the barcaderes, or landing places.

In January 1769, the free inhabitants. of the ifland amounted to 2,524; the flaves to 10,270. It had in cattle 598 nules and horfes, 1,819 horned beafts, and 2,378 fheep, its plantations were 1,279,680 plants of cocoa-2,463,880 of coffee-681 fquares of cotton-and 254 of fugar canes; there were 16 fugar-works going on, and 18 nearly completed. Its produce yielded 112,000l. which by improvement might be in-The English creafed to 500,000. firft fettled in this ifland in 1637. From this time they met with various misfortunes from the natives and French; and at length it was agreed on between the latter and the English, that this island, together with Dominica and St. Vincent, fhould remain neutral. But the French, hefore the war of 1756 broke out, began to fettle thefe iflands, which by the treaty of peace were yielded up to Great Britain, and this island to France. The British made themselves mafters of it in 1758; but it was reftor-ed again to the French in 1783; and retaken by the British in 1794. St. Lu-cia had 900 of its inhabitants destroyed by an earthquake, Oct. 12, 1788. It is 63 miles N. W. of Barbadoes. N. lat.

14. W. long. 61. LUDLOW, a township in Hampfhire

houfe. thip in

Terriles beuth in

hamp

Tu, at

mazon

1, and

r capi-

name,

7.10.

everal

ge in-

, with

name

inter-

Logo

t there

effica-

+ they

ineal.

d alfo

fouls,

crous.

: and

e alfo

: fine-

mber-

ts in-

uque-

a few

from

line,

The

mong

and

State.

p for

: dio-

Gua-

and

grain

ines ;

com-

lorth-

y be-

ande. The

. E.

county, Maffachufetts, fouth of Granby, no miles north-easterly of Springfield, and 90 westerly of Boston. It was incorporated in 1784, and contains 360 inhabitants.

LUDLOW, a township on Black river, Windfor county, Vermont. It contains 179 inhabitants, and is about to or 12 miles W. of Weathersfield, on Connecticut river.

LUE, ST: the chief town of the captain hip of Petagues, in the northern division of Brazil.

LUKE, ST. a parish in Beaufort diftrict, S. Carolina.

LUMBERTON, a post-town of N. Carolina, and capital of Robefon county, fituated on Drowning creek, 32 miles fouth of Fayetteville, and 93 S. by W. of Raleigh.

LUNENBURGH, a county of Virginia, adjoining Nottaway, Brunfwick, Mecklenburgh, and Charlotte counties. It is about 30 miles long, and 20 broad, and contains 8959 inhabitants, including 4332 flaves.

LUNENBURG, a township in Effex. county, in Vermont; fituated on Conmedicut river, S.W. of Guildhall, and N.E. of Concord. The river takes a S.E. course along these towns, separating them from Lancaster, Dalton, and Littleton, in the State of New-Hampfhire. The Upper Bar of the Fisteen Mile Falls is opposite this town. The Cat Bow, a bend of the Connecticut, is near the middle of the town. The Upper Bar lies in lat. 44. 21. 30. The township contains 119 inhabitants.

LUNENBURG, a township of Worcefter county, Massachuletts, on an elevated situation, 25 miles from the Great Monadnock mountain in New-Hampfhire, 12 from Watchusett mountain in this county, and 45 miles N. W. of Boston. It contains 14,000 acres of land, on which are 1300 inhabitants; and is much more remarkable for the health than the wealth of its possible fors. The people have little trade or intercourse with the neighbouring country, and live a folitary but independent life. The nailing bussness is carried on to advantage. There is a hill in the middle of the township, called Turkey Hill, on account of the great number of wild turkies which formerly frequented the place, and which denominated the whole tract previous to its incorporation in LUZ

1728; when its prefent name was given to it, in compliment to King George II. who was flyled Duke of Lunenburg, from a town in his German dominions.

LUNENBURG, a township of New-York, fituated in Albany county, on the W. fide of Hudfon's river, opposite to the city of Hudfon, and 30 miles fouth of Albany! It is a thriving village of about 20 or 30 houfes, chiefly new, with a neat Dutch church, ftanding on the bank of the river. A new road is cutting from this village into the fettlements on the upper branches of the Delaware and Sufquehannah rivers, which will probably prove highly beneficial to the town: A number of the Meffirs: Livingstons have purchased land in and about this village; to the amount of 10,000l. and have laid out a regular town, which will be a rival to Kaats' Kill, 5 miles below. The fcite of the town is uneven, and not of a very good foil.

LUNENBURG, a county of Nova-Scotia, on Mahone Bay, on the fouthern coaft of the province, facing the Atlantic Ocean. Its chief towns are New-Dublin, Lunenburg, Cheffer, and Blandford. In Mahone Bay, La Have, and Liverpool, feveral fhips trade to England with timber and boards. Chefter is fettled by a few New-England families and others: from hence to Windfor is a road the diffance of 25 miles.

LUNENBURG, a township in the above county, fituated on Merliqueth, or Merlinguash Bay, well settled by a number of industrious Germans. The lands are good, and generally well cultivated. It is 35 miles S.W. by S. of Halifax, and 27 N. by E. of Liverpool.

LURGAN, a township in Franklin county, Pennsylvania.

LUTTERELLE, an island in Machias Bay, in the District of Maine.

LUTTERLOCK, a township in Orleans county, in Vermont, north of Craftsborough, Irasburgh, Coventry, and Salem, which lie in a N. N. E. direction, from this town. Hazen's Road, which extends S. S. E. to the Oxbow on Connecticut river, passes through Lutterlock.

LUZERNE, a large county of Penns fylvania, bounded north by Tioga country in the State of New-York, east and form-east by Northampton, welt by Lycoming and Northumberland counties. It is about 79 miles in length from north to fouth, and 75 in breadth from east

east to v townships 33 faw m mills, an inhabitan A great where rer watered b hannah ri furnish n feats. T markably of wheat, ern parts lugar-ma barre, Ki are large in feveral been ered remains c are of an with larg Wilkfbar LYCO north-wel bounded York, a ty. Lyco fouth, and of Sulqu Loyalfoch LYCON 40 miles from the New-Yol LYMA ty, Newof a mou necticut Bath, and Concord. and conta LYME ton count the east miles abo incorpora inhabitan LYME county, (the India of Conn bounded north by east by 1 about the rated in 1 parifhes,

given

ge II.

nions

New-

fite to buth of

about

a neat

ank of

from

he upd Suf-

bably

A A

s have

illage

ve laid

a rival The

ot of a

a-Sco-

uthern

Atlan-

New-

Bland -

e, and ngland

fter is

milies

dfor is

in the

eth, or

num-

e lands

vated .

alifax,

anklin

achias

Drleans

Craft[-

nd Sa-

ection,

which

n Con-

erlock.

Penn 4

coum-

aft and

reft by

coun-

h from

a from

eaft

aft to weft, and is divided into 12 townships. In this county are 2 churches, 33 faw mills, 24 grift mills, 2 fulling mills, and t oil mill. The number of inhabitants is 4904, including 11 flaves. A great part of the county is barren where remote from rivers. It is well watered by the east branch of Susque hannah river and its tributaries, which furnish numerous and excellent mill feats. The foil near the river is remarkably fertile, producing good crops of wheat, flax, and hemp. The northern parts abound with pine timber and fugar-maple. In the townships of Wilksbarre, Kingston, Exeter, and Plymouth are large beds of coal. Bog iron is found in feveral places, and two forges have been crected. In this county are many remains of ancient fortifications. They are of an elliptical form, and overgrown with large white-oak trees. Chief town, Wilkfbarre.

LYCOMING, a new county in the north-weitern part of Pennfylvania, bounded north by the State of New-York, and weft by Alleghany coun-

LYCOMING, a finall creek which runs fouth, and empties into the weft branch of Sufquehannah, a few miles weft of Loyalfock Creek. See Layalfock.

LYCOMING, a village in Pennfylvania, to miles from Northumberland, and 66 from the Painted Post in the State of New-York.

LYMAN, a township in Grafton county, New-Hampfhire, fituated at the foot of a mountain on the east fide of Connecticut river, between Littleton and Bath, and 7 miles W. by N. of New-Concord. It was incorporated in 1761, and contains 202 inhabitants.

LYME, or Lime, a township in Grafton county, New-Hampshire, fituated on the east fide of Connecticut river, 12 miles above Dartmouth College. It was, incorporated in 1761, and contains 816 inhabitants.

LYME, a township in New-London county, Connecticut, the Nebantick of the Indians, is fituated on the east fide of Connecticut river, at its mouth : bounded fouth by Long-Ifland Sound, north by Haddam and Colchefter, and east by New-London. It was fettled about the year 1664, and was incorporated in May, 1667. It contains three paratifts, and another of Baptifts. In 1790 it contained 3859 inhabitants.

LYNCHBURG, a post-town of Virgi nia, fituated in Bedford county, on the fouth fide of James river, nearly oppofite to Maddison, and one mile diftant. Here are about 100 houfes, and a large warehouse for the inspection of tobacco. There is also a printing-office which flues a weekly gazette. In the vicinity of the town are feveral valuable merchant mills. It is 12 mil s from New-London, 23 from Cabellfburg, 50 from Prince Edward's court-houfe, 150 W. by N of Richm and, and 408 S. W. of Philadelphia.

LYNDEBOROUGH, a township in Hillfborough county, New-Hampfhire, about 68 miles from Port mouth. It was incorporated in the year 1764. In 1775 it contained 713; and in 1790, 1280 inhabitants, who are chiefly farmers.

LYNDON, a township in Caledonia county, in Vermont, lies north of St. Johnfbury, and fouthward of Billymead and Burke. It contains 59 inhabitants.

LYNN, a maritime town in Effex county, Maffachusetts, fituated on a bay which fe's up from that of Maffachu fetts, north eaft of Bolton Bay, and about 9 miles north by east of the town of Bolton. The compact part of the The town forms a very long freet. township, named Saugaus by the Indians, was incorporated in 1637, and contains 2291 inhabitants. Here are two parishes, besides a fociety of Methodifts, and a large number of Friends. The bufinels which makes the greatest figure, and for which the town of Lynn is celebrated, is the manufacture of womens' filk and cloth fhoes. Thefe are disposed of at Bofton, Salem, and other commercial towns, and fold for home use, or shipped to the southern States, and to the West Indies. By a calculation made in 1795, it appeared that there were 200 mafter workmen and 600 apprentices constantly employed in this bufinefs, who make annually 300,000 pair of fhoes. Lynn Beach may be reckoned a curiofity. It is a mile in length, and connects the peniniula called Ne-This is a bant with the main land. place of much refort for parties of pleafure from Bofton, Charlestown, Salem, Marblehead, &c. in the fummer featon. The beach is used as a race ground, for parifhes, belides a congregation of Se- | which it is well calculated, being level, fmooth.

⁴mooth, and hard. A mineral fpring has been difcovered within the limits of the township, but is not of much note.

LYNNFIELD, a township in Effex county, Massachusetts, N. E. of Salem, and 15 miles N. by E. of Boston. It was incorporated in 1782, and contains 491 inhabitants.

LYNNHAVEN Bay, at the fouth end of Chefapeak Bay, and into which Lynnhaven river empties its waters, lies between the mouth of James's river and Cape Henry. The mouth of the river is 7 miles weft of Cape Henry. Here Compte de Graffe moored the principal part of the French fleet, at the blockade of York town in 1781.

LYONS, a town lately laid out in Ontario county, New-York, about 12 miles N.W. of Geneva, at the junction of Mud Creek and Canandaque Ouflet.

LYSANDER, a township in Onondago county, N. Mork, incorporated in 1794, and comprehends the military towns of Hannibal and Cicero. The town meetings are held at the Three Rivers in this town. It is 10 miles S.E. of Lake Ontario. In 1796 there were 10 of its inhabitants entitled to be electors.

LYSTRA, a fmall town in Nelfon county, Kentucky, fituated on a weft water of Rolling Fork, a fouth branch of Salt river. N. lat. 37. 25.

\mathbf{M}

MAATEA, one of the Society Itlands, in the S. Sea, lat. 17. 52. W. long. 148. 1.

MACAPA, a town fituated on the north-weft bank of Amazon river, W. of Caviana ifland, at the mouth of the river, and a few minutes north of the equinoctial line.

MACAS, the fouthern diffrict of Quixos, a government in Peru, in S. America, bounded E. by the government of Maynas; S. by that of Bracamoros and Yaguarfongo; and on the W. the E. Cordillera of the Andes feparates it from the jurifdictions of Riobamba and Cuenca. Its capital is the city of Macas, the name commonly given to the whole country. It produces in great plenty, grains and fruits, copal, and wild wax; but the chief occupation of

the country people is the cultivation of tobacco. Sugar-canes thrive alfo here, as alfo cotton; but the dread of the wild Indians prevents the inhabitants from planting more than ferves for prefent ufe. Here are cinnamon trees, faid to be of fuperior quality to thofe of Ceylon. There are alfo mines of ultra marine, from which very little is extracted, but a finer colour cannot be imagined. Among the vaft variety of trees which crowd the woods, is the ftorax, whofe gum is exquititely fragrant, but fcarce.

MAC GILLIVEAY'S Plantation, on Coofa river, is a little above the Old French fort Alabamous.

MACHALA, a town of Guayaquil, on the coaft of Tumber, in Peru, in a declining flate. The jurifdiction of the fame name produces great quantities of cocoa, reckoned the beft in all Guaya-quil. In its neighbourhood are great numbers of mangles, or mangrove trees, whole ipreading branches and thick trunks cover all the plains; which lying low are frequently overflown. This tree divides itfelf into very knotty and difforted branches, and from each knot a multitude of others germinate, forming an impenetrable thicket.' The wood of the mangrove tree is to heavy; as to fink in water, and when used in fhips, &c. is found very durable, being fubject neither to fplit or rot. The Indians of this jurifdiction pay their annual tribute in the wood of the mangrove tree:

MACHANGARA, a river formed by the junction of feveral freams iffuing from the fouth and weft fides of the Panecillo or Sugar Loaf mountain, on the fouth-weft fide of Quito, in Peru. It washes the fouth parts of the city, and has a ftone bridge over it.

and has a ftone bridge over it. MACHIAS, a port of entry, pofttown and feat of juilled, in Washington county, District of Maine, fituated on a bay of its own name, 20 miles S.W. of Passanauoddy, 95 E. by N. of Penobfcot, and 236 north-east of Portland, in 47. 37. N. lat. It is a thriving place, and carries on a confiderable trade to Boston and the West-Indies in fish, lumber, &c. It is contemplated to establish a regular post between this town and Halifax, in Nova Scotia. The name of the cown is altered from the Indian name Mechifies, given to the river in

tion of o here, of the bitants es for trees, hofe of of ultra xtractmaginof trees ftorax, nt, but ion, on the Old iquil, on in a de-1 of the itities of Guayare great we trees, d thick ich lying This lotty and ich knot e, form-The 1.1 b heavy; uifed in t. The their anthe man-

ormed by as iffuing is of the ntain, on in Peru. the city, try, poftafhington uated on a s S.W. of of Penobirtland, in ing place, e trade to i fifh, lumto effablish town and he name of the Indian he river in

the

MAC

the oldest maps. It is 400 miles northeaft of Bolton, and about 300 by water. Early attempts were made to fettle here, but the first permanent fettlement was made in 1763, by 15 perfons of both fexes from Scarborough, in Cumberland county, and in 1784 the town was in-corporated. The chief fettlements are at the east and west Falls, and at Middle river, Machias river safter running a north course, 6 miles distance from Crofs ifland, (which forms its entrance) feparates at a place called the Rim; one branch taking a north east direction, runs $2\frac{1}{2}$ miles, with a width of 30 rods to the head of the tide, where are two double faw-mills, and one grift mill. The main branch runs a north-west courfe, nearly 3 miles, and is 70 rods. wide, to the head of the tide, where are two double and fingle faw-mills, and two grift-mills. The chief fettlement is at Weft Falls, the county courts being held and the gaol erected there. The main channel of the river takes its courfe to these falls, which, though crooked and narrow, admits vefiels of burden to load at the wharves within so rods of the mills. This advantage no other part of the town can enjoy. The entrance of Machias river is in N. lat. 44. 35. W. long. 66. 56. The town is divided into 4 diffricts for the fupport of schools; and into 2 for the convenience of public worthip. In 1792 Washington academy was established here. The general court incorporated a number of gentlemen as truffees, and gave for its support a township of land. In 1790 the town contained 818 inhabitants. Since that time its population has rapidly increased. The exports of Machias confift principally of lumber, viz. boards, fhingles, clapboards, laths, and various kinds of hewed timber. The cod-fifthery might be carried on to advantage though it has been greatly neglected. In 1793, between 70 and So tons were employed in the fifthery ; and not above 500 quintals were exported. The mill-faws, of which there are 17, cut on an average three million feet of boards annually. A great proportion of timber is usually thipped in Britith veffels. The total amount of exports annually exceeds 1 5,000 dollars. From Machias Bay to the mouth of St. Croix, there are a great many fine illands; but the navigation is generally without thefe

in the open fea. In the year 1704, when Colonel Church made an attack on the French plantation on the riverSchoodick, he found one Lutterelle, a French nobleman, on one of these islands, and removed him. The island still retains his name.

MAC COWAN'S Ford, on Catabaw river, is upwards of 500 feet wide, and about three feet deep. Lord Cornwallis croffed here in purfuit of the Americans in 1781, in his way to Hillfborough.

MAC-INTOSH, a new county in the Lower diffrict of Georgia, between Liberty and Glynn counties, on the Alaramaha river.

MAC-KENZIE's River, in the N.W. part of N. America, rifes in Slave Lake, runs a N.N.W. courfe, and receives a number of large rivers, many of which are 250 yards wide, and fome are 12 fathoms deep at the influx. It empties into the North Sea, at Whale Island in lat. 69. 14, between 130. and 135. W. long. after a course of 780 miles from Slave Lake. It has its name from Mr. M'Kenzie, who afcended this river in the fummer of 1789. He crected a post with his name engraven on it, on Whale Island, at the mouth of this river. He faw there a number of men and canoes, also a number of animals refembling pieces of ice, fuppoled by him to be whales ; probably fea-horfes, defcribed by Captain Cook. The tide was observed to rife 16 or 18 inches. In fome places the current of the river makes a hiffing noife like a boiling pot. It passes through the Stoney Mountains, and has great part of that range on the W. fide. The Indian nations, inhabiting the W. fide from the Slave Lake, are the Strongbow Mountain and Hare Indians; those on the E. fide, the Bea. ver, Inland, Nathana, and Quarrelers, Indians. No difcoveries welt of this river have been made by land.

MACOKETH, or Macoketch, River, Great, empties into the Miffifippi from the N.W. in N. lat. 42. 23. Little Macoketh falls through the E. bank of the Miffifippi, about 45 miles above the mouth of Great Macoketh, and opposite to the Qld Lead Mine,

MACOPIN, a fmall river which empties into the Illinois, from the S.E. 18 miles from the Miffifippi; is 20 yards wide, and navigable 9 miles to the hills. The fhore is low on both fides, clad with paccan, maple, afh, button-wood, T 2 & &c.

Sec. The land abounds with timber, and is covered with high weeds.

MACORIZ, a fmall river on the S. fide of the island of St. Domingo ; 16 leagues E. of the city of Domingo.

MACUNGY, a township in Northampton county, Pennfylvania. MAD, a river, called alfo Pickawa

Fork, a rapid branch of the great Miami, having a S.W. course. It is a beautiful ftream, paffing through a pleafant level country of the greatest fertility. MADAME Ise forms the N. E. fide

of the Gut of Canfo, as you enter from the S. E. and is opposite to the caftern extremity of Nova-Scotia. The north point of the ifland lies 14 miles foutherly of St. Peter's harbour, in Cape Breton ifland. The ifles de Madame are dependent on Cape Breton island.

MADBURY, a township in Strafford county, New-Hampshire, fituated be-tween Dover and Durham, about 10 miles N. W. of Portfmouth. It was incorporated in 1755, and has 592 inhabitants.

MADDISON, a county of Kentucky, adjoining Fayette, Clarke, Lincoln, and Mercer's counties. Chief town, Milford.

MADDISON, a fmail town of Amherft county, Virginia; fituated on the N. fide of James's river, oppofite Lynchburgh. It lies 150 miles W. by N. of Richmond.

MADDISON'S CAVE, the largeft and most celebrated cave in Virginia, fituated on the N. fide of the Blue Ridge. It is in a hill of about 200 feet perpendicular height, the afcent of which, on one fide is fo fleep, that you may pitch a bifcuit from its fummit into the river which washes its base. The entrance of the cave is in this fide, about twothirds of the way up. It extends into the earth about 300 feet, branching into fubordinate caverns, fometimes afcending a little, but more generally defcending; and at length terminates in two different places, at basons of water of unknown extent, and which appear to be nearly on a level with the water of the river. The vault of this cave is of folid lime-ftone, from 20 to 40 or 50 feet high, thro' which water is continually exudating. This trickling down the fides of the cave, has incrufted them over in the form of elegant drapery; and dripping from the top of the vault, generates on that, and on the bale below, fta-

lactites of a conical form, fome of which

have met and formed la ge maffycolumns. MADERA, or Madeira, one of the largest branches of the famous Maranon or river of Amazons, in S. America. In 1741, the Portuguese failed up this ftream, till they found themfelves near Santa Cruz de la Sierra, between lat. 1 and 18, S. From the mouth of this river in lat. 3. 20. S. the Maranon is known among the inhabitants by the name of the river of Amazons; and upwards they give it the name of the river of Solimoes. At Loretto, the Madera receives two branches from the fouth. From Loretto to Trinidad in lat. 15 S. its courfe is N. thence to its mouth its general courfe is N. E. by N. and N.

MADRE DE DIOS, Port. See Chriftiana, St. Alfo Refolution Bay.

MADRE DE POPA, a town and convent of Terra Firma in S. America, fituated on the river Grande, or Magdalena. The pilgrims in S. America refpect this religious foundation with zeal, and refort to it in great numbers : many miracles being faid to have been wrought here by the Holy Virgin, in favour of the Spanish fleets and their failors, who are therefore very liberal in their donations at her fhrine. It lies 54 miles E. of Carthagena. N. lat. 10. 51. W. long. 76. 15.

MADRID. See New Madrid.

MADRIGAL, atown of Popayan, in S. America. N. lat. 0. 50. W. long. 75.45. MAGDALEN Ifles, a clufter of illes N.E. of the ille of St John's, and N.W. of that of Cape Breton, in the gulf of St. Lawrence; fituated between 47. 13. and 47. 42. N. lat. and in 61. 40. W. long. They are inhabited by a few fishermen. Sea-cows used to frequent them; but they are now become fcarce. These illes have been fatal to many veffels. The chief of them are the Dead Man, Entry, and Romea iflands. Seamen with to make them in fair weather, as they ferve them to take a new departure; but in foggy weather or blowing weather they as fludioufly avoid them.

MAGDALENA, La, one of the Marquefas' Iflands in the South Sea; about 6 leagues in circuit, and has a harbour under a mountain on its fouth fide nearly in lat. 10. 25. S. long. 138. 50. W. MAGDALENA, a river of Louifiana, which empties into the gulf of Mexico, W. by S. of Mexicano river.

MAG-

MAG principa diftance Terra down th North S its wate name of North Se Popa. T well inh above 20 frequente to Carth Granada many ot banks ar gua, Mo MAGI tory in there is great ad the good ty of the MAGI of N. A ton's If Edward by two falling in long. 13 ed by Do ing into Port Per MAGE Eaftern . famaquo true St. eaftern b ed State disputed ment, ag MAGI extremit 52. and 84. W. Patagon Terra d from E. breadth i They we lan, or N fervice o out there to the Pa was the the work MAGE A Valt tri

MAG

MAGDALENA, a large river; the two principal fources of which are at no great diftance from the city of Popayan, in Terra Firma. Belcazar, by going down this river, found a paffage to the North Sea. The river, after uniting its waters with the Cance, takes the name of Grande, and falls into the North Sea below the town of Madre de Popa. The banks of this great river are well inhabited, and it has a courfe of above 200 leagues. Its mouth is much frequented by imugglers, and conveys to Carthagena the productions of New Granada, viz. gold and grain'. Among many other confiderable places on its banks are Malambito, Teneriffe, Talay-gua, Monpox, Tamalameque, &c.

MAGDALENE, Cape of, a promontory in the centre of Canada, where there is an iron mine, which promifes great advantages, both with regard to the goodness of the metal and the plenty of the ore.

MAGEE's Sound, on the N. W. coaft of N. America, is fituated in Wafhington's Iflands, or what the Britifh call Edward's, or Charlotte's Ifles, fo called by two different captains on their firft falling in with them. Lat. 52. 46. N. long. 131. 46. W. This found is divided by Dorr's Ifland, into two parts, leading into one. The other port is called Port Perkins.

MAGEGADAVICK, or Magacadava, or Eastern River, falls into the bay of Paffamaquoddy, and is supposed to be the true St. Croix, which forms part of the eastern boundary line, between the United States and New-Brunswick. This disputed line is now in train for fettlement, agreeable to the treaty of 1794.

MAGELLAN, Straits of, at the fouth extremity of S. America, lie between 52. and 54. S. lat. and between 76. and 84. W. longitude. Thefe ftraits have Patagonia on the N. and the iflands of Terra del Fuego on the S. and extend from E. to W. 110 leagues, but the breadth in fome places falls fhort of one. They were first difcovered by Magellan, or Magelhaens, a Portuguefe, in the fervice of Spain, who, in 1320, found out thereby a paffage from the Atlantic to the Pacific or Southern ocean. He was the first navigator who failed round the world.

MAGELLANIA, or Terra Magellanica, a valt tract of land, extending from the

province of Rio de la Plata, quite to the utmost verge of S. America, viz. from lat. 35. to 54. S. The river Sinfondo divides the W. part from the S. of Chili : the northern part of it alfo borders on Chili, and Cuvo or Chicuito on the W. The South Sea bounds it, in part, on the W., The N. ocean wholly on the E. and straits of Magellan on the S. Magellan himfelf made no great discoveries in this country, except the two capes of Virgins and Defire. The two principal nations discovered by the missionaries, are, the Chunians and Huillans; the former inhabit the continent, and feveral iflands, to the northward of the Huillans, who inhabit the country near Magellan Straits. The foil is generally barren, hardly bearing any grain, and the trees exhibit a difinal afpect; fo that the inhabitants live miferably in a cold, inhospitable climate. The Huillans are not numerous, being hunted like wild beafts, by the Chunians, who fell them for flaves. The other nations are not known, much lefs their genius or manner of living. The eaftern coafts of Magellan are generally low, abounding with bogs, and have feveral iflands near the fhore; the most remarkable of

MAH

202

imoke, and appears terrible in the night. The Spaniards erected a fort on this ftrait, and placed a garrifon in it; but the men were all ftarved. MACUANA, St. Jahn of, a canton and town on the S. fide of the inland of St. Domingo, is fituated on the left fide of the river Neybe. The capital of the ancient Indian kingdom of Maguana, flood where the town St. John of Maguana is fituated. The ancient capital difappeared with the unfortunate prince Anacoana. This canton was pillaged by the Englifh privateers, in 1543. In 1764, the diffrict of the new parifh contained 3600 perfons, of whom 300 were capa-

which is the Ifle of Penguins, fo called

from a bird of that name, which abounds

on it. The iflands S. of the ftraits are

Terra del Fuego; as there is a volcano

in the largest of them, emitting fire and

amounts now to more than 5000 fouls. MAHACKAMACK, a river which falls into the Delaware from the N. E. at the N.W. corner of the State of New-Jerfey.

ble of bearing arms. Its population

MAHONE BAY, on the coaft of Nova-Scotia, is feparated from Margaret's Bay T e by

MAG-

which

umns.

of the

ranon

ra. In

his this

s near

it. 17.

of this

non is

by the

nd up-

he riv-

Aadera

fouth.

. 15 S.

uth its

Chrif-

d con-

ica, fi-

Aagda-

rica re-

th-zeal,

: many

rought

your of

s, wha

r dena-

iles E.

1. W.

in, in S.

75.45.

lesN.E.

. of that

t. Law-

and 47.

7. long.

hermen.

m; but

refe ifles

, Entry,

wifh to

ney ferve

her they

Marque-

about 6

harbour

ide near-

50. W.

ouifana,

Mexico,

but in

The

d N.

by the promontory on which is the high land of Afpotagoen.

204

MAHONING; a township on Susquehannah river, in Pennsylvania.

MAHONOY, a township on Susquehannah river, in Pennsylvania. See Northumberland county.

MAIDENHEAD, a fmall neat village in Hunterdon county, New-Jerfey, having a Prefbyterian church, half way between Princeton and Trenton, on the great poft-road from New-York to Philadelphia; fix miles from each. The townfhip of Maidenhead contains 1032 inhabitants, including 160 flaves.

MAIDSTONE, a township in Effex county, in Vermont, on Connecticut river, containing 125 inhabitants.

MAINE, DISTRICT OF, belonging to Maffachufetts, is fituated between lat. 43. and 48. 15. N. and between long. 64. 53. and 70. 39. weft; bounded north by Lower Canada, eaft by the province of New Brunfwick, fouth by the Atlantic Ocean, west by New-Hampfhire. The Diftrict of Maine is in length, on an average, 200 miles, and its average breadth 200 miles ; containing 40,000 fquare miles, or 25,600,000 acres. It is divided into five counties, viz. York, Cumberland, Lincoln, Hancock, and Washington : these are fubdivided into near 200 incorporated townfhips and plantations; inhabited by 96,540 free people. The chief towns are Portland, the metropolis of the Diftrict of Maine, York, Pownalborough and Wiscaffet, Hallowell, Bath, Waldoborough, Penobícot, and Machias. The last mentioned is the only incorporated town in Washington county, the other fettlements being only plantations. The chief rivers are Penobicot, Kennebeck, Saco, Androfcoggin, St. Croix, &c. befides a vaft number of fmall rivers. The moft noted lakes are Moofehead, Scoodic, Sebacook, and Umbagog. The chief bays are those of Casco, Penobfcot, Machias, Saco, and Paffamaquoddy. The most remarkable capes are thole of Neddock, Porpoife, Elizabeth, Small Point, Pemaquid, and Petit Manan. The Diffrict of Maine, though an elevated tract of country, cannot be called mountainous. A great proportion of the lands are arable and exceedingly fertile, particularly between Penobicot and Kennebeck rivers. On fome parts of the fea-coaft, the lands

are but indifferent. The lands in this District may be confidered in three divifions ; the first comprehending the tract lying east of Penoblcot river, of about 4,500,000 acres; the fecond, and beft tract, of about 4,000,000 acres, lying between Penobfcot and Kennebeck rivers ; the third, first fettled and most populous at prefent, weft of Kennebeck river, containing also about 4,000,000 acres. The foil of this country, in general, where it is properly fitted to receive the feed, appears to be very friendly to the growth of wheat, rye, barley, oats, peas, hemp, and flax, as well as for the production of almost all kinds of culinary roots and plants, and for English grafs; and also for Indian corn, efpecially if the feed be procured from a more northern climate. Hops are the fpontaneous growth of this country; and it is alfo uncommonly good for grazing, and large flocks of neat cattle may be fed both fummer and winter. The natural growth of this District confifts of white pine and spruce trees in large quantities, fuitable for masts, boards, and shingles; maple, beech, white and grey oak, and yellow birch. The low lands produce fir, which is neither fit for timber nor fuel, but yields a balfam that is highly prized. Almost the whole coast northeast of Portland is lined with islands, among which veffels may generally anchor with fafety. The principal exports of this country are various kinds of lumber, as pine boards, fhip timber, and every fpecies of fplit lumber manufactured from pine and oak; thefe are exported from the various ports in immense quantities. A spirit of improvement is increasing here. A charter for a college has been granted by the legiflature, and five academies incorporated and endowed with handfome grants of public lands. Town fchools are generally maintained in most of the towns. The Commonwealth of Maflachnfetts poffels between eight and nine million acres in this Diffrict, independent of what they have fold or contracted to fell, which brings into the treafury the neat fum of 269,0051. 8s. 7d. currency ; and befides about two million acres between St. Croix and Paffamaquoddy in difpute between the U. States and the British nation. Exclusive of the lands fold, about 385,000 acres have been granted for the enencourager uleful and were made ly as 1607 beck river ful, and w 1620 and part of it Gorges, h and he fit this provi came unde fetts, and with it, in to upward will, it i into a feps MAIRE del Fuego rica. MAISY point of t MAJAI Maine, at on the eaf MAKE townfhips vania. MALA narrow 1 from the in Maffa W. N. Greenwic MALA of Peru, MALA of Carth 60 miles the W. f MALD ty, Maff road, 4 n ing 1031 with Cha tic river, MALI Plata, ea America ta Maria MALI fouthern leagues erected Several 1 at this p vering if or Hero and one

en-

MAL

encouragement of literature and other uleful and humane purpoles. Attempts were made to fettle this country as early as 1607, on the west fide of Kennebeck river; but they proved unfucceffful, and were not repeated till between 1620 and 1630. In 1635, the western part of it was granted to Ferdinando Gorges, by the Plymouth Company, and he first instituted government in this province. In 1652, this province came under the jurifdiction of Maffachufetts, and was, by charter, incorporated with it, in 1691. It has fince increafed to upwards of 100,000 inhabitants, and will, it is expected, fhortly be erected into a separate State.

MAIRE, Le, a ftrait between Terra del Fuego and Staten Island, in S. America.

MAISY, Cape, is the eafternmost point of the ifland of Cuba.

MAJABAGADUCE, in the Diffrict of Maine, at the mouth of Penobleot river, on the eaft fide.

MAKEFIELD, Upper and Lower, townships in Buck's county, Pennsylvania.

MALABAR, Cape, or Sandy Point, a narrow ftrip of land projecting out from the fouth eaft part of Cape Cod, in Maffachufetts, about 8 miles S. by W. N. lat. 41. 33. W. long. from Greenwich 70. 3.

MALABRIGO, a harbour on the coaft of Peru, in the S. Sea,

MALAMBITO, a town in the province of Carthagena, in Terra Firma, about 60 miles eafterly of Carthagena, and on the W. fide of the river Magdalena.

MALDEN, a town in Middlefex county, Maffachufetts, on the eaftern poftroad, 4 miles north of Bofton, containing 1033 inhabitants. It is connected with Charleftown by a bridge over Myftic river, built in 1787.

MALDONADO, a bay in the river La Plata, eaftward of Buenos Ayres, in S. America, and 9 leagues from Cape Santa Maria.

MALIGASH, a finall creek on the fouthern fide of Chaleur Bay, about 3 leagues from Jaquit river, where are erected faw-mills and pot-afh works. Several fhips and brigs have been built at this place. Opposite to it, and covering its front, lies L'Iste aux Herons, or Heron Island, about two leagues long and one wide. It lies E, and W, and about two miles in fome places from the main.

MAN

MAMA KATING, a township in Ulfter county, New-York, W. of Montgomery and Wallkill, on Delaware river. It contains 1763 inhabitants, including 232 electors, and 51 flaves.

MAMARÓNECK, a township in West-Chefter county, New-York, containing 452 inhabitants, including 57 flaves. It is bounded foutherly by New Rochelle, and easterly by the Sound.

MAMARUMI, a place on the road from Guayaquil to Quito, in S. America, where there is a very beautiful cafcade. The rock from which the water precipitates itfelf, is nearly perpendicular, and 50 fathoms high; and on both fides edged with lofty and fpreading trees. The clearnefs of the water dazzles the fight, which is delighted, at the fame time, with the large volume of water formed in its fall; after which it continues its courfe in a bed, along a fmall defcent, and is croffed over by a bridge.

MANALLIN, a township in York county, Pennsylvania.

MANCA, a town of Weft-Florida, on the eaft bank of the Miffifippi, at the mouth of Hona Chitto river.

MANCENILLA, a large bay on the N. fide of the ifland of St. Domingo ; about 4000 fathoins long from W. to E. and 2800 broad from N. to S. The S. E. part of the bay is very wide and affords excellent anchorage, even for veffels of the first fize. In other parts it is too fhallow. The river Maffacre, which was the point of feparation of the French and Spanish colonies on the N. of the ifland, runs a N. courfe, towards its mouth N. W. and enters the eastern part of the bay. The bay of Mancenilla, though a very fine one, is not fo useful as it might be, if its bottom were well known. There are feveral shallows in it, owing to the overflowings of the Maffacre, which rolls into it wood, fand, and ftones, in great quantities, fo that it feems neceffary to found the bay annually, after they are over. In general, it is prudent, on entering, to keep clofer to the point of Ycaque, than to the S, fide of the bay; because the fandy point has no rocks. The bottom of the bay is muddy. The river Maffacre is, during a league, from 5 to 12 feet deep, and pretty wide; but its bed T 4 18

6.5

MAN

296

is often full of the wood which the current brings down. It fwarms with fifh ; and here are found those enormous mullets which are the pride of the table at Cape Francois. In the times of the floods, these fish are driven towards the bay, where negroes, well practiled in the bufinefs, fifh for them. Fifhing in the bay is difficult enough, on account of the drifted wood; but the negroes are good divers, and are often obliged to go to the bottom and difengage the feine; but when it gets near the beach, it is a fingular and striking spectacle, to fee the negroes, the fifh, and the alligators, all flouncing about in the water together. The negroes kill the alligators, knock out their teeth, and fell them to make corals, the garniture of which ferves to mark the degree of luxury or pride of those who hang them to the necks of their children. The plenty of fifh often attracts fhips of war to this bay. The mouth of Maffacre river lies in N. lat. 19. 44. W. long. from Paris

MANCHAC, a town on the Miffifippi, two miles below the Indian town of Alabama. 'The banks of the river at Manchac, though frequently overflowed by the vernal inundations, are 50 feet perpendicular height above the furface of the water; and the river, at its loweft ebb, is not lefs than 40 fathoms deep, and nearly a mile in width. The Spanish fortress on the point of land below the Ibberville, clofe by the banks of the river, has a communication with Manchac, by a flender, narrow, wooden bridge, acrois the channel of Ibberville, and not a bow-fhot from the habitations of Manchac.

MANCHESTER, a fmall fifting-town, fituated on the fea-coaft between Cape Anne and Beverly, in Effex county, Maflachufetts. The fiftery is carried on from this port chiefly in the veffels, and for the account of the merchants in Bofton, and other places. The townfaip lies S. E. of Wenham, and 30 miles N. E. of Bofton. It was incorporated in 1645, and contains 965 inhabitants.

MANCHESTER, a post-town of Vermont, in Bennington county, on Battenkill. It is 22 miles N. by E. of Bennington, and 59 N. E. of Albany in New-York. This township contains 1276 inhabitants. In the S. part of the town, in a hill a little W. of the BattenMAN

kill, is deep a firatum of friable calcarous earth, of the whitenefs of chalk; and apparently compoled of fhells, which requires but little burning to produce good lime.

MANCHESTER, a township in York county, Pennsylvania.

MANCHESTER, a finall town of Virginia, fituated on the S. fide of James river, oppofite to Richmond, with which it is connected by a bridge. In 1781 this town fuffered much during Arnold's deftructive expedition.

MANCHESTER, a town of Nova-Scotia, 10 leagues N. W. of Cape Canfo. It contained 250 families in 1783.

MANCHESTER HOUSE, one of the Hudíon Bay Company's factories, lies too miles W. of Hudíon's Houfe, and 75 S. E. of Buckingham Houfe. It ftands on the S. W. fide of Safkafhawan river, in the N. W. part of N. America. N. lat. 53. 14. 18. W. long. 109. 20.

MANCORA, a place on the road from Guayaquil to Truxilla, in Peru, fituated on the fea-coaft. Through it, during winter, runs a rivulet of fresh water, to the great relief of the mules that travel this way. In summer, the little remaining in its channel is so brackish, as to be hardly tolerable.

MANGEEA, an ifland of the S. Seas, vifited by Captain Cook in the beginning of his laft voyage. The coaff is guarded by a reef of coral rocks, againft which a heavy furf is continually breaking. The ifland is about 15 miles in circumference. The inhabitants appear of a warlike difpofition. S. lat. 21. 27. W. long. 158.7.

MANHATTAN, the ancient name of Long-Ifland, and also of York-Ifland.

MANHEIM, a town of Pennfylvania, in the county of Lancaster. It contains about 60 houses, and a Dutch church. Glass works were erected here previous to the revolution, but they are fallen to decay. It is strmiles N. by W. of Lancaster, and 77 W. by N. of Philadelphia. —Alfo the name of a town in Lincoln county, Maine. There is another of the fame name in York county, Pennfylvania.

MANICOUAGAN, or Black River, rifes from a lake of its name, in Lower Canada; runs a fouthern courfe, and falls into the St. Lawrence 85 miles N. E. of Tadoufac.

MANIEL, or rather Baheruce, moun-

tains

and almo for So ye the fugit Thefe b fied thei mountai and the gold duf MANI county, MANI near the confider MAN county, 1794, an It is we ftone, a unite at and the l runs not miles n town. Ononda ly by th by One Of its i cording MAN caway of the l Miami. MAN county, MAN Pennfy MAN of Hud ifland a 62. 38 MAI county inhabit fituated 7 miles far nor MAI county fouther rated i ants. MA tenden Moille diftand E. of MA

tains in t Domingo tains in the ifland of Hifpaniola or St. Domingo, 20 miles in circumference, and almost inacceffible. They have been for So years pass the place of refuge of the fugitive Spanish and French negroes. These brigands have as yet always defied their pursuers. The foil of these mountains is fertile, the air temperate, and the streams in them abound with gold dust.

e calca-

chalk ;

ning to

n York

of Vir-

ge. In

during

va-Sco-

Canfo.

of the

es, lies

ife, and

afe. It

Mawan

merica.

19. 20.

ad from

fituated

during

ater, to

at travel remain-

as to be

S. Seas,

ginning

guard-

ft which

eaking.

circum-

rar of a

27. W.

name of

ylvania,

contains

church.

previous

fallen to

of Lan-

delphia.

Lincoln

other of

Penn-

ver, rif-

rfe, and

niles N.

moun-

tains

Lower

Ifland.

\$3.

James with

fhells,

MAN

MANILLON, a township in Fayette county, Pennsylvania.

MANITOUALIN, a clufter of iflands near the northern fhore of Lake Huron, confidered as facred by the Indians.

MANLIUS, a township in Onondago county, New-York, incorporated in \$794, and is the feat of the county courts. It is well watered by Butternut, Limeftone, and Chittenengo creeks, which unite at the N. E. corner of the town; and the ftream, affuming the latter name, runs north to Oneida lake, which is to miles northerly of the centre of the town. It comprehends that part of the Onondago refervation bounded fouther-谜. ly by the Geneffee road, and wefterly by Onondago creek and the Salt lake. Of its inhabitants 96 are electors, according to the ftate cenfus of 1796.

MANMIC. Indian villages on the Picaway fork of the Mannic, or Miami of the lake, and St. Mary's river. See Miami.

MANNINGTON, a township in Salem county, New-Jersey.

MANOR, a township in Lancaster co. Pennsylvania.

MANSEL, an island in the N. E. part of Hudíon's bay, between Southampton island and the coaft of Labrador. N. lat. 62. 38.

MANSFIELD, a township in Suffex county, New-Jersey, containing 1482 inhabitants, including 35 flaves. It is fituated on Mulconecunk river, about 7 miles south-easterly of Oxford, and as far northerly of Greenwich.

MANSFIELD, a township in Bristol county Massachuletts, fituated 30 miles foutherly of Boston. It was incorporated in 1770, and contains 983 inhabitants.

MANSFIELD, a township in Chittenden county. Vermont, between La Moille and Onion rivers, about 7 miles distance from each, and 113 miles N. by E. of Bennington.

MANSFIELD, a township in Burling-

ton county, New-Jerfey, on the S. fide of Black's creek, confifting of 19,000 acres, of an excellent foil, noted for its fine paftures and large dairies. It is 3 miles W. by N. of Burlington, and 12. S. by E. of Trenton. The inhabitants are moftly Friends.

MANSFIELD, a township in Windham county, Connecticut, about 30 miles north of New-London, and as far east of Hartford.

MANTA, a bay of Guayaquil, in South-America, formerly famous for a confiderable pearl fifhery; but it has been totally difcontinued for fome years. There is also a point of this name on the coaft near it. The bay has its name from the great numbers of large fifth called mantas, the catching of which is the common employment of the inhabitants. The method of carrying on this fifthery is as follows: they throw into the water a log of wood, about 18 feet long, and near a foot in diameter; on one end they place their net, and on the other an Indian ftands in an erect polition, and with a fingle oar rows his tottering bark to the diftance of half a league from the fhore, where he fhoots his net; another Indian follows on a fimilar log, takes hold of the rope faftened to one end of the net, and when fully extended, they both make towards the land, hauling the net after them. It is altonishing to observe with what agility the Indians maintain an equilibrium on these round logs, notwithstanding the continual agitations of the fea, and their being obliged to mind the oar and the net at the fame time. They are indeed excellent fwimmers; fo that if they flip off, they are immediately on the log again, and in their former polition.

MAPLETON, a name given to a pleafant range of excellent farms, 3 miles eaft of Princeton, in New-Jerfey.

MAQUOIT, a bay of fhoal waters in Cafco Bay, in the diffrict of Maine, about 20 miles north of Cape Elizabeth, frequently mentioned in the hiftory of Maine; where the Indians were used to land with their cances, and from thene carry them to Pejebfcat Falls, on Androfcoggin river. This was done with the toil of only 4 hours walk. From these falls they went down into Kennebeck river; and from thence continued their route up that river to Wefferunfett.

fett, and thence over to St. Lawrence; or furned and went down through Monfeag bay; towards Penobicot; or from the falls they continued their progrefs up Androicoggin river, beyond the White Mountains, and over to Connecticut river, and from thence to Lake Memphremagog, and down to the limits of Canada.

208

MARACAIBO, Maracaybo, or Maracaya, a finall but rich city of Venezuelo, a province of Terra Firma in South-America, fituated on the weftern bank of the lake of the fame name, about 18 miles from its mouth and 73 S. W. of Corg. It is well built, has feveral ftately houfes, very regular, and adorned with balconies, from which there is a profpect of the lake, which has the apearance of a fea. Here are about 4000 inhabitants, of whom 300 are able to bear arms. It has a governor fubordi-nate to the governor of Terra Firma. Here is a large parochial church, an hospital, and 4 convents. Vessels from 25 to 30 tons frequent this port, with manufactures and merchandize from the places near the lake, which are afterwards put on board Spanish ships that come hither to buy them. Ships are built at Maracaibo, which trade all over America, and even into Spain, this place being very commodious for thip-building. It lies 338 miles eaft of Rio de la Hacha. N. lat. 10. 51. W. long. 70. 35.

MARACAIBO Lake, or rather Gulf, a large collection of waters, on which the town above mentioned is fituated. It is near 208 miles long, and in fome parts, 50 in breadth, running from S. to N. and emptying itfelf into the N. Sea; the entrance of which is well defended by ftrong forts; but Sir Henry Morgan paffed by them, plundered feveral Spanifh towns on the coaft, and defeated a fquadron which had been fent to intercept him. As the tide flows into the lake, its water is fomewhat brackifh, notwithstanding the many rivers it receives. It abounds with all forts of fifh, fome of which are very large. By the navigation of this lake, the inhabitants of Venezuela carry on a trade with those of New Granzda. The lake becomes narrower towards the middle, where the town is crected.

MARAGNON. See River of Amazons. MARAGNON, or Maranon, or MarigMAR

non, the name of a northern captainship of Brazil. "Chief town, St. Louis.

imminen

great det

A batter

in 1795

by order

ery emp

the inh:

this bufi

other in

year 17

lars. N

1649, a

long. 69

county,

tance fro

Elopus,

city. It

cluding

fus of I

electors.

Ononda

on Skar

Ononda

corpora

the tow

Ononda

referved

were ele

county,

of Dela

ladelphi

lies. I

long wh

driving

E. fide

and of

banks (

Paflam

mated :

da, Te

in the l

New-H

bagog

and run

gin riv

fouth

Profpe

from w

MAI

MAI

MAI

MAF

MAR

MAR

Lake.

MAR

MAR

fide of

MAR

MARANHAO, a fmall island at the mouth of the noted rivers Maracu; Topecoru, and Mony, on the N. fide of the province of Maranhao, or Maranon in Brazil. The island is oblong, 4 miles in circuit, very fertile, and well inhabited. The French, who feized on it in 1612, built a town here, called St. Louis de Maragnan; but it is now in the hands of the Portuguele, and is a bishop's fee. It is very strong, and has a ftout caffle built on a rock, towards the fea, which commands a very convenient harbour. The ifland itfelf is very difficult of access; by reafon of the rapidity of the three rivers which form it : fo that veffels mult wait for proper winds and feafons to vifit it. Befides the town mentioned here, are two finaller ones, viz. St. Andero, on the most northerly point, and St. Jago on the fouthern. The natives have about 27 hamlets, each confifting of four large huts, forming a fquare in the middle; all being built of large timber, and covered from top to bottom with leaves : fo that each may contain 200 of 300 perfons. The inhabitants are ftrong and healthy, and live to a great age; bows and arrows are their only weapons, with which they are very dextrous : but they are fierce and cruel, efpecially to their enemies. The continent, 3 or 4 leagues from the filand, is inhabited by the Tapouytapare, and Toupinambois nations, who are wild and fierce, and divided into 15 or 20 fuch hamlets, as have been defcribed above. Contiguous to these are the territories of Cuma and Gayeta, inhabited by nearly the fame fort of people. The capital, Maragnan, has a harbour at the mouth of the river St. Mary, on the Atlantic ocean; 495 miles N. W. of Cape St. Roque. S. lat 2. 27. W. long. 44. 36.

MARBLEHEAD, a port of entry and post-town in Effex county, Massachusetts, 4 miles S. E. of Solem, 19 N. E. of Boston; containing 4 Episcopal and 2 Congregational churches, and 5,665 inhabitants. The harbour lies in front of the town S. E. extending from S. W. to N. E. about one mile and a half in length, and half a mile broad. It is formed by Marblehead neck on the S. and E. and is protected by a fea wall, which, before its late repairs, was in imminent imminent danger of giving way, to the great detriment, if not ruin of the port. A battery and citadel were erected here in 1795, for the defence of the place, by order of Congress. The bank fiftery employs the principal attention of the inhabitants, and more is done of this business, in this place, than in any other in the State. The exports of the year 1794, amounted to 184,532 dollars. Marblehead was incorporated in 1649, and lies in N. lat. 42. 50. W. long, 69. 49.

MARBLETOWN, a township in Ulfter county, New-York, fituated on the W. fide of Hudson's river, and fome diftance from it; 8 miles S. W. by S. of Esopus, and near 80 N. of New-York city. It contains 2, 190 inhabitants, including 374 flaves. By the State cenfus of 1796, 374 of the inhabitants are electors.

MARC, ST. See Mark.

MARCELLUS, a military township in Onondago county, New-York, fituated on Skaneatetes lake, 11 miles W. of Onondago Caffle. Marcellus, as incorporated in 1794, comprehends alfo the township of Camillus, part of the Onondago refervation. and part of the referved lands lying S. W. of the Salt Lake. In 1796, 65 of its inhabitants were electors.

MARCUS HOOK, a town in Chefter county, Pennfylvania, on the weft fide of Delaware river, 20 miles below Philadelphia. It contains about 30 families. Here are two rows of piers, or long wharves, to defend veficls from the driving of ice in winter.

MARECHAUX, Cape, forms the N. E. fide of the bay of Jacmel, in the ifland of St. Domingo. N. lat. 18, 18.

MARECHITES Indians inhabit the banks of the river St. John, and around Paflamaquoddy bay. They are effimated at 140 fighting men.

MAREQUITA, a city of New Granada, Terra Firma, S. America.

MARGALLAWAY, a river which rifes in the Diffrict of Maine, and croffes the New-Hampfhire line between Lake Umbagog and a mountain on the north, and runs fouth-weftward to Amarifcoggin river. Its mouth is ro rods wide.

MARGARET's Bay, St. a port on the fouth coalt of Nova-Scotia, between Prospect Harbour and Mahone Bay; from which laft it is separated by a pro-

montory, on which is the high land of Afpotagoen.

MARGARETTA, or Santa Margaretta de las Caraccas, an island of Terra Firma, in S. America, from which it is parted by a ftrait 24 miles wide; 68 miles W. of Paria, or New Andalufia. Columbus discovered it in his third voyage, anno 1498. It is 40 miles in length and 24 in breadth; and, being always verdant, affords a most agreeable profpect. It abounds in pasture, maize and truit; but there is a fearcity of wood and water. There was once a pearlfiftery on its coaft, which produced one pearl, the fineft ever feen, valued at £25,000 fterling, bought by the king of Spain. The inhabitants are a mixture of Indians and Spaniards, who are lazy and fuperftitious. Here are feveral forts of animals, particularly wild hogs, with fish and fowl. N. lat. 11. 46. W. long. 64. 12.

MARGARET'S Iflands, in the N. Pacific ocean, were discovered by Capt. James Magee, in the ship Margaret, of Boston, in his voyage from Kamschatka in 1780. Their latitude is 24. 40. N. long. 141. 12. E.

MARGARETTSVILLE, a village in Washington county, Maryland, about 10 miles S. by E. of Elizabeth-Town and 6 N. E. of William's Port.

MARGOT, the river and heights of Margot are on the E. fide of the Miffilippi. The river has a westerly course. and is faid to be navigable for hatteaux a number of miles. The ground below its junction with the Miffifippi, in lat. 35. 28. N. affords a commanding, airy, pleafant, and extensive fituation for fettlements ; the foil is remarkably fertile. About 3 miles below this, the French built Assumption Fort in 1736. when at war with the Chickafaws, but the year after it was demolifhed, when a peace was concluded. It is 70 miles from the river St. Francis, and 104 from the Chickalaw river.

MARCOT PORT, a maritime village on the N. fide of the ifland of St. Domingo, in 19.48.N. lat. 9 leagues weftward of Cape Francois.

MARIA, *Cape Santa*, is the northern cape at the mouth of La Plata river, in S. America; 9 leagues from the bay of Maldonade, and 20 from Montebideo, a bay fo called from a mountain which overlooks it.

MARIA

nthip it the racu; ide of anon 6 45 well feized called now d is a d has wards conitfelf on of which it for it it. , are

o, on

Jago

have

ng of

in the

mber,

10 005

ftrong

age ;

wea-

trous:

ecially

3 or 4

ited by

mbois

e, and

ets, as

iguous

with

na and e fame agnan, e river 1; 495 ie. S. try and flachu-N. E.

pal and

in front

S. W.

half in

It is

the S.

ea wall,

was in

minent

5,661

00

MARIA SANTA, 2 town of the audience of Panama, in S. America. It was built by the Spaniards foon after they difcovered the gold mines in its neighbourhood. N. lat 7. 43. W. long. 78. 12.

MARIAGALANTE, one of the Caribbee Islands in the Atlantic ocean; fo called from the fhip's name in which Columbus discovered it, in 1493. It s of an elliptical figure, 41 leagues from N. to S. and 3 from E: to W. It lies 5 or 6 leagues S. eafterly of Guadaloupe, about half its furface is barren mountains. There are only two parifhes, the principal at the fouth defended by a fort called Baffeterre. It is indifferently watered, but produces 800,000lb. of coffee, 100,000lb. cotton, and 1,000,000lb. of fugar. The French planted a colony here in 1648. It was taken by the English in 1692, but the French foon fettled there again, and still posses it. N. lat. 15. 55. W. long. 61. 6.

MARIANNA, was the name given to the diffrict granted by the Plymouth Council to Captain John Mafon in 1621. It extended from the river Naumkeag, now Salem, round Cape Ann, to Merrimack river, and from the fea to the heads of thefe rivers, with the Iflands lying within 2 miles of the coaft.

MARIE, Cape Dame, the westernmost point of the island of St. Domingo, which with Cape St. Nicholas, forms the entrance of the bay of Leogane. N. lat. 18. 38. W. long. from Paris 76. 51. The town of this name, fituated on the cape, is on the northwesternmost part of the fouth peninfula; 8 leagues welt of Jeremie, and 60 weft of Port au Prince. The towns and villages, along the north coaft of the peninfula, and in the bay or bite of Leogane, between the cape and Port au Prince, are Petit Trou, Anfe a Veau, Maragoane, Petite Goave, Grand Goave, &c.

MARIE, Straits of, connect Lakes Superior and Huron, which will permit boats to pais, but not larger veffels. Near the upper end of these firaits, which are 40 miles long, is a rapid which (though it is impossible for canoes to ascend) may be navigated by boats without danger, when conducted by able pilots. The firaits afford one of the most pleasing prospects in the world: on the left, leading to lake Su-

perior, may be feen many beautiful little iflands that extend a confiderable way before you; and on the right an agreeable fucceffion of finall points of land which project a little way into the water; and contribute with the iflands to render it delightful.

MARIEL, Port, a harbour on the north fide of the island of Cuba, which will admit frigates of 30 guns.

MARIETTA, a polt-town and fettle-ment of the N. W. Territory, fituated on the Ohio at the mouth of the Mufkingum. The Campus Martius in this town is an elevated public fquare, founded by the Ohio Company; in the year 1788. The fortification is all of hewn timber, and for appearance; convenience; and defence, of fuperior excellence. It is more than 30 feet above the high banks of the Muskingum; and only 159 yards diftant from that river, with a beautiful natural glacis in front. The town confifts of 1,000 houfe-lots of 90 by 180 feet; the spacious freets interfect each other at right angles, and there are neceffary fquares referved for ufe; pleasure and ornament. There are but tew houses yet erected. It is ig miles above Bel-Pre, 86 fouth-weft of Wheeling, 146 fouth-weft of Pittfburg, 24d north-eaft of Lexington in Kentucky, and 460 W. by S. of Philadelphia: The mouth of Mulkingum river lies in

lat. 39. 34. long. 82. 9. MARK, St. 1 town of E. Florida, at the head of the bay of Apalachy; 180 miles weft of St. Auguitine, and 105 from the Alachua Savannah. N. lat. 30. 12. W. long. 85. 45.

30. 12. W. long. 85. 45. MARK, St. a jurifdiction in the weft part of the island of St. Domingo, con-taining 4 parisher. Its exports, thipped from the town of its name, from Jan. 1, 1789, to Dec. 31, of the fame year, were 3,06 5,047lb. white fugar, 7,931,710lb. brown fugar, 7,041,852lb. coffee, 3,250,890lb. cotton, 349,819lb. indigo, and various articles to the value of 2,250 livres : the total value of duties on exportation 116,974 dollars 4 cents. The town of St. Mark lies at the head of a bay of its name, which is at the head of the Bay or Bite of Leogane. The bay is formed by Cape St. Mark on the fouth, and Morne au Diable on the north. This town, although fmall, is reckoned the pleafanteft in the ifland. Its commerce is confiderable. It owes

MAR townfhij Montgo Marlbor

tants ;

58 flave

a great

a great deal of its embelliftments to the attention of M. de Marbois, during his administration. It is 22 leagues welt of Hinche, 19¹/₂ north-welt of Port au Prince, 14 fouth by welt of Les Gonaives, 30 fouth of Port de Paix, and 26¹/₂ fouth-welt of Cape Francois. N. lat. 19. 5. W, long, 75, 10.

ul lit-

erable

ght an

nts of

to the

flands

in the

which

fettle-

tuated

Muf-

in this

found-

ie year

hewn

nience,

ce. It

e high

ly 159

with a

The

of 90

inter

d there

n ulei

re but

) miles

Nheel-

5, 240

tucky,

elphiac

lies in

ida, at

1; 180

nd 105

N. lat.

he weft

), con-

hipped

Jan. 1,

r, were

710lb.

coffee,

. indi-

alue of

duties

cents.

ie head

at the

ogane.

lark on

on the

sall, is

ifland.

t owes

a great

J.

MARLBOROUGH, a county in the north-eaft corner of Cheraws diffrict, on the Great Pedee river, S. Carolina, 25 miles long, and 19 broad.

MARLBOROUGH, New, a township in Berkshire county, Massachusetts, containing 1,550 inhabitants. It was incorporated in 1759, and is 144 miles welt by fouth of Boston.

MARLBOROUGH, an ancient and wealthy township in Middlefex county, Maffachusetts, (the Okommakamefit of the Indians) was incorporated in 1660, and contains 1,554 inhabitants. It is 28 miles W. of Bolton. A mode of manufacturing Spanish brown, from a kind of earth or loam, faid to refemble bed-ore, though not impregnated with particles of iron, has lately been difcovered in this town, by an ingenious gentleman. He constructed an air furnace, at a trivial expense; and in the year 1794, could calcine and prepare for the mill a ton in 24 hours, 6 days in fucceffion, without great expense of wood. Connoiffeurs in paints acknow-ledge it is good. His first attempts in making spruce yellow were likewife flattering.

MARLEOROUGH, a township in Windham county, Vermont, having Newfane on the north, Halifax south, Brattleborough east, and Wilmington on the west. It contains 629 inhabitants.

MARLBOROUCH, a poft-town in Chefhire county, New-Hampfhire, fix miles from Keene, 20 north of Winchendon, and 26 from Athburnham in Maffachusetts. It was incorporated in 1276, and contains 786 inhabitants.

MARLBOROUGH, New, a township in Ulster county, New-York on the west fide of Hudson's river, north of Newburgh. It contains 2,241 inhabitants; of whom 339 are electors, and 58 flaves.

MARLBOROUGH, the name of three townships in Pennsylvania, the one in Montgomery county, and East and West Marlborough in Chefter county.

MARLEOROUGH, Lower, a town of Maryland, fituated in Calvert county on the eafl fide of Patuxent river, 24 miles fouth eafl of Washington city. It contains about 60 houses, and a ware house for the inspection of tobacco. The river is navigable for ships of burden for fome miles above the town.

MARLBOROUGH, Upper, the chief. town of Prince George's county, Maryland. It is fituated on the fouth-weft fide of Hatavifit, one of the two principal branches of Patuxent river. It contains about 120 houfes, a courthoufe, and a ware-houfe for the infpection of tobacco. It is 47 miles 5. S. W. of Baltimore, and about 15 eafterly of the city of Wafhington.

MARLOW, a township in Cheshire county, New-Hampshire, settled in 1761, 108 miles from Portsmouth. It contains 313 inhabitants.

MARMOSETS, a harbour in the ifland of St. Domingo, which may receive merchantmen, but the entrance of it is rendered difficult by the breakers. It lies between Cape Rouge and Grand Port Berhagne.

MARQUES, a cape on the coaft of Old-Mexico, or New-Spain in the South Sea.

Thefe illands are 5 MARQUESAS. in number, viz. La Magdalena, St. Pedro, La Dominica, Santa Chriftina, and Hood's Ifland, fituated in the South Pacific Ocean, between the latitude of g. 26. and 10. 25 fouth ; and between the longitude of 138. 47. and 139. 13. welt. They were first discovered by Mendana and Quiros, in 1595; and in 1774, Capt. Cook afcertained their fituation more particularly, which before was different in different charts. La Dominica, the largest, is about 16 leagues in circuit, in lat. 9. 44. fouth. Hood's Island was difcovered by Capt. Cook in 1774. The inhabitants, taken collectively, are, without exception, the finest race of people in these feas; and for good fhapes and regular features they perhaps furpais all nations. They are thought to be of the fame origin as those of Otaheite and of the Society Islands. They have hogs, fowls, plantains and other vegetables and roots; likewife a few bread-fruit and cocoa trees. Northnorth-weft of these islands, from 35 to 50 leagues diftant, are the 7 ifles called Ingraham's Ifles; which fee.

MARROWYNE,

Guiana, in S. America.

MARSHFIELD, a township in Ply-mouth county, Massachusetts, bounded S. by Duxborough, and 36 miles S. E. of Boston. It was incorporated in 2640, and contains 1269 inhabitants.

MARSHFIELD, a township in Caledonia county, in Vermont; adjoining to Calais on the N. W. and Peachum N. E.

MARSHPEE, by feveral writers called Masspee, an ancient Indian town in Barnstable county, Massachusetts, containing 308 inhabitants. There is ftill an Indian church here, but not more than 40 or 50 perfons are pure Indians. The whole confifts of about 80 families, principally of a mixed race, being 280 fouls in all. They have greatly decreafed fince 1693, when there were 214 adults, befides ftragglers in the plantation and places adjacent; under the care of Mr. Rowland Cotton, minister of Sandwich.

MARSHY HOPE, the north-weltern branch of Nanticoke river in Maryland. Federalfburg lies on the E. fide, 13 or 14 miles from its mouth.

MARTHA BRAE, a finall town havving a harbour, 7 leagues W. of Montego Point. It is frequented only by fuch veffels as are particularly defined for this place. There is a bar with 16 or 17 feet water in going in; and the paffage in coming out between the Triangle Rocks is not more than 60 feet wide with 61 or 7 fathoms water. See Falmouth.

MARTHA, River, St. See Magdalena.

MARTHA, St, a province of Terra Firma, or Caftile del Oro, in S. America; bounded N. by the North fea; E. by Rio de la Hacha; S. by New-Granada, and W. by the territory of Carthagena. The air is colder here and more pure than in the adjoining countries. The vallies are fertile, and produce maize, with other grains and fruits, efpecially oranges, lemons, pine-apples, grapes, &c. alfo indigo and cochineal, and fome woods for dying. The mountains which are known to failors by the name of the Snowy mountains of St. Martha, produce gold, emeralds, fapphires, chalcedonies, jafper, and curious marble. On the coafts where finuggling is carried on, are falt-works, and two

MARROWYNE, a river of Dutch | pearl fisheries. It is about 300 miles inlength, and 200 in breadth, is a mountainous country, and in general reckoned the highest in this part of the world.

MARTHA, St. a city in the province last mentioned, with a harbour on the N. Sea, at the mouth of the Guayra; about 124 miles N. E. of Carthagena, It is the refidence of a governor and bishop. The houses are built with canes, and are very neat. Its harbour is large, convenient, and fafe, and the environs agreeable and fertile. At prefent it contains about 3000 inhabitants, who carry on an extensive rich trade, and make great quantities of cottons, ftuffs, &c. with earthen ware, which is much efteemed. . It has a valuable pearl fifhery, in which great numbers of flaves are employed, whofe dexterity in diving for the oyfters is very extraordinary; fome of whom will remain for a quarter of an hour under water, and will rife with a bafket full. N. lat. 11. 26. W. long. 73. 59. MARTHA's VINEYARD, an ifland be-

longing to Duke's county, Maffachufetts, called by the Indians Nope, or Capawock, is fituated between 40. 17. and 41. 29. N. lat. and between 70. 22. and 70. 50. W. long. about 21 miles long and 6 broad, and lies a little to the W. of Nantucket. Martha's Vineyard, Chabaquiddick, Noman's Ifland, and the Elizabeth Islands, which contain about 16,500 acres of valuable land, conftitute Duke's county, containing 3,265 white inhabitants, and between 400 and 500 Indians and mulattoes ; who fublift by agriculture and fifting. Cattle and theep are raifed here in great numbers; and rye, corn and oats are the chief produce of the ifland. White pipeclay, and yellow and red ochre are found in Martha's Vineyard. The ravages of war were feverely felt in this industrious fpot. In September, 1778, the British made a requisition of their militia arms, delivered up. See Gay Head. MARTICK, a township in Lancaster

county, Pennfylvania.

MARTIN, a county of Halifax diftrict, N. Carolina, adjoining Tyrrel, Halifax, Bertie, and Pitt counties. It contains 6,080 inhabitants, of whom 1,889 are flayes.

MARTIN, Cape St. on the coaft of New-Spain on the North Sea.

MARTIN'S

MART molt of 1 in the At on the n a league mew on about 1 commod W. fide. lakes of way with water bu and is fa terns. fifh, par water po bers of hogs, tu able. I gums; fplinters ed, emit bacco, 1 is recke iflands. ifland in they ha Dutch : tween t tacked Thornh yen out return ti now enj the 55,0 tains. and fhee iflands. ton and French lies, and no more flaves. MAR the Car lat. 14. lying al badoes, is abou breadth miles. from w fide, a rivers, and in the foil and fue found it fugar i

les in--autor ckonvorld. vince n the ayra ; gena, r and with rbour id the t pretants, e, and ftuffs, much rl fifhflaves diving inary; uarter vill rife 6. W. and beflachupe, or 10. 17. 70. 22. 1 miles e to the neyard, d, and contain le land, taining between attoes ; filling. in great are the ite pipere found ages of uffrious British ia arms, ch were

ancaster

fax dif-Tyrrel, ies. It f whom

coaft of

MARTIN's, St. one of the northernnost of the Caribbee islands; fituated in the Atlantic ocean, between Anguilla on the north, from whence it is diftant a league and a half, and St. Bartholomew on the fouth-east, 15 miles. It is about 15 leagues in circumference, with commodious bays and roads on the N. W. fide. Here are good falt-pits, and lakes of falt water, which run a great way within the land; but has no fresh water but what falls from the clouds, and is faved by the inhabitants in cifterns. The falt lakes abound in good fifth, particularly turtle; and the falt water pools are frequented by valt numbers of birds. In the woods are wild hogs, turtle-doves, and parrots innumerable. Here are feveral trees producing gums; and plenty of the candle-tree, fplinters of which, when dry and lighted, emit a very fragrant imell. Its tobacco, the chief commodity cultivated, s reckoned the beft in the Caribbee iflands. The Spaniards abandoned this ifland in 1650, and blew up a fort which they had erected. The French and Dutch afterwards thared the island between them. But in 1689, were attacked and plundered by. Sir Timothy Thornhill, and in July, 1744, were driyen out by the British forces, and did not return till after the peace of 1763. They now enjoy about 35,000 acres, out of the 55,000 which the whole ifland con-The two colonies breed poultry tains. and fheep, which they fell to the other islands. They also cultivate a little coton and coffee. About 20 years ago the French part contained 400 white fami-lies, and 10,000 flaves. The Dutch part no more than 60 families, and about 200 flaves. - N. lat. 18, 6, W. long. 62. 30. MARTINICO, one of the largest of the Caribbee iffands, fituated between lat. 14. and 15. N. and in long. 61. W. lying about 40 leagues N. W. of Barbadoes, and 22 S. by E. of Guadaloupe, is about 60 miles in length, and 30 in breadth; containing about 260 fquare miles. The inland part of it is hilly, from which are poured out on every fide, a number of agreeable and uteful rivers, which adorn and enrich this iffand in a high degree. The produce of the foil is fugar, cotton, indigo, ginger and fuch fruits and productions as are found in the neighbouring iflands. But fugar is here, as in all the Weft-India

MAR

MAR

iflands, the principal commodity, of which they export a confiderable quantity annually. Martinico is the refidence of the governor of the French islands in thefe feas, Its bays and harbours are numerous, fafe, and commodious, and well fortified, It is divided into 28 parifhes, which contain about the fame number of towns and villages, and 2 principal towns, Fort Royal and St. Pierre. In 1770, it contained 12,450 white people; 1814 free blacks or mulattoes; 70,553 flaves, and 443 fugitive negroes. About the fame time its products were computed at 23 million lb. of fugar, 3 million lb. of coffee, 600,000 lb, of cotton, and 40,000 lb. of cocoa. Foreigners carry off privately about a 12th part of the produce of the ifland, and the reft goes to France. This ifland called Madanina by the ancient natives, was fettled by the French in The British reduced it in 1762. 1635. but reftored it at the conclusion of peace in 1763. It was again taken by the British in 1794.

MARTINICO, Little. See Bekia. MARTINSBOROUGH, a town of N. Carolina, fituated on the S. fide of Tar river, and 20 miles above Washington.

MARTINSBURG, a post-town of Virginia, and capital of Berkeley county, fituated about 8 miles fouth of the Patowmac, in the midft of a fertile and well cultivated country, and 25 miles from the mineral (prings at Bath. It contains upwards of 70 houfes, a courthoufe, gaol, and Epifcopal church; and contiguous to the town is one for Prefbyterians. It is 10 miles from Shepherdftown, 30 from Pittfylvania courthoufe, 25 from Rocky Mount or Franklin court houfe, 22 N. E. of Winehefter, 88 N. N. W. of Alexandria, and 244 from Philadelphia.

MARTINVILLE, a post-town, and the capital of Guilford county, in N. Carolina, is agreeably fituated on the east fide of Buffaloe creek, a branch of Haw river and contains about 40 houses, a court-house and gaol. It lies N. E. of Bell's Mill, at the head of Deep river; 48 miles north-west of Hillsborough 27 east of Salem; 50 north-east of Salifbury; 151 west by fouth of Halifax, and 500 fouth-west of Philadelphia. N. lat. 36. 5. W. dong. 79. 43.

It was near this town that General Greene and Lord Cornwallis engaged

in one of the best fought actions in the late war, on the 15th of March, 1781: and although the Americans were driven off the field, the British fuffered fo great lofs, that they could not purfue the victory. The greatest part of the country in which the action happened, was a wildernefs, with a few cleared fields interfperfed. The American army, when the action commenced, was posted on a rising ground about a mile and a half from Guilford court-house. MARYLAND, one of the United States of America, lies between lat. 37. 56. and 39. 44. N. and between 75. 8. and 79. 38. W. long. It is about 734 miles in length, and 110 in breadth, and contains 14,000 fquare miles, one-fourth of which is water. It is bounded N. by Pennfylvania; E. by Delaware State, and the Atlantic ocean; S. and W. by Virginia : and is divided into 19 counties, II of which are on the Western and s on the Eaflern shore of Chefapeak bay. Those on the Western shore are Hartford, Baltimore, Ann Arundel, Frederick, Alleghany, Wafhington, Mont-gomery, Prince George, Calvert, Charles, and St. Mary's, which contain 212,089 inhabitants ; those on the Eastern fore are Cecil, Kent, Queen Ann, Caroline, Talbot, Somerlet, Dorchefter, and Worcefter; containing 107,639 inhabitants. The whole number of inhabitants in the State being 319,728; of whom 103,036 are flaves. Each of the counties fends 4 reprefentatives to the house of delegates; befides which the city of Annapolis, the metropolis, and the town of Baltimore fend two each. The chief towns of the State, befides thele two, are Georgetown bordering on the city of Washington on the river Patowmack, Fredericktown Hagarftown and Elkton. The city of Wafhington, or the Federal City, was ceded by the State of Virginia and Maryland, to the United States, and by them eftablifhed as the feat of their government, after the year 1800.

Chefapeak bay, which divides this State into eaftern and weftern divisions, is the largeft in the United States. From the eaftern fhore in Maryland; among other fmaller ones, it receives Pokomoke, Nanticoke, Choptank, Chefter and Elk rivers. From the north, the rapid Sufquehannah; and from the weft, Patapico, Severn, Patuxent and Pato-

MAR

mak, half of which is in Maryland, and half in Virginia. Except the Sufquehannah and Patomak, these are small rivers.

The face of the country is uniformly level and low in most of the counties on the eastern shore, and confequently covered in many places, with flagnant water, except where it is interfected by numerous creeks. Here also are large tracts of marsh, which, during the day, load the atmosphere with vapour, that falls in dew, in the close of the summer and fall seasons, which are fickly. The spring and summer are most healthy. Wheat and tobacco are the staple commodities. In the interior country, on the uplands, considerable quantities of hemp and flax are raised.

The inhabitants, except in the populous towns, live on their plantations often feveral miles diftant from each other. To an inhabitant of the middle, and efpecially of the eaftern States, which are thickly peopled, they appear to live retired and unfocial lives. The negroes perform all the manual labour. The inhabitants of the populous towns, and those from the country who have intercourfe with them, are in their manners and customs genteel and agreeable.

The inhabitants are made up of various nations of many different religious fentiments; few general observations, therefore of a characteristical kind, will apply. It may be faid, however, with great truth, that they are in general, very federal, and friends to good government. They owe little money as a State, and are willing and able to difcharge their debts. Their credit is very good ; and although they have fo great a proportion of flaves, yet a number of influential gentlemen have evinced their humanity and their disposition to abolish fo difreputable a traffic, by forming themielves into a fociety for the abolition of negro flavery.

The trade of Maryland is principally carried on from Baltimore, with the the other States, with the Weft-Indies, and with tome parts of Europe. To these places they tend annually about 30,000 hogheads of tobacco, besides large quantities of wheat, flour, pigiron, lumber and corm-beans, pork, and flax-feed in small quantities: and receive in return, cloathing for themfelves and negroes, and other dry goods, wines, spirits, sugars, and other West-India

India con nerally in The tot ports fro 1790 wa! Value the fame 1791 1792 1793 1794 1795 In the wheat exp Indian co 4,286 do 151,445 do. India 3,104 kej The R firft fettle numerous there are] lifh, Scot German (Friends, I ifts, Nico all enjoy feminaries Wasbington ty, which Wasbington tertown, i a law en fund was 1250l. a College wa a permane a year. polis, whe for it. V obtained 1 ing on t colleges (the name land,' wh State, for and the pr chancellor alfo erecti on Patown of genera Methodift ton, in Hi of Cokefbi The leg pofed of ty and Houfe General 1

\$04

MAR

India commodities. The balance is generally in their favour.

. and

ies on ly cont waby nu-

large

e day,

, that

Immer

althy.

: com-

ry, on

ties of

popu-

ns oft-

other.

and ef-

ich are

ive re-

egroes

he in-

s, and

: inter-

anners

f vari-

ligious

ations,

d, will

r, with

eneral,

govern-

y as a

to dif-

is very

o great

nber of

ed their

abolifh

orming

e aboli-

ncipally

ith the

Indies,

c. To

/ about

befides

Ir, pig-

, pork,

es: and

r them-

r Weit-

goods,

India

The

ivers.

The total				Dollars. Cts.
1790 was Value o				2,027,777 64
the fame ye		-	-	1,945,899 55
1791		1.	4.80	2,239,690 96
1792		4		2,623,808 33
1793	1.	192	124	3,665,055 50
1794	•			5,686,190 50
1705	S. MAR	1.23	per la	6.811.270 CC

In the year 1791, the quantity of wheat exported was 205,571 bufhels— Indian corn 205,643 do.—buck-wheat 4,286 do.—peas, 10,619 do. befides 151,445 barrels of wheat flour, 4,325 do. Indian meal, 6,761 do. bread, and 3,104 kegs of crackers.

The Roman Catholics, who were the first fettlers in Maryland, are the most numerous religious fect. Befides thefe, there are Protestant Episcopalians, Englifh, Scotch, and Irish Prefbyterians, German Calvinists, German Lutherans, Friends, Baptifts, Methodifts, Mennonifts, Nicolites or new Quakers; who all enjoy liberty of confcience. The feminaries of learning are as follow : Walbington Academy, in Somerfet county, which was inftituted by law in 1779. Washington College, instituted at Cheftertown, in Kent county, in 1782. By a law enacted in 1787, a permanent fund was granted to this inftitution of 12 50l. a year, currency. St. John's College was instituted in 1784, to which a permanent fund is affigned, of 17 501. a year. This college is to be at Annapolis, where a building is now prepared for it. Very liberal fubfcriptions were obtained towards founding and carrying on these seminaries. The two colleges conftitute one university, by the name of ' the University of Maryland,' whereof the governor of the State, for the time being, is chancellor, and the principal of one of them, vicechancellor. The Roman Catholics have also erected a college at Georgetown, on Patowmac river, for the promotion of general literature. In 1785, the Methodifts inftituted a college at Abington, in Hartford county, by the name of Cokefbury college.

The legislature of this State is compoled of two diffinct branches, a Senate and House of Delegates, and flyled, The General Affembly of Maryland. On MAR

the fecond Monday in November, annually, a governor is appointed by the joint ballot of both houses. The governor cannot continue in office longer than three years fucceffively.

305

Maryland was granted by king Charles I. to George Calvert, baron of Baltimore, in Ireland, June so, 1632. The government of the province was by Charter, vefted in the proprietary. In the year 1689, the government was taken out of the hands of lord Baltimore, by the grand convention of England and in 1692, Mr. Copely was appointed governor, by commission from William and Mary. In 1692, the Protestant religion was established by law. In 1716, the government of this province was reftored to the proprietary, and continued in his hands, till the late revolution, when, though a minor, his property in the lands was confilcated, and the government affumed by the freemen of the province, who, in 1776, formed the conftitution now exifting. At the close of the war, Henry Harford, Efq. the natural fon and heir of lord Baltimore, petitioned the legiflature of Maryland, for his eftate; but his petition was not granted. Mr. Harford effimated his lofs of quit-rents, valued at twenty years purchafe, and including arrears, at 6259,488: 5:0, dollars a 7/6-and the value of his manors and referved

lands, at £327,441, of the fame money. MARYLAND POINT, is formed by a bend in Patowmac river, W. of Port Tobacco.

MARY, St. a port on the fouth fide of the Bay of Fundy.

MARY Cape, St. is the moft fouthern promontory of Brazil, in South-America.

MARY, Cape St. the point of land which forms the northern fide of the mouth of La Plata river in Paraguay or La Plata, in South America. S. lat. 35. 14. W. long. 55. 32.

MARY, Cape St. forms the foutheaftern head land at the mouth of Placentia Bay, Newfoundland Ifland.

centia Bay, Newfoundland Ifland. MARY'S RIVER, St. a branch of the Miami which empties into Lake Erie. See Girty's Town.

MARY'S RIVER, St. forms a part of the fouthern boundary line of the United States. It in part divides Georgia from Eaft-Florida, and is very crooked, with a wide open marfh on each fide,

from

from its mouth upwards 30 miles, where the marfh is terminated by thick woods. It is nearly ftraight for 30 miles farther, up to Allen's, an Indian trader at the head of navigation; where it is like a dead creek, 4 fathoms deep, and 30 rods wide. It rifes in the great Okalonoka' or Ekanfanoga (wamp, which extends fouthwardly into Eat-Florida. It is thought to be what is called May river, difcovered by John Ribalt, in 2563. Between this, and Nafiau river, lies the low even coaft of Amelia Ifland. The harbours of both rivers are spacious, but St. Mary's is the fareft. It has 9 feet of water at low fpring tides. It runs a courie of 150 miles, and enters the ocean between the points of Amelia and Talbert's iflands, in lat. 30. 44. and is navigable for veffels of confiderable burden for 90 miles. Its banks afford immenie quantities of fine timber, fuited to the Weft-India market. Along this river, every 4 or 5 miles, are bluffs convenient for veffels to hand to and load.

MARY's, St. a post-town and port of entry of Georgia, fituated on St. Mary's river, a few miles from its mouth. It is a fmall place, and has little trade. It is 129 miles fouth of Savannah. N. lat. 30. 45. W. long. 79. 12. MARY's, St. a county of Maryland,

MARY's, St. a county of Maryland, on the peninfula between Patowmac and Patuxent rivers, 39 miles in length, and 15 in breadth. It contains 15,544 inhabitants; of whom 6,985 are flaves.

MASANETTE, Point, on the fouthern fide of Chaleur Bay, lies about W. by N. above a league and a half from Caraguil Ifland, between which and the ifland runs the main channel.

MASCOMY, a confiderable pond in New-Hampfhire, in the fouth weftern part of Grafton county, lying partly in Lebanon and partly in Enfield townfhips. This pond is from 30 to 40 fathoms deep. The furrounding land bears evident marks, that the furtace of this pond was once 30 or 40 feet higher than its prefent level. By what caufe the alteration was made, and at what time, is unknown; but appearances indicate a fudden rupture, there being no fign of any margin between its former and prefent height. About a mile diftant from its outlet, there is a declivity of rocks, 40 feet higher than the ftream,

et in the

as it new runs. By the fituation of thefe rocks, it appears that they were once a fall, over which the water flowed; but it has now made for itfelf a very deep channel, through folid earth, nearly a mile in length, where it feems confined for futurity.

MASCAUTENS, an Indian nation who inhabit on Lake Michigan, and between that and the Miffifippi. The number of warriors, 400.

MASHEET. See Hancock's River.

MASON, a county of Kentucky, on the fouthern fide of Ohio river. It contains 2,267 inhabitants, of whom 208 are flaves.

MASON, a township in Hillsborough county, New-Hampshire, on the Masiachusetts line, about 70 miles welt of Portsimouth, and 30 N. W. of Boston. It was incorporated in 1768, and contains 922 inhabitants.

MASQUE POCONA, a jurifdiction of Chareas in Peru, extending above 30 leagues. Its air is hot, but not too great for vines. The city of the fame name, where the bishop of Santa Cruz de la Sierra refides, is very thinly inhabited; but there are in other parts of the jurifdiction, feveral populous towns. It produces all kinds of grain and fruits; honey and wax conftitute a principal part of its trade.

MASQUES, or Chilques and Mafques, a jurifdiction of Cufco, in Peru, which begins about 7 or 8 leagues from Cufco, extending about 30 in length. See Chilques,

MASSAC, a fort built by the French, on the north-western fide of the Ohio, about 11 miles below the mouth of Tennessee river. Its remains shand on a high bank, in a healthy agreeable fituation.

MASSACHUSE TTS Proper, (which with the Diffrict of Maine conffitutes) one of the United States of America, is fituated between lat. 41.13. and 43.52. north, and between long. 69.57. and 73.38. weft. Its greateft length is 190 miles, its greateft breadth 90 miles; and is bounded north by Vermont and New-Hampfhire, caft by the Atlantic Ocean, fouth by the Atlantic, Rhode-Ifland and Connecticut, weft by New-York. Maifachufetts is divided into the following counties, whole polls, propertion of the public tax of £1,000, and number of lenators in 1793 were as follows New-

Polls.

3742 6142 12376 LOION 13012 13762 6912 3759 763 1128 6547 6265 6484 5723 6349 1967 493 The 5 included chufetts at 3,631 on the dule, for the fupp in each general June, 1 to their amounts every fq State in flaves. legiflatu ern part tainous Wachul Worceft the level miles. all the y to very different climate, barley, field bea peaches, part of by the n lony, in ftable,] Plymon eft part fandy ar with m The not of the S itrong, and gra

Polls.

MAS

Counties On the Thoufand. Senat. Polls. 3742 Suffolk . 6.93:14: 94 4 Norfolk 68:17: 3 3 6142 12376 Effer 1 1331191 7 5 101091 Middlefex 104:13: 41 4 Hampfhire 1111:18: 01 5 13012 13762 Worcefter 127: 5: 01 5 Plymouth 59: 9: 91 2 6912
 3759
 Barnítable
 so:15:111

 763
 Duke's county
 5:91
 8:31

 1121
 & Nantucket
 6:13:82
 3:

 6547
 Briftol
 53:19:65
 2
 6265 Berkfhire 52: 31 32 2 6484 York 501 11 9 2 5723 Cumberland 43: 6: 51 2 6349 Lincoln 50:131101 2 1967 Hancock 13:17:1 493 Washington 3:1:1 493 Washington 3: 1: 1 5 The 5 counties of the District of Maine 493 Washington included in the above, belong to Maffachufetts. The town of Bolton is rated at 3,631 polls, and is to pay for : 16:81 on the frooo. From the above fchedule, some opinion may be formed of the fuppofed value of the rateable eftates in each county. A committe of the general court reported the above in June, 1793; which report was referred to their next feffion. The population amounts to 378,787 fouls, about 60 for every square mile. This is the only State in the Union in which there are no flaves. Slavery was abolifhed by the legislature fome years ago. The western part of this State is fomewhat mountainous and hilly. See New England. Wachulett mountain in Princetown, Worcefter county, is 2989 feet above the level of the fea, and may be feen 67 miles. In Maffachusetts are to be found all the varieties of foil, from very good to very bad, capable of yielding all the different productions common to the climate, fuch as Indian corn, rye, wheat, harley, oats, hemp, flax, hops, potatoes, field beans, and peas, apples, pears, peaches, plums, cherries, &c. That part of the State which is diffinguished by the name of the Old or Plymouth Colony, including the counties of Barnftable, Duke's, Nantucket, Briftol and Plymouth, in point of foil, is the pooreft part of the State, being generally fandy and light, interspersed, however,

with many excellent tracts of land.

The northern, middle, and western parts

of the State have, generally speaking, a

strong, good foil, adapted to grazing

and grain; very fimilar to the foil of

MAS

New-Hampfhire and Vermont on one fide, and to that of Rhode-Ifland and Connecticut on the other. It has been obferved that the effects of the eaft winds extend farther inland than formerly, and injure the tender fruits, particularly the peach, and even the more hardy apple. The average produce of the good lands, well cultivated, has been effimated as follows : 40 bufhels of corn on an acre, 30 of barley, 20 of wheat, 30 of rye, 100 of potatoes. The ftaple commodities of this State are fifh, beef, lumber, &c.

The country is well watered by a number of fmall rivers, fome of which fall into Connecticut river, which paffee foutherly through the well part of the State; others run northward to Merrimack river, which enters from New-Hampfhire and waters the north-east corner of the State; others pais into Connecticut and Rhode-Ifland ; Myflick and Charles rivers fall into Bofton bay : others fall into the Atlantic Ocean in different parts of the fea-coaft. The chief capes are Ann, Cod, Malabar, Poge, Gay Head, &c. The most noted bays are Massachuletts, Ipswich, Boston, Plymouth, Barnftable, and Buzzard's. There are many other bays of lefs note. The chief illands are Plumb-Ifland. Nantucket, Martha's Vineyard, Elizabeth-Iflands, and numerous finall ifles in Bofton Bay,

The chief iron/manufactures in this State are deferibed in the account of Plymouth and Briftol counties, and their towns Taunton, Bridgewater, Middleborough, &c. where nails have been made in fuch quantities as to prevent, in a great measure, the importation of them from Great-Britain. Nail making was not an object of confiderable attention, until the general court laid a duty on imported nails of every fize. This foon " gave nerves to the arm, and motion to the hammer; and from 400 to 500 nails indifferently made by one hand in one day, 1000 are now well made in the fame time." The machine invented by Caleb Leach of Plymouth, will cut and head 5,000 nails in a day, under the direction of a youth of either fex. There is a machine for cutting nails at Newbury-Port, invented by Mr. Jacob Perkins, which will turn out two bundred thousand nails in a day. The nails are faid to have a decided fuperiority U 2 OVIE

on of the umber of ws: Polls.

no mo

were

flow-

very

near-

con-

a who

tween

mber

ver

y, on

t con-

n 208

rough

Mafia-

veft of

lofton.

d con-

tion of

Dye 30

tot too

le fame

a Cruz

y inha-

parts of

towns.

in and

a prin-

lafques,

which

Cuico,

. See

French,

e Ohio.

of Ten-

nd on a

ble fitu-

, (which

fitutes)

ierica, is

143. 52.

57. and

th is 190

les; and ind New-

ic Ocean.

fland and

k. Mai-

over those of English manufacture, and are fold 20 per cent. cheaper. There are duck manufactories at Bofton, Salem, Haverhill and Springfield, which are in a promiting way. Manufactories of cotton and woollen have been attempted with various fuccefs at Beverley, Worcefter, Bofton and Newbury. There are in this State upwards of 20 paper-mills, which make more than 70,000 reams of writing, printing, and wrapping paper, annually. It was effimated in 1792, that £20,000 worth of paper was yearly made by these mills. The other manufactories for cotton and wool cards, playing cards, floes, lace, wire, &c. are noticed under the defcription of Bolton, Lynn, Iplwich, Dedham, &c. There are feveral fnuff, oil, chocolate and powder mills in different parts of the State, and a number of iron-works and flitting-mills, befides other mills, in common ufe for fawing lumber, grinding grain, and fullingcloth. There were in 1792, 62 diftilleries in this State, employed in diffilling from foreign materials. One million, nine hundred thousand gallons have been diffilled in one year, which at a duty of 11 cents a gal-ion, yields a revenue to the government of 209,000 dollars. There are indeed few articles which are effentially neceffary, and minister to the comfort and convenience of life, that are not manufactured in this state. This Commonwealth is remarkable for its literary, humane and other focieties, which are noticed in their proper places. The militia of Maffachufetts is com-

The militia of Maffachufetts is compofed of all the able-bodied white male citizens from 18 to 45 years of age, excepting from the enrolment, within thefe ages, clergy, fchool-mafters, civil officers of importance, either under the State or federal government, and alfo thofe who have held any military commifion whatever The whole is formed into 10 divifions, and 21 brigades, and confifts of 82 regiments of infantry; 48 troops compoing 12 fquadrons or battalions of cavalry, and 36 companies of artillery, generally two to each brigade. Thele, together, compose a body of about 30,000 infantry, 2,000 cavalry, and 7,550 artillery; the latter are furnished with 60 field pieces, and with tumbrils and apparatus complete. This State, including the Diffrict of Maine, owns more than 3 times as many tons of fhipping as any other of the States, and more than one

third part of the whole that belongs to the united States. Upwards of 29,000 tons are employed in carrying on the fifheries ; 46,000 in the coafting bufinefs, and 96,564 in trading with almost all parts of the world. Pot and pearl afhes, ftaves, flax-feed, bees wax, &c. are carried chiefly to Great-Britain, in remittance for their manufactures ; mafts, provisions, &c. to the East-Indies; fifh, oil, beef, pork, lumber, candles, &c. are carried to the Weft-Indies for their produce, and the two first articles, fish and oil, to France, Spain, & Portugal; roots, vegetables, fruits, and fmall meats, to Nova-Scotia and New-Brunfwick ; hats, faddlery, cabinet-work, men's and women's fhoes, nails, tow-cloth, barley, hops, butter, cheefe, &c. to the fouthern States. The value of exports in the year ending Sept. 30, 1791, was 2,445,975 dollars 53 cents-in 1792, 2,889,922 dollarsin 1793, 3,676,412 dollars, and in 1794 -5,380,703 dollars. For an account of the climate, &c. fee New-England. The chief towns of this State, befides Bofton, the metropolis, are Salem Newbury-Port, Charleftown, Worcefter, Northampton, Springfield, &c.

MASSACHUSETTS, Fort, ftands on the north-western corner of the State of its name, in N. lat 42. 41. 30. 19 miles N. E. by N. of Pittsfield, and 20 due E. of Lanfinburgh city, in New-York State.

MASSACHUSETTS Sound, on the N. W. coaft of North-America, is fituated on the fouthern fide of the Quadras Isles, and leads from the W. into Nootka Sound along the N. fide of Kenrick's Island whole eastern fide forms, with Point Breakfaft, the mouth of Nootka Sound.

MASSACRE River paffes out of the Straits of Magellan S. W. into the fuppofed channel of St. Barbara, which cuts through the ifland of Terra del Fuego, through which, we are informed, Capt. Marcanille of Marfeilles paffed in 1713 into the South Pacific Ocean.

MASSACRE River, on the N. fide of the ifland of St. Domingo, falls into the bay of Mancenilla; which fee.

MASSACRE, a finall ifland on the coaft of Weft-Florida, 2 miles to the eattward of Horn Ifland; 10 miles from the main land, all the way acrofs there is from 2 to 3 fathoms; except the Shoal called La Grand Bature, which firetches a league from the main land, with 2 or 3 feet water on it, and in fome places

places large b Bature, See Da MAS Pacific the Lef W. by des. I the Spar wood, Anfon afferted touchin the N. gle fhip the fhor except t Magee leagues nandes, 82. W. MAS branch MAS Ocean; tuated b a port n Sir Tho paffed th MAS ritory, Ohio ri Miami MAS county, Market by W. o than 5 m MAS ifland of It is e near the fhore, ca MAS of the if W. Ind the N. fouth-ea MAST ward int north of yards w MAT of the if W. of u MAT dious ba of Cub

places not fo much. Behind it is a large bay called L'Ance de la Grand Bature, 8 miles E. of Pafcagoula Bluff. See Daupbin Mand.

gs to

.000

fifh-

inefs.

ft all

thes.

car-

emit-

pro-

i, oil,

e car-

duce.

il, to

vege-

Nova-

fad-

men's

hops,

tates.

nding

ollars

ars-

11794

untof

The

ofton,

bury-

Jorth-

on the

of its

les N.

E. of

State.

the N.

tuated

s Ifles.

lootka

's 10-

Point

Sound.

of the

re fup-

which

rra del

nform-

es paff-

Ocean.

fide of

nto the

on the

to the

miles

acrofs

except

, which

in land,

in fome

places

MASSAFUERO, an island in the S. Pacific Ocean, called by the Spaniards the Leffer Juan Fernandes, 22 leagues W. by S. of the Greater Juan Fernandes. It has always been reprefented by the Spaniards as a barren rock, without wood, water or provisions. But Lord Anfon found this to be a political falfity, afferted to prevent hoffile veffels from touching there. There is anchorage on the N fide in deep water, where a fingle fhip may be fheltered clofe under the fhore, but is exposed to all winds except the fouth. According to Capt. Magee of the fhip Jefferson, it is 38 leagues to the weftward of Juan Fernandes, and in about 33. 30. S. lat. and 82. W. long, from Greenwich.

MASSANUTEN's *River*, a western branch of the Shenandoah.

MASSEDAN Bay, on the N. Pacific Ocean; and W. coaft of Mexico, is fituated between Acapulco and Aquacara, a port near the cape of California, where Sir Thomas Cavendifh lay after he had paffed the Straits of Magellan.

MASEY'S-TOWN, in the N.W. Territory, flands on the northern bank of Ohio river, between the rivers Little Miami and Sciota.

MASSY'S CROSS ROADS, in Kent county, Maryland, is N. E. of New Market, S. E. of George-Town, and S. by W. of Saffafras-Town, a little more than 5 miles from each.

MAST Bay, on the north fide of the ifland of Jamaica, in the N. W. part. It is eaftward of Montego Bay, and near the fhelf of rocks that lies from the fhore, called Catlin's Cliffs.

MASTICK Gut, on the S. W. fide of the island of St. Christopher's in the W. Indies, is between Moline's Gut on the N. W. and Godwin's Gut on the fouth-eaft.

MASTIGON, a river which runs weftward into LakeMichigan, about 11 miles north of La Grande Riviere, It is 150 yards wide at its mouth.

MATA, Point, on the northern fide of the ifland of Cuba, and 9 leagues N. W. of Cape Maify.

MATACA, or Mantaca, is a commodious bay on the N. coaft of the ifland of Cuba, where the galleons ufually come to take in frefh water on their return to Spain, about 12 leagues from the Havannah. It appears to be the fame as Matanze, in lat. 23. 12. N. long. 81. 16. W. Peter Heyn took a great part of a rich fleet of Spanish galleons here in 1627.

MATAIA, a province of S. America, towards the river Amazon, between the mouth of Madeira and Tapaifa rivers.

MATANCA, or Manances, a flort and broad river of E. Florida which falls into the ocean fouth of St. Augustine.

MATANCHEL, a fea-port on the weft coaft of New Mexico, about 20 leagues to the N. E. of the rocks of Ponteque, over which, in clear weather, may be feen a very high hill, with a break on the top, called the hill of Xalifco, and may be feen 8 or 9 leagues from the port.

MATANE, a river of Canada, in N. America, the mouth of which is capable of admitting veffels of 200 tons burden. All this coaft, efpecially near this river, for 20 leagues, abounds in cod, which might employ 500 fhallops or fifthing finacks at a time. The fifth is very fine, and fit for exportation to the Straits, Spain, and the Levant. Great numbers of whales have been allo feen floating upon the water, which may be flouck with a harpoon, and prove a very valuable fifthery.

MATANZAS, or Matance, a large bay on the north fide of the ifland of Cuba, 14 leagues fouth-eaft of the Havannah, but fome accounts fay 20 leagues. From Cape Quibanico to this bay the coaft is WiN. W.

MATAVIA Bay, or Port Royal Bay, is fituated within Point Venus near the N. part of the island of Otaheite, but open to the N. W. and in the South Pacific Ocean. The east fide of the bay has good anchorage in 14 and 16 fathoms. S. lat. 17, 29. W. long. 149. 30. and the variation of the compass 3. 44. east.

MATCHADOCK Bay, in the cafternmost part of Lake Huron.

MATHANON Port, in the fouth-east part of the island of Cuba, is one of those ports on that coast which afford good anchorage for ships, but without any use for want of them. It is between Cape Cruz and Cape Maizi, at the east end of the island.

MATHEO River, in E. Florida, or St. John's; which fee.

MATHEWS

MATHEWS, Fort, ftands on the eastern fide of Oconce river, in the S. weftern part of Franklin county, Georgia. MATHEWS, a county of Virginia, bounded W. by Gloucester, from which it was taken fince 1790; lying on the W. fhore of the Bay of Chefapeak. It is about 18 miles in length, and fix in breadth.

MATICALOC River, on the W. coaft of New Mexico, is 7 leagues from Catalta Strand, or the port of Sanfonate. It is much exposed to northerly winds, and is known by fome finall but high hills that are opposite to it. There is another large river to the weftward of it, about 4 leagues, which has 2 fa-thoms upon the bar; and from thence to the bar of Eftapa it is 15 leagues. MATILDA, a village of Virginia, fi-

tuated on the fouth-weft bank of Patow-mac river, above Washington city, and near the Great Falls.

MATINICUS Mands, on the coaft of Maine. When you pais to the weft of thefe islands, the main passage from the fea to Penobscot Bay lies about N. by W. Martinicus lies N. lat. 43. 56. W. long. 68. 20.

MATTA DE BRAZIL, a town in the captainship of Pernambuco, in Brazil; about 9 leagues from Olinda. It is very populous; and quantities of Brazil are tent from this country to Europe.

MATTAPONY, a navigable river of Virginia, which rifes in Spottfylvania county, and running a S. E. courle, joins Pamunky river, below the town of De la War, and together form York river. This river will admit loaded floats to Downer's Bridge, 70 miles above its mouth.

MATTES, on the east coast of South-America, in the fouth Atlantic Ocean, is in lat. 45. 5. fouth, and long. 64. 25. weft.

MATTHEO Island, St. or St. Matthew's Island, in the S. Atlantic Ocean. S. lat. 1. 24.

MATTHEW's Bay, St. in the Gulf of Mexico, on the W. thore of Campeachy Gulf, is more than 100 leagues to the N. of Tumbez.

MATTHEWS, St. or Mattheo Bay, on the coaft of Peru, on the N. Pacific Ocean, is 6 leagues to the N. E. by E. from Point Galera, and 5 or 6 leagues tween which there is anchorage all the the flore, over coral rocks. MAURICE

\$57 \$6 TAU

way, if thips keep at least in 6 fathoms water. It is all high land with hollow red crags, and feveral points run out, forming good retreats for fhips driven in by hard fqualls and flaws from the hills, and by the feas running high, which often happen.

MAUGERVILLE, a township in Sunbury county, province of New-Brun(wick, fituated on St. John's river, oppofite St. Ann's, and 30 miles above Bellifle.

MAURA. See Society Mands.

MAUREPAS, an ifland on the northeaft coaft of Lake Superior, and N. E. of Ponchartrain ifland.

MAUREPAS, a lake in W. Florida, which communicates weftward with Miffifippi river, through the Gut of Ib-berville, and eaftward with Lake Ponchartrain. It is 10 miles long, 7 broad, and has 10 or 12 feet water in it. The country round it is low, and covered with cyprefs, live-oak, myrtle, &c. Two creeks fall into this lake, one from the north fide, called Nattabanie, the other from the peninfula of Orleans. From the Ibberville at its junction with Maurepas to the river Amit is 39 miles, and from thence, following the Ibber-ville, to the Miffifippi at the W. fide of the peninfula of Orleans, 21 miles. From the Ibberville acrofs the lake, it is 7 miles to the passage leading to Ponchartrain. The length of this paffage is 7 miles, and only 300 yards in width, which is divided into two branches by an island that extends from Maurepas to about the diftance of a mile from Ponchartrain. The fouth channel is the deepeft and fhorteft. The paffage thence through Lake Ponchartrain, to the Gulf of Mexico, is above fifty miles.

MAUREPAS Ifland, on the coaft of Cape Breton, the same as the Ifle Madame; which fee.

MAURICE Bay, on the W. fide of Cape Farewell Ifland, or S. extremity of E. Greenland, and the principal harbour of that fea.

MAURICE, Port, on the E. coaft of Terra del Fuego Ifland, is on the W. fhore of Le Maire Straits, between that ifland and Staten Land on the E. and N. of the bay of Good Success. It is a fmall cove, having anchorage before it in 12 fathoms, about half a mile from

in Cumb MAU corruptly county, wardly a Delawar of 100 ti confider MAX port of New-M Ocean. MAY of land the N. 1 ware B long. 74 water of before n MAY MAY Newfou ninfula Bays. MAY iflands with M at the 1 MAY mery co abin on nawaga 1796, 1 lified el MAT tucky, ing riv ton, on 1 5 nort MAT the eaf Quito i the gos Bracan fources verfing fluence zons. fions o line of thole c Portug de Bo nor, h tiago (miffior and di the riv

MAUI

above (BAR) north-N.E.

, op-

lorida, with of Ibe Ponbroad, The overed &c. e from ie, the rleans. n with miles, Ibberfide of miles. ke, it is o Ponpaffage width, ches by aurepas le from nnel is paffage rain, to ve fifty

coaft of fle Mafide of stremity

pal har-

coaft of the W. een that E. and . It is e before ile from A AURICE

MAY

MAURICE River, the name of a place in Cumberland county, New-Jerfey. MAURICE River, in fome maps called corruptly Morris, rifes in Gloucefter county, New-Jerley, and runs fouth-wardly about 40 miles, and empties into Delaware Bay; is navigable for veffels of 100 tons 20 miles, and for fmall craft confiderably further.

MAXANTALLA Ifland, is near the port of Matanchel on the W. coaft of New-Mexico, and on the north Pacific Ocean. 5513 JUES/88253

MAY, Cape, the most foutherly point of land of the State of New-Jerley, and the N. point of the entrance into Delaware Bay and river, in lat. 39. and long. 74. 56. W. The time of high water on spring-tide days, is a quarter before nine o'clock.

MAY COUNTY, Cape. See Cape. MAY POINT, on the fouth fide of Newfoundland Ifland, a point of the peninfula between Fortune and Placentia Bays.

MATAGUANA, one of the Bahama iflands in the West-Indies, and the fame with Maranella, and in lat. 22. 51. N. at the N. point, and long. 72. 57. W. MAYFIELD, a township in Montgo-mery co. New-York, adjoining Broadabin on the weftward, taken from Caughnawaga, and incorporated in 1793. In 1796, 126 of its inhabitants were quanon the 1756 lified electors.

MAY's Lick, in Mafon's county, Kentucky, a falt fpring on a branch of Licking river, 9 miles S.S.W. of Washington, on the fouth bank of the Ohio, and as northerly of the Blue Licks.

MAYNAS, a government, formerly the eaftern limit of the jurildiction of Quito in Peru, and joining on the east to the governments of Quixos and Jaen de Bracamoros. In its territory are the fources of those rivers, which after traverfing a valt extent, form, by their confluence, the famous river of the Amazons. It is feparated from the poffeffions of the Portuguefe, by the famous ine of demarcation, or the boundary of thole countries belonging to Spain and Portugal. Its capital is San Francifco de Borja, the refidence of the governor, but the Superior refides at Santiago de la Laguna. There are feveral miffions in the government of Maynas, and diocefe of Quito, particularly 12 on the river Napo, and 24 on the Maranon | ated on large river, well flored with

MEC

or Amazon; many of them are both

large and populous. MAYO River, on the east flore of the Gulf of California, and welt coaft of New Bifcay, in the province of that name, forms a fpacious bay at its mouth, in lat. 27. 40. N. and long. 114. W. MAYZI, the eaftern cape of the ifland

of Cuba, and the western point of the windward passage. N. lat. 20, 19, 30. W. long. from Paris 76, 40, 30. See

Maify. MAZALTAN, a province of Mexico, or New Spain. It is well watered by the Alvarado, which discharges itself by 3 navigable mouths, at 30 miles diftance from Vera Cruz.

MEADOWS, a fmall river which falls into Cafco Bay, in the Diftrict of Maine.

MEADS, a place fituated on a fork of French Creek; a branch of the Alleghany, in Pennfylvania. N. lat. 41. 36. and about 23 miles N.W. of Fort Franklin, at the mouth of the creek.

MECATINA, Great, Point of, on the fouth coaft of Labrador, and the north thore of the Gulf of St. Lawrence, in N. America. N. lat. 50. 42. W. long. 59.13

MECATINA Ifland, Little, on the fame coaft and fhore, lies fouth weft of Great Mecatina. N. lat. 50. 36. MECHOACAN, a province in the au-

dience of Mexico, in North-America, bounded north by part of Panuco and the provinces of Zacatecas and Guadalajara, east by another part of Panuco and Mexico Proper, fouth by the latter and the South Sea, which together with Xalifco, bound it allo on the weft and north-weft. It extends 70 leagues along the coaft, and thill farther inland. The cilimate is good and the foil The climate is good, and the foil re-markably fruitful. There are here mines of filver, and a few of gold and copper. Among its numerous productions are cocoa, mechoacan root, feveral odorife. rous gums and balfams, farfaparilla, ambergris, vanilla, caffia, &c. Mechoacan was formerly a kingdom, but the Spaniards have reduced it to a bifhoprick, in which are about 200 towns of civilized natives. The greatest part of the trade of this province is carried on by land, there being hardly any feaports deferying that name.

MECHOACAN, an Epifcopal city and capital of the province of its name, fitu-U 4. fifh.

fifh, near the welt fide of a lake, about | lina, about the year \$750, and whofe an-130 miles welt of Mexico. It is a large place, having a fine cathedral and hand-fome houses belonging to rich Spaniards, who own the filver mines at Guanaxoato or Guaxafiata.

MECKLENBURG, a county of Vir-ginia, bounded fouth by the State of N. Carolina. It contains 14,733 inhabi-tants, of whom 6762 are flaves.

MECKLENBURG, a county of North-Carolina, in Salifbury diffrict, bounded fouth by the State of S. Carolina. It contains 11,395 inhabitants, of whom 1603 are flaves. Chief town, Charlotte. MECOWBANISH, a lake in N. Ame-

rica, in 49. N. lat. MEDFIELD, a township in Norfolk county, Massachuletts, 20 miles southwelterly of Bolton. It was incorporated in 1650, and contains 731 inhabitants.

MEDFORD, a pleafant, thriving, compact town in Middlefex county, Maffachufetts, 4 miles north of Bolton, fituated on Mystick river, 3 miles from its mouth. Here are feveral distilleries and brick-works which give employment to a confiderable number of people. The river is navigable for small veffels to this lace. The township was incorporated in r610, and contains r029 inhabitants, who are noted for their industry.

MEDOCTU, a fettlement in New-Brunfwick, fituated on the weft fide of St. John's river, 35 miles above St. Ann's.

MEDOROSTA, a lake in the north part of the Diftrict of Maine, whole northern point is within 8 miles of the Canada line, in lat. 47. 56. and long. 68. 22. W. It gives rife to Spey river, which runs S.S.E. into St. John's river.

MEDUNCOOK, a plantation in Lin-coln county, Diftrict of Maine, 230 miles from Bofton, having 322 inhabitants.

MEDWAY, a township in Norfolk county, Maffachusetts, bounded cast and fouth by Charles river, which feparates it from Medfield, and of which it was a part until 1713. It has two pa-rifhes of Congregationalifts, and contains 2035 inhabitants. It is 25 miles fouthweft of Bofton, on the middle poft-road from thence to Hartford.

MEDWAY, or Midway, a settlement i Liberty county, Georgia, formed by emigrants from Dorchefter in S. Caro-

ceftors migrated from Dorchefter and the vicinity of Boston about the year 1700. A handfome Congregational meeting-houfe, belonging to this fettlement, was burnt by the British during the war, and the fettlement was deftroyed. It has fince recovered, in a confiderable degree, its former importance. Medway is 30 miles fouth of Savannah, and 9 weft of Sunbury.

M'KESSENSBURG, a town of Pennfylvania, York county, on Tom's Creek, 40 miles W.S.W. of York.

MEHERRIN, a principal branch of Chowan river, in N. Carolina, which rifes in Charlotte county, Virginia, and running an eaft by fouth courfe, unites with the Nottaway about 7 miles fouth of the Virginia line. See Chowan River.

MELAQUE PORT, on the west coast of New-Mexico, is to the north-weft of Port Natividad, or Nativity, and near 3 leagues at fouth-east from a row of 4 or crocks, or naked iflands above water, in the direction of north-weft. This port is land-locked against all winds from the north-weft to the fouth-weft.

MELA, or Mala, on the coaft of Peru in S. America, lies between Canette and Chilca. It is three leagues from Afia Ifland, whofe latitude is about 13. 6. S.

MELAWASKA, a French fettlement of about 70 families, fecluded in a fingular manner from the reft of mankind, in the north-eaftern part of the Diftrict of Maine. These people are Roman Catholics, and are industrious, humane, and hospitable.

MELETECUNK River, in Monmouth county, New-Jerfey, falls eaftward into Beaver Dam, which is at the head of the bay which is north of Cranberry New Inlet.

MELFORD's Place, on Tallapoofee river, in the western part of Georgia, is feparated from fome Indians towns by that river, a confiderable dittance from its mouth.

MEMORONCOK, a ftream a little weft of Byram river. Douglass fays the partition line between New-York and Connecticut, as fettled Dec. 1, 1664, ran from the mouth of this river N. N. W. and was the ancient limits of New-York, until Nov. 23, 1683, when the line was run nearly the fame as it is now fettled.

MEMORY ROCKS, amongft the Bahama hama If long. 79 MEM the prov

length f 3 wide f line of 1 fouth pa Memphi cation, St. Law confidera and Clye The foil country &c. Мем commen ry betwe wick an to the takes a ! MEN. leagues on the c the fout rence, h tofore ci fite to it MEN county, erly of 1 riftown. MEN coaft of N. lat. MEN county, weft of Pomfret thip call was inco 2 congr Friends bounded Rhode-] and Mil which | 2 clothi are 3 hi and Mi be feen, land Sta MEN S. Ame name, : Cordille tiago, i well fu

e an-

and

year

ional

ttle-

ning

troy-

onfi-

ance.

mah.

enn-

reek,

ch of

vhich

, and

nites

fouth

iver.

coaft

eft of

ear 3 4 or

er, in

port

m the

Peru

te and

Afia

6. S.

ent of

gular

d, iņ

ict of

n Ca-

mane,

nouth

d into

ad of

berry

poofee

gia, is

ns by

from

little

s fays

York

1664,

N. N.

New-

en the

snow

e Ba-

hama

hama Iflands, are in lat. 27. 20. N. and long. 79. 40. W. MEMPHREMAGOG, a lake chiefly in the province of Canada, 40 miles in length from north to fouth, and 2 or a wide from east to west. The north line of Vermont state passes over the fouth part of the lake in 45. N. lat. Memphremagog, which has communication, by the river, St. Francis, with St. Lawrence river, is the refervoir of 3 confiderable ftreams, viz. Black, Barton, and Clyde rivers, which rife in Vermont. The foil on its banks is rich, and the country round it is level. See Vermont, &c. WILL COMPANY GENEX Y

MEMRAMCOOK *River* has been recommended as the most proper boundary between the province of New-Brunfwick and Nova-Scotia. It lies a little to the eastward of Petitcodiak, and takes a north-casterly direction.

MENADOU Bay, or Panadou, is 2 leagues from Port Balene, or Port Nove, on the coaft of Cape Breton Ifland, at the fouth part of the gulf of St. Lawrence, having the ifland of Scatari, heretofore called Little Cape Breton, oppofite to it.

MENDHAM, a township in Morris county, New Jersey, 3 miles north-westerly of Veal-town, and 6 west of Morristown.

MENDOCIN, a cape on the north-weft coaft of America, and N. Pacific ocean. N. lat. 42. 20. W. long. 130. 5.

MENDON, a post-town in Worcester county, Maffachufetts, 37 miles fouthwelt of Bolton, and 31 north-east of Pomfret in Connecticut. This townthip called Quanfbipauge by the Indians, was incorporated in 1667, and contains 2 congregational parifhes, a fociety of Friends, and 1555 inhabitants. It is bounded on the fouth by the flate of Rhode-Ifland. It is watered by Charles and Mill rivers, and other finall ftreams, which ferve 5 grift-mills, 2 faw-mills, 2 clothier's works, and a forge. There are 3 hills here, viz Caleb's, Wigwam, and Mifkee, from either of which may be feen, in a clearday, the 4 New-England States.

MENDOZA, a jurifdiction in Chili, in S. America. It has a town of the fame name, and lies on the eaft-fide of the Cordillera, about 50 leagues from Santiago, in a plain adorned with gardens, well supplied with water by means of

canals. The town contains about 100 families, half Spaniards and the other half cafts, together with a college founded by the Jefuits, a parochial church, and 3 convents. In the jurifdiction are alfo the towns of St. Juan de la Frontera, fituated on the eaft of the Cordillera, and about 30 leagues north of Mendoza; and St. Louis de Loyola, about 50 eaft of Mendoza; the latter is very finall, but has a parifh church, a Dominican convent, and a college founded by the Jefuits.

MENDOZA, a river which rifes in the Cordillera of the Andes in S. America. Over this river is a natural bridge of rocks from the vaults of which hang feveral pieces of ftone refembling falt, which congeal like ificles, as the water drops from the rock. This bridge is broad enough for 3 or 4 carts to pais a-breaft. Near this is another bridge, called the bridge of Incas, betwixt two rocks; and " to very high from the river, that the fream, which runs with great rapidity, cannot be heard."

-MENICHLICK Lake, in the northweft part of N. America, lies in lat. 61. N. long. 105. W. N. of this is Lake Dobount.

MENIOLAGOMEKAH, a Moravian fettlement E. of the Great Swamp, at the head of Lehigh river in Pennfylvania, about 33 miles N. W. by N. of Bethlehem.

MENOLOPEN, a wealthy and pleafant farming fettlement, in Monmouth county, New-Jerfey; making a part of a nich glade of land, extending from the fea, weftward to Delaware river. It is 18 miles fouth-east of Princeton.

MERASHEEN Ifland, in Placentia bay, Newfoundland Ifland.

MERCER, a county of Kentucky, adjoining Woodford, Shelby, and Madifon counties. Harodfburgh is the chief town.

MERCERSBOROUGH, a village of Penniylvania, S. E. of North Mountain, and about 13 miles S. W. of Chamberfburgh.

MERCER'S Greek, in the N. E. part of the ifland of Antigua, in the W. Indies, is a pretty deep inlet of the coaft, the entrance to which is between the iflands of Codrington, Crumps, or Pelican. Lavicount's Hand is a fmall ifland alfo within it towards the fouth fhore; and in the fouth-weft part of

it

314

it is Farley's Bay, at the mouth of a 118

MERCHANT's Careening Place, within the harbour of Port Royal in Jamaica, on the N. fide of the long peninfula. Along this narrow flip of beach is the andy way to pais by land to Port Royal, for 9 or 10 miles, the careening place being almost at midway, but fornewhat nearer to the east end of the peninfula. MERCY, Cape of God's, the most foutherly point of Cumberland's Island, on the N. fide of Cumberland's Straits,

in lat. about 66. N. and has Cape Walfingham on its N. E. and Exeter Sound on its north.

MEREDITH, Cape, among the Falkland Iflands in the S. Atlantic Ocean, is between Port Stephen's and Cape Orford.

MEREDITH, a township in Strafford county, New Hampfhire, fituated on the S. W. fide of Lake Winnipifeogee, 15 miles N. of Gilmantown, 9 S. E. of Plymouth, and 70 N.W. of Portimouth. It was incorporated in 1768. In 1775, it contained 259, and in 1790, 881 inhabitants. It was first called New-Salem.

MERIDA, the capital of Yucatan, in the audience of Mexico, in N. America. It lies near the N. fide of the province, between the gulfs of Mexico and Hondwas; 45 miles S. of the ocean, and 135 N. E. of the city of Campeachy, N. lat. 21. 38. W. long. 90. 36.

MERIDA, a town of New Granada, in S. America, fituated near the limits which divide the province from Venezuela. The foil round this place abounds with fruit of all forts, and there are gold mines near it. It is about 54 miles from Lake Maracabo, 130 N. E. of Pampehina, and 260 N.E. of St. Fe. The inhabitants fend their fruit and merchandize to Truxillo. N. lat. 8. 30. W. long. 71.

MERIM, a large lake in Paraguay in S. America, very near the coaft of the S. Atlantic Ocean, where the land is very flat. Fort St. Miguel flands at the S. end, and Fort Mangaveira at its north-eaftern extremity. There is a very narrow lake, parallel to Lake Meriam between it and the ocean, and nearly as long. The forts command the extremities of the peninfula.

MERIMEG, or Marameg, a large ri-

ver of Louisiana, which empties into the Miffifippi, below the mouth of the Miffouri, and 50 miles above the fettlement of Genevieve. Fine meadows lie be-tween this and the Miffouri. MERION, Upper and Lower, two townships in Montgomery county, Pennfylvania.

MERO DISTRICT, in the State of Tenneffee, on the banks of Cumberland river. It comprehends the counties of Davidson, Sumner, and Tennefice. In 1790 it contained 7,042 inhabitants, including 1,151 flaves. By the State cenfus of 1795 there were 14,390, of which number 2,466 were flaves.

MERO POINT, in the S. Pacific Ocean and coaft of Peru, between Cape Blanco on the S. W. and Tunibez river to the N. E. on the S. E. fide of Guayaquil bay, in lat. 3. 40. S. The coaft at the point of Mero is low and flat, but the country within is high and mountainous.

MERRIMACK River, has its course foutherly through the State of New-Hampfhire, till it enters Maffachuletts ; it then turns eafterly, and paffes into the ocean at Newbury-Port. This river is formed by the confluence of Pemigewalfet and Winnipifeogee rivers, in about lat. 43. 26. This river is navigable for veficls of burden about 20 miles from its mouth, where it is obstructed by the first falls or rapids, called Mitchell's Eddy, between Bradford and Haverhill. Vaft quantities of thip-timber, and various kinds of lumber are brought down in rafts, fo constructed as to pass all the falls in the river except those of Amulkeag and Pawtucket. In the fpring and fummer, confiderable quantities of falmon, fhad and alewives are caught, which are either ufed as bait in the codfifhery, or pickled, and fhipped to the Weft. Indies. As many as 6 or 7 bridges have been thrown over this fine river at different diffances, from New-Concord, downwards; the most elegant and expensive are the one two miles above Newbury-Port, and the one at Haverhill. A canal is now in procefs to open a communication between the waters of the Mervimack at Chelmsford and the harbour of Bofton, through Myflick river. See Middlefex Canal. The bar acrol's the mouth of this river is a very great incumbrance to navigation, and is effectially terrible to ftrangers. There

are

o th

Mif-

ment

: be-

1201

two

2.63

Penn-

ite of

rland

ies of

. In

tants,

State

D, of

5 76 AN

acific

Cape

river

uaya-

coaft

flat,

noun-

courfe

New-

fetts ;

ito the

ver is

rewal-

about

ple for

from

ed by

theil's

erhill.

nd va-

down

all the

Amuf-

ng and of fal-

aught,

e cod-

to the

ridges

: river

-Con-

int and

above

Haver-

o open

ters of

ind the

lyftick

he bar

a very

and is

There

are

are 16 feet of water upon it at common tides. There are two light houfes of wood removeable at pleafure, according to the fhifting of the bar. The lights now bear E. IN. and W. I S. Bringing both the light-houfes to bear into one, until you are a breaft of the lower one, will bring you in over the bar in the deepeft water; where is a bold fhore and good anchoring ground. The N. point of Plumb-Ifland which forms the S. fide of the entrance into the river, lies in lat. 42. 47. 40. MERRIMACE, a township in Hillfborough county, New-Hampfhire, fituated on the fouth fide of Souhegan river, which runs eastward into the Merrimack. It is 55 miles wefterly of Portfmouth, was incorporated in 1746, and contains 819 inhabitants.

MERRIMICHI River falls into the head of a bay of that same on the N. E. coaft of the province of New Brunfwick. A little above its confluence with the bay, it forms into two branches, and runs through a fertile tract of choice intervale land; and the land is, in general, well cloathed with timber of all kinds. From this river there is a communication with St. John's, partly by land, but principally by water carriage in cances. The falmon fifthery is carried on with fuccefs, and the cod fifthery is improving near the entrance of the bay.

MERRYCONEAG. See Harpfwell. MERRY MEETING Bay, in Strafford county, New-Hampfhire, is the foutheasternmost arm of Lake Winnipiscogee. Mount Major ftands on its welt fide. MERRY-MEETING Bay, in the Diftrict of Maine, is formed by the junction of Androfcoggin and Kennebeck rivers, oppolite to the town of Woolwich, 20 miles from the fea. Formerly, from this bay to the fea, the confluent ftream was called Sagadahock. The lands here are good. Steven's river heads within a mile of the bay, and a canal has lately been opened which unites thele waters. A company has been incorporated to build a bridge over Androfcoggin river, at its entrance into the bay, to connect the towns of Brunfwick and Topfham; the former on its fouthern fide, the latter on its northern fide.

MERTEQUE, a town in the province of Honduras in New-Spain, which produces the cochineal. MESA, Lq, the fouthernmost of 4

ifles in the Pacific Ocean, near to each other, and E. of the Sandwich Ifles. N. lat. 19. W. long. 137, 30.

MESSASAGUES, Indians inhabiting between Lakes Superior and Huron. They have about 1,500 warriors.

MESSERSBURG, a town in Franklin county, Pennfylvania, 16 miles S. W. of Chamberfburgh, and 168. W. by S. of Philadelphia.

MESSILLONES, or Muscle Bay, on the coaft of Chili or Peru, in S. America, is 18 leagues N. by E. of Morrenas bay, and 5. S. by W. of Atacama. It is properly within the bay of Atacama, and is to deep on the S. fide that there is no foundings; but at the entrance or anchoring-place it is moderate, and fhips may ride in 15 fathoms, clean ground, and fecured from moft winds.

MESTRE Bay, Little, on the N. E. part of Newfoundland Island, fouthward of St. Julian, and N. by W. of the islands Gros and Belle.

MESUCKAMA Lake, in the N. part of N. America. N. lat. 50. 10. W. long. 80.

METCHIGAMIAS, a long narrow lake, or rather dilation of the northern branch of the river St. Francis, in Louisiana, which falls into the Missing from the N. W. about 4 miles above Kappas Old Fort.

METRUEN, the north-westernmost township in Eflex county, Massachusetts, fituated on the E. bank of Merrimack river, between Dracut and Haverhill. It contains 2 parishes and 1,297 inhabitants. It was incorporated in 1725. Hufbandry and the cutting and felling lumber divide the attention of the inhabitants.

MEW Iflands, on the coaft of the Spanish Main, in the Weft-Indies, between Cape Cameron, and Cape Gracias a Dios, lie across the entrance into the bay of Cotroe, or Crotoe. They are furrounded with rocks, and are very dangerous, especially in case of hard guilts from the N. and N. E.

MEXICANO River, or Adayes, in Louisiana, has a S. E. course and empties into the gulf of Mexico, at Cabo du Nord; W. by S. of Ascension bay, and E. by N. of the mouth of Trinity river. On its banks are rich filver mines: Fort Adayes stands on its north-eastern fide in about lat. 30. 31. north. MEXICO, a township in Herkemer

county

county, New-York, incorporated in 1796, lying on Canada and Wood Creeks, and Oneida Lake.

MEXICO, or New-Spain, bounded north by unknown regions, eaft by Louifiana and the gulf of Mexico, fouth by the Ifthmus of Darien, which feparates it from Terra Firma in South-America, weft by the Pacific Ocean. Its length is about 2,100 miles, its breadth 1600; fituated between lat. 9. and 40. north, and between long. 83. 8. and 125. 8. weft. This waft country is divided into Old-Mexico, which contains the audiences of Galicia, Mexico, and Gautimala, which are fubdivided into 22 provinces; New Mexico, divided into two audiences, Apacheira and Sonora; and California, on the weft, a peninfula. The land is in great part abrupt and mountainous, covered with thick woods, and watered with large rivers. Some of these run into the Gulf of Mexico, and others into the Pacific Ocean. Among the first are Alvarado, Coatzacualco, and Tabafco. Among the latter is the river Guadalaxara or great river. There are feveral lakes which do not lefs embellish the country than give convenience to the commerce of the people. The lakes of Nicaragua, Chappalan, and Pazaquaro, are among the largest. The lakes Tetzuco and Chalco occupy a great part of the vale of Mexico, which is the fineft tract of country in New-Spain. The waters of Chalco are fweet, those of Tetzuco are brackish. A canal unites them. The lower lake (Tetzuco) was formerly as much as 20 miles long and 17 broad, and, lying at the bottom of the vale, is the refervoir of all the waters from the furrounding mountains. The city of Mexico ftands on an ifland in this lake.

In this country are interfperfed many fountains of different qualities. There are an infinity of nitrous, fulphurcous, vitriolic, and alluminous mineral waters; fome of which fpring out to hot, that in a fhort time any kind of fruit or animal food is boiled in them. There are alfo petrifying waters, with which they make little white, fmooth ftones, not difpleafing to the taffe; fcrapings from which taken in hroth, or in gruel, made of Indian corn, are molt powerful diaphoretics, and are ufed with remarkable fuccefs in various kinds of fevers.

The climate of this extensive country

is various. The maritime parts are hot and for the most part most and unhealthy. Lands, which are very high, or very near to high mountains, which are perpetually covered with fnow, are cold.

The mountains of Mexico abound in ores of every kind of metal, and a great variety of follils. There are entire mountains of loadftone, and among others, one very confiderable between Tcoiltyfan and Chilapan, in the country of the Gohuixcas.

However plentiful and rich the mineral kingdom of Mexico may be, the vegetable kingdom is still more various and abundant. Dr. Hernandez defcribes in his natural history, about 1,200 medicinal plants, natives of that country. The fruits of Mexico, are, pine-apples, plums, dates, water-melons, apples, peaches, quinces, apricots, pears, pomegranates, figs, black-cherries, walnuts, almonds, olives, chefnuts, and grapes. The cocoa-nut, vanilla, chia, great-pepper, tomati, the pepper of Tabafco, and cotton, are very common with the Mexicans. Wheat, barley, peas, beans and rice have been fuccefstully cultivated in this country. With respect to plants which yield profitable refins, gums, oils or juices, the country of Mexico is fingularly fertile. Of quadrupeds, there have been transported into this country horfes, affes, bulls, fheep, goats, hogs, dogs and cats, which have all multiplied. Of the ancient quadrupeds, by which is meant those that from time immemorial have been in that country, fome are common to both the continents of Europe and America, fome peculiar to the new world, others natives only of the kingdom of Mexico. The ancient quadrupeds common to Mexico and the old continents, are, lions, tigers, wild-cats, bears, woives, foxes, the common ftags and white ftags, bucks, wild-goats, badgers, pole-cats, weazles, martins, fquirrels, rabbits, hares, otters and rats. Their prodigious number of birds, their variety, and many valuable qualities, have occafioned fome authors to obferve, that, as Africa is the country of bealls, fo Mexico is the country of birds. It is faid there are 200 species peculiar to that kingdom.

The civil government of Mexico is administered by tribunals called audiences. In these courts, the viceroy

of the king ployment er his Ca pofal, and ment entr world. 7 three year: numerous monks an fifth of 1 here and i rica. Th dued by C MEXIC province, of which foundation 1325. It vale of Me in Lake I and 103. This vale verdant m tained no besides vil ing the ar there are w rians moft was nearly and contai containing tants. B made by t appears th bitants ex curiofity i floating g about the the Colhu: confined to having no taught by gardens, Their con take will plants, ar light, and firmly uni

platform,

ing the ea

foundation

which floa

foread the

draw up

Their reg

their leng

generally and their

the water

of the king of Spain prefides. His employment is the greateft truft and power his Catholic Majefty has at his difpofal, and is perhaps the ritcheft government entrufted to any fubject in the world. The viceroy continues in office three years. The clergy are extremely numerous in Mexico. The priefts, monks and nuns of all orders make a fifth of the white inhabitants, both here and in other parts of Spanish America. The empire of Mexico was fubdued by Cortez in \$521.

re hot

theal.

h, or

:h are

bound

und a

re en-

mong

tween

untry

min-

i, the

trious

ribes

> me-

intry.

oples,

oples,

ome-

nuts,

apes.

-pep-

th the

beans

Itiva-

et to

efins,

Mex-

peds,

roats.

re all

adru-

en in

both

erica,

others

xico.

on to

pives,

ftags,

-cats,

bbits,

digi-

, and

fioned

Africa

is the

re are

audi-

iceroy

of

om. ico is

are,

that

this

are

MEXICO, the capital of the above province, is the oldeft city in America, of which we have any account; its foundation being dated as far back as 1325. It is fituated in the charming vale of Mexico, on feveral imall iflands, in Lake Tetzcuco, in N. lat. 19. 26. and 103. 35. W. long. from Ferro. This vale is furrounded with lofty and verdant mountains, and formerly contained no lefs than 40 eminent cities, befides villages and hamlets. Concerning the ancient population of this city there are various opinions. The hiflorians most to be relied on fay, that it was nearly nine miles in circumference ; and contained upwards of 60,000 houfes, containing each from 4 to 10 inhabitants. By a late accurate enumeration, made by the magistrates and priefts, it appears that the prefent number of inhabitants exceeds 100,000. The greateft curiofity in the city of Mexico, is their floating gardens. When the Mexicans, about the year 1325, were fubdued by the Colhuan and Tepanecan nations, and confined to the finall islands in the lake, having no land to cultivate, they were taught by necellity to form moveable gardens, which floated on the lake. Their construction is very limple. They take willows and the roots of marth plants, and other materials which are light, and twift them together, and fo firmly unite them as to form a fort of platform, which is capable of fupporting the earth of the garden. Upon this foundation they lay the light bushes which float on the lake, and over them foread the mud and dirt which they draw up from the bottom of the lake. Their regular figure is quadrangular; their length and breadth various, but generally about 8 rods long and 3 wide; and their elevation from the furface of

were the first fields that the Mexican owned, after the foundation of Mexico; there they first cultivated the maize great-pepper, and other plants necef-lary for their fupport. From the induftry of the people these fields foon became numerous. At prefent they cultivate flowers and every fort of garden herbs upon them. Every day of the year at funrile, innumerable veffels or boats, loaded with various kinds of lowers and herbs, which are cultivated in these gardens, are feen arriving by the canal, at the great market-place of Mexico. All plants thrive in them furprifingly; the mud of the lake makes a very rich foil, which requires no water from the clouds. . In the largeft gardens there is commonly a little tree and a little hut to fhelter the cultivator and defend him from the rain or the fun. When the owner of a garden of the Chinampa, as he is called, wifnes to change his fituation, to get out of a bad neighbourhood, or to come nearer to his family, he gets into his little boat, and by his own strength alone, if the garden is fmall, or with the affiftance of others, if it is large, conducts it wherever he pleafes, with the little tree and hut upon it. That part of the island where these floating gardens are, is a place of delightful recreation, where the fenfes receive the highest poffible gratification. The buildings, which are of ftone, are convenient, and the public edifices, efpecially the churches, are magnificent; and the city has the appearance of immenfe wealth. The trade of Mexico confilts of 3 great branches, which extend over the whole world. It carries on a traffic with Europe, by La Vera Cruz, fituated on the Gulf of Mexico, or North Sea; with the East-Indies, by Acapulco, on the South Sea, 210 miles S. W. of Mexico; and with South-America, by the fame port. These two fea-ports, Vera Cruz and Acapulco, are admirably well fituated for the commercial purposes to which they are applied.

foundation they lay the light buffes which float on the lake, and over them foread the mud and dirt which they draw up from the bottom of the lake. Their regular figure is quadrangular; their length and breadth various, but generally about 8 rods long and 3 wide; and their elevation from the furface of the water is lefs than a foot. Thefe MIA

operly by the N. W. point of the Ithmus of Darien, supposing a line to be drawn from one to the other. The Gulf of Mexico is therefore to be confidered as the western part of the great gulf between the northern, and fouthern continents of America. This fpacious gulf contains a great many iflands of various extent and fize; and it receives feveral great rivers, particularly the Millippi, the N. river, and a multitude of others of comparatively lefs note. Its coafts are fo irregular and indented, that its leffer gulfs and bays are almost innumerable; the chief of these are the gulf of Honduras, and Guanajos, and the bays of Campeachy, Palaxay, and St. Louis. It is conjectured by fome to have been formerly land; and that the constant attrition of the waters in the Gulf Stream, has worn it to its prefent form. See Gulf Stream, and Gulf of Florida.

MIAMI River, Little, in the N. W. Territory, has a fouth-western course, and empties into the Ohio, on the eaft fide of the town of Columbia, 20 miles eaftward of the Great Miami, in a fraight line, but 27 taking in the meanders of the Ohio. It is too fmall for batteaux navigation. Its banks are good land, and fo high as to prevent in common the overflowing of the water. At the diftance of 30 miles from the Ohio, the Miamies approximate each other within eight miles and a half. On this river are feveral falt fprings.

MIAMI River, Great, or Great Mineami, called alio Affereniet, or Rocky river, in the N. W. Territory, has a S. by W. courfe, and empties into the O. his by a mouth 200 yards wide, 321 miles from Big Bones, 154 miles from the Rapids, and 604 from the mouth of the Ohio. It is one of the most beautiful fireams in the Territory, and is fo clear and transparent, at its highest state, that a pin may very plainly be feen at its bottom. It has a very flony channel, a fwift ftream, but no falls. At the Picque or Pickawee towns, above 75 miles from its mouth, it is not above 30 yards broad, yet loaded batteaux can afcend 50 miles higher. The portage from the navigable waters of its caftern branch to Sandusky river is 9 miles, and from those of its western branch to the Miami of the Lakes, only five miles. It alio interlocks with the Scioto. In the fhape of a horn.

的推定

MIC

MIAMI of the Lakes, a navigable ris ver of the N. W. Territory, which falls into Lake Eric, at the S. W. corner of the lake. A fouthern branch of this river communicates with the Great Miami, by a portage of 5 miles. This river is called by fome writers Mawmee, alfo Omee, and Manmick. See Terri. tory N. W. of the Obio.

MIAMI, a village on the Miami of the Lake near the Miami Fort. Large canoes can come from Quiatanon, a finall French fettlement on the W. fide of the Wabash, 197 miles below the Miami Carrying-place, which laft is 9 miles from this village.

MIAMIS, an Indian nation who inhabit on the Miami river and the fouthern fide of Lake Michigan. They can raile about 300 warriors. In confequence of lands ceded to the U. States by the treaty of Greenville, August 3d, 1795, government paid them a fum in hand, and engaged to pay them annually for ever, to the value of 1000 dollars

in goods. MIAMIS Bay, at the mouth of the Miami of the Lakes.

MIATA Island, one of the Society Iflands, in the S. Pacific ocean. S. lat. 17. 52. W. long. 148. 6.

MICHAEL, St. or St. Miguel, a town in the province of Quito in Peru, and faid to be the first town the Spaniards built in that country. It is of confiderable fize, standing in a fruitful valley, about 20 leagues from the fea. The inhabitants call it Chila. Another town, called St. Miguel, is the fecond city in Tucumania, 20 leagues from St. Jago del Eftero, on the road to Charcara or Potofi, at the foot of a range of rugged mountains in a well watered place, having the river Quebrador on the one fide, and feveral-finall freams on the other, 5 or 6 leagues from it. The country produces all kinds of grain, plenty of grapes, cotton and flax, and yields excellent pasturage.

MICHAEL, St. a town of N. America, in New-Spain, and in the province of Mechoacan. It is very populous, and 100 miles from Mexico. N. lat. 20. 35. W. long. 102. 55.

MICHAEL's Bay, St. on the E. fide of the ifland of Barbadoes, in the Weft-Indies ; a little N. of Foul's Bay . N. E. of which laft bay are Cobler's Rocks,

MICHAEL'S

MICH. part of P outlet of s fall into i Місн is alfo on tween N. N. Pacifi W. of Pa Guibalti at flood. is the bu in the mi MICH ma, on t MICH

tan diffri

county,

ton, and

Місн

MICH town on illand, 1 MICH ritory, i able lake United S 10. and 30. and 1 length is its bread circumte contains 10,368,0 thipping cates wi eaftern Michilli broad, : on an if In this particul ty, weij and fom which 1 N. W. p through

into two

called M

fourhwa

laft with

fula, ca

lion Poi

de Puar

commu

portage

cation,

bago L

dwough

MICHAEL'S Galf, St. in the S. E. part of Panama Bay, is formed by the outlet of St. Maria and other rivers that fall into it.

ble ri-

h falls

ner of

his ri-

t Mi-

his ri-

wmee.

Terri-

ami of

Large

on, a

V. fide

w the

At is 9

inha-

fouth-

ey can

confe-

States

uft 3d,

fum in

nnual-

dollars

of the

ty If-

S. lat.

a town

u, and

aniards

mider-

valley,

The in-

r town,

city in

t. Jago

'cara of

rugged

ice, ha-

me fide,

: other,

country

lenty of

elds ex-

Ameri-

rovince

pulous,

N. lat.

E. fide

: Weft-

IV N.

Rocks,

HAEL'S

MICHAEL, St. or St. Miguel River, is also on the S. coast of the isthmus be tween N. and S. America, and on the N. Pacific ocean, and 18 leagues to the W. of Port Martin Lopez, and 3 E. of Guibaltigue. "It has 3 fathoms water at flood. Within the river to the N. E. is the burning mountain of St. Miguel, in the midst of an open plain.

MICHAEL's Bay, St. in Ferra Firma, on the S. Sea.

MICHAEL's, St. a parish in Charlestan district. S. Carolina.

MICHAEL's, St. a town in Talbot county, Maryland, 8 miles W. of Eafton, and 21 S. E. of Annapolis.

MICHAEL, St. or Fond des Negres, a town on the S, peninfula of St. Domingo ifland, 10 leagues N. E. of St. Louis.

MICHIGAN Lake, in the N. W. Territory, is the largest and most confiderable lake, which is wholly within the United States, and lies between lat. 42. 10. and 45. 40. N. and between 84. 30. and 87. 30. W. long. Its computed length is 280 miles from north to fouth ; its breadth from 60 to 70 miles, and its circumference nearly 600 miles; and contains, according to Mr. Hutchins, 10,368,000 acres. It is navigable for fhipping of any burden ; and communicates with Lake Huron, at the northeaftern part, through the Straits of Michillimakkinak." The ftrait is 6 miles broad, and the fort of its name stands on an ifland at the mouth of the ftrait. In this lake are feveral kinds of fifh; particularly trout of an excellent quality, weighing from 20 to 60 pounds; and fome have been taken in the ftrait which weighed 90 pounds. On the N. W. parts of this lake, the waters pufh through a narrow ftrait, and branch out into two bays; that to the northward is called Noquet's Bay, the other to the fourhward, Puans, or Green Bay, which laft with the lake, forms a long peninfula, called Cape Townfend, or Vermillion Point. About 30 miles S. of Bay de Puans, is Lake Winnebago, which communicates with it : and a very thort portage interrupts the water communication, fouth-weltward from Winnebago Lake through Fox river, then through Oosconfin, into the river Mif-

filippi. Chicago river, alfo at the S. W. extremity of Lake Michigan, furnithes a communication interrupted by a full thorter paffage, with Illinois river. See all these places mentioned under their refpective names. Lake Michigan receives many finall rivers from the W. and E. fome 150 and even 250 yards broad at their mouths. See Grand, Mafricon, Marame, St. Joseph, &cc.

MICHILLIMAKKINAK Straits, connect Lakes Michigan and Huron, in a N. E. and S. W. courfe.

MICHILLIMARKINAK, an iflend, fort, and village on the S. W. fide of th ftraits of the fame name. The fmall ifle on which the village and the fort commanding the ftrait, ftand, is W. N. W. of White Wood Island, in Lake Huron. In addition to the lands round this post to which the Indian title had been extinguished by the French and Britifh governments, the Indians have ceded by the treaty of Greenville, a tract of land on the main, to the north of the island on which the post of Michillimakkinak ftands, to m iure 6 miles on lakes Huron and Michigan, and to extend 3 miles back from the water of the lake or ftrait, and also De Bois Blanc, or White Wood Ifland. This laft was the voluntary gift of the Chipewa nation. The ifland of Michillimakkinak is very barren, but, as it is the grand rendezvous of the Indian traders, a confiderable trade is carried on; and its very advantageous fituation. feems to enfure that it will be, at fome future period, a place of great commercial importance. It is within the line of the United States, and was lately delivered up by the British. It is about 200 miles N. N. W. from Detroit, and 974 N. W. of Philadelphia. N. lat. 45. 20. W. long. 84. 30.

MICHILLIMAKENAK, Little, a river in the N. W. Territory, which enters the fouth-eaftern fide of Illinois river, by a mouth 50 yards wide, and has between 30 and 40 finall iflands at its mouth; which at a diffance appear like a finall village. It runs a N. W. courfe, and is navigable about 90 miles. On its banks is plenty of good timber, viz. red and white cedar, pine, maple, walnut, &c. as alfo coal mines. Its mouth is 13 miles below the Old Piorias Fort and village, on the opposite fide of the river, at the S. W. end of Illi-

nçis

nois Lake, and 195 miles from the Mif- | tween lat. 44. 32. and 45. 34. N. and

ббррі. Міснірісотом, a river which empties into Lake Superior, on the north-east fide of the lake. It has its fource not far diftant from Moofe river, a water of James's Bay it forms at its mouth a bay of its own name; and on the W. part of the bay, is a large ifland fo called, clofe to the land, a fmall frait only separates it from Otter's Head on the north.

MICHIPICOOTON Houfe, in Upper Canada, is fituated on the E. fide of the mouth of the above river, in lat. 47. 56. N. and belongs to the Hudfon Bay Company.

MICHISCOUI is the Indian and prefent name of the most northerly river in Vermont. It rifes in Belvidere, and runs nearly north-east until it has croffed into Canada, where it runs fome diffance, it. turns W. then foutherly, re-enters the State of Vermont in Richford, and empties into Lake Champlain, at Michifcoui Bay at Highgate. It is navigable for the largest boats to the falls at Swantown, 7 miles from its mouth. Michifcoui, La Moelle, and Onion rivers, are nearly of the fame magnitude.

MICHISCOUI Tongue or Bay, a long point of land which extends foutherly into Lake Champlain from the northeast corner of the State of Vermont on the W. fide of the bay of this name, and forms the township of Allburgh.

MICKMACKS, an Indian nation which inhabit the country between the Shapo. dy Mountains, and the Gulf of St. Lawrence in Nova-Scotia, opposite to St. John's Ifland. This nation convey their fentiments by hieroglyphics marked on the rind of the birch and on paper, which the Roman miffionaries perfectly understand. Many of them relide at the heads of the rivers, in King's and Hants counties.

MICOYA Bay is fituated on the S. W. coaft of Mexico, or New-Spain, on the North Pacific Ocean. In fome charts it is laid down in lat. 10. 15. N. and having Cape Blanco and Chira Ifland for its fouth-east limit.

MIDDLE BANK, a fifting ground in the Atlantic Ocean, which lies from north-east to fouth-west, between St. Peter's Bank and that of Sable Ifland; and opposite to, and S. E. of Cape Breton Ifland, laid down in fome charts bebetween long 57. 37. and 59. 32.

MIDDLEBOROUGH, the Namaskett of the ancient Indians, a township in Plymouth county, Massachusetts, bounded weft by Freetown and Taunton, eaft by Carver and Warham, and is 40 miles S. by E. of Bofton; was incorporated in 1669, and contains 4, 526 inhabitants. This town was formerly thickly inhabited by Indian natives, governed by the noted fachem Tifpacan : there are now only 30 or 40 touls remaining, who, to fupply their immediate neceffities, make and fell brooms and bafkets. The town is remarkable for a large range of ponds. which produce feveral forts of fifh, and large quantities of iron ore. The bottom of Affowamfet Pond may be faid to be an entire mine of iron ore. Men go out with boats, and use instruments like oyfter dredges, to get up the ore from the bottom of the pond. It is now fo much exhaufted, that half a ton is thought a good day's work for one man; but for a number of years one man could take up four times the quantity. In an adjacent pond there is yet great plenty at 20 feet deep, as well as from thoaler water. Great quantities of nails are made here. In winter, the farmers and young men are employed in this manufacture. Here, and at Milton in Norfolk county, the first rolling and flitting mills were erected about 40 years ago, but were imperfect and unproductive, in comparison with those of the prefent time. The prints of naked hands and feet are to be feen on feveral rocks in this town," fuppofed to have been done by the Indians. These are probably fimilar to those observed in the States of Tenneffee and Virginia.

MIDDLEBOURG Key, a fmall islot feparated from St. Martin's in the Weft-Indies on the N.E.

MIDDLEBERG, a new town of New-York in Schoharie co. incorporated in 1797.

MIDDLEBURY, a post-town of Vermont, and capital of Addison county. It is 33 miles N. by W. of Rutland, 15 from Vergennes, and 37 S. E. of Burlington. Here is a brewery upon a pretty large fcale, The township lies on the E. fide of Otter Creek, and contains 393 inhabitants.

MIDDLE Gape is to the S. W. of Cape Anthony, in Staten Land, on the firait

Le Mair of that i America. MIDDI fhire cou N. W. (wefterly o in 1783, MIDD Jerfey, 8 the crofs Flemingt riton rive MIDDI on the W are betwe Luke. ocean, in from 6 to iflands, a to them t MIDDI foutherly the fouth. 10 league MIDDI setts, bou New-Han S. by Suf county. fquare of length bei 42 miles. contain 4 gious foci ifts, 6 of rians. I It is wate Merrimac and Myft The chief bride, and the only cord is the and is ne being 20 n are in the 70 tan-ya mills, 6 di pearl afh northern fi not mount ceeding 10 wered with their fum ferene, and extreme w mometer, a year ; b

Le Maire, and the most westerly point of that island; at the extremity of S. America.

and

afkett

p in

und-

eaft

niles

rated

ants.

nha

y the

now

o, to

nake

town

onds.

, and

bot-

uid to

n go

like

from

w fo

n is

I one

juan-

is yet

ell as

tities

, the

ed in

Mil-

alling

ut 40

1 un-

ofe of

naked

veral

have

e are

ed in

iflot

Weft-

New-

ed in

Ver-

unty.

10,15

Bur-

on a

p lies

con-

Cape

ttrait

σt

nia.

one

MIDDLEFIELD, a township in Hampfhire county, Maffachufetts, 30 miles N. W. of Springfield, and 125 miles wefterly of Bolton. It was incorporated in 1783, and contains 608 inhabitants.

MIDDLEHOOK, a village in New-Jerfey, 8 miles W. of Brunfwick, on the crofs post-road, from Brunswick to Flemington, and on the N. bank of Rariton river.

MIDDLE Islands or Ilbas de en Medio. on the W. coaft of New-Mexico, and are between the iflands of Chira and St. Luke. They are in the North Pacific ocean, in lat. 9. 30. N. There is only from 6 to 7 fathoms from Chira to thefe iflands, and all veffels fhould keep nearer to them than to the main.

MIDDLEBURG, or Ecoa, the most foutherly of all the Friendly Iflands, in the fouth Pacific Ocean; and is about to leagues in circuit.

MIDDLESEX, a county of Maffachufetts, bounded north by the State of New-Hampfhire, E. by Effex county, S. by Suffolk, and W. by Worcefter county. Its figure is nearly equal to a fquare of 40 miles on a fide ; its greateft length being 52, and its greateft breadth 42 miles. It has 42 townships, which contain 42,737 inhabitants. The religious focieties are 55 of Congregational-ifts, 6 of Baptifts, and fome Prefbyterians. It was made a county in 1643. It is watered by five principal rivers, Merrimack, Charles, Concord, Nafhua, and Myftick; befides finaller ftreams. The chief towns are Charlestown, Cambride, and Concord. Charleftown is the only fea-port in the county; Concord is the most respectable inland town, and is near the centre of the county, being 20 miles N. W. of Bofton. There are in the county 24 fulling-mills, about 70 tan-yards, 4 paper-mills, 2 fnuff-mills, 6 diftilleries, and about 20 pot and pearl ash houses. The fouthern and northern fides of the county are hilly, but not mountainous, few of the hills exceeding 100 feet in height, and are covered with wood, or cultivated quite to their fummits. The air is generally ferene, and the temperature mild. The extreme variation of Farenheit's thermometer, may be confidered as 100° in a year; but it is in very few inftances,

that in the course of a year it reaches either extreme: 92° may be confidered as the extreme fummer heat, and 5 or 6º below oo, as that of the winter cold. In the winter of 1796-'97, it funk to 11° below o. The foil is various, in fome parts of rich, black loam, and in others it is light and fandy. It pro-duces the timber, grain and fruit which are common throughout the State, either by natural growth or cultivation.

MIDDLESEX, a maritime county of Connecticut, bounded north by Hartford county, fouth by Long-Ifland Sound, east by New-London county, and weft by New-Haven. Its greatest length is about 30 miles, and its greateft breadth 19 miles. It is divided into 6 townthips, containing 18,855 inhabitants, of whom 221 are flaves. Connecticut river runs the whole length of the county, and on the ffreams which flow into it are a number of mills. Middleton is the chief town.

MIDDLSEX, a county of New-Jerfey, bounded north by Effex, N. W. and W. by Somerfet, S. W. by Burlington, S. E. by Monmouth, east by Rariton Bay and part of Staten Island. It contains 15,956 inhabitants, including 1,318 flaves. From the mouth of Rariton river up to Brunswick, the land on both fides is generally good, both for pasturage and tillage, producing confiderable quantities of every kind of grain and hay. Chief town New-Brunfwick.

MIDDLESEX, a county of Virginia, on the fouth fide of Rappahannock river, on Chefapeak Bay. It is about 35 miles in length, and 7 in breadth, containing 4,140 inhabitants, including 2,558 flaves. Urbanna is the chief town.

MIDDLESEX, a township in Chittendon county, Vermont, on the north-east fide of Onion river. It contains 60 inhabitants.

MIDDLESEX Canal (Maffachufetts) it is expected will be of great import-ance to the States of Maffachufetts and New-Hampfhire. It is now opening ata vaft expence by an incorporated comcommunication from the waters of Merrimack river at Chelmsford to the harbour of Bofton. The route of the canal will be foutherly through the east parts of Chelmsford, and Billerica, the weft part of Wilmington, and the middle of Woburn; where it comes to fome ponds, from

\$22

from which the waters run by Myflick river into Boston harbour. The diftance from the Merrimack to these ponds will be 17 miles. The canal will, without meeting, with any large hills or deep vallies, be straighter than the country road near it. The diftance from the Merrimack to Medford, as the canal will be made, is 27, and to Bofton, 31 miles. The canal is to be 24 feet wide at the bottom, and 32 at the top, and 6 feet deep. The boats are to be 12 feet wide and 70 feet long. The toll is to he 6 cents a mile for every ton weight which shall pais, befides pay for their boats and labour.

MIDDLE STATES, one of the Grand Divisions of the United States, (fo denominated in reference to the northern and fouthern States) comprehending the States of New-York, New-Jerley, Pennfylvania, Delaware, and the Territory N. W. of the Ohio.

MIDDLETON, an interior township in Effex county, Massachusetts, 28 miles northerly of Boston. It was incorporated in 1728, and contains 682 inhabitants.

MIDDLETON, a city and post-town of Connecticut, and the capital of Middlefex county, pleafantly fituated on the western bank of Connecticut river, 31 miles from its mouth at Saybrook Bar, according to the course of the river; 14 miles S. of Hartford, 26 N. by E. of New-Haven, 40 N. W. by W. of New-London, and 209 N. E. of Philadelphia. Its public buildings are, a Congregational church, an Epifcopalian church, a court-houfe and naval-office. It contains about 300 houfes, and carries on a confiderable trade. Here the river has to feet water at full tides. N. lat 41. 35. W. long. 77. 12. This place was called *Mattabefick*, by the Indians, and was fettled in 1650 or 1651. Two miles from the city is a lead mine which was wrought during the war, and was productive; but it is too expensive to be worked in time of peace.

MIDDLETOWN, a township in Strafford county, New-Hampshire; about 40 miles N. by N. W. of Portsmouth. It was incorporated in 1778, and contains 617 inhabitants.

MIDDLETOWN, a township in Rutland co. Vermont. It contains 699 inhabitants, and is 39 miles north of Bennington.

MIDDLETOWN, a village on Long-

Island, New-York State; 12 miles from Smithtown, and 13 from Bridgehampton.

MIDDLETOWN, a township in Ulfter county, New-York, crected from Rochefter, and Woodftock in 1789, and contains 1,019 inhabitants, including 6 flayes. In 1796 there were 135 of the inhabitants entitled to be electors.

MIDDLETOWN, a township in Newport county, Rhode-Island State, contains \$40 inhabitants, including 15 flaves. In this town which is on the island which gives name to the State, and about 2 miles from Newport is the large and curious cavity, in the rocks, called *Purgatory*.

MIDDLETOWN, a fmall post-town in Newcastle county, Delaware, lies on Apoquinimy Creek, 21 miles S. S. W. of Wilmington, and 49. S. W. of Philadelphia.

MIDDLETOWN, in Monmouth county, New-Jerfey, a townfhip which contains two places of Worfhip, one for Baptifts and one for the Dutch Reformed church, and 3,226 inhabitants, including 491 flaves. The centre of the townfhip is 50 miles E. by N. of Trenton, and 30 S. W. by S. of New-York city. The light-houfe built by the citizens of New-York on the point of Sandy Hook, is in this townfhip. The high lands of Navefink, are on the feacoaft, near Sandy Hook. They are 600 feet above the furface of the water, and are the lands first difcovered by mariners on this part of the coaft.

MIDDLETOWN Point, in the above township, lies on the S. W. fide of the bay within Sandy Hook, 9 miles E. by N. of Spotfwood, and 14 north-weft of Shrewfbury. A post-office is kept here. MIDDLETOWN, a flourishing town in Dauphin county, Pennfylvania, fituated on the N. W. fide of Swatara creek, which empties into the Sulquehannah, 2 miles below. It contains a German church and above 100 houfes, and carries on a brick trade with the farmers in the vicinity. It is effimated that above 200,000 bufhels of wheat are brought down these rivers annually to the landing place, 2 miles from the town. Contiguous to the town is an excellent merchant mill, implied with a conftant ftream, by a canal cut from the Swatara. It is 6 mills S. of Hummelfton, and 62 W. by N. of Philadelphia. N. lat. 40.

49. 12: alfo other State; th other in t MIDD ty, Mary N. W. o MIDDI ty, Mary the Ceda quaking and 81 N MIDW ty, Geor and to m inhabitan are the d Dorcheft land, whe MIDW county, 1 Rutland. MIFFI furround Cumberl phin, and tains 1, acres, ar The mo with iron which, fe It is wel other ftre quehanna MIFFI out in th of the Ju town, an MIFF fituated (of Schuy of Philad MILF Hampfhi MILF county, MILF of Delaw north fid miles w Bay, 19 Frederic delphia. all built The in Quakers MILF county, the N. J

40. 12: W. long. 76: 44: There are alfo other townfhips of this name in the State; the one in Delaware county; the other in that of Cumberland.

from amp-

Jlfter

Ro-

and

ing 6

of the

New-

con-

g 15

on the

State, is the

rocks,

t-town

ies on

S. W.

of Phi-

1 coun-

th con-

me for

eform -

its. in-

: of the

F Tren-

v-York

the cipoint of

. The

the fea-

hey are

e water.

by ma-

ne above

le of the

es E. by

i-weft of

ept here.

g town in

fituated

ra creek,

channah,

German

and car-

armers in

hat above

: brought

the land-

vn. Con-

llent mer-

conftant

he Swata-

ilfton, and

. N. lat.

40.

MIDDLETOWN, in Frederick county, Maryland, lies nearly 8 miles W. N. W. of Frederickflown.

MIDDLETOWN, in Dorchefter county, Maryland, is about 5 miles N. of the Cedar Landing Place, on Tranfquaking Creek ; 7 wefterly of Vienna, and 81 N. W. of Cambridge.

MIDWAY, a village in Liberty county, Georgia, 30 miles S. of Savannah, and 10 miles N. W. of Sunbury. Its inhabitants are Congregationalifts, and are the descendants of emigrants from Dorchefter near Bofton, in New-England, who migrated as early as 1700.

MIDWAY, a township in Rutland county, Vermont, east of and adjoining Rutland.

MIFFLIN, a county of Pennfylvania, furrounded by Lycoming, Franklin, Cumberland, Northumberland, Dauphin, and Huntingdon counties. It contains 1,851 fquare miles 1,184,960 acres, and is divided into 8 townships. The mountains in this county abound with iron ore, for the manufacturing of which, feveral forges have been erected. It is well watered by the Juniatta, and other ftreams which empty into the Sufquehannah. Chief town, Lewistown.

MIFFLIN, a fmall town lately laid out in the above county, on the eaft fide of the Juniatta; 12 miles eaft of Lewif town, and 138 from Philadelphia.

MIFFLIN, Fort, in Pennfylvania, is fituated on a fmall island, at the mouth of Schuylkill river, about 6 miles fouth of Philadelphia.

MILFIELD, in Grafton county, New-Hampfhire, fettled 1774.

MILFORD, a township in Mifflin county, Pennfylvania.

MILFORD, a post-town of the State of Delaware, pleafantly fituated on the north fide of Muspilion Creek, about 12 miles west of its mouth in Delaware Bay, 19 S. by E. of Dover, 7 fouth of Frederica, and 95. S. by W. of Philadelphia. It contains nearly 100 houfes, all built fince the war, except one. The inhabitants are Epifcopalians, Quakers and Methodifts.

MILFORD, a town of Northampton county, Pennfylvania, lately laid out on the N. W. fide of the Delaware, on a

lofty fituation, at Well's Ferry, sao miles above Philadelphia. In front of the town, which contains as yet only a the town, which contains as yet only a few houles; the fiver forms a cove well fitted for fheltering boats and lumber in florms, or freihes in the river: A faw-mill and paper-mill have been crefted here; the latter belongs to Mr. Biddis, who has difcovered the method of ma-fing paper and pafte-board, by fubfi-tuting a large proportion of faw-duft in the composition.

MILFORD, a polt-town of Connecti-cut, on Long-Ifland found, and in New-Haven county, 13 miles S. W. of New-Haven, and east of Stratford. The mouth of the creek on which it ftands has 3 fathoms water. This town was called *Wopewage* by the Indians, and was fettled in 1638. It contains an Epifcopal church, and 2 Congregational churches.

MILFORD Haven, a deep bay on the coaft of Nova Scotia, to the S. W. round the point of the ftrait of Canfo. It receives feveral rivers from the N. W. and S. W. MILITARY Townships, in the State

of New-York. The legislature of the State granted one million and a half acres of land, as a gratuity to the offi-cers and foldiers of the line of this State. This tract, forming the new county of Onondago, is bounden W. by the eaft fhore of the Seneca Lake, and the Maffachufetts lands in the new county of Ontario; N. by the part of Lake Ontario near Fort Ofwego; S. by a ridge of the Alleghany Mountains and the Pennfylvania line; and E. by the Tufcarora Creek (which falls nearly into the middle of the Oneida Lake) and that part of what was formerly Montgomery county, which has been fettling by the New-England people very rapidly fince the peace. This pleafant county is divided into 25 townships of 60,000 acres each, which are again fubdivided into 100 convenient farms, of 600 acres; making in the whole 2,500 farms. This tract is well watered by a multitude of fmall lakes and rivers.

The referved lands embofomed in this tract are as follow : a tract about 171 miles long, and 10 broad, including the northern part of the lake Cayuga, which lies in the centre of it, to the Cayuga Indians. The Indians have a village on each fide of the lake; and X 2

the

324

the ferry at the north end lies in lat. 42. 54. 54. 54. in orth. Connoga Caftle is about 3 miles fouth of the ferry, on the east fide of Lake Cayuga. The Onondago Refervation is uniformly 11 miles long, and 9 broad; bounded north by the Public Refervation, and part of the townfnips of Manlius and Camillus; A very finall part of the fouth end of Salt Lake is within the Refervation. The Salt Spring, and the Salt Lake; with a finall portion of ground on each fide is referved by the State; its greateft length is 64 miles, and the greateft breadth of the Refervation 34.

MILLER, Fort, is on the E. fide of Hudfon's river, 4t miles north of Albany, confifting of rapids in the river, and feveral mills thereon. It is fo called from a little mud fort formerly built there against the Indians.

MILLER'S, or Payquage, a river of Maffachufetts, which runs W. by S. and falls into Connecticut river, hetween Northfield and Montague. It is a beautiful fiream, though in fome places very rapid. Its chief fource is in Monomenock pond in Rindge, New-Hampfhire, and partly in Winchendon; the other in Naukheag pond in Afhburnham. Thefe with various fireams unite in Winchendon, and form Miller's river.

MILLERS, a fettlement in Kentucky, on a branch of Licking river, 32 miles north-eaft of Lexington.

MILLER'S Falls. See South Hadley. MILLER'S-TOWN, in Northampton county, Pennfylvania, is pleafantly fituated on a branch of Little Lehigh river; 26 miles S. W. of Eafton, and 47 N. W. by N. of Philadelphia. It contains about 40 houfes.

MILLER's-TOWN. See Anville.

MILLER'S-TOWN, a fmall town in Shenandoah county, Virginia, 32 miles fouth of Winchefter. Two or three miles from this place is the narrow pafs, formed by the Shenandoah river on one fide, and a fmall brook on the other. It is about a rod and a half wide, and 2 or 3 long; on each fide is a bank of about 100 feet high.

MILL Ifland, near the N. W. end of Hudfon's Straits; N. N. W. of Nottingham Ifland, and S. by E. of Cape Comfort, but nearer to the latter. N. lat. 64. 36. W. long. 80. 30.

MILL Island, a finall island in that

MIN

branch of Chignecto Bay which runs up due north, whilft the Bay particu-Jarly to called, runs in north-eaft. It is nearly due weft 4 miles from the neareft point of land.

MILLSTONE, a fouth branch of Rariton river, in New-Jerfey,

MILLSTONE, a pleafant rural village, fituated on the river of its name, 14 miles N. of Princeton, in New-Jerfey, containing the feat of General Frelinghuyfon, and formerly the county town of Somerfet.

MILLTOWN, in the State of Delaware, two miles from Wilmington.

MILLTOWN, in Northumberland county, Pennfylvania, on the E. fide of the W. branch of Sulquehannah river, containing about 60 houfes, and 14 miles N. by W. of Sunbury.

MILTON, a township in Chittenden county, Vernont, situated on the east fide of Lake Champlain, opposite to South Hero Island. It is divided into nearly equal parts by La Moille river, which empties into the lake in Colchester, near the S. line of Milton. The township contains 282 inhabitants.

MILTON, the Uncataquiffett, or Unquety of the Ancient Indians, a township in Norfolk county, Massachusetts; adjoining to Dorchester, from which it is partly separated by Naponset river, noted for the excellent quality of its water. It is 7 miles S. of Boston, and contains 1039 inhabitants; 3 papermills, and a chocolate-mill. It was incorporated in 1662. Milton hill affords one of the finest prospects in America.

MILTON, a township in the yew county of Saratoga in New-York. By the State census of 1796, there were 301 of the inhabitants who were electors.

MILTON, a military township in Onondago county, New-York, fituated on the N. E. fide of Cayuga Lake, near its fouthern extremity; 40 miles N. of Tioga river, and 21 S. by E. of the ferry on the N. end of Cayuga Lake. It was incorporated in 1794. By the State cenfus of 1796, 181 of its inhabitants were electors.

MILTON, a finall town in Albemarle county, Virginia, fituated on the S. W. fide of the Rivanna, about 80 miles N. W. by W. of Richmond. It has about zo houles and a warehouse for the infpection of tobacco.

MINAS, Bafin of, or Les Mines Bay,

fometim is a gull Fundy, narrow f tia in an bout 30 Annapol Bedford length, 7 of Mina. MINA middlem as mark Bay and S. Ame Bay, and 75. 18. MINE the E. 1 miles N. 15 S. by is nearly dering c fperfed w nences. near the MINE county, MING the moul They ha to leagu 63.25. MING the W. I N. E. of Path, ar burg. 1 creek, w the petro MING habit ne Sciota ri MINI on the N on the v about 5 N. W. MINI county, by the \ State of] inhabita to be ele MIQU 8 miles foundlan ly of wh of St. P ich runs particueaft. It from the

ch of Raural vilits name. New-Jerneral Free county

of Delagton. mberland E. fide of hah river. 1 14 miles

hittenden

the east polite to ided into ille river, Colchefn. The nts. t, or Untownship etts : adhich it is et river, ty of its fton, and 3 papert was in-Il affords merica. ew coun-

By the re 301 of ors. nhip in , fituated ake, near les N. of E. of the ga Lake. By the

lbemarle he S. W. miles N. nas about r the in-

s inhabi-

ines Bay, fomeMIQ

fometimes also called Le Grand Praye; is a gulf on the S. E. fide of the Bay of Fundy, into which its waters pals by a narrow ftrait, and fet up into Nova-Scotia in an E. and S. direction. It is about 30 leagues from the entrance of Annapolis, and 10 from the bottom of Bedford Bay. It is 12 leagues in length, and three in breadth. See Bafin of Minas.

MINAS, or De las Minas Hill, is the middlemoft of the three hills, defcribed as marks within land for Bonaventura Bay and river, on the coast of Peru, in S. America : thefe, are S. of Panama Bay, and in N. lat. 3. 20. W. long. 75. 18.

MINE AU FER, or Iron Mines, on the E. fide of Miffifippi river, is 671 miles N. by E. of Chickafaw river, and 15 S. by E. of the Ohio. Here the land is nearly fimilar in quality to that bordering on the Chickafaw river, interfperfed with gradual rifings or finall eminences. There was a post at this place, near the former S. boundary of Virginia. MINEHEAD, a township in Effex county, Vermont, on Connecticut river. MINGUN Islands, on the N. fide of the mouth of the river St. Lawrence. They have the ifland Anticofti S. diftant to leagues. N. lat. 50. 15. W. long. 63. 25.

MINGO-TOWN, an Indian town on the W. bank of the Ohio river, 86 miles N. E. of Will's-Town, by the Indian Path, and 40 fouth-westerly of Pittsburg. It stands a few miles up a imall creek, where there are fprings that yield the petral, a bituminous liquid.

MINGOES, an Indian nation who inhabit near the fouthern branch of the Sciota river. Warriors, 50.

MINISINK, a village in New-Jerfey, on the N. W. corner of the State, and on the western fide of Delaware river; about 5 miles below Montague, and 57 N. W. of Brunfwick.

MINISINK, a township in Orange county, New-York, bounded eafterly by the Wallkill, and foutherly by the State of New-Jerley. It contains 2,215 inhabitants; of whom 320 are entitled to be electors, and 51 are flaves.

MIQUELON, a small defert island, 8 miles S. W. of Cape May in Newfoundland Ifland. It is the most wefterly of what have been called the 3 iflands of St. Pierre, or St. Peter, and is not fo 325

high as the other two; but its foil is very indifferent, and it is not more than three-fourths of a league in length. There is a paffage or channel from the weftward along by the N. end of this island into Fortune Bay on the S. coast of Newfoundland. N. lat. 47. 4. W. long. 55. 55. It is fometimes called Maguelon.

MIRAGOANE, a town on the N. fide of the fouth peninfula of the ifland of St. Domingo, and S. fide of the Bight of Leogane, at the head of a bay of its name. It is on the road from Jeremie to Port au Prince, about 31 leagues E. by S. of the former, and 23 W. by S. of the latter. N. lat. 18. 27.

MIRAMICHI, or Mirachi, a port, bay and river on the N. E. coaft of New Brunswick. The port is at the mouth of the river. The entrance into the bay is very wide; it has Point Portage for its northern entrance, and its fouthern fide is formed by Escuminax point, which is 53 miles N. E. of Shediac harbour, and 34 S. E. of the mouth of Nippifighit river, which empties into Chaleur bay. There is a falmon fifhery in Miramachi river,

MIRAY Bay, on the coaft of the ifland of Cape Breton, is to the S. from Morienne Bay. Large vefiels may go up 6 leagues, and have good anchorage, and lie fecure from all winds. N. lat. 46. 5. W. long. 59. 49.

MIREBALAIS, an interior town in the French part of the ifland of St. Domingo, fituated nearly 12 leagues N. of Port au Prince, on the road from that city to Varettes; from which laft it is 14 leagues fouth-eaft."

MISCOTHINS, a small tribe of Indians who inhabit between Lake Michigan and the Miffifippi.

MISCOU, or Mifco, an island which forms the S. fide of the entrance of Chaleur Bay, and is now called Mufcow Ifland. The gut of Chepayan, about 2 or 3 leagues in length, and in fome parts near a league wide, feparates it from the N. E. coaft of New-Brunfwick. It abounds with falt marsh hay.

MISERY, an ifle between Salem and Cape Ann in Maffachufetts.

MISKO, an island on the fouth-weft fide of Chaleur Bay, at its mouth.

MISSINABE Lake is fituated in the north part of North-America, in lat. 48. 29. 42. N. and long, 84. 2. 42. W. X 3 MISSINABE

MISSINABE House is fituated on the east fide of Moofe river, 8 miles from Miffinabe lake, and 80 W. by S. of Frederick House; and is a flation belonging to the Hudson Bay Company.

MISSIQUASH River. Nova-Scotia and New-Brunfwick provinces are feparated by the feveral windings of this river, from its confluence with Beau Bafin (at the head of Chignecto channel) to its rife or main fource; and from thence by a due east line to the bay of Verte, in the firaits of Northumberland. See New-Brunfwick.

MISSISCOUI. See Michifcouie.

MISSISIPPI River. This noble riyer, which, with its eastern branches, waters five eighths of the United States, forms their western boundary, and feparates them from the Spanish Province of Louifiana and the Indian country. Its fources have never been explored ; of course its length is unknown. It is conjectured, however, to be upwards of 3,000 miles long. The tributary ftreams which fall into it from the weft and east, are numerous, the largest of which are the Miffouri from the weft, and the Illinois, Ohio, and Tenneffee from the eaft. The country on both fides of the Miffinppi, and on its tributary ftreams, is equal in goodness to any in N. America. This river is navigable to St. Anthony's Falls without any obstruction, and some travellers describe it as navigable above them. On both fides of this river are falt fprings or licks, which produce excellent falt; and on its branches are innumerable fuch fprings. Befides the doal mines in the upper parts of the Ohio country, there are great quantities of coal on the upper branches of this river. Some account of the valuable productions on the banks of this majettic river, and the lands which its branches water, will be feen under the description of Louisiana, Weft-Florida, Tenneffee, Georgia, &c. &c.' An itland of confiderable fize is formed by its mouths. befides many fmaller ifles. These mouths are fituated between the latitude of 29. and 20. N. and between the longitude of 89 and 90. W.

MISSOURI River, in Louifiana, falls into the Mitinippi from the weftward, 18 miles below the mouth of the Illihois, 195 above the mouth of the Ohio, MIS

and about I 160 miles from the Balize, or mouths of the Miffifippi in the gulf of Mexico. We have not fufficient knowledge of this river to give any correct account of the extent of its navigation. In Capt. Hutchins's map, it is faid to be navigable 1300 miles. Late travellers up this river, (among whom, is a French gentleman, a general officer, who has made a map of his expedition) reprefent that the progrefs of fettlement by the. Spaniards on the S. and W. and by the English on the N. and E. of the Miffouri, is aftonishing. People of both these nations have trading-houses 600 or 700 miles up this river. A Mr. M'Kenzie has performed a tour from Montreal to the South Sea; and it appears by his map that by fhort portages, and these not very numerous, there is a water communication, without great interruption, from the Upper Lakes to Nootka Sound, or its neighbourhood,

MISSOURIS, one of the Indian nations who inhabit the banks of the above river, having, it is faid, 1500 warriors,

MISTAKE Bay, a large bay on the weft fide of the entrance of Davis's Straits, and to the north of Hudfon's Straits; from which it is feparated by a peninfula of the porth main on the W. and Refolution Ifland on the fouth. It is to the N. E. of Nieva Ifland, and N. W. of Cape Elizabeth.

MISTAKEN Cape, the fouth point of the cafternmoft of the Hermit's Iflands, is about 3 leagues E. N. E. from Cape Horn, at the extremity of S. America. Between thefe, it is fuppofed, there is a paffage into Naffau Bay.

MISTAKEN Point, to the weltward of Cape Race, at the S. E. point of the Ifl nd of Newfoundland, and to the eaftward of Cape Pine, is fo called becaufe it has been frequently miftaken by feamen for Cape Race when they first make the island from the fouthward, though it is a leagues W. N. W. from it.

MISTIC, or Myflic, a flort river which fails into the north fide of Bofton harbour, by a broad mouth on the east fide of the peninfula of Charlestown. It is navigable for floops 4 miles to the industrious town of Medford; and is crossed a mile above its mouth, by a bridge 130 rods in length, through which vessels pairs by means of a draw.

MISTINSINS, an Indian nation who inhabit inhabit o of the far MIST the S. E. Houfe, o MITC Merrima mouth, which co ford. T of burde MITC who wit fettlemen Piorias. MOAC S. Amer of Venez to S. and ba; are cept one The fout MOBI formed b bama, a weftern confidera which is long. 87 fouth cou fluent ftr at Mobil leagues b veffels ci town. T neral abo bers of la as well as See Geor From th waters of at the me ing to th large box canoes m MOBI formerly importar It is pre

and fitua The Bay to the no number fubject t in the ho of Mob junction of Mobi Penfacol

inhabit on the fouthern fide of the lake of the fame name in Lower Canada.

MISTISSINNY Lake, in Canada, on the S. E. fide of which is a Canadian House, or station for trade.

MITCHELL's Eddy, the first falls of Merrimack river, 20 miles froms its mouth, and 8 above the new bridge which connects Haverhill with Bradford. Thus far it is navigable for fhips of burden.

MITCHIGAMAS, an Indian nation, who with the Piorias inhabit near the fettlements in the Illinois country. See *Piorias*.

MOAGES Iflands, on the N. coaft of S. America, in the entrance of the Gulf of Venezuela. They extend from N. to S. and lie weft of the Ifland of Aruba; are 8 or 9 in number, and all, except one, low, flat and full of trees. The foutheramoft is the largeft.

MOBILE, a large navigable river, formed by two main branches the Alabama, and Tombeckbee, in the fouthwestern part of Georgia, just below a confiderable ifland, the fouth point of which is in about lat. 31. 26. N. and long. 87. 55. W. Thence puriving a fouth courfe into Weft-Florida, the confluent fream enters the Gulf of Mexico, at Mobile Point in lat. 30. 17. N. 11 leagues below the town of Mobile. Large veffels cannot go within 7 miles of the town. The breadth of the bay is in general about 3 or 4 leagues. Vaft numbers of large alligators balk on the fhores, as well as fwim in the rivers and lagoons. See Georgia, Alabama, Tombeckbee, &c. From the north-eastern source of the waters of the Alabama to Mobile Point, at the mouth of Mobile Bay, is, according to the beft maps, about 460 miles : large boats can navigate 350 miles, and canoes much farther.

MOBILE, a city of Weft-Florida, formerly of confiderable fplendor and importance, but now in a ftate of decline. It is pretty regular, of an oblong figure, and fituated on the W. bank of the river. The Bay of Mobile terminates a little to the north-eaftward of the town, in a number or marfhes and lagoons; which fubject the people to fevers and agues in the hot leafon. It is 33 miles north of Mobile Point, about 40 below the junction of the two principal branches of Mobile river, and 30 W. N. W. of Penfacola. There are many very elegant houfes here, inhabited by French, Englifh, Scotch, and Irifh. Fort Conde, which ftands very near the bay, towards the lower end of the town, is a regular fortrefs of brick; and there is a neat fquare of harracks for the officers and foldiers. Mobile, when in poffeffion of the Britifh, fent yearly to London fkins and furs to the value of from 12 to £15,000 fterling. It furrendered to the Spanifh forces in 1780.

MOBJACK Bay, fets up N. W. from Cheiapeak Bay, into Gloucefter county, Virginia, on the N. fide of York river.

MOCOA, a city of Terra Firma, S. America, fituated at the main fource of Oronoko river, there called Inirchia.

MOCOMORO, or Little Oronoke, a giver to the S. E. of the great river Oronoko, on the E. coaft of S. America, 4 leagues weftward of Amacum.

MODER and Daughters Iflands, a long ifland 2 leagues eaft by fouth of the Father, or Vaader Ifland, with 2 fmall ones, fo called, near Cayenne, on the eaft coaft of S. America, not far from the Conftables, and in about lat. 5. N. long. 52. W.

MOGHULBUGHKITUM, or Mubulbucktitum, a creek which runs westward to Alleghany river, in Pennfylvania. It is passable in flat-bottomed boats to the settlements in Northumberland county. Wheeling is its northern branch.

MOHAWK River, in New-York, rifes to the northward of Fort Stanwix, about 8 miles from Black, or Sable river, a water of Lake Ontario, and runs fouthwardly 20 miles to the fort, then eaftwardly 110 miles, and after receiving many tributary ftreams, falls into Hudfon river, by three mouths opposite to the cities of Lanfinburgh and Troy, from 7 to 10 miles N. of Albany. The produce that is conveyed down this river, is landed at Schenectady, on its S. bank, and is thence conveyed by land 16 miles, over a barren, fandy, fhrub plain, to Albany. It is in contemplation either to cut a canal from Schenectady to the navigable waters of Hudson river, or to establish a turnpike road between Schenectady and Albany. This fine river is now navigable for boats, from Schenectady, nearly or quite to its fource, the locks and canals round the Little Falls, 56 miles above Albany, having been completed in the autumn of 1795; fo that boats full loaded now X4 pale

alize, or gulf of t knowrrect action. In id to be ravellers French who has represent : by the d by the the Mifof both s 600 or A Mr. ur from id it apwrtages, here is a great inakes to rhood, lian nahe above varriors. on the Davis's **Judfon's** rated by 1 the W. uth. It , and N.

point of Islands, om Cape America. here is a

weftward int of the l to the alled bemiftaken hen they e fouth-. N. W.

ort river of Bofth on the rleftown, les to the s and is th, by a through f a draw. tion who inhabit

328

pais them. The canal round them is nearly 1 of a mile, cut almost the whole diftance through an uncommonly hard. rock. The opening of this navigation is of great advantage to the commerce of the State. A fhore of at least 1000 miles in length, is, in confequence of it, washed by boatable waters, exclusive of all the great lakes, and many millions of acres of excellent tillage land, rapidly fettling, are accommodated with water communication for conveying their produce to market. The intervales on both fides of this river, are of various width, and now and then interrupted by the projection of the hills quite to the banks of the river, are some of the richeft and heft lands in the world. The fine farms which embrace these intervales, are owned and cultivated principally by Dutch people, whole mode of managing them would admit of great improvement. The manure of their barns they confider as a nuisance, and inftead of fpreading it on their upland, which they think of little value, (their meadow lands do not require it) they either let it remain for years in heaps, and re-move their barns, when accels to them becomes difficult, or elfo throw it into the river, or the gullies and fireams which communicate with it. The banks of this river were formerly thickly fettled with Indians. At the period when Albany was first fettled, it has been faid by respectable authority, that there were 800 warriors in Schenectady; and that 300 warriors lived within a fpace which is now occupied as one farm. The Cohoez in this river are a great curiofity. They are 3 miles from its entrance into the Hudfon. The river is about 1000 feet wide; the rock over which it pours, as over a mill-dam, extends from S. W. to N. E. almost in a line from one fide of the river to the other, and is about 40 feet perpendicular height, and including the defeent above, the fall is as much as 60 or 70 feet. About a mile below the falls, is a handfome bridge, finished in July, 1795. It is 1100 feet in length, 24 in breadth, and 15 feet above the bed of the river, which for the most part is rock, and is supported by thirteen folid ftone pillars. It is a free bridge, and including the expence of cutting through a ledge on the N. E. fide of the river, coft 12,000 dollars. The river imme-

diately below the bridge, divides into three branches, which form feveral large iflands. The branches are ford-, able at low water, but are dangerous. From the bridge you have a fine view of the Cohoez on the N. W.

the Cohoez on the N. W. MOHAWK, a branch of Delaware river. Its courfe from its fource in Lake Uttayantha is S. W. 45 miles, thence S. E. 12 miles, when it mingles with the Popachton branch; thence the confluent fream is called Delaware.

MOHAWK, a town on the S. fide of the river of its name, in Montgomery county, New-York, fituated in one of the moft fertile countries in the world. It was abandoned by the Mohawk Indians in the fpring of 1780. See Hunter Fort. The township is bounded northerly by Mohawk river, easterly and foutherly by Albany county. In 1790, it contained 4440 inhabitants, including 111 flaves.

MOHAWKS, an Indian nation, acknowledged by the other tribes of the Six nations to be "the true old heads of the confederacy." They were formerly very powerful, and inhabited on Mohawk river. As they were ftrongly attached to the Johnfon tamily, on account of Sir William Johnfon, a part of them emigrated to Canada with Sir John Johnfon, as early as the year 1776. About 300 of this nation now refide in Upper Canada. See Hunter Fort and Six Nations.

MOHEGAN, fituated between Norwich and New-London, in Connecticut. This is the refidence of the remains of the Monhegan tribe of Indians. A confiderable part of the remains of this tribe lately removed to Oneida with the late Mr. Occom. See Brathertown.

MOHICCONS, a tribe of Indians who inhabit on a branch of the Sufquehannah between Chagnet and Owegy. They were reckoned by Hutchins, about 30years ago, at 100, but by Imlay, in 1773, at only 70 fighting men. They were formerly a confederate tribe of the Delawares. Allo an Indian tribe, in the N. W. Territory, who inhabit near Sandufky, and between the Sciota and Mufkingum; warriors, 60.

MOINS, a river of Louisiana, which empties from the N. W. into the Missifippi, in lat. 40. 20. N. The Sioux Indians defeend by this river.

MOISIE River, on the N. shore of the

the St. La S. W. a which to Seven Ifla thefe iflan MOLE part of th leagues E is often ca though in Francois, firft port of war, t nature an der whole conftruct here the but the p were of 1 fucceffors fo that it fon. It and is co tion in S purity o from Jar the fame coffee-1 digo, an lue of 11 on expor It is 4 le N. W. (Francois Paix. N Moli the ifland Indies, of Brim which is and a cl of it are MON a fmall Point l' ernmoft ming, a W. poil It is 2 little m ral port water, i for fettle ing of c ticularly A leage a very i the Lit MON the St. Lawrence, is about 3 leagues W. S. W. of Little Saguena river from which to the W. N. W. within the Seven Iflands, is a bay fo called from thefe iflands.

MON

MOLE, The, is fituated in the N. W. part of the illand of St. Domingo, 2 leagues E. of Cape St. Nicholas, and is often called by that name. The Mole, though inferior, by a great deal, to Cape Francois, and Port au Prince, is the first port in the island for fafety in time of war, being ftrongly fortified both by nature and art. Count D'Eftaing, under whole direction thele works were' constructed, intended to have established here the feat of the French government; but the productions of its dependencies were of too little value to engage his fucceffors to carry his plan into effect; fo that it is now no more than a garrifon. It has a beautiful and fafe port, and is confidered as the healthieft fituation in St. Domingo, by reafon of the purity of its fprings. The exports from Jan. 1, 1789, to December 31, of the fame year, were only 265,615lb. coffee-26,861lb. cotton-2,823lb. indigo, and other fmall articles to the value of 129 livres. The value of duties on exportation 1,250 dollars 21 cents. It is 4 leagues W. of Jean Rabel, 11 N. W. of Bombarde, 36 W. of Cape Francois, and 171 W. by S. of Port de Paix. N. lat. 19. 50. W. long. 75.48. MOLINE'S Gut, on the S. W. fide of

MOLINE's Gut, on the S. W. fide of the island of St. Christopher's in the W. Indies, is the first rivulet to the S. E. of Brimstone Hill, near the mouth of which is anchorage in 5 and 10 fathoms, and a clear shore; but to the eastward of it are some sunken rocks.

MONA, or La Guenon, or The Mone, a finall ifland, 11⁴/₂ leagues S. W. of Point l'Epee, which is the fouth-wefternmoft point of the ifland of St. Doming, and 14⁴/₂ leagues W. of the S. W. point of the ifland of Porto Rico. It is a leagues from E. to W. and a little more from N. to S. It has leveral ports for finall veffels, plenty of good water, and all that would be neceffary for fettlements of culture, and the breeding of cattle. Its fruit trees, and particularly the orange, are much extolled. A league and a half N. W. of Mona is a very fmall ifland, called Monique, or the Little Monkey.

MONADNOCK, Great, a mountain

fituated in Chefhire co. New-Hampfhire, between the towns of Jaffray, and Dublin, 10 miles N, of the Maffachufetts line, and 22 miles E. of Connecticut river. The foot of the hill is 1395 feet, and its fummit 3254 feet, above the level of the fea. Its bafe is 5 miles in diameter from N. to S. and 3 from E. to W. On the fides are fome appearances of fubterraneous fires. Its fummit is a bald rock.

MONADNOCK, Upper Great, a high mountain, in Canaan, in the N.E. corner of the State of Vermont.

MONAHAN, a township in York co. Pennsylvania.

MONDAY Bay, on the S. fhore of the ftraits of Magellan, in that part of the ftraits called the Long Reach, and 4 leagues W. of Piffpot Bay. It is nearly S. of Buckley Point, on the N. fide of the ftrait, and affords good ancherage in 20 fathoms.

MONDAY, a cape in the above firaits, 7 leagues W. N. W. of Cape North. S. lat. 53: 12. W. long. 75. 20.

Mongon, on the coaft of Peru, on the S. Pacific Ocean, is 10 leagues N. of the harbour of Guarmey, and 4 leagues from Bermejo Ifland, which lies between the former places. Cafma is 4 leagues N. of it. Mongon is known at fea by a great mountain juft over it, which is feen farther than any others on this part of the coaft.

Mongon, Cape, on the S. fide of the ifland of St. Domingo, is 3000 fathoms N. of Point Bahoruco and the river Nayauco, and nearly S. of the little port of Petit Trou.

MONHEGAN, or Menbegan, 2 finall ifland in the Atlantic Ocean, 12 miles fouth-eafterly of Pemaquid Point, in Lincoln co. Diffrict of Maine, and in lat. 43. 42. North of it are a number of finall ifles at the mouth of St. George's river. Captain Smith landed his party here in 1614. The chimneys and remains of the houfes are yet to be feen.

MONETOU Islands, in the N.W. Territory, lie towards the E. fide of the Michigan Lake, towards its N. end, and fouthward of Beaver Islands.

MONKTON, a township in Addison county, Vermont, E. of Ferrisburgh, and contains 450 inhabitants.

MONKTON, a township in Annapolis county, Nova-Scotia, inhibited by Acadians, and a few families from New-England:

everal ford-, rous. iew of aware ce in miles, ingles

into

re. ide of omery one of world. vk In*funter* northy and

1790, luding

ce the

n, acof the heads re forted on rongly on acpart of r John

3776.

refide

ort and

Nor-Elicut. ains of A conof this th the wn. ns who uehan-They out 30-11775, y were e Dela-

in the it near it and

which

Miffi-Sioux

the

England. It lies partly on the bason of Annapolis, and partly on St. Mary's Bay, and confifts chiefly of wood-land and falt-marsh. It contains about 60 families.

330

MONCLOVA, a town of New-Leon, N. America, fituated S. E. of Conchos.

MONMOUTH, a large maritime county of New-Jerfey, of a triangular fhape, so mikes in length, and from 25 to 40 in breadth; bounded north by part of Rasiton Bay, N. W. by Middlefex co. S. W. by Burlington, and E. by the ocean. It is divided into 6 townfhips, and contains 36,918 inhabitants, including 1596 flaves. The face of the county is generally level, having but few hills. The most noted of thefe are the high-lands of Navefink and Centre-Hill. See Middletown. A great part of the county is of a fandy foil; but other parts are fertile. There is a very curious cave, now in ruins, at the mouth of Navefink river, 30 feet long and 15 wide, and contains three arched apartments.

MONMOUTH, or Freehold, a posttown of New-Jerfey, and capital of the above co. fituated 22 miles N. E. by E. of Allentown, 34 eaft of Trenton, 14 S. W. by S. of Shrewfbury, and 64 N. E. by E. of Philadelphia. It contains a court-house and gaol, and a few compact dwelling-houfes. This town is remarkable for the battle fought within its limits on the 27th of June, 1778, between the armies of General Washington and Sir Henry Clinton. The latter having evacuated Philadelphia, was on his march to New-York. The loss of the Americans, in killed and wounded, was about 250; that of the British, inclusive of prifoners, was about 350. The Britifh purfued their march the night after, without the lofs of their covering party or baggage. See Freebold.

MONMOUTH, a finall post-town in Lincoln co. fituated on the east fide of Androscoggin river, 15 miles W. by S. of Hallowell court-house, 5 westerly of Winthrop, 10 N. E. by N. of Greene, 49 N. of Portland, and 180 N. by E. of Boston.

MONMOUTH Cape, on the E. fide of the Straits of Magellan, about half way from the fouthern entrance of the fecond Narrows to the fouth-eaft angle of the ftraits oppofite Cape Forward. MONMOUTH Island, one of the four islands of Royal Reach, in the Straits of Magellan, and the second from the westward.

MONOCACY, a river which after a S. S. W. courfe, empties into the Patowmac, about 50 miles above Georgetown.

MONONGAHELA River, a branch of the Ohio, is 400 yards wide at its junetion, with the Alleghany at Pittfburg. It is deep, gentle and navigable with batteaux and barges beyond Red Stone Creek, and still further with lighter craft. It rifes at the foot of the Laurel Mountain in Virginia, thence meandering in a N. by E. direction, paffes into Pennfylvania, and receives Cheat river from the S. S. E. thence winding in a N. by W. courfe, feparates Fayette and Weftmoreland from Washington county, and paffing into Alleghany county, joins the Alleghany river at Pittfburg and forms the Ohio. It is 300 yards wide 12 or 15 miles from its mouth, where it receives the Youghiogany from the fouth-eaft, which is navigable with batteaux and barges to the foot of Laurel hill. Thence to Red Stone, at Fort Byrd, by water is 50 miles, by land 30. Thence to the mouth of Cheat river, by water 40 miles, by land 28; the width continuing at 300 yards, and the navigation good for boats. Thence the width is about soo yards to the weftern fork, 50 miles higher, and the navigation frequently interrupted by rapids; which, however, with a fwell of 2 or 3 feet, become very paffable for boats. It then admits light boats, except in dry feations, 65 miles farther, to the head of Tygart's Valley, prefenting only fome fmall rapids and falls of one or two feet perpendicular, and leffening in its width to 20 yards. The western fork is navigable in the winter, towards the northern branch of the Little Kanhaway, and will admit a good waggon road to it. From the navigable waters of the fouth-easternmost branch of the Monongahela, there is a portage of 10 miles to the fouth branch of Patowmae river. The hills opposite Pittfburg on the banks of this river, which are at leaft 300 feet high, appear to be one fo-lid body of coal. On the Pike run of this river, a coal hill has been on fire 10 years; yet it has burnt away only 20 yards.

MONONGALIA,

MONO W. part long and inhabitant

about 75 Monsi

Diffrict of Sheepfout myfquam Moss county, N and 80 m and 52 fr porated in

habitants Mons the Delay Mont fhire co.

land and of North north of in 1753, A compa to build

The wor

MONT

of Conne

fhip in N co. on the about 51 north of habitant MoN

islands in the N. V Mon mity of tract her ceded to of build

MON

and river of St. D high hil by the F It is fitu in long. ftrip of of Mont that the and. I

Cape Fi a clear d doublin Monte It is for fide, and

MONONGALIA, a county in the N. W. part of Virginia, about 40 miles long and 30 broad, and contains 4,768 inhabitants; including 154 flaves. MONPOX, a city of Terra Firma, about 75 miles S. E. by E. of Tolu.

MONSEAG Bay, in Lincoln county, Diffriet of Maine, is feparated from Sheepfcut river, by the illand of Jere-

myfquam. Monson, a township in Hampshire county, Massachusetts, E. of Brimfield, and 80 miles S. W. by W. of Bofton, and sa from Portfmouth. It was incorporated in 1760, and contains 1331 inhabitants.

MONSIES, the third tribe in rank of the Delaware nation of Indians.

MONTAGUE, a township in Hamp-shire co. Maffachusetts, on the E. bank of Connecticut river, between Sunderland and Wendel, about 18 miles north of Northampton, and 97 miles weft by north of Bofton. It was incorporated in 1753, and contains 906 inhabitants. A company was incorporated in 1792 to build a bridge over the river here. The work has not yet been completed. MONTAGUE, the northernmost townfhip in New-Jerfey, is fituated in Suffex co. on the eaft fide of Delaware river, about 5 miles N. E. of Minifink, and 17 porth of Newtown. It contains 543 inhabitants, including 25 flaves.

MONTAGUE, the largeft of the finall iflands in Prince William's Sound, on the N. W. coaft of North-America.

MONTAUK Point, the eaftern extremity of Long-Ifland, New-York. A tract here, called Turtle Hill, has been ceded to the U. States for the purpole of building a light-house thereon.

MONTE Chrift, a cape, bay, town, and river, on the north fide of the ifland of St. Domingo. The cape is a very high hill, in the form of a tent, called by the French Cape la Grange, or Barn. It is fituated in lat. 19. 54. 30. N. and in long. 74. 9. 30. W. of Paris. A ftrip of level land joins it to the territory of Monte Chrift, and it is owing to this that the cape has been taken for an ifland. It is 14 leagues N. E. by E. of Cape Francois, where it may be feen in a clear day with the naked eye. After doubling this cape, we find the bay of Monte Chrift running nearly S. W. It is formed by Cape la Grange, on one fide, and Point des Dunes (Down Point)

on the other ; about 6, 500 fathoms afunder. The bay is about 1,400 fathoms deep, and its winding is nearly 4 leagu About 900 fathoms from the cap About 900 fathoms from the cape, de-fcending the bay, we find the little iff-and of Monte Chrift, 350 fathoms from the thore. One may fail between the two, with 2, 4, and 5 fathoms water : and about 250 fathoms further on, i anohorage in from 6 to 10 fathoms. A league and a quarter from Cape la Grange, is a battery intended to protect a landing place, of 100 fathoms wide, which is below, and opposite the town of Monte Chrift. The town of Monte Chrift ftanding at 800 fathoms from the fea fide, rifes in form of an amphitheatre on the fide of the coaft, which is very high all round this bay. The town is aoo fathoms fquare, which fpace is divided into 9 parts, cut by two ftreets running from E. to W. and two others from N. to S. It was founded in 1533. abandoned in 1606, and now but a poor place, deftitute of every refource but that of cattle raifed in its territory, and fold to the French. The town and territory contain about 3,000 fouls. There is a trifling garrison at Monte Chrift. About a league from the battery, following the winding of the bay, is the river of Monte Chrift, or more proper-ly, the river Yaqui. The land round the town is harren and fandy; and the river contains great numbers of croco-diles. Monte Chrift is a port well known to American finugglers, and carries on a great commerce from its vicinity to the French plantations. In the time of peace, all the produce of the plain of Mariboux fituated between Port Dauphin and Mancenille Bay, is thipped here, and in a war between France and Britain, it used to be a grand market, to which all the French in the north part of the ifland tent their produce, and where purchafers were always ready.

MONTE Chrift, a chain of mountains which extend parallel to the north coaft of the ifland of St. Domingo, from the bay of Monte Chrift, to the bay of Samana on the E. Two large rivers run in opposite directions along the fouthern fide of this chain. The river Monte Chrift or Yaqui in a W. by S. direction, and Yuna river in an E. by S. courfe to the bay of Samana. They both rife near La Vega, and have numerous branches.

MONTEGO

ily 20 ALIA,

e four

Straits

m the

fter a ic Pacorge-

nch of

june-

fburg.

: with

Stone

ighter

Laurel

inder-

s into

river

z in a

te and coun-

minty,

thurg

yards

nouth.

ogany

igable

oot of

ne, at

s, by

Cheat

d 28 ;

and

hence

to the

d the

by ra-

vell of

le for

S. ex-

er, to

inting

of one

ingin

eftern

wards

Kan-

aggon

vaters

of the

of 10

wmac

irg on

are at

ne fo-

un of

ire 10

MONTECO Bay is on the N. fide of the ifland of Jamaica, 20 miles E. by N. of Lucea harbour, and 21 W. of Martha Brae. This was formerly a flourifhing and opulent town : it confifted of 225 houfes, 33 of which were capital flores, and contained about 600 white inhabitants. The number of topfail veffels which cleared annually at this port were about 150, of which 70 were capital fhips; but in this account are included part of thofe which entered at Kingfton. This fine town was almost totalby deftroyed by an accidental fire, in July, 1795; the damage was estimated at f.200,000 fterling.

July, 1995, MONTEVIDEO, a bay and town of La Plata or Paraguay, in S. America, fituated on the northern fide of La Plata river, in lat. 34. 30. S. It lies E. of Buenos Ayres, and has its name from a mountain which overlooks it, about 20 leagues from Cape Santa Maria, at the mouth of the Plata.

MONTGOMERY, a new county in the Upper Diffrict of Georgia.

MONTGOMERY, a county of New-York, at first called Tryon, but its name was changed to Montgomery in 1784, by act of the Legislature. It confisted of 11 townships, which contained 28,848 inhabitants, according to the census of 1791. Since that period the counties of Herkemer and Otsego have been erected out of it. It is now bounded N. and W. by Herkemer, E. by Saratoga, S. by Schoharie, and S. W. by Otsego co. By the state census of 1796, it is divided into 8 townships; and of the inhabitants of these 3379 are qualified electors. Chief town, Johnston.

MONTGOMERY, a township in Ulffer co. New York, bounded eafterly by New-Windfor and Newburgh, and contains 3563 inhabitants, including 236 flaves. By the flate census of 1796, 497 of the inhabitants were qualified electors.

MONTGOMERY, a fort in New-York State, fituated in the High Lands, on the W. bank of Hudfon's river, on the N. fide of Popelop's Creek, on which are fome irou-works, oppofite to St. Anthony's Nofe, 6 miles S. of W. Point, and 32 from New-York city. The fort is now in ruins. It was reduced by the Britifh in October, 1777. See Anthony's Nofe. MONTGOMERY, a township in Franklin county, Vermont.

MONTGOMERY, a township in Hampshire co. Massachusetts, 100 miles from Boston. It was incorporated in 1780, and contains 449 inhabitants.

MONTGOMERY, a county in Pennfylvania, 33 miles in length, and 17 in breadth, N.W. of Philadelphia county. It is divided into 26 townfhips, and contains 22,929 inhabitants, including 114 flaves. In this county are 96 grift mills, 61 faw-mills, 4 forges, 6 fulling mills, and 10 paper-mills. Chief town, Norritown.

MONTGOMERY, a township in the above county. There is also a township of this name in Franklin county.

MONTCOMERY, a county in Salifbury diffrict, N. Carolina, containing 4725 inhabitants, including 834 flaves.

MONTGOMERY, a county of Virginia, S. of Botetourt county. It is about too miles in length, and 44 in breadth, and contains fome lead mines. Chief town, Chriftianfburg.

town, Chriftianfburg. MONTGOMERY Court-Houfe, in Virginia, is 28 miles from Anion courthoufe, 46 from Wythe court-houfe, and 40 from Salifbury. It is on the poltroad from Richmond to Kentucky. A post office is kept here.

MONTCOMERY, a county of Maryland, on Patowmac river. It contains 18,003 inhabitants, including 6,039 flaves.

MONTCOMERY Court-Houfe, in the above county, is 28 miles S.E. by S. of Frederickstown, 14 north by weft of George-town on the Patowmac, and 35 fouth-wefterly of Baltimore.

MONTGOMERY, a new county in Tenneffee State, Mero diffrict. This and Robertion county are the territory formerly called *Tenneffee County*, the name of which ceases fince the State has taken that name.

MONTMORIN, a new town on the north bank of Ohio river, 18 miles below Pittfburgh, fituated on a beautiful plain, very fertile, and abounding with coal.

MONTPELIER, a township in Caledonia co. Vermont, on the N. E. fide of Onion river. It has 118 inhabitants, and is 43 miles from Lake Champlain.

MONTREAL, the fecond city in rank in Lower Canada, ftands on an ifland in the river St. Lawrence, which is 10 leagues in length and 4 in breadth, and has its name from a very high mountain about

about th overlook hence th Royal N had poffe vate prop fo well t a deligh thing the venience is a very of Franc vided by and whe houses v manner; one view fouthern hill on t falls.gra contains elegant; of the 1 much fi are ftati of the It is abo thore of weft of about h Crown 1 ton, and North la St. Lav is about There is river op of which all kept one whe coft f.1 of ftone, ftops a 1 mill in c very cui or dam, while th there is the wor MONT eaftware foutherr MON end of 1 at the I N. E. o MON of the ifl

\$32

ampfrom 1780,

Penn-17 in unty. l cong 114 mills, mills. Nor-

n the vnfhip

Salifining laves. Virgiabout adth, Chief

n Vircourt-, and poft-

Maryntains 6,039

in the S. of eft of nd 35

ty in This ritory the State

n the miles utiful with

Caleide of tants, plain. rank ifland **is** 10 , and ntain about

MON

about the middle of it which it feens to overlook like a monarch from his throne; hence the French called it Mont-real or Royal Mountain. While the French had poffeffion of Canada, both the city and illand of Montreal belonged to private proprietors, who had improved them fo well that the whole ifland had become a delightful fpot, and produced every thing that could administer to the convenience of life. The city, around which is a very good wall, built by Louis XIV. of France, forms an oblong iquare, divided by regular and well formed ftreets; and when taken by the British, the houfes were built in a very handfome manner; and every house might be seen at one view from the harbour, or from the fouthernmost fide of the river, as the hill on the fide on which the town flands falls gradually to the water. Montreal contains about 600 houses, few of them elegant; but fince it fell into the hands of the British in 1760, it has fuffered much from fire. A regiment of men are flationed here, and the government of the place borders on the military. It is about half a league from the fouth thore of the river, 170 miles fouthweft of Quebec, Trois Rivieres being about half way; 110 north by welt of Crown Point; 308 north by weft of Bofton, and 350 north by east of Niagara. North lat. 45. 35. weft long. 73. 11. See St. Lawrence. The river St. Lawrence is about three miles wide at Montreal. There is an ifland near the middle of the river opposite the city, at the lower end of which is a mill with 8 pair of ftones, all kept in motion, at the fame time, by one wheel. The works are faid to have coft £.11,000 fterling. A large mound of stone, &c. built out into the river; stops a sufficiency of water to keep the mill in continual motion. And what is very curious, at the end of this mound or dam, veffels pais against the stream, while the mill is in motion. Perhaps there is not another mill of the kind in the world.

MONTREAL, a river which runs northeaftward into Lake Superior, on the fouthern fide of the lake.

MONTREAL Bay lies towards the E. end of Lake Superior, having an ifland at the N. W. fide of its entrance, and N. E. of Caribou island.

MONTROUIS, a town in the weft part of the island of St. Domingo, at the head | Fayette district. It contains 3770 in-

of the Bight of Leogane, 5 leagues foutheast of St. Mark, and 15 north-welt of Port au Prince.

MOO

MONTSERRAT, one of the Caribbee islands, and the smallest of them in the Atlantic Ocean. Columbus discovered it in 1493. It is of an oval form, 3 leagues in length, and as many in breadth, containing about 30,000 acres of land, of which almost two-thirds are very mountainous, or very barren. The cultivation of fugar occupies 6000 acres; cotton, provision and pasturage have 2000 acres allotted for each. No other tropical ftaples are raifed. The productions were, on an average, from 1784 to 1788, 2737 hhds of fugar, of 16 cwt. each, 1107 puncheons of rum, and 275 bales of cotton. The total exports from Montferrat and Nevis in 1787 were in value 214,1411. 16s., 8d. of which the value of 13,9811. 128. 6d. was exported to the American States. The inhabitants of Montferrat amount to 1300 whites, and about 10,000 negroes. The first fettlers, in 1632, were Irishmen, and the present inhabitants are chiefly their descendants, or other natives of Ireland fince fettled there, by which means the Irifh language is preferved there even among the negroes. The island is furrounded with rocks, and the riding before it is very precarious and dangerous on the approach of a tornado, having no haven. It has only three roads, viz. Plymouth, Old Har-bour, and Ker's Bay; where they are obliged to observe the fame methods as at St. Christopher's in loading or unloading the veffels. It lies 30 miles S. W. of Antigua; the fame diftance S. E: of Nevis, and is fubject to Great-Britain. N. lat. 16. 47. W. long. 62.

MONTSIOUGE, a river or bay in Lincoln co. District of Maine, which communicates with the rivers Sheepfcut and Kennebeck.

MONTVILLE, a township in New. London co. Connecticut, about 10 miles N. of New-London city. It has 2053 inhabitants.

MONUMENT Bay, on the east coast of Maffachufetts, is formed by the bending of Cape Cod. It is fpacious and convenient for the protection of thipping.

MOORE, a county of N. Carolina, in habitants, habitants, including 373 flaves. Chief | yord Brunfwick house is a fall of go town, Alforditon.

MOORE Court House, in the above-co. where a post-office is kept, is 38 miles from Randolph court-house, and 40 from Fayetteville.

MOORFIELD, in New-Jerley, 13 miles eafterly of Philadelphia.

MOORE Fort, a place to called in S. Carolina, is a flupendous bluff, or high perpendicular bank of earth on the Carolina fhore of Savannah river, perhaps 90 or 100 feet above the common flurface of the water, exhibiting the fingular and pleafing spectacle to a ftranger, of prodigious walls of parti-coloured earths, chiefly clays and marl, as red, brown, yellow, blue, purple, white, &c., in horizontal ftrata, one over the other. A fort formerly flood here, before the erection of one at Augusta, from which it flood a little to the north-east. The water now occupies the spot on which the fort flood.

MOORE'S Creek is 16 miles from Wilmington, in North Carolina. Here General M'Donald, with about 2,000 royalifts, were defeated (after a retreat of eighty miles, and a desperate engagement) by General Moore, at the head of 800 continentals. General M'Donald and the flower of his men were killed.

MOORFIELDS, a post-town, and the tapital of Hardy co. Virginia, fituated on the east fide of the fouth branch of Patowmac river. It contains a courthouse, a gaol, and between 60 and 70 houses. It is 25 miles from Romney, 75 from Winchefter, and 180 from Richmond.

MOOSE River, rifes in Milinabe lake, a fhort diftance from Michipicoten river, a water of Lake Superior, and purfues a north-eaftern courfe, receiving, about 12 miles from its mouth, a large fouth branch, and empties into the fouthern part of James's Bay, N. America, by the fame mouth with Abbitibee river. Moole Fort, and a factory are fituated at the mouth of this river, N. lat. 51. 16. W. long. \$1. 51. and Brunfwick Houfe is on its weft bank, about lat. 50. 30. Round the bottom of James's Bay, from Albany Fort and river, on the weft fide, to Rupert's river on the east fide, the woods afford large timber trees of various kinds, as oak, afh, befides the pine, cedar, fpruce, &c. Up Moofe river beMOR

yond Brunfwick houfe is a fall of go feet, above which it is deep and navigable for a great diftance; the foil and the climate above the fall are faid to be very good.

Moose River, a fhort fiream in Grafton county, New-Hampfhire, which runs north-eafterly from the White Mountains into Amarifcoggin river.

tains into Amarifcoggin river. MOOSEHEAD Lake, or Moofe Pond, in Lincoln co. Diffrict of Maine, is an irregular fhaped body of water, which gives rife to the eaftern branch of Kennebec river, which unites with the other, above Norridgewock, about 20 miles S. of the lake. The lake is faid to be 3 times as large as Lake George. There are very high mountains to the north and weft of the lake; and from these the waters run by many channels into the St. Lawrence.

MOOSEHILLOCK, the higheft of the chain of mountains in New-Hampfhire, the White Mountains excepted. It takes its name from its having been formerly a remarkable range for moofe, and lies 70 miles weft of the White Mountains. From its N. W. fide proceeds Baker's river, a branch of Pemigewaffet, which is the principal branch of Merrimack. On this mountain fnow has been feen from the town of Newbury, Vermont, on the 30th of June and 31ft of August; and on the mountains intervening, fnow, it is faid, lies the whole year.

Moose Ifland, on the coaft of the Diffrict of Maine, at the mouth of Schoodick river, contains about 30 families. On the fouth end of this illand is an excellent harbour fuitable for the confurction of dry docks. Common tides rife here 25 feet.

MORANT Keys, off the island of Jamaica, in the Weft-Indies. N. lat. 17.

47. W. long. 75. 35. MORINT Point, the most easterly promontory of the island of Jamaica. On the N. fide of the point is a harbour of the fame name. From Point Morant it is usual for ships to take their departure that are bound through the Windward Passage, or to any part of the W. end of the island of St. Domingo. N. lat. 17. 58. W. long. 76. 10.

MORANT Harbour, Port, is about 4 leagues weftward of Point Morant, on the fouth coaft of the ifland of Jamaica. Before the mouth of it is a finall ifland, called called Goo point of the MORAN weftward o rant. The an anchora MOREN S. America leagues nor bay between rable to ftr: W. wind the wind b makes a v Here is a v exceedingly might be c MOREN Chili, S. J leagues du bay of Ata MORE, co. Pennfy MOREL thips of Pe delphia co. gomery. MORG is bounded fee, and S It is divid Wilkes, R comb; and including MORGI chief town ated in B Here are a and gaol. 46 from I and 661 35. 47. MORG. ginia, and is pleafan Monongal W. of th contains a about 40 Brownfvil Pennfylva Maryland MORG 38 miles] of Boonfb MORG in Washi ed in, and and W. b

called Good Ifland, and a fort on each point of the entrance.

f 50

riga

and

to be

iraf.

runs

oun-

ond,

is an

hich

Ken-

ther,

es S.

be 3

here

) and

t the

o the

f the

hire,

for-

oofe,

Vhite

pro-

emi-

anch

fnow

wbu-

e and

tains

s the

f the

choo-

ilies.

is an

con-

tides

of Ja-

t. 17.

fterly

naica.

rbour

orant

lepar-

Vind-

e W.

out 4

it, on

naica.

fland,

called

N.

It

MORANT *River*, is two leagues weftward of the weft point of Point Morant. The land here forms a bay, with an anchorage along the shore.

MORENA, a cape on the coaft of Chili, S. America, is in lat. 23. 45. S. and 15 leagues north eaft of Cape George. The bay between thefe capes feems very defirable to firangers to go in; but in a N. W. wind is very dangerous, becaufe the wind blows right on the fhore, and makes a very heavy fea in the road. Here is a very convenient harbour, but exceedingly narrow, where a good fhip might be careened.

MORENA MORRO, on the coaft of Chili, S. America, in lat. 23. S. and 20 leagues due S. of the north point of the bay of Atacama.

MORE, a township in Northumberland co. Pennsylvania.

MORELAND, the name of two townfhips of Pennsylvania; the one in Philadelphia co. the other in that of Montgomery.

MORCAN Diffrid, in N. Carolina, is bounded W. by the State of Tennefice, and S. by the State of S. Carolina. It is divided into the counties of Burke, Wilkes, Rutherford, Lincoln, and Buncomb; and contains 33,292 inhabitants, including 2693 flaves.

MORGANTOWN, a post-town and the chief town of the above district, is fituated in Burke co. near Catabaw river. Here are about 30 houses, a court-house and gaol. It is 45 miles from Wilkes, 46 from Lincolntown, 113 from Salem, and 661 from Philadelphia. N. lat. 35. 47.

MORGANTOWN, a post-town of Virginia, and thire-town of Monongalia co. is pleafantly fituated on the east fide of Monongahela river, about 7 miles S. by W. of the mouth of Cheat river; and contains a court-house, a ftone-gaol, and about 40 houses. It is 30 miles from Brownfville, 24 from Union-Town, in Pennfylvania, 76 from Cumberland in Maryland, and 329 from Philadelphia.

MORGANS, a fettlement in Kentucky, 38 miles E. of Lexington, and 18 N. E. of Boonfborough.

MORGANZA, a town now laying out in Washington co. Pennsylvania, situated in, and almost surrounded by the E. and W. branches of Charter's river, in-

cluding the point of their confluence; 13 miles S. of Pittfburg, and on the post-road from thence to Washington, the county town, diftant 10 miles.' Boats carrying from 2 to 300 barrels of flour, have been built at Morganza, laden at the mill tail there, and fent down the Chartiers into the Ohio, and fo to New Orleans. By an act of the legislature of Pennfylvania, the Chartiers, from the Ohio upwards as far as Morganza, is declared to be a high way. This town is furrounded by a rich country, where numbers of grift and faw mills are already built; and the lands in its envi rons well adapted to agriculture and grazing; and is spoken of as a countr that is or will be the richest in Penniyivania. Morganza, from its fituat and other natural advantages, must become the centre of a great manufactur ing country; especially as confiderable bodies of iron ore, of a superior quality have been already difcovered in th neighbourhood, and have been aflayed, The high waving hills in this country are, from the quality of the foil, con vertible into the most luxuriant grazing lands, and are already much improved in this way. Thefe hills will be peculiarly adapted to raife live flock, and more particularly the fine long-wooled breed of fheep ; fuch as that of the Coefwold hills in England, whole fleeces fell for 28. sterling per pound; when others fetch only 12d. or 1gd. The wheat of this country is faid to weigh, generally, from 62 to 66 lb. and the bufhel of 8 gallons. From hence, confiderable exports are already made to New-Orleans, of flour, bacon, butter, cheefe, cider, and rye and apple fpirits. The black cattle raifed here are fold to the new lettlers, and to cattle merchants, for the Philadelphia and Baltimore markets ; many have also been driven to Niagara and Detroit, where there are frequent demands for live flock, which fuffer much in those northern countries, from hard winters, failures in crops, and other caufes.

MORGUE Fort, or Fortabeza de Morgue, on the fouth shore of the entrance to Baldivia Bay, on the coast of Chili, on the South Pacific Ocean. The channel has from 9 to 6 fathoms.

MORIENNE, a bay on the E. coaft of the island of Cape Breton, near Miray Bay, from which it is separated only by Cape

MOR Cape Brule. It is a tolerably deep

MORO Cafle is on the point or headland on the E. fide of the channel of the Havannah, in the N. W. part of the illand of Cuba, and is the first of two frong caffles for the defence of the channel against the approach of an enemy's thips. It is a kind of triangle, fortified with baffions, on which are mounted about 60 pieces of cannon, 24 pounders. From the caffle there alfo runs a wall or line mounted with 12 long brais cannon, 36 pounders; called, by way of eminence, " The twelve Apoleles:" and at the point, between the caftle and the fea, there is a tower where a man ftands and gives fignals of what veffels approach. See Hawannab.

MOROKINNEB, or Morotinnee, in the ifland of Mowee, one of the Sandwich Mands, in the N. Pacific Ocean, is in lat. 20. 29. N. and long. 126. 27. W. MOROSQUILLO Bay is to the fouthward of Carthagena, on the coaft of the Spanish Main, and in the bight of the oast coming out of Darien Gulf, on the eastern shore.

MOROTOI, or Morokoi, one of the Sandwich Iflands in the Pacific Ocean, is about 21 leagues W. N. W. of Moree Island, and has feveral bays on its S. and W. fides. Its W. point is in lat. 21. 20. N. and long. 157. 14. W. and is computed to contain 36,000 inhabitants. It is 7 leagues S. E. of Woahoo Ifland.

MORRIS, a county on the northern line of New-Jerley, weft of Bergen co. It is about 25 miles long, and 20 broad, is divided into 5 townships, and contains about 156,809 acres of improved, and 30,429 acres of unimproved land. The eastern part of the county is level, and affords fine meadows, and good land for Indian corn. The western part is more mountainous, and produces crops of wheat. Here are feven rich iron mines, and two fprings famous for curing rheumatic and chronic diforders. There are allo two furnaces, two flitting and rolling mills, 35 forges and fire-works, 37 faw mills, and 43 grift mills. There are in the county 16,216 inhabitants, of whom 636 are flaves.

MORRISSINA, a village in West-Chefter co. New-York, contiguous to Hell Gate, in the Sound. In 1790 it contained 133 inhabitants, of whom 30 | and north-weft of the gulf of Effequibo,

MOR

were flaves. In 1791 it was annexed to the township of West-Chefter.

MORRISTOWN, a post-town and capital of the above county, is a handfome town, and contains a Prefbyterian and Baptift church, a court-houfe, an academy, and about 50 compact houses; 19 miles N. W. of Newark, and about 100 N.E. of Philadelphia. The head-quarter of the American army, during the revolution war, was frequently in and about this town.

MORRISVILLE, a village in Pennfylvania, fituated in Berk's co. on the W. bank of Delaware river, one mile from Trenton, 9 from Briftol, and 29 from Philadelphia. A post-office is kept here.

MORRIS Bay, on the W. coaft of the island of Antigua, in the West-Indies. It cannot be recommended to fhips to pass this way, as there is in one place S. from the Five Iflands only 2 fathoms water. Vefiels drawing more than 9 feet water must not attempt it.

MORROPE, a town on the road between Quito and Lima, in S. America. It contains between 70 and 80 houses, containing about 160 families, all Indians : near it runs the river Pozuelos, the banks of which are cultivated and adorned with trees. Morrope is 28 or 30 leagues distant from Sechura, all that way being a fandy plain, the track continually fhifting.

MORRO VEIJO: See St. Gallan.

MORTIER's Rocks, on the S. coaft of Newfoundland Ifland. N. lat. 47. W. long. 54. 55.

MORTO Island, on the coaft of Peru, fo called by the Spaniards, from its firiking refemblance to a dead corple, extended at full length. It is also called St. Clara. It is about 5 leagues N. N. E. from the river Tumbez's and is 2 miles in length, and 27 leagues from Guyaquil.

MORTON Bay, on the N. W. coaft of the ifland of Nevis, in the Weft-Indies, is near the Narrows, or channel between that ifland and St. Chriftopher's, to the N.W. of which there is from 3 to 8 fathoms, according to the diftance from fhore.

MORUES Bay, on the fouthern fhore of the river St. Lawrence, fouthward of Gafpee Bay, and weft of Bonaventura and Mifcan iflands.

MORUGO, a finall river to the weft

ca. Moss the bank hottom (fmall ba tities of Spain ; M floops an Mose on the E. avilta B: foundland ward of 1 miles fou Mosc Most er, 9 mil 3 above 1 upper co and fent Peteribur Mosq Mexico; N. and E duras on well mad They an Spaniard ber of th Mexico, pean nati are very tles and 1 fail in Bi Mosq Greenlan 57. W. Mosq S. E. extr topher's, channel c going rou within th coaft is h fmall diff on the W Mosq W. fide fouthwar Mosq Virgin If the N. co it is depe 63. 15. Mosq point of Bay in Ja gazines a

on the co

on the coaft of Surinam, in S. Ameri-

Mosz, or Villa del Mofe, a town on the bank of the river Tabafco, in the hottom of Campeachy Gulf, to which fmall barges may go up. Great quantities of cocoa are thipped here for Spain; which brings a great many floops and fmall veffels to the coaft.

MOSES Point, a head or cape of land, on the E. fide of the entrance into Bonavista Bay, on the E. coast of Newfoundland Island. It is to the fouthward of the rocks called Sweers, and 5 miles fouth-west of Cape Bonavista. MOSCHEOS. See Kikapus.

Moster's, a place on Roanoke riv-

er, 9 miles below St. Tammany's, and 3 above Eaton's. The produce of the upper country is brought to these places, and sent from thence by waggons to Petersburg in Virginia.

Mosourro Country, a diffrict of Mexico, having the North Sea on the N. and E. Nicaragua on the S. and Honduras on the W. The natives are tall, well made, firong, and nimble of foot. They are implacable enemies to the Spaniards, who maffacred a vaft number of their people when they invaded Mexico, and will join with any European nation against the Spaniards. They are very dexterous in firiking fifh, turtles and mannaties. Many of the natives fail in British vefiels to Jamaica.

Mosquito Cove, on the coast of Greenland, in lat. 64. 55. and Ion. 52. 57. W.

Mosourro Bay, or Mufkite, is at the S. E. extremity of the ifland of St. Chriftopher's, and on the larboard fide of the channel of the Narrows, from the S.W. going round the point along the fhore, within the reef to the northward. The coaff is here lined with rocks, and at a fmall diftance is from 4 to 6 fathoms, on the W.N.W. fide of Booby Ifland. MOSQUITO, or Mufguite Cove, on the W. fide of the illand of Antigua, and

fouthward of Five Iflands Harbour.) MosQUITO Ifland, one of the finall

Virgin Idands, in the Weft-Indies, near the N. coaft of Virgin Gorda, on which it is dependent. N. lat. 18. 25. W. long. 63. 15.

Mosquito Point, is the larboard point of the channel into Port Royal Bay in Jamaica, where the powder magazines are fituated, and on which is s 237

battery of 80 guns, for the defence of the channel, which is here very narrow. Round the point to the north-wefferly, is a fpacious bay or balon, into which comes the river of Spanish. Town.

MosQuiro Point, at the entrance of the river Effequibo, on the coaft of Dutch Guiana, South-America; round, which, as foon as fhips are within, they are directed to run S. E. and then due S. and come to an anchor before the first village.

MOTHER Creek, in Kent co. Delaware. See Frederica.

MOTTE Ifte, a finall ifland in Lake Champlain, about eight miles in length and 2 in breadth, diftant 2 miles W. of North Hero Ifland. It confitutes a townthip of its own name in Franklin co. Vermont, and contains 47 inhabitants:

Vermont, and contains 47 inhabitants. MOUCHA, *f.a*, a bay on the coalt of Chili, on the W. coaft of S. America. MOULTONBOROUGH, a poft-town in Strafford co New-Hampihire, fituated at the N. W. corner of Lake Winniplfeogee, 18 miles E. by N. of Plymouth, and 43 N. W. by N. of Portimouth. This township was incorporated in 1777, and contains 365 inhabitants.

MOULTRIE Fort. See Sullivan's

MOUNT BETHEL, Upper and Lower, two townships in Northampton county, Pennsylvania.

MOUNT DESERT, an island on the coaft of Hancock co. Diffrict of Maine, about 15 miles long and 12 broad. It is a valuable tract of land, interfected in the middle by the waters flowing into the S. fide from the fea. There are two confiderable iflands on the fouth-east fide of Mount Defert Island, called Cranberry Islands, which affift in forming a harbour in the gulph which fets up on the fouth fide of the illand. In 1790, it contained 744 inhabitants. The northerly part of the ifland was formed into a township called Eden, in 1796. The fouth-eafternmost part of the island lies in about lat. 44. 12. N. On the main land, opposite the north part of the ifland, are the towns of Trenton and Sullivan. It is 335 miles north-eaft of Bofton.

MOUNT HOLLY, a village in Burlington co. New-Jerfey, fituated on the northern bank of Anocus Creek, about feven or eight miles fouth-east of Burlington.

MOUNT

nexed

nd cadfome

n and

aca-\$; 19 t 100 quarg the n and nnfyle W. from from here. aft of A.Ined to in one mly 2 more t it. d beerica. oules, Il Inuelos, d and 28 or

I, all

track

100

aft of

. W.

Peru,

m its

orple,

call-

les N.

and is

from

baft of

ndies,

tween

to the

to 8

from

fhore

ard of

ntura

e weft

uibo,

on

an.

MOUNT HOPE Bay, in the northeast part of Narraganiet Bay.

338

MOUNT HOPE, a finall river of Connecticut, a head branch of the Shetucket, riling in Union.

MOUNT JOLI, on the northern coaft of the Gulf of St. Lawrence, in Labrador.

MOUNT Ifland, on the above coaft, N. lat. 50. 5. W. long. 61. 35. MOUNT JOY, the name of two town-

MOUNT JOY, the name of two townfhips in Pennfylvania, the one in Lancafter the other in York co.

MOUNT Joy, a Moravian fettlement in Pennfylvania, 16 miles from Litiz.

MOUNT PLEASANT, a township in Weff-Chefter co. New-York, fituated on the east fide of Hudson river; bounded southerly by Greensburg, and northerly and easterly by Philipsburg. It contains 1924 inhabitants, of whom 275 are qualified electors, and 84 flaves. Also the name of a township in York co. Pennsylvania.

MOUNT PLEASANT, a village of Maryland, fituated partly in each of the counties of Queen Ann and Caroline, about 11 miles eafl of the town of Church Hill.

MOUNT TOM, a noted mountain on the weft bank of Connecticut river, near Northampton. Also the name of a mountain between Litchfield and Washington, in Connecticut.

MOUNT VERNON, the feat of GEORGE WASHINGTON, late Prefident of the United States. It is pleafantly fituated on the Virginia bank of Patowmac river, in Fairfax co. Virginia, where the river is nearly 2 miles wide; 9 miles below Alexandria; 4 above the beauti-ful feat of the late Col. Fairfax, called Bellevoir ; 127 from Point Look Out, at the mouth of the river, and 280 miles from the fea. The area of the mount is 200 feet above the furface of the river; and, after furnishing a lawh of five acres in front, and about the fame in rear of the buildings, falls off rather abruptly on those two quarters. On the north end it subfides gradually into extensive pasture grounds; while on the fouth it pes more fteeply, in a fhort diftance, and terminates with the coach-houfe, ftables, vineyard, and nurferies. On either wing is a thick grove of different flowering forest trees. Parallel with them, on the land fide, are two fpacious gardens, into which one is led by two

ferpentine gravel walks, planted with weeping willows and fhady fhrubs. The manfion house itself (though much embellished by, yet not perfectly fatisfac-tory to the chafte tafte of the prefent poffefior) appears venerable and convenient. The fuperb banqueting-room has been finished fince he returned home from the army. A lofty portico, 96 feet in length, fupported by 8 pillars, has a pleafing effect when viewed from the water; the whole affemblage of the green-houfe, fchool-houfe, offices, and fervants' halls, when feen from the land fide, bears a referablement for the land fide, bears a refemblance to a rural village; efpecially as the lands on that fide are laid out fomewhat in the form of English gardens, in meadows and grass-grounds, ornamented with little copies, circular clumps, and fingle trees. A finall park on the margin of the riv-er, where the Englifh fallow deer and the American wild deer are feen through the thickets, alternately with the veffels as they are failing along, add a romantic and picturefque appearance to the whole fcenery. On the oppofite fide of a finall creek to the northward, an extensive plain, exhibiting corn-fields and cattle grazing, affords in fummer a luxuriant landscape; while the blended verdure of wood-lands and cultivated declivities, on the Maryland fhore, variegates the profpect in a charming manner. Such are the philosophic fhades to which the Commander in Chief of the American army retired in 1783, at the close of a victorious war; which he again left in 1789, to dignify with his unequalled talents, the highest office in the gift of his fellow-citizens; and to which he has again retreated (1797) loaded with honours, and the benedictions of his country, to fpend the remainder of his days as a private citizen, in peace and tranquillity.

MOUNT VERNON, a plantation in Lincoln co. Diffrict of Maine, in the neighbourhood of Sidney and Winflow.

MOUNT WASHINGTON, in the upper part of the island of New-York.

MOUNT WASHINGTON, one of the higheft peaks of the White Mountains, in New-Hampshire.

MOUNT WASHINGTON, the fouthwesternmost township of Massachusetts, in Berkshire co. 150 miles W. by S. of Boston. It was incorporated in \$779, and contains 67 inhabitants.

MOUSE

ifland o angle of tween E goes in derately Mou Diffri& ocean b Mow next in hee. form, o Taboon bout 16 thought bitants. Mor ladelphi Muc of Cuba with If Cape Q Mun or 7 mi phia; v not yet large pi dation fire. MUL is fmall Crooke branch Muc Men E are to the E. o On the is good thoms, MU Domini 15. 16. MUI of S. A of Anc davayll Mu Bay. 1 Mu in Lew river, a Mu fmall, works Egg H the tow miles f

Mou

MOUSE Harbeur, at the E. fide of the island of St. John's, and at the S. W. angle of the gulf of St. Lawrence, is between East Point and Three rivers, and goes in with a finall creek that is moderately fpacious within.

Mousom, a fmall river of York co. District of Maine, which falls into the occan between Wells and Arundel.

MOWEE, one of the Sandwich Ifles, next in fize to, and N. W. of, Owhyhee. A large bay of a femicircular form, oppofite to which are the illands Tahoorowa and Morokinnee. It is about 162 miles in circumference, and is thought to contain nearly 70,000 inhabitants.

MOYAMENSING, a township in Philadelphia co. Pennsylvania.

MUCAROS Ifland, near the N. coaft of Cuba Ifland, in the W. Indies, which with Ifland Verde, lies opposite to the Cape Quibannano.

Mud Ifland, in Delaware river, is 6 or 7 miles below the city of Philadelphia; whereon is a citadel, and a fort not yet completed. On a fand bar, a large pier has been erected, as the foundation for a battery, to make a crofs fire.

MUD Lake, in the State of New-York, is fmall, and lies between Seneca and Crooked Lakes. It gives rife to a north branch of Tioga river.

MUGERAS Iflands, otherwife called Men Eaters or Women-Eaters Iflands, are 10 leagues S. of Cape Catoche, on the E. coaft of the peninfula of Yucatan. On the fouth of them, towards the land, is good anchorage in from 7 to 8 fathoms, and clean ground.

MULATRE Point, in the ifland of Dominica, in the W. Indies. N. lat. 15. 16. weft long. 61. 21.

MULATTO Point, on the west coast of S. America is the S. cape of the port of Ancon, 16 or 18 miles north of Cadavayllo river.

MULGRAVE Port. See Admiralty Bay. N. lat. 67. 45. W. long. 165.9.

MULHEGAN *River*, in Vermont, rifes in Lewis, and empties into Connecticut river, at Brunfwick.

MULLICUS *River*, in New-Jerfey, is fmall, and has many mills and ironworks upon it, and empties into Little Egg Harbour Bay, 4 miles eafterly of the town of Leeds. It is navigable 20 miles for veficls of 60 tons. 840

MUNCY, a creek which empties into the Sulquehannah from the N.E. about 23 miles N. of the town of Northumberland.

MUNSIES, DELAWARES, and SA-POONES, three Indian tribes, who inhabit at Diagho, and other villages up the N. branch of Sufquehannah river. About 20 years ago, the two first could furnish 150 warriors each, and the Sapoones 30 warriors.

MURDERERS Creek, in New-York State.

MURFREESBOROUGH, a post-town of N. Carolina, and capital of Gates co. It is fituated on Meherrin river, and contains a few houses, a court-house, gaol, and tobacco warehouse. It carries on a small trade with Edenton, and the other sea-port towns. It is 3 miles from Princeton, 12 from Winton, 50 N. by W. of Edenton, and 422 S. W. of Philadelphia.

MURGA MORGA River, on the coaft of Chili, in S. America, is fouthward of the S. point of Quintero Bay, and not far from the entrance into Chili river. It is not navigable, but is very good to water in.

MUSCLE Bank, at the entrance into Trinity Bay or harbour, in the direction of S.W. on the E. coaft of Newfoundland Hand.

MUSCLE Bay, in the Straits of Magellan, in S. America, is half way between Elizabeth's Bay, and York Road; in which there is good anchorage with a wefterly wind.

MUSCLE Bay, or Meffilones, on the coaft of Chili or Peru, in S. America, 5 leagues S. by W. of Atacama.

MUSCLE Sheals, in Tenneffee river, about 250 miles from its mouth, extend about 20 miles, and derive their stame from the number of shell-fish found there. At this place the river spreads to the breadth of three miles, and forms a number of islands; and the passage is difficult, except when there is a swell in the river. From this place up to the Whirl, or Suck, where the river breaks through the Great Ridge, or Cumberland Mountain, is 250 miles, the navigation all the way excellent.

MUSKOGULGE, Mufkogee, or as they are more commonly called, Creek Indiano, inhabit the middle parts of Georgia. The Creek or Mufkogulge language, which is foft and mufical, is Y a fooker

n 1779, Mouse

with

The

n em-

isfac.

refent

onve-

m has

home

6 feet

has a

n the

f the

e land

al vik-

that

form

s and

little

trees.

le riv-

er and

rough

veffels

oman-

to the

te fide

Ird, an

1-fields

nmer a

lended

tivated

t, vari-

g man-

ades to

of the

at the

nich he

ith his

office in

and to

(1797)

enedic-

the re-

citizen,

tion in

in the

inflow.

the up-

: of the

untains,

e fouth-

:hufetts,

by S. of

ork.

and

poken throughout the confederacy; (although confifting of many nations, who have a fpeech peculiar to them felves) as alfo by their friends and allies the Natchez. The Chickafaw and Chac-taw language, the Mufkogulges fay, is a dialect of theirs. The Mufkogulges fay, eminently deferve the encomium of all nations for their wildom and virtue, in expelling the greatest, and even the common enemy of mankind, viz. *firi-tions liquers*. The first and most co-gent article in all their treaties with the white people is, that "there shall not be any kind of fpirituous liquors fold or brought into their towns." Inftances have frequently occurred, on the difcohave requestly occurred, on the difco-very of attempts to run kegs of fpirits into their country, of the Indians firik-ing them with their tomahawks, and giving the liquor to the thirfty fand, not tailing a drop of it themfelves. It is difficult to account for their excellent policy in civil government ; it cannot derive its efficacy from coercive laws, for they have no fuch artificial fyftem. Some of their molt favourite longs and dances they have from their enemies, the Chactaws; for it feems that nation. is very eminent for poetry and mulic. The Mulkogulges allow of polygamy in the utmost latitude ; every man takes as many wives as he pleafes, but the first is queen, and the others her handmaids and affociates. The Creek or Mufkoguige confederacy have 55 towns, be-fides many villages. The powerful empire of the Mulkogulges eftablished itfelf upon the ruin of that of the Natchez. The Oakmulge Fields was the first fettlement they fat down upon, after their emigration from the welk, Beyond the Miffinppi, their original native country. They gradually fubdued their furrounding enemies, ftrengthening themfelves by taking into confederacy the van-quifhed tribes. Their whole number, fome years fince, was 17,280, of which 5,860 were fighting men. They confit of the Appalachies, Alibamas, Abecas, Cawittaws, Coofas, Confhacks, Coofactees, Chacfihoomas, Natchez, Ocomes, Oakmulgies, Okohoys, Pakanas, Taenfas, Talepoofas, Weetumkas, and fome others. Their union has rendered them victorious over the Chactaws, and formidable to all the nations around them. They are a well-made, expert, hardy, fagacious, politic people, extremely

tatoes, beans, peas, cabbage, melans, and have plenty of peaches, plums, grapes, frawberries, and other fruits. They are faithful friends, but inveterate enemies; hospitable to frangers, and honeft and fair in their dealings. No nation has a more contemptible opinion of the white men's faith in general than these people, yet they place great confi-dence in the United States, and with to agree with them upon a permanent boundary, over which the fouthern States shall not trefpals. The country which they claim is bounded northward by about the 34th degree of latitude; and extends from the Tombeckbee, or Mobile river, to the Atlantic Ocean, though they have ceded a part of this tract on the fea-coaft, by different treaties, to the State of Georgia. Their principal towns lie in latitude 32. and longitude 11. 20. from Philadelphia. They are fettled in a hilly but not mountainous country. The foil is fruitful in a high degree, and well watered, abounding in creeks and rivulets, from whence they are called the Greek Indians.

MUSCONECUNK, a finall river of New-Jerfey, which empties into the Delaware 6 miles below Eafton.

MUSKINGUM, that is, Elk's Eye, a navigable river of the N.W. Territory. It is 250 yards wide at its confluence with the Ohio, 172 miles below Pittfburg, including the windings of the Ohio, though in a direct line it is but 90 miles. At its mouth ftands Fort Harmar and Marietta. Its banks are fo high as to prevent its overflowing, and it is navigable by large batteaux and barges to the Three Legs, 110 miles from its mouth, and by fmall boats to the lake at its head, 45 miles farther. From thence, by a portage of about one mile, a communication is opened to Lake Erie, through Cayahoga, a ffream of great utility, navigable the whole length, without any obstruction from falls. From Lake Erie, the avenue is well known to Hudson's river in the State of New-York. The land on this river and its branches is of a fuperior quality, and the country abounds in fprings and conveniences fitted to fettlements remote from from fea. coal, freefalt-fpring ed, 8 mile Marietta, a quantit 1000 gall allons of lias proved perior qui coaft. Musq fouthern v ing 200 w Musq habiting i Muski in lat. 64. Musq fmall dift on the coa of Mulqu abound in

Florida, whilft the the fea, a Musqu neighbou Outtagon

MYER co. Pennf of Tulpe low the houfes, a Harrifbu MYNO Indian tr Chipewas Puan, an 20 years manies h MYRT leurs or] on the co of the per

> AA ware rive NAB's Hudion's the Wel its fouth NACO province welt of

from fea navigation, viz, falt-fprings, coal, free-ftone, and clay. A valuable falt-fpring has been very lately difcovered, 8 miles from this river, and 50 from Marietta, called the *Big Spring*. Such a quantity of water flows, as to keep rooo gallons conftantly boiling. Ten gallons of this water will, as experiment inas proved, afford a quart of falt of fuperior quality to any made on the feacoaft.

MUSQUARIES Indians inhabit the fouthern waters of Lake Michigan, having 200 warriors.

MUSQUATONS, an Indian tribe inhabiting near Lake Michigan.

MUSKITTO Cove, in N. America, lies

in lat. 64. 55. 13. and in lon. 53. 3. 45. W. MUSQUITO River and Bay lie at a finall diffance north of Cape Canaverel, on the coaft of E. Florida. The banks of Mufquito river towards the continent abound in trees and plants common to Florida, with pleafant orange groves; whilf the narrow ftrips of land towards the fea, are moftly fand-hills.

MUSQUITONS, an Indian nation in the neighbourhood of the Piankefhaws and Outtagomies; which fee.

MYERSTOWN, a village of Dauphin co. Penniylvania, fituated on the N. fide of Tulpehockon creek, a few miles below the canal. It contains about 25 houfes, and is 32 miles east by north of Harrifburg, and 77 from Philadelphia.

MYNOMANIES, or *Minomanier*, an Indian tribe, who with the tribes of the Chipewas and Saukeys, live near Bay Puan, and could together furnish about 20 years ago, 550 warriors. The Minomanies have about 300 fighting men.

MYRTLE Island, one of the Chandeleurs or Myrtle islands, in Naffau Bay, on the coaft of Florida, on the west fide of the peninfula,

N

NAAMAN's Creek, a fmall fream which runs S. eafterly into Delaware-river, at Marcus' Hook.

NAB'S Bay, near the weftern limit of Hudion's Bay, known by the name of the Welcome Sca. Cape Efkimaux is its fouthern point or entrance.

NACO, a town of New-Spain, in the province of Honduras, 50 miles northweft of Valladolid,

NAHANT Point forms the N. E. point of Bolton harbour, in Malfachufetts; 9 miles E. N. E. of Bolton. N. lat, 42. 27. W. long. 70. 57. See Lynn Beach. NAHUNEBAG, a fmall illand in Ken.

NAHUNEBAG, a fmall island in Kennebeck river, 35 miles from the fea, fignifies, in the Indian language, the land where eels are taken.

NAIN, a Moravian fettlement, which was established in 1763, on Lehigh river, in Pennfylvania.

NAIN, a lettlement of the Moravians on the coaft of Labrador, near the entrance of Davis's Straits, being S. S. W. of Cape Farewell. It was begun under the protection of the British government, but is now deferted.

NAMASKET, a finall river which empties into Narraganfet Bay.

NANJEMY River, a flort creek which empties into the Patowmac in Charles county, Maryland, fouth-weltward of Port Tobacco river.

NANSEMOND, a county of Virginia, on the S. fide of James's river, and W. of Norfolk co. on the N. Carolina line. It is about 44 miles in length, and 24 in breadth, and contains 9010 inhabitants, including 3817 flaves.

NANSEMOND, a thort river of Virginia, which rifes in Great Difinal Swamp, and purfuing a N, then a N. E. direction, empties into James's river, a few miles W. of Elizabeth river. It is mavigable to Sleepy Hole, for veffels of 250 tons; to Suffolk, for those of 100 tons; and to Milner's, for those of 25 tons.

NANTASKET Road, may be confidered as the entrance into the channels of Bolton harbour; lies S. of the lighthoule, near Kainsford or Hofpital Ifland. A veffel may anchor here in from 7 to 5 fathems in fafety. Two huts are erected here with accommodations for thipwrecked feamen.

NANTIKOKE, a navigable river of the eaftern fhore of Maryland, empties into the Chefapeak Bay.

NANTIRORES, an Indian nation who formerly lived in Maryland, upon the above river. They first retired to the Sufqu-hannah, and then farther north. They were skilled in the art of poiloning; by which shocking art nearly their whole tribe was extirpated, as well as fome of their neighbours. These, with the Mohickons and Conoys, ao years ago inhabited Utfanango, Chagnet and Owegy, on the E. branch of the Suf-Y 3 quehannah.

fe to have , turthey n, poclons, lums, ruits. terate , and No pinion I than confivifh to nanent uthern ountry hward itude : ee, or Ocean, of this fferent Their 2. and elphia. mounitful in

whence iver of to the

bound-

Eye, a rritory. fluence v Pittfthe Obut 90 rt Harfohigh nd it is barges from its the lake From ne mile, o Lake ream of length, n falls. is well e State his river quality, ngs and remote

from

townships in Chefter co. Pennfylvania. NANTUCKET Island, belonging to the State of Maffachusetts, is fituated between lat. 41. 13. and 41. 22. 30. N. and between 69. 56. and 70. 13. 30. W. long. and is about 8 leagues fouthward of Cape Cod, and lies eaftward of the ifland of Martha's Vineyard. It is 15 miles in length, and 11 in breadth, in-cluding Sandy Point; but its general breadth is 31 miles. This is thought to be the ifland called *Nanticon* by ancient voyagers. There is but one bay of any note, and that is formed by a long fandy point, extending from the **B**. end of the ifland to the N. and W. (on which ftands a light house, which was erected by the State in 1784) and on the north fide of the ifland as far as Eel Point. This makes a fine road for thips, except with the wind at N. W. The harwhen there is a heavy fwell. bour has a bar of fand, on which are only 71 feet of water at ebb tide, but within it has 12 and 14 feet. The island conftitutes a county of its own name, and contains 4,620 inhabitants, and fends one reprefentative to the general court. There is a duck manufactory The here, and 10 spermaceti works. inhabitants are, for the most part, a robuft and enterprifing fet of people, The mostly feamen and mechanics. feamen are the most expert whale-men in the world. The whale fishery originated among the white inhabitants in the year 1690, in boats from the fhore. In 1715, they had 6 floops, 38 tons burden, and the fiftery produced 11eol. fterl. From 1772, to 1775, the fiftery employed 1 50 fail from 90 to 180 tons, upon the coaft of Guinea, Brazil, and the Weft-Indies; the produce of which amounted to 167,000l. fterl. The late war almost ruined this business. They have fince, however, revived it again, and purfue the whales even into the great Pacific Ocean. There is not here a fingle tree of natural growth; they have a place called The Woods, but it has been destitute of trees for these 60 years past. The island had formerly plenty of wood. The people, especially the females, are fondly attached to the illand, and few with to migrate to

uchannah. The two first could at that period furnish a soo warriors each; and the Conoys 30 warriors. NANTMILL, East and West, two alifts. Some part of the E. end or the ifland, known by the name of Squam, and fome few other places, are held as private farms. At prefent there are near 300 proprietors of the ifland. The proportional number of cattle, fheep, &c. put out to passure, and the quantity of ground to raile crops, are minutely regulated; and proper officers are appointed, who, in their books debit and credit the proprietors accordingly. In the month of June, each proprietor gives in to the clerks the number of his fheep, cattle, and horfes, that he may be charged with them in the books; and if the number be more than he is entitled to by his rights, he hires ground of his neighbours who have lefs. But, if the proprietors all together have more than their number, the overplus are either killed or transported from the island.

In the year 1659, when Thomas Macy removed with his family from Salisbury in Effex co. to the W. end of the ifland, with feveral other familics, there were nearly 3,000 Indians on the ifland, who were kind to ftrangers, and benevolent to each other, and lived happily until contaminated by the bad example of the whites, who introduced rum; and their number foon began to decrease. The whites had no material quarrel or difficulty with them. The natives fold their lands, and the whites went on purchafing; till, in fine, they have obtained the whole, except fome finall rights, which are ftill retained by the natives. A mortal fickness carried off 222 of them in 1764; and they are now reduced to 4 males, and 16 females.

NANTUCKET, (formerly Sherburne) a post-town, capital and port of entry in the above island. The exports in the year ending Sept. 30, 1794, amounted to 20,517 dollars. It is 60 miles S. E. of New-Bedford, 123 S. W. of Bofton, and 382 E. N. E. of Philadelphia.

NANTUCKET Shoal, a bank which ftretches out above 15 leagues in length, and 6 in breadth, to the S.E. from the ifland of its name.

NANTUXET Bay, New-Jerfey, is on the eaftern fide of Delaware Bay, oppofite Bombay Hook.

NARRAGANSET Bay, Rhode-Ifland, makes up from fouth to north between the the main l embofoms iflands, 1 Rhode If Patience, ands. T port, Wi Greenwic tuxet; th Patuxet 1 dence riv finaller ft bay. It lobiters i NARR bay betv chias, in Maine, 1 thence for the navig ber of fin thip-way inhabited A river (bay. NARR ted on th east of G fcot, 9 f from Ph NARR fage from ten Iflan before N junction thus call of the ci NARS miles br vis and ! Weft-In NASH containi 2,009 a valuable ty; but crected. NASI where a from I Lewifby NASI the Eli: Hon. J fituated and 3 r peninfu able m fupport

the main land on the eaft and weft. It embofoms many fruitful and beautiful iflands, the principal of which are Rhode Ifland, Canonicut, Prudence, Patience, Hope, Dyers, and Hog Iflands. The chief harbours are Newport, Wickford, Warren, Briftol, and Greenwich, befides Providence and Patuxet; the latter is near the mouth of Patuxet river, which falls into Providence river. Taunton river and many finaller fireams fall into this capacious bay. It affords fine fifh, oyfters and lobfters in great plenty.

peo-

kers.

ition-

of the

juam,

eld as

re are

theep,

Janti-

inute-

rs are

debit

ingly.

rietor

per of

at he

ooks;

he is

round

But,

niore

ifland.

homas

from

end of

milics,

s, and

d hap-

ad ex-

duced

gan to

aterial

whites

, they

ned by

carried

ley are

males.

burne)

ntry in

in the

ounted

s S.E.

Bofton,

which

length,

om the

is on

oppo-

Ifland.

etween

fome

The

The

NARRAGUAGUS Bay. A part of the bay between Goldíborough and Machias, in Walhington co. Diftrict of Maine, goes by this name. From thence for the space of 60 or 70 miles, the navigator finds, within a great number of fine islands, a fecure and pleasant hip-way. Many of these islands are inhabited and make a fine appearance. A river of the same name falls into the bay.

NARRAGUAGUS, a post-town, fituated on the above bay, 16 miles northeast of Goldsborough, 63 east of Penobfcot, 9 from Pleasant river, and 673 from Philadelphia.

NARROWS, The. The narrow paffage from fea, between Long and Staten Islands into the bay which spreads before New-York city, formed by the junction of Hudson and East rivers, is thus called. This strait is 9 miles south of the city of New-York.

NARROWS, The, a firait about 3 miles broad, between the islands of Nevis and St. Christopher's Islands, in the Weft-Indies.

NASH, a county of Halifax diffrict, containing 7,393 inhabitants, of whom 2,009 are flaves. There is a large and valuable body of iron-ore in this county; but only one bloomery has yet been crected.

NASH, Court-Houfe, in N. Carolina, where a post-office is kept 28 miles from Tarborough, and as far from Lewifburg.

NASHAUN, or Naw/hawn, one of the Elizabeth Ifles, the property of the Hon. James Bowdoin, Efq. of Bofton, fituated at the mouth of Buzzard's Bay, and 3 miles from the extremity of the peninfula of Barnftable co. Considerable numbers of fheep and cattle are fupported upon this ifland; and it has

0

become famous for its excellent woo' and cheefe. Here Capt. Bartholomew Gofnold landed in 1602, and took up his abode for fome time.

NASHUA, *River*, is a confiderable ftream in Worcefter co. Maffachufetts, and has rich intervale lands on its banks. It enters Merrimack river at Dunftable. Its courfe is north-north-eaft.

NASHVILLE, the chief town of Mero District in the State of Tennessie, is pleafantly fituated in Davidion's co. on the fouth bank of Cumberland river, where it is 200 yards broad. It was named after Brig. Gen. Francis Nafh, who fell on the 4th of Oct. 1777, in the battle of Germantown. It is regularly laid out, and contains 75 houfes, a courthouse, an academy, and a church for Prefbyterians, and one for Methodifts. It is the feat of the courts held femi-annually for the district of Mero, and of the courts of pleas and guarter feffione for Davidson co. It is 185 miles weft of Knoxville, 66 from Big Salt Lick garrifon, 190 S. by W. of Lexington in Kentucky, 635 W. by S. of Richmond in Virginia, and 1015 W. S. W. of Philadelphia. N. lat. 36. W. long. 87.

NASKEAG Point, in Lincoln co. Difirict of Maine, is the eastern point of Penoblcot Bay.

NASPATUCKET River. See Wanafpatucket.

NASQUIROU *River*, on the Labrador coaft, is to the weftward of Elquimaux river.

NASSAS River. See St. Andre. NASSU Bay, or Spirito Santo, is a large bay on the coalt of West-Florida, about 70 miles from north to fouth. It has 4 iflands on a line for 50 miles from S. W. to Na E. with openings between them a mile or two wide. The most northerly is called Myrtle Island, between which, and the continent, is the entrance of the bay. The bay is 19 miles broad from Myrtle Ifland to a row of islands running parallel with the main land, and another bay between them ftretching 50 or 60 miles to the fouth, as far as one of the fmaller mouths of the Miffifippi. See Naffau Road.

NASSAU Bay, an extensive bay of the ocean, on the S. coatt of Terra del Fuego island, at the S. extremity of S. America. It is to the E. of Falle Cape Horn, which forms the western limit of Y 4 the

the bay ; Cape Horn being the S. point [deleurs, by the French, from the candles, of the fouthernmost of the Hermits Isands, a groupe of iflands which lie off the coast opposite to this bay. This bay is large and open, well theltered from the tempefts of the ocean. It is capable of holding a fleet of thips, and though there are fmall iflands near its entrance, all the dangers are visible, and thips may fail freely between them, or on each fide of them. See Mistaken Cape. NASSAU Cape, on the coaft of Surinam, or N. E. coaft of S. America, is to the N. N. W. of Effequibo gulf, and the E. point of the entrance into the river Pumaron. It is in about lat. 7.40. N. and long. 59. 30. W.

NASSAU Capt, on the N. fhore of Terra Firma, S. America.

NASSAU, a imall town in Dauphin co. Pennfylvania. It contains a German church, and about 35 houfes. It is alfo called Kempflown.

NASSAU Mand, at the mouth of Byram river, in Long-Ifland Sound.

NASSAU Road, on the coalt of Weft-Florida, liesW. of Mobile Bay, 5 leagues to the northward of Ship Island, and within the north end of the Chandeleurs or Myrtle Iflands. It is one of the best roads for large vessels on the whole coaft of Florida. _It affords good flielter from winds that blow on thore, has no bar, and is eafy of accels. Veffels, however, mult not go within } of a mile of the infide of the ifland, it being thoal near that diftance from the fhore. Veffels may go round the north end of it from the fea in 51 and 6 fathoms at half a mile from the fhore, and afterwards must keep in 44 and 5 fathoms till the north point bears N. N. E. about a miles, where they can anchor in 4 fathoms good holding ground, fheltered from easterly and foutherly winds : this is necefiary for all veffels frequenting the coaft of Florida, as eafterly winds are very frequent. There is fresh water to be got any where on the Chandeleurs by digging; and there is a kind of well at the north end, near an old hut. There is no wood to be found here but drift wood, of which there is great plenty along thore. Naffau Road was first difcovered by Dr. Daniel Cox, of New-Jerfey, who named it fo in ho nour of the reigning prince, William III. He also gave the name of Myrtle Islands to those afterwards called ChanNAT

made of the Myrtle wax, with which, thefe islands abound.

NASSAU River, on the coaft of Eaft Florida, has a bar generally about 8 feet water, but is fubject to frifting. The tides are about 7 feet at low fpring tides. An E. S. E. moon makes high water here, as alfoin most places along the coaft.

NASSAU, the chief town of Providence Island, one of the Bahamas, and the feat of government. N. lat. 25. 3. It is the only port of entry except at Turk's Ifland. See Bahamas.

NASTLA, a town of Mexico. Sce Angelos.

NATA, a town and bay in the province of Terra Firma, S. America. The bay of Nata lies on the S. coaft of the Ifthmus of Darien, and on the North Pacific Ocean. From hence and the adjacent parts, provisions are fent for the fupply of the inhabitants of Panama, which city is 67 miles N. E. of Nata. The bay is spacious and deep, but is not used by ships but in cases of necessity, as they are liable to be embayed by the winds that blow frequently at E. upon the fhore. The bay extends to the ifland Iguenas. N. lat. 8. 12. W. long. 81. 12.

NATA POINT, or Chama, or Chaumu Cape, is at the W. point of the gulf. of Panama, from whence the coaft trends W. to Haguera Point 7 leagues. All thips bound to the N. W. and to Acapulco make this point. It is alfo called the S. point of the bay, which lies within on the W. fide of this great Gulf of Panama.

NATACHQUOIN River, a large river of the coaft of Labrador, in N. America, to the weftward of Nalquirou river, under Mount Joli, where it forms a foutherly cape in lat. 50. 25. N. and long. 60. 45. W. The little Natachquoin is to the W. S. W. of this.

NATAL, a cape and town, on the S. thore of the Rio Grande, on the N. E. coaft of Brazil in S. America, is to the S. W. of the four fquare fhoal, at the mouth of the entrance of that river, which contains fome dangerous rocks. On this point is the Caftle of the Three Kings, or Fortaleza des Tres Magos. The town of Natal is 3 leagues from the caffle before which is good anchorage for thips, in from 4 to 5 fathoms, and well fecured from winds. NATCHEZ,

NATCH Western T NATCH dians who

try on the Rofalie is they poffe now rema by which called. rofe upon French 4 1730. dians, an deracy w Louifian: NATC in Louis Red river had a ve called N on the miles fre leagues Rouge v NATI dlefex c Charles and 10 in the I place of tormed 1670, 1 cants. Court contain dians. howeve porated and int contain NAT Nootka N. An taract, northw long. f NAT County NAL habitin and Su NAT branch cut. A works branch NA

100, 01

NATCHEZ, or Natches. See Georgia | California, which feparates it from the

Weftern Territory. NATCHEZ, a powerful nation of In-dians who formerly inhabited the country on the E. fide of the Miffifippi, Fort Rofalie is fituated in the country which they poffelled, in lat. 31, 40. Nothing now remains of this nation but the name, by which the country continues to be called. The Creeks or Mulcogulges role upon the ruins of this nation. The French completed their destruction in 1730. The Natchez or Sun Set In-dians, are a part of the Creek confedederacy which they joined after they left Louifiana.

NATCHITOCHES. A tract of country in Louisiana, on the river Rouge, or Red river, bears this name. The French had a very confiderable post on this river called Natchitoches. It was a frontier on the Spanish fettlements, being 20 miles from the fort of Adayes, and 70 leagues from the confluence of the Rouge with the Miffifippi.

NATICK, an ancient township in Middlefex co. Maffachufetts, fituated upon Charles river, 18 miles S. W. of Bofton. and 10 N. W. of Dedham. Its name in the Indian language fignifies " The place of hills." The famous Mr. Eliot formed a religious fociety here; and in 1670, there were 50 Indian communicants. At his motion, the General Court granted the land in this town, containing about 6000 acres, to the Indians. Very few of their descendants, however, now remain. It was incorporated into an English district in 1761, and into a township in 1781; and now contains 615 inhabitants.

NATTENAT, an Indian village on Nootka Sound, on the N. W. coaft of N. America. It has a remarkable cataract, or water-fall, a few miles to the northward of it. N. lat. 48. 40. W. long. from Greenwich 124. 6.

NATURAL Bridge. See Rockbridge County, Virginia.

NAUDOWESIES, an Indian nation inhabiting lands between Lakes Michigan and Superior. Warriors, 500.

NAUGATUCK River, a north-eaftern branch of Houlatonic tiver in Connecticut. A great number of mills and iron. works are upon this fiream and its branches.

NAVARRE, a province of New-Mexico, on the N. E. fide of the Gulf of NAV

eninfula of California, on the S. W.

MAVAGIA, a fmall ifland in the Windward Paffage, or ftrait between Cuba, and Hifpaniola in the Weft-Indies Thither the inhabitants of Jamaica come in boats to kill guaras, an amphibious creature that breeds plentifully at the roots of old trees. They are in the fhape of a lizard, with feales, and fome are 3 feet in length, Their flefh is firm and white, and faid by feamen to make good broth.

NAVAZA, a fmall barren ifland in the Weft-Indies, not very high, is fteep all round, and lies in lat. 18. 20. N. It is. 21 leagues W. S. W. I W. of the E. end of Jamaica, and 11 leagues from Tiburon, in the ifland of St. Domingo.

NAVESINK Harbour, on the fea-coaft of Monmouth, co New-Jerfey, lies in. lat. 40. 24. N. having Jumping Point. on the north, and is 24 miles S. of the N. end of Sandy Hook Ifland ; and its mouth is 5 miles from the town of Shrewfbury. The fmall river of its name falls into it from the W. and rifes in the fame county. Navefink Hills extend N. W. from the harbour on the Atlantic Ocean, to Rariton Bay ; and are the first land difcovered by mariners when they arrive on the coaft. They are 600 feet above the level of the fea. and may be feen 20 leagues off.

NAVIDAD, a town of Mechoacan a province of Mexico, with a harbour on the N. Pacific Ocean, is 156 miles W. of Mexico city. N. lat. 18. 51. W. long. 111. 10.

NAVIRES, or Cas de Vavires Bay, in the ifland of Martinico in the Weft-Indies.

NAVY, a township in Orleans co. in Vermont.

NAVY Hall, in Lower Canada, ftands on the fouth fide of Lake Ontario, at the head and weft fide of Niagara river, which last separates it from Fort Niagara, on the E. fide, in the State of New York. It is 20 miles N. by W. of Fort Erie, and 23 S. E. by S. of York.

NAVY Island lies in the middle of Niagara river, whole waters feparate it from Fort Sluther, on the east bank of the river, and the fame waters divide it from Grand Ifland, on the S. and S. E. It is about one mile long, and one broad, and is about 13 miles N. by E. of Navy Hall.

NAZARETH,

8 feet The ides. water coaft. roviand 5.3. pt at See ro-The f the North ie adw the

ndles

which

Eaft-

Nata. is not fity, y the upon

o the

long.

lama.

Shau-: gulf coaft gues. nd to s alfo which great

: tiver

meri-

river,

ms a

and

itach-

he S.

I. E.

to the

at the

river,

ocks.

Chree

agos.

m the

plage

, and

HEZ,

346

NAZARETH, a beautiful town in | Northampton co. Pennfylvania, inhabited by Moravians, or United Brethren. It is fatuated 10 miles north of Beth-Schem, and 63 N. by W. of Philadelphia. It is a tract of good land, containing about 5,000 acres, purchased by the Rev. G. Whitfield, in 1740, and fold z years after to the brethren. They were however obliged to leave this place the fame year, where it feems they had made fome fettlements before. Bishop Nitchman arrived from Europe this year (1740) with a company of brethren and fifters, and purchased and fettled upon the fpot which is now called Bethlchem. The town of Nazareth ftands about the centre of the manor, on a fmall creek, which lofes itfelf in the earth about a mile and a half E. of the town. It was regularly laid out in 1772, and confifts of a principal ftreets which crofs each other, at right angles, and form a fquare in the middle, of 340 by 200 feet. The largest building is a fone house, erected in 1755, named Na-zareth Hall, 98 feet by 46 in length, and 54 in heighth. The lower floor is formed into a fpacious hall for public worthip, the upper part of the houfe is fitted up for a boarding ichool, where youth, from different parts, are under the infpection of the minister of the place and feveral tutors, and are instructed in the English, German, French and Latin languages; in history, geography, bookkeeping, mathematics, music, drawing, and other sciences. The front of the house faces a large square open to the fouth, adjoining a fine piece of meadow ground, and commands a most delight-ful prospect. Another elegant building on the E. of Nazareth Hall is inhabited by the fingle fifters, who have the fame regulations and way of living as those at Bethlehem. Befides their principal manufactory for spinning and twifting cotton, they have lately begun to draw wax tapers. At the fouth-west corner of the aforefaid square, in the middle of the rown, is the fingle brethren's houfe, and on the E. S. E. corner a flore. On the southernmost end of the street is a good tavern. The dwelling-houses are, a few excepted, built of lime-ftone, one or two ftories high, inhabited by tradefmen and mechanics, mottly of German extraction. The inhabitants are fuppli ed with water conveyed to them by pipes | Charles' river. The lower fall of the

NEE

from a fine fpring near the town. The fituation of the town, and the falubrious. air of the adjacent country, render this a very agreeable place. The numberof inhabitants in the town and the farms belonging to it, (Shoeneck included) conftituting one congregation, and meeting for divine fervice on Lord's days and holidays, at Nazareth Hall, was, in the year 1788, about 450.

NECESSITY, Fort, in Virginia, is fituated in the Great Meadow, within 4miles of the W. bounds of Maryland, and on the north fide of the head water of Red Stone Creek, which empties from the E, into the Monongahela, in N. lat. 39. 43. about 26 miles from the fpot where this fort was crected. It is 238 miles E. by N. of Alexandria, and 258 north-weft of Frederick burg. This fpot will be forever famous in the hiftory of America, as one of the first icenes of Gen. WASHINGTON's abilities as a commander. In 1753, it was only a small unfinished entrenchment, when Mr. Washington, then a colonel, in the 22d year of his age, was fent with 300 men towards the Ohio. An engagement with the enemy enfued, and the French were defeated. M. de Villier, the French commander, fent down 900 men befides Indians, to attack the Virginians. Their brave leader, however, made fuch an able defence with his handful of men in this unfinished fort, as to confirain the French officer to grant him honourable terms of capitulation.

NEDDICK, Cape, or Neddock, lies between York river and Well's Bay on the coaft of York co. Diffrict of Maine.

NEDDICK River, Cape, in the above county, is navigable about a mile from the fea, and at full tide only for veffels of any confiderable burden, it having a bar of fand at its mouth, and at an hour before and after low water, this rivulet is generally to fhallow as to be fordable within a few rods of the fea.

NEEDHAM's Point, on the S. W. angle of the ifland of Barbadoes in the Weft-Indies, is to the S. eafterly from Bridgetown, having a fort upon it called Charles Fort.

NEEDHAM, a township in Norfolk co. Maffachufetts, 11 miles from Bofton. It is about 9 miles in length and 5 in breadth, and is almost encompassed by river. river, at and Nee direct de Middlefe incorpor inhabita has latel NEEF illands, of Atoo tants. 21. 50. Sometin beow. NEG. Caribbe is low fhoals a gada, f by high weft of crabs. 1 NEG end of t Negril moft wi maica. NEG fouth-v NEG zil, is 3 Grande NEG ary of NEC the nc Ameri great in the about NEI Chief : NEI W. fh the ma 2 50 m and 6c the po pany. long. are fai long. water nutes - NEI of Ha fon's chann of wh

eiver, at the bridge between Newton and Needham is about 20 feet in its direct defcent. Here the river divides Middlefex from Norfolk co. It was incorporated in 1711, and contains 1130 inhabitants. A flitting and rolling mill has lately been crected here.

NEEHEEHEOU, one of the Sandwich iflands, about 5 leagues to the weftward of Atooi, and has about 10,000 inhabitants. Its place of anchorage is in lat. 21. 50. N. and long. 160. 15. W. Sometimes it is called *Nebeegw* or *Oneebeow*.

NEGADA, or *Anegada*, one of the Caribbee iflands in the Weft-Indies. It is low and defart, encompafied with shoals and fand-banks. It is called Negada, from its being moftly overflown by high tides. It is 50 miles northweft of Anguilla, and abounds with crabs. N. lat. 18. 6. W. long. 63. 5.

NEGRIL Harbour, North, at the W. end of the ifland of Jamaica, has North Negril Point on the north, which is the most westerly point of the Island of Jamaica. N. lat. 18.45. W. long. 78.

NEGRO Cape and Harbour, at the fouth-weft extremity of Nova-Scotia.

NEGRO Point, on the E. coaft of Brazil, is 3 leagues at S. S. E. from the Rio Grande, and 14 from Cape St. Rocque.

NEGRO River is the western boundary of Guiana in S. America.

NEGRO Fort, in Amazonia, ftands on the north fide of Amazon river in S. America, just below the junction of its great branches the Purus and Negro, in the 4th degree of north latitude, and about the 6oth of W. longitude.

NELSON, a county of Kentucky. Chief town, Bairdftown.

NELSON'S Fort, a fettlement on the W. fhore of Hudfon's Bay, fituated at the mouth of a river of the fame name, 250 miles fouth-eaft of Churchill Fort, and 600 north-weft of Ruper's Fort, in the poffeffion of the Hudfon's Bay Company. It is in lat. 57. 12. north, and long. 92. 42. W. The fhoals fo called are faid to be in lat. 57. 35. north, and long. 92. 12. weft, and to have high water at full and change days at 20 minutes paft 8 o'clock.

NELSON'S *River*, is the N. W. branch of Hayes river, on the W. fhore of Hudfon's Bay, which is feparated into two channels by Hayes Island, at the mouth of which Nelfon's Fort is fituated. NENAWEWHCK Indians inhabit near Severn river, fouth of Severn lake.

NEOMINAS River, on the coaft of Peru, is 12 or 14 leagues to the N. W. of Bonaventura river. It is a large river, and empties into the ocean by a mouths. The flore is low, but there is no landing upon it, as it is inhabited only by favages whom it would not be very fafe to truft, as their peaceable or hoffile difpofition towards Europeans cannot be eafily known. The coaft, though in the Wight of the moft flourithing Spanifa colonies, remains unfrequented and wild. Palmas Ifland is oppofite to this river, being low land, and having feveral floals about it; and from hence to Cape Corientes is 20 leagues to the N. W. The river and ifland are in lat. about 4. 30. N.

NEPEAN Ifland, a fmall ifland of the South Pacific Ocean, opposite to Port Hunter on the fouth coaft of Norfolk Ifland.

NEPEAN Sound, an extensive water on the north-weft coalt of N. America, having a number of islands in it, in fome charts called Princes Royal Islands. It opens eastward from Cape St. James, the iouthernmost point of Washington's or Queen Charlotte's Islands. Fitzbugh's Sound lies between it and Queen Charlotte's Sound to the fouthward.

NEPONSET, a river of Maffachufetts, originates chiefly from Muddy and Punkapog Ponds, in Stoughton, and Mafhapog Pond, in Sharon, and after paffing over falls fufficient to carry mills, unites with other finall freams, and forms a very conftant fupply of water, for the many mills fituated on the river below, until it meets the tide in Milton, from whence it is navigable for vcficls of 150 tons burden to Bofton Bay, diftant about 4 miles. There are 6 papermills, befides many others of different kinds on this finall river.

NERUKA, a port in the ifland of Cape Breton, where the French had a fettlement.

NESBIT'S Harbour, on the coaft of New Britain, in N. America, where the Moravians formed a fettlement in 1752; of the first party, fome were killed and others were driven away. In 1764, they made another attempt under the protection of the British government, and were well received by the Efquimaux, and by the last account the mission fucceeded.

NESCOPECK

s in d by the

The

rious

this

mber

arms

ded)

neet-

(and

a the

nin 4

land,

vater

1, in

n the

It is

and

This

hif-

firft

was

nent,

onel.

with

and

Vil-

lown

c the

low-

with

ifhed

ficer

:api-

s be-

V OD

line.

bove

from

ffels

ng a

hour

rulet

lable

an-

the

from

alled

folk

fton.

iver,

is fi-

NESCOPECK River falls into the N. E. branch of Sulquehannah river, near the mouth of the creek of that name, in Northumberland co. Pennfylvania, and oppolite to the town of Berwick, 160 nules N. W. of Philadelphia, and in lat. 47. 3. An Indian town, called Nelcopeck, formerly flood near the feite of Berwick.

NETHERLANDS, New, is the tract now included in the States of New-York, New-Jerfey, and part of Delaware and Pennfylvania, and was thus named by the Dutch. It paffed first by conquest and afterwards by treaty into the hands of the English.

NE ULTRA, or Sir Thomas Roe's Welcome, a narrow strait between lat. 62. and 63, in New North Wales, in the arctic regions of America.

NEUS, a river of N. Carolina, which empties into Pamlico Sound below the town of Newbern. It is navigable for fea veffels 12 miles above Newbern; for feows 50 miles, and for fmall boats 200 miles.

NEUSTRA Sennora, Baia de, or Our Lady's Bay, on the coast of Chili, on the S. Pacific Ocean, in S. America, is 30 leagues from Copiapa, and ao S. S. W. of Cape George. It is indifferent riding in this bay, as the N W. winds blow right in, and the gufts from the mountains are very dangerous.

NEVERSING Creek, a ftream in the Hardenberg Patent, in Ulfter co. New-York. On an ifland in this creek Mr. Baker having cut down a hollow beech tree, in March, 1790, found near two barrels full of chimney fwallows in the eavity of the tree. They were in a torpid ftate, but fome of them being placed near a fire, were pleafantly reanimated by the warmth, and took wing with their ufual agility.

NEVIL Bay, on the weft fhore of Hudion's bay, is nearly due W. a little northerly from Cape Digges and Manfel ifland at the entrance into the bay. north lat. 6a. 30. weft long. 95.

NEV15, an island lefs than a league fouth-casterly of the peninfula of St. Christopher's, one of the Caribbees. This beautiful little spot is nothing more than a single mountain rising like a cone in an easy ascent from the sea; the circumference of its base not exceeding 8 British leagues. This island was doubtlefs produced by some volcanic cruption,

for there is a hollow crater near the fummit still visible; which contains a hot fpring, ftrongly impregnated with fulphur, and fulphur is frequently found in fubftance, in the neighbouring gullies and cavities of the earth. The iffand is well watered, and the land in general, fertile. Four thousand acres of canes are annually cut, which produce an equal number of hogheads of fugar. The ifland, fmall as it is, is divided into 5 parifhes. It has one town, Charleftorun, which is a port of entry, and the feat of government; where is also a fort called Charles Fort. There were two other fhipping places, viz. Indian Caffle and New-Caftle. Nevis contains 600 whites and 10,000 blacks. It was first fettled by the English in 1628, under the protection of Sir Thomas Warner. It is faid, that, about the year 1640 the ifland contained 4,000 whites, and fome writers fay that before the year 1688 it had 30,000 inhabitants. The invation of the French about that time, and fome epidemic diforders ftrangely diminished the number. Charleftown, the capital lies in lat. 17. 15. N. and long. 62. 35. W. There are feveral rocks and fhoals on the coaft, particularly on the fouthweft fide, but thips ride between them in tolerable fafety, the hurrican featons excepted, when they are obliged to put off to fea, and run into Antigua if poffible.

NEW-ALBION, a name given to a country of indefinite limits, on the weftern coaft of N. America, lying north of *Caiifornia*.

NEW, a river of N. Carolina, which empties, after a fhort course, into the ocean, through New River Inlet. Its mouth is wide and shoal. It abounds with mullet during the winter feason.

NEW-ANDALUSIA, a province of Terra Firma, S. America, lying on the coaft of the N. Sea, opposite to the Leeward Islands; bounded by the river Oroonoko on the weft. This country is called Paria by fome writers. Its chief town is St. Thomas. Some gold mines were difcovered here in 1785.

NEW-ANDOVER, a settlement in York co. District of Maine, which contains, including Hiram and Potterfield, 214 inhabitants.

New-ANTICARIA, a town of New-Spain, 34 leagues northward of Acapulco.

NEW-ANTIGUERA, an epifcopal city

of New-S aca, erec III. 154 fupporter NEWA in Verme NEW formed h Hackenf is fepara river op Bergen alfo, wit form a 1 North ri fo comm the mou in a S. b fide of S from N Point, 1 NEW and cap ly fitua Paffaich Bay, as city. town, its cyde shoe ma rage nu year, i The to Elizab There the lar the kir an Epi gaol. lifhed | be a u in Ora there a ries of in Net £1000 men li fettled Conne NE Delaw and V of Ne Wiln NE the I river Onta and f of New-Spain, in the province of Guazaca, crected into a bishoprick by Paul III. 1547. It has a noble cathedral, supported by marble pillars.

NEWARK, a township in Effex co. in Vermont.

NEWARK Bay, in New-Jerfey, is formed by the confluence of Paffaick and Hackenfack rivers from the north, and is feparated from that part of North river oppofite to New-York eity, by Bergen Neck on the E. which neck, alfo, with Staten Ifland on the S. of it, form a narrow channel from the bay to North river eaftward. Newark Bay alfo communicates with Rariton Bay, at the mouth of Rariton river, by a channel in a S. by W. direction along the weftern fide of Staten Ifland. The water paffage from New-York to Elizabeth Town Point, 15 miles, is through this bay.

NEWARK, a post-town of New-Jerfey and capital of Effex county, is pleafantly fituated at a fmall diftance welt of Paffaick river, near its mouth in Newark Bay, and nine miles W. of New-York city. It is a handfome and flourishing town, celebrated for the excellence of its cyder, and is the feat of the largest shoe manufacture in the State : the average number made daily throughout the year, is estimated at about 200 pairs. The town is of much the fame fize as Elizabeth-Town, and is 6 miles N. of it. There is a Prefbyterian church of ftone, the largest and most elegant building of the kind in the State. Befides these is an Epifcopal church, a court-houfe and gaol. The academy which was eftablished here in June, 1792, promifes to be a ufeful inftitution. In Newark and in Orange which joins it on the N. W. there are 9 tanneries, and valuable quarries of stone for building. The quarries in Newark, would rent, it is faid, for £1000 a year, and the number of workmen limited. This town was originally fettled by emigrants from Branford, Connecticut, as long ago as 1662.

NEWARK, a village in Newcaffle co. Delaware, fituated between Christiana and White Clay Creeks, 9 miles welt of New-Caftle, and 10 fouth-wefterly of Wilmington.

NEWARK, a town lately laid out by the Britifli in Upper Canada, on the river which connects lake Erie and Ontario, directly opposite Niagara town and fort.

NEW-ATHENS, or Tioga Paint, ftands on the poft-road from Cooperflown to Williamfburg, in Luzenne co. Pennfylvania, on the point of land formed by the confluence of 1 ioga rives with the E. branch of Sufquehannah river, in lat. 41. 54. and long. 76. 32. W. and about 3 miles S. of the New-York line 5 20 miles S. E. by E. of Newtown in New-York, 14 S. W. of Owego, and 116 S. W. of Cooperflown.

NEW-BARBADOES, a township in Bergen co. New-Jerfey.

NEW-BEDFORD, a post-town and port of entry in Briftol co. Maffachuletts, fituated on a fmall bay which fet up north from Buzzard's Bay, 58 miles S. of Bofton. The township was incorporated in 1787, and is 13 miles in length and 4 in breadth ; bounded E by Rochefler, W. by Dartmouth, of which it was originally a part, and S. by Buzzard's Bay. Acebufnutt was the Indian name of New Bedford ; and the fmall river of that name, difcovered by Goinold in 1602, runs from north to fouth through the township, and divides the villages of Oxford and Fairhaven from Bedford village. A company was incorporated in 1796, for building a bridge across this river. From the head to the mouth of the river is 7 or 8 miles. Fairhaven and Bedford villages are a mile apart, and a ferry constantly attended is ettablished between them. The harbour 'is very fafe, in fome places 17 of 18 feet of water ; and veffels of a or 400 tons lie at the wharves. Its mouth is formed by Clark's Neck on the W. fide, and Sconticutt Point on the other. An island between these points renders the entrance narrow; in 5 fathoms water. High water at full and change of the moon 37 minutes after 7 o'clock. Dartmouth is the fafeft-place to lie at with an eafterly wind : but at New-Bedford you will lie fate at the wharves. The river has plenty of fmall fifh and a fhort way from its mouth they catch cod, bais, black fifh, fheep's head, &c. The damage done by the British to this town in 1778 amounted to the value of £97,000. It is now in a flourishing fate. In the township are a post-office, a printing office, 3 meetings for Friends, and 3 for Congregationalists, and 3313 inhabitants. The exports to the different States and to the Welt-Indies for one year, ending Sept. 30, 1794, amount-

349.

ed

city

r the

ins a

with

found

gul-

e ifi-

n ge-

es of

oduce

ugar.

d into

arles-

id the

a fort

two

Caftle

600

s firft

ander

urner.

o the

fome

88 it

afion

fome

ifhed

pital

. 35.

hoals

outh-

them

atons

utoff

lible.

to a

weft-

th of

hich

) the

unds

e of

1 the

Lee-

river

ntry

Its

gold

in

con-

ield,

lew-

n.

Its

ed to \$2,085 dollars. It is 357 miles [delphia. N. lat. 35. 20. W. long. N. E. by E. of Philadelphia. 77. 25.

350

NEWBERN, one of the eaftern maritime districts of N. Carolina, bounded E. and S. E. by the Atlantic, S. W. by Wilmington, W. by Fayette, N. W. by Hillfborough, N. by Hallifax, and N. E. by Edenton diffrict. It comprehends the counties of Carteret, Jones, Craven, Beaufort, Hyde, Pitt, Wayne, Glafgow, Lenoir, and Johnston; and contains 55,540 inhabitants, including 15,900 flaves.

NEWBERN, the capital of the above district, is a post-town and port of entry, fituated in Craven co. on a flat, fandy, point of land, formed by the confluence of the rivers Neus on the N. and Trent on the fouth. Opposite to the town, the Neus is about a mile and a half, and the Trent three-quarters of a mile wide. Newbern is the largeft town in the State, contains about 400 houfes, all built of wood except the palace, the church, the gaol, and two dwelling houses, which are of brick. The palace was erected by the province before the revolution, and was formerly the refidence of the governors. It is large and elegant, two fories high, with two wings for offices, a little advanced in front towards the town; these wings are connected with the principal building by a circular arcade. It is much out of repair; and the only use to which this once handsome and well furnished building is now applied, is for schools. One of the halls is used for a school, and another for a dancing room. The arms of the king of Great Britain ftill appear in a pediment in front of the building. The Episcopalian church is a small brick building with a bell. It is the only house for public worship in the place. The court house is raised on brick arches, fo as to render the lower part a convenient market place; but the principal marketing is done with the people in their canoes and boats at the river fide. In September, 1791, near one third of this town was confumed by fire. It carries on a confiderable trade to the Weft Indies and the different States in tar, pitch, turpentine, lumber, corn, &c. The exports in 1794 amounted to 69,615 dollars: . It is 149 miles from Raleigh, 99 S. W. of Edenton, 103 N. E. by Lof Wilmington, 238 S. of Petersburgh in Virginia, and 501 S. W. of Phila-

NEW-BISCAY, a province in the audience of Galicia, in Old-Mexico or New-Spain. It is faid to be 100 leagues from E. to W. and 120 from north to fouth. It is a' well watered and fertile country. Many of the inhabitants are rich, not only in corn, cattle, &c. but alfo in filver mines, and fome of lead.

NEW BOSTON, a township in Hillsbo-rough co. New-Hampshire, about 70 miles wefterly of Portimouth. It was incorporated in 1763, and contains 1202 inhabitants.

NEW-BRAINTREE, a township in Worcefter co. Maffachufetts, confifting of about 13,000 acres of land, taken from Braintree, Brookfield, and Hardwick, and was incorporated in 1751. It con-tains 940 inhabitants, moftly farmers, and lies 19 miles north-weft of Worcef-ter, and 66 north-weft of Bofton.

NEW-BRITAIN. See America, La-brador, and Britain New. NEW-BRITAIN, atownship in Buck's

co. Pennfylvania.

NEW BRUNSWICK, in the State of New-York is fituated on Paltz Kill, about 8 miles S. W. of New Paltz, and 69 north-westerly of New-York city.

NEW-BRUNSWICK, in Middlefex co: New Jerfey. See Brunfwick.

NEW-BRUNSWICK, a Britifh province in N. America, the north-weft part of Nova-Scotia; bounded west by the District of Maine, from which it is separated by the river St. Croix, and a line drawn due north from its fource to the Canada line; north by the fouthern boundary of the province of Lower Canada, until it touches the fea-fhore at the weftern extremity of Chaleur Bay; then following the various windings of the fea-fhore to the Bay of Verte, in the ftraits of Northumberland; on the S.E. it is divided from Nova-Scotia by the feveral windings of the Miffiquash river, from its confluence with Beau Bafon (at the head of Chegnecto channel) to its main fource; and from thence by a due eatt line to the Bay of Verte. The northern fhores of the Bay of Fundy conftitute the remainder of the fouthern boundary. All iflands included in the above limits belong to this province. According to Arrowsmith's map, it extends from lat. 45. 7. to 47. 15. N. and from long. 64. to 69. 50.W. It is about 260 260 miles chief tow of the rive ne's, the miles up t a few mile rivers are codiac, N Nipifigui is indent commodi Chaleur, is feparat a narrow wide; B so leagu to Bay, Paffamad the Diftr of this b ral gent thire, v At a ver tempted failed. bay the ple from merous Grand J 30 miles in fome Canada NEW co. New fon's ri Windfo of whom The co built, weft ba of New ing, 7 Gofhen fie. It houfes ated on The co ed, and of con load at veffels and thi NEN diffrið 9,342 flaves. miles Laure

NEW

260 miles long and 170 broad. The chief towns are St. John's, at the mouth of the river of the fame name; St. Anne's, the prefent feat of government, 80 miles up the river ; and Frederickftown, a few miles above St. Anne's. The chief rivers are St. John's, Merrimichi, Petitcodiac, Memramcook, Riftigouche, and Nipifiguit. The coaft of this province is indented with numerous bays and commodious harbours; the chief are Chaleur, Merrimichi, Verte, which laft is feparated from the Bay of Fundy by a narrow ifthmus of about 18 miles wide; Bay of Fundy, which extends 50 leagues into the country ; Chegnecto Bay, at the head of the Bay of Fundy; Paffamaquoddy Bay, bordering upon the Diffrict of Maine. At the entrance of this bay is an ifland granted to feveral gentlemen in Liverpool, in Lancathire, who named it Campo Bello. At a very confiderable expense they attempted to form a lettlement here, but failed. On feveral other islands in this bay there are fettlements made by people from Maflachufetts. Here are numerous lakes, as yet without names. Grand Lake, near St. John's river, is 30 miles long and 8 or 10 broad; and in fome places 40 fathoms deep. See Canada, St. Jobn's river, &c.

NEWBURGH, a township in Ulker co. New-York bounded eafterly by Hudfon's river, and foutherly by New-Windfor, and contains 236 5 inhabitants; of whom 373 are electors, and 57 flaves. The compact part of the town is neatly built, and pleafantly fituated on the weft bank of the Hudion, 66 miles north of New-York, opposite Fish-Kill Landing, 7 miles from Fifh-Kill, 13 from Gofhen, and 14 fouth from Poughkeepfie. It confifts of between 50 and 60 houses and a Presbyterian church, fituated on a gentle afcent from the river. The country northward is well cultivated, and affords a rich prospect. Veffels of confiderable burden may load and unload at the wharves, and a number of veffels are built annually at this buly and thriving place.

NEWBURY, a county of Ninety-Six diffrict, S. Carolina, which contains 9,342 inhabitants, of whom 1,144 are flaves. Newbury court-houfe is 45 miles from Columbia, and 32 from Laurens court-houfe.

NEWBURY, a township in York co. Pennfylvania.

NEWBURY, the expital of Orang co. Vermont, pleafantly fituated on the welt fide of Connecticut river, op polite to Haverhill, in Grafton co. New-Ham thire, and from which it is s miles diftant. It contains about 50 houses, a gaol, a court-house, and a handsome church for Congregationalifts with a steeple, which was the first crected in Vermont. The court-house stands on an eminence, and commands a pleating prospect of what is called the Great Oxbow of Connecticut river, where are the rich intervale lands called the Little Coos. Here a remarkable fpring was discovered, about 20 years fince, which dries up once in two or three years. Ic has a ftrong fmell of fulphur, and throws up continually a peculiar kind of white fand : and a thick yellow fcum rifes upon the water when fettled. This is the more noticeable as the water of the ponds and rivers in Vermont are remarkably clear and transparent. It is 130 miles N. E. of Bennington, and 417 N. E. by N. of Philadelphia. N. Number of inhabitants lat. 44. 5. 873

NEWBURY, a township in Effer co. Maffachusetts, incorporated in 1635; fituated on the fouthern bank of Merrimack river, and contains 3,972 inhabitants. It formerly included Newbury-Port, and with Merrimack river encircles it. It is divided into five parifhes, befides a fociety of Friends, or Quakers. Dummer Academy, in this township, is in a flourishing state; it was founded by Lieut. Gov. Dummer in 1756, opened in 1763, and incorporated in 1782. The inhabitants are principally employed in hufbandry. The land, particularly in that part of the town which lies on Merrimack river, and is here called Newbury-Newton, is of a fuperior quality, under the beft cultivation, and is faid by travellers to be little inferior to the most improved parts of Great Britain. Some of the high lands afford a very extensive and variegated view of the furrounding country, the rivers, the bay, and the fea coaft from Cape Ann to York, in the District of Maine. Some few veffels are here owned and employed in the fifhery, part of which are fitted out from Parker river. It rifes

Jong.

cico or eagues orth to fertile nts are c. but ead. Lillfboput 70 It was ontains

hip in unifting en from dwick, It conurmers, Vorcef-

a, La-

Buck's

itate of Kill, tz, and city. fex.co:

h pro-

th-weft

veft by ch it is and a urce to uthern er Calore at Bay; ings of in the eS.E. by the a river, fon (at to its y a due he norly conouthern in the ovince. , it ex-N. and sabout 260

in Rowley, and after a course of a few miles, paffes into the found which fepa-rates Plumb Ifland from the main land. It is navigable about two miles from its mouth. A woollen manufactory has en established on an extensive scale in Byfield parifh, and promifes to fueceed. This township is connected with Salifbury by Effex Merrimack bridge, about 2 miles above Newbury-Port, built in 1792. At the place where the bridge is erected, an ifland divides the river into two branches : an arch of 160 feet diameter, 40 feet above the level of high water, connects this ifland with the main on the opposite fide. The whole length of the bridge is 1030 feet; its breadth 34; its contents upwards of 6000 tons of timber. The two large arches were executed from a model invented by Mr. Timothy Palmer, an ingenious housewright in Newbury-Port. The whole is executed in a ftyle far exceeding any thing of the kind hitherto effayed in this country, and appears to unite elegance, ftrength and firmnefs. The day before the bridge was opened for the infpection of the public, a thip of 350 tons paffed under the great arch. There is a commodious house of entertainment at the bridge, which is the refort of parties of pleafure, both in fummer and winter.

NEW

350

NEWBURY-PORT, a port of entry, 352. and post-town in Effex co. Maffachufetts; pleafantly fituated on the S. fide of Merrimack river, about 3 miles from the fea. In a commercial view it is next in rank to Salem. It contains 4837 inhabitants, although it is, perhaps, the finalleft township in the State, its contents not exceeding 640 acres. It was taken from Newbury, and incorporated in 1764. The churches, 6 in number, are ornamented with fteeples; the other public buildings are the courthoufe, gaol, a bank, and 4 public fchoolhoufes. To the honour of this town, there are in it to public fchools, and 3 printing-offices. Many of the dwelling houfes are elegant. Before the war there were many thips built here; but fome years after the revolution, the bufinefs was on the decline ; it now begins to revive. The Bofton and Hancock confinental frigates, were built here, and many privateers during the war. The harbour is fafe and capacious, but difficult to enter. See Merrimack Rimer. The Marine Society of this town, and

NEW

other gentlemen in it, have humanely crefted feveral fmall houses, on the fhore of Plumb-Ifland, furnished with fuel and other conveniencies, for the relief of hip-wrecked mariners. Large quanti-ties of rum are diftilled in Newbury-Port, there is also a brewery ; and a confiderable trade is carried on with the Weft-Indies and the fouthern States. Some veffels are employed in the freighting bufinefs, and a few in the fifnery, In Nov. 1790, there were owned in this port, 6 fhips, 45 brigantines, 39 ichooners, and 28 floops; making in all, 11,870 tons. The exports for a year, ending Sept. 30, 1794, amounted to 361,380 dollars. A machine for cutting nails, has been lately invented by Mr. Jacob Perkins of this town, a gentleman of great mechanical genius, which will turn out, if neceffary, 200,000 nails. in a day. Newbury-Port is 40 miles north-north-eaft of Bofton, 22 fouth-byweft of Portfmouth, 12 N. of Ipfwich, and 389 north-caft of Philadelphia. The harbour has 10 fathoms water : high water at full and change 15 minutes after 11 o'clock. The light-houfe on Plumb-Ifland lies in 42. 47. north la-titude, and in 70. 47. weft longitude.

NEW CALEDONIA, the name given by the Scotch to the ill-fated fottlement which that nation formed on the ifthmus of Darien, and on the fouth welf fide of the gulf of that name. It is fituated eaftward of the narroweft part of the ifthmus, which is between Panama and Porto Bello, and lies fouth-eaft of the latter city. The fettlement was formed in 1698. See Darien.

NEW-CANTON, a fmall town lately established in Buckingham co. Virginia, on the fouth-fide of James's river, 70 miles above Richmond. It contains a few houfes, and a ware-house for inspecting tobacco.


NEW - CARLISLE. See Bonaventure.

NEW-CASTLE, the most northern county of Delaware State. It is about 40 miles in length and 20 in breadth, and contains 19,686 inhabitants, including 2,502 flaves. Here are 2 fhuffmills, a flitting-mill, 4 paper-mills, 60 for grinding different kinds of grain, and feveral fulling-mills. The chief towns of this county are Wilmington and New-Caffle. The land in it is more thoken than any other part of the State. The









NEW-CASTLE, a post-town, and the feat of juffice of the above county. I is fituated on the weft fide of Delaware river, 5 miles fouth of Wilmington and 34 S V. of Philadelphia. It contains about 70 houses, a court-house and gaol a church for Epifcopalians and er for Prefbyterians. This is the anoth oldeft town on Delaware river, having been fettled by the Swedes, about the year 1627, who called it Stockbolm, after the metropolis of Sweden. When it fell into the hands of the Dutch, it received the name of New-Amfterdam and the English, when they took pof-feffion of the country, gave it the name of New-Cafile. It was lately on the decline; but now begins to flourish. Piers are to be built, which will afford a fafe retreat to veffels, during the winter featon. Thefe, when completed, will add confiderably to its advantages. It was incorporated in 1672, by the governor of New-York, and was for man years under the management of a bailiff and fix affiftants. N. lat. 19. 18.

NEW-CASTLE, a township in West-Chester co. New-York, taken from North-Castle in 1791, and incorporated. In 1796, there were 151 of the inhabitants qualified electors.

NEW-CASTLE, a finall town in the county of Rockingham, New Hampshire, 8 miles distant from Portsmouth, was incorporated in 1693, and contains 534 inhabitants.

NEW-CASTLE, a finall post-town in Lincoln co. District of Maine, fituated between Damariscotta and Skungut rivers. It is so miles E. by N. of Wiscassed the construction of the start cassed of the start of the start of the start N. by E. of Boston. The township contains 896 inhabitants.

NEW-CASTLE, a poft-town of Hanover co. Virginia, fituated at the mouth of Affequin creek, on the S. W. fide of Pamutky rivec, and contains about 36 houfes. It is 54 miles N. W. of Williamfburg, 24 N. E. of Richmond, and 297 from Philadelphia.

NEW-CHESTER, a township in Grafton co. New-Hampshire, fituated on the W. fide of Pemigewaffet river. It was incorporated in \$778, and contains 312 inhabitants. It is about 13 miles below the town of Plymouth.

NEW-CONCORD, formerly called

Cuntbouaite, a township in Graston co. New-Hampshire, on Amonoosuck river, and was incorporated in 1768, and contains 147 inhabitants.

NEW-CORBUDA, a town of the province of Tucaman, in South America. NEW-CORNWALL, a township in Orange co. New-York; bounded northerly by Ulfter co. and easterly by Hudfon's river and Haverstraw. It contains

4,225 inhabitants, inclusive of 167 flaves. NEW-DUBLIN, a township in Lunenburg co. Nova-Scotia; fitnated on Mahone Bay; first fettled by Itish, and afterwards by Germans.

NEW-DURHAM, in Strafford county, New-Hampthire, lies on the east coast of Winnepisfeoga Lake, west of Merry Meeting Bay, nearly 40 miles northwest of Portsmouth. Incorporated in 1762, having 554 inhabitants.

NEW-EDINBURGH, a new fettlement in Nova-Scotia.

NEWENHAM, Cape, is the north point of Briftol Bay, on the north weft coaft of North-America. All along the coaft the flood tide fets ftrongly to the northweft, and it is high water about noon on full and change days. N. lat. 58. 42. W. long. 162. 24.

NEW-ENGLAND, (or NORTHERN or EASTERN STATES) lies between 41 and about 48 N. lat. and between 64. 53. and 74. 8. W. longitude ; bounded. north by Lower-Canada; caft by the province of New-Brunfwick and the Atfantic Ocean ; fouth by the fame ocean ; and Long-Ifland Sound : weft by the State of New-York. It lies in the form of a quarter of a circle. Its weft line, beginning at the mouth of Byram river. which empties into Long-Ifland Sound, at the fouth weft corner of Connecticut, lat. 41. runs a little E. of N. until it frikes the 45th degree of latitude; and then curves to the eaftward almost to the Gulf of St. Lawrence. This grand divisi of the United States comprehends the States of Vermont, New-Hampfbire, Maffachufetts, (including the Diffriet of Maine,) Rhode-Island and Providence Plantations, and Connecticut. New-England has a very healthful climate. It is effimated that about one in feven of the inhabitants live to the age of 70 years; and about one in thirteen or fourteen to fouth-welt which are the most prevalent. East and north-east winds, which are upelattic and difagreeable, are frequent at cer-tain featons of the year, particularly in April and May, on the fea-coafts. The weather is lefs variable than in the middle, and efpecially in the fouthern States, and more for the feature of the fourthern States, and more fo than in Canada. The extremes of heat and cold, according to Farenheit's thermometer, are from 20° below, to 100° above o. The medium is from 48 to 50°. The dif-eafes most prevalent in New-England, are alvine fluxes, St. Anthony's fire, afthma, atrophy, catarth, cholic, in-flammatory, flow, nervous and mixed fevers, pulmonary confumution, quinfevers, pulmonary confumption, quin-fy, and rheumatiin. A late writer has observed, that " in other countries, men are divided according to their wealth or indigence, into three claffes ; the opulent, the middling, and the poor; the idlenefs, luxuries, and debaucheries of the first, and the mifery, and too frequent intemperance of the laft, deftroy the greater proportion of these two. The intermediate class is below those indulgencies which prove fatal to the rich, and above those fufferings to which the unfortunate poor fall victims : this is therefore the happieft division of the three. Of the rich and poor, the American republic furnishes a much smaller reportion than any other diffrict of the m world. In Connecticut, particularly, the distribution of wealth and its concomitants, is more equal than elfewhere, and therefore, as far as excels, or want of wealth, may prove deftructive or fatutary to life, the inhabitants of this State may plead exemption from difeases." What this writer, Dr. Foulke, fays of Connecticut in particular, will, with very few exceptions, apply to New-England at large. New-England is a high, hilly, and in

NEW

554

New-England is a high, hilly, and in fome parts a mountainous country, form-ed by nature to be inhabited by a hardy-nace of free, independent republicans. The mountains ar comparatively finall, running nearly north and fouth in ridges parallel to each other. Between thefe ridges, flow the great rivers in majeflic meanders, receiving the innumerable ri-vulets and larger fireams which proceed from the mountains on each fide. To from the mountains on each lide. To a fpectator on the top of a neighbouring mountain, the vales between the ridges, while in a flate of nature, exhibit a romontic appearance. They feem an ocean

NEW

furface like that of the great ocean itfelf. A richer, though lefs romantic view is prefented, when the vallies have been cleared of their natural growth by the industrious husbandmen, and the fruit of their labour appears in loaded orchards, extensive meadows, covered with large herds of fheep and neat cattle, and rich fields of flax, corn, and the various kinds of grain. These vallies are of various breadths from two to twenty miles; and by the annual inundations of the rivers and fmaller ftreams, which flow through them, there is frequently an accumulation of rich, fat foil left upon the furface when the waters retire. The principal rivers in New-England are Penobicot, Kennebeck, Androfcoggin, or Amariscoggin, Saco, Merrimack, Connecticut, Houfatonic, Otter Creek. and Onion rivers; befides many fmaller ones. New-England, generally fpeak-ing, is better adapted for grazing than for grain, though a fufficient quantity of the latter is raifed for home confumption, if we except wheat, which is imported in confiderable quantities from the middle and fouthern States. Indian corn, rye, oats, barley, buck-wheat, flax, and hemp, generally fucceed very well. Apples are common, and in general plenty in New-England; and cyder constitutes the principal drink of the inhabitants. Peaches do not thrive fo well as formerly. The other comnion fruits are more or lefs cultivated in different parts. The high and rocky ground is in many parts covered with clover, and generally affords the beft of pafture ; and here are raifed fome of the fineft cattle in the world. The quantity of butter and cheefe made for exportation is very great. Confiderable attention has lately been paid to the raifing of theep. This is the most populous division of the United States. It contained, according to the cenfus of 1790, 1,009,522 fouls. The great body of these are landholders and culti. vators of the foil. As they poffers, in fee fimple, the farms which they cultivate, they are naturally attached to their country ; the cultivation of the foil makes them robult and healthy, and enables them to defend it. New-England may, with propriety, be called a nurfery of men, whence are annually transplanted, into other parts of the of woods, fwelled and depressed in its United States, thousands of its natives. Vaft

Vaft num have emit of New-Weftern and fome and every The in almoft u and it is and to th that has the Engl ed amon Learning among a any othe the exce almoft e circulati tempt to this cou 1607, number turned that la Englan Plymon founder 101 101 fettlers tive wh Ameri affairs numbe over, i ning o men, about numbe Bay, I Rhode half a NE moft t cut. NE ham river, tlebor NE fide o parat the n is ab betw betw from and 4493

cean itave and the loaded covered t cattle, the vallies are twenty tions of which quently foil left s retire. England rofcogrimack, Creek, fmaller fpeakng than quantity nfumph is ims from Indian -wheat, d in geand cyot thrive er comvated in d rocky ed with e beft of e of the ne quanfor exfiderable to the moft po-States. enfus of e great offels, in ched to the foil hy, and w-Engcalled a nnually of the natives. Vaft

Vast numbers of them, fince the war, have emigrated into the northern parts of New-York, into Kentucky and the Western Territory, and into Georgia,

NEW

and fome are feattered into every State and every town of note in the Union. The inhabitants of New-England are, almost universally, of English descents and it is owing to this circumftance, and to the great, and general attention that has been paid to education, that the English language has been preferv-ed among them to free from corruption. Learning is diffuled more univerfally, among all ranks of people here, than in any other part of the globe ; arising from the excellent establishment of schools in almost every township, and the extensive circulation of newspapers. The first attempt to form a regular fettlement in this country, was at Sagadahock, in 1607, but the year after, the whole number who furvived the winter, returned to England. The first company that laid the foundation of the New-England States, planted themfelves at Plymouth, November, 1620. The founders of the colony confifted of but 101 fouls. In 1640, the importation of fettlers ceafed. Perfecution, (the motive which had led to transportation to America) was over, by the change of affairs in England. At this time the number of paffengers who had come over, in 298 veffels, from the beginning of the colony, amounted to 21,200 men, women and children; perhaps about 4,000 families. In 1760, the number of inhabitants in Maffachuletts Bay, New-Hampfhire, Connecticut, and Rhode ifland, amounted, probably, to half a million.

NEW-FAIRFIELD, thenorth-westernmost township in Fairfield co. Connecticut.

NEW-FANE, the chief town of Windham co. Vermont, is fituated on Weft river, a little to the north-west of Brattleborough. It has 660 inhabitants.

NEWFOUNDLAND Island, on the east fide of the gulf of St. Lawrence, is feparated from the coaft of Labrador on the north by the Straits of Belifle, which is about 21 miles wide. It is fituated between lat. 46. 45. and 51. 46. N. and between long. 52. 31. and 59. 40. W. from Greenwich ; being 381 miles long, and from 40 to 287 miles broad. The

125 11 20

NEW 355 coafts are fubject to fogs, attended with almoft continual forms of fnow and fleet, the fky being ufually overcaft. From the foil of this ifland the Britifla reap no great advantage, for the cold is long continued and fevere, and the fum-mer heat, though violent, warms it not enough to produce any thing valu-able; for the foil, at leaft in thole parts of the ifland which have been explored, is rocky and barren./ However, it is watered by feveral good rivers, and has many large and good harbours. This ifland, whenever the continent fhall come to fail of, timber, convenient to naviga-tion (which on the fea-coaft perhaps will be at no very remote period) it is faid will afford a very large fupply for mafts, yards, and all forts of lumber for the W. India trade. But what at prefent it is chiefly valuable for, is the great fiftery of cod carried on upon those filhery of cod carried on upon those thoals, which are called the Banks of Newfoundland. Great Britain and the U.States, at the loweft computation, an nually employ 3000 fail of fmall cra in this fifthery; on board of which, and on fhore to cure and pack the fifh, an upwards of 100,000 hands : fo that this filhery is not only a very valuable branch of trade to the merchant, but a fource of livelihood to many thousands of poor people, and a most excellent nursery to the royal navy. This fiftery is comput ed to increase the national flock 300,0001. a year in gold and filver, remitted for the cod fold in the north, in Spain, Portugal, Italy, and the Levant. Th plenty of cod, both on the great ban and the leffer ones, which lie to the E, and S. E. of this ifland, is inconceivable; and not only cod, but feveral other fpecies of fifh, are caught there in abundance; all of which are nearly in an equal plenty along the fhores of Newfoundland, Nova-Scotia, New-England, and the ifle of Cape Breton; and very profitable fifheries are carried on upon all their coafts.

NEW

This island, after various disputes about the property, was entirely ced to England by the treaty of Utrecht, in 1713; but the French were left at liberty to dry their nets on the northern fhores of the ifland; and by the treaty of 1763, they were permitted to fifh in the gulf of St. Lawrence, but with this limitation, that they thould not approach Z2 within

within three leagues of any of the coafts belonging to England. The fmall iflands of St. Pierre and Miquelon, fituated to the fouthward of Newfoundland, were alfo ceded to the French, who ftipulated to erect no fortifications on thefe iflands, nor to keep more than 50 foldiers to enforce the police. By the laft freaty of peace, the French are to enjoy the fiftheries on the north and on the weft coafts of the ifland; and the inhabitants of the United States are allowed the fame privileges in fifting, as before their independence. The chief towns in Newfoundland are, Placentia, Bonavifta, and St. John's; but not above 1,000 families remain here in winter. A fmall fquadron of men of war are fent out every fpring to protect the fiftheries and inhabitants, the admiral of which, for the time being, is governor of the ifland, befides whom, there is a lieutenant-governor, who refides at Placentia. In 1785, Great Britain employed in the Newfoundland fifthery, 292 fifting fhips, and 58 colony thips, whofe tomage together amounted to 41,990. The fame year, they carried to foreign markets 591,276 quintals of fifth.

NEW

3 (6

Veffels lie in the bays and harbours of this island in perfect fecurity, being well fheltered, except at the entrance, by the mountains; and fome of them (the whole circuit of the illand being full of them) are a league or two leagues in length, and near half a league in breadth, into which feveral rivers and brooks of excellent water come from the adjacent mountains. Thefe are also contiguous to each other, being feparated ufually only by a point of land, feldom exceeding two leagues in breadth. But the towns and villages are only on the larger and more commodious bays. The cod are usually found to be most abundant where the bottom is fandy, and the leaft numerons where it is muddy, and the beft depth is allo between 30 and 40 fathoms. When a thip has taken her flation, the is immediately unrigged, and a proper place felected for curing and fecuring the fifh, and huts erected for the men who work afhore : a large fcaffold is also crected at the water's edge, where the number of shallops defined for the fifhery is got ready, and also fecured after the featon is over, till the following fummer. Ships first enNEW

tering any bay, have the privilege of applying these to their own use. The mafter who arrives first in the feafon in each of the numerous harbours, is for that year ftyled Lord of the Harbour: who also fettles disputes among the fiftermen. We shall not detail the mode of managing and curing the fish, which is purfued with much perfevering labour; we fhall only add, that the Great Bank of Newfoundland, which may properly be deemed a vaft mountain under water, is not lefs than 330 miles in length, and about 75 in breadth. The depth of water upon it varies from 15 to 60 fathoms, and the bottom is covered with a vaft quantity of fhells, and frequented by vaft fhoals of fmall fifh, moft of which ferve as food to the cod, that are inconceivably numerous and voracious. It is a fact, in proof the plenty of cod here, that though fo many hundred veffels, have been annually loaded with them, for two centuries paft, yet the prodigi-ous confumption has not yet leffened their plenty. The number of fowls called penguins, are certain marks for the bank, and are never found off it ; these are sometimes seen in flocks, but more ufually in pairs. The fifhery on the banks of Newfoundland, may be juftly effeemed a mine of greater value than any of those in Mexico or Peru. The French uled to employ in this fifhery 264 thips, tonnage 27,439; and 9,403 men. Total value £ 270,000 sterling.

NEW GARDEN, a township in Chefter co. Pennsylvania.

NEW GARDEN, a fettlement of the Friends in Guildford co. N. Carolina.

NEW-GENEVA, a fettlement in Fayette co. Pennfylvania.

NEW-GERMANTOWN, a post-town of New-Jerley, fituated in Hunterdon co. It is 28 miles north-west of Brunswick, 47 north by east of Trenton, and 77 north east by north of Philadelphia.

NEW-GLOUCESTER, a finall pofttown in Cumberland co. Diffrict of Maine, 27 miles northerly of Portland, and 146 north of Bofton. It was incorporated in 1774, and contains 1355 inhabitants.

NEW-GOTTINGEN, a town of Georgia, fituated in Burke co. on the weft bank of Savannah river, about 18 miles eaft of Waynelborough, and 35 northweft of Ebenezer.

NEW-C fouthern America, Fede Bag NEW. Chefhire corporate inhabitan eaft of D NEW United S between and betw long. fro by Lowe of Maine weft by I rates it nearly th The Dif the line lar, and nufe. or 6,074 100,000 168 mil its leaft This viz. Ro Hillfbo towns a Dover, Plymon townfh whole tions in fons, il the nu at 52,1 miles ner. coves harbou cataqu rocky beach es, int good interv great caule by th bring Conn a qui on ea

abun

kind

NEW-

vilege of The feafon in s, is for larbour : the fifthe mode h, which g labour; at Bank properly er water, gth, and lepth of o 60 fa. red with quented of which e inconus. It is cod here, veffels, th them, prodigileffened of fowls arks for off it i ks, but ifhery on may be ter value or Peru. this fifh-39; and 270,000

in Chef.

ht of the arolina. in Fay-

oft-town

erdon co. unfwick. and 77 phia. all poftiffrict of Portland, was inins 1355 of Georthe weft 18 miles 5 north-

NEW-

NEW

NEW-GRANADA, a province in the fouthern division of Terra Firma, S. America, whole chief town is Santa Fede Bagota. See Cibola. NEW-GRANTHAM, a township in Cheshire co. New-Hampshire, was incorporated in 1761, and contains 333 inhabitants, and is about 1 5 miles foutheaft of Dartmouth college.

NEW-HAMPSHIRE, one of the United States of America, is fituated between lat. 42. 41. and 45. 11. north, and between 70. 40. and 72. 28. well long. from Greenwich; bounded north by Lower Canada; east by the District of Maine; fouth by Maffachuletts, and weft by Connecticut river, which feparates it from Vermont. Its shape is nearly that of a right angled triangle. The District of Maine and the fea its leg, the line of Maffachuletts its perpendicular, and Connecticut river its hypothenufe. It contains 9,491 fquare miles, or 6,074,240 acres; of which at leaft 100,000 acres are water. Its length is 168 miles; its greateft breadth 90; and its leaft breadth 19 miles.

This State is divided into c counties. viz. Rockingham, Strafford, Chefhire, Hillfborough, and Grafton. The chief towns are Portfmouth, Exeter, Concord, Dover, Amherft, Keen, Charleftown, Plymouth, and Haverhill. Moft of the townships are 6 miles square, and the whole number of townships and locations is 214; containing 141,\$85 perfons, including 158 flaves. In 1767, the number of inhabitants was effimated at 52,700. This State has but about 18 miles of fea-coaft, at its fouth-eaft corner. In this diftance there are feveral coves for fifting veffels, but the only harbour for thips is the entrance of Pifcataqua river, the fhores of which are rocky. The thore is mostly a fandy beach, adjoining to which are falt marfhes, interfected by creeks, which produce good pasture for cattle and sheep. The intervale lands on the margin of the great rivers are the most valuable, becaule they are overflowed and enriched by the water from the uplands which brings a fat flime or fediment, On Connecticut river these lands are from a quarter of a mile to a mile and an half. on each fide, and produce corn, grain, and grafs, efpecially wheat, in greater abundance and perfection than the fame kind of foil does in the higher lands.

NEW

The wide fpreading hills are effeemed a warm and rich ; rocky moift land is accounted good for pafture; drained fwamps have a deep mellow foil ; and the vallies between the hills are generally very pro-ductive. Agriculture is the chief occupation of the inhabitants; beef, pork, mutton, poultry, wheat, rye, Indian corn, barley, pulfe, butter, cheefe, hops, esculent roots and plants, flax, hemp, &c. are articles which will always find a market, and are raifed in immenfe quantities in New-Hampfhire, both for home confumption and exportation. Apples and pears are the most common fruits cultivated in this State, and no hufbandman thinks his farm complete without an orchard. Tree fruit of the first quality, cannot be raifed in fuch a northern climate as this, without particular attention. New-York, New-Jerfey and Pennfylvania have it in perfe tion. As you depart from that tract, either fouthward or northward, it degenerates. The uncltivated lands are covered with extensive forests of pine, fir, cedar, oak, walnut, &c. For climate, difeafes, &c. fee New England,

Several kinds of earths and clays are found in this State, chiefly in Exeter, New-Market, Durham, and Dover. Marle abounds in feveral places, but is little ufed. Red and yellow ochres are found in Somerfworth, Chefterfield, Rindge, and Jaffray. Steatites, or foap rock, is found in Orford. The best lapis specularis, a kind of tale, commonly called ifing-glafs, is found in Grafton and other parts. Cryftals have been difcovered at Northwood, Rindge, and Conway ; allum, at Barrington, Orford, and Jaffray ; vitriol, at Jaffray, Brentwood, and Rindge, generally found combined in the fame ftone with fulphur. Free-ftone fit for building is found in Orford; also a grey ftone fit for millflones. Iron ore is found in many places; black lead in Jaffray, and fome lead and copper ore has been feen; but iron is the only metal which has been wrought to any advantage.

New-Hampfhire is interfected by feveral ranges of mountains. The first ridge, by the name of the Blue Hills, paffes thro' Rochefter, Barrington and Nottingham, and the feveral fummits are diftinguifhed by different names. Behind thefe are feveral higher detached mountains. Farther back the mountains rife ftill 23

higher,

igher, and among the third range, Chorues, Offapy, and Kyarfarge, are the rincipal. Beyond thefe is the lofty dge which divides the branches of Connecticut and Merrimack rivers, decominated the Height of Land. 'In this ridge is the celebrated Monadnock nountain, thirty miles north of which s Sunapee, and 48 miles further is Moofehillock, called also Moofhelock nountain. The ridge is then continud northerly, dividing the waters of the river Connecticut from those of Saco, and Amarifcoggin. Here the moun-tains rife much higher, and the most elevated fummits in this range, are the White Mountains. The lands W. of White Mountains. The lands W. of this laft mentioned range of mountains, bordering on Connecticut river, are in-terfperfed with extensive meadows, rich and well watered. Offapy Mountain lies adjoining the town of Moultonbo-rough on the N. E. In this town it is observed, that in a N. E. form the wind alls over the mountain, like water over a dam ; and with fuch force, as fremently to unroof houses. People who live near these mountains, by noticing the various movements of attracted vapours, can form a pretty accurate judgent of the weather ; and they hence tyle thefe mountains their Almanack. If a cloud is attracted by a mountain, and hovers on its top, they predict rain ; and if, after rain, the mountain continues capped, they expect a repetition of flowers. A form is preceded for feveral hours by a roaring of the mountain, which may be heard 10 or 12 miles. But the White Mountains are undoubtedly the highest land in New-England, and, in clear weather, are discovered before any other land, by veffels coming into the eaftern coaft; but by reafon of /their white appearance, are frequently miftaken for clouds. They are vifible on the land at the diftance of 80 miles, on the S. and S. E. fides; they appear higher when viewed from the N. E. and it is faid, they are feen from the neighbourhood of Chamblee and Quebec. The Indians gave them the name of Agiocochook. The number of fummits in this clufter of mountains cannot at prefent be afcertained, the country around them being a thick wildernefs. The greateft number which can be feen at once, is at Dartmouth, on the N. W. fide, where feven fum-

Chimes

NEW

NEW

mits appear at one view, of which four are bald. Of these the three highest are the most diffant, being on the eastern fide of the clufter; one of these is the mountain which makes fo majeffic an appearance all along the fhore of the eaftern counties of Maffachufetts: It has lately been diffinguished by the name of MOUNT WASHINGTON. During the period of 9 or 10 months, these mountains exhibit more or less of that bright appearance, from which they are denominated white. In the fpring, when the fnow is partly diffolved, they appear of a pale blue, ftreaked with white, and after it is wholly gone, at the diftance of 60 miles, they are altogether of the fame pale blue, nearly approaching a fky colour; while at the fame time, viewed at the diftance of \$ miles or lefs, they appear of the proper colour of the rock. These changes are obferved by people who live within con-fant view of them; and from thefe facts and obfervations, it may with certainty be concluded, that the whitenefs of them is wholly cauled by the fnow, and not by any other white fubstance, for in fact there is none.

The reader will find an elegant defcription of these mountains in the 3d vol. of Dr. Belknap's History of New-Hampshire, from which the above is extracted.

The most confiderable rivers of this State are Connecticut, Merrimack, Pifcataqua, Saco, Androfcoggin, Upper and Lower Amonoofuck, befides many other smaller streams. ' The chief lakes are Winnipifcogee, Umbagog, Sunapee, Squam, and Great Offipee." Before the war, fhip-building was a fource of confiderable wealth to this State ; about 200 veffels were then annually built, and fold in Europe and in the Weft-Indies, but that trade is much declined. Although this is not to be ranked among the great commercial States, yet its trade is confiderable. Its exports confift of lumber, fhip-timber, whale-oil, flax-feed, live ftock, beef, pork, Indian corn, pot and pearl afhes, &c. &c. In 1790, there belonged to Pifcataqua 33 veffels above 100 tons, and 50 under that burden. The tonnage of foreign and American veficis cleared out from the ift of October, 1789, to ift of October, 1791, was 31,097 tons, of which 26,560 tons were American veffels. The

oroduce icale fifh of Pifcat Ift of Od 1791, an dollars, Septemb in 1793 year 175 of New 1792, W by an al can incr and 100 The on! over, ci is ampl a flouri academ Iplwich New-E NEW New-H on the 9 miles of Mer poratec habita NE1 of Wil tendin along 6831 Chief NE lingto \$0,00 large tivate hip about delph NE gan c NF in Li N.E Harti NI exten dlefe: on th north It is cont fons 44.

The fifth

the life (

hich four e higheft the eaft-i there is majeftic re of the fetts : It by the IGTON. months. or lefs of which they he fpring, ved, they ked with gone, at y are altonearly ap-ile at the ance of \$ the proper hanges are ithin confrom thefe with cer-: whitenefs the fnow, fubstance,

legant dein the 3d y of Newbove is ex-

ers of this mack. Piftin, Upper fides many chief lakes g, Sunapee, Before the irce of conite; about ally built, e Weft-Inch declined. hked among es, yet its xports conwhale-oil, ork, Indian ici &c. In fcataqua 33 id 50 under : of foreign d out from If of Ofto-, of which

can veffels. The NEW

The fiftheries at Pifcataqua, including the Ifle of Shoals, employ annually 27 fchooners and 20 boats. In 1791, the produce was 25,850 quintals of cod and fcale fifth. The exports from the port of Pifcataqua in two years, viz. from ift of October, 1789, to ift of October, 1791, amounted to the value of 296,839 dollars, 51 cents; in the year ending September 30th, 1792, 181,407 dollars; in 1793, 198,197 dollars; and in the year 1794, 153,856 dollars. The bank of New-Hampfhire was effablished in 1792, with a capital of 50,000 dollars ; by an act of affembly the flock-holders can increafe it to 200,000 dollars fpecie, and 100,000 dollars in any other effate. The only college in the State is at Hanover, called Dartmouth College, which is amply endowed with lands, and is in a flourishing fituation. The principal academies are those of Exeter, New-Ipswich, Atkinfon, and Amherft. See New-HAMPTON, a post-town of New-Hampfhire, fituated in Strafford co.

NEW-HAMPTON, a post-town of New-Hampshire, situated in Strafford co. on the W. fide of Lake Winnipsseege, 9 miles S. E. of Plymouth, and 9 N. W. of Meredith. The township was incorporated in 1777, and contains 652 inhabitants.

NEW-HANOVER, a maritime county of Wilmington diffrict, N. Carolina, extending from Cape Fear river north-east along the Atlantic Ocean. It contains 6831 inhabitants, including 3738 flaves. Chief town, Wilmington.

NEW-HANOVER, a townfhip in Burlington co. New-Jerfey, containing about so, ooo acres of improved land, and a large quantity that is barren and uncultivated. The compact part of the townfhip is called New Mills, where are about 50 houfes, 27 miles from Philadelphia, and 13 from Burlington.

NEW HANOVER, a township in Morgan co. Pennsylvania.

NEW-HARTFORD, a finall polt-town in Litchfield co. Connecticut, 14 miles N. E. of Litchfield, 20 W. by N. of Hartford.

NEW-HAVES County, Connesticut, extends along the Sound between Middlefex co. on the eaft, and Fairfield co. on the weft; about 30 miles long from north to fouth, and 28 from eaft to weft. It is divided into 14 townfhips. It contained in 1756, 17,955 free perfons, and 226 flaves; in 1774, 25,896

free perfons, and 925 flaves; and in 1790, 30,397 free perfons, and 432 flaves.

NEW-HAVEN, (City) the feat of juf-NEW-HAVEN, (Chy) the leat of mi-tice in the above county, and the femis-metropolis of the State. This city lies round the head of a bay which makes up about four miles north from Long Ifland Sound. It covers part of a large plain which is circumfcribed on three fides by high hills or mountains. Two fides by high hills or mountains. finall rivers bound the city eaft and weft. It was originally laid out in fquare of 60 rods; many of these fquares have been divided by crofs ftreets. Four ftreets run north-weft and fouth eaft, and are croffed by others at right angles. and are croffed by others at right angles. Near the centre of the city is the public fquare, on and around which are the public buildings, which are a ftate-houfe, two college edifices, and a chapel, three churches for Congregationalifts, and one for Epifcopalians; all which are hand-fome and commodious buildings. The college edifices, chapel, ftate-houfe, and one of the churches are of brick. The public fouare is encircled with rows of public fquare is encircled with rows o trees, which render it both convenient and delightful. Its beauty, however, is greatly diminished by the burialground, and feveral of the public build-ings which occupy a confiderable part of it. Many of the freets are ornamented with rows of trees on each fide, which give the city a rural appearance. The prospect from the steeples is great-ly variegated and extremely beautiful. There are between 3 and 400 neat dwelling-houfes in the city, principally of wood. The freets are fandy but clean, Within the limits of the city are 4000 fouls. About one in 70 die annually. Indeed as to pleafantness of fituation and falubrity of air, New-Haven is hardly exceeded by any city in America. It carries on a confiderable trade with New-York and the West-India islands. The exports for one year, ending Sept. 30, 1794, amounted to the value of 171,868 dollars. Manufactures of cardteeth, linen, buttons, cotton, and paper are carried on here. Yale college, which is eftablished in this city was founded in 1700, and remained at Killingworth until 1707, then at Saybrook until 1716, when it was removed and fixed at New-Haven. It has its name from its principal benefactor Governor Yale. There are at prefent fix college domiciles, two Z4

of which, each 100 feet long and 40 wide, are inhabited by the fludents, containing 32 chambers each, fufficient for lodging 120 fludents; a chapel 40 by 50 feet, with a fleeple 130 feet high; a dinning-hall 60 by 40 feet; a houle for the prefident, and another for the profeffor of divinity. In the chapel is lodged the public library, confifting of about 3000 volumes, and the philotophical apparatus, as complete as most others in the United States, and contains the mahines neceffary for exhibiting experiments in the whole courfe of experimental philotophy and aftronomy. The mufeum, to which additious are conflantly making, contains many natural curiofities. From the year 1700 to 1793, there had been educated and graduated at this university about 2303. The number of fludents is generally 150. The harbour, though inferior to New-London, has good anchorage, with 3 fathom and 4 feet water at common tides, and 24 fathom at low water. This place and Hartford are the feats of the legiflature alternately. It is 40 miles fouth-weft by fouth of Hartford, 54 from New-London, 88 from New-York, 152 from Bofton, and 183 north-eaft of Philadelphia. N. lat. 41. 18. W. long. 72. 56.

NEW-HAVEN, a township in Addison co. Vermont, on Otter Creek or River, containing 723 inhabitants.

NEW-HEBRIDES, a cluster of islands in the Pacific Ocean, to called by Capt. Cook in 1794—the fame as the Archipelage of the Great Cyclades of Bouganville, or the Terra Austral of Quiros; which fee.

NEW-HAMPSTEAD, a township in Orange co. New-York, bounded easterly by Clarkstown, and southerly by the State of New-Jersey. It was taken from Haverstraw, and incorporated in 1791. By the State census of 1796, there were 245 of its inhabitants qualified electors.

NEW-HOLDERNESS, a township in Grafton co. New-Hampshire, fituated on the E. fide of Pemigewasser river, about 3 miles E. by S. of Plymouth. It was incorporated in 1761, and contains 329 inhabitants.

NEW-HOLLAND, a town of Pennfylvania, Laucaster co. in the midst of a fertile country. It contains a German church and about 70 houses. It is 12 York to Philadelphia, croffes 3 confi-

miles E. N. E. of Lancaster, and 54 W. N. W. of Philadelphia.

NEW-HUNTINGTON, a mountainous township in Chittenden co. Vermont, on the S. W. fide of Onion river, containing 136 inhabitants.

NEWICHWAWANICK. See Pifcata-

NEWINGTON, a township; formerly part of Portsmouth and Dover, in Rockingham co. New-Hampshire, 5 miles distant from the former. It contains 542 inhabitants.

NEW INVERNESS, in Georgia, is fituated near Darien on Alatamaha river, It was built by the Scotch Highlanders, 160 of whom landed here in 1735.

NEW-IPSWICH, a township in Hillfborough co. New-Hampshire, on the W. fide of Souhegan river, upon the fouthern line of the State. It was incorporated in 1762, and contains 124t inhabitants. There is an academy, founded in 1789, having a fund of about 1000l. and has generally about 40 or 50 fludents. It is about 24 miles S.E., of Keene, and 75 W. S. W. of Portfmouth.

NEW JERSEY, one of the United States of America, is fituated between 39 and 41. 24. N. latitude, and between 74. 44. and 75. 33. W. longitude from London; bounded E. by Hudfon's river and the Ocean : W. by Delaware Bay and river, which divide it from the States of Delaware and Pennfylvania; N. by the line drawn from the mouth of Mahakkamak river, in lat. 41. 24. to a point on Hudfon's river, in lat. 41. It is about 160 miles long and 52 broad, containing about 8,320 fquare miles, equal to 5,324,800 acres. It is divided into 13 counties, viz. Cape May, Cumberland, Salem, Gloucefter, Burlington, Hunterdon, and Suffex; thefe 7 lie from S. to N. on Delaware river; Cape May and Gloucefter extend across to the fea; Bergen, Effex, Middlelex, and Mon-mouth, he from N. to S. on the eaftern fide of the State; Somerfet and Morris are inland counties. The number of inhabitants is 184, 139, of whom 11,423 are flaves. The most remarkable bay is Arthur Kull, or Newark Bay, formed by the union of Paffaick and Hackinfac rivers. The rivers in this State, though not large, are numerous. A traveller in paffing the common road from Newderable derable Paffaick and the is a ver about a at the f Falls, i natural river is in a flo within a rock descend dicular of the by for clofed : out wil acute and is whenc throug broad from of the to ari fun-be view. dous town Great is for called one o the c paffes ming Kull bour been and betw The inter cities and mou of m four tirel part of fo may the the barı oak land iron

id 54 W.

vermont,

Pifcata-

formerly in Rock-5 miles contains

ia, is fitutha river, hlanders, 735. in Hillfin Hillfins 124t academy, of about ut 40 or niles S.E. of Portfne United

he United 1 between d between tude from on's river ware Bay from the fylvania ; he mouth 41. 24. to 1 lat. 41. 52 broad, re miles, is divided ay, Cumurlington, 7 lie from ape May o the fea ; nd Monhe eaftern nd Morris umber of m 11,423 ble bay is formed Hackinfac te, though A traveller rom News 3 confiderable

NEW

derable rivers, viz. the Hackinfac and Paffaick, between Bergen and Newark, and the Rariton by Brunfwick. Paffaick is a very crooked river. It is navigable about 10 miles, and is 230 yards wide at the ferry. The cataract, or Great Falls, in this river, is one of the greateft natural curiofities in the State. The river is about 40 yards wide, and moves in a flow, gentle current, until coming within a fhort diffance of a deep cleft in a rock, which croffes the channel, it descends and falls above 70 feet perpendicularly, in one entire fheet. One end of the cleft, which was evidently made by fome violent convultion in nature, is closed; at the other, the water rufhes out with incredible fwiftnefs, forming an acute angle with its former direction, and is received into a large balon, whence it takes a winding courfe through the rocks, and fpreads into a broad fmooth fiream. The cleft is from 4 to 12 feet broad. The falling of the water occasions a cloud of vapour to arife, which, by floating amidit the fun-beams, prefents rainbows to the view, which adds beauty to the tremendous fcene. The new manufacturing town of Patterson is crected upon the Great Falls in this river. Rariton river is formed by two confiderable fireams, called the north and fouth branches ; one of which has its fource in Morris, the other in Hunterdon county. It paffes by Brunfwick and Amboy, and, mingling with the waters of the Arthur Kull Sound, helps to form the fine har-bour of Amboy. Bridges have lately been erected over the Paffaick, Hackinfac and Rariton rivers, on the post-road between New-York and Philadelphia. These bridges will greatly facilitate the intercourse between these two great cities. The counties of Suffex, Morris, and the northern part of Bergen, are mountainous. As much as five-eighths of most of the fouthern counties, or onefourth of the whole State, is almost entirely a fandy barren, unfit in many parts for cultivation. All the varieties of foil, from the worft to the beft kind, may be found here. The good land in the fouthern counties lies principally on the banks of rivers and creeks. The barrens produce little else but shruboaks and yellow pines. Thefe fandy lands yield an immenfe quantity of bog iron ore, which is worked up to great

advantage in the iron-works in the counties. In the hilly and mountainon parts which are not too rocky for culti-vation, the foil is of a ftronger kind, vation, the foil is of a ftronger kind, and covered in its natural date with flately oaks, hickories, chefnuts, &c. and when cultivated, produces wheat, rye, Indian corn, buck-wheat, oats, barley, flax, and fruits of all kinds common to the climate. The land in this hilly country is good for grazing, and farm-ers feed great numbers of cattle for New-York and Philadelphia markets. The orchards in many parts of the State equal any in the United States, and their cyder is faid, and not without reafon, to be the beft in the world. The markets of New-York and Philadelphia, receive a very confiderable proportion of their supplies from the contiguous parts of New Jersey. These supplies confift of vegetables of many kinds, apples, pears, peaches, plums, ftrawber. ries, cherries and other fruits-cyder in large quantities, butter, cheefe, beef, pork, mutton; and the leffer meats. The trade is carried on almost folely with and from those two great commercial cities, New-York on one fide, and Philadelphia on the other; though it wants not good ports of its own. Manufactures here have hitherto been inconfiderable, not fufficient to fupply its own confumption, if we except the articles of iron, nails, and leather. A spirit of industry and improvement, particularly in manufactures, has, however, of late, greatly increased. The iron manufacture is, of all others, the greateft fource of wealth to the State. Iron-works are erected in Gloucefter, Burlington, Suf-fex, Morris, and other counties. The mountains in the county of Morris give rife to a number of ftreams, neceffary and convenient for these works, and at the fame time furnish a copious supply of wood and ore of a fuperior quality. In this country alone are no lefs than 7 rich iron mines, from which might be taken ore fufficient to fupply the United States; and to work it into iron, there are 2 furnaces, 2 rolling and flitting mills, and about 30 forges, containing from 2 to 4 fires each. These works produce annually, about 540 tons of bar iron, 800 tons of pigs, befides large quantities of hollow ware, fheet iron, and nail-rods. In the whole State it is fuppofed there is yearly made about 1200 tons

tons of bar iron, 1200 do. of pigs, 80 do. of nail-rode, exclusive of hollow ware, and various other caffings, of which vaft quantities are made. The inabitants are a collection of Low Dutch, Germans, English, Scotch, Irish, and New-Englanders, and their defcendants. National attachment, and mutual convenience, have generally induced these several kinds of people to fettle together in a bolly, and in this way their peculiar national manners, cuftoms and character, are full preferved, efpecially among the poorer clafs of people, who have little intercourfe with any but those of their own nation. The people of New-Jerfey are generally industrious, frugal, and hospitable. There are in this State, about 50 Presbyterian congregations, fubject to the care of 3 Presbyteries; befides upwards of 40 congregations of Friends, 30 of Baptifts, 25 of Epifcopalians, 28 of Dutch Reformed, belides Methodists, and a settlement of Mora-vians. All these religious denominations live together in peace and harmony; and are allowed, by the conftitu-tion of the State, to worthip Almighty God agreeably to the dictates of their own confciences. The college at Princeton, called Naffau Hall, has been under the care of a fucceffion of Prefidents, eminent for piety and learning; and has furnished a number of Civilians, Divines, and Phyficians of the first rank in America. It has confiderable funds, is under excellent regulations, and has generally from 80 to 100 ftudents, principally from the fourhern States. There are academies at Freehold, Trenton Hackinfac, Orangedale, Eliza-beth-Town, Burlington, and Newark; and grammar-schools at Springfield, Morristown, Bordentown, and Amboy. There are a number of towns in this State, nearly of equal fize and impor-tance, and none that has more than 300 tance, and none that has more than 300 houses compactly built. Trenton is one of the largeft, and the capital of the State. The other principal towns are Brunswick, Burlington, Amboy, Bordentown, Princetown, Elizabeth-Town, Newark, and Morristown. This State was the feat of war for feveral years, during the bloody contest be-tween Great Britain and America. Her both of both of mean and america. Joffes both of men and property, in proportion to the population and wealth of

the State, was greater than of any other

NEW

62

NEW

vitriol; I

lours of

did it red

it; nor d

from gal the white

lity of th

is, theref

Saratoga ifh, thof

ating.

Lebanon

in and grow wi

ratoga,

foon exp that the

call aer

in the c

the Leb

wrough

matifm

and eve digeftic

ble. 1

train o

Twallor

river w

fo keel

thirft

fuch :

open c

render

move

mal m

up itt

there

water

of the

the ar

mong

chym inhab

view

es th

tures

and v

32 1

north Pitts N Peni

Con

corn Iflan

abo

of the Thirteen States. When General Wathington was retreating through the Jerfies, almost forfaken by all others, her militia were at all times obedient to his orders; and, for a confiderable length of time, composed the firength of his army. There is hardly a town in the State that lay in the progrefs of the Britilh army, that was not rendered fignal, by fome enterprife or exploit.

NEW JERSEY Company's Grant of Lands, lies on the E. fide of Miffifippi river; fouth of Illinois, and north-weft of the Army lands, which form the tract fhaped by the confluence of Ohio with Miffifippi.

NEW-KENT, a county of Virginia, bounded on the S. fide of Pamunky and York rivers. It is about 33 miles long, and 22 broad, and contains 6239 inhabitants, including 3700 flaves. New-Kent court houfe is 30 miles from Richmond, and as far from Williamfburg. NEW-LEBANON, a poff-town in Du-

cheis co. New-York, celabrated for its medicinal fprings. The compact part of this town is pleafantly fituated partly in an ex enfive valley, and partly on the declivity of the furrounding hills. The fpring is on the fouth fide, and near the bottom of a gentle hill, but a few rods weft of the Maffachufetts' weft line, and is furrounded with feveral good houfes, which afford convenient accommodations for the valetudinarians who vifit thefe waters. Concerning the medicinal virtues of this fpring, Dr. Waterhoufe, Profeffor of the theory and practice of physic, at Harvard Univerfity, and who vifited it in the fummer of 1794, obferves, "I confeis myfelf at a lois to determine the contents of thefe waters by chymical analyfis, or any of the ordinary tefts. I fulpect their impregnation is from fome caufe weakened. Excepting from their warmth, which is about that of new milk, I never thould have fulpected them to come under the head of medicinal waters. They are used for the various purposes of cookery, and for common drink by the neighbours, and I never could difcover any other effects from drinking them, than what we might expect from rain or river water of that temperature. There was no visible change produced in this water by the addition of an alkali, nor by a folution of allum; nor was any

Genebrough others, obedionfideed the hardl he prowas not rife of ant of iffifipp th-wef he tract o with irginia. iky and :s long. 9 inha-Newn Richburg. in Dufor its ict part I partly rtly on hills. le, and but a ts' weft feveral venient narians cerning ig, Dr. theory rd Unie fums myfelf ents of fis, or A their weak. varmth, , I neto come waters. urpofes rink by uld dif. rinking A from grature. roduced in alkalor was

any

NEW

lours of gold, filver, or copper; nor did it redden beer or mutton boilet in it; nor did it extract a black tincture from galls ; neither did it curdle milk, the whites of eggs, or foap. The quality of the waters of the pool at Lebanon is, therefore, very different from those of Saratoga. Thefe are warm and warmifh, those very cold, fmart, and exhilerating. Frogs are found in the pool of Lebanon, and plants grow and flourish in and around it; but plants will not grow within the vapour of those of Sa-ratoga, and as for imall animals, they foon expire in it. Hence we conclude that that fpiritus mineralis which fome call aerial acid, or fixed air, abounds in the one but not in the other. Yet the Lebanon pool is famous for having wrought many cures, especially in rheu-matifins, fliff joints, fcabby eruptions, and even in vicceral obftructions and indigeftions; all of which is very proba-ble. If a perfon who has brought on a train of chronic complaints, by intemperance in eating and drinking, fhould fwallow four or five quarts of rain or river water in a day, he would not feel fo keen an appetite for animal food, or thirft for fpirituous liquors. Hence fuch a course of water drinking will open obstructions, rinfe out impurities, render perspiration free, and thus remove that unnatural load from the animal machine, which caufes and keeps up its diforders. Poffibly, however, there may be fomething fo fubtle in these waters as to elude the fcrutinizing hand of the chymifts, fince they all allow that the analyfis of mineral waters is one among the most difficult things in the chymical art." A fociety of Shakers inhabit the fouth part of the town in view of the main ftage-road, which paffes through this town. Their manufactures of various kinds are confiderable, and very neat and excellent. It is about 32 miles E. by S. of Albany, 103 north of New-York, and 6 W. of Pittsfield . H

NEWLIN, a township in Chefter co. Pennsylvania.

NEW-LONDON, a maritime county of Connecticut, comprehending the S.E. corner of it, bordering E. ou Rhode-Ifland, and S. on Long Ifland Sound, about 30 miles from E. to W. and 24

iny effervescence raised by the oil of vitriol; neither did it change the colours of gold, filver, or copper; nor did it redden beef or mutton boilet in it; nor did it extract a black tincture from galls; neither did it curdle milk, the whites of eggs, or soap. The quality of the waters of the pool at Lebanon

NEW

NEW-LONDON, a city, port of entry, and post-town in the above county, an one of the most confiderable commercia towns in the State. It flands on the W fide of the river Thames, about 3 miles from its entrance into the Sound, and is defended by Fort Trumbull and Fort Grifwold, the one on the New-London, the other on the Groton fide of the Thames. A confiderable part of the town was burnt by Benedict Arnold in 1781. It has fince been rebuilt. Here are two places of public worship, one for Episcopalians, and one for Congregationalists, about 300 dwelling-houses, and 4,600 inhabitants. The harbour is large, fafe and commodious, and has fathoms water; high water at full an change, 54 minutes after 8. On the W. fide of the entrance is a light-house, on a point of land which projects confider -ably into the Sound. The exports for a year ending September 30th, 1794, amounted to 557,453 dollars. In that year 1,000 mules were thipped for the West-Indies. It is 14 miles fouth of Norwich, 54 S. E. by S. of Hartford, 54 E. of New-Haven, and 237 N. E. b E. of Philadelphia. N. lat. 41. 25. W. long. 72. 15. The township of New-London was laid out in lots in 1648, but had a few English inhabitants two years before. It was called by the Indians Nameag or Towawog, and from being the feat of the Pequot tribe, was called Pequot. It was the feat of Saffacus, the grand monarch of Long-Ifland, and part of Connecticut and Narraganfet.

NEW-LONDON, a fmall township in Hillsborough co. New-Hampshire, incorporated in 1779, and contains 311 inhabitants. It lies at the head of Blackwater river, and about 3 miles from the N. E. fide of Sunapee Lake.

NEW-LONDON, a post town of Virginia, and the chief town of Bedford co. It stands upon rising ground, and contains about 130 houses, a court-house and gaol. There were here in the late war several workshops for repairing fire-arms. It is 133 miles W. by S. of Richmond, 152 well of Petersburg, and 393 S. W. by W. of Philadelphia.

NEW

NEW-MADRID, in the northern part of Louisiana, is a fettlement on the W. bank of the Miffifippi, commenced tome years ago, and conducted by Col. Morgan of New-Jerley, under the patronage of the Spanish king. The pot on which the city was propoled to be built is finiated in lat. 36. 30. N. and 45 miles below the mouth of Ohjo river. The limits of the new city of Madrid were to extend 4 miles S. and W. from the river; fo as to crofs a beautiful, living deep lake, of the pureft fpring water, 100 yards wide, and fe-veral miles in length, emptying itfelf, by a constant and rapid narrow ftream, through the centre of the city. The banks of this lake, called St. Annis, are high, beautiful and pleafant; the water deep, clear and fweet, and well fored with fish; the bottom a clear fand, free from woods, fhrubs, or other vegetables. On each fide of this delightful lake, freets were to, be laid out, 100 feet wide, and a road to be continued round it, of the fame breadth ; and the freets were directed to be preferved forever, for the health and pleasure of the citizens. A fireet 120 feet wide, on the bank of the Miffifippi, was laid out; and the trees were directed to be preferved for the fame purpole. Twelve, acres, in a central part of the city were to be preferved in like manner, to be ornamented, regulated, and improved by the magistracy of the city for public, walks; and 40 half-acre lots for other public ufes; and one lot of 12 acres for the king's ufc. We do not hear that this fcheme is profecuting, and conclude it is given up. The country in the vicinity of this intended city is represent ed as excellent, and, in many parts, be yond description. The natural growth confifts of mulberry, locust, sassafafras, walnut, hickory, oak, afh, dog wood, &c. with one or more grape vines run ning up almost every tree; and the grapes yield, from experiments, good red wine in plenty, and with little la-bour. In fome of the low-grounds grow large cyprefs trees. The elimate is faid to be tavourable to health, and to the culture of fruits of various kinds, particularly for garden vegetables. The prairies or meadows are fertile in grafs,

NEW

flowering-plants, firawberries, and when cultivated produce good crops of wheat, barley, Indian corn, flax, hemp, and tobacco, and are eafily tilled. Iron and lead mines and falt-fprings, it is afferted, are found in fuch plenty as to afford an abundant fupply of these neceffary articles. The banks of the Miffifippi, for many leagues in extent, commencing about 20 miles above the mouth of the Ohio, are a continued chain of limeftone. A fine tract of high, rich, level land, S. W., W. and N. W. of New-Madrid, about 25 miles wide, extenda uite to the river St. Francis.

NEWMANSTOWN, Pennfylvania, fituated in Dauphin co. on the east fide of Mill Creek. It contains about to houfes, and is 14 miles E. by N. of Harciburg, and 72 N. W. by W. of Philadelphia. NEWMARKET, a township in Rockingham co. New-Hampfhire, north of Exeter, of which it was formerly a part, and 17 miles well of Portfmouth. It was incorporated in 1727, and contains 1137 inhabitants. Foffil thells have been found near Lamprey river in this town, at the depth of 17 feet; and in fuch a fituation as that the bed of the river could never have been there. The fhells were of oyfters, mufcles, and clams intermixed.

NEWMARKET, a village in Frederick co. Maryland, on the high road to Frederickflown, from which it lies nearly 13 miles W. S. W. and about 36 miles north-weft of the Federal City.

NEWMARKET, a village in Dorchefter co. Maryland, 3 miles north-east of Indian-Town, on Choptank river, nine north-east of Cambridge, and as far north-west of Vienna.

NEWMARKET, a town in Virginia, Amherift co. on the north fide of James river, at the mouth of Tye river. It is a fmall place, contains a tobacco warehouse; is 100 miles above Richmond, and '78 from Philadelphia.

NEW-MARLBOROUGH, a township in Ulster co. New-York. See Markborough.

NEW-MARLBOROUGH, Berkhire co. Maffachuletts. It is 23 miles louthward of Lenox, and 144 S.W. by W. of Bofton.

NEW MARLBOROUGH, a town in King George's co. Virginia, on the weft fide of Patowmae river, 10 miles eaft of Falmeuth.

NEW-MEADOWS River, in the Dif-

mift of M navigable burden a f NEW-N NEW-N necticut, 1 fide of H miles nort of Litchfi Hartford. NEWN New-1 and New NEW-Louisiana French i ide of the north, an from De Turn, an the mout are perfe and crof There w this tow frames, ground v and the with th building water. dens. a fire, w houfes. fide next ed from a raifed which e to the mans, a with a is reafc New-O opulent tages o from th fertile and wh fail of French iflands becom produc countr other more I wealth city. Miffi NEW

wich of Maine, a water of Cafco Bay, pavigable for veffels of a confiderable burden a finall diftance. See Cafco Bay. NEW-MEXICO. See Mexico.

NEW-MILFORD, a post-town of Connecticut, Litchfield co. on the eastern fide of Housatonick river, about 16 miles north of Danbury, 20 fouth-west of Litchfield, and 52 W. by S. W. of Hartford.

NEWNHAM Cape. See Newenham. NEW-NORTH-WALES. See Wales, and New-Britain.

NEW-ORLEANS, the metropolis of Louisiana, was regularly laid out by the French in the year 1720, on the east fide of the river Miffilippi, in lat. 30. 2. north, and long. 89. 53. welt ; 18 miles from Detour des Anglois, or English Turn, and 105 miles from the Balize at the mouth of the river. All the freets are perfectly fraight but too narrow, and crofs each other at right angles. There were, in 1788, 1,100 houfes in this town, generally built with timber frames, railed about 8 feet from the ground with large galleries round them, and the cellars under the floors level with the ground; any fubterraneous buildings would be constantly full of water. Moft of the houfes have gardens. In March, 1788, this town, by a fire, was reduced in five hours to 200 houfes. It has fince been rebuilt. The fide next the river is open, and is fecured from the inundations of the river, by a raifed bank, generally called the levee, which extends from the English Turn, to the upper fettlements of the Germans, a distance of more than 50 mi'es, with a good road all the way. There is reason to believe that in a flort time New-Orleans may become a great and opulent city, if we confider the advantages of its fituation, but a few leagues from the fea, on a noble river, in a most fertile country, under a moft delightful and wholefome climate, within 2 weeks fail of Mexico, and ftill nearer the French, Spanift, and Britifh Weft-India islands, with a moral certainty of its becoming a general receptacle for the produce of that extensive and valuable country on the Miffifippi, Ohio, and its other branches; all which are much more than fufficient to enfure the future wealth, power, and profperity of this city. The veffels which fail up the Miffifippi haul clofe along fide the bank

BARRY MARKET A. 1913 HART A.

All the let

next to New-Orleans, to which they make faft, and take in or difcharge their cargoes with the fame cafe as at a wharf.

300

NEW

NEW-PALTZ, a township in Ulfter co. New-York, bounded casterly by Hudion river, foutherly by Mariborough and Shawangunk. It contains 2,309 inhabitants, including 302 flaves. The compact part of it is fituated on the caffern fide of Wall-Kill, and contains about 250 houfes and a Dutch church. It is 10 miles from Shawangunk, 14 foutherly of Kingfton, 20 fouth-weft of Rhinebeck, and 80 northnorth-weft of New-York.

NEWPORT, a township of Nova-Scotia, in Hants co. on the river Avop. The road from Halifax runs part of the way between this township and Windfor; and has settlements on it at certain distances.

NEWPORT, a township in Cheshire co. New-Hampshire, east of Claremont. It was incorporated in 1761, and contain 780 inhabitants.

NEWPORT, a maritime county of the State of Rhode-Island, comprehending Rhode-Island, Cannonicut, Block, Prudence, and feveral other small islands. It is divided into feven townships, and contains 14,300 inhabitants, including 366 flaves.

NEWPORT, the chief town of this county, and the femi-metropolis of the State of Rhode-Ifland; ftands on the fouth-west end of Rhode-Island, about 5 miles from the fea. Its harbour, (which is one of the fineft in the world) preads weltward before the town. The entrance is easy and fafe, and a large fleet may anchor in it and ride in pertect fecurity. It is probable this may, in fome future period, become, one of the man-of-war ports of the A merican empire. The town lies north and fouth upon a gradual afcent as you proceed eaftward from the water, and exhibits a beautiful view from the harbour, and from the neighbouring hills which lie westward upon the main. Welt of the town is Goat-Illand, on which is Fort Washington. It has been lately repaired and a citadel erected in it. The fort has been ceded to the united States. Between Goat-Ifland and Rhode-Ifland is the harbour. New port contains about 1,000 houfes, built chiefly of wood. It has so houses for public

eaft of trift

Mari-

nire co.

thward

Bofton.

own in

he weft

ablic worthip, 4 for Baptifts, 2 for ongregationalifts, one for Episcopaians, one for Quakers, one for Moravians, and one for Jews. The other public buildings are a flate-house, and m edifice for the public library. The fituation, form and architecture of the fate-house, give it a pleasing appearance. It ftands fufficiently elevated, and a long wharf and paved parade lead up to it from the harbour. Front or Water fireet is a mile in length. Here is a flourishing academy, under the direction of a rector and tutors, who teach the learned languages, English grammar, geography, &cc. A marine ciety was established here in 1 572, for the relief of diffreffed widows and orphans, and fuch of their fociety as may ed relief. This city, far famed for he beauty of its fituation and the falubrity of its climate, is no lefs remarkable for the great variety and excellent quality of fresh fish which the market furnifbes at all feations of the year. No lefs than fixty different kinds have been produced in this market. The excel-ent accomodations and regulations of the numerous packets, which belong to this port, and which ply thence to Providence and New-York, are worthy of notice. They are faid, by European travellers, to be fuperior to any thing of the kind in Europe. This town, although greatly injured by the late war, and its confequences, has a confiderable trade. A cotton and duck manufactory have been lately eftablished. The exports for a year, ending Sept. 30, 1794, amounted to 311,200 dollars. At was first fettled by Mr. William Coddington, afterwards governor, and the father of Rhode-Ifland, with 17 others, in 1639. It is 30 miles S. by E. of Providence, 14 fouthcatt of Briftol, 75 S. W. by S. of Bol-ton, 113 E. N. E. of New Haven, and 192 N. E. by E. of Philadelphia. N. lat. 41. 19. W. long. from Greenwich

NEW

71. 17. NEWFORT, a fmall post town in Newcastle co. Delaware; stuated on the north fide of Christiana Creek, three miles W. of Wilmington. It contains about 200 inhabitants, and carries on a confiderable trade with Philadelphia, in flour. It is 6 miles N. E. by N. of Christiana Bridge, and 31 S. W. of Philadelphia.

NEW

NEWPORT, a township in Luzerne co. Pennfylvania.

NEWFORT, a fmall post-town in Charles co. Maryland, 11 miles S. E. of Port Tobacco, 94 S. by W. of Baltimore, and 195 touth-west of Philadelphia.

NEWPORT. See Ifle of Wight County, Virginia.

NEWPORT, a very thriving fettlement in Liberty co. Georgia, fituated on a navigable creek, 34 miles fouth of Savannah, and 7 or 8 fouth of weft from Sunbury. This place, commonly known by the name of Newport Bridge, is the rival of Sunbury, and commands the principal part of the trade of the whole county. A post-office is kept here.

NEW-RIVER, a river of Tenneffee, which rifes on the north fide of the Alleghany mountains, and running a north eaft courfe enters Virginia, and is called Kanhaway; which icc.

NEW-ROCHELLE, a township in West-Chefter co. New-York, on Long-Island Sound. It contained 692 inhabitants, of whom 89 were flaves, in 1790. In 1796, there were 100 of the inhabitants qualified electors. It is 6 miles S. W. of Rye, and 20 north-easterly of New-York city.

NEW-SALEM, or *Pequettink*, a Moravian settlement, formed in 1786, on the E. fide of Huron river, which runs northward into Lake Erie.

NEW-SALEM, a township in Hampshire co. Massachusetts, bounded E. by the west line of Worcester co. It was incorporated in 1753, and contains 1543 inhabitants. It is 25 miles W. by N. of Boston.

NEW-SALEM, a township in Rockingham county, New-Hampshife, adjoining Pelham and Haverhill.

NEW-SAVANNAH, a village in Burke co. Georgia, on the S. W. bank of the Savannah, 12 miles S. E. of Augusta. NEW-SHOREHAM. See Block-Ifland.

NEW-SMYRNA Entrance, or Molkito Inlet, on the coaft of Florida, is about 11 leagues north-north-weft, 1 weft from Cape Canaverel.

 \odot

NEW-SOUTH-WALES. See Wales and New Britain. NEW-SPAIN. See Mexico. NEW-STOCKBRIDGE. See Stockbridge New. NEW-SWEDELAND, was the name of

of the tern New-York Swedes, a or rather chief town NEW-J NEWTI Middlefex on Charles Bofton. and conta NEWT co, Pennf ladelphia. NEWT ham co. river, ad chufetts, Exeter, 1 was incor 530 inhal NEWT co. Conn of Danbu Haven, So nor h ftands p and was NEWI York, is as far ei wefterly NEWI co. New in the Sc about 8 contains 533 flav NEW Chefter (bitants : NEW New-Yo of Sene ving C which it \$792.0 were ele NEW ter co. NEW Suffex c S. E. o NEW Pennfyl rian chu an acad was fet

of Trer

366

of the territory between Virginia and New-York, when in policition of the Swedes, and was afterwards pofiefied. or rather claimed by the Dutch. The chief town was called Gottenburg.

NEW-THAMES River. See Thames. NEWTON, a pleafant townfluip in Middlefex co. Maffachufetts, fituated on Charles river, and is 9 miles weft of Bofton. It was incorporated in 1691, and contains 1360 inhabitants

NEWTON, a fmall town in Chefter co, Pennfylvania, 22 miles fouth of Philadelphia.

NEWTON, a township in Rockingham co. New Hampfhire, on Powow river, adjoining Amelbury, in Maffachufetts, 10 or 12 miles foutherly of Exeter, and 26 from Portsmouth. It was incorporated in 1749, and contains 530 inhabitants.

NEWTOWN, a post-town in Fairfield co. Connecticut, 9 miles eaft-north-eaft of Danbury, 26 weft-north weft of New-Haven, 61 fouth-weft of Hartford, and So nor h-east of New-York. The town ftands pleafantly on an elevated fpot, and was fettled in 1708.

NEWTOWN, on Staten-Ifland, New-York, is 3 miles N. E. of Old-Town, as far east of Richmond, and 9 fouthwefterly of New-York.

NEWTOWN, a township in Queen's co. New-York, includes all the itlands in the Sound opposite the fame. It is about 8 miles eaft of New-York, and contains 2, 111 inhabitants, including 533 flaves.

NEWTOWN, a township in West-Chefter co. New-York ; of whole inhabitants 276 are electors.

NEWTOWN, a township in Tioga co. New-York, lies between the fouth end of Seneca Lake and Tioga river; having Chemung township east, from which it was taken, and incorporated in 1792. In 1796, 169 of its inhabitants were electors.

NEWTOWN, a township in Gloucester co. New-Jerley.

NEWTOWN, the feat of justice in Suffex co. New Jerfey, is about 10 miles S. E. of Sandyfton.

NEWTOWN, the capital of Bucks co. Pennfylyania. It contains a Prefbyterian church, a ftone gaol, a court houfe, an academy, and about 50 houses. It was fettled in 1725, and is to miles W.

E. by N. of Philadelphia. There a two other townships of this name, th one in Delaware co. the other in that o Cumberland.

NEWTOWN, a fmall town of Virginia, fituated in Frederick co. between the north and fouth branches of Shenandoah river ; 7 miles fouth of Winchefter, and 173 north-north-weft of Richmond.

NEW-UTRECHT, a fmall maritime town of New-York, fituated in King's co. Long-Ifland, opposite the narrows, and 7 miles fouth of New-York city. The whole township contains 562 inha-bitants ; of whom 76 are qualified electors, and 206 flaves.

NEW-WINDSOR, a township of Ulfter co. New York, pleafantly fituated on the W. bank of Hudfon river, just above the high lands, 3 miles fouth of Newburgh, and 6 north of Weft Point. It contains 1819 inhabitants; of whom 261 are qualified electors, and 117 flaves. A valuable fet of works in this town for manufacturing fcythes were deftroyed by fire. In 1795, the legiflature granted the unfortunate proprietor, Mr. Boyd, £.1 500 to enable him to re-eftablish them. The compact part of the town contains about 40 houses and a Prefbyterian church, 64 miles N. of New-York. The fummer refidence of Gov. Clinton was formerly at a rural feat, on the margin of the river, at this place.

NEW-WRENTHAM, Diffrict of Maine, a township 6 miles E. of Penoblcot river, adjoining Orrington, and 15 miles from Buckfton.

NEW YEAR'S Harbour, on the north coaft of Staten Land Ifland, "at the fouth extremity of S. America, affords wood and good water ; was diffeovered Jan. 1, 1775; hence its name. S. lat. 54. 49. west long. 64. 11.

NEW YEAR's Islands, near the above harbour, within which is anchorage at north half welt from the harbour, at the dittance of 2 leagues from it.

NEW YORK, one of the United States of America, is fituated between lat 40. 40. and 45. north, and between long. 73. 10. and 80. wett; is about 350 miles in length, and 300 in breadth ; bounded fouth-easterly by the Atlantic Ocean; east by Connecticut, Maliachuletts, and Vermont; north by Upper Canada; fouth-weft and weft by Pennof Trenton, in New-Jerfey, and 30 N. fylvania, New-Jerfey and Lake Erie. It

fituated outh of of weft mmonly Bridge, mmands e of the is kept enneffee. the Alming a a, and is thip in n Long-92 inhaaves, in to of the It is 6 orth-caft-, a Mo-

Luzerne

wn in

s S. E.

of Bal-

Phila-

t Coun-

r fettle-

1786, on uch runs

Hamped E. by It was contains niles W.

in Rockhire, adin Burke nk of the Luguita. ck-Island. or Mofkito is about , 1 weft Bee Wales

0

ส้าย ขางเก ice Stock-140 the name of

State 1-

is fubdivided into 21 counties as follows, viz. New-York, Richmond, Suffolk, Wefl-Chefter, Queen's, King's, Orange, Ulfter, Dutchefs, Columbia, Renficher, Wafhington, Clinton, Saratoga, Albany, Montgomery, Herkemer, Onondago, Otfego, Ontario, and Tioga. In 1790, this State contained 340,120 inhabitants; of whom 23,324 were faves. Since that period the counties of Renficher, Saratoga, Herkemer, Onondago, Otfego, and Tioga have been taken from the other counties. In 1796, according to the State cenfus, there were 195 townfhips, and 64,017 qualified electors. Eléctors in this State are divided into the following claffes :

NEW

and a second second

It is difficult to afcertain accurately the proportion, the number of electors bears to the whole number of inhabitants in this State. In the county of Herkemer the electors to the whole number of inhabitants was, in 1795, nearly as 1 to 6, but this proportion will not hold through the State. In 1790 the number of inhabitants in the State was, as already mentioned, 340,120, of whom 41,785 were electors. In 1795 the number of electors was 64,017, which, if the proportion between the electors and the whole number of inhabitants be the fame, gives, as the whole number of inhabitants in 1795, 530,177, an in creafe, in 5 years, of 190,057.

The chief rivers are Hudíon, Mohawk and their branches. The rivers Delaware and Sulquehannah, rife in this State. The principal lakes are Otiego, Oneida, George, Seneca, Cayuga, Salt, and Chautaughque. The principal bay is that of York, which fpreads to the fouthward before the city of New-York. The legislature of New-York, flinulated by the enterprizing and active Pennfylvanians, who are competitors for the trade of the weftern country, have lately granted very liberal funs, towards improving thole roads that traverfe the moft fettled parts of the country, and opening fuch as lead into the weftern and northern parts of the State, uniting as far as possible the establishments on Hudíon's river, and the most populous parts of the interior country by the nearest practicable distances. By

NEW

late effablishments of post-roads a fafe and direct conveyance is opened be-tween the most interior western parts of this State, and the feveral States in the. Union: and when the obftructions be-tween Hudfon's river and Lake Ontario are removed, there will not be a great deal to do to continue the water communication by the lakes and through Illinois river to the Miffifippi. New-York, to fpeak generally, is interfected by ridges of mountains extending in a N. E. and S. W. direction. Beyond the Alleghany Mountains, however, the country is level, of a fine rich feil, covered in its natural flate with maple, beech, birch, cherry, black walnut, lo-cuft, hickory, and fome mulberry trees. On the banks of Lake Erie are a few chefnut and oak ridges. Hemlock fwamps are interfperfed thinly through the country. All the creeks that empty into Lake Erie have falls, which afford many excellent mill-feats. The lands between the Seneca and Cayuga Lakes, are repretented as uncommonly excellent, being most agreeably diversified with gentle rifings, and timbered with lofty trees, with little underwood. The legiflature have granted a million and a half acres of land, as a gratuity to the officers and foldiers of the line of this State. This tract forms the military townships of the county of Onondago. See Military Town/bips, and Onondage. East of the Alleghany Mountains, which commence with the Kaat's Kill, on the weft fide of Hudson's river. the country is broken into hills with rich intervening vallies. The hills are cloathed thick with timber, and when cleared afford fine pasture ; the vallies, when cultivated, produce wheat, hemp, flax, peas, grafs, oats, Indian corn, &c. Of the commodities produced from culture, wheat is the principal. Indian corn and peas are likewife raifed for exportation; and rye, oats, barley, &c., for home confumption. The best lands in the State, along Mohawk river, and north of it and weft of the Alleghany Mountains, but a few years ago was mostly in a flate of nature, but has been of late rapidly fettling. In the northern and unfettled parts of the State are plen-ty of moole, deer, bears, fome beavers, martins, and most other of the inhabitants of the foreft, except wolves. The Ballftown, Saratoga, and New Lehanon

non medicin ted ; thele a fpective heat the Salt Spi nefs to that and. The falt is 136lh have been d nah country from which Tame manne from the quantities o A filver mi lipfburg, w Lead is fou fulphur in I spelter, a i glazings, F rious kinds coal mines, petrified w glass in the rious kinds and feveral ftone has a fies with a makes exce factures are pearl aftes. and molaffe manufactu State, havi the ocean, great prop beft cultiva Their exp bifcuit, per ons, board ter, cheefe pork, Bu dity of the 677,700 b ago as the of bread, a increase fu the increal and flour a annually e are receive ticles. Be merated as wool, farf pig-iron, turs, deergany, bees tar, pitch. fugars, mo but moft

a fafe ied beparts of in the ons be-Ontario a great ricomhrough New erfected ng in a Beyond ver, the oil, comaple, nut, loy trees. : a few emlock hrough it emplich af-The Cayuga nmonly diverfimbered rwood. million ratuity line of e milinonda-Onon-Moun-Kaat's s river. is with ills are when vallies. hemp, m, &c. m cul-Indian for ex-, &c., At lands er and eghany to was as been orthern e plencavers, inhabi-The Lehanon

23

non medicinal fprings are much celebra-ted; these are noticed under their re-spective heads. The falt made from the Salt Springs here is equal in good-nels to that imported from Turk's Ifl-and. The weight of a buffel of the falt is 136lb. A foring is reported to have been difcovered in the Sulquehannah country, impregnated with nitre, from which falt-petre is made in the fame manner that common falt is made from the Onondago fprings. Large quantities of iron ore are found here. A filver mine has been worked at Phillipfburg, which produced virgin filver. Lead is found in Herkemer county, and fulphur in Montgomery. Spar, zink or fpelter, a femi-metal, magnez, ufed in glazings, pyrites of a golden hue, various kinds of copper ore, and lead and coal mines, are found in this State, alfo petrified wood, plaster of Paris, ifingglass in sheets, talcs, and crystals of various kinds and colours, flint, albeftos and feveral other foffils. A fmall black stone has also been found, which vitrifies with a fmall heat, and it is faid makes excellent glafs. The chief manufactures are iron, glafs, paper, pot and pearl alhes, earthen ware, maple fugar and molaffes, and the citizens in general manufacture their own cloathing. This State, having a fhort and eafy accels to the ocean, commands the trade of a great proportion of the best settled and beft cultivated parts of the United States. Their exports to the Weft-Indies are, biscuit, peas, Indian-corn, apples, onions, boards, staves, horses, sheep, butter, cheefe, pickled oysters, beef and pork. But wheat is the ftaple commodity of the State, of which no lefs than 677,700 bufhels were exported to long ago as the year 1775, belides 2,555 tons of bread, and 2828 tons of flour. The increase fince has been in proportion to the increase of the population. In wheat and flour about a million bufhels are now annually exported. Weft-India goods are received in return for the above articles. Befides the articles already enumerated are exported flax-feed, cotton, wool, farfaparilla, coffee, indigo, rice, pig-iron, bar-iron, pot-afh, pearl-afh, furs, deer-fkin, log wood, fuftic, maho-gany, bees-wax, oil, Madeira wine, ram, tar, pitch, turpentine, whale-fins, fish, fugars, molaffes, falt, tobacco, lard, &cc. but most of these articles are imported

NEW

for re-exportation. The exports to for-reign parts, for the year ending Sept-30, 1791, 1792, &cc. confifting princi-pally of the articles above enumerated amounted as follows; in 1791, to 2,505,465 dolls. 10 centes 1792-2,535,790 dolls. 25 centes 1793-2,932,370 dolls. 1794-5,442,182 dolls. 10 centes 1795-10,304,580 dolls. 78 cents. This State owned in dons. 78 cents. This State owned in 1792, 46,626 tons of fhipping, befides which fhe finds employment for about 40,000 tons of foreign veffels. There are in this State, two handfomely en-dowed and flourifhing colleges, viz. Co-lumbia, formerly King's College, in the city of New-York, and Union College, at Schenectady. See New-York City, and Schenettady. Befides thefe, there are different in different parts of the State, 14 incorporated Academics, containing in the whole, as many as 6 or 700 ftudents. These, with the effa-blishment of schools, one at least in every diffrict of 4 fquare miles, for the com-mon branches of education, must have the most beneficial effects on the flate of fociety. The fums granted by the legiflature of this State for the encouragement of literature fince the year 1790, have been very liberal and is evineive of the wifeft policy. In March, 1790, the legislature granted to the regents of the Univerfity, who have by law the fuperintendance and management of the literature of the State, feveral large and valuable tracts of land, on the waters of Lakes George and Champlain, and alfo Governor's Ifland in the harbour of New-York, with intent that the rents and income thereof fould be by them applied to the advancement of literature. At the fame time they granted them frooo currency, for the fame general purpose. In April, 1792, they ordered to be paid to the Regents, f1500 for enlarging the library, f200 for a chemical apparatus, £1200 for crecting a wall to support the college grounds, and £ 5000 for erecting a hall and an additional wing to the college : Alfo f1500 annually for 5 years to be difcretionally distributed among the academies of the State. Allo £750, for 5 years, to be applied to the payment of the falaries of additional profeffors. In their feffions, fince 1795, the fums they have granted for the fupport of the colleges, academies, and of common fchools A 2 throughthroughout the State, have been very liberal. The religious fects or denominations in the State are, English Presby-terians, Dutch Reformed, Baptists, Epifcopalians, Friends or Quakers, German Lutherans, Moravians, Methodifts, Roman Catholics, Shakers, a few followers of Jemima Wilkinfon at Geneva, and fome Jews in the city of New-York. The treasury of this State is one of the richeft in the Union. The treafurer of the State reported to the legiflature in Jan. 1796, that the funds amounted to 2,119,068 dollars, 33 cents, which yields an annuity of 234,218 dolls. Befides the above immense fum, there was at that period in the treasury L134,207 198. 101d. currency. The ability of the State, therefore, is abundantly competent to aid public inftitutions of every kind, to make roads, erect bridges, open canals, and pufh eve-ry kind of improvement to the moft defirable length. The body of the Six Nations of Indians inhabit the weftern part of this State. See Six Nations.

The English language is generally fpoken throughout the State, but is not a little corrupted by the Dutch dialect, which is ftill fpoken in fome counties, particularly in King's, Ulfter, Albany, and that part of Orange which lies S. of the mountains. But as Dutch schools are almost, if not wholly discontinued, that language, in a few generations, will probably ceafe to be used at all. And the increase of English schools has already had a perceptible effect in the improvement of the English language. Befides the Dutch and English, there are in this State many emigrants from Scotland, Ireland, Germany, and fome few from France. Many Germans are lettled on the Mohawk, and fome Scots people on the Hudson, in the county of Washington. The principal part of the two former fettled in the city of New-York; and retain the manners, the religion, and fome of them the lan. guage of their respective countries. The French emigrants settled principally at New-Rochelle, and on Staten-Island, and their descendants, several of them, now fill fome of the highest offices in the United States. The weftern parts of the States are fettled and fettling principally from New-England. There are three incorporated cities in this State, New-York, Albany, and Hudfon.

NEW-YORK County, in the above State, comprehending the iffand of New-York, or Manhattan, on which the metropolis flands, and the following fmall iffands: Great Barn, Little Barn, Manning's, Nutten, Bedfow's, Bücking, and Oyfter Iflands. It contained, in 1790, 33,131 inhabitants, including 2369 flaves. Now, in 1796, the number of inhabitants amounts to about 70,000, of whom 7,272 are qualified electors.

NEW-YORK City is fituated on the S. W. point of York ifland, at the confluence of Hudfon and East rivers, and is the metropolis of the State of its name, and the fecond in rank in the Union. The length of the city on East river is upwards of two miles, and rapidly increasing, but falls short of that distance on the banks of the Hudson. Its breadth on an average, is about a mile; and its circumference, 4 or 5 miles. The plan of the city is not perfectly regular, but is laid out with reference to the fituation of the ground. The ground which was unoccupied before the peace of 1783, was laid out in parallel ftreets of convenient width, which has had a good effect upon the parts of the city lately built. The principal ftreets run nearly parallel with the rivers. These are intersected, though not at right angles, by ftreets, running from river to river. In the width of the ffreets there is a great diverfity. Water ftreet and Pearl ftreet, which occupy the banks of East river, are very conveniently fituated for bufinefs, but they are low and too narrow; not admitting in fome places of walks on the fides for foot Broad ftreet, extending paffengers. from the Exchange to the city hall, is fufficiently wide. This was originally built on each fide of the creek, which penetrated almost to the city hall. This ftreet is low, but pleafant. But the most convenient and agreeable part of the city is the Broadway. It begins at a point which is formed by the junction of the Hudfon and Eaft rivers-occupies the height of land between them, upon a true meridional line-rifes gently to the northward-is nearly 70 feet wide -adorned, where the fort formerly ftood, (which has lately been levelled) with an elegant brick edifice, for the accomodation of the governor of the State, and a public walk from the extremity of the the poi lower b alfo wi a numb It term angular alms-ho point, Since 1 city, w the wa the ftre in the I to carr and fo fide. deftroy gant b nerally the bu and De for bu Willia venien retaili ftreets are irr are ge roofs houfes but th moft a edifice ated a its fre which by an lery tende prefe the fa large frout, ration pril build for p form es, t Gern Frier tifts, vians Fren fyna gove and The 2:363

370

he above iffand of on which following ttle Barn, 's, Buckcontained, including the numto about qualified Ĵ 10 ted on the at the conivers, and f its name, the Union. aft river is rapidly inat diffance tion. Its ut a mile; r 5 miles. erfectly re-1 reference und. The pied before ut in paral-, which has parts of the cipal ftreets the rivers. ugh not at nning from idth of the ity. Water roccupy the convenientthey are low ting in fome des for foot extending city hall, is as originally reek, which hall. This t. But the able part of It begins at the junction rs-occupies them, upon fes gently to

70 feet wide ort formerly een levelled) c, for the acrof the State, extremity of the

4 : Bill

the point, occupying the ground of the lower battery which is now demolifhed; alfo with two Epifcopal churches and a number of elegant private buildings. It terminates to the northward, in a triangular area, fronting the bridewell and alms-houfe, and commands from any point, a view of the Bay and Narrows, Since the year 1788, that part of the city, which was buried in ruins during the war, has been rapidly rebuilding, the ftreets widened, ftraigntened, raifed in the middle under an angle fufficient to carry off the water to the fide gutters, and foot-ways of brick made on each fide. At this time, the part that was deftroyed by fire is all covered with elegant brick houfes. Wall freet is generally 50 feet wide and elevated, and the buildings elegant. Hanover fquare and Dock freet are conveniently fituated for bufinefs, and the houfes well built. William ftreet is also elevated and convenient, and is the principal market for retailing dry goods. Many of the other ftreets are pleafant, but most of them are irregular and narrow. The houses are generally built of brick, and the roofs tiled. There are remaining a few houfes built after the old Dutch manner; but the English taste has prevailed almost a century. The most magnificent edifice in this city is Federal Hall, fituated at the head of Broad ftreet, where its front appears to great advantage, in which is a gallery 12 feet deep, guarded by an elegant iron railing. In this gallery our beloved WASHINGTON, attended by the fenate and house of representatives, took his oath of office in the face of Heaven, and in prefence of a large concourse of people affembled in front, at the commencement of the operation of the Federal Conflication, April 30th, 1789. The other public buildings in the city are, three houses for public worthip for the Dutch Re-formed church, four Prefbyterian churches, three Episcopal churches, two for German Lutherans and Calvinifts, two Friends' meeting houfes, two for Baptifts, two for Methodifts, one for Moravians, one Roman Catholic church, one French Protestant church, and a Jews' fynagogue. Befides these there is the governor's house, already mentioned, a handfome building, the college, gaol, and feveral other buildings of lefs note. The city is accomodated with four

markets in different parts, which are furnished with a great plenty and variety of provisions in neat and excellent order.

King's college in the city of New-York, was principally founded by the vo-luntary contributions of the inhabitants of the province, affifted by the general affembly, and the corporation of Trinity Church; in the year 1754, a royal charter (and grant of money) being then obtained, incorporating a number of gentlemen therein mentioned, by the name of " The Governors of the College of the province of New-York, in the city of New-York, in America ;" and granting to them and their fucceffors forever, amongst various other lights and privileges, the power of conferring all fuch degrees as are ufually conferred by either of the English universities. By the charter it was provided that the prefident fhall always be a member of the church of England, and that a form of prayer collected from the liturgy of that church, with a particular prayer for the college, shall be daily used, morning and evening, in the college chapel; at the fame time, no telt of their religious persuafion was required from any of the fellows, profeffors or tutors; and the advantages of education were equally extended to fludents of all denominations. The building (which is only one third of the intended ftructure) confifts of an elegant ftone edifice, three complete ftories high, with four stair-cases, 12 apartments in each, a chapel, hall, library, muleum, anatomi-cal theatre, and a school for experimental philosophy. The college is fituated on a dry gravelly foil, about 1 50 yards from the bank of Hudson's river, which it overlooks, commanding a most extenfive and beautiful prospect. Since the revolution, the legislature passed an act conflituting 21 gentlemen (of whom the governor and lieutenant-governor, for the time being, are members ex officiis) a body corporate and politic, by the name and flyle of "The Regents of the University of the State of New-York." They are entrusted with the care of literature in general in the State, and have power to grant charters of in-corporation for crecting colleges and academies throughout the State, are to vifit these inftitutions as often as they (hall think proper, and report their ftate

Aaa

372. NEW to the legiflature once a year. King's college, which we have already deferib-ed, is now called *Columbia College*. This college, by an act of the legiflature paff-ed in the Ipring of 1787, was put under the care of 24 gentlemen, who are a body corporate, by the name and flyle of "The Truftees of Columbia College in the city of New-York." This body poffers all the powers vefted in the go-vernors of King's college, before the re-volution, or in the regents of the uni-verfity, fince the revolution, to far as their power respected this inftitution. No regent can be a truftee of any parti-No regent can be a truttee of any parti-cular college or academy in the State. The regents of the university have power to confer the higher degrees, and them only. The college edifice has received no addition fince the peace, though the erection of a hall and a wing have been contemplated, and fands for the purpole granted by the legiflature. The annual revenue arising from the effate belonging to the college, exclusive of fome bords which are not at prefent productive, amounts to frags currency. Colum-bia college confifts of a faculties : a faenity of arts and a faculty of physic. The first has a prefident and 7 protessions, and the second a dean and 7 protessors. The students attending both the faculties at the beginning of the year 1795 amounted to 140. The officers of in-firuction and immediate government in the faculty of arts, are a prefident, profellor of mathematics and natural philofonhy, a professor of logic and geograhy, and a profesior of languages. To efe have lately been added a profeffor of chymittry and agriculture, a profesfor of oriental languages, a professor of law, and a professor of the French language. In the faculty of physic, the dean is lecturer on clinical medicine in the New-York hospital; and there are the professorial of botany, of anato-my, of the obsetric art, of materia medica, of the inftitutes of medicine, of furgery, and the practice of physic. These professions afford the necessary instruc-tion in the healing art. The library and muleum were destroyed during the war. Upwards of £800 (of monies granted by the legiflature) have been lately exended in books to increase the library. The philosophical apparatus is new and complete. The government of the city (which was incorporated in 1696) is now

NEW

NEW

in the hands of a mayor, alderman and common council. The city is divided into feven wards, in each of which there is choicn annually by the people an al-derman and an alfiftant, who, together with the recorder, are appointed annual-iy by the council of appointment. The mayor's court, which is held from time to time by adjournment, is in high re-putation as a court of laws. A court of fellion is likewife held for the trial of criminal caules. The fituation of the city is both healthy and pleafant. Sur-rounded on all fides by water, it is refreshed with cool breezes in finmmer, and the air in winter is more temperate than in other places under the fame parallel. This city is effected the most eligible fituation for commerce in the United States. It almost necessarily commands the trade of one half New-Jerfey, molt of that of Connecticut, part of that of Maffachufetts, and almost the whole of Vermont, befides the whole fertile interior country, which is penetrated by one of the largest rivers in America. This city imports most of the goods confumed between a line of 30 miles E. of Connecticut river, and 20 miles weft of the Hudson, which is 130 miles; and between the ocean and the confines of Canada, about 400 miles; a confiderable portion of which is the beft peopled of any part of the United States; and the whole territory contains nearly a million people, or one-fifth of the inhabitants of the Union. Befides, fome of the other States are partially supplied with goods from New-York. But in the ftaple commodity, flour, Pennfylvania and Maryland have exceeded it, the fuperfine flour of those States commanding a higher price than that of New-York ; not that the quality of the grain is worfe, but becaufe greater attention is paid in those States to the inspection and manufacture of that article. In the manufacture likewile of iron, paper, manufacture likewife of iron, paper, cabinet works, &c. Pennfylvania ex-ceeds not only New-York, but all her fifter States. In times of peace, how-ever, New-York will command more commercial bufinels than any town in the United States. In time of war it will be infecure, without a marine force; but a finall number of fhips will be able to defend it from the most formidable attacks by fea. A want of good water is a great inconvenience to the citizens, there there

shore be of the with f doors i head of from a centre zo fee The as this rea of 130 mer d drawn Gar, the bout 3 ter is hogihe fals ha fupply have y view o ago, a parifo partic elegan affecte form t The n and co 10,88 1790, proba There veffels Eaft r violen cent i tides Long tweet creali rivers obltr alway the w entri port -br -fct ofd çonfi ed or fecu New lade N. 1 ton, fron 813

nan and divided th there e an alogether annual-I. The m time high re-A court trial of 1 of the . Surner, and ate than parallel. eligible United nmands y, moth that of hole of ile inteited by merica. e goods niles E. les weft miles ; confines a conthe beft States ; s nearly the ins, fome upplied But in mfylyal it, the nmand_ f Newe grain ttention fpection In the paper, nia ex-all her e, howown in f war it e force ; be able midable d water itizens,

there

NEW

shere being few wells in the city. Moft of the people are fupplied every day with fresh water, conveyed to their with frefh water, conveyed to their doors in cafks, from a pump near the head of Queen fireet, which receives it from a firing almost a mile from the centre of the city. This well is about to feet deep and four feet diameter. The average quantity drawn daily from this remarkable well, is 110 hogheads of 130 gallons each. In fome hot fummer days 216 hogheads have been drawn from it; and what is very fingudar, there is never more or leis than a-bout 3 feet water in the well. The water is fold commonly at three pence a hogthead at the pump. Several propo-fals have been made by individuals to fupply the citizens by pipes; but none have yet been accepted. On a general view of this city, as defcribed 40 years ago, and in its prefent flate, the comparifon is flattering to the prefent age; particularly the improvements in taffe, elegance of manners, and that eafy un-affected civility and politeneis which form the happiness of locial intercourfe. The number of inhabitants in the city and county of New-York in 1756, was ro,881; 1771, 21,863; 1786, 23,614; 1790, 33,131; 1796, 7,272 electors; probably about 70,000 inhabitants. There is no balon for the reception of veffels, but the road where they lie in East river, which is protected from the violence of the fea, by the circumjacent islands. The great rapidity of the tides in the narrow channels between Long-Island and York-Island, and between Long-Ifland and Staten-Ifland, increaled by the water of Hudfon and Eaft rivers, preferves the channel from being obstructed by ice; fo that navigation is always open, except a few days when the weather is uncommonly fevere. The entries from foreign ports only into this port in 171,5 were 941, viz. fhips, 178 -brigs, 309-barques, 9-fnows, 7 -fchooners, 268-floops, 170. Works of defence have been erected here to a confiderable extent, and when completed on the original plan, will afford great fecurity to the city, from enemies' thips. New York city is 95 miles N. E. of Phi-ladelphia, 127 S. W. of Hartford, 197 N. E. of Baltimore, 252 S. W. of Boi-ton, 375 from Portland, in Maine, 373 from Richmond, 620 from Fayetteville, 913 from Charletton, and 2,020 from AUGARA

Savannah. N. lat. 40. 41. 8. W. long

74. 9. 45. NEW-YORK, an Indian town of the Creek nation, fituated on Tallapoole river, in Georgia; and fo named by Col. Ray, a New-York British loyalist. NEW-YORK *Mand*, on which the ci-ty of that name stands, is about 15 miles

long, and does not extend two in any part in breadth. It is joined to th part in breadth. It is joined to the main land by a bridge, called King's Bridge, 15 miles N. of New-York city. NEYBE, or Neive, a fertile plain on the jouth fide of the island of St. Domin-

go; bounded E. by the bay and river of its name, on the W. by the river of Dames, and the Pond of Henriquella. It contains about 80 fquare leagues, abounds with game, and is a choir fpot for flamingoes, pheafants, and royal or crowned peacocks. Thefe laft have a more delicate flavour and more brilliant plumage than the peacocks of Europe. Nine leagues from the W. bank of the Neybe is the town, containing about Neybe is the town turn out 300 men fit to bear arms. This town is 15 leagues W. by N. of Azu, and 16 from the point where the line of demarcation cuts Brackish Pond. This territory produces a fort of plaister, tale, and fosfil falt. The natural re-production of the falt is fo rapid, that a pretty large hollow is abfolutely filled up again in the course of a year. The river might be rendered navigable for finall craft, and the plain is able to afford eli-

gible fituations for 1 50 fugar plantations. NIAGARA *River* and *Falls*. Niaga-ra river, connects the N. E. end of Lake Erie with Lake Ontario, and is about 30 miles in length, from Fort Erie to Niagara Fort, and forms a part of the boundary between the United States and Upper Canada. It receives Chip-peway or Welland river from the W. and Tonewanto Creek from the E. and embofoms. Great and Navy Iflands. Fort Slufher ftands on the E. fide of this river near Navy Island. The Falls, in this river, are opposite Fort Sluther, about 7 or 8 miles south of Lake Cntario, and form the greatest curiofity which this, or indeed any other country, affords. In order to have a tolerable idea of this ftupendous fall of water, it will be neceffary to conceive that part of the country in which Lake Erie is fituated, to be elevated above that which Aa3

374

which contains Lake Ontario, about 300 feet ; the flope which separates the upper and lower country is generally very freep, and in many places almost perpen-dicular; it is formed by horizontal ftrata of ftone, great part of which is lime-ftone. The flope may be traced by the north fide of Lake Ontario, near the bay of Torrento, round the may of the set the bay of Torento, round the welt end of the Lake; thence the direction is generally eaft. Between Lake Ontario and Lake Eric it croffes the ftrait of Niagara and the Genneffee river; after which it becomes loft in the country towards Seneca Lake. It is to this flope the country is indebted both for the Cataract of Niagara and the great Falls of Gennefice. The Cataract of Niagara, fome have fuppoled, was formerly at the northern fide of the flope near the landing; and that from the great length of time, and the quantity of water, and diftance which it falls, the folid ftone is worn away for about feven miles up torards lake Erie *, and a chaim is formed which no perfon can approach with-out terror. Down this chaim the water rufhes with a most aftonishing noife and velocity, after it makes the great pitch. Here the fancy is conftantly engaged in the contemplation of the most romantic and awful prospect imaginable; when the eye catches the falls, the contemplation is inftantly arrefted, and the beholder admires in filence. The river is about 742 yards wide at the falls. The perpendicular pitch of this valt body of water produces a found that is frequently heard at the diftance of 20 miles, and in a clear day, and fair wind, 40 and even 50 miles. A per ceptible, tremulous motion in the earth is felt for feveral rods round. A heavy cloud or fog is constantly afcending from the falls, in which rainbows may always be feen when the fun fhines. This fog or fpray, in the winter fealon, falls upon the neighbouring trees, where it congeals, and produces a most beautiful chrystaline appearance : this remark is applicable alto to the falls of Genneffee. It is conjectured that the water muft fall at leaft 65 feet in the chaim; the perpendicular pitch at the cataract

* Gen. Lincoln who vifited and examined thefe falls, in 1794, fays, "On a careful examination of the banks of the river, there appears to be no good foundation for this opinion."

is 1 50 feet ; other accounts fay only 137 feet : to these add 58 feet, which the water falls the laft half mile immediately above the falls, and we have 273, which the water falls in the diffance of 74 miles. Animals for imming near the Rapids above the great Cataract are inftantly hurried to deftruction. Just below the Great Pitch, the water and foam may be feen puffed up in large spherical figures ; they burft at the top, and project a column of the fpray to a prodigious height, and then fubfide, and are fucceeded by others which burft in like manner. This appearance is most remarkable about half way between the ifland that divides the falls and the weft fide of the ftrait, where the largeft column of water defcends. The defcent into the chaim of this stupendous cataract is very difficult, on account of the great height of the banks; but when once a perfon has de-fcended, he may go up to the foot of the Falls, and take fhelter behind the defcending column of water, between that and the precipice, where there is a space fufficient to contain a number of people in perfect fafety, and where conversation may be held without interruption from the noife, which is lefs here than at a confiderable diftance. On Christmas 1795, a fevere flock of an earthquake was felt here, and by which a large piece of the rock that forms the famous cataract was broken off.

NIAGARA, a fort and post town in the State of New-York, fituated on the E. fide of Niagara river, at its entrance into Lake Ontario, and opposite to Newark, in Canada. Niagara Fort is a most important post, and fecures a greater number of communications, through a large country, than probably any other pals in interior America. It is about 9 miles below the cataract, 80 N. W. of Williamfburgh op Genneffee river, 370 N. W. of Philadelphia, and 560 W. by N. of Botton. N. lat. 43. io. W. long. 79. The fort was built by the French about the year 1725, and was delivered up to the United States, according to the treaty of 1794, by the British, in 1796. Although it is a degree N. of Bofton, yet the featon is quite as mild here as at that town, and vegetation quite as early and forward. It is thought that the climate meliorates in the fame latitude as one proceeds from the Atlantic weftward. 1.14

NICARAGUA,

NICARA of New-Spa ence. Its 20 miles fr co. It fe ocean, by a which divid from Cofta towns on th perable imp ties of Gra The first is 8. N. and miles wefty that ftands the lake. lake, and ir The lake i ands, and alligators. to the fea, glares. N. NICARA Mexico, h the North on the S. S. W. It 120 broad temperate, quantities chocolate. garden of and fruitfu vifited it, radife. NICHO extremity in the We of the tow monly cal caft of Ca the ifland (eaft by no with this into the 1

> Leogane. NiCHO Peru, in S St. John, the river of Port (John's h wood nor NICKA S. E. fide of a large eaft of Half way

Town of

GUA,

NICARAGUA, a lake in the province New-Spain, 117 leagues in circumfer-

of New-Spain, 117 leagues in circumference. Its weftern part is not more than 20 miles from the S. W. coaft of Mexi co. It fends its waters eaft to the ocean, by a spacious river of its name, which divides the province of Nicaragua from Cofta Rico. This renders the towns on the banks of the lake of confiperable importance, particularly the cities of Granada, Leon, and Nicaragua. The first is on the fouth fide in lat. 11. 8. N. and long. 85. 12. W. and is 45 miles weftward of the city of Nicaragua, that stands at fome distance fouth from the lake. Leon is at the west end of the lake, and in lat. 12. N. and long. 87. W. The lake is interfperfed with feveral iflands, and full of fifh, but infefted with alligators. Nicaragua river empties into the fea, opposite to the island of Monglares. N. lat. 11. 40. W. long. 82. 47.

NIC

NICARAGUA, a maritime province of Mexico, having Honduras on the north, the North Sea on the eaft, Cofta Rico on the S. E. and the South Sea on the S. W. It is about 400 miles long, and 120 broad. The air is wholefome and temperate, and the foil fertile, producing quantities of fugar, cochineal, and fine chocolate. This is confidered as the garden of America; being fo pleafant and fruitful, that when the Spaniards first vifited it, they called it Mahomet's paradile.

NICHOLAS, *Cape St.* the north-weft extremity of the ifland of St. Domingo, in the Weft-Indies. It is a leagues W. of the town of its name, but more commonly called *The Mole*, 9 or 10 leagues eaft of Cape Mayzi, at the eaft end of the ifland of Cuba, and 46 leagues northeaft by north of Cape Dame Marie, and, with this laft cape, forms the entrance into the large bay called the Bight of Leogane. See *The Mole*.

NICHOLAS, Part St. on the coaft of Peru, in S. America, lies north of Port St. John, about a league to leeward of the river Maica, and 6 leagues S. S. E. of Port Cavallo. It is fafer than St. John's harbour, but affords neither wood nor water.

NICKAJACK, an Indian town on the S. E. fide of Tennessee river, at the point of a large bend, about 26 miles northeast of the Creek's Crossing Place. Half way between these lies the Crow Town on the same fide of the river.

NICKER, one of the fmall Virgin Iflands, fituated between Anegada and Virgin Gorda, on the latter of which it is dependent. N. lat. 18, 20, W. long. 65, 5,

pendent. N. lat. 18. 30. W: long. 65. 5. NICHOLA, or Nichola Town Gut, on the north-east coast of the island of St. Christopher's.

NICOYA, or St. Lucar, a town of Cofta Rico, in the kingdom of Mexico, North-America, having a harbour on a bay of the North Pacific Ocean, in lat. 10. 20. N. and long. 88. 10. W. About 10 leagues is the bay of Salinas, from whence the inhabitants of this place procure and fend to Panama the purple juice of a shell-fish found in it. befides falt, honey, maize, fowls and wheat; and here is also a pearl fifthery. The town is up within the land, but thips ride in the river Cipanfo, 2 leagues to the N. W. from the island of Chira, to take in goods from it ; which river is navigable for large periaguas that bring down the goods to the fhips. The ifland of Chira affords plenty of fresh water and provisions.

NICTAY, a river of Nova-Scotia, which waters the township of Annapolis; on its banks are quantities of bog and mountain ore. A bloomery has been crefted in the town.

NICUESA; Gulf of, is on the caft coaft of the country of Honduras, on the Spanish Main, having Cape Gracias a Dios for its north limit, and Cape Blanco, on the fouth; Catharine, or Providence, is due caft from it.

NIEBE, or Neybe, a bay and river on the fouth coaft of the ifland of St. Domingo. The bay is fituated at northnorth-east from Cape Beata. N. lat. 18. 3. W. long. 73. 46.

NIEVA Island, lies fouth-weft of Miftake Bay, and on the north-east fide of Hudson's Straits.

NIEVA TERRA, near the eaft end of Hudion's Straits, in North-America, in lat. 62. 4. N. and long. 67. 7. W. and has high water on the fpring-tide days at 50 min. paft 9 o'clock.

NIGANICHE, an ifland on the coaft of Cape Breton Ifland, and in the fouth part of the Gulf of St. Lawrence, is to the fouthward of a cape about 4 leagues fouth-fouth-weft of Achepe harbour, and 8 leagues from North Cape.

NIGUA, a river on the fouth fide of the island of St. Domingo. Its mouth is 7 leagues east of the Nisao. The A a 4 rivers

375

rivers Nigua and Jayna are not very far apart. But as they advance from their fprings, they recede from each other, the former running wettward from the latter. Between them lies an extensive and fettile plain. The quantity of pure gold that was dug from its cavities, its fugar, cocca, indigo, and other plantations, paid duties of a greater amount than those now paid by all the Spanish part of the island put together. All these rivers might be easily rendered mavigable. The parish and small town of Nigua contain about 2,500 persons, partly free people of colour.

NINETY-SIX, a diffrict of the upper country of South-Carolina, weft of Orangeburg diffrict, and comprehends the counties of Edgefield, Abbeville, Laurens, and Newbury. It contains 33,674 white inhabitants, fends 12 reprefentatives and 4 fenators to the State legiflature, 3 of the former and one of the latter for each county, and one member to Congress. It produces confiderable quantities of tobacco for exportation. Chief town, *Cambridge*, or, as it was formerly called, *Ninety-Six*, which is 60 miles weft by north of Columbia, 147 north-weft of Charlefton, 49 north of Augusta in Georgia, and 752 from Philadelphia. In May, 1781, this town was closely belieged by Gen. Greene, and bravely defended by the British, commanded by Col. Cruger.

NIPECON, a large river which empties into Lake Superior, from the northward. It leads to a tribe of the Chippewas, who inhabit near a lake of the fame name. Not far from the Nip. gon is a finall river, that, juft before it enters the lake, has a perpendicular fall, from the top of a mountain of 600 feet, It is very narrow, and appears like a white garter fulpended in the air.

NIPISSING Lake is north-eaft of Lake Huron, and connected with it by French river.

NIPISIGUIT, a finall village of New-Brunfwick, on the fouthern fide of Chaleur Bay, inhabited by Roman Catholics; above 12 leagues W. of Caraquit Ifland; hetween which and Point Malanette, are the capes of Poiquehaw. At this village a number of coafting traders touch during the fummer, where they purchafe of the inhabitants cod-fifth and falmon, as allo feathers, peltry, and fome furs.

alfo feathers, peltry, and fome furs. NIPISSINS. Indians inhabiting near

the head waters of the Ottowas river. Warriors, 300.

NISAO, a river which rifes in the centre of the ifland of St Domingo, and falls into the fea on the fouth fide, and on the weftern fide of the point of its name; 7 leagues W. of Nigua river.

NISQUEUNIA, a fettlement in the State of New-York, above the city of Albany. This is the principal feat of the fociety called Shakers. A few of this fect came from England in 1774; and a few others are featured in different parts of the country.

NITTANY Mountain, in Pennfylvania, is between the Juniatta and the W. branch of Sufquehannah river.

NIVERNOIS, a large bay at the eaft end of Lake Ontario.

NIXONTON, a post-town of N. Carolina, and capital of Pafquotank county; lies on the northern water of Albemarle Sound, and contains a court-house, gaol, and a few dwelling-houses. It is 28 miles N. E. of Edenton, and 468 S. W. of Philadelphia.

NOBLEBOROUGH, a township in Lincoln co. District of Maine, incorporated in 1788, and contains 516 inhabitants. It is 10 miles S. E. of New-Castle, and 192 N. E. of Boston.

NOBLEBOROUGH, a township in the north-eastern part of Herkemer county, New-York, fituated on the north western fide of Canada Creek.

NOCKAMIXON, a township in Buck's co. Pennfylvania.

NODDLE's Ifland, a finall pleafant and fertile island in Boston harbour, Massachusetts. It is about 2 miles east-northeast of the town, on the Chelsea shore. It is occupied as a farm, and yields large quantities of excellent hay.

NODWAY, a river or rather a long bay which communicates with James' Bay, at the S. E. extremity of Rumert's river

at the S. E. extremity of Rupert's river, NOIR, or Black River, in Louisiana, runs southward, and joins Rogue or Red River; which see.

Red River; which fee. NOIR, Cape, on the S. W. coaft of the ifland of Terra del Fuego, at the entrance of the Straits of Magellan. S. lat. 54. 30. W. long. 73. 13.

NOIR, Cape, or Black Cape, on the northern fide of Chalcur Bay, is about 7 leagues W. N. W. of Bonaventure,

NOIX, Ifte au, or Nu: Ifte, a fmall file of 50 acres, near the north end of Lake Champlain, and within the province of Lower Lower (a garrili about 5 La Cole and IZ NOL part of runs W ver, abo Near th College NOL ver in] an infer NON W. of 3 miles to Dul 41.15 Noi S. E. c to Bell coaft o about : a larg eaft fid 35. W are in freque is fron Experi in dan is the to the vifit it prefer Porto No of M fic Oc a littl Cance Guad long. No co. D fea th and r dinar No of the foul more one p No north bo, t N ands

376

was river.

es in the Domingo, outh fide. point of gua river. at in the he city of bal feat of A few of in 1774 ; in differ.

'ennfylyaid the W.

at the eaft

N. Carok county; Albemarle ufe, gaol, It is 28

68 S. W.

vnfhip in incorpo-6 inhabiof Newon. hip in the

r county, with weft-

in Buck's

eafant and r, Maffaaft-northfea fhore. nd yields long bay nes' Bay, rt's river. ouifiana, logue or . coaft of , at the ellan. S.

r, on the is about aventure. fmall ifle l of Lake ovince of Lower

Lower Canada. Here the British have ! a garrifon containing 100 men. It is about s miles N. N. E. of the mouth of La Cole river, 20 N. of Ifle La Motte, and 12 or 15 fouthward of St. John's.

NOLACHUCKY, a river in the eaftern part of the State of Tenneffee, which runs W. S. W. into French Broad river, about 26 miles from Holftein river. Near the banks of this river Greenville College is eftablished.

NOLIN Creek, a branch of Green river in Kentucky. The land here is of an inferior quality.

NOMAN's Land Island, lies a little S. W. of Martha's Vineyard, and is about 3 miles long and 2 broad. It belongs to Duke's co. Maffachufetts. N. lat. 41. 15. W. long. 71. 5.

NOMBRE DE DIOS, a port to the S. S. E. of the cape to the eaftward of Porto Bello, on the Spanish Main, or N. coaft of S. America, at the diftance of about 7 leagues. It is at the bottom of a large deep bay, being wide to the eaft fide in lat. 9. 43. N. and long. 78. 35. W. The iflands called Baftimentos are in this bay. Large veficls feldom frequent this part now, although there is from 5 to 8 fathoms and clean ground. Experience pointed out that they were in danger of foundering at anchor, fuch is the fury with which the fea pours into the bay. Those veffels that now vifit it, if their bufinefs require any ftay, prefer riding at the Baltimentos, or at Porto Bello.

NOMBRE DE DIOS, on the W. coaft of Mexico, fituated on the North Pacific Ocean, is a large and populous town, a little to the northward of the tropic of Cancer, and 20 leagues to the north of Guadalaxara. N. lat, 23. 38. W. long. 104.

NONESUCH, a river of Cumberland co. District of Maine. It passes to the fea through the town of Scarborough; and receives its name from its extraordinary freshets.

NONESUCH, a harbour at the E. end of the island of Antigua. The road is foul and full of rocks; and it has not more than 6 or 8 feet water, except in one place, which is very difficult. NOORT Point, on the coalt of Chili, is the

north point of the bay or port of Coquimbo, the other is called Point Tortugas. NOOHEEVA, one of the Ingraham Iflands, faid to be the parent of them all, 377

fituated about 10 leagues S. W. of Ooahoona. Capt. Roberts named it Adams : it is the fame which Ingraham called Federal Island. The lat. of the body of the ifland is 8. 58. S. and nearly in the fame meridian with Wooapo, between 140. and 140. 10. W. long. from Greenwich. All accounts of the natives concurred, fays Capt. Roberts, in reprefenting it as populous and fruitful, and to have a large bay with good anchorage.

NOOTKA, or King George's Sound. on the N. W. coaft of North-America. is very extensive. That part of it where the fhips under Capt. Cook anchored. lies in lat. 49, 16. N. and long. 1 26. 42. W. from Greenwich. Capt. Cook judged the found to occupy a degree and a half in latitude, and two of longitude. exclusive of its arms and branches unexplored. The whole found is furrounded by high land, in many places broken and rugged, and in general covered with wood to the very top. The natives were numerous and were in polfeffion of iron and beads ; which probably were conveyed to them across the continent from Hudion's Bay. They are rather below the middle fize, and befmear their bodies with red paint, but their faces are bedaubed with various colours. The Strait de Fuego encompaffes the large clufter of iflands among which this found is fituated. See Fuca. Pintard, Washington Islands, and North-Welt Coaft. It was formally taken poffeffion of by Lieutenant Pearce of the British navy, in 1795, in the name of his Britannic Majefty.

NORD, Rio del, or Rio Bravo. See North River, in the gulf of Mexico.

NORFOLK, a populous maritime county of Maffachuletts, lately taken from the fouthern part of Sutfolk co. and lies to the fouthward around the town and harbour of Bofton. It contains 20 townships, of which Dedham is the feat of juffice. Number of inhabitants 24,280.

NORFOLK, a populous county of Virginia, bounded north by James's river, which divides it from Warwick. It contains 14,524 inhabitants, including 5,345 flaves.

NORFOLK, a port of entry and post- 37/. town and feat of justice in the above county, on the east fide of Elizabeth river, immediately below the confluence of the eaftern branch. It is the most confiderable

378

confiderable commercial town in Virgiginia. The channel of the river is from 350 to 400 yards wide, and at common ood tide has 18 feet water up to the town. The harbour is fafe and commodious, and large enough to contain 300 fhips. It was burnt on the aft of January, 1776, by the Liverpool man of war, by order of the British governor Lord Dunmore; and the lofs amounted to £300,000 fterling. It now contains about 500 dwelling-houfes, a courthouse, gaol, an epilcopal and methodift church, a theatre, and an academy. In 1790, it contained 2,959 inhabitants, including 1294 flaves. The town is governed by a mayor and feveral aldermen. It carries on a brick trade to the Weft-Indies, Europe, and the different States, and conftitutes, with Portfmouth, which flands on the opposite fide of the ziver, a port of entry. The exports for one year, ending Sept. 30th, 1794, amounted to 1,660,752 dollars. A canal. of 16 miles in length, is now cutting from the north branch of Albemarle Sound in. N. Carolina, to the waters of the S. branch of Elizabeth river. It will communicate with Elizabeth river miles from Norfolk. Merchant vefiels of the largest fize may go within a mile from the mouth of the canal ; and here, the water being fresh, the worm, which does fuch damage to veffels in Norfolk and Portimouth, will not affect them. It is 114 miles E. S. E. of Richmond, 54 from Williamfburgh, 30 N. E. of Suffolk, and 389 S. by W. of Philadelphia. N. lat. 36. 55. W. long. 76. 28.

NORFOLK, a townfhip in Litchfield co. Connecticut, 15 miles N. of Litchfield, on the Maffachuletts line.

NORMAN, Cape, on the welt coaft of Newfoundland ifland, is on the gulf of St. Lawrence, and the weitern entrance of the narrow bay of Mauco, 20 leagues from Cape Ferrol. N. lat. 51. 39. W. long 55. 58. High water at full and change days at 9 o'clock.

NORONHA Island, Ferdinando, in the S. Pacific Ocean, laid down in lat. 3. 56. fouth, and long 32. 38. weft. Cap-tain Cook, in his tecond voyage, looked for it in long. 32. 5. but did not find it. NOREDGEWALK, or Norridgewock, a post-town in Lincoln co. on Kenne-

Bofton, and 587 north-eaft of Philadelphia. The Indian town of this name ftood about 40 miles above Fort Halifax, where Kennebeck river, as you afcend it, after taking a fouth-weltward courfe, turns to the northward, and forms a point where the town flood. It was deftroyed by a party under Col. Harman, in 1724.

NORRITON, the principal town in Montgomery co. Pennfylvania, is about 20 miles N. W. of Philadelphia, on the N. bank of the Schuylkill, having about 20 houles a court-houle and gaol, and a handfome edifice of ftone for the prefervation of records, and an obfervatory. This town was the refidence of that celebrated philosopher and philanthrophift, Dr. David Rittenboufe. In his Obfervatory, near his manfion houfe, he was interred, agreeably to his requeft, June, 1796. His tomb ftone contains. nothing but his name and the simple record of the days and years of his birth. and death. "Here, (fays the elegant writer of his eulogy, Dr. Ru/b) shall the philosophers of future ages refort to do homage to his tomb, and children yet unborn thall point to the dome which covers it, and exultingly fay, " There lies our Rittenhoufe."

NORTH-AMERICA comprehends all that part of the continent of America which lies N. of the ifthmus of Darien, extending N. and S. from about the 10th degree of N. latitude to the North Pole; and E. and W. from the Atlantic to the Pacific Ocean, between the 57th and 168th degrees of W. longitude from Greenwich. Beyond the 70th degree N. lat. few discoveries have been made. North-America was discovered in 1495, in the reign of Henry VIII. by John Cabot, a Venetian; and was then thickly inhabited by Indians. It is now supposed that there are not more than two millions and an half of the Aborigines in North and South America. In July, 1779, Capt. Cook proceeded as far as lat. 71, when he came to a folid body of ice from continent to continent. The valt tract of country, bounded W. by the Pacific Ocean, S. and E. by California, New-Mexico and Louifiana-the United States, Can da and the Atlantic Ocean, and exbeck river, Maine, incorporated in 1788, and contains 376 inhabitants. It is 10 miles weft of Canaan, 339 N. by E. of French, and fome other European fettlements

tlements exc by various n The Indian country wit and Britifh North-Ame dians, belor to Denmark rican States East and W the Miffifip boundaries/ ico, and (claims all th ropeans, ly States, exc longs to I part is the ed States. and States, ing table.

long

Weft

New

Upper

Lower

Newfo

Cape

New .

Nova-

St. Jo

Verm

New-

Maffa

Diftri

Rhod

Conne

New-

New-

Penní

Delav

Mary Virgi

Kent

North

South

Geor Tenn Terri

to.

Britiff Prov

America

States of

United

iladelname Haliou af. itward and ftood. r Col. wn in about on the about and a e preatory. nat centhro-In his afe, he equeft, Intains fimple s birth legant) fhall fort to nildren dome y fay, ehends merica)arien, ut the North Atlanen the gitude : 70th re been overed II. by is then is now e than Aborinerica. receded o a foto conuntry, Ocean, Mexi-States, ind exntry is British,

an fet-

ements

NOR

elements excepted) is inhabited wholly by various nations and tribes of Indians. The Indians also posses large tracts of country within the Spanish, American, and British dominions. Those parts of North-America, not inhabited by Indians, belong (if we include Greenland) to Denmark, Great Britain, the American States, and Spain. Spain claims East and West Florida, and all W. of the Miflifippi, and S. of the northern boundaries of the Louisiana, New Mexico, and California. Great Britain claims all the country innabited by Europeans, lying N. and E. of the United States, except Greenland, which belongs to Denmark. The remaining part is the territory of the Sixteen United States. The particular provinces and States, are exhibited in the following table.

ABLE.

Guiden and Chine Bard

anner a car anner anne	6 P	Notes
Be-	Countries, Pro- vinces, and	Number of Inbabit-
long to.	States.	ants.
ar \	stand water state	and Environment
Wef	-Greenland.	10,0000
AL		
(New	Britain	unknown
Upper-Canada Lower-Canada		20,000
		130,000
8 New	foundland	7,000
Cape	Breton Ifland	1,000
New	Brunfwick	35,000
Nova	-Scotia .	各人的新闻的问题
[St.]	ohn's Island S in	1783 5,000
(Vern	nont	85,539
New	Hampfhire	141,885
	achuletts 2	378,787
	ict of Maine S	96,540
	le-Ifland	68,825
	ecticut	237,946
	York	340,120
A New	-Jerley	184,139
Penn	fylvania	434,373
Dela		59,094
	y and	319,728
Virg	inia de la contra	747,610
E Ment	ucky	73,677
Nort	h Carolina h-Carolina	393,751
		249,073
Geor	effee, in 1795,	82,548
a em	ience, in 1795,	//,400

NOR 379

Eaft-Florida Weft-Florida Louisiana Prov New-Mexico P California

Mexico, or New-Spain.

NORTHAMPTON, a large uneven co. of Pennfylvania; fituated in the N. E. corner of the State on Delaware river, which feparates it from the State of New-Jerfey and New-York. It is divided into 27 townships, and contains 24,250 inhabitants.

NORTHAMPTON, a township in Buck's co. Pennfylvania.

NORTHAMPTON, a town in Northampton co. Pennfylvania, on the S. W. bank of Lehigh river, 5 or 6 miles S. W. of Bethlehem.

NORTHAMPTON, a co. of Halifax diffrict, N. Carolina, bounded north by the Stare of Virginia, containing 9,981 inhabitants, including 4,409 flaves.

NORTHAMPTON, a maritime co. of Virginia, fituated on the point of the peninfula, which forms the E. fide of the entrance into Chefapeak Bay. It has the ocean E. and Accomack co. on the north. Its fouthern extremity is Cape Charles, in lat. 37. 11. N. and long. 75. 57. W. off which is the imall ifland called Smith's ifland. This county contains 6,889 inhabitants, including 3,244 flaves. The lands are low and fandy.

NORTHAMPTON Court-Houfe, in the above co. where a post-office is kept, is 40 miles S. by W. of Accomack court-houfe, 43 north-east of Norfolk, and 239 fouth of Philadelphia.

NORTHAMPTON, a respectable posttown and capital of Hamphire co. Maffachufetts, fituated within a bend of Connecticut river, on its W. fide, 40 miles north of Hartford, in Connecticut and 100 W. of Bolton. It contains a fpacious congregational church, a courthouse, gaol, and about 250 dwellinghouses, many of which are genteel buildings. Its meadows are extensive and fertile; and it carries on a confiderable inland trade. This township was incorporated in 1685, and contains 1,628 inhabitants.

NORTHAMPTON, a townfhip in Burlington co. New-Jerfey, which contains about 56,000 acres, half of which is under improvement, the other half is moftly

mofily pine barren. The chief place of the townfhip is called Mount Holly. It contains about 150 houfes, an Epifcopal church, a Friend's meeting-houfe, and a market-houfe. It is 22 miles from Trenton, and 20 from Philadelphia. See Mount Holly.

NORTHBOROUGH, a township in Worcester co. Massachusetts, formerly the northern part of Westborough. It was incorporated in 1760, and contains 619 inhabitants. It is 10 miles E. of Worcester, and 36 W. of Boston.

NORTHERIDGE, a township in Worcefter co. Massachus, taken from Uxbridge, which bounds it on the S. It was incorporated in 1772, and contains 569 inhabitants. Blackstone river runs through this town. It is 12 miles S. by E. of Worcester, and 45 S. W. of Boston.

NORTH-CAROLINA, one of the United States, is bounded N. by Virginia; E. by the Atlantic Ocean; S. by S. Garolina, and W. by the State of Tennefice. It lies between 33. 50, and 36. 60. W. lat. and between 76. 8. and 83. 8. W. long. being about 450 miles in length) and 180 in breadth, containing about 3:,000 fquare miles. The districts of this State are claffed in three divisions, viz. The Eastern diffricts, Edenton, Newbern, and Wilmingtonthe Middle Diffricts, Fayetteville, Hillfborough, and Halifax-and the Western diffricts, Morgan and Salifbury. The eaftern diffricts are on the lea-coaft, ex. tending from the Virginia line fouthward to S. Carolina. The five others cover the whole State, W. of the maritime districts; and the greater part of them extend acrofs the State from N. to S. These districts are subdivided into 58 counties which contained, in 1790, 303,751 inhabitants, of whom 100,571 were flaves. The chief rivers of N. Carolina are Chowan and its branches, Roanoke, Tar, Neus, and Cape Fear or Clarendon. Moft of thefe and the finallcritivers have bars at their mouths ; and the coast furnishes no good harbours except Cape Fear. There are two remarkable fwamps in this State, the one in Currituck co. the other on the line between this State and Virginia. See Currituck County and Difmal. The moft remarkable founds are Albemarle, Pamlico and Core Sounds-the capes, Lookout, Hatteras and Fear; which are def-

cribed under their refpective names. Newbern is the largeft town in the State ; the other towns of note are Edenton. Wilmington, Halifax, Hillfborough, Salifbury, and Fayetteville; each of which have been, in their turns, the feat of the general affembly. Raleigh, fituated near the centre of the State, has lately been effablished as the metropolis. N. Carolina, in its whole width, for 60 miles from the fea, is a dead level. A great proportion of this tract lies in foreft, and is barren. On the banks of fome of the rivers, particularly of the Roanoke, the land is fertile and good. Interfperied through the other parts, are glades of rich fwamp, and ridges of oak land, of a black, fertile foil, Sixty or eighty miles from the fea, the country rifes into hills and mountains, as in S. Carolina and Georgia. Wheat, rye, barley, oats and flax, grow well in the back hilly country. Indian corn and pulfe of all kinds, in all parts. Cotton and hemp are also confiderably cultivated here, and might be raifed in much greater plenty. The cotton is planted yearly : The falk dies with the froft, The labour of one man will produce rooo pounds in the feeds, or 2 50 fit for manufacturing. A great proportion of the produce of the back country, confifting of tobacco, wheat, Indian corn, &c. is carried to market in S. Carolina and Virginia. The fouthern interior counties carry their produce to Charleftown, and the northern to Petersburg, in The exports from the lower Virginia. parts of the State, are tar, pitch, turpentine, rofin, Indian corn, boards, fcantling, flaves, fhingles, furs, tobacco, pork, land, tallow, bees-wax, myrtle-wax, and a few other articles, amounting in the year, ending September 30th, 1791, to 524,548 dollars. Their trade is chiefly with the Welt-Indies and the northera States. In the flat country near the fea-coast, the inhabitants, during the fummer and autumn, are fubject to intermitting fevers, which often prove fatal, as bilious or nervous fymptoms prevail. The western hilly parts of the State are as healthy as any part of America. That country is fertile, full of fprings and rivulets of pure water. Autumn is very pleafant, both in regard to the temperature and ferenity of the weather, and the richnels and variety of the vegetable productions, which the fealon Galfon affor in fome yes to continue is in the be Indian cor The lar plains, in univerfally handfome t pine of the may be cal N. Carolin pentine, ai which, top half of the country p oak for ft with cypre is an ever cattle in w mon in th thrub, wh from all of the earth. roots (if th der the bar with the w fembling late war, greatly in iron-work naces in th a proportio weltern pa been fettle are chiefly from Peni people from are exceedi difcipline Scotland. ous peopl veral flour part of thi kers have a Guildford at Pequin Methodift and increa of N. C. paffeil a la men, 5 fr the Unive State has the mdow General A loaned [5 them to p buildings

180

tive names. in the State ; re Edenton, illfborough, :; each of turns, the . Raleigh, ie State, has metropolis. width, for dead level. tract lies in the banks of larly of the : and good. other parts, nd ridges of foil, Sixty i, the countains, as in Wheat, rye, well in the n corn and Cotton ts. ly cultivated in much n is planted th the froft. vill produce r 250 fit for roportion of untry, conindian corn, S. Carolina ern interior to Charlefsterfburg, in m the lower tch, turpenards, fcanthacco, pork, le-wax, and nting in the h, 1791, to ade is chiefd the northtry near the during the ibject to inen prove fanptoms prearts of the art of Ametile, full of water. Auh in regard enity of the and variety , which the fealon

NOR

feafon affords. The winters are fo mild in fome years, that autumn may be faid to continue till fpring. Wheat harveft is in the beginning of June, and that of Indian corn early in September.

The large natural growth of the plains, in the low country, is almost univerfally pitch pine, which is a tall handfome tree, far fuperior to the pitch pine of the northern States. This tree may be called the ftaple commodity of N. Carolina. It affords pitch, tar, turpentine, and various kinds of lumber, which, together, conffitute at least one half of the exports of this State. No country produces finer white and red oak for fraves. The fwamps abound with cyprefs and bay trees. The latter is an evergreen, and is food for the cattle in winter. The mifletoe is common in the back country. This is a thrub, which differs in kind, perhaps, from all others. It never grows out of the earth, but on the tops of trees. The roots (if they may be fo called) run under the bark of the tree, and incorporate with the wood. It is an evergreen refembling the garden box-wood. The late war, by which N. Carolina was greatly injured, put a ftop to feveral iron-works. There are four or five furnaces in the State, that are in blaft, and a proportionable number of forges. The weltern parts of this State, which have been fettled within the laft 40 years, are chiefly inhabited by Prefbyterians from Pennfylvania, the defcendants of people from the North of Ireland, and are exceedingly attached to the doctrines, difcipline and usages of the church of Scotland. They are a regular industrious people. The Moravians have feveral flourishing fettlements in the upper part of this State. The Friends or Quakers have a fettlement in New-Garden in Guildford co, and feveral congregations at Pequimins and Pafquotank. The Methodists and Baptists are numerous and increasing. The General Affembly of N. Carolina, in December, 1789, paffeil a law incorporating 40 gentlemen, 5 from each diftrict, as truffees of the University of N. Carolina. The State has given handlome donations for the endowment of this feminary. The General Affembly, in December, 1791, loaned £ 5,000 to the truffees, to enable them to proceed immediately with their buildings. There is a very good aca- I beek and Connecticut weft line. In

NOR

demy at Warenton, another at Williamfoorough, in Granville, and three or four others in the State, of confider-able note. North-Carolina has had a rapid growth. In the year 1710, it contained but about 1200 fencible men. In 1794, the number was estimated at about goooo. It is now, in point of numbers, the fourth Stare in the Union. By the conftitution of this State, which was ratified in December 1796, all legislative authority is vefted in two diffinet branches, both dependent on the people, viz. a Senate and Houfe of Commons, which, when convened for bunnels, are ftyled the General Affembly. The fenate is composed of representatives, one from each county, chofen annually by ballot. The Houle of Commons confilts of reprefentatives chofen in the fame way, 2 for each county, and one for each of the towns of Edenton, Newbern, Wilmington, Salifbury, Hillfborough, Halifax, and Fayetteville. The hiltory of North Carolina is lefs known than that of any other of the States. From the belt accounts that hiltory affords, the first permanent lettlement in North-Carolina was made about the year 1710. by a number of Palatines from Germany, who had been reduced to circumftances of great indigence, by a calamitous war. The infant colony remained under the general government of South-Carolina, till about the year 1729, when 7 of the proprietors, for avaluable confideration, vefted their property and jurifdiction in the crown; and the colony was erected into a feparate province, by the name of North-Carolina, and its prefent limits. eftablished by an order of George II.

NORTH-CASTLE, a township of New-York, in Weft-Chefter co. north of Mount Pleafant, and the White Plains. on the borders of Connecticut. In 1790, it contained 2,478 inhabitants. In 1796, there were \$73 of the inhabitants qualified electors. It is so miles from White Plains, and 20 from Ridgefield in Connecticut.

NORTH EAST, a fmall river which empties in at the head of Chefapeak Bay, about 5 miles below Charleftown ; only noticeable for the quantity of herrings caught in it.

NORTH-EAST-TOWN, a township in Dutchels co. New-York ; about go miles N. of New-York city ; between Rhyn-

1790 it contained 3,401 inhabitants. In 1796 there were in it 391, qualified electors.

NORTH-EDISTO Inlet, on the coaft of S. Carolina, is 11 miles from Stono Inlet, and 3 E. N. E. from South Edifto.

NORTHERN Archipelago confifts of feveral groups of Islands, which are fituated between the eastern coaft of Kamtichatka, in Afia, and the weltern coaft of America. These islands are frequented on account of their valuable furs. If the accounts of navigators who have vifited them may be credited, the moth perfect equality reigns among thefe iflanders; they live in the primitive patriarchal manner, and every perfon looks upon his ifland as a poffeffion, the property of which is common to all the ndividuals of the fame fociety. They feem cold and indifferent in n:oft of their actions; but let an injury or even a fufpicion roufe them from this phlegmatic flate, they become inflexible and furious, taking the most violent revenge, without any regard to the confequences. The leaft affliction prompts them to fuicide.

NORTHFIELD, a township in Orange co. Vermont, between 20 and 30 miles W. of Newbury, in the W. part of the county.

NORTHFIELD, a thriving townfhip, in the N. part of Hampfhire co. Maffachufetts; fituated on the E. fide of Connecticut river, 30 miles N. of Northamptou, 100 N. W. by W. of Bofton. It contains 868 inhabitants. The town was incorporated in 1763, and fome years after defolated by the Indians. The inhabitants returned again in 1685, but it was foon after deftroyed a fecond time. In 1713 it was again rebuilt, and one third of the townfhip was taken off, and incorporated by the name of Hinfdale. Fort Dummer was in the vicinity of this town.

NORTHFIELD, a fmall town in Rockingham co. New-Hampshire taken from Canterbury, on the E. fide of Merrimack river, and incorporated in 1780. It contained 606 inhabitants.

NORTHFIELD, a township in Richmond county, Staten-Island, New-York, containing 1021 inhabitants, including 133 qualified electors, and 133 flaves.

NORTH HAMPTON, a township of

New-Hampfhire, in Rockingham co. which contains 657 inhabitants, taken from Hampton and incorporated in 1742.

NORTH-HAVEN, a township of Connecticut, fituated in New-Haven co. on the E. fide of East river, 8 miles N. by E. of New-Haven, and 32 S. by W. of Hartford. It was fettled in 1660 by 35 men, principally from Saybrook. This town is the birth-place of that learned, pious and excellent man, Dr. Ezra Stiles, late prefident of Yale college.

NORTH-HEMPSTEAD, a township in Queen's co. Long-Island, New-York, bounded easterly by Oyster Bay, northerly by the found, and fouth by South-Hempstead. In 1790, it contained 2696 inhabitants, of whom 507 were flaves. In 1796, 232 of the inhabitants were qualified electors. The foil is but indifferent.

NORTH-HUNTINGTON, a township in Westmoreland co. Pennsylvania.

NORTH Ifland, on the coaft of South-Carolina, lies on the north fide of Winyah harbour.

NORTHLINED Lake, in N. America, is about 160 miles S. of the head of Chefterfield Inlet; is full of iflands, and about 80 miles long, and 25 broad.

NORTH KINGSTOWN, a town in Washington co. Rhode-Island, which carries on a considerable trade in the fisheries, befides some to the West-Indies. Its harbour is called Wickford, on the west fide of Narraganset Bay, opposite the north end of Canonnicut Island. It is about 8 miles north-west of Newport, and 20 southerly of Providence. The township contains 2,907 inhabitants.

NORTH MOUNTAIN, one of the ridges of the Alleghany Mountains, which extends through Virginia and Pennfylvania. There is a curious fyphon fountain in Virginia, near the interfection of Lord Fairfax's boundary with the North Mountain, not far from Brock's Gap, on the fiream of which is a grift-mill, which grinds two bufhels of grain at every flood of the fpring.

of grain at every flood of the fipring. NORTHPORT, a township in Hancock co. District of Maine, taken from the northerly part of Duck-Trap Plantation, and incorporated in 1796.

NORTH REEF, off the island of St. Domingorin the Weft-Indies, lies in lat. 20. 33. N. and long. 69. 12. W. NORTH

NORT Hudfon's Nort its fize, water, than 40 100 tons fcend to tant, as Head P ferpenti Marshfi boats t fource. which I three n waters munica chufett as it w navigat NOF river of ca, wh and di emptie W. en Not na rive Pafur No Chefte erly by northe by the it cont 58 fla bitant No given of the walh can c Gulf furth washi Spain Firm diftin been Gulf Span of D in op which Sea. E.c time pella

ingham co. tants, taken rporated in

fhip of Conlaven co. on miles N. by 5. by W. of 1660 by 35 rook. This hat learned, Ezra Stiles, e. a townfhip New-York, Bay, north-

Bay, northh by Southt contained m 507 were the inhabithe foil

a township Ivania. If of Southide of Win-

N. Amerithe head of iflands, and 5 broad. a town in and, which rade in the ie Weft-In-Wickford, ganfet Bay, Canonnicut i north-weft ly of Provitains 2,907

me of the Mountains, irginia and ious fyphon he interfecndary with far from of which is wo bushels e fpring. ip in Hantaken from Trap Plan-1796. fland of St. lies, lies in . 12. W. NORTH

NOR

NORTH RIVER, in New-York. See Hudfon's River.

NORTH RIVER, in Maffachuletts, for its fize, is remarkable for its depth of water, being in fome places not more than 40 or 50 feet wide, yet veffels of 300 tons are built at Pembroke, and defcend to Maffachufetts Bay, 18 miles dif. tant, as the river runs. It rifes in Indian Head Pond, in Pembroke, and runs a ferpentine courfe between Scituate and Marshfield. The river is navigable for boats to the first fall, 5 miles from its fource. Thence to the nearest waters which run into Taunton river, is only three miles. A canal to connect the waters of these two rivers, which communicate with Narraganfet and Maffachufetts bays, would be of great ntility, as it would fave a long and dangerous navigation round Cape Cod.

NORTH RIVER, a very confiderable river of New-Mexico, in North-America, which rifes in the north part of it, and directs its courfe to the S. E. and empties into the Gulf of Mexico, at the W. end, in and about lat. 26. 12. N.

NORTH RIVER, a branch of Fluvanna river, in Virginia. See Cow and Calf Pafure:

NORTH SALEM, a township in Weft-Chefter co. New-York, bounded foutherly by Salem, eafterly by Connecticut, northerly by Duchefs co. and wefterly by the middle of Croton river. In 1790, it contained 1058 inhabitants, including 58 flaves. In 1796, 162 of the inhabitants were qualified electors.

NORTH SEA, is a name that has been given by geographers to various parts of the oceans, where they happen to wash the northern parts of the American continent or iflands. Thus, the Gulf of Mexico, and the Atlantic Ocean further to the east, from their waters washing the N. coaft of Mexico or New Spain in North-America, and Terra Firma in South-America, have been diftinguished by this name. It has alfo been applied to the fouthern part of the Gulf of Mexico, in particular by the Spaniards, on their croffing the ifthmus of Darien from the N. to the S. coaft, in opposition to the Pacific Ocean, to which they gave the name of the South Sea. The Atlantic Ocean also on the E. coaft of N. America has been fometimes also called the N. Sea; which appellation has also been given to the

Frozen Ocean, from its bounding North-America on the north.

NORTH SOUND POINT is the projecting point of land on the N. E. fide of the illand of Antigua, in the Weff-Indies and is about S. S. E. from Long Ifland.

NORTHUMBERLAND, a town in Grafton co. New-Hampfhire, fituated on the E. fide of Connecticut river, ar the mouth of the Upper Amonoofuck. It was incorporated in 1779, and contains 117 inhabitants.

NORTHUMBERLAND, a county of Pennfylvania, bounded N. by Lycoming; S. and W. by Dauphin and Mifflin counties. It is divided into 16 townfhips, and in 1790 contained 17,162 inhabitants. The county of Lycoming has fince the cenfus been lately taken from it, but the county is fuppofed to contain nearly as many inhabitants as before; a great number of people having emigrated to this part of the State. Chief town, Sunbury.

NORTHOMBERLAND, a flourishing post-town in the above county, fituated on the point of land formed by the junction of the E. and W. branches of the Susquehannah. It is laid out regularly, and contains about 120 houses, a Prefbyterian church, and an academy. It is 2 miles N. by W. of Sunbury, and 124 N. W. by W. of Philadelphia.

NORTHUMBERLAND, a county of Virginia, bounded E. by Chefapeak Bay, and W. by Richmond. It contains 9,163 inhabitants, including 4,460 flaves. The court-houfe, where a poftoffice is kept, is 12 miles from Kinfale, 18 from Lancafter court-houfe, 86 from Frederickfburg, and 317 from Philadelphia.

NORTHUMBERLAND, a co. of Penafylvania. There is iron ore in this county; also a falt fpring.

NORTH-WALES, a town of Caroline co. Virginia, on Pamunky river, about 2 miles below the junction of N. and S. Anna branches.

NORTH WEST COAST of America. The country on the N. weftern part of the continent of America, lying on the Pacific Ocean, is thus denominated. According to accounts given by voyagers to this coaft, the valt country lying upon it, with very little deviation, has the appearance of one continued foreft, being covered with pines of different fpecies,

fpecies, and these intermixed with al-der, birch, witch-hazle, &c. besides va-rious kinds of brushwood; and the vallies and low grounds afford wild currants, goolcherries, rafpherries, and va-rious flowering fhrubs. On the coaft are many iflands, spacious bays, commodious harbours, and months of navimodious harbours, and months of navi-gable rivers; among the former are Wafhington, or Queen Charlotte's Ifl-ands, extending from N. lat. 51. 42. to 54. 18. W. long from Greenwich 129. 54. to 133. 18. Here are Nootka Sound, Admiralty Bay, and Port Mulgrave, Prince William's Sound, Cook's river; the peninful of Alafka, and the iflands furrounding it, Brittol Bay, and Nor-ton Sound; which laft lie S. eaftward of Behring's Straits. The coaft is in-habited by numerous but fmall tribes of habited by numerous but fmall tribes of Indians; each tribe appearing to be independent, and governed by its own chief. They differ from each other in their languinge and cultoms, and are frequently at war. It is impoffible to afcertain with any degree of certainty the number of inhabitants; but they have been computed at 10,000, from Nootka Sound to Cook's river, an ex-tent of about 1000 miles. The natives are for the most part thort in stature, their faces, men and women, are in general flat and round, with high cheek bones and flat nofes, and their teeth white and regular. Their complexions are lighter than the fouthern Indians, and fome of their women have roly cheeks. Both fexes are fond of ornamenting themfelves with beads and trinkets, and they generally paint their hands and faces. They have a cuftom of making a longitudinal flit in the under lip, between the mouth and chin, fome of them as large as the mouth, in which they wear a piece of bone, wood or ivory, fitted with holes in it, from which they fuspend beads as low as the chin. There appears to be a greater uniformity in the drefs of the different tribes, than in their ornaments. The aperture or fecond mouth, above the chin, feems confined to the men of Cook's river and Prince William's Sound ; whilft the wooden ornament in the under lip is worn by the women only, in that part of the coaft from Port Mulgrave to Queen Charlotte's Iflands. The inhabitants wholly fublift by fifhing and hunting. Their cloathing is lightful country, comprehending four

1 dia sigi

NOR

NOR

made of the fkins of animals and birds. They live in a very dirty manner, and are a complete picture of filth and indolence. The chief object of civilized nations in navigating this coaft hitherto, has been to traffic with the natives for furs; which they give in exchange for pieces of iron, nails, beads, penknives and other trifling trinkets. These furs are carried to China, and disposed of to a great profit. The fkins obtained are those of the sea-otter, racoon, pine-martin, land beaver, earles mammot, &c. The other articles which might be procured are ginfeng, copper, oil, spars, &c. with great quantities of falmon. From 1785 to February 1788, there had arrived at China from this coaft 9 veffels of different nations. Six of these had furs, fold for 96,842 dollars; two French ships, 54,837 dolls. and 17,000 fkins imported by the Spaniards unfold. What furs the Ruffians procure is not known, as they never carry them to Canton. An inland fea has been lately difcovered in this country. Mr. Etches, who fitted out thips from England, has lately difcovered, that all the weftern coaft of America from lat. 48. to 57. N. is not a continued tract of land, but a chain of iflands which had never been explored, and that those concealed the entrance to a vaft inland fea, like the Baltic or Mediterranean in Europe, and which feems likewife to be full of iflands. Among thefe Mr. Etches' fhip, the Princefs Royal, penetrated feveral hundred leagues in a N. E. direction, till they came within 200 leagues of Hudson's Bay; but as the intention of the voyage was merely commercial, they had not time fully to explore the Archipelago just mentioned, nor did they arrive at the termination of this new Mediterranean Sea. The islands, of which upwards of 50 were vilited, were inhabited by tribes of Indians, who appeared very friendly, and well difposed to carry on a commerce. Some thips are fitting out at one of the ports of England for the fame place, fo that further difcoveries may foon be expected. In confequence of an expedition undertaken in 1787, Capt. J. Kendrick, of the fhip Columbia, while profecuting an advantageous voyage with the natives for furs, purchased of them it is faid, for the owners, a tract of dedegrees

degrees of The deeds registered i conful; th thorized to or affociati of land no and climat a prudent conftitution portance. NORTH

Cape Fear Carolina. of Haw an yards wide above the is low, and Fear Rive river, abo in the banl low the fi projecting trunks of NORTH Territory. NORTH

ed townfhi Hampfhire ders, are a waters fe rivers. I contains 7 39 miles Cryftals a here. NORTH of the Di land co. o to Calco I S. of Brun and 140 F is extenfiv and conta fen's river the N. E. NORTO

Vermont, having Ca weft. NORTO

fetts, fitus fouthward rated in 1 bitants, manufact tons. Th ochre wh that at T

id birds. ner, and nd indocivilized hitherto, tives for inge for enknives nele furs ed of to ined are ne-mar-10t, &c. be pro-, fpars, falmon. here had ft 9 vefof thefe rs; two 17,000 unfold. e is not them to in lately Ar. Etingland, he weft-1. to 57. nd, but ler been aled the ike the pe, and full of es' fhip, feveral rection, gues of ntion of nercial. ore the nor did of this iflands, vinted, ndians, nd well imerce. of the ace, fo be exexpedi-Kenile proge with f them of deg four degrees

NOR

degrees of latitude, or 240 miles fquare. The deeds are faid to be in China, and regiftered in the office of the American conful; the agents in London are authorized to treat with any gentleman or affociation for the purchafs of a track of land no where exceeded for fertility and climate, and which may perhaps by a prudent management of fome wile conflitution, become of the utmost importance.

NORTH-WEST *River*, a branch of Cape Fear, or Clarendon river, in N. Carolina. It is formed by the junction of Haw and Deep rivers; and it is 300 yards wide at Afhwood, 80 or 90 miles above the Capes; even when the fream is low, and within its banks. See *Cape Fear River*. On the weft fide of this river, about 40 miles above Afhwood, in the banks of a creek, 5 or 6 feet below the fandy furface, are to be feen projecting out many feet in length, trunks of trees entirely petrified.

NORTH-WEST TERRITORY. See Territory.

NORTHWOOD, an interior and elevated township in Rockingham co. New-Hampshire, in which, and on its borders, are a number of small ponds, whose waters feed Piscataqua and Suncook rivers. It was incorporated in 1773; contains 744 inhabitants, and is about 39 miles north-west of Portsmouth. Crystals and crystalline spars are found here.

NORTH-YARMOUTH, a post-town of the District of Maine, in Cumberland co. on a small river which falls into Casco Bay. It is 17 miles W. by S. of Brunswick, 14 north of Portland, and 140 E. of Boston. The township is extensive, was incorporated in 1713, and contains 1,978 inhabitants. Cufsen's river divides it from Freeport on the N. E:

NORTON, a township in Effex co. Vermont, fituated on the Canada line, having Canaan east, and Holland on the west.

NORTON, a township of Massachufetts, fituated in Bristol co. and 33 miles fouthward of Boston. It was incorperated in 1711, and contains 1428 inhabitants. The annual amount of the nail manufacture here is not less than 300 tons. There is also a manufacture of ochre which is found here, similar to that at Taunton. NORTON, a fettlement on the northeast coast of Cape Breton island.

NORTON's Sound, on the N. W. coaft of N. America, extends from Cape Darby on the N. N. W. to Cape Denbigh, or Cape Stephen's on the S. or S. E. N. lat. 64. 50.

NORWALK, a pleafant post-town in Fairfield co. Connecticut, fituated on the N. fide of Long-Ifland Sound. It contains a Congregational and Epifcopal church, which are neat edifices, and between 40 and 50 compact houses. It is 13 miles W. by S. of Fairfield, 34 S. W. by W. of New-Haven, 54 N. E. of New-York, and 149 from Philadelphia. N. lat. 41. 9. W. long. 73. 47. The township is fituated in a fertile wheat country, and was fettled in 1651. Here are iron-works and a number of mills. It has a finall trade to New-York and the Weft-Indies.

NORWAY, a township of New-York, in Herkemer co. incorporated in 1792. By the State census of 1796, it contained 2164 inhabitants, of whom 353 were electors.

NORWAY, a new township in Cumberland co. District of Maine, incorporated 1797.

NORWICH, a confiderable township in Windsor co. Vermont, on the welt fide of Connecticut river, opposite to Dartmouth College. It contains 1158 inhabitants.

NORWICH, a township in Hampshire co. Massachusetts, 24 miles S. W. of Northampton, and 114 west of Boston. It was incorporated in 1773, and contains 742 inhabitants.

NORWICH, a city and post-town of Connecticut, and of the fecond rank in New-London co. fituated at the head of navigation on Thames river, 14 miles north of New-London, and 40 S.E. of Hartford. This commercial city has a rich and extensive back country; and avails itfelf of its happy fituation on a navigable river, which affords a great number of convenient feats for mills, and water machines of all kinds. The inhabitants manufacture paper of all kinds, flockings, clocks and watches, chaifes, buttons, ftone and earthen ware, oil, chocolate, wire, bells, anchors, and all kinds of forge-work. The city contains about 450 dwelling houses, a court-houfe, and two churches for Congregationalist, and one for Epifcopalians, Вb

palians, and about 3000 inhabitants. The city is in three detached, compact divisions, viz. Chelfea, at the landing, the Town, and Bean Hill; in the latter division is an academy, and in the town is an endowed ichool. The courts of law are held alternately at New-London and Norwich. This town was fettled in a660, by 35 men, principally from Saybrook. It is 251 miles N.E. of Philadelphia. N. latt. 34. W. long. 72. 29.

delphia. N. lat 41. 34. W. long. 72. 29. Norwich, a townfhip in Tioga co. New York, taken from the towns of Jericho and Union, and incorporated in 1793. It is fettled principally by people from Connecticut; is bounded foutherly by Oxford, and lies 55 miles weft of Cherry Valley. By the State cenfus of 1796, 129 of its inhabitants were electors.

NOTCH, The, a pais in the western art of the White Mountains, in New-Hampfhire; the narroweft part of which is but 22 feet wide, between two perpendicular rocks. It is 25 miles from the Upper Coos. From the height above it a brook defcends, and meanders through a meadow, formerly a beaver pond. It is furrounded by rocks, which, on one fide, are perpendicular, and on the others, rife in an angle of 45 degrees, a firikingly picturesque scene. This defile was known to the Indians, who formerly led their captives through it to Canada; but it had been forgotten or neglected, till the year 1771, when two hunters passed through it. There is a

road this way now to the Upper Coos. NOTCH, CAPE, is the W. point of Goodluck Bay, in the Straits of Magellan. S. lat. 52, 22, W. long. 74, 24

Ian. S. lat. 53. 33. W. long. 74. 34 NOTTAWAY, a fmall river of Virginia, which runs E. by S. and receives Black Water on the line of N. Carolina; thence purfuing a S. by W. courfe of about 10 miles, it joins the Meherrin; the confluent ftream then affumes the name of Chowan river, and empties into Albemarle Sound.

NOTTAWAY, a county of Virginia, bounded N. and N. W. by Amelia, from which it was taken in the year 1788. See Amelia.

NOTTINGRAM, 2 township in Rockingham co. New-Hampshire, 14 miles N. of Exeter, and 25 N. W. of Portsmouth, It was incorporated in 1722, and contains 1068 inhabitants.

NOTTINGHAM, Weft, a township in

painting.

Hillfborough co. New-Hampfhire, fituated on the E. fide of Merrimack river, 50 miles diftant from Portfmouth, was incorporated in 1746, and contains 1064 inhabitants. It has Maffachufetts line for its fouthern boundary, which divides it from Dracut, and is about 45 miles N. N. W. of Bofton.

NOTTINGHAM, a township in Chefter co. Pennsylvania.

NOTTINGHAM, the most northern town of Burlington co. New-Jersey, fituated on the eastern bank of Delaware river, between Bordentown and Trenton.

NOTTINGHAM, a town in Prince George's co. Maryland, fituated on Patuxent river, nearly 16 miles north-eafterly of Pilcataway, and 20 S. E. of the Federal City.

NOVA-SCOTIA, formerly called New-Scotland, a British province of North-America; feparated on the N.E. from Cape Breton Island, by the Gut of Canfo; on the N. it has a part of the Gult of St. Lawrence, and the Straits of Northumberland, which divide it from the island of St. John's; on the W. it has New-Brunfwick and the bay of Fundy : on the S. and S.E. the Atlantic Ocean. Its length is about 235 miles from Cape Sable on the S. W. to Cape Canfo on the N. E. Its extreme breadth is 88 miles ; but between the head of Halifax harbour and the town of Windfor, at the head of the S. E. arm of the Bafin of Minas it is only about 22 miles broad. It contains \$,789,000 acres; of which 3 millions have been granted, and 2. millions fettled and under improvement. Nova-Scotia is accommodated with many fpacious harbours, bays, and coves of shelter, equal to any in the world. The chief of these are Canso, Halifax, on Chebucto Bay, Chedabucto, Frederick, George, Torbay, Charlotte, King's, Barrington, Townfend, St. Mary's, Annapolis Royal, the Bafin of Minas, the Bay of Fundy; and a yaft number of. capes, lakes, and rivers, which are defcribed under their respective names. The most remarkable mountains are the Highland of Afpotagoen, and the Ardois Mountain. The fouthern fhores prefent to the eye of a ftranger rather an unfavourable appearance, being in general broken and itoney; but the innumerable iflands along its coafts, coves, and harbours, though generally composed

of rocky f nature for vered with ftages ; an paftures an poles of f into the ba promifing wallis, W Cumberlar along the vince, then farms. I huíbandry by the lat experimen lately eftat ground to become a lands in county of few hills (intersperse The grow fpruce, he fome rock exhauftibl other purp

The co ous kinds herring, a near to th Quero, an proper m might be fuccefs. Cumberla which fall is plenty Annapolis Nictau riv there. C D'Or, on Minas. Fort Edw wallis. counties, Annapoli Queen's, fubdivide The who New-Bru joining is The amo Britain to 3 years, b about 26, in exchan of the fift

hire, fituack river, buth, was tains 1064 uletts line which diabout 45

p in Chef-

Jerfey, fi-Delaware and Tren-

in Prince ed on Paporth-eaft-E. of the Iled Newof North-I.E. from at of Canthe Gulf ts of Nort from the W. it has of Fundy ; tic Ocean. from Cape Canfo on dth is 88 of Halifax indfor, at the Bafin iles broad. of which ed, and 2. covement. with maand coves he world. , Halifax, to, Fredee, King's, ary's, An-Minas, the number of. ch are deve names. ins are the he Ardois res prefent er an unin general innumercoves, and

compoled of

NOV

of rocky fubftances, appear defigned by nature for the drying of fifh, being covered with materials for fifh-flakes and ftages; and there is land fufficient for paffures and gardens, to ferve the purpoles of filhermen. As you advance into the back country, it wears a more promifing appearance; and at Cornwallis, Windfor, Horton, Annapolis, Cumberland, Cobequid, Pictou, and along the northern fhores of the province, there are extensive, well improved farms. The gradual improvements in hufbandry, which has been encouraged by the laudable efforts and fuccefsful experiments of the agricultural fociety, lately eftablished here; afford fome good ground to expect that Nova-Scotia may become a flourishing colony. The lands in general, on the fea-coaft, the county of Lunenburgh excepted, and a few hills of good land, are rocky, and interspersed with swamps and barrens. The growth in general is a mixture of fpruce, hemlock, pine, fir, beech, and fome rock maple, which furnish an inexhaustible supply for ship-building and other purpofes.

The coaft abounds with fifh of various kinds, as cod, falmon, mackerel, herring, alewives, trout, &c. and being near to the banks of Newfoundland, Quero, and Sable banks, fifheries, under proper management and regulations, might be carried on with certainty of fuccefs. There are mines of coal at Cumberland, and on the East river, which falls into Pictou harbour. There is plenty of bog and mountain ore in Annapolis township, on the borders of Nictau river, and a bloomery is crected there. Copper has been found at Cape D'Or, on the north fide of the Bafin of Minas. The forts in this province are Fort Edward, Cumberland, and Cornwallis. Nova-Scotia is divided into 8 counties, viz. Hants, Halifax, King's, Annapolis, Cumberland, Sunbury, Queen's, and Lunenburg. Thefe are fubdivided into above 40 townships. The whole population of Nova-Scotia, New-Brunfwick, and the iflands adjoining is effimated at about 50,000. The amount of imports from Great-Britain to this country, at an average of 3 years, before the new fettlements, was about 26, gool. The articles exported in exchange are, timber and the produce of the fifhery, which at a large average

amounts to 38,000l. Nova-Scotia was confirmed to Great-Britain in 1760. Halifax is the metropolis. See New-Branfwick, Canada, &c.

NOUVELLE, La, commonly called East Nouvelle, lies on the northern fide of Chaleur Bay. It is a small river, about 4 leagues from Port Daniel.

NOUVILLE, La Grande, or West-Nonwille, on the northern fide of Chaleur Bay, is above one league from Carleton, where is alfo a custom-house, and a restate the field of the second s

NoxAN, or Noxonton, or Nox Town, a town of New-Caftle co. D. laware, 21, miles N. of Dover, and 9 S. by S. W. of St. George's Town.

NUBLADA, an island in the Pacific Ocean, with 3 finall ones north of it and near to it, W. by S. of Cape Corienles, on the coast of Mexico, and east of Roco Portida. N. lat. 16. 40. W. long. 122. 30.

NUCHVUNK, a place in New-Britain, the refort of Walruffes, in winter; with the teeth of these animals the Indians head their darts. Lat. 60. N.

NUESTRA Senora de la Paz, an epifcopal fee and town of Peru, in S. America. S. lat. 17. 10. W. long. 64.

NUESTRA Senora de la Vittoria, a town of Mexico. N. lat. 18. W. long. 92. 35.

NUEVO Baxo, a bank called by the British the New Bear, being about 32 leagues S. of the W. end of the island of Jamaica, in lat. 15. 57. morth. It has a key, a cables length long and 14 broad; firetching E. by N. and W. by S. The British find this a good flation in a Spanish war, as most thips come this way from the Spanish Main, going to the Havannah.

ste Altaneta-Man Ostrata, a tr**O** widdw head tra St& of Ulleria Mand, Mer

OACHATE Harbour, near the S. point of Ulietea, one of the Society Islands, in the S. Pacific Ocean, N.W. of Otaheite. S. lat. 16. 55. W. long. 151. 24.

OAHAHA, a river of Louisiana, which empties into the Missippi from the N. W. in lat. 39. 10. N. and 7 miles N. of Riviere au Beuf.

OAHOONA, one of the Ingraham Ifles, which is faid to be the northern B b 2 moft most of all this cluster. It lies about | foot rivers. It is 70 yards broad, 19 10 leagues N. E. of Nooheeva. To this ifland Capt. Roberts gave the name of Maffachufetts. Captain Ingraham had before called it Wasbington.

OAITIPIHA, or Aitepeba Bay, fituated near the north-east end of the lesser peninfula of the ifland of Otaheite, has good anchorage in 12 fathoms. S. lat. 17. 46. W. long. 149. 14.

OAK Bay, or the Devil's Head, in the Bay of Fundy, is 9 leagues S. S. E. of Moofe Ifland. It is very high land, and may be feen at 10 or 12 leagues diftance.

OAKFUSKEE. See Tallapoofe River. OAKFUSKIES, an Indian tribe in the western part of Georgia. The warrior Mico, called the White Lieutenant, has the fole influence over 1000 gun men.

OAKHAM, a township in Worcester co. Maffachufetts; 15 miles north-weft of Worcefter, and 62 weft of Bofton. It was incorporated in 1762, and contains 772 inhabitants.

OAK Ifland, a long narrow ifland on the coalt of N. Carolina, which with Smith's Ifland form the S.W. channel of Cape Fear river. See Bald Head, and Cape Fear.

OAKMULGEE River is the fouthern great branch of the beautiful Alatamaha, in Georgia. At the Oakmulgee Fields it is about 300 or 400 yards wide. These rich and fertile fields are on the east fide of the river, above the confluence of the Oconee with this river ; thefe two branches are here about 40 miles apart. Here are wonderful remains of the power and grandeur of the ancients of this part of America, confifting of the ruins of a capital town and fettlement, vast artificial hills, terraces, &c. See Alatamaba River.

OATARA, a fmall woody ifland on the S. E. of Ulietea Ifland, in the S. Pacific Ocean; between 3 and 4 miles from which to the north-west are two other fmall iflands in the fame direction as the reef, of which they are a part.

OBED'S River, in Tenneffee, runs fouth-wefterly into Cumberland river, 200 miles from its mouth, by the course of the fiream. Thus far Cumberland river is navigable for large veffels.

OBION, a navigable river of Tenneffee, which runs touth-westerly into the Miffifippi, 24 miles foutherly of Reel-

miles from its mouth.

OBITEREA, an island 100 leagues S. of the Society Islands. S. lat. 22. 40. W. long. 150. 50. It contains no good anchorage, and the inhabitants are averse to the intrusion of ftrangers.

OCCOA, or Ocea, a bay on the fouth fide of the island of St. Domingo, into which fall the fmall rivers Sipicepy and Ocoa. It lies east of Neybe or Julienne bay, and is bounded fouth-eastward by Point Salinas, and weftward by the east point at the mouth of Bya river. Spanish ships of war anchor in this bay. Point Salinas is 22 leagues welt of the city of St. Domingo.

OCCOA, a bay near the east end of the ifland of Cuba, in the windward paffage, about 20 miles caft of Guantanamo Bay.

OCCOCHAPPO, or Bear Creek, in the Georgia Western Territory, empties through the S. W. bank of Tenneffee river, just below the muscle shoals. There is a portage of only about 50 miles from this creek to the navigable waters of Mobile river. The mouth of this creek is in the centre of a piece of ground, the diameter of which is s miles, ceded by the fouthern Indians to the United States for the establishment of trading pofts.

OCCONEACHEY Mands, two long. narrow iflands at the head of Roanoke river, in Virginia, just below where the Staunton and Dan unite and form that river.

OCONA Port, on the coaft of Peru, on the S. Pacific Ocean, is 11 leagues N. W. of Quilca, and a bold coaft, and 14 leagues S. E. of Attico.

OCONEE, the north main branch of Alatamaha river, Georgia. It is, in many places, 250 yards wide. Its banksabound with oak, afh, mulberry, hickory, black-walnut, elm, faffafras, &c.

OCONEE Torun lies on the east bank of the river of its name in Georgia; about 26 miles weft-north weft of Golphington, and 62 weft by north of Augufta.

Occoquan, a river in Virginia which, after a fhort courie, empties into Patowmac river, at High Point, 5 miles below Colchefter.

OCRECOCK Inlet, on the coaft of N. Carolina, leads into Pamlico Sound, and out of it into Albemarle Sound, through through w are bound Bath, or N N. A bar on which The land cock, that miles with fand fhoal called the ! channel are dry. Few quainted w without a during the about 71 Cape Hatt

OENEM tol Bay, or rica. N. la OGEECI miles fouth courfes an other. It the north miles fout

Lexington upper part OGLET north fide Liberty co

corner of t OHAM! bour, on t the Societ Ocean. S. The varia was 6. 19 OHAMI E. fide o Iflands. tween the and Whe forms a g

fathoms w OHERI W. part o the Socie bour to t

Bay. Th fathoms, water. opens a pr

a mile bro \$ 51. 30. OHET

Iflands, w 6 broad, large fta road, 19 ragues S. 22.40. s no good ants are gers. the fouth ngo, intoicepy and or Julien--eaftward d by the bya river. this bay.

ft end of windward Guanta-

rek, in the empties Tenneffee le fhoals, about 50 navigable mouth of a piece of hich is 5 Indians to blifhment

two long. Roanoke where the form that

t of Peru, r leagues coaft, and

branch of is, in ma-Its banks rry, hickras, &c. eaft bank torgia; aof Golphh of Au-

nia whick, no Patowmiles be-

co Sound, rle Sound, through OHE

through which all vefiels must pais that I are bound to Edenton, Washington, Bath, or Newbern. It lies in lat. 35. 10. N. A bar of hard fand crofies the inlet, on which is 14 feet water at low tide. The land on the north is called Ocrecock, that on the S. Portfmouth. Six miles within the bar, there is a hard fand fhoal which croffes the channel called the Swafh. On each fide of the channel are dangerous fhoals, fometimes dry. Few mariners, however well acquainted with the inlet, choose to go in without a pilot; as the bar often fhifts during their absence on a voyage. It is about 71 leagues fouth-welt 1 welt of Cape Hatteras.

OENEMACK, the fouth point of Briftol Bay, on the N. W. coaft of N. America. N. lat. 54. 30. W. long. 160. 30.

OGEECHEE, a river of Georgia, 18 miles fouth of Savannah river, and whole courfes are nearly parallel with each other. It empties into the fea oppofire the north end of Offabaw Ifland, 18 miles fouth of Savannah. Louisville, Lexington and Georgetown are on the upper part of this river.

OGLETHORPE, a new county on the north fide of Alatamaha river, weft of Liberty co. Fort Telfair is in the S.E. corner of this county on the Alatamaha.

OHAMANENO, a fmall but good harbour, on the W. fide of Ulietea, one of the Society Mands, in the S. Pacific Ocean. S. lat. 16. 45. W. long. 151.38. The variation of the compais in 1777, was 6. 19. E.

OHAMENE Harboar, a fine bay on the E. fide of Otaha, one of the Society Iflands. It paffes in by a channel between the two fmall iflands Toahoutu, and Whennuaia. Within the reef it forms a good harbour, from 25 to 16 fathoms water, and clear ground.

OHERURUA, a large bay on the S. W. part of the ifland of Otaha, one of the Society Iflands, and the next harbour to the northward from Apotopoto Bay. There is anchorage from 20 to 25 fathoms, and has the advantage of frefh water. The breach in the reef which opens a paffage into this harbour, is $\frac{1}{2}$ of a mile broad, in lat. 26. 3%. S. and long. 251. 30. W.

OHETEROA, one of the Society Iflands, which is about s 2 miles long and 6 broad, inhabited by a people of very large flature, who are rather browner 380

than thole of the neighbouring islands. It has no good harbour nor anchorage-Lat. 22/27. S. long. 150. 47. OHETUNA, a harbour on the S.E. fide of Ulietea, one of the Society Islands. OHEVAHOA, an island in the South Pacific Ocean. S. lat. 9.41. W.long. 139.2.

OHIO, a most beautiful river, feparates the North Wettern Territory from Kentucky on the S. and Virginia on the S. E. Its current gentle, waters clear, and bofom fmooth and unbroken by rocks and rapids, a fingle inflance only excepted. It is one quarter of a mile wide at Fort Pitt ; 500 yards at the mouth of the Great Kanhaway; 1200 yards at Louisville, and at the Rapids half a mile, but its general breadth does not exceed 600 yards. In fome places its width is not 400, and in one place particularly, far below the Rapids, it is less than 300. Its breadth, in no one place, exceeds 1200 yards; and at its junction with the Miffifippi, neither river is more than 900 yards wide. Its length, as meafured according to its meanders by Capt. Hutchins, is as follow

s :- From Fort Pitt to	
Log's Town	181
Big Beaver Creek	101
Little Beaver Creek	134
Yellow Creek	111
Two Creeks	212
Long Reach	531
End of Long Reach .	161
Mulkingum	261
Little Kanhaway	12
Hockhocking	16
Great Kanhaway	821
Guiandot	43
Sandy Creek	141
Sioto, or Scioto	482
Little Miami	1261
Licking Creek	\$
Great Miami	261
Big Bones	321
Kentucky	44
Rapids	774
Low Country	1552
Buffalo river	64
Wabaflı	974
Big Cave	423
Shawanee river	522
Cherokee river	13
Maffac	11
Miflifippi	46
. I.	

In common winter and fpring floods, B b 3 it

it affords 30 or 40 feet water to Louifville ; 25 or 30 feet to La Tarte's Rapids; 40 above the mouth of the Great Kanhaway; and a fufficiency at all times for light batteaux and canoes to Fort Pitt. The Rapids are in lat. 38. 8. The inundations of this river begin about the last of March, and fubfide in July, although they frequently happen in other months; so that boats which carry 300 barrels of flour from the Monongahela, or Youhiogany, above Pittfburgh, have feldom long to wait for water. During these floods, a first rate man-of-war, may be carried from Louifville to New-Orleans, if the fudden turns of the river and the ftrength of its current will admit a fafe steerage. It is the opinion of fome well informed gentlemen, that a veffel properly built for the fea, to draw 12 feet water, when loaded, and carrying from 12 to 1600 barrels of flour, may be more eafily, cheaply and fafely navigated from Pittfburgh to the fea, than those now in use; and that this matter only requires one man of capacity and enterprize to afcertain it. A veffel intended to be rigged as a brigantine, fnow, or thip, thould be double-decked, take her mafts on deck, and be rowed to the Ibberville, below which are no iflands, or to New Orleans, with 20 men, fo as to afford reliefs of 10 and 10 in the night. Such a veffel, without the use of oars, it is fuppofed, would float to New Orleans from Pittfburg in 20 days. If this be fo, what agreeable prospects are prefented to our brethren and fellow citizens in the western country ! The Rapids at L uisville descend about 10 feet in the distance of a mile and a half. The bed of the river is a folid rock, and is divided by an ifland into two branches, the fouthern of which is about 200 vards wide, but impaffable in dry feafons. The bed of the northern branch is worn into channels by the conftant course of the water, and attrition of the pebble ftones carried on with that, fo as to be paffable for batteaux through the greater part of the year. Yet it is thought that the fouthern arm may be most easily opened for constant navigation. The rife of the waters in these Rapids does not exceed 20 or 25 feet. There is a fort fituated at the head of the Falls. The ground on the fouth fide rifes very gradually. At Fort Pitt gentle cathartic.

the river Ohio lofes its name, branching into the Monongahela and Alleghany.

OHIO Rapids lie in lat. 30. 8. N. 705 miles below Pittíburg to the S. W. and 482 miles from the confluence of the Ohio with the Miffifippi. They are occalioned by a ledge of rocks that firetch acrofs the bed of the river Ohio. The fituation of the Rapids is truly delightful. The river is full a mile wide, and the fall of the water, which is a conflant calcade, appears as if nature had defigned it, to fhew how inimitable and flupendous are her works. The town of Louifville commands a grand view of the Rapids.

OHIO, the north-westernmost county of the State of Virginia, bounded east by Washington co. in Pennsylvania, and N. W. by the river Ohio, which divides it from the N. W. Territory. It contains 5,212 inhabitants, including 281 flaves. Chief town, Liberty.

OH10 Company's Purchafe, in the N. W. Territory, is a tract of excellent land fituated on the north bank of the Ohio, east of Col. Symes's purchased. In this tract there were about 2,500 inhabitants in 1792.

OHIOPE, a fmall northern tributary ftream of Alatamaha river, in Oglethorpe co. Georgia.

OHIOPIOMINGO, a trast of land for called in the State of Kentucky, fituated in Nelfon co. on Ohio river, and fouth-weftward of Salt river.

OHIOPYLE Falls, in Youghiogany river, are about 20 feet perpendicular height, where he river is \$0 yards wide. They are 30 0 40 miles from the mouth of this river, where it mingles it waters with the Monongahela,

OHITAHOO, an ifland in the S. Pacific Ocean. S. lat. 9. 55. W, long. 139. 6.

OIL Creek, in Alleghany co. Pennfylvania, iffues from a fpring, on the top of which floats an oil, fimilar to that called Barbadoes tar, and empties into Alleghany river. It is found in fuch quantities, that a man may gather feveral gallons in a day. The troops fent to guard the Weftern Pofts, halted at this fpring and collected fome of the oil, and bathed their joints with it. This gave them great relief from the rheumatic complaints, with which they were afflicted. The waters, of which the troops drank freely; operated as a gentle cathartic.

OISTINS

OISTING extremity in the We

the S. E.

bay is we town of Oi OLD CA point of E the N. E. mingo. A from Euro and bound St. Domin in fight of leagues for or at leaft count of th It is about Roche. 1 from Paris OLD F fouth end the Weft Island and OLD F Bay, on t America.

> OLD H the ifland dies, is to There are in the entr there isfaft OLD M empties in miles belo the counti OLD M Lima rive Cadavayil OLD R the ifland

48.

OLD R of the ifla Weft-Ind and Blood to 15 fat leaft towa OLD R between 1 a port of

OLD T on Juniat OLD T York, is miles S. V wefterly OLD-T

branching lleghany. 8. N. 705 i. W. and ice of the cy are ocnat firetch nio. The y delightwide, and is a connature had itable and The town rand view

off county ded east by vania, and which diritory. It including berty. , in the N. f excellent ank of the purchase, t 2,500 in-

, in Ogle-

of land for icky, fituriver, and

ughiogany rpendicular yards wide, the mouth ts it waters

e S. Pacific ng. 139. 6, co. Pennng, on the allar to that mpties into nd in fuch gather fetroops fent , halted at eof the oil, it. This n the rheuwhich they , of which erated as a

OISTINS.

OISTINS Bay, is near the fouthern extremity of the illand of Barbadoes, in the Weft-Indies. It is formed to

OLD

in the Weft-Indies. It is formed to the S. E. by Kendal's Point. The bay is well defended by forts. The town of Oiftins flands on this bay.

OLD CAPE FRANCOIS forms the N. point of Ecosibile or Colbeck Bay, on the N. E. part of the island of St. Domingo. All the French fhips coming from Europe or the Windward Islands, and bound to the north or welt part of St. Domingo Island, are obliged to come in fight of the Cape Samana, (near 27 leagues fouth-east by east of this cape) or at least of Old Cape Francois, on account of the dangers of shoals to the east. It is about 5 leagues east of Cape de la Roche. N. lat. 79.40.30. W. long. from Paris 72.22.

OLD FORT Bay is fituated at the fouth end of the island of St. Lucia, in the West-Indies, having St. Mary's Island and Bay to the east.

OLD FORT *Islands*, in Efquimaux Bay, on the coaft of Labrador, in N America. N, lat. 51. 24. W. long. 57. 48.

OLD Harbaur, on the fouth coaft of the ifland of Jamaica in the Weft-Indies, is to the weftward of Port Royal. There are a number of fhoals and iflands in the entrance to it. Under fome of them there is fafe riding, in from 6 to 8 fathoms.

OLD MAN's Creek, in New-Jerfey, empties into Delaware river, about 4 miles below Penn's Neck, and feparates the counties of Salem and Glouceffer.

OLD MEN'S Port lies northward of Lima river in Peru, 8 or 9 miles N. of Cadavayllo river.

OLD ROAD, a town and harbour in the ifland of Antigua, in the W. Indies.

OLD ROAD Bay, on the S. W. coaft of the island of St. Christopher's, in the West-Indies, between Church Gut W. and Bloody Point E. There is from 5 to 15 fathoms near the shore, and the least towards the fort.

OLD ROAD Town, on this bay, lies between East and Black rivers, and is a port of entry.

OLD TOWN, or Frank's Old Town, on Juniatta river. See Frankflown.

OLD TOWN, in the State of New-York, is fituated on Staten-Ifland, 3 miles S. W. of Newtown, and 12 fouthwefterly of New-York city.

OLD-TOWN, a fmall post-town of

Maryland, fituated in Alleghany co. in lat. 39. 30. on the N. bank of Patowmac river, and W. fide of Saw Mill Run; 14 miles S. E. of Cumberland, 142 W. by N. of Baltimore, and 213 from Philadelphia.

OLD TOWN, in N. Carolina, near Brunfwick.

OLD TOWN, a finall town of Georgia, lying on the Ogeechee river, 85 miles N. W. by W. of Savannah.

OLEOUT, a imall creek, which empties into the east branch of Susquehannah, 5 miles N. E. of the mouth of Unadilla river.

OLINDA, the chief town of the captaiofhip of Pernambuco, in Brazil, S., America. It is fometimes called *Pernambuco*, and has a good harbour fituated north of Cape St. Augustine, and iouth of Paraibo. It was taken by the Dutch in 1630, but was retaken by the Portuguese: S. lat. 8. 13. W. long-35. 5.

OLLEROS, Point, on the coaft of Peru, is 6 leagues S. E. of Quemada Morro, or Headland, and as far N. N. W. of Porto Cavaldo. It is little frequented on account of want of trade, although it is a good harbour in cafe of fqualls from the mountains, or of ftrong currents fetting down from the fea.

OMAGUAS, a tribe of Indians inhabiting the banks of the river Amazon, and converted to Christianity in the year 1686, by father Fritz, a Spanish millionary. They flat the hind and fore part of the heads of their children, which gives them a monstrous appearance. They make a jeft of other nations, calling them calabash heads.

OMARA, a river on the coaft of Brazil, whofe mouth is in lat. 5. o. S. and hong. 36. o. W. See Cape Recyue.

OMASUOS, a jurifdiction in the diocefs of La Paz, in Peru. It begins almost at the gates of the city of La Paz, and extends 20 leagues, being bounded on the well by the famous lake of Titi Caca. The air of this jurifdiction is fomewhat cold, so that it produces little grain; but has numerous flocks of cattle fed'in its pattures; there is befides, a very advantageous trade carried on in another jurifdiction by the Indians living on the borders of the lake, who are remarkably industrious in improving that advantage.

OMEE, a corrupt name for The Mia-B b 4/ mi 302

mi of the Lake; which fee. The Miami towns on its banks are called the Omee towns, or Au-Mi, by the French Americans, as a contraction of Au Miami.

OMEE-TOWN, one of the Miami towns, fituated on a pleasant point formed by the junction of the rivers Miami and St. Joseph. This town stood on the E. bank of the latter, opposite the mouth of St. Mary's river, and was destroyed in Gen. Harmar's expedition, in 1790.

OMOAH, a fmall fortified town in the Spanish Main, at the bottom of the bay of Honduras, on the S. fide, and is within a gulf to the eastward of Dolce Gulf, into which the river of its name comes in from the fouthward. It has a good harbour which is open to the N. W. in which thips of any burden may ride in perfect fafety. The British admiral, Parker, in conjunction with the people of Honduras, reduced the ftrong fort, which is fituated on the E. fide of the river, in 1779. The fpoil was immenfe, being valued at 3 millions of dollars. The Spaniards in vain offered 300,000 dollars as a ranfom for 250 quintals of quickfilver; a commodity indifpenfably neceffary in working their gold and filver mines.

OMPOMPANOOSUCK, a fhort, furious river of Vermont, which empties into the Connecticut at Norwich, oppofite to Dartmouth College. Its courfe is S. E. its breadth not more than 40 or 50 yards.

ONDA. See Vincent de la Pazes.

ONATIAYO, or Oneatoyo, an ifland in the S. Pacific Ocean. S. lat. 9. 58. W. long. 138. 51.

ONEEHOW, one of the Sandwich iflands, in the N. Pacific Ocean, called alfo Neeheeheew, about 5 or 6 leagues to the weftward of Atooi. There is anchorage all along the coaft of the ifland. It produces plenty of yams, and a fweet root called tee, N. lat. 21. 50. W. long. 160, 15.

ONEIDA, one of the Six Nations of Indians, containing 628 fouls, who inhabit the country S. of Oneida Lake, called the Oneida Refervation. Their principal village, Kahnonwolohale, is about 20 miles S. W. of Whiteftown. These Indians for a number of years past, have been under the pastoral care of the Reverend Mr. Kirkland, who

ONI

with the Reverend Mr. Sarjeant, have been chiefly fupported in their miffion, by the fociety eftablished in Scotland for promoting Christian knowledge. This nation receive an annuity from the State of New-York of 3552 dollars for lands purchased of them in 1795, and an annuity of about 628 dollars from the United States. With these annuities, (which operate as a discouragement to industry) together with the corn; beans and potatoes railed by the fquaws, and the fifh and game, caught by the men, afford them a barely tolerable fubliftence. They are a proud nation, and affect to despife their neighbours, the Stockbridge and Brotherton Indians, for their attention to agriculture ; but they already begin to feel their dependence on them, and are under a neceffity of purchasing provisions of them. The nation is divided into three tribes, or clans, by the names of the Wolf, the Bear, and the Turtle. They have their name from their Pagan Deity, which fome few of the nation ftill work thip, and which is nothing more than a mithapen, rude, cylindrical flone, of about 120 pounds weight, in their language called Oneida, which fignifies the Upright Stone ' Formerly this ftone was placed in the crotch of a tree, and then the nation fuppoled themfelves invincible. These Indians are all of mixed blood ; there has not been a pure Oneida for feveral years paft.

ONEIDA Lake, is about 20 miles W. of Old Fort Stanwix, now called Rome, State of New York, and is between 20 and 30 miles long, and narrow. It is connected with Lake Ontario on the W. by Ofwego river, and with Fort Stanwix by Wood Creek.

ONEMACK Point is the fouth weft point of the continent of N. America, on the N. W. coait, and the fouth limit of Briftol Bay. It is \$2 leagues S. S. W. of Cape Newenham, or the north point of that extensive bay; and in lat. 54. 30. worth, and long. 162. 30. W. O-NMAMOU, a harbour on the S. E. coat of Ulietea, one of the Society Illands, in the S. Pacific Ocean. It is north-east of Ohetuna Harbour, on the fame coaft.

ONION, Cape, on the fouth-weft fide of Newfoundland Ifland, is about four leagues weft of Quirpon Ifland, or the northern point of that extensive ifland. ONION

ONION mont, for and by th Cabot, at Connectic fmall veffe Lake Cha Burlingto boats bety of the fir runs thro produce o each fide to the lal 20 to 30 mouth, a is 172 fe mile. Be ter this r rock of l of remot at this The cha in depth 70 feet wooden Bolton I kind, bu is at leaf fide feve river, in natural fituation It was a formerly they ma fettleme ONO Referva York, i Caftle. ONO State o long an ters to Salt fpr ing im perfon rate of 1792, bufhel and at in the benefit which as tor neceffa

which

eant, have ir miffion. a Scotland nowledge. from the dollars for 1795, and llars from efe annuiifcouragewith the fed by the ne, caught rely tolerprond naeir neigh-Brotherton to agriculo feel their re under a visions of into three nes of the le. They gan Deity, a ftill worlore than a flone, of their lanignifies the s ftone was ;, and then wes invinl of mixed pure Onei-

miles W. lled Rome, between 20 ow. It is rio on the with Fort

fouth weft America, fouth limit gues S. S. the north and in lat. 3. 30. W. on the S. the Society can. It is our, on the

h-weft fide about four ind, or the five ifland. ONION

ONO

ONION River, in the State of Vermont, formerly called French River, and by the Indians Winoofki, rifes in Cabot, about 14 miles to the west of Connecticut river, and is navigable for fmall vefiels 5 miles from its mouth, in Lake Champlain, between the towns of Burlington and Colchefter; and for boats between its feveral falls. It is one of the fineft ftreams in Vermont, and runs through a most fertile country, the produce of which for feveral miles on each fide of the river, is brought down to the lake at Burlington. It is from 20 to 30 rods wide, 40 miles from its mouth, and its defcent in that diffance is 172 feet, which is about 4 feet to the mile. Between Burlington and Colchefter this river has worn through a folid rock of lime-ftone, which in fome time of remote antiquity muft have formed at this place a prodigious cataract. The chaim is between 70 and 80 feet in depth at low water, and in one place 70 feet from rock to rock, where a wooden bridge is thrown across. At Bolton there is a chaim of the fame kind, but fomewhat wider, and the rock is at least 1 30 feet in height. From one fide feveral rocks have fallen acrofs the river, in fuch a manner as to form a natural bridge at low water, but in a fituation to he an object of curiofity only. It was along this river that the Indians formerly travelled from Canada, when they made their attack's on the frontier fettlements on Connecticut river.

ONONDAGO Cafile, on the Onondago Refervation Lands in the State of New-York, is 25 miles fouth-weft of Oneida Caftle.

ONONDAGO, or Salt Lake, in the State of New York, is about 5 miles long and a mile broad, and fends its waters to Seneca river. The waters of the Salt fprings here are capable of producing immense quantities of falt. One perfon near the lake boiled down at the rate of 50 bufhels a week, in the year 1792, which he fold for five fhillings a bufhel; but any quantity may be made, and at a lefs price. These fprings are in the State refervation, and are a great benefit to the country, every part of which is fo united by lakes and rivers as to render the fupply of this bulky and

neceffary article very easy. ONONDAGO, a river of New-York,

ONS

runs weftwardly into Lake Ontario at Ofwego. It is boatable from its mouth to the head of the lake, 74 miles, except a fall which occasions a portage of 20 yards, thence batteaux go up to Wood-Creek almost to Fort Stanwix, 40 miles, whence there is a portage of a mile to Mohawk river. Toward the head of this river, falmon are caught in great numbers.

ONONDAGO, a county of New-York State, confilting of military lands divided into 11 townships, viz. Homer, Pompey, Manlius, Lyfander, Marcellus, Ulyfics, Milton, Scipio, Aurelius, Ovid, and Romulus. Some of these comprehend other towns, as will be noticed under their respective names. The county is bounded westerly by Ontario co. and northerly by Lake Ontario, the Onondago river, and Oneida Lake. The county courts are held in the village of Aurora, in the township of Scipio. This county is admirably fituated for inland navigation, being interfected by the two navigable rivers Seneca and Ofwego, having befides 5 lakes and a number of creeks. For an account of the referved lands, fee Military Townhips. There were 1 323 of the inhabitants qualified to be electors in 1796, as appears by the State cenfus.

ONONDAGO, formerly the chief town of the Six Nations, fituated in a very pleafant and fruitful country, and confifted of five fmall towns or villages, about 30 miles S. W. of Whiteftown.

ONONDAGOES, a tribe of Indians who live near Onondago Lake. About 20 years fince they could furnish 260 warriors. In 1779 a regiment of men was fent from Albany, by Gen. I. Clinton, who furprifed the town of this tribe, took 33 pritoners, killed 12 or 14, and returned without the loss of a man. A part of the Indians were then ravaging the American frontiers. This nation, which now confifts of 450 fouls, receives annually from the State of New-York, 2,000 dollars; and from the United States about 450 dollars.

ONSLOW, a maritime county of Wilmington diffrict, N. Carolina, W. of Cape Lookout. It contains 5,387 inhabitants, including 1748 flaves. Chief town, Swanfborough.

ONSLOW, a township of Nova-Scotia, Halifax co. at the head of the Bafin of which rifes in the Oneida Lake, and Minas, 35 miles N. E. of Windtor, and

46 N.

46 N. by W. of Halifax. It was fettled by emigrants from New-England.

394

ONTARIO, one of that grand chain of lakes which divide the United States from Upper Canada. It is fituated between lat. 43. 15. and 44. N. and long. 76. 30. and 80. W. Its form is nearly elliptical; its greateft length is from S. W. to N. E. and its circumference about 600 miles. The division line between the State of New-York and Canada, on the N. paffes through this lake and leaves within the United States 2,390,000 acres of the water of Lake Ontario, according to the calculation of Mr. Hutchins. It abounds with fifh of an exceltent flavour, among which are the Ofwego bals, weighing 3 or 4 lbs. Its banks in many places are fleep, and the fouthern fhore is covered principally with beech trees, and the lands appear good. It communicates with Lake Erie by the river Niagara. It receives the waters of Genefice river from the S. and of Onondago, at Fort Ofwego, from the S. E. by which it communicates through Oneida Lake, and Wood Creek, with the Mohawk river. On the N.E. the lake discharges itself into the river Cataraqui, (which at Montreal takes the name of St. Lawrence) into the Atlantic Ocean. It is afforted that theie lakes fill once in feven years; but the fact is doubted. The idands are all at the eaftern end, the chief of which are Wolf, Amherit, Gage, and Howe Islands.

ONTARIO, a large, fertile county of New-York, comprehending the Geneffee country, and bounded N. by the lake of its name. It is well watered by Genefice river, its tributaries, and a number of fmall lakes. Here are \$ townships, viz. Geneffee, Erwine, Jerufalem, Williamsburg, Toulon, Seneca. Bloomfield, and Ganadaqua, or Kanandaigua, which is the laft chief town, fituated at the N.W. corner of Canandarqua Lake, 15 miles W. of Geneva, and 30, N. E. of Williamfburg. This county was taken from Montgomery in 1789, and in 1790 contained 1075 inhabitants, including 11 flaves. Such has been the emigration to this county, that there were, in 1796, 1258 of the inhabitants who were qualified to be electors.

ONZAN, a cape or point on the north. coaft of Brazil, opposite to cape St. Lawrence, forming together the points

of Laguariba river; the latter cape being on the weft fide of the river. The river is 10 leagues S. E. by E. of Bohia Baxa.

OONALASHKA, one of the islands of the northern Archipelago, on the N. W. coaft of America, the natives of which have the appearance of being a very peaceable people, being much polisted by the Russians, who also keep them in subjection. There is a channel between this and the land to the north, about a mile broad, in which are foundings from 40 to 27 fathoms. N. lat. 53. 55. W. long. 166. 31.

OPECKON Creek, in Virginia, a fouthweft water of Patowmac river.

OPPS, a village in Northampton co. Pennfylvania, 6 miles fouth-east of Bethlehem, and about 7 north by east of Quaker's Town.

OR, Cape d', in Nova-Scotia, is fituated on the north fide of the Bafin of Minas. Some imall pieces of copper have been found here.

ORA Cabeca Bay, on the north fide of the ifland of Jamaica, in the W. Indies, has a ftrong fort on the eaft fide, and Salt Gut wetterly; at both these places is good anchorage for large veffels.

ORANAL, or *Ranai*, one of the Sandwich Iflands in the N. Pacific Ocean, 9 miles from Mowee and Morotoi. The fouth point is in lat. 20, 46. north, and long. 156, 52. weft.

ORANG'S Key, one of the Bahama iflands, in the W. Indies. N. lat. 24, 28. wett long. 79. 37.

ORANGE, a bay on the north-east coast of the island of Jamaica, E.N. E. of the high mountain, a little within land, under which is Crawford's-Town. Also a bay at the north-weit end of the fame island, between Green-Island N. and North Negril harbour S. or S. W.

ORANGE, a cape, the east point of Oyapok river, S. E. of Cayenne Island. N. lat. 4, 20. W. long. 50. 50.

ORANGE Key, or Cay, a fmall island in Orange bay, at the north-west end of the island of Jamaica.

ORANGE, a county of Vermont, which in 1790, contained 10,529 inhabitants. Since that time feveral other counties have been erected out of it. It is bounded weft by part of Addifon and Chittenden counties, and eaft by Connecticut river. It now contains 20 townfhips, The The count townships Fairlee and river. It merous ftr both to Co Champlain ORANGI I ne of the eaft corner tain. ORANG thip in G which giv Malcomy in 1796;

is 20 mile ORANC fetts, fitu fhire co. c W, by W rated in 1 tants.

ORANG county of all that p erly by th erly by therly by the and nort from the It is divi Gothen i inhabitar ors, and are raife butter, v and Nev ported t of the 1 very val Lands, (acres. the furre

> and rea they exp cinity to which empties foring, great pl is a brol for acc ened fo

ditcharg

cover th

thereby tract of Indian er. The of Bohia

islands of n the N. uatives of f being a much poalfo keep is a chand to the which are ums. N.

safouth-

pton co. t of Bethy caft of

1, is fitufin of Mipper have

w. Ineast fide, oth these arge vel-

he Sand-Ocean, 9 i. The orth, and

Bahama . lat. 24.

orth-east E. N. E. le within s-Town. ad of the fland N. r S. W. point of e Ifland. o. all ifland cft end of nt, which

abitants. counties s boundid Chitconnectiwnships, The The county town, Newbury, and the townships south of it, viz. Bradford, Fairlee and Thetford front Connecticut river. It is high land, and fends numerous streams in opposite directions, both to Connecticut river and to Lake Champlain.

ORA

ORANCE, a township on the north Ine of the above county, in the northeast corner of which is Knox's Mountain.

ORANGE, formerly Cardigan, a townfhip in Grafton co, New-Hampfhire; which gives rile to an east branch of Malcomy river. It was incorporated in 1796; con ains 131 inhabitants; and is 20 miles east of Dartmouth College.

ORANGE, a township of Massachufetts, fituated on the east line of Hampshire co. on Miller's river, 94 miles N. W. by W. of Boston. It was incorporated in 1783, and contains 784 inhabitants.

ORANGE, a mountainous and hilly county of New-York, which contains all that part of the State bounded foutherly by the State of New-Jerfey, wefterly by the State of Pennfylvania, eafterly by the middle of Hudfon's river, and northerly by an east and weft line from the middle of Murderer's Creek. It is divided into 8 townships, of which Gothen is the chief, and contains 18,492 inhabitants, of whom 2098 are electors, and 966 flaves. In this county are raifed large quantities of excellent butter, which is collected at Newburgh and New-Windfor, and thence tranfported to New-York. On the N. fide of the mountains in this county, is a very valuable track called the Drowned Lands, containing about 40 or 50,000 acres. The waters which defcend from the furrounding hills, being but flowly ditcharged by the river iffuing from it, cover these valt meadows every winter, and render them extremely fertile; but they expose the inhabitants of the vicinity to intermittents. Wallkill river, which paffes through this tract and empties into Hudson river, is, in the fpring, flored with very large eels in great plenty. The bottom of this river is a broken rock; and it is supposed that for 2000l. the channel might be deepened to as to drain off the waters, and thereby redeem from the floods a large tract of rich land, for grafs, hemp and Indian corn.

ORA

ORANGE, called alfo Orangedale, a town in Effex co. New-Jerfey; containing about \$0 houfes, a Prefbyterian, church, and a flourifhing academy, and lies north-weft of Newark, adjoining.

ORANGE, a co. of Hillfborough diftrict, North-Carolina; bounded north by Cafwell co. and fouth by Chatham. The rivers Haw and Ence in this county have rich lands on their borders. It contains 12,216 inhabitants, of whom 2060 are flaves. Chief town, Hillfborough.

ORANGE, a county of S. Carolina, in Orangeburg diffrict.

ORANGE, a county of Virginia, bounded north by Culpepper, and fouth by Albemarle. It contains 9921 inhabitants, including 4421 flaves. The courthoufe is fituated so-miles from Culpepper court-houfe, 30 from Charlotteville, and 273 from Philadelphia.

ORANGEBURG, a ditrict of S. Carolina, bounded fouth-weft by Savannah river; eaft by the river Santce, and north-eaft by the Congaree, which divide it from Camden diftrict; fouth by Beaufort, and fouth-eaft by Charlefton diftrict. It contains 18,513 inhabitants; of whom 5931 are flaves. Sends to the State legislature 10 reprefentativés and 3 fenators; and with the diftrict of Beaufort, one member to Congrefs. It is divided into 4 counties, viz. Lewifburg, Orange, Lexington and Winton.

ORANGEBURGH, a post town of S. Carolina, and capital of the above diftrict, is on the E. fide of the N. branch of Edifto river. It has a court-house, gaol, and about 50 houses; diftant 77 miles N.N.W. of Charlestown, 36 southerly of Columbia, and 721 from Philadelphia.

ORANGETOWN, or Greenland, a plantation in Comberland co. Maine, N.W. of Waterford. One branch of Songo river rifes in the northern part of this plantation, within about 3 miles of Amarifcoggin river, where there is a pond, 2 miles long, called Songo Pond, from thence the fream runs louthward. It is very difficult to effect roads through this mountainous courtry; tome of the mountains affording precipices 200 feet perpendicular. The fides of the mountains and vallies are fertile, produce good crops, and in fome inftances afford wild onions which refemble those that are cultivated

cultivated. Winter rye, which is the chief produce, has amounted to zo bufnels an acre. The country in the neighbourhood formerly abounded with variety of game, viz. moofe, deer, bears, beaver, raccoon, fable, &c. but fince it has been inhabited, game has become fearce; deer are extirpated from the vicinity; fome moofe remain smong the mountains, and a few beaver, that are too fagacious to be taken by the most crafty hunter. Since the deer have been deftroyed, the wolves have wholly left this part of the country.

ORT

ORANGETOWN, in Orange co. New-York, is fituated on the welf fide of the Tappan Sea, opposite Philipsburgh, and about a7 miles north of New-York city. The township is bounded casterly by Hudson's river, and southerly by the State of New Jersey. It contains 1175 inhabitants; of whom 162 are electors, and so3 are flaves.

ORANGETOWN, in Washington co. Maine, is 19 miles distant from Machias.

ORCHILLA, one of the Leeward Iflands in the Weft-Indies, fituated near the coaft of Terra Firma, S. America ; between the iflands of Tortuga and Roca, 15 or 16 leagues north-weft of the former, and 6 or 7 E. and E. by N. of the latter. It is about 8 leagues long. On the S. and S. W. fide, the ftrand is fleep and bold, fo that a fhip may lay her broad fide close to the fhore; but the north fide is foul and rocky. Here is no good water, nor indeed any thing elie but thelter from northerly winds, and goat's flefh. It is divided into feveral fimall iflands, feparated from each other by thallow canals. N. lat. 11. 52. W. long. 65. 15.

ORCOS, a lake of Peru.

ORDADO Reck, near the coaft of Peru, is 4 miles fouth by eaft of Port Callao. Near it are fome fmaller ones, and round them from 9 to 16 fathoms water. OREAHOU, or Oreeboa, a fmall elevated ifland, close to the north fide of Onceheow, one of the Sandwich Iflands; with which it is connected by a reef of coral rocks. It contains about 4000 inhabitants. N. lat. 22. 2. W. long. 166, 8.

OREGAN River. See River of the Weft.

ORFORD, a township in Grafton co. New-Hampshire, situated on the east

bank of Connecticut river, about 12 miles north of Hanover, and opposite to Fairlee in Vermont, 395 miles N. N. E. of Philadelphia. It was incorporated in 1761, and contains 540 inhabitants. The foap-rock, which has the property of fuller's earth in cleanfing cloth, is found here; also allum ore, free-ftone fit for building, and a grey-ftone, in great demand for millftones, reckoned equal in quality to the imported burr ftones.

ORFORD, Cape, the north-weffernmost point of the large island to the westward of Falkland's Sound in the Falkland's Islands, in the S. Atlantic Ocean, and fouth-east of Cape Percival.

ORINORO. See Oronoks River. ORLEANS, the middle of the three northern counties of Vermont. A part of Lake Memphremagog projects into the northern part of it from Canada. It contains 23 townfhips. It is very high land, and fends its waters in almost every direction of the compais. Clyde, Barton and Black rivers empty into Lake Memphremagog; the waters of many branches of Mifficoui, La Moelle, and Onion rivers, rifing here, fall into Lake Champlain; thole of Mulhegan and Paíumplick empty into Connecticut river.

ORLEANS, a township in the co. of Barnstable, Massachuletts, taken from the southerly part of Eastham, and incorporated 1797.

ORLEANS, Iffe of, is fituated in the river St. Lawrence, a fmall diffance helow Quebec, and is remarkable for the richneis of its foil. It lies in the middle of the river, the channel is upon the S. fide of the ifland, the N. fide not having depth of water at full tide, even for fhallops. The S. W. end of the ifland is called Point Orleans. The coaft is rocky for a mile and a half within the S. channel, where there is a carcening place for merchant fhips. Round Point Levi, and along the S. E. fide of the river, the fhore is rocky, but the middle of the balon is entirely free.

ORLEANS, New. See New Orleans. ORLEANS, Old Fort, is fituated on the W. bank of a bend of Miffouri river, in Louifiana, a confiderable diffance from its mouth.

ORODADA PENA, on the coaft of Peru, is two leagues due north of Lobos de Payta, and 2 fouth by weft of Payta. OROMCOTO,

OROMC wick, whi river. By have a con quoddy Ba ORONDO live near T nifh 100 W ORONO largeft rive markable t a year only ing the fr remains o which it fa ftate conti Thefe alte and even il of the wat on the rain mountains river has the month height of the breadt river, yet roweft, it of 120 feet S, by E. (30. N. an fite to the and navig on its ban by the Sp E. fide 1 are two o entrance t gerous, a conflict t and the c for the re very rapi cluding i 1380 mil of its wi mouth o within w be confid mouths, iflands tl wards th that are purpofes the chan otherwife ter lies is alfo d acls that ifland of

about IT oppolite iles N.N. corporato inhabih has the cleanflfo allum ing, and for millity to the -wefternnd to the d in the Atlantic Percival. ver. the three A part ects into Canada. is very in almost Clyde, pty into vaters of Moelle, fall into lulhegan mecticut e co. of en from and ind in the diftance able for

able for is in the is upon fide not de, even l of the . The l a half ere is a t fhips. we S. E. ky, but ely free. Drieans. ated on ouri rivdiftance

FLobos Payta. ORO

OROMCOTO, a river of New Brunfwick, which empties into St. John's river. By this paffage the Indians have a communication with Paffamaguoddy Bay.

ORONDOCKS, an Indian tribe who live near Trois Rivieres, and could furnifh too warriors about 20 years ago.

ORONOKO, or Oronoque, one of the largeft rivers of S. America, and is remarkable for its rifing and falling once a year only ; for it gradually rifes during the space of 5 months, and then remains one month flationary, after which it falls for c months, and in that state continues for one month alfo. Thefe alternate changes are regular, and even invariable. Perhaps the rifing of the waters of the river, may depend on the rains which constantly fall in the mountains of the Andes, (where the river has its fource) every year about the month of April; and though the height of the flood depends much upon the breadth or extent of the bed of the river, yet in one part where it is narroweft, it rifes to the aftonishing height of 120 feet. The mouth of the river is S, by E. of the Gulf of Paria, in lat. 8. 30. N. and long. 59. 50. W. and oppofite to the Ifland of Trinidad. It is large and navigable, and has many good towns on its banks, that are chiefly inhabited by the Spanish, and is joined alfo on the E. fide by the Lake Calipa. There are two other illands at its mouth, the entrance to which is also fomewhat dangerous, as there is frequently a dreadful conflict between the tide of the ocean and the current of the river, that muft, for the realons affigned, fometimes run very rapidly." It is faid the river, including its windings, takes a courfe of 1380 miles, and preferves the frefhnefs of its waters twelve leagues from the mouth of that vaft and deep channel, within which it was confined. It may be confidered, however, as having many mouths, which are formed by the iflands that lie before its opening towards the ocean; yet there are only two that are confidered as of any ule for the Thefe are purpoles of navigation. the channels of Sabarima and Corobana, otherwife called Caribbiana. The latter lies in a S. by W. direction, and is also divided into two diffinct channels that afterwards meet again at the island of Trinidad in the mouth of the

Grand river. But pilots pretend to fay, that the mouth of this great river begins from the river Amugora, reaching from thence to the river Sabarima. and from thence about to the river Caribbiana ; and fome accounts flate its mouths to be 40 in number, as if it were a collection of many rivers, all uniting at the mouth of the great river, and al. fifting to convey the main fream of that river into the ocean. The weft paffage or channel of the river Oronoko, called by the Spaniards the Gulf of Paria, lies between Cape Salinas on the main and the north-welt point of the ifland of Trinidad. It contains feveral iflands, which divide the fiream of the river into feveral branches, particularly the Great Boco, or mouth, which is the easternmost, being about gun fhot wide, but having no foundings, with 300 fa-thoms, and the Little Boco, or Mouth, which is the westernmost, being almost as wide as the other, and having ground at from so to 60 fathoms. At New Cape Araya, on the northward fide of the mouth of this river, are fast pits, which yield the fineft falt in the world. In fome maps, the head-waters are called Inirchia.

ORONOKO, Little. See Mocomoco.

OROPESA, a town in the jurifdiction of La Piata, S. America; fituated 60 miles N. W. of that city, in the valley of Cochabamba, on a finall rivulet which empties into the river Guapay. It has a confiderable trade in corn and fruits.

OROPESA, a town of S. America, in Peru, feated at the foot of the mountains, 750 miles from Lima, and 150 N. E. of Popofi. S. lat. 18. W. long 63. 30.

ORPHAN'S Bank, a fifting bank of the S. E. point of Chaleur's Bay, on the N. E. coaft of New-Brunfwick, in N. America. On it is from 75 to 30 fathoms water.

ORPHAN'S Ifland, a fettlement belonging to Hancock co. Diffrict of Maine, having 124 inhabitants.

ORRINGTON, a plantation in Hancock co. Diffrict of Maine, having 477 inhabitants. It lies on the east fide of Penobicot river, 16 miles above Buckftown, and 256 N.N.E. of Bofton.

ORUA, Orubo, or Aruba, the most westerly of the Caribbee islands in the West Indies, called by the Spaniards Las Islas de Sottoyento. It is on the coait

055.

398

coaft of the Spanish Main. N. lat. 12. Great Officer River, which empties into 3. W. long. /69. 3. Saco river, near the division line be-

ORURO, /a jurifdiction in the archbishopric of La Plata. Its capital is San Phelipe de Austria de Oruro, 30 leagues from the city of La Plata.

ORWEL, a township of Vermont, the north-westernmost in Rutland co. and fituated on the east fide of Lake Champlain. It contains 778 inhabitants. Mount Independence stands in this township opposite Ticonderoga, in the State of New-York. Near Mount Independence is a chalybeate spring.

OSAGES, an Indian nation who inhabit fouth of the Miffouri, and can furnifh 400 with fors.

OSAGES, a river of Louifiana, which runs eaftward to the Miffouri.

OSNABURG, a finall ifland in the S. Pacific Ocean, having the appearance of the roof of a houle. It is about 4 leagues in circuit; is high land; full of cocoa-trees; has no anchoring place, and fearcely affords landing for a boat. It was diffeovered by Capt. Wallis, and is called *Maitea* by the natives. S. lat. 17. 52. W. long. 148. 6.

OSNABURG, another ifland in the fame fea, difcovered by Capt. Carteret. S. lat. 22. W. long. 141. 34.

lat. 22. W. long. 141. 34. OSNABURG Houje, a fettlement of the Hudfon's Bay Company, in N. America; fituated at the N. E. corner of Lake St. Jofeph, 120 miles W. by S. of Gloucefter Houfe, N. lat. 51. W. long. 00. 15.

ter Houfe. N. lat. 51. W. long. 90. 15. OSORNO, an inland town of the kingdom of Chili, fituated on the N. bank of the river Buena; 42 miles E. of the fea-coaft, and 45 S. E. of Baldivia. The adjacent country is far from being fruitful, but very rich in gold mines, which renders the place very populous. S. lat. 40. 30. W. long. 71. 50.

OSSABAW Sound and Island, on the coaft of the State of Georgia. The found opens between Waflaw Island on the N. and Offabaw Island on the S. and leads into the river Ogeochee.

OSSIPEE, or Ofapy, a townfhip, mountain, and pond, in New-Hampfhire, in Strafford co. near the E. line of the State. The town was incorporated in 1785, and has 139 inhabitants. The lake lies N. E. of Winnipifeogee Lake, between which and Offipee Lake is Office Mountain, defcribed in the account of New-Hamplhire. Its waters run E. and, joined by South river, form

O S W

Great Office River, which empties into Saco river, near the division line between York and Cumberland counties, in Maine, between Limerick and Gorham.

OSSNOBIAN, or Affeneboyne Indians, a tribe found about the fource of Offnobian or Affeneboyne river, far W. of Lake Superior. They are faid by the Moravian miffiona ies to live wholly on animal food, or at leaft to confine themfelves to the fpontaneous productions of nature; giving those who dig the ground, the appellation of Aaves. Bread is unknown to them. A traveller, who lived fome months in their country, offered to fome a few remnants of bread, which they chewed and fpit out again, calling it rotten wood. These Indians, as well as those numerous nations who inhabit the country from Lake Superior, towards the Shining Mountains, are great admirers of the best huntinghorfes, in which the country abounds. The horfes prepared by them for hunters, have large holes cut above their natural noftrils, which they fay makes them longer winded than others not thus. prepared, The Offnobians have no permanent place of abode, but live wholly in tents, made of buffaloe and other hides, with which they travel from one place to another, like the Arabs ; and as foon as the food for their horfes is expended, they remove, and pitch their tents in another fertile fpot; and fo on continually, fcarcely ever returning to the fame fpots again.

Ostico, a finall lake in Onondago co. New-York, partly in the S. E. corner of Marceilus, and N. W. corner of the township of Tully. It fends its waters from the N. end, which is eight miles S. westerly of Onondago Castle, by a stream 16 miles long, to Salt Lake.

OSTINES, or Charlestown, a confiderable town in the ifland of Barbadoes.

OSWEGATCHIE River and Lake, in Herkemer co. New-York. The river empties into the river St. Lawrence, or Cataraqui. Of wegatchie Lake is about 19 miles long. from S. W. to N. E. and 7 broad, and fends its waters north eaftward into the river of its name. It is about 10 miles S. E. of The Thoufand Lakes, near the entrance into Lake Ontario. There is a fort of the fame name fituated on the Cataraqui river, 58 miles

s miles N Ontario. OswEG! refiding at § Lawrence, furnish abo fince. OSWEGO York, wh Oneida an into Lake monly calle OSWEGO E. fide of t and fouthin lat. 43. It was tal French in a by the peac up to the L It is about of Niagara OTABA vince of C that of Sa lands are produce gr Indians in who are in variety of ions for be wholly of variegated which are province (they are di The whea like India diftant from corns into reap above try is rea quantities OTABA the above pulous, an 20,000 for fiderable n ОТАНА in the S. end is in 151. 20.1 See Obam OTAHI who firft the Societ

It was fir 1767, and and other OTA

Ontario.

OSWEGATCHIES, an Indian tribe refiding at Swagatchey, on the river St. Lawrence, in Canada. They could furnish about 100 warriors, 20 years fince.

OswEGO, a navigable river of New-York, which conveys the waters of Oneida and a number of fmall lakes, into Lake Ontario. It is more commonly called Onondago; which fee.

OswEGO, a fortress fituated on the E. fide of the mouth of the above river, and fouth-eastern fide of Lake Ontario, in lat. 43. 18. N. and long. 76. 30. W. It was taken by the British from the French in 1756, and confirmed to them by the peace of 1763. It was delivered up to the United States, July 14, 1796. It is about 1 50 or 160 miles E. by N. of Niagara.

OTABALO, a jurifdiction of the province of Quito, joined on the fouth to that of San Miguel de Ibarra. The lands are laid out in plantations, and produce great quantities of fugar. The Indians in the villages, as also those who are independent, manufacture great variety of cottons, viz. carpets, pavilions for beds, quilts in damafk work, wholly of cotton, either white, blue, or variegated with different colours; all which are bighly valued, both in the province of Quito and Peru, where they are disposed of to great advantage. The wheat and barley here, is fowed like Indian corn, in little holes, a foot. diftant from each other, putting 5 or 6 corns into each; and they generally reap above an hundred fold. The country is remarkably fertile, and large quantities of cheele are made.

OTABALO, the principal village of the above jurifdiction, is large and populous, and faid to contain 18,000 or 20,000 fouls. Among them is a confiderable number of Spaniards.

OTAHA, one of the Society Iflands in the S. Pacific Ocean, whole north end is in lat. 16. 33. fouth, and long. 151. 20. weff. It has 2 good harbours. See Obamene and Oberurua.

OTAHEITE, the Sagitaria of Quiros, who first discovered it in 1606, one of the Society Iflands, in the South Sea. It was first visited by Capt. Wallis, in 1767, and afterwards by Capt. Cook and other circumnavigators. It confifts

2314643

st miles N. E. of Kingfton, on Lake | of 2 peninfulas, which are connected by a low neck of land, about 2 miles over : the circumference of both peninfulas is fomewhat more than 90 miles. The whole island is furrounded by a reef of coral rocks, within which the fhore forms feveral excellent bays and harbours, where there is room and depth of water for any number of the largest thips. The face of the country, except that part of it which borders upon the fea, is very uneven ; it rifes in ridges that run up into the middle of the ifland, and there form mountains, that may be feen at the diffance of 60 miles. Between these ridges and the sea is a border of low land, extending along all the coaft, except in a few places, where the ridges rife directly from the fea. This border is of different breadths, but no where more than a mile and a half. There are feveral rivers much larger than could be expected from the extent of the island; among the rocks through which these precipitate their waters from the mountains, not the least appearance of minerals is to be found. The ftones fhew evident tokens of having been burnt. Traces of fire are alfo manifest in the very clay upon the hills. It may therefore not unreasonably be fupposed, that this and the neighbouring iflands are either fhattered remains of a continent, which were left behind when the reft was funk by the explofion of a fubterraneous fire, or have been. torn from rocks under the bed of the fea, by the fame caufe, and thrown up in heaps to an height which the waters never reach. The foil, except upon the very tops of the ridges, is extremely rich and fertile, watered by a great number of rivulets of excellent water, and covered with fruit trees of various. kinds, fome of which are of a flately growth and thick foliage, fo as to form one continued wood; even the tops of the ridges, though in general bare and burnt up by the fun, are in fome parts not without their produce. The low lands between the foot of the ridges and the fea, and fome of the interjacent vallies, are the only parts of the ifland that are inhabited. Here indeed it is populous. The houses do not form villages or towns, but are ranged along the whole border, at the diffance of about 50 yards from each other. When the island was first difervered, hogs,

pties into line becounties, and Gor-

e Indians,

of Offno-

ar W. of

uid by the wholly on ine themoductions o dig the ves. Bread eller, who intry, ofof bread, out again, e Indians, tions who Superior, ains, are huntingabounds. for hunttheir naay makes s not thus. have no but live faloe and ey travel like the 1 for their iove, and tile fpot ; y ever ren. Duondago, 5. E. corcorner of fends its h is eight. to Caffle, to Salt confideradoes. Lake, in The river rence, or

is about

I.E. and

orth-eaft-

ne. It is

Choufand

to Lake

the fame

ui river,

58 miles

dogs

400

animals ; ducks, pigeons, paroquets, with a few other birds and rats, the only wild animals. The breed of hogs has been reatly improved by fome of a larger kind, that were left by the Spaniards in 1774. Goats were first introduced by Capt. Cook in 1773; to thefe the Spa-niards have added fome, and they are now in fuch plenty, that every chief of any note as them. Cats were left by Capt. Cook, and European dogs of feveral forts by the Spaniards. In 1777, the flock of new animals received the important addition of a turkey cock and hen; a peacock and hen; a gander and 3 grefe ; a drake and 4 ducks ; a horfe and mare; a bull and 3 cows. A bull and a ram had been alfo left by the Spaniards. Beafts of prey, or noxious reptiles, there are none. The vegetable productions are bread-fruit, cocoanuts, bannanas of 13 forts, and all excellent ; plantains ; a fruit refembling an apple; fweet potatoes, yams, and cocoas. The people exceed the middle fize of Europeans in stature. In their difpofitions, they are brave, open, and generous, without either fufpicion or treachery. Except a few traces of natural cunning, and fome traits of diffimulation, equally artlefs and inoffenfive, they poffels the most perfect fimplicity of character. Their actions are guided by the immediate impulse of the reigning paffion. Their paffions are the genuine effutions of the heart, which they have never been taught to difguife or reprefs, and are therefore depictured by the ftrongeft expressions of countenance and gesture. Their feelings are lively, but in no cafe permanent : they are affected by all the changes of the paffing hour, and reflect the colour of the time, however frequently it may vary. Their vivacity is never diffurbed by anxiety or care, infomuch, that when brought to the brink of the grave by difeafe, or when preparing to go to battle, their faces are unclouded by melancholy or ferious reflection. Their language is, foft and melodious; it abounds with vowels, and is eafily pronounced. It is rich in beautiful and figurative expreffions, and admits of that inverted arrangement of words, which diffinguishes the ancient from moft modern lauguages. It is fo copious, that for the bread-fruit alone they | 197 inhabitants.

elogs and poultry were the only tame have above twenty names. Add to thise that befides the common dialect, they often expostulate in a kind of stanza or recitative, which is answered in the fame manner. The 2 peninfulas formerly made but one kingdom. They are now divided into two, under the names of Opureanou or Otaheitenooe, and Tirabou ; although Otoo, the fovereign of the former, still possesses a neminal fuperiority over the latter, and is ftyled king of the whole ifland. To him also the island of Eimeo is subject. These kingdoms are subdivided into districts, each with its respective chief. The number of inhabitants in 1774, was effimated by Capt. Cook at 204,000. Wars are frequent between the two kingdoms, and perhaps between feparate districts of each. The inhabitants of Eimeo are often excited by fome powerful chief to affert their independence. The power and ftrength of this and the neighbouring iflands lie entirely in their navies; and all their decifive battles are fought on the water. Ctaheite alone is fuppofed able to fend out 1720 war canoes, and 68,000 able men. The chief of each district superintends the equipping of the fleet in that diftrict; but they must all pass in review before the king, fo that he knows the ftate of the whole before they affemble to go on fervice. Otaheite lies in about 18 deg. of S. lat. and 1 50 deg. of W. lon. OTAROOTAL, a fimall ifland in the S. Pacific Ocean, 4 leagues from Watecoo, and about 3 miles in circuit. S. lat. 19.

> 15. W. long. 158. 23. OTCHIER, a bay on the north coaft of S. America, to the weftward of the river or creek called Urano, and east of Cape Caldero.

OTEAVANOOA, a large and spacious harbour and bay on the fouth west coast of the ifland of Bolabola, one of the Society Iflands. S. lat. 16. 30. W. long. 151.43.

OTISFIELD, a plantation in Cumberland co. District of Maine, east of Bridgetown in York co, and 152 miles N. N. E. of Bofton. A ftream from Songo Pond paffes through the wellerly part of this town, on its way to Sebago. It is very free of ragged hills and mountains. The greatest part of it affords a growth of beech, maple, afh, hafs, and birch, and is good land. It contains 248 - C.Y.Y.

OTOGAN N. W. terr the Lake of river. Wa OTOQUE Ocean, or fituated in th S. of the cit it is fupplie 7. 50. W. OTSEGO. on the S. fic fite the G waters of Si quage bran this county. Otlego, and their waters Sufquehann viz. Kortrig Cherry Vall fego, Burlin tained, a f inhabitants rapid fettler January 179 ants, qualifi when this co as many as were manuf The courts the townshi

OTSEGO. county abou was taken f rated in 179 encloses La it from Ch is about nin than a mile banks are v of it eafy. inhabitants; ftate cenfus its inhabita OTTAW. W. territor of Lake Mi limackinack lie between ! They could years ago. near St. Joh Another tri

on Saguinan raife 200 w lately hoftil with the U August 3d,

DGAMIES,

OTT

OTOGAMIES, an Indian nation in the N. W. territory, who inhabit between the Lake of the Woods and Miffifippi river. Warriors 300.

Oroque, an ifland on the N. Pacific Ocean, or W. coaft of New-Mexico, fituated in the Bay of Panama, 17 leagues S. of the city of that name, from whence it is fupplied with provisions. N. lat. 7. 50. W. long. 81. 10.

OTSEGO, a county of New-York, on the S. fide of Mohawk river, oppofite the German Flats. The head waters of Sufquehannah, and the Cookquage branch of Delaware, interfect this county. Here are also the lakes Otfego, and Caniaderago, which fend their waters, in an united fream, to the Sufquehannah. It contains 9 townships, viz. Kortright, Harpersfield, Franklin, Cherry Valley, Dorlach, Richfield, Otfego, Burlington; and Unadilla. It contained, a few years ago, about 1000 inhabitants; but fuch has been the rapid fettlement of this county, that in January 1796, it contained 3237 inhabitants, qualified to be electors. In 1791, when this county was but thinly fettled, as many as 300 chefts of maple fugar, were manufactured here, 400lbs. each. The courts are held at Cooperftown, in the township of Otfego.

OTSECO, a township and lake, in the county above deferibed. The township was taken from Unadilla, and incorporated in 1796. On the E. the township encloses Lake Otfego, which separates it from Cherry Valley. Lake Otlego is about nine miles long, and little more than a mile wide. The lands on its than a mile wide. banks are very good, and the cultivation of it eafy. In 1790, it contained 1702 inhabitants, including 8 flaves. By the ftate cenfus of 1796, there were 490 of its inhabitants electors.

OTTAWAS, an Indian nation in the N. W. territory, who inhabit the E. fide of Lake Michigan, 21 miles from Michilimackinack. Their hunting grounds lie between Lakes Michigan and Huron. They could furnish 200 warriors 20 years ago. A tribe of thefe alfo lived near St. Jofeph's, and had 1 50 warriors. Another tribe lived with the Chippewas, on Saguinam Bay, who together could raile 200 warriors. Two of these tribes lately hoftile, figned the treaty of peace with the United States, at Greenville, 401

lands ceded by them to the United States, government has agreed to pay them in goods, 1000 dollars a year, for ever.

OTTAWAS, a large river of Canada, which empties into the St. Lawrence at the Lake of the Two Mountains, 9 miles from Montreal. The communication of the city of Montreal with the high lands, by this river, if not impracticable, is at least very expensive and precarious, by reason of its rapids and falls.

OTTER Bay, on the fouth coaft of the ifland of Newfoundland, is between Bear Bay and Swift Bay, and near Cape

Raye, the fouth-west point of the island. OTTER Creek, called by the French Riviere a Lotris, a river of Vermont, which rifes in Bromley, and purfuing a northern direction about 90 miles, empties into Lake Champlain at Ferrifburg ; and in its course receives about 15 fmall tributary fireams. In it are large falls at Rutland, Pittsford, Middlebury, and Vergennes. Between the falls the water is deep and navigable for the largeft boats. Veffels of any burden may go up to the falls at Vergennes, 5 miles from its mouth. The head of this river is not more than 30 feet from Batten Kill, which runs in a contrary direction, and falls into Hudfon's river. Its mouth is 3 miles north of Bason Harbour.

OTTER Creek, a finall ftream which empties into Kentucky river, in the State of that name, and E. of Boonfborough.

OTTER's Head, a small peninfula, projecting from the north-eaftern fhore of Lake Superior, and north-weft of Michipicoton Ifland.

OUABASH. See Wabaft River.

OUAIS's Bay and River, are about 2 leagues round the north point of the ifland of Cape Breton, in the Gulph of St. Lawrence, and fouth-fouth-weft of the ifland of Limbach.

OUANAMINTHE, a French parifh, and village on the N. fide of the illand of St. Domingo, about a league and a half W. of Daxabon, in the Spanish part, from which it is feparated by the river Maffacre; 6 leagues from the mouth of the river, and 5 S. E. of Fort Dauphin.

OUAQUAPHENOGAW, or Ekanfanoka is a lake or rather marsh, between Flint and Oakmulgee rivers, in Georgia, and is nearly 300 miles in circumference. In wet feafons it appears like an August 3d, 1795. In confequence of inland fea, and has feveral large iflands Cc

fay it is inhabited by a peculiar race of Indians, whole women are incomparably beautiful. They tell that this terrestrial paradife has been seen by some enterprizing hunters, when in purfuit of their game, who being loft in inextricable fwamps and bogs, and on the point of perifhing, were unexpectedly relieved by a company of beautiful women, whom they call daughters of the Sun, who kindly gave them fuch provisions as they had with them, confifting of fruit and corn cakes, and then enjoined them to fly for fafety to their own country, because their husbands were fierce men and cruel to ftrangers. They further fay that these hunters had a view of their fettlements, fituated on the elevated banks of an island, in a beautiful lake; but in all their endeavours to approach it, they were involved in perpetual labyrinths, and, like enchanted land, ftill as they imagined they had just gained it, it feemed to fly before them; and having quitted the delufive purfuit, they with much difficulty effected a retreat. They tell another ftory conceraing this sequestered country, which feems not improbable, which is, that the inhabitants are the posterity of a fugitive remnant of the ancient Yamafes, who escaped maffacre after a bloody and decifive battle between them and the Creeks, (who, it is certain, conquered and nearly exterminated that once powerful people) and here found an afylum, remote and fecure from the fury of their proud conquerors. The rivers St. Mary and Sitilla, which fall into the Atlantic, and the beautiful Little St. Juan, which empties into the bay of Appalachi at St. Mark's, are faid, by Bartram, to flow from this lake.

OUASIOTO Mountains are fituated N. W. of the Laurel Mountains in N. Carolina and Virginia. They are so or 60 miles wide at the Gap, and 450 in length N. E. and S. W. They abound in coal, lime, and free-ftone. Their fummits are generally covered with good foil, and a variety of timber, and the intervale lands are well watered. OUEPAS, a town on the coaft of Cof-

ta Rica, on the N. Pacific Ocean, and S. of Carthago.

OVI

of rich land; one of which the prefent generation of Creek Indians reprefent as the most blifsful spot on earth. They N, and long. 87. 58. W. and faid to be fide of the Wabash river, in lat. 40. 38. N. and long. 87. 58. W. and faid to be about 130 miles foutherly of Fort St. Joseph. This was formerly a French post. Thus far the Wabash is navigable, 412 miles from its mouth, for batteaux drawing 3 feet water. A filver mine has been discovered here. The neighbouring Indians are the Kickapoos, Mulquitons, Pyankishaws, and a principal part of the Ouiatanons. The whole of these tribes could furnish, about 20 years ago, 1000 warriors. The fertility of foil, and diversity of timber in this country are the fame as in the vicinity of Poft St. Vincent.

OUINEASKE, or Shelburne Bay, on the E. fide of Lake Champlain, fets up S. eafterly through the town of Burlington, in Vermont into the northern part of Shelburne.

OUISCONSING, a navigable river of the N. W. territory, which empties into the Miffifippi in lat. 43. 33. and long. 94. 8.; where are villages of the Sack and Fox tribes of Indians. This river has a communication with Fox river, which, paffing through Winnebago Lake, enters Puan Bay in Lake Michigan. Between the two rivers there is a portage of only 3 miles. On this river and its branches refide the Indians of its name. Warriors 300.

OULIONT, a village of the flate of New-York, on the poaft-road from Hudfon to the Painted Poft. It is 35 miles W. of Harpersfield, and 50 N. E. of Union, on Sufquehannah river, and lies on the north fide of a creek of its name which empties into Unadilla river.

OUTER Buoy, in Hudson's Bay, lies in lat. 51. 38. N. and five miles E. of North Bluff.

OUTER Mand, on the coast of Labrador, is in the clufter called St. Auguffine's Square; S. W. of Sandy Ifland, and east of Inner Ifland.

OUTIMACS, a tribe of Indians, in the N.W. Territory, reliding between Lakes Michigan and St. Clair. Warriors 200.

OVEN'S MOUTH Bay, in the diffrict of Maine, lies on the S. fide of Boothbay township, in Lincoln co. 12 miles from the fhire town, and 190 N. by E. of Bofton.

Ovid, a township of New-York, in Onondago co. It was incorporated in OUIATANON, a fmall flockaded fort 1794; is feparated from Milton on the

E. by Cayu all the lands fide of Sent the township fide of the 1796, there qualified to OWASCO of Aurelius co. New-Y long, and or with Seneca which runs The high r ward, paffe near the N. OWEGO, New-York, Sufquehann Union, 34 Point, and 1796, 170 1 OWEGO as the eaft | its name. which unite bank of the river, abou of Cheneng OUYAT the coaft of the Gulf c weftward of OWHAR ern part of one of the N. W. by lat. 16. 44 OWHYH Sandwich] circumferer #6. N. lat. # 7. E. long. tenfive mot on the S. E feet high. which are fnow, thou are vifible the fouther lage called eastern fide eastern pai is on the ne north-wefte Toyahyah N. W. of I kooa. It the Society 100.15

40Z

ne Bay, on in, fets up n of Burne northern

ble river of empties in-, and long. of the Sack This river Fox river, Winnebago ake Michirs there is . On this the Indians

the flate of from Hudis 35 miles to N. E. of er, and lies of its name a river. flon's Bay, five miles E.

oaft of Laed St. Auof Sandy nd. dians, in the tween Lakes

arriors 200. n the diffrict le of Booth-10, 12 miles 90 N. by E.

w-York, in orporated in lilton on the OWH

E. by Cayuga Lake, and comprehends all the lands in the county on the W. fide of Seneca Lake. The centre of the township is 20 miles S. of the W. fide of the ferry on Cayuga Lake. In 1796, there were 107 of its inhabitants qualified to be electors:

Owasco, a lake, partly in the towns of Aurelius and Scipio, in Onondago co. New-York. It is about 11 miles long, and one broad, and communicates with Seneca river on the N. by a ftream which runs through the town of Brutus. The high road from Kaats' Kill weftward, paffes towards Cayuga ferry, near the N. end of the lake.

OWEGO, a poft-town in Tioga co. New-York, on the east branch of the Sufquehannah, 20 miles wefterly of Union, 34 N. E. of Athens, at Tioga Point, and 284 from Philadelphia. In 2796, 170 of its inhabit. were electors. OWEGO Creek, in Tioga co. ferves as the east boundary of the township of its name. It has several small branches which unite and empty through the N. bank of the east branch of Sufquehannah river, about 184 miles W. of the mouth of Chenengo river.

OUVATOISKA Bay and River, on the coaft of Efquimaux, or N. fhore of the Gulf of St. Lawrence, is to the weftward of Natachquoin river.

OWHARREE, a harb our on the northern part of the weft coaft of Houaheine, one of the Society Islands, 25 leagues N.W. by W. of Otaheite Island. S. lat. 16. 44. W. long. 151. 8.

OWHYHEE, one of the largeft of the Sandwich Islands, is about 300 miles in circumference; between 18. 50. and 20. #6. N. lat. and between 203. 48. and 205. 7. E. long. from Greenwich. The extenfive mountain, named Mouna Roa, on the S. E. part of the island, is 16,020 feet high. It confitts of three peaks which are perpetually covered with fnow, though within the tropics, that are visible 40 leagnes out at fea. At the fouthern end of the island is a village called Kaoo . A-poona, on the foutheastern fide; Aheedoo, on the northeastern part of the ifland; Amakooa is on the northern end; Tirooa on the north-western fide, where is the bay of Toyahyah; and on the western fide, N. W. of Kaoo, is the bay of Kara-kakooa. It has the fame productions as the Society and Friendly Islands, and

about 1 50,000 inhabitants, who are naturally mild, friendly and hofpitable to ftrangers. The fea abounds with a great variety of excellent fifh. The celebrated navigator Capt. James Cook loft his life here, by an unfortunate and momentary jealouty of the natives.

OwL's Head, a head land on the W. fide of Penobicot Bay, in the diffrict of Maine. It h s a good harbour on the larboard hand as you go to the eaftward. The harbour makes with a deep cove; has 4 fathoms water, and a muddy bortom. It is open to the E. to N, and E. N. E. winds; but in all other winds you are fafe. The tide of flood fets to the eaftward, and the tide of ebb S. W. through the Mufcle Ridges.

Ox, a river of Louisiana. See Red. River.

OXBOW, Great, a bend of the river Connecticut, about the middle of the townfhip of Newbury, in Vermont; which ice. It contains 450 acres of the fineft meadow land in New England. OXFORD, a townfhip in Worcefter co. Mafiachufetts. It contains 1000 inhabitants; is 11 miles fouthward of Worcefter, and 54 S. W. of Bofton.

OXFORD, a village in Briftol co. Maffachufetts; fee New-Bedford.

OXFORD, a parish in the northern part of Derby in Connecticut, containing 140 families; 17 miles N. W. of New-Haven.

OXFORD, a post-town of New-York, in Tioga co. 45 miles N. E. of Union, and 20 S. W. of Butternuts. This township, lies between Jericho and Union, and is bounded northerly on Norwich, and westerly by the tract called the Chenengo Triangle. It was incorporated in 1793. Here is an incorporated academy.

OXFORD, a township of New-Jersey, fituated in Suffex co. on the east bank of Delaware river, 15 or 20 miles N. E. of Easton in Pennsylvania. It contains 1905 inhabit, including 65 flaves.

OXFORD, a township of Penniylvania, fituated in Philadelphia co. There is one of the same name in Chefter co.

OXFORD, a port of entry, on the eastern there of Chelapeak Bay, in Talbot co. Its exports in 1794 amounted to 6,956 dollars. It is 13 miles S. by W. of Easton, and about 48. S. E. of Baltimore.

OXFORD, a fintall post-town of N. Cc 2 Carolina,

Carolina, 36 miles from Hillfborough, and about 416 from Philadelphia.

Vork, fituated in Queen's co. Long-Ifland, extending from the Sound S. to the Atlantic Ocean, and includes Lloyd's Neck, or Queen's Village, and Hog-Ifland. It contains 4,097 inhabit. of whom 61 tare electors, and 381 flaves.

OXSTER Bay, a harbour for finall veffels in the S. W. limits of the town of Barnftable, in Barnftable co. Maffachufetts; which fee. It affords excellent eyfters: hence its name.

OYSTER Beds, in Delaware Bay, lie opposite Nantuxet Bay.

OYSTER Point, on the coaft of S. Carolina, where the water does not ebb till an hour and a half after it begins to ebb at the bar of Afhley river, near Charleftown. It is beft to go in an hour and an half before high water.

OYSTER Pond, a part of the waters of the Atlantic Ocean, which fet up weftward into Long-Ifland, in the flate of New-York, between the north-cafternmoft point of the ifland called Oyfter Pond Point, and Gardner's Ifland. Off the point are two finall ifles, one of which is called Plumb-Ifland.

OVETER River, a W. branch of Pifcatiquariver in New-Hampthire; which fee. Durham flands on its S. fide, near its junction with the main ftream at Helton's Point.

O-YONG-WONGEYE, on Lake Ontario, at Johnson's Landing-Place, about 4 miles caffward of Fort Niagara.

OZAMA, one of the largest rivers of the island of St. Domingo, in the Weft-Indies, and on which the city of St. Domingo is fituated. It is navigable 9 or 10 leagues from S. to N. One may judge of the enormous volume of water which the confluent fiream of Habella and Ozama fends to the fea, by the red colour it gives it in the time of the floods, and which is perceivable as far as the eye can diffinguift. There is a rock at the mouth, which prevents the entrance of veffels drawing more than r8 or 20 feet of water. The river for a league is 24 feet deep; and its banks are 20 feet perpendicular, but N. of the city this height is reduced to 4 feet. This real narural bafon has a bottom of mud or foft fand, with a number of careening places. It feldom overflows its banks, except in very extraordinary

Cherry Parts

inundations. The road before the mouth of the Ozama is very indifferent, and lies exposed from W. S. W. to E. It is impossible to anchor in it in the time of the fonth winds, and the north winds drive the veffels from their moorings out into the fea, which here runs extremely high. See Domingo City. The mouth of the river is in lat. 18. s8. N. & Ion. from Paris 72. 34. W.

P

PABLO, St. a lake in the jurifdiction of Otabalo, in the province of Quito, 3 leagues in length, and about half a league in breadth. The lake is every where furrounded with a fpecies of rufhes called Totoral, among which are vaft numbers of wild geefe and galarettes. Its waters empty into the Rio Blanco.

PABLO, St. a village on the above lake, inhabited principally by Indians. PABLO, St. a town on the S. coaft of the Ifthmus of Darien, in the province of Veragua, S. America.

PABO, the Micmac name of a river, on the northern fide of Chaleur Bay, about fix leagues from Grand Riviere, W. N. W. of Cape Defpair.

PACAJES, a province of S. America, which is rich in filver mines, though they are not much worked. Here are also mines of tale, called Jaspes Blancos de Verenguela, on account of their transparent whiteness. In this province are an abundance of emeralds.

PACAMORES, a district of Peru, in S. America. The air is temperate, and the earth abounds in gold. An Indian nation of this name inhabits the banks. of Amazon river.

PACATITA, a volcano in Guatimala, in New-Spain. In 1773, the lava which iffued from it deftroyed the city of St. Jago, which was fituated in the valley of Panchoi.

PACHACAMA, or Pachamac, a famous, fruitful, and pleafant valley in Peru, 4 leagues from Lima, formerly beautified with a magnificent temple built by the Incas, and dedicated to the Creator of the Univerie. The Peruvians had in it feveral idols; but they had fo great a reverence for God, whom they called PACHACAMAC, that they offered him what they efteemed moft precious, and durft not look upon him; fo that their their kings ple with th and came o turn about. fructure, f its former Such imme up in it, th to the valu although 4 as much as Spanifh fol came. Th the natives, covery of th

PACHEA iflands calle all low and from Panan ifland there PACHEG

Wales, in PACHEQ on the S. V on the coaft and one of the femicine Point Mala water, frui ford excelle

PACHUC for the filve is faid tha 1000 of the the city of PACIFIC

French chan a prodigio from Afia. breadth, an PACKER Hampfhire, on the head It is 86 mi was incorpo 727 inhabit PACMOT

the ifland c clin Bay on Creck on th PACOLE rolina, whi Mountains, 30 miles a fouth of the courfe is ab the celebrat above its cc

PADOUG

before the ery indiffe-W. S. W. chor in it in ds, and the from their which here e Domingo ver is in lat. 72. 38. W.

jurifdiction nce of Quito, bout half a ce is every ies of rufhes ch are vaft galarettes. io Blanco. 1 the above by Indians. e S. coaft of he province

of a river, aleur Bay, Grand Ri-Despair. 5. America, nes, though Here are fpes Blancos nt of their his province

of Peru, in nperate, and An Indian s the banks

Guatimala, e lava which city of St. the valley

mac, a faht valley in a, formerly ent temple cated to the e Peruvians they had to whom they they offered ft precious, m; fo that their

their kings and priefts entered this temple with their backs towards his altar, and came out again without daring to turn about. The ruins of this fuperb structure, fays Jovet, do yet demonstrate its former magnificence and greatnefs. Such immenfe treafores had been laid up in it, that Ferdinand Pizarro found to the value of 900,000 ducats in it; although 400 Indians had taken away as much as they could carry ; and the Spanish foldiers pillaged it before he The cruel Spaniards tortured

PAC

covery of the hidden treafure. PACHEA, the most northerly of the iflands called the Pearl or King's Iflands, all low and woody, and about 12 leagues from Panama. Within a league of this island there is anchorage in 17 fathoms.

the natives, but could not extract a dil-

came.

PACHEGOIA, a lake of New South Wales, in N. America, in lat. 55. N.

PACHEQUE, a fine, but finall ifland on the S. W. fide of the bay of Panama, on the coaft of the N. Pacific Ocean, and one of the beautiful iflands within the femicircular bay from Panama to Point Mala. Thefe iflands yield wood, water, fruit, fowls, hogs, &c. and afford excellent harbour for fhipping.

PACHUCO, a town of Mexico famous for the filver mines in its vicinity. is faid that within 20 miles there are 1000 of them. It lies 60 miles from the city of Mexico.

PACIFIC OCEAN, ealled in the French charts Mar del Zur, or South Sea, a prodigious ocean dividing America from Afia. It is about 10,000 miles in breadth, and 11,000 in length.

PACKERSFIELD, a township of New-Hampfhire, Chefnire co. E. of Keene, on the head branches of Afhuelot river. It is \$6 miles wefterly of Portfmouth, was incorporated in 1774, and contains 721 inhabitants.

PACMOTE, a bay on the east fide of the island of Martinico, between Vauclin Bay on the north, and Fere Ance or Creek on the fourth.

PACOLET, a small river of South-Carolina, which rifes in the White Oak Mountains, and unites with Broad river, 30 miles above Tyger river, and 24 fouth of the North-Carolina line. Its courfe is about fouth-east, and on it are the celebrated Pacolet Springs, 17 miles above its confluence with Broad river, PADOUCAS, a weftern branch of MifPAK

fouri river. The tribe of Indians of the name are faid by fome to be of Welch origin.

PAGET's Port, a fmall harbour within the great found of the Bahama Islands, and in the most easterly part of the found.

PAGUISA, or Paquifa, on the west fide of South-America, in lat. 21. 55. S. and to leagues north of the harbour of Cobija, in the bay of Atacama. Haguey de Paguila, or the watering place Paguila, is 1 5 leagues from Cobija. The whole coaft between is high, mountain. ous and rocky, in the direction of northnorth-eaft.

PAINTED Post, a flation, fo called in New-York State, in Tioga co. on the northern fide of Tioga river, between Bath and Newtown; 40 miles N. W by W. of Tioga Point, or Athens, fouth-east of Williamsburg on Genefice river, and 230 N. W. of Philadelphia. A post-office is kept here.

PAINTED Rock is on French Broad river, by which the line runs between Virginia and Tenneffee.

PAINTER's Harbour, on the weft coaft of Cape Breton Island, is nearly due east of East Point in the island of St. John's. N. lat. 46. 22. W. long. 61. 16.

PAITA. See Payta. PAIX, Port de. See Port de Paix. PAJARO, Pajaros, or Paxaros, iflands on the coaft of Chili, on the South Pacific Ocean. Thefe are 3 or 4 rocks, the largest of which is called Pajaro Ninno, or Paxaro Ninno, and 2 miles N. W. by N. from the fouthernmost point of the Main, or Point Tortugas, that closes the port of Coquimbo.

PAJAROS, LES, or Mands of Birds a clufter of fmall iflands on the coaft of Chili, 8 leagues N. N. W. of the Bay of Coquimbo, and 7 S. S. E. of the harbour of Guafco. The ifland of Choros is 4 miles north of these islands, towards the harbour of Guafco.

PAKANOKIT, the feat of Mafaffoit, the famous Indian Chief, was fituated on Namafket river, which empties into Narraganfet Bay.

PALATINE, (New-York). A part of this town was crected into 2 new towns by the legislature, in 1797.

PALATINE, or Palentine, a township in Montgomery co. New-York, on the north fide of Mohawk river, and weft of Caghnawaga. In 1790 it contained 3,404 inhabitants, including 192 flaves. Cc 3 In

PAL

406

PALATINE Town, in the flate of New-York, lies on the east bank of Hudfon's river, and north fide of the mouth of Livingston river, which empties into the former; 11 miles north of Rhynbeck, and 15 foutherly of Hudfon city.

PALLISER's Iflands, in the South Pacific Ocean, are between 15 and 16 degrees of S. lat. and from 146 to 147 degrees of W. long. From lat. 14. to 10. S. and long. 1:8. to 150. W. the ocean is ftrewed with low, half-overft wed iflands, which renders it neceffary for navigators to proceed with much caution.

PALMA, a town of Terra Firma, in N. America, 50 miles N W. of St. Fe de Bagota. N. lat. 4. 30. W. long. 73. 40. PALMAS, a large river on the weft coaft of the Gulf of Mexico, whole mouth is in lat. 25 N and long. 98. 36. W. Some of its branches un in a course alm ft directly east from the mount ins to the eaftward of the gulf of California.

PALMER, a rough and hilly townthip in Hampfhire co, Maffachufetts, \$\$ miles W. by S. of Bolton, it is fituated on the fouth fide of Chickopee river, and bounded eaftward by Weftern, in Worcefter co. An act paffed in last leffion, 1796, to incorporate a fociety to make a turnpike-road between thefe two towns. It was incorporated in 1752, and contains 809 inhabitants.

PALMER's River, a water of Narraganiet Bay, which empt es with another fmall river, and forms Warren river, opposite the town of Warren.

PALMERSTON'S Ifland, of which one in particular has been fo named, is in lat. 18. S. and long. 162. 57. W. and is the fecond in fituation from the S. E. of a group of 9 or 10, all known by the fame general name. It affords neither anchorage nor water; but if the weather is moderate, a thip that is paffing the S. Pacific Ocean in this track, may be fupplied with grais for cattle, cocoa-nuts, filb, and other productions of the illand. The principal illand is not above a mile in circumference; nor is it elevated more than 3 feet above the furface of the fea. PALMETTO, the most easterly point

mingo, in lat. 18. 13. N. and long. 73. 2. W. of Paris.

PALTZ, New, a township on the W. fide of Hudson's river, in Ulfter co. New-York, about 20 miles N. W. of Newburgh, and 32 north of Gofhen. It contains 2,309 inhab. including 302 flaves.

PAM

of the bay fo called, on the fouth-weft-

coaft of the ifland of St. Chriftopher's,

in the West-Indies. The shore is rocky,

and a fort protects the bay .- Alio, the

most northerly point of the island of Ja-

maica ; having Manatee Bay on the weft,

PALMISTE Point, on the north fide

of the N. W. part of the illand of St.

Domingo; 3 leagues fouth of Point Por-

tugal, the east point of the imall island

La Tortue, and s east of Port de Paix.

of entry and delivery, in the flate of

Tenneffee, conffituted a port of entry by

law of the United States, Jan. 31, 1797.

coaft of Peru, South America; 3 miles

weft of St. Lawrence ifland, or St. Lo-

renzo. They have from 13 to 14 fa-

Point, at the mouth of Nifao river, on

the fouth fide of the ifland of St. Do-

PALONQUE, the cape eaft of Nifao

PALOMINOS, fmall islands on the

PALMYRA, a town, and the only port

and Ifland Bay on the eaft.

thoms water on them.

PAMBAMACCA, a lofty mountain in the province of Quito, being one of the pikes of the eaftern Cordilleras.

PAMLICO Sound, on the east coast of N. Carolina, is a kind of lake or inland fea, from 10 to 20 miles broad, and nearly 100 miles in length. It is feparated from the Atlantic Ocean, in its whole length, by a beach of land, hardly a mile wide, generally covered with fmall trees or bufhes. Through this bank are feveral finall inlets, by which boats may pais; but Ocrecok Inlet is the only one that will admit veffels of burden into the diffricts of Edenton and Newbern. This inlet is in lat. 35. 10. N. and opens between Ocrecok Ifland and Core Bank. This found communicates with Core and Albemarle Sounds; and receives Pamlico or Tar river, the river Neus, beides other imall ftreams. See Ocrecok, Cape Hatteras, &cc.

PAMPELUNA, a town of New Granada, in S. America. In its vicinity are gold mines. N. lat. 6. 30. W. long. 71. 30. It is 150 miles from San-ta Fe, and 200 from Maricaibo.

PAMUNKY, the ancient name of York river, river, in Vi confined to by the con

South Ann branch, M York river La War. PANA, 1

7 leagues 1 as far from na, which thips boun ftop for pil age over ag in 5 fathon It is alto c PANAC

W. coaft leagues fro PANAD coaft of Ca part of the PANAM

ma Proper capacious fide of the rien, oppo fide of the ceptacle of and filver, from all p they are lo proper fea to Europe formed in eral iflands about $2\frac{1}{2}$ city. T high wat 3 o'clock confiderab on a gent dry to a found her few perfo who do n of their Negroes both expe holding work bei the fea. whofe bi Firma. who, in 1 the usual taken, fa gan, an l

town wa

buth-weft ftopher's, is rocky, Alfo, the and of Jathe weft,

north fide ad of St. Point Pornall ifland de Paix. only port e flate of if entry by 31, 1797. i on the i 3 miles or St. Loto 14 fa-

of Nifao river, on f St. Do., long. 73.

on the W. r co. New-. of New-1. It con-302 flaves. ountain in one of the IS. aft coaft of e or inland woad, and It is fepaean, in its land, hardvered with trough this , by which k Inlet is veffels of denton and 15. 10. N. Ifland and nmunicates ounds; and r, the river eams. See

New Graits vicinity 6. 30. W. 5 from Sanibo. une of York

river,

PAN river, in Virginia ; but this name is now

confined to the fouthern branch, formed by the confluence of the North and South Anna. This and the northern branch, Mattapony, unite and form York river, just below the town of De La War.

PANA, an ifland on the coaft of Peru, 7 leagues E. N. E. of Santa Clara, and as far from Guayaquil. At Point Arena, which is the wefternmoft point, all thips bound farther into Guayaquil Bay flop for pilots, as there is good anchorage over against the middle of the town, in 5 fathoms, and a fort oozy ground. It is also called *Pana*.

PANACA, a burning mountain on the W. coaft of New-Mexico, about 3 heagues from the volcano of Sanfonate. PANADOU, or Manadou, a bay on the coaft of Cape Breton Island, near the S. part of the Gulf of St. Lawrence.

PANAMA is the capital of Terra Firma Proper, S. America; fituated on a capacious bay of its name, on the fouth fide of the Ifthmus of Panama or Darien, opposite to Porto Bello, on the N. fide of the ifthmus. It is the great receptacle of the vaft quantities of gold and filver, with other rich merchandize from all parts of Peru and Chili. Here they are lodged in ftore-houfes, till the proper leafon arrives to transport them to Europe. The harbour of Panama is formed in its road by the fhelter of feveral iflands, where thips lie very fafe, at about 21 or 3 leagues diftant from the city. The tides are regular, and it is high water at the full and change at 3 o'clock. The water rifes and falls confiderably; fo that the fhore, lying on a gentle flope, is at low water left dry to a great diffance. Pearls are found here in fuch plenty, that there are few perfons of property near Panama, who do not employ all, or at leaft part of their flaves, in this fifthery. The Negroes who fifh for pearls muft be both expert fwimmers, and capable of holding their breath a long time, the work being performed at the bottom of the fea... This city is a bifhop's fee; whole bifnop is the primate of Terra Firma. It was built by the Spaniards, who, in 1521, conflituted it a city, with the usual privileges. In 1670 it was taken, facked and burnt by John Morgan, an English adventurer. The new town was built in a more convenient fituation, about a league and a half from the former. In 1737, this new town was almost entirely deftroyed by an accidental fire. It is furrounded with a ftone wall and other fortifications, and the public buildings are very hand/ome. N. lat. 8. 57. 48. W. long. 82. 5. 14. See Chagre River.

PANAMA, a province of Terra Firma, of which the city above mentioned is the capital. This provine is called by moft writters *Terra Firma Proper*. It contains 3 cities, 12 villages, and a great number of *rancheries* or affemblages of Indian huts; thefe are fituated in fimall plains along the fhore, the reft of the country being covered with enormous and craggy barren and uninhabited mountains. It has feveral gold mines; but the pearl fiftery affords a more certain profit, and at the fame time is acquired with much greater eafe.

PANAMARIBO, on the coaft of Su-, rinam, in Guiana, in S. America, is E. S. E. of Demarara, in lat. about 6. N. and long. 56. 26. W.

PANAMBUCO, a harbour or bay on the coaft of Brazil. See Pernambuco.

PANECILLO, an eminence near Quito, which fupplies that city with excellent, water.

PANIS. There are two Indian nations to named. The white Panis inhabit S. E. of the Miffouri, and can furnish 1500 warriors; and the Speckled Panis S. of the Miffouri, 1200 warriors.

PANSE DE LA, a branch of Wabafh river in the N. W. Territory. PANTON, a township in Addison co.

PANTON, a township in Addison co. Vermont, fituated on the E. fide of Lake Champlain, between Addison and Ferrisburg, and about \$7 miles N. of Bennington. It contains 200 inhabitants.

PANUCO, or Guaffica, a province of N. America, in New-Spain, bounded E. by the Gulf of Mexico, and W. by the provinces of Mechoacan and New-Bifcay. The tropic of Cancer divides this province. It is about 55 leagues each way. The part neareft to Mexico is much the beft and richeft, abounding with provifions, and having fome veins of gold, and mines of falt. Other parts are wretchedly poor and barren.

PANUCO, the capital of the above mentioned province; it is the fea of a biflop, and ftands upon a river of its own name, 17 leagues from its mouth, on the W. fhore of the Gulf of Mexico, C c 4 and

PAR

nd 60 N. W. of the city of Mexico. I two high points fecure it from the north The river is navigable for large fhips a great way above the city : but the haryour has to large a bar before it, that no thius of burden can enter it. N. lat. 23. 50. W. long 99. 50.

PAPAGAYO, a gulf on the N. Pacific Ocean, and on the W. fide of the Ifthmus of Nicaragua, a small diftance from the western parts of the lake of Nicaragua, and in lat. about 11. 14. N.

PAPALOAPAIN, the largest river of Guaxaca, in New-Spain, called alfo Alvarada. It rifes in the mountains Zoncoliucan, and, being enlarged by the accellion of leffer rivers, falls into the North Pacific Ocean.

PAPINACHOIS, a bay on the north fhore of the river St. Lawrence, in N. America, 5 leagues fouth-weft of St. Margaret's river. An Indian nation of the fame name inhabit the country fouth of Piretibbe Lake in Lower Canada.

PAPPA FORD, on Pelefon or Clinch river, lies 12 miles from Emery's river, and 10 from Campbell's Station, near Holfton.

PAPUDA, on the coaft of Chili, and on the S. Pacific Ocean, 5 leagues north of the floals of Quintero, and 4 from Port Liga. The water is very deep in Papuda, but the anchorage is good, and the entrance fafe.

PARA, the most northern of s colonies or governments, Para, Maragnon, Matto Groffo, Goyas, and St. Paul, in S. America, at which places the Indians have been united in 117 villages, over which a white man prefides with defpotic fiway. The government of Para comprehends that portion of Guiana which belongs to the Portuguese, the most barren and unwholefome country in all thefe regions.

PARA Ifland, is one of the range of iflands to the fouth-eaft of Sypomba, to the eastward of the great river Amaron, which is the north-west limit of the Brazil coaft in S. America. Thefe iflands form the great river or bay of Para. About 9 leagues eaft by fouth of this island is Cape Cuma, the western' boundary of the great gulf of Maranhao. On the island is a fort belonging to the Portuguese. There is also a small river of the fame name, at the mouth of which is good riding for large fhips, becaufe the ifland breaks off the fea, and

PAR

and east winds.

PARA River or Bay, near the N. W. part of the coaft of Brazil, in S. America, has a town of its name at the mouth of it, with a large fort and a platform of cannon at the water's edge, commanding the road. Above this is the caffle featon a high rock, furrounded by a firong ftone wall that is also mounted with cannon. The road, within the mouth of the river, is good, having clean ground. and fecured by high land on both fides. The mouth of the river is about 6 miles broad at the town; and thips may ride in 15 fathoms, within a cable's length of the fhore, and in 10 fathoms clofe under the fort. This harbour is much frequented for all kinds of provisions which abound here. Tobacco is carried from this, to Pernambuco, to be fhipped for Europe. The river is about 200 miles long.

PARACA, a bay on the coaft of Peru. 40 leagues S. E. by S. of the port of Callao. Ships receive fhelter here. when driven out of the harbour of Cangallan or Sangallan, which is 3 leagues S. E. of Carette Island, and N. N. W. of the ifland of Lobos.

PARADISE, a township of Pennfylvania, in York co.

PARADIS. See Plate Forme.

PARAGUAY, a country of S. America, claimed by Spain, about 1,500 miles in length, and 1,000 in breadth. It lies between 12, and 37. S. lat. and between so, and 7 s. W. long, bounded north by Amazonia, fouth by Patagonia, eaft by Brazil, and weft by Peru and Chili. Itis divided into the following provinces, viz. Paraguay, Parana, Guira, Uragua, Tucuman and Rio de la Plata. Befides a vaft number of fmall rivers which water this country, there is the grand river La Plata, which deferves a particular defcription. A Modenete Jefuit, by the name of P. Cattanco, who failed up this river, fpeaks in the following language concerning it : "While I refided in Europe, and read in books of history and geography that the river La Plata was 1 50 miles in breadth, I confidered it as an exaggeration, because in this hemifphere we have no example of fuch vaft rivers. When I approached its mouth, I had the most vehement defire to afcertain the breadth with my own eyes, and I have found the matter to be exactly as

te was repl ticularly t we took of do, a fort from the r its breadt we failed a covered th of the riv middle of cover land but the fk in fome g have take ter of the the Po, h a river." country, tremely h fuence of parts mu But the h by the ge gin about ing, and c day. Son mountain find exten the foil is tobacco. Paraguay fruits. 7 paftures, of cattle. only part left to t beafts of annually many as travel ov tance of I vince of 7 nually, 1 5000 ho upon its is the car ation on and pleaf is regula bitants i the town a garrifo town ftar accels to difficult. can be ol 100,000 Spaniard mixed b

he north

N.W. Amee mouth tform of manding file feata firong ith cannouth of ground, th fides. t 6 miles may ride ength of fe under uch frens which ied from pped for oo miles of Peru, port of

of Canleagues N. W. Pennfyl-

merica, miles in It lies between north by eaft by hili. It ovinces Uragua, Befides hich waand river cular deby the d up this anguage d in Euory and lata was red it as is hemiuch vaft mouth, to afceryes, and xactly as iŧ

ticularly from one circumftance : when we took our departure from Monte Viedo, a fort fituated more than 100 miles from the mouth of the river, and where its breadth is confiderably diminished, we failed a complete day before we difcovered the land on the oppofite bank of the river; and when we were in the middle of the channel we could not difcover land on either fide, and faw nothing but the fky and water, as if we had been in fome great ocean. Indeed we fhould have taken it to be fea, if the fresh water of the river, which was turbid like the Po, had not fatisfied us that it was a river." From the fituation of this country, fome parts of it must be extremely hot, from the almost vertical influence of the rays of the fun; while other parts must be pleafant and delightful. But the heat is in fome measure abated by the gentle breezes which generally begin about 9 or 10 o'clock in the morning, and continue the greatest part of the day. Some parts of the country are very mountainous; but in many others, you and extensive and beautiful plains, where the foil is very rich, producing cotton, tobacco, and the valuable herb called Paraguay, together with a variety of fruits. There are also prodigiously rich pastures, in which are bred fuch herds of cattle, that it is faid, the hides are the only part exported, while the flefh is, left to be devoured by the ravenous beafts of the wilderneis. Paraguay fends annually into the kingdom of Peru as many as 1500 or 2000 mules. They travel over dreary deferts for the diftance of 800 or 900 leagues. The province of Tucuman furnishes to Potoh, annually, 16 or 18,000 oxen, and 4000 or

PAR

sooo hories, brought forth and reared upon its own territory. Buenos Ayres is the capital of this country. Its fituation on the river La Plata is healthy and pleafant, and the air temperate. It is regularly built: the number of inhabitants is about 30,000. One fide of the town is defended by a fortrefs, with a garrifon of 600 or 700 men. The town ftands 1 80 miles from the fea. The accels to the town up the river, is very difficult. From the best information that can be obtained, there are not more than 100,000 fouls in this country, including Spaniards, Indians, Neguces, and the mixed blood, or Creoks. The Spa-

it was represented. This I deduce par- | niards exhibit much the fame character here, as in the other kingdoms already defcribed. The Spaniards first difcovered this country in the year 1515, and founded the town of Buenos Avres in 1535. Most of the country is still inhabited by the native Americans. The lefuits have been indefatigable in their endeavours to convert the Indians to the belief of their religion, and to introduce among them the arts of civilized life. and have met with furprifing fuccefs. It is faid that above 340,000 families, feveral years ago, were fubject to the]efuits, living in obedience, and an awe bordering on adoration, yet procured without any violence or conftraint. In 1767, the Jefuits were fent out of America, by royal authority, and their fubjects were put upon the fame footing with the reft of the country.

> PARAGUAY, a large river of S. America, which falls into the river La Plata that forms the fouthern boundary of Brazil. At the diffance of 100 leagues from the fea, where this and Parana river fall into the channel, it is it leaft 10 leagues over.

PARAIBA, or Parayba, the most northern province of Brazil, in S. America, lying between Rio Grande to the north, and the river Tamarack to the fouth; the South Atlantic Ocean to the east, and Figuares to the west. It belongs to the Portuguele, and abounds in fugar-canes, Brazil-wood, cattle, tobacco, cotton, &c. This diffrict was given by John III. of Portugal, to the historian De Barros, but he neglected the peopling of it. Some vagabonds who went over in 1560, and in 1391, were fubdued by the French, who were foon obliged to evacaute it. Philip III. caufed a city to be built upon this royal domain, which is at preient known by the name of Notre Dame de Neves.

PARAIBA, the metropolis of the above province, or captainfhip, fituated on the fouth bank of a river of its name, three leagues from the fea; according to others, to leagues; the river being navigable for fhips loaded with 600 or 700 hhds. of fugar, a confiderable diffance above the city. The Dutch captured it in 1635; but the Portuguefe retook it foon after. It has many flately houfes decorated with marble pillars, together with large warehoufes and magazines belonging to the merchants. The

mouth

mouth of the river is well fortified. S. lat. 6. 50. W. long. 49. 53.

PARAMABIRO, corruptly called Paramaribo, the chief town of Surinam, containing about 400 houfes, on the bank of Surinam river, in a pleafant but mhealthy fituation. The houfes are of wood, tolerably convenient, erected on foundations of European bricks. Its port is 5 leagues from the fea, and has every convenience. It is the rendezyous of all the fhips from the mother country which come hither to receive the produce of the colomy.

PARANA, a province in the E. division of Paraguay, South-America. Its chier town is St. Ann.

PAREN, a lake of Chili, S. America. PARATEE, a bay on the fouth-weft 6de of the ifland of Jamaica. It is foutheaft of Banifter Bay, its fouth-eaft point is alfo called *Paratee*.

PARAYBA, a river on the coaft of Brazil, 10 leagues N. of Port Francezes. The city lies 8 leagues from its mouth. S. lat. 6, 50. W. long. 49. 53. See Paraiba.

PARDUBA, a bay on the coast of Brazil, 10 leagues W. N. W. of Brandihi Bay.

PARHAM Torum and Harbour, on the north fide of the ifland of Antigua, in the Weft-Indies. The harbour is defended by Byram Fort, at Barnacle Point, on the weft fide, and farther up by another fort on the E, fide. The town is regularly built, and lies at the head of the harbour, and in St. Peter's parifh.

PARIA, or New Andalufia, a country of S. America, and in Terra Firma, bounded on the north by the north fea, and fouth by Guiana. The fea-coaft is moftly inhabited, on which there are feveral towns.

PARIA, a jurifiliction in the abp. of La Plata, in S. America, beginning 70 leagnes N. W: of that city, and extending about 40 leagues. It has fome filver mines; and the cheefe made here is much efteemed, and fent all over Peru.

PARIA, Gulf of, a ftrait lying between the N. W. part of New-Andalufia, and the fouthern fhore of the island of Trinidad. N. lat. 9. 12. W. long. 62. 5.

PARILLO, a town of Peru, generally called Santa; which fee.

PARINA, a point N. W. of the harbour of Payta, on the coaft of Peru. The country within the point is high

and mountainous. Between Payta and it, is a large bay, having fhoals. The land is low, and fome white hills all the way.

PARINA COCAS, a jurifdiction in the diocefe of Guamanga, in the andience of Lima, beginning about 20 leagues fouth of the city of Guamanga, and extending above 25 leagues. It has excellent pattures, grain, and finits. The mines of filver and gold are more productive than formerly; and thele form the chief branch of its commerce.

PARIS, a thriving township of excellent land in New-York State, Herkemer county. It is fouth-weft of Whiteftown 6 miles, from which it was taken, and incorporated in 1792. In 1795, 4 townfhips were taken from it, viz. Hamilton, Sherburne, Brookfield, and Sangerffield. It contained, by the State cenfus of 1796, 3,459 inhabitants, of whom 564 were electors. Iron ore is found in the vicinity of Paris. Hamilton academy is fituated in this town, in Clinton parifh, where also a Congregational church has lately been erected, and marks of rapid progrefs in improvements and wealth are visible.

PARIS, an ifland on the coaft of S, Carolina; which fee.

PARKER's Ifland, in Lincoln co. Diftrict of Maine, is formed by the waters of Kennebeck river on the weft, by the fea on the fouth, by Jeremyfquam Bay on the eaft, and by a finall ftrait, which divides it from Arrowfick Ifland, on the north. It derives its name from John Parker, who purchafed it of the natives in 1650; and a part of it ftill remains to his pofterity. It is in the township of Georgetown; which fee.

PARKER'S *River* takes its rife in Rowley, in Effex co. Maffachufetts, and, after a courfe of a few miles, paffes into the found which feparates Plumb-Ifland from the main land. It is navigable about two miles from its mouth, where a bridge croffes it \$70 feet long and 26 feet wide, confifting of folid piers and \$ wooden arches. It is on the poft-road from Bofton eaftward, and was built in 175\$. It is fupported by a toll.

PARRAMORE, one of the finall islands in the Atlantic Ocean, which line the east coast of Northampton co. Virginia. PARR-TOWN, a new and thriving town in Nova-Scotia.

PARR'S

PARR's of Half M fide of the in the Wei rocky.

PARSOI Diffrict of on the N Great and is 118 mil incorporat inhabitant

PARTI high hill weft part in the fais Catoche t PARTF Maffachu W. N. W weftward rated in

bitants. PASCA Weftern by E. c and empt by fevera cupy a f one conti very fho branch h cft, Afts 3 to 6 f

tance, ar ble more this rive that pai Gulf of

advance PASC the E. fi can furi

about IC PASC only lar

in Newin the Wakefi to the fi It divid co. in t ed Salm the low affumes which

cho riv when b to Hil Payta and als. The ills all the

tion in the andience o leagues a, and ex-It has exaits. The more prothefe form FCe. o of excel-Herkemer Vhiteftown aken, and 5, 4 town-Hamilton, Sangerftate cenfus of whom s found in ton acadein Clinton gregational ected, and improve-

oaft of S.

In co, Difthe waters eft, by the fquam Bay rait, which and, on the from John the natives ill remains ie townfhip

its rife in ufetts, and, iles, paffes es Plumb-It is naviits mouth, o feet long g of folid It is on eaftward, s fupported

mall iflands ich line the . Virginia. id thriving

PARR'S

PARR's Point, is the fouth-east point of Half Moon bay, on the north-east fide of the isl and of St. Christopher's, in the West-Indies. The coast here is nocky.

PAS

PARSONSFIELD, a township of the District of Maine, in York co. stuated on the New-Hampshire line, between Great and Little Offipee rivers; and is 118 miles north of Boston. It was incorporated in 1785, and contains 655 inhabitants.

PARTIDO, a finall ifland, under the high hill of St. Martin, in the fouthweft part of Campeachy Gulf. It lies in the fairway across the bay from Cape Catoche to Vera Cruz.

PARTRIDGEFIELD, a township of Massachuletts, in Berkshire co. 26 miles W. N. W. of Northampton, and 128 westward of Boston. It was incorporated in 1775, and contains 1041 inhabitants.

PASCAGOULA, a river of the Georgia Western territory, which purfues a S. by E. courfe through West-Florida, and empties into the Gulf of Mexico, by feveral mouths, which together occupy a space of 3 or 4 miles; which is one continued bed of oyfter-fhells, with The wefternmost very fhoal water. branch has 4 feet water, and is the deepeft. After croffing the bar, there is from 3 to 6 fathoms water for a great diftance, and the river is faid to be navigable more than 150 miles. The foil on this river, like that on all the others that pafs through Georgia into the Gulf of Mexico, grows better as you advance to its fource.

PASCAGOULA, an Indian village on the E. fide of the river Miffifippi, which can furnish about 20 warriors. It is about 10 miles above the Tonica village.

PASCATAQUA, or Pifcataqua, is the only large river, whole whole course is in New Hampshire. Its head is a pond in the N. E. corner of the town of Wakefield, and its general course thence to the sea is S. S. E. about 40 miles. It divides New Hampshire from York co. in the Diffrict of Maine, and is called Salmon-Fall river, from its head, to the lower falls at Berwick, where it affimes the name of Newichawannock, which it bears till it meets with Cochecho river, which comes from Dover, when both run together in one channel to Hilton's Point, where the western

branch meets it : from this junction to the fea, the river is fo rapid that it never freezes; the diffance is 7 miles, and the course generally from S, to S, E. The western branch is formed by Swamfcot river, which comes from Exeter,

The western branch is formed by Swamfcot river, which comes from Exeter, Winnicot river, which comes throug Greenland, and Lamprey river, which divides. Newmarket from Durham ; thefe empty into a bay, 4 miles wide, called the Great Bay. The water, in its further progrefs, is contracted into a leffer bay, and then it receives Oyfter river, which runs through Durham, and Back river, which comes from Dover, and at length meets with the main ftream at Hilton's Point. The tide rifes into all thefe bays, and branches as far as the lower falls in each river, and forms a most rapid current, especially at the feafon of the freshets, when the ebb continues about two hours longer than the flood; and were it not for the numerous eddies, formed by the indentings of the fhore, the ferries would then be impaffable. At the lower falls in the feveral branches of the river, are landing places, whence lumber and other country produce is transported, and veffels or boats from below discharge their lading; so that in each river there is a convenient trading place, not more than 12 or 15 miles diftant from Portimouth, with which there is conftant communication by every tide. Thus the river, from its form, and the fituation of its branches, is extremely favourable to the purposes of navigation and commere. A lighthouse, with a fingle light, stands at the entrance of Piscataqua harbour, in lat.

43. 4. N. and long. 70. 41. PASPAYA, a jurifdiction in the archbifhoprick of La Plata, about 40 leagues to the S. of the city of that name. It is mountainous, but abounds in grain, pulle, and fruits.

PASQUOTANK, a county of North-Carolina, in Edenton diffrict, N. of Albemarle Sound. It contains 5,497 inhabitants, including 1623 flaves.

PASQUOTANK, a finall river of N. Carolina, which rifes in the Great Difmal Swamp, and, paffing by Hertford,. falls into Albemarle Sound.

PASSAGE Fort, a finall town of the Ifland of Jamaica, fituated in the road between Port-Royal and Spanifh-Town, 7 miles S. E. of the latter, and at the mouth

PAS

. PASSAGE Island lies across the mouth of the river Coheca, near the N. W. part of the island of Porto Rico. The harbour for thips is at the E. end of the island.

PASSAGE Iflands, Great and Little, two of the Virgin Iflands, in the Weft-Indies, near the E. end of the ifland of Porto Rico. N. lat. 18. 20. W. long.

PASSAGE Point, in the Straits of Marellan, lies at the W. end of Royal Reach, and 5 leagues W. N. W. of Fortefcue's Bay. S. lat. 53. 45. W. long. 73. 40.

PASSAIK, or Pafaick, is a very crooked river. It rifes in a large fwamp in Morris co. New. Jerfey, and its courfe is from W. N. W. to E. S. E. until it mingles with the Hackinfak at the head of Newark Bay. It is navigable about to miles, and is 230 yards wide at the ferry. The cataract, or Great Falls, in this river, is one of the greatest natural curiofities in the State. The river is about 40 yards wide, and moves in a flow, gentle current, until coming with-in a thort distance of a deep cleft in a rock, which croffes the channel, it defcends and falls above 70 feet perpendicular, in one entire fheet, prefenting a most beautiful and tremendous fcene. The new manufacturing town of Patterfon is crected on the Great Falls of this river; and its banks are adorned with many elegant country feats. It abounds with fifh of various kinds. There is a bridge 500 feet long, over this river, on the post-road from Philadelphia to New-York.

PASSAMAQUODDY, a bay and river, near which is the division line between the British province of New-Brunswick, and the United States of America. The island of Campo Bello, in the N. Atlantic Ocean, is at the middle or W. palfage of the bay, in lat. 44. 50. N. and long. 66. 46. W. The distance from Crois life, Machias, to Weft Paffiamaquody Head is 9 leagues N. E. by E; and from the Head over the bar to Alkn's Isle N. N. W. 2 leagues. When you come from the S. W. and are bound into Weft Paffamaquoddy, you must give the Scal Rocks a birth of three quarters of a mile before you haul in from the harbour, as there is a whirlpool to the eaftward of them. The bay is about a league from this point. It is high water here at full and change of the moon, about the fame time as at Bofton. There are 3 rivers which fall into this bay; the largeft is called by the modern Indians, the Scoodick; but by De Mons and Champlaine, Etchemins. Its main fource is near Penobfcot river, and the carrying-place between the two rivers is but 3 miles. See New Branfwick. The mouth of Pafiamaquoddy river has 25 fathoms water.

PASSAMQUODDY Poll-Office, on the above deferibed bay, is kept at a little village at the mouth of Cobfeook river, 17 miles this fide Brewer's, the eafternmoft polt-office in the United States, 20 N. E. of Machias, 378 N. E. of Bofton, and 728 in a like direction from Philadelphia.

PASSAMAQUODDIES, a tribe of Indians who inhabit near the waters of Paffamaquoddy Bay.

PASSAO, a cape on the coaft of Peru, on the South Pacific Ocean, under the equator. Long. 78. 50. W.

PASSO MAGNO, a river of Florida, in lat. 36. N.

PASSUMPSICE, a fmall river of Vermont, runs a fouthern courfe and emptics into Connecticut river, below the Fifteen Mile Falls, in the town of Barnet.

PASSYUNE, a township in Philadelphia co. Pennsylvania.

PASTO, or St. Juan de Paflo, a town of Popayan in S. America. N. lat. 1. 50. W. long. 76. 55.

PATAGOA, a river on the coaft of Brazil, which enters the ocean S. W. of Rio Janeiro.

PATAGONIA, -a country of S. America, little known, extending from 35 to near 54 S, lat, being 1100 miles long. and upwards of 300 broad, lying S. of Chili and Paraguay, The E. couft is generally low, but has few good harbours; that of St. Julian is one of the beft. It is fo called from Patagons, a principal tribe of its inhabitants. There is no timber in the fouth parts, though the north parts contain an immense quantity, and numerous flocks of cattle. PATAPSCO, a navigable river of Maryland, which empties from the N. W. into Chefapeak Bay ; its month being formed

formed Point on 39. 8. 30 fylvania, courfe ti about 8 there tu widens in its mout wide juf the bafo commerc firft difc from the fembling ble for v Fell's Po a little vents the PATA jurifdicti fifting of the road miles no quarters near the fome hug ing the r Indian p with the a moft and on peet of t PATA of Trux ated am variety . the chief PATE Mexico, mine in long. 99 PATI Bay, R of War mile. 1 broad. PATO and nobl es, the n originate Mountai courle, the State Its cour thence I Conecoc nia; the receives Sec.

Sec.

ou haul in s a whirlm. The his point. Id change ime as at which fall called by lick ; but e, Etche-Penobfcot between See New Pafiamawater. e, on the at a little ook river, e easternstates, 20 f Bofton. m Phila-

be of Inwaters of of Peru.

under the lorida, in

r of Verand empelow the n of Bar-

Philadel-

, a town . lat. s. coaft of

1 S. W. S. Ame.

om 35 ta les long. ing S. of . coaft is od hare of the agons, a . There though immenfe of cattle. rof Ma-N. W. th being

formed

39. 8. 30. N. It rifes in York co. Penn-fylvania, and purfues a S. and S. E. courfe till it reaches Elkridge Landing, about 8 miles S. W. of Baltimore; it there turns eaftwardly over falls, and widens into a broad bay-like ftream to its mouth. It is about 30 or 40 yards wide just before it communicates with the bason on which stands the large commercial town of Baltimore. The first discoverer called it Bolus river, from the red earth found near it, refembling bole-ammoniac. It is navigable for veffels drawing 18 feet water to Fell's Point at Baltimore; but the falls a little above Elkridge Landing, prevents the navigation farther.

PAT.

PATAVIRCA, a town of Peru, in the jurifdiction of Santa, or Guarmey, confifting of about 60 houses. It lies on the road leading from Paita to Lima, 67 miles north of that city. About three quarters of a league from this town, and near the fea-coaft, are ftill remaining fome huge walls of unburnt bricks, being the ruins of a palace of one of the Indian princes. Its fituation corresponds with the tradition; having on one fide, a most fertile and delightful country, and on the other, the refreshing profpect of the fea. 的推动。

PATAZ, a jurifdiction in the diocefe of Truxillo, in S. America. It is fituated among the mountains, and has a variety of products; of which gold is the chief.

PATEHUCA, or Patioca, a town of Mexico, in N. America, having a filver mine in its vicinity. N. lat. 21. W. long. 99. 58.

PATIENCE, an island in Narraganset Bay, Rhode-Ifland, and lies fouth-east of Warwick Neck, three-fourths of a mile. It is about 2 miles long, and r broad.

PATOWMACK, or Potomack, a large and noble river which rifes by 2 branches, the northern and the fouthern, which originate in and near the Alleghany Mountains, and forms, through its whole courfe, part of the boundary between the States of Virginia and Maryland. Its courfe is N. E. to Fort Cumberland, thence turning to the E. it receives Conecocheague Creek from Pennfylvania; then purfuing a fouth-east course, it receives the Shenandoah from the S.W.

Sec.

formed by North Point, and Bodkin after this it runs a S. E. and S. course Point on the fouth, which laft is in lat. till it reaches Maryland Point; then its course it receives several confiderable fireams, which are defcribed under the respective heads. The distance from the Capes of Virginia to the termination of the tide water in this river, is above 300 miles ; and navigable for thips of the greatest burden, nearly that distance. From thence this river, obstructed by 4 confiderable fails, extends through a vaft tract of inhabited country towards its fource. Early in the year 1785, the legislatures of Virginia and Maryland paffed acts to encourage opening the navigation of this river. It was effimated that the expense of the works would amount to £ 50,000 fterling, and 10 years were allowed for their completion. Great part is already finished ; and the whole it is expected will be completed within two years from March, 1796, according to the report of the engineers to the Patowmack Company. This noble river paffes by many flouristing towns; the chief of which are, Shepherditown, Georgeftown, Wafhington City, Alexandria, New-Marl-borough, and Charleftown, or Port Tobacco. It is 71 miles wide at its mouth ; 41 at Nomony Bay; 3 at Aquia; 11 at Hallooing Point; and 11 at Alexandria. Its foundings are 7 fathoms at the mouth; 5 at St. George's Island; 44 at Lower Matchodic; 3 at Swan's Point, and thence up to Alexandria. The tides in the river are not very ftrong, excepting after great rains, when the ebb is pretty ftrong ; then there is little or no flood, and there is never more than 4 or 5 hour's flood, except with long and ftrong fouth winds. In order to form just conceptions of this inland navigation, it would be requisite to notice the long rivers which empty into the Patowmack, and furvey the geographical polition of the western waters. The distance of the waters of the Ohio to Patowmack, will be from fifteen to forty miles, according to the trouble which will be taken to approach the two navigations. The upper part of this river, until it passes the Blue Ridge, is called, in Fry and Jefferion's map, Cohongoroute.

PAT

PATRICK's, St. a fmall town, the chief of Camden co. Georgia, fituated on Great Satilla river, about 32 miles from its mouth, and the fame diffance north

month-wefferly of the town of Saint to conduct the fireams of their refpec-

PATTERSON, a town in Bergen co. New-Jerfey, called fo in honour of the governor of the State of that name, and now one of the judges of the supreme federal court. It was eftablished in confequence of an act of the legislature of New-Jerfey, in 1791, incorporating a manufacturing company with peculiar privileges. Its fituation on the Great Falls of Paffaic river, is healthy and agreeable. It now contains about 50 dwelling-houfes, independent of those appropriated for the machinery; and it is certainly one of the most convenient fituations for a manufacturing town, of any on the continent. This company was incorporated to encourage all kinds of manufactures, and the fum of 500,000 dolls, was foon fubfcribed; but for want of experience, and a proper knowledge of the bulinels, much was expended to little purpole; and they were at laft reduced to the neceffity of having recourse to a lottery to affist them in carrying their plan into execution. It is faid that matters are now conducted more judiciously, and that the undertaking promifes to be uleful to the public, and beneficial to the proprietors. It is 19 miles N. E. of Morrikown, 10 N. of Newark, and 100 N E. by N. of Phila-delphia. N. lat. 40. 12. W. long. 74. 57.

PATUCKET, a fmall village about 4 miles N. E. of Providence, a buly place of confiderable trade, and where manufactures of feveral kinds are carried on with fpirit. Through this village runs Patucket, or Pawtucket river, which empties into Seekhonk river at this place. The river Patucket, called more northerly Blackftone's river, has a beautiful fall of water, directly over which a bridge has been built on the line, which divides the commonwealth of Maffachufetts from the State of Rhode-Ifland : diftant about 40 miles S. by W. of Bofton. The confluent ftream empties into Providence river about a mile below Weyboffett, or the Great Bridge. The fall, in its whole length, is upwards of fifty feet; and the water paffes through feveral chaims in a rock, which, extending diametrically across the bed of the fiream, ferves as a dam to the water. Several mille have been erected upon their falls; and the fpouts and channels which have been conftructed

to conduct the fireams of their refpective wheels, and the bridge, have taken very much from the beauty and grandeur of the fcene; which would otherwife have been indefcribably charming and romantic.

PATUXENT, or Patuxet, a navigable river of Maryland, which rifes near the fource of Patapico river, and empties into the W. fide of Chefapeak Bay, between Drum and Hog Ifland Points, 15 or ao miles N. of the mouth of the Patowmac. It admits veffels of 250 tons to Nottingham, nearly 40 miles from its mouth, and of boats to Queen Anne, 12 miles higher. Patuxent is as remarkable a river as any in the bay, having very high land on its north fide, with red banks or cliffs. When you double Drum Point, you come too in 25 and 3 fathoms water, where you will be fecure from all winds.

PAUCAR-COLLA, a jurifdiction in the bifhoprick of La Paz, in South-America, bordering on Chucuito. It is fituated in the mountains, and abounds in cattle. The air is here very cold. The filver mine here, called Laycacota, was formerly fo rich, that the metal was often cut out with a chiffel ; but the waters having overflowed the works, it is abandoned.

PAUCARTAMBO, a jurifdiction of the diocefe of Cufco, in S. America. It is very fruitful, and lies 80 leagues eaftward of the city of Cufco.

PAUKATUCK, a fmall river which empties into Stonington harbour, and forms a part of the division line between Connecticut and Rhode-Island.

PAUL'S BAY, St. on the N. W. fhore of the river St. Lawrence, in N. America, is about 6 leagues below Cape Torment, where a chain of mountains of 400 leagues in length terminate from the weftward.

PAUL'S BAY, St. on the N. W. coaft of Newfoundland Ifland. N. lat. 49. 50. W. long 57. 55.

PAUL'S ISLAND, St. an illand in the ftrait between Newfoundland and Cape Breton Iflands. It is about 15 miles north-eaft of North Cape, in Cape Breton. N. lat. 47. 13. W. long. 60. 2. PAUL, St. a town of Brazil, S. America, in the captainline of St. Vincent. It is a kind of an independent republic, composed of the banditti of feveral nations. However, they pay a tribute of gold gold to the rounded by thick foreit 45. 52.

PAUL,

New Mexi

of the two

Rio Bravo PAUL, Pearl Iflan S. Americ channel ; s place for c PAUL'S diffrict, S. inhabitant and 3,202 PAULING thip in Du on the we cut, and h the fouth. ighabitant In 1796, ants qual PAULI Jerfey. PAULS

ton co. 1

waters of

which paf

PAULL Jerfey, is river, opp the river i the ferry, than any This was war: In that the was pract PAWL Vermont, ftands on on the not co. on the let river, the conflu at Fiddle tain is in PAWT river, are PAWT thip of C Island.

> Paxat Californi lat. 30. 1 Paxt

ave takes and granild othercharming

navigable s near the i empties tak Bay, d Points, uth of the s of 250 40 miles to Queen xent is as the bay, sorth fide, When you too in 25 you will

tion in the America, s fituated in cattle. The filver was forwas often the waters ks, it is

tion of the ca. It is igues eaft-

ver which bour, and nebétween 1. . W. fhore N. Ameri-Cape Toruntains of nate from

. W. coaft at. 49. 50.

land in the and Cape 15 miles Cape Breg. 50. 2. l, S. Ame-Vincent. t republic, feveral natribute of gold PAX .

gold to the king of Portugal. It is furrounded by inacceffible mountains and thick forefts. S. lat. 23. 25. W. long. 45. 52.

PAUL, St. a town of N. America, in New Mexico, fituated at the confluence of the two main head branches of the Rio Bravo.

PAUL, St. the most foutherly of the Pearl Islands, in the gulf of Panama. S. America. In the north fide is a fafe channel; where, if necessary, there is a place for careening ships.

PAUL'S, St. a parifh in Charleftown diftrict, S. Carolina, containing 3,433 inhabitants; of whom 276 are whites, and 3,202 flaves.

PAULINGSTOWN, or Pawling, a townfhip in Duchefs co. New-York, lying on the weftern boundary of Connecticut, and has South and Eaft Town on the fouth. In 1790, it contained 4,330 inhabitants, of whom 42 were flaves, In 1796, there were 560 of the inhabiants qualified electors.

PAULIN'S Kill. See Suffex co. New-Je fey.

PAULSBURGH, a township in Grafton co. New-Hampshire, on the head waters of Amonooluck river, and thro' which passes Androscoggin river.

which paffes Androfcoggin river. PAULUS Hook, in Bergen co. New-Jerfey, is on the welt bank of Hudson river, opposite New-York city, where the river is 2,000 yards wide. Here is the ferry, which is perhaps more used than any other in the United States. This was a fortified post in the late war. In 1780 the frost was so intense that the passage across the river here was practicable for the heaviert cannon.

PAWLET, a townfhip in Rutland co. Vermont, having 1,458 inhabitants. It ftands on the New-York line, has Wells on the north, and Rupert in Bennington co. on the fouth, and is watered by Pawlet river, which joins Wood creek and the confluent ftream, falls in South Bay at Fiddler's Elbow. Hayftack mountain is in this townfhip.

PAWTUCKET Falls, in Merrimack river, are in the township of Dracut.

PAWTUXET, a village in the townthip of Crantton, Providence co. Rhode-Island.

PAXAROS, an ifland on the coaft of California, in the N. Pacific Ocean. N. lat. 30. 18. W. long. 120. 45.

PAXTON, Upper and Lower, two

PAZ

townships in Dauphin co. Pennsylvania. PAXTON, a township of Massachufetts, situated in Worcester co. 8 miles welt of Worcester, and 55 south-welterly of Boston. It was incorporated in 1765, and contains 558 inhabitants.

PAYJAN, a fmall town in the jurifdiction of Truxillo, in Peru, 8 leagues S. of St. Pedro.

PAYRABA, a town and captainfhip in the northern division of Brazil.

PAYTA, or Paita, a finall fea-port of Quito on the coaft of Peru, with an excellent harbour, 11 leagues north of the ifland called Lobos de Payta. Shipe from Acapulco, Sonfonnate, Realeijo, and Panama, to Callao, can only touch and refresh here ; and the length of their voyages, by reafon of the winds being most of the year against them, occasions the port to be very much fre-quented. Yet so parched is the fituation of Payta, that it affords little befides fifh, a few goats, and frefh water; their chief provisions being furnished by Colan and Piura, the one 3, and the other 14 leagues diffant. The bay is defended by a fort, and it is fo fituated that even mufkets alone can hinder boats from landing, being under a pretty high hill, on the fummit of which is another fort, that commands the town and lower fort. It had only a fort with 8 guns, when Commodore Anfon took it in 1741. He burnt the town, in which was merchandize to the value of a million and a half of dollars, because the governor refused to ranfom it. The plunder, in dollars and plate, amounted to £ 30,000 fterling. It was plundered and burnt by Capt. Cavendifh, in 1587, and by George Spilberg in 1615. There is anchorage in 101 fathoms, about a mile and a half from the town. S. lat. s. 15. W. long. 80. 55.

Paz, La, a imall jurifdiction of the audience of Charcas, in Peru, S. America. It is fituated in the mountains, one of which, called Illimani, contains, in all human probability, immenfe riches, for a crag of it being broken off fome years fince by a flash of lightning, fuch a quantity of gold was found among the fragments, that it was fold for iome time at La Paz for eight pieces of eight per ounce. But the fummit of this mountain being perpetually covered with ice and fnow, no attempt has been made to open a mine.

PAZ,

Paz, I.a, a city of Peru, and capital of the above jurifdiction, is fituated eaft-ward of the lake Titiaca, on the fide of a valley, among the breaches of the mountains, through which a pretty large river flows. In freshets, the current of the river forces along huge maffes of rocks, with some grains of gold. In the year 1730, an Indian, while washing his feet in the river, found a lump of gold of fuch a fize, that the Marquis de Caflel Fuerte gave 12,000 pieces of eight for it, and fent it to Spain as a prefent worthy the curiofity of his fovereign. This city contains, befides the cathedral, many public edifices, and about 20,000 inhabitants. It is 180 miles north of La Plata, and 3 50 foutheaft of Cuico. S. lat. 15. 59. W. long. 64. 30.

PEA

PAZARO, a cape of N. America, on the W. fide of the peninfula of California, towards the fouth end of it, in about lat. 14. N. and long. 113. W. PAZQUARO, a lake in Mexico, or

New-Spain.

PEACE, an island on the coast of Nova-Scotia, a little to the fouthward of Mirachi Point.

PEACHAM, a township in Caledonia co. Vermont, lies W. of Barnet on Connecticut river. It contains 365 inhabitants.

PEACOCK, a township in Buck's co. Pennsylvania.

PEAKS OF OTTER are thought to be the highest part of the Blue Ridge, or perhaps any other in North-America, measuring from their base. The height is 4,000 feet ; /which, however, is not one-fifth of the height of the mountains of South-America.

PEARL, a fmall ifle or fhoal in the Weft-Indies, in lat. 14. 53. N. and long. 79. 13. W.

PEARL, an island in the Gulf of Mexico, towards the mouth of the Miffifippi, a few leagues from Dauphin Ifland; about 6 or 7 miles in length, and 4 in breadth.

PEARL Mands, in the Bay of Panama, called alfo King Iflands, fituated in the S. Pacific Ocean. They are 12 leagues from the city of Panama. They are low, and produce wood, water, fruir, fowle and hoge; they also afford good harbours for thips The northernmoft is named Pachea; the fouthernmost St. Paul's. N. lat. 7. 10. W. long. 81.45.

PEARL, a river which rifes in the Chactaw country, in the W. part of Georgia, has a foutherly courfe to the Gulf of Mexico, and is navigable upwards of 150 miles. Its principal mouths are near the entrance at the E. end of the Regolets, through which is the paffage to Lake Ponchartrain. It has 7 feet at its entrance, and deep water afterwards. In 1769, there were fome fettlements on this river, where they raifed tobacco, indigo, cotton, rice, Indian corn, and all forts of vegetables. The land produces a variety of timber. fit for pipe and hoghead flaves, mafts, vards, and all kinds of plank for thipbuilding.

PEARN's Point, on the W. fide of the ifland of Antigua, and the W. fide of Mufketo Cove. Off it are the Five Iflands.

PECKWALKET, an ancient Indian village, now called Fryeburg, 60 miles from the fea.

PEDEE, a river which rifes in N. Carolina, where it is called Yadkin river. In S. Carolina it takes the name of Pedee; and receiving the waters of Lynche's Creek, Little Pedee, and Black river, it joins the Wakkamaw river, near Georgetown. These united streams, with the accession of a small creek on which Georgetown flands, from Winyaw Bay, which, about 12 miles below, communicates with the ocean.

PEDRA Shoals, in the West-Indies, extend from lat. 17. 20. to 30. N. and from long. 79. 9. to 79. 17. W.

PEDRAS Point, on the coaft of Brazil, is 7 leagues E. S. E. from the ftrait of St. John's Ifland, and 75 from Cape North. Alfo a point on the fame coaft ro leagues W. N. W. of Brandihi Bay.

PEDRAS, a river on the N.W. fide of Punta des Pedras, at the fouthern extremity of Amazon river.

PEDRO, St. a town in the jurifdiction of Lambeyque, in Peru, confifting of 130 houfes, mostly inhabited by Indian families. It is washed by the river Pacalinayo, which renders the country round very fertile. It is feated near the S. Sea, 20 leagues from Lambeyque. S. lat. 7. 25. 49. W. long. 78. 20. 15. PEDRO, St. one of the Marquefas Iflands, in the S. Pacific Ocean, called by the natives Onateyo; it is about 3 leagues in circuit, and lies S. 41 leagues from

from the lat. 9. 58 PEDRO N. Amer Coral rive river wit ftream ru falls into California PEDRO coaft of 1 Portlant] is W. by S. Į E. Pedro, lie PEDR of the far dro Poin but has outer edg PEDR li, is 8 let and 14 S St. Pedro PEDR the Iflanc S. E. co: the river PEDR the Gulf about lat PEER Welt-Ch fide of I the creek mouth. Kill, an In the w encampe vicinity. - PEGU of Paffai rifes in name li another W. of N PEJEI Androfe River, PELE to Clinci PELH fetts, in catterly of Bofto and cont PELI co. Ne fouth St

V. fide of the W. fide the Five

nt Indian 60 miles

in N. Cakin river. name of waters of dee, and akkamaw efe united of a fmall inds, from 12 miles ocean. ft-Indies, . N. and w. of Brazil. e ftrait of om Cape ame coaft Brandihi

W. fide of thern ex-

rifdiction fifting of by Indian the river e country ated near nbeyque. . 20. 15farquefas n, called s about 3 1 leagues from PEL

from the E. end of La Dominica. S. lat. 9. 58. W. long. 158. 30.

PEDRO, St. a town of New-Mexico, N. America, fituated on the S. fide of Coral river, near the confluence of that river with the Colorado. The united fream runs a fhort way fouthward, and falls into the north part of the Gulf of California.

PEDRO Point, Great, is on the fouth coaft of the illand of Jamaica. From Portlant Point to this point, the courfe is W. by N. about 11 leagues. About S. J. E. diffance 14 leagues from Point Pedro, lies the cafternmoft Pedro Key. PEDRO, Little Point, on the S. coaft of the fame ifland, lies E. of Great Pedro Point, within a floal partly dry; but has 5 fathoms within and to on the outer edge of it.

PEDRO Point, St. on the coalt of Chili, is 8 leagues N. N. E. of Point Qudar, and 14 S. S. W. of Cape Galera. Port St. Pedro is contiguous to this point.

PEDRO, Pori St. is fituated S.W. of the Island of St. Catherine, and on the S. E. coaft of Brazil, at the entrance of the river La Plata.

PEDRO *River*, St. runs weltward to the Gulf of Mexico. Its mouth is in about lat. 21. N. and long. 98. W.

PEER's-KILL, a finall post-town in Well-Chefter co. New-York, on the E. fide of Hudson's river, and N. fide of the creek of its name, 5 miles from its mouth. It is 20 miles fouth of Fish-Kill, and 50 northerly of New-York. In the winter of 1780, Gen. Walhington encamped on the strong grounds in this vicinity.

PEGUNNOCK, a north-western branch of Passaik river, in New-Jersey, which rifes in Suffex co. The town of its name lies between it and Rockaway, another branch south of this river, N. W. of Morristown.

PEJEPSCOT, or Pejipfkaeg Falls, in Androscoggin river. See Kennebeck River, &c.

PELESON, a name fometimes applied to Clinch River; which fee.

PELHAM, a township of Maffachufetts, in Hampshire co. 12 miles northcatterly of Northampton, and 85 welt of Bolton. It was incorporated in 1742, and contains 1040 inhabitants.

PELHAM, a township of Rockingham co. New-Hampshire, fituated on the fouth State line, which separates it from Dracut in Maffachufetts. It lies on the E. fide of Beaver river, 30 miles fouthwefterly of Exeter, and 36 N. of Bolton. It was incorporated in 1746, and contains 791 inhabitants.

PELHAM, a township of New-York, fituated in West Chefter co. bounded foutherly and easterly by the Sound, northerly by the north bounds of the manor of Pelham, including New-City, Hart, and Applesby's Islands. It contains 199 inhabitants; of whom 27 are electors, and 38 flaves.

PELICAN, Great, an island a mile long and very narrow, east of the Bay of Mobile in the Gulf of Mexico. Its concave fide is towards the east end of Dauphin Island. Hawk's Bay lies between these two islands. Little Pelican Island is a small fand key, fouth-east of Great Pelican. Its eastern curve meets a large shoal extending from Mobile Point:

PELICAN Iflands, on the fouth coaft of the island of Jamaica, are fituated off the point fo called, weltward of Port-Royal harbour.

PELICAN, a fmall ifland at the fouthweft point of the ifland of Antigua,

PELICAN Rocks lie in Runaway Bay, on the welt fide of the ifland of Antigua, towards the north-weft. They lie under water, and are very dangerous.

under water, and are very dangerous. PELICAN Shoals, fmall patches of faud-banks about half a mile from the fhore of the fouth-welt coaft of the Island of Barbadoes.

PEMAQUID, a bay on the fea-coaft of Lincoln co. Diffrict of Maine. It has east of Sheepicot river, and contains a number of iflands, many of which are under cultivation.

PEMAQUID Point, on the weft fide of the above bay, lies 2 miles east of Booth Bay, and about 4 leagues northweft of Menhegan Ifland. N. lat. 44. 5. W. long. 69.

PEMAGON, a fettlement of the Diftrict of Maine, 7 miles from Denney's river, and 14 from Moole Illand.

PEMBRORE, a township of Maffachufetts, in Plymouth co. 31 miles fouth by east of Boston. It was incorporated in 1712, and contains 1954 inhabitants. It lies 18 miles from the mouth of North river; and vessels of 300 tons have been built here. See North River. PEMBRORE, the Suncool of the In-

PEMBRORE, the Suncold of the Indians, a township of New-Hampshire, in Rockingham co. on the east fide of D d Meerimack Merrimack river, opposite to Concord. | in length, and half a mile in breadth It lies upon two small rivers, Bowcook | from E. to W. and Suncook, which run a fouth by-weft courfe into Merrimack river. In 1728, it was fettled and called Loverwell's Town. It was incorporated in 1759, and contains 956 inhabitants.

PEMIGEWASSET, a river of New-Hampfhire, which fprings from the eaft-ern part of the ridge called the Height of Land. Moofe-hillock Mountain gives it one branch; another comes from the S. W. extremity of the White Mountains, and a third comes from the township of Franconia. Its length is about 50 miles; its course generally S. and it receives from both fides a number of fireams. Winnipifeogee river, comes from the lake of that name, and unites its waters with the Pemigewaffet at the lower end of Sanborntown. From this junction, the confluent stream bears the name of Merrimack, to the fea. See Merrimack.

PENDLETON, a county of Virginia, bounded north-weft by Randolph, and fouth by Rockingham counties; watered by the fouth branch of the Patowmack. It contains 2,452 inhabitants, including 73 flaves. Chief town, Frankford.

PENDLETON, acounty of Washington district, S. Carolina, on Keowee and Savannah rivers. It contained, in 1795, 9,568 inhabitants, of whom 834 are flaves; and fends 3 reprefentatives and a fenator to the State legiflature. The court-house in this county is 33 miles N. N. E. of Franklin court-houfe in Georgia, and 52 weltward of Cam-bridge. A post-office is kept at this court-houfe.

PENGUIN, an island in the Atlantic Ocean, about 10 miles N. E. of the coaft of Newfoundland. It has this name from the multitude of birds of that name which frequent it. N. lat. 50. 5. W. long. 50. 30. There is alfo an island of the fame name, on the coaft of Patagonia, in the S. Atlantic Ocean, 3 leagues fouth-eaft of Port Defire. It is an uninhabited rock, high at the ends and low in the middle, and is the largeft and outermost of a number of fmall ifles or rocks, and is about a mufket thot from the main land. It abounds in an extraordinary manner, with penguins and feals. It is three-fourths of a mile

10458

Marridgen bi

The best to

PEN

PENN's Rocks, two clufters of iflands in the broadest and fouth-weft part of Hudson's Bay, N. America; diftinguished by the names of E. and W. Penn's.

PENNINGTON, or Pennytown, a pleafant and flourifling village in Hunterdon co. New-Jerfey, 9 miles W. of Prince-ton, and 56 N. E. by N. of Philadelphia. It contains a church for public worfkip, and about 40 houfes.

PENN Fort, stands at the mouth of a fmall creek, on the welt fide of Delaware river, in Northampton co. about 21 miles north of the town of Eafton, and near 70 north of Philadelphia. N. lat. 40. 59. W. long. 75. 13. The road from Philadelphia to Tioga Point, paffes through the opening in the Blue Mountains, called Wind Gap, about 9 miles fouth-weft of this fort.

PENN, Port, in New-Caftle co. Delaware, is fituated on the W. bank of Delaware river, oppofite to Reedy Inand.

PENN's a township of Pennsylvania, on Sulquehannah river. See Northumberland.

PENNSBOROUGH, East and West, two townships in Cumberland co. Pennsylvania. There is alfo a townfhip of this name in Chefter co. Pennfylvania.

PENNSBURY, a finall town of Pennfylvania, in Buck's co. on a fmall creek of Delaware river. It was a manor which the celebrated Mr. Penn referved for himfelf. Here he built a houfe, and planted gardens and orchards; which, with many additional buildings and improvements, still continue.

PENN's Neck, in Salem co. New-Jerfey, lies on Old Man's Creek, which is part of the boundary between Salem and Gloucefter counties. It is 12 miles N. E. by N. of Salem, 31 miles from the Delaware, and 5 below Swedefborough.

PENN's Neck, the name of a range of farms of excellent foil, fituated about a mile and a half fouth-east of Princeton in New-Jerfey, on a point of land formed by Millstone river and Stony brook. It derived its name from the celebrated legiflator, William Penn, who formerly owned this tract.

PENNSYLVANIA, one of the United States of America, is fituated between tween 39. ween 74. 4 heing in le breadth 15 aware rive New-Jerfe Lake Erie, weft by the a part of V Virginia, D State (exc below) lie logram. State, con was lately this State. fquare mil counties, Delaware, Lancafter, zerne, Yo berland, F don, Miffl Fayette, V Lycoming. townships, legiflature, cient num neighbourl court of quarter fef townfhip t of affembli overfeers (collector o the roads, ber of inha fus of 1790 flaves : Bu ers has bee period, the greater the the natura There are with their : late the w ware, Schu iogany, M The bay a gable up to Trenton, a fhip of ft phia, the the fea, by aware. State may | ticularly th ingdon, Cu Dauphin, a

.18

n breadth

of iflands ft part of 1; diftinand W. m, a plea-Iunterdon of Princeladelphia. : worfhip, outh of a of Delaco. about of Eafton, shia. N. The road int, paffes ae Mounat 9 miles : co. Del-. bank of Reedy Innfylvania.

Weft, two Pennfylip of this nia. of Pennnall creek a manor a referved ioufe, and ; which, s and im-

Northum-

New-Jerwhich is ialem and miles N. from the borough, range of d about a Princeton and formty brook. celebrated formerly

of the Uuated between

tween 39. 43. and 42. N. lat. and beween 74. 48. and 80. 8. W. longitude : being in length about 288 miles, and in breadth 156. It is bounded east by Delaware river, which feparates it from New-Jerfey; north by New-York and Lake Erie, where there is a good port ; weft by the N. Weftern Territory, and a part of Virginia; fouth by a part of Virginia, Maryland, and Delaware. The State (except the purchase mentioned below) lies in the form of a parallelogram. The north-weft corner of this State, containing about 202,000 acres, was lately purchafed of Congress by this State. Pennfylvania contains 44,900 fquare miles, and is divided into 23 counties, viz. Philadelphia, Chefter, Delaware, Bucks, Montgomery, Berks, Lancaster, Dauphin, Northampton, Luzerne, York, Cumberland, Northumberland, Franklin, Bedford, Huntingdon. Mifflin, Westmoreland, Somerset, Fayette, Washington, Alleghany, and Lycoming. These are fubdivided into townfhips, not by any fpecial law of the legislature, but on application of a fufficient number of the citizens, in any neighbourhood, to the judges of the court of common pleas and general quarter feffions of the county. In each township the citizens have the privelege of affembling once a year, to choose two overfeers of the poor, two affeffors, a collector of taxes, two fupervifors of the roads, and a conftable. The number of inhabitants, according to the cenfus of 1790, is 434, 373, including 3,737 flaves : But the immigration of foreigners has been fo confiderable, fince that period, that the number must be far greater than could be expected from the natural increase of population. There are 6 confiderable rivers, which, with their numerous branches, peninfulate the whole State, viz. The Delaware, Schuylkill, Sufquehannah, Youghiogany, Monongahela, and Alleghany. The bay and river Delaware are navigable up to the Great or Lower Falls at Trenton, 155 miles from the fea, and a fhip of the line can afcend to Philadelphia, the metropolis, 120 miles from the fea, by the fhip-channel of the Delaware. A confiderable part of the State may be called mountainous; particularly the counties of Bedford, Huntingdon, Cumberland, part of Franklin, Dauphin, and part of Buck's and North-

ampton, through which pafs, under various names, the numerous ridges and fours which collectively form the Great Range of Alleghany Mountains. The principal ridges here are the Kittatinny, or Blue Mountains, which pals north of Nazareth, in Northampton co. and purfue a S. W. courfe, across the Lehigh, through Dauphin co. just above Harrifburg, thence on the weft fide of the Sulquehannah, through Cumberland and Franklin counties. Back of thefe, and nearly parallel with them, are Peter's, Tufcarora, and Nefcopek Mountains, on the east fide of the Sufquehannah; and on the weft, Shareman's Hills, Sideling Hills, Ragged, Great Warriors, Evits and Wills Mountains ; then the Great Alleghany Ridge ; weft of this are the Chefnut Ridges. Between the Juniatta and the weft branch of the Sulquehannah are Jack's, Tuffy's, Nitting, and Bald-Eagle Mountains. The vales between these mountains are generally of a rich, black foil. fuited to the various kinds of grain and grafs. Some of the mountains will admit of cultivation almost to their tops. The other parts of the State are generally level, or agreeably varigated with hills and vallies. The foil of Pennfyl-vania is of various kinds ; in fome parts it is barren, but a great proportion of the State is good land; and no inconfiderable part of it is very good. The richeft tract that is fettled, is Lancaster co. and the valley through Cumberland, York and Franklin. The richeft that is unfettled, is between Alleghany river and Lake Erie, in the N. W. part of the State, and in the country on the heads of the eaftern branches of the Alleghany. Pennfylvania includes the greater part of the kinds of trees, fhrubs, and plants, that grow within the Uni-Oaks, of feveral fpecies, ted States. form the bulk of the woods. Hickory and walnut make a greater proportion than in the northern States. Saffafras, mulberry, tulip-tree, and cedar, are common and grow to perfection. The magnolia glauca, or fwamp-faffafras are found in low grounds; the twigs and roots are used both in bath and decoction for removing the rheumatifm. The magnolia acuminata, or cucumbertree, grows very tall about the weftern mountains. , The magnolia tripetala, or umbrella-tree, is found in fome parts 16 Dd 2

or 20 feet high. The bark is fmooth, and the leaves fometimes exceed 12 or s juches in length, and 5 or 6 in breadth, terminating in a point at each extremity. The leaves are placed at the ends of he branches, in a circular form, refembling an umbrella; hence the name. The bark of the tulip-tree is effected a tolerable fubftitute for the Peruvian bark; but the cornus florida, or dogwood, which is frequent in the State, preferred. Befides many other valuable trees and firubs, are the feveral species of maple; of these the fearlet flowered and fugar maple are the most useful they are common in the northern and reftern parts of the State, and are larger than the other species, growing from so to 60 feet high, and yield abundance of Jap for the making of sugar. The afh-leaved tooth-ach tree, is found here and in Maryland. The bark and capales have an acrid tafte, and are uled in relieving the tooth-ach, whence it has got its name. The furubby bithwort rows near Fort Pitt. It thrives in the made, in a rich foil ; grows about 30 feet high, and fends off many twining branches. The roots have a lively aromatic tafte, and are thought to have equal medicinal virtue to the fmall Virginia make-root. The fambacus canadenfis, or red-berried elder, is found here. Among the Indians it is called fever-bufh; and a decoction of its wood and buds is highly effected by them. It would be endlefs to defcribe the beautiful flowering thrubs, and uleful as alfo ornamental plants in this State. Grapes of feveral forts are common: the late kind, when mellowed by froft, make, with the addition of fugar, good wine. At prefent, the cultivation of the vine is much in vogue in Pennfyluania, and good wine has been already made. Iron ore abounds in this State : copper, lead, and allum appear in fome places. Lime flone is common, as allo feveral kinds of marble. In the middle and weftern country is abundance of coal. At the head of the weftern branch of Sulquehannah is an extensive bed, which firetches over the country fouth-weftwardly, fo as to be found in the greatest plenty about Pittfburg. There are also confiderable bodies on the head waters of the Schuylkill and Lehigh; and at Wyoming there is a bed open, which gives very intenfe heat.

PEN

161.

PEN

Uleful quadrupeds, in the new diftricts, are deer, in great numbers, bea. vers, otters, racoons, and martins, Buffaloes rarely crofs the Ohio, and elks feldom advance from the north: Panthers, wild cats, bears, foxes and wolves are not rare; the laft do moft milchief, efpecially in the winter ; but the fur and fkins of all are valuable. In the thick fettlements, rabbits and fquirrels are frequent; also minks and musk-rats in marfhes; partridges are yet numerous, though the late hard winters have deftroyed many, and wild turkies in the new fettlements; pheafants and groufa are become fcarce; pigeons, ducks and wild geele are generally found in plenty in their proper featons. Here are a great number of finging birds, as many migrate to this State from N. and S. in. certain fealons.

Trouts are common in the rivulets, in length feldom above a foot. In the eaftern invers, the principal filh are rock. and fheep's head, with fhad and herring, which, in the fpring, come up from the fea in great floals. Thefe are not found in the weftern waters, which are faid to have their own valuable kinds, efpecially a fpecies of cat fifh, weighing from 50 to reo pounds; yellow perch and pike are also in them much larger and more numerous. The fouth fide of Pennfylvania is the beft fettled. throughout, owing entirely to the circumftance of the weftern road having been run by the armies, prior to 1762, through the towns of Lancaster, Carlifle and Bedford, and thence to Pittfburg. For the purpofe of turning the tide of fettlers from this old channel into the unfettled parts of the State, the government and landed interest of Pennfylvas nia have been, and are still, buly in cutting convenient roads. During the fummer of 1788, they laid out a road northfrom the former roads beyond Bethlehem, to the north portage between Delaware and Sufquehannah; and thence north 80° weft to the mouth of the Tioga, the former 70 miles, and the latter above 60. It is now in contemplation. to cut a roade from Sunbury, at the forks of the E. and W. branches of Surquehannah, W. 130 miles, to the mouth of Toby's creek, which empties into the Alleghany from the eaft. A road is. alfo cut from the mouth of the Tioga, fouthward to the mouth of Loyal, which empties

mpties in annah. Huntingdo branch of miles to C of the Alle been lately to Lancast between th are in con to the Tul kill, a ca undertaker by an inco pital is 4 through th When this will be of Juniatta, 1 branches water at From this of the Sufe until it fal Bay at h River. (fent plans ently inter of its fize greatly fa new lands. of Pennfy ly this Sta gation. 1 inland la Philadelph from each is no dou State may the land tenths. I to Pittibu may be ul the whole thefe rout portion o the wefter and their flax, pot-brought t Pennfy grain, & ing State grain of the year a \$ 50,000 barrels; a years fine tate are

Long St -

new difbers, bea. martins o, and elks the Pan-and wolves ft milchief. the fur and h the thick nirrels are ofk-rats in numerous. rs have dekies in the and groufe ducks and d'in plenty fere are a s, as many . and S. in ie rivulets, st. In the Th are rock i and hercome up Thefe are ers, which able kinds, , weighing llow perch such larger fouth fide weighing fettled. to the cirbad having IF to 1762, er, Carlifle Pittfburg. the tide of iel into the the govern-Pennfylvas suly in cutig the fumroad north and Bethletween Deland thence of the Tiod the latter itemplation. at the forks of Sulquehe mouth of ies into the. A road is. the Tioga, oyal, which empties

PEN

mpties into the west branch of Sufguehannah. Another road is cut from Huntingdon town, on Franks-Town branch of the Juniatta, weltward 30 miles to Conemagh, a navigable branch of the Alleghany. A turnp ke road has been lately completed from Philadelphia to Lancaker, which fhortens the diffance between these places 8 miles; and others are in contemplation. From Swetara to the Tulpehoken branch of the Schuylkill, a canal and lock navigation is undertaken, and the works commenced, by an incorporated company, whole ca-pital is 400,000 dolla s. This leads through the Schuylkill to Philadelphia. When this thall be effected, a paffage will be open to Philadelphia from the Juniatta, the Tioga, and the E. and W. branches of the Sufquehannah, which water at least 15,000,000 of acres. From this junction, the general course of the Sulquehannah is about fouth-east, until it falls into the head of Chefapeak Bay at Havre de Grace. See Tiega River. On the completion of the prefent plans, the State will be as conveniently interfected by roads as any other of its fize in the Union, which will greatly facilitate the fettlement of its new lands. A flight view of the map of Pennfylvania will beft fhew how finely this State is fituated for inland navigation. Nature has done fo much for inland land-carriage, that although Philadelphia and Lake Erie are diffant from each other above 300 miles, there is no doubt but that the rivers of the State may be fo improved, as to reduce the land carriage between them ninetenths. In the fame way the navigation to Pittfburg, after due improvement, may be used instead of land-carriage for the whole distance, except 23 miles. By these routes it is clear, that a large proportion of the foreign articles used on the western waters must be transported, and their furs, Ikins, ginleng, hemp, flax, pot-aft, and other commodities brought to Philadelphia.

Pennfylvania has the various kinds of grain, &c. common to the neighbouring States, but wheat is the principal grain of very general cultivation. In the year 1786, the exports of flour were 150,000 barrels; in 1789-369,618 barrels; and much greater quantities in years fince. The manufactures of this flate are of numerous kinds. Iron 421

works are of long flanding, and their products increase in quantity, and improve in quality. The furnaces are 16, and the forges 37. There are 18 rolling and flitting mills, which are faid to cut and roll 150 tons a year. The forges will, it is thought, if properly conducted; manufacture each 170 tons of bar iron a year-total 6290 tons. Belides pigs caff at the furnaces, there are pots, kettles, pans, ovens, indies, tongs, thoyels, and irons, plough-irons, spades, hoes, sheet-iron, hoops; iron and steel work for pleafure and working carriages; nails, bolts, fpikes; various iron-work for thips, mills and buildings, cannon balls, and fome mufkets ; fcythes, fickles, axes, drawing-knives, fome faws and planes, and other tools. The other extenfive manufactures are numerous, vizthofe of leather, fkins, and fur, wood, paper, gunpowder, bricks, earthen ware, copper, lead, tin wares, pewter, cotton, jugar, molaffes, tobacco, &c. &c. There are 52 paper-mills in the State and their annual product is comput-ed at 25,000 dollars. Since the year 1770, 25 gunpowder mills have been erected. There are about 300,000 wool and fur hats manufactured annually in the State; nearly one half of which are of fur. In the manufacture of iron, paper, pleafure carriages, and cabinet work, Pennfylvania exceeds not only New-York, but all her fifter States. Much cotton is worked up in families; and imported linen is now printed, in an increasing degree. The manufactures of Pennfylvania have greatly increased within a few years, as well by mafter workmen and journeymen from abroad, as by the fkill and industry of the natives. Some performs have begun to prefs oil from hickory The Mefirs. Marshalls of Philanots. delphia, have commenced the making of Glauber's falt, fal ammoniac, and volatile falts; they already fupply the whole Union with the first article, and export a part of the others. A mill of Rumfay's (the improvement of Barker's) near that city. grinds, by water, flour, chocolate, inuff, hair powder, and mustard ; shells chocolate nuts ; preffes tobacco for chewing and fmoaking; and bolts meal. The water-works near the falls of Trenton, which grind grain, roll and flit iron, and pound plaster of Paris, exhibit great Dda mechanifm.

PEN

mechanifin. Card manufactories are lately fet up. The hand machines for carding and fpinning cotton have been introduced and improved. Sir Richard Arkwright's famous water-mill for fpinning cotton yarn has been obtained; also the machinery to fliver, rove, and spin flax and hemp into thread, fit for linen of thirty cuts to the pound ; which will also ferve for the roving and spinning combed wool into worked yarn. Screws for papermills are now cut from folid caft iron. Lanterns for light-houles are made by Mr. Wheeler of Philadelphia; who alfo executes work for fugar-mills in the Weft-Indies: during the war he made cannon from wrought-iron. The commerce of Pennfylvania with the eaftern and fouthern States is, in great part, an exchange of staple commodities. Wheat-flour and bar-iron are exported to New-England for whale-oil and bone, spermaceti, seal-skins, mackerel, cod fifh and falmon, Rhode-Ifland and Connecticut cheefe; to S. Carolina and Georgia for live-oak, cedar, cotton, rice and indigo; to N. Carolina for tar, pitch, turpentine, and lumber. Much of the trade with the fouthern States arifes from the fuperiority of Pennfylvania in manufactures and commerce. Great quantities of deer-fkins, with those of otters, racoons, foxes, mulk-rats, and beavers, are imported from the back country. Virginia fends a great deal of wheat, and unmanufactured tobacco. In return, the receives many articles of cloathing, furniture, farming utenfils, equipage; fome Eaft-India and European goods; and even Weft-India produce ; of all thefe, more or lefs, according to the local improvement and fituation. Hats, faddlery, thoes, windfor chairs, carriages, hewn stones, iron castings for domestic use, wheel tire, fpades, hoes, axes, paper, books, tin-ware, and brushes, constitute a great proportion of the exports to the fouthward. Numerous droves of lean cattle come from the western parts of these States, where they have a wide range, but want meadow. Virginia fends of late a confiderable deal of coal, fome lead, and peach brandy. This liquor alfo comes from Maryland; but from both in quantity very fmall, confidering its value, and the facility of railing the fruit. The eaftern fhore of

PEN

Maryland fends to Philadelphia confiderable quantities of wheat, and Indian corn : from the weftern comes the kitefoot tobacco. This State has also fome trade with the fouth of Pennfylvania, by the way of Chelapeak hay: fome parts of it receive the fame commodities as Virginia, efpecially pleafore carriages. The trade with New-York depends chiefly on the fluctuation of the market; American and foreign goods, of the fame kinds, are carried between the two capital cities, as their prices fall and rife. Albany peas and craw-fifh are, however, articles in regular demand, from New-York. Great part of New-Jerfey and Delaware State have, as neighbours, much intercourfe with Pennfylvania. The first supports in a great measure the market of Philadelphia, furnishes rye-meal, much Indian corn and lumber, and fome iron bloomery t the other fends great quantities of excellent flour from the mills of Brandywine, lumber from the diffrict on the bay, and fat cattle from the paftures adjoining Delaware. Many of thefe, and of those fattened in the vicinity of Philadelphia, are brought from the fouth; and alfo from the countries on the North and Connecticut rivers, as far as Vermont and Maffachufetts. The commerce of Pennfylvania, in the weft, is by the Ohio with the Spanish, and by the lakes with the British dominions; and both ways with the Indian tribes. This trade will probably be confiderable, fince commercial flipulations are formed with those powers, and peace is concluded with the Indians. At prefent nearly the whole foreign commerce is carried on by the port of Philadelphia. Its diffance from the fea, and its clofing by ice in the winter, are diladvantages; but the first is lesened by improved pilotage; the other by the conftruction of the piers below, and by the occasional thaws which permit veffels to clear their way during the winter. In common leafons the navigation is obttructed fix weeks; a fhorter period is as probable as a longer; though in the late hard winters, loads of wood have paffed the river near the city, in the first days of March. The population of this state has been already mentioned; it is nearly to for every fquare mile. The number of militia is eftimated at upwards of 90,000, between 18 and 18 and 5 tants are English, l Scotch, 1 Dutch. Irifh and young of and Epik lifh extra third of chiefly ir counties c and Moni Prefbyter Catholics the N. of fettled fro been fom denote the habit the and are compole a bitants of numerous tropolis, 1 phia, Mo Lancafter moftly in ing in oth therans, fect) Cal Moravian ifts, Tur are a fpe all difting industry, except t] Baptifts, defcended and are no affemblag the manr political form th The nun State is a German German kers, 54; 15; Ron Prefbyteri Quakers, nanters, 1 Jewish Sy ing to 3 and other merous an than in a feminaries

phia confiand Indian s the kites alfo fome ylvania, by fome parts nodities as carriages. k depends f the margoods, of d between heir prices d craw-fifh lar demand rt of Newhave, as urfe with ports in a f Philadeluch Indian ron bloomquantities e mills of the diffrict m the paf-Many of in the viciought from e countries it rivers, as flachufetts. ania, in the he Spanish, ritish domithe Indian robably be ial Aipulaowers, and e Indians. ole foreign the port of rom the fea, winter, are is leffened ther by the ow, and by permit vefthe winter. ation is ober period is ough in the wood have ity, in the population ly mentionvery fquare itia is eftio, between 18 and

PEN

18 and 53 years of age. The inhabitants are principally the defcendants of English, Irish, and Germans, with some Scotch, Welch, Swedes, and a few Dutch. There are also many of the Irifh and Germans who emigrated when young or middle aged. The Friends and Episcopalians, are chiefly of Englifh extraction, and compose about onethird of the inhabitants. They live chiefly in the metropolis, and in the counties of Chefter, Philadelphia, Bucks and Montgomery. The Irifh are mothly Prefbyterians, but fome are Roman Catholics : their anceftors came from the N. of Ireland, which was latterly fettled from Scotland; hence they have been fometimes called Scotch Irifh, to denote their double descent. They inhabit the weftern and frontier counties, and are numerous. The Germans compose about one quarter of the inhabitants of Pennfylvania. They are most numerous in the north parts of the metropolis, and the counties of Philadelphia, Montgomery, Bucks, Dauphin, Lancaster, York, and Northampton; moffly in the four laft, and are fpreading in other parts. They confift of Lutherans, (who are the most numerous fect) Calvinift, or Reformed Church, Moravians, Roman Catholics, Mennonifts, Tunkers, and Zwingfelters, who are a species of Quakers. These are all diffinguished for their temperance, industry, and economy. The Baptifts, except the Mennonists and Tunker Baptifts, who are Germans, are chiefly defcended of emigrants from Wales, and are not numerous. A proportionate affemblage of the national prejudices, the manners, cultoms, religions and political fentiments of all thefe, will form the Pennfylvanian character. The number of congregations in the State is as follows: Prefbyterians, 86; German Calvinists, 84; nearly 84 of German Lutherans; Friends or Quakers, 54; Episcopalians, 26; Baptifts, 15; Roman Catholics, 11; Scotch Presbyterians, 8; Moravians, 8; Free Quakers, 1; Univerfalifts, 1; Covenanters, 1; Methodifts, 3 or 4; and a Jewish Synagogue; the whole amount-ing to 384. The literary, humane, and other useful focieties, are more numerous and flourishing in Pennsylvania than in any of the fixteen States. The feminaries of learning are respectable.

PEN

There is an university at Philadelphia, and colleges at Carlifle and Lancafter. The Epifcopalians have an academy at Yorktown in York co. There are alfo academies at Germantown, at Pittfburg, at Washington, at Allen's-Town, and other places; thefe are endowed by donations from the legislature, and by liberal contributions of individuals. The legislature have also referved 60,000 acres of the public lands for public Schools. The United Brethren, or Moravians, have academies at Bethlehem, and Nazareth on the beft eftablishment of any schools perhaps in America. Befides Philadelphia, the metropolis, the chief towns are, Lancaster, the larg-eft inland town of the United States, Carlifle, Pittfburg, Sunbury, Bethle-hem, Reading, Yorktown, Harrifburg, Washington, &c. This State was fettled by the celebrated William Penn, fon of the famous Admiral Penn, in 1682. By the favourable terms which Mr. Penn offered to the fettlers, and an unlimited toleration of all religious denominations, the population of the province was extremely rapid. The proprietaries, after the revolution, accepted of £130,000 from the legislature, in lieu of all quit-rents. They, however, ftill poffeis in Pennfylvania many large tracts of excellent land. The prefent conftitution of this State was ratified June 12th, 1792. A convention, to amend the conftitution, may be called where a majority of the people shall fignify their with fo it. The expence of the government of this State amounts to £32,280 annually See Philadelphia, for an account of the exports and imports of the State, &c.

PENNYTOWN. See Bennington. PENOBSCOT, a bay on the coaft of Hancock co. Diffrict of Maine, and called Norombsga by the first discoverer, is about 16 leagues wide from Nafkeag Point and Burnt Coat Ifland, on the F to the point on which Thomasty ftands, on the weft fide of the JWD The chief iflands it encloses ar bay, Haut, Long and Deer Islands a number of fmall ifles, rocks, e Fox, Through this bay, to the the river of its name, the the river of its name, the mouth of 1 befides nel goes up by a head- weftern chancalled Owl's Head, ? land on the W. Ifland on the W. ad between Longthe E. to Bagad and Cape Rofier on sce Point. The eaft ... ern channel is t Atween Haut-Island or 1 Dd4

the

the west and Burnt Coat Island on the raft, and through a reach, called Long-Reach, formed by the flores of Nafkeag, or Sedgwick, on the E. or N. E. and Deer-Iflands on the W. or S. W. till it unites with the other channel, between Point Roher and Long-Island. On a fine peninfula on the east fide of the bay, the British built a fort and made a fettlement which is now the fhire-town of the county of Hancock, and is a commodious place for the lumber trade. Haut-Ifland, or Ifle of Holt, lies in lat. 44. 23. N. and long 68. 10. W. and is the fouthernmost of the large ifles.

PENOBSCOT, the noble river which empties its waters into the above defcribed bay, is the most confiderable in the Diffrict of Maine, and rifes by two branches in the high lands. Between the fource of the welt fork, and its junction with the east, is Mooschead Lake, 30 or 40 miles long, and 15 wide. The eaftern branch paffes through feveral fmaller lakes. From the forks, as they are called, the Penobfcot Indians pafs to Canada, up either branch, principally the weft, the fource of which, they fay, is not more than 20 miles from the waters which empty into the St. Lawrence. At the forks is a remarkable high mountain. From thence down to Indian Old Town, fituated on an ifland in this river, is about 60 miles, 40 of which, the water flows in a ftill fmooth ftream, and in the whole diftance there are no falls to interrupt the paffage of boats. In this diftance the river widens and embraces a great number of iflands. About 60 rods below Indian Old Town are the Great Falls, where is a carryingplace of about 20 rods; thence 12 miles to the head of the tide there are no falls to obstruct boats. Veffels of 30 tons come within a mile of the head of the tide. Thence 35 miles to the head of the bay, to the feite of Old Fort Pownal, the river flows in a pretty ftraight courfe, and is eafily navigated. . Paffing by Majabagadule on the east 7 miles, and Owl's Head 20 miles further, on the weft, you enter the ocean. It is high water here, at full and change, 43 mi-"" nutes paft 10, At the entrance of the river is 10 fathons water. The Indians have a communication from this river to Scoodick river by a portage of 3 miles. This river was the weftern limits of Nova-Scotia or Acadia, by the treaty of Utrecht. La Midesti ason

a

PENOBSCOT," a post-town of the District of Maine, on the east fide of the bay of its name, fituated in lat. 44. 24. N. 3 miles N. by W. of Blue-Hill, 141 N. W. of Portland, a62 N. by E. of Bofton, and 606 from Philadelphia. It is a port of entry, and carries on a small trade in fifh and lumber. The exports in 1794, ending Sept, 30, amounted to 5,825 dollars. This township contained in 1790-1,048 inhabitants. In Feb. 1796, it was divided into two towns; the one retaining the name Penobicot, the other named Caftine, was made the fhire-town, is a port of entry, and contains the poft-office.

PENOBSCOTS, a fmall tribe of Indians who live in Indian Old Town, on an island in Penobscot river. They aver that they have poffeffed the ifland, on which their town flands, 500 years. It ftands just above the Great Falls, and confifts of about 200 acres of land. See Indian Old Town. In a former war, this tribe loft their lands; but at the commencement of the last war, the Provincial Congress forbade any person fettling on the lands from the head of the tide on Penobscot river, included in lines drawn fix miles from the river on each fide; that is, a tract 12 miles wide, interfected by the middle of the river. They, however, confider that they have a right to hunt and fifh as far as the mouth of the Bay of Penoblcot extends. This was their original right, in opposition to any other tribe, and they now occupy it.

PENSACOLA Harbour and Town. The Harbour is on the N. fhore of the Gulf of Mexico, 11 leagues caft of Port Lewis, and Mobile, and 158 W. of the iflands of Tortuga. It is large, fafe from all winds, and has 4 fathoms water at its entrance, deepening gradually to 7 or . The bar lies in lat. 30. 15. N. and long. 87. 14 W. The town of Penfacola, the capital of Weft-Florida, lies along the beach of the bay, is of an oblong form; about a mile in length, and a quarter of a mile in breadth. It contains feveral hundred habitations; and many of the public buildings and houses are fpacious and elegant. The governor's palace is a large ftone building, ornamented with a tower, built by the

* This defeription applies to this town as it flood before its division, in 1796.

Spaniards.

Spaniards. fort, called exports fro fkins, logv dollars, an fion of the The aver: years, from The town dered to th 1781, and vince. E the largeft facola Ba miles up, a PENTE pelago of It was dif 22,1768, ing the d leagues d which is i E. long. f. PENUC feparated Tlafcala, PEPCH land, on 1 of Chaleu of the pro is alfo cal S. W. of PEPIN of the riv the river lat. 44. below the PEPPI chufetts, river, and co. It j ward, and ton. It contains PEPPI York co. fide of S: which fe the fout! S. W. of ton. It contains PEPSI Carlifle, biac, on PEPSI fide of C biac Poin

of Eaft 1

be of In-Town, on r. They the ifland, soo years. Falls, and land. See rmer war, but at the war, the any perfon he head of , included the river t 12 miles ddle of the nfider that fifh as far Penobleot ginal right, e, and they

nd Town. hore of the east of Port W. of the large, fafe homs water radually to 30. 15. N. Florida, lies is of an oblength, and h. It conations; and s and houses The goveruilding, oruilt by the

this town as 796.

Spaniards.

Spaniards. It is defended by a finall fort, called St. Mary de Galve. The exports from this town, confifting of fkins, logwood, dying-ftuff and filver dollars, amounted, while in the pofferfion of the Britifh, to £63,000 annually. The average value of imports, for 3 years, from Great. Britain, was £97,000. The town and fort of Penfacola furrendered to the arms of Spain, in the year 1781, and with them the whole province. Efcambria river, or Shambe, is the largeft fream which falls into Penfacola Bay. It admits fhallops fome miles up, and boats upwards of 50 miles.

PENTECOST, an ifland in the Archipelage of the Great Cyclades, which fee. It was different by Bougainville, May 22,1768, and named from the day, being the day of Pentecoft. It is two leagues diffant from Aurora Ifland, which is in 15.8. S. lat. and 165.58. E. long. from Paris.

PENUCO, a province of Mexico; feparated from that of Angelos, or Tlafcala, on the N. by Tufpa river.

PEPCHIDIACHICH, a point or head land, on the S. fhore of the Great Bay of Chaleurs, near the N. E. extremity of the province of New-Brunfwick. It is alfo called Pepchidjehi, and lies W. S. W. of Port David.

PEPIN, a lake, or rather a dilatation of the river Miffifippi, where it receives the river Chippeway from the N. E. in lat. 44. 5. N. and long. 93. 42. W. below the Falls of St. Anthony.

PEPPERELL, a township of Massachusetts, on the E. branch of Nashaway river, and on the N. line of Middlesex co. It joins Groton on the south-eastward, and is 40 miles N. by W. of Boston. It was incorporated in 1753, and contains 1132 inhabitants.

PEFPERELBOROUGH, a township in York co. District of Maine, on the N.E. fide of Saco river, near the mouth, and which separates it from Biddeford to the southward. It is about 12 miles S. W. of Portland, and 109 N. of Boston. It was incorporated in 1772, and contains 1,352 inhabitants.

PEPSIGUIACHE, now called New-Carlifle, is about 3 leagues from Pafpibiac, on the north fide of Chaleur Bay, PEPSIGUIACH Point, on the northern fide of Chaleur Bay, now called Pafpibiac Point, is about 3 leagues W. N. W. of East Nouville. It is a barren plain

that is nearly a league in length. A very extensive fishery is carried on here, for fuch a small place.

PEPY's Islands, the fame with Falkland Iflands. Pepy's Ifland, deferibed in Commodore Anfon's Voyage, lies in lat. 47. S. 8 lengues E. of Cape Blanco, on the coaft of Patagonia, and was difcovered by Capt. Cowley in 1680, who reprefents it to be commodious for taking in wood and water, and provided with a harbour capable of holding 1000 fail of fhips; abounding with fowls, and promifing great plenty of fifh.

PEQUANACK, a township of Morris co. New Jersey; perhaps the same an in some maps is called *Pegunnock*, which is separated from Bergen co. northward by Pegunnock river.

PSQUANNOCK Point and River. The river is a finall fiream which runs fouthward through the towns of Huntington and Stratford, in Fairfield co. Connecticut, and empties into a bay in the Sound where veffels may anchor. The point forms the weftern extremity of the bay near which are fome rocks; from thence the outer bar extends N. by N. E. The point is 5 miles S. W. of Stratford river.

PERAMUS, or Perames, in Bergen co. New Jerfey, lies on the point of land formed by the branches of Saddle river, a north water of Paflinik; about 18 miles northward of Bergen, 10 weft of Tappan, and 21 N. W. by N. of New-York city.

PERCEE, l'Isle, a finall but remarkable island on the weft fide of the Gulf of St. Lawrence, being a perpendicular rock, pierced with two natural arches, through which the fea flows. One of thefe arches is fufficiently high to admit a large boat to pais freely through it. It is 15 miles fouth of Cape Gaspee. It is afferted that it was formerly joined to Mount Joli, which lies opposite to it on the continent.

PERCIPANY, a village in Morris co. New-Jerfey, fituated on a branch of Paffaik river, and 6 miles N. of Morriftown.

PERCY, an extensive township in Grafton co. New-Hampshire, watered by the feveral branches of Upper Amonoosuck river, bounded welt by Northumberland, on Connecticut river. It was incorporated in 1774, and contains only 48 inhabitants.

PERDIDO, a river and bay on the coaft

of Weft-Florida. The mouth of the river is about 10 leagues caltward of Mobile Point, and 4 weftward of the bar of Peníacola. The entrance is narrow, with a bar of fix feet, but afterwards it widens confiderably. This was formerly the boundary between Florida and Louifiana, dividing the French and Spanish dominions! The river stretches in one place north-east, where it goes within a mile of the great lagoon west of the entrance of Peníacola harbour.

PERES Island, or Conflantine Peres, on the coaft of Chili, S. America. It is opposite to Port Coral. On this island is a fort called Mansera, and on the back of the island there is an entrance for boats into the harbour of Baldivia.

PERICA, three islands in the bay of Panama, S. America; which give shelter to ships out of the command of the rown of Panama.

PERITAS Iflands, on the Spanish Main, coast of S. America, 3 leagues westward of Cumana Bay.

PERKINS, Port, lies on the S. W. of Wathington's Ifle, on the N. W. coaft of N. America. Set Magee's Sound.

PERKIOMY, a township of Pennsylvania, in Montgomery co.

PERLICAN, Old, an indifferent fhip road with rocky ground on the E. coaft of Newfoundland Ifland, 2 leagues S. W. by S. of Break Heart Point. Sherwick is the name of its N. point.

PERLICAN, New, a noted harbour on the E. coast of Newfoundland Island, 8-leagues W. S. W. of Old Perlican, and 5 leagues from Random Head. It has a wide and fafe entrance, and ships may ride in it landlocked from all winds in from 10 to 5 fathoms water.

PERNAMBUCO, a captainfhip in the northern division of Brazil, whole chief town is Olinda.

PERNAMBUCO, or Phernambuce, otherwife called Panambuce, a place of confiderabie trade on the E. coaft of Brazil, having a bay or harbour of the fame name; fituated between Paraiba on the N. and Cape St. Augustine on the S. in lat. 8. S. and long. 35. W. Provisions and other articles are brought hither from Para, and from hence great quantities of tobacco are fent off to Europe.

PERNAMEUCO, a river on the coaft of Brazil. S. America, fouthward of Tamerica Island. It is blocked up with fand; and ships enter it from the northward, at the entrance of the Receif harbour, 3 leagues from it. S. lat. 8. 30. W. long. 35. 7.

W. long. 35. 7. PERPETUA, *Cape*, on the north-weft coaft of N. America. N. lat. 44. 6. W. long. 124. 8. Variation of the compais in the year 1779, 17. 50. E.

PERQUIMONS, a co. of Edenton diftrict, N. Carolina, bounded weft by Chowan co. and E. by Pafquotank, from which laft it is feparated by the river Pafquotank, a water of Albemarle Sound. It contains 5,440 inhabitants, of whom 1,878 are flaves.

PERSON, a new co, in Hillfborough diftriæ, N, Carolina. The court-houle, where a poft-office is kept, is 26 miles N. of Hillfborough, and 34 E. of Cafwell New Court-Houfe.

PERTH-AMBOY, a city of New-Jerfey, pleafantly fituated in Middlefex co. at the head of Rariton Bay, and stands on a neck of land included between Rariton river and Arthur Kull Sound, Its fcite is high and healthy. It lies open to Sandy-Hook, and has one of the beft harbours on the continent. Veffels from fea may enter it in one tide, in almost any weather. It is a port of entry and poft town; but although it is admirably fituated for trade, and the legiflature has given every encouragement to induce merchants to fettle here, it is far from being in a flourishing state. It contains about 60 houfes, and carries on a small trade to the W. Indies. Its exports for a year, ending 30th Sept. 1794, were to the value of 58,159 dolls. It is 35 miles fouth-weft of New-York, and 74 north-east of Philadelphia. N. lat. 40. 35. W. long. 74. 50.

PERU, a new township of New-York, in Clinton co. on the west fide of Lake Champlain. It was taken from the towns of Plattsburg and Willsburg, and incorporated in 1792. It is an excellent tract of land, and settling fast. In 1796, there were, of the inhabitants, 120 qualified electors.

PERU, a diftrict of S. America, about 1800 miles in length, and about 500 in breadth; bounded W. by the South Pacific Ocean; E. by the Cordillera de los Andes, or Mountains of Andes, which feparate it from the country of Amazonia and Paraguay; N. by Terra Firma, from which it is divided by the equator; and the 25th degree of S. latitude feparates it from Chili and La Plata

eccif har-

orth-weft it. 44. 6. on of the 50. E. enton difweft by ank, from the river Albemarle habitants,

lfborough art-houfe, 26 miles . of Caf-

New-Jerdlefex co. und ftands een Rariund. Its lies open f the beft fiels from in almost entry and idmirably egiflature nt to init is far state. It carries on Its expt. 1794, lls. It is ork, and N. lat.

w-York, of Lake from the Villfburg, is an exling faft. abitants,

ica, about ut soo in South Padillera de of Andes, ountry of by Terra led by the ree of S. ili and La Plata PER

Plata on the S. It lies between 60 and 81 W. long, and is fubdivided into the provinces of Quito, Lima, and Los, Charcos. The chief towns are Quito, Payta, Lima, Cuíco, Potofi, and Porco. From the fituation of this country, which is within the torrid zone, it is natural to fuppofe that it would be almost uninhabitable; but the Andes Mountains being on the one fide, and the South Sea on the other, it is not fo hot as tropical countries in general are; and in fome parts it is difagreeably cold. In one part, are mountains of a ftupendous height and magnitude, having their fummits covered with fnow; on the other, volcanoes flaming within, while their fummits, chafms and apertures are involved in ice. The plains are temperate the beaches and vallies hot; and laftly, according to the dilpofition of the country, its high or low fi-tuation, we find all the variety of gradations of temperature between the two extremes of heat and cold. It is remarkable, that in fome places it never rains, which defect is fupplied by a dew that falls every night, and fufficiently refreshes the vegetable creation; but in Quito they have prodigious rains, attended by dreadful ftorms of thunder and lightning. In the inland parts of Peru, and by the banks of the rivers, the foil is ufually very fertile; but along the fea coaft, it is a barren fand. Vaft numbers of cattle were imported by the Spaniards into Peru, when they took poffeffion of that country; thefe are now fo increased, that they run wild and are hunted like game. This country produces fruits peculiar to the climate and most of those in Europe. The culture of maize, of pimento and of cotton, which was found established there, has not been neglected; and that of wheat, barley, caffava, potatoes, fugar, and of the olive and vine is attended to. The goat has thriven very well; but the fheep have degenerated, and their wool is become extremely coarle. In the northern parts of Peru are leveral gold mines; but those of filver are found all over the country, particularly in the neighbourhood of Potofi. Nature never afforded to the avidity of mankind, in any country on the globe, fuch rich mines as those of Potofi. These famous mines were accidentally discovered in the year 1545, in this

manner : An Indian, named Hualpa, one day following some deer, which made directly up the hill of Potofi, came to a fteep craggy part of the hill, and the better to enable him to climb up, laid hold of a fhrub, which came up by the roots, and laid open a mais of filver ore. He for some time kept it a fecret, but afterward revealed it to his friend Guanca, who, because he would not difcover to him the method of refining it, acquainted the Spaniard his mafter, named Valaroel, with the difcovery. Valaroel registered the mine in 1545; and from that time till 1638 thefe mines of Potofi had yielded :95,619,000 pieces of eight, which is about 4,255,000 pieces a year. Potofi is about 20 or 25 leagues from the city of La Plata. The hill, and also the country for a confiderable diftance round, is quite barren and defart, and produces neither tree, plant nor herb, fo that the inhabitants of Potofi, which is fituated at the foot of the hill, on the fouth fide, are obliged to procure all the neceffaries of life from Peru. Thefe mines begin to decrease, and others rife in reputation. It is impoffible to afcertain with any degree of precifion the number of inhabitants in Peru. The city of Lima is faid to contain 54,000; Guagaquill, 20,000; Potofi, 2 5,000; LaPas, 20,000; and Cufco, 26,000. Among all the inhabitants of Peru, pride and lazineis are faid to be the most predominant paffions. Avarice may likewife be attributed to fome of them with a great deal of propriety. There is very little commerce in this fine country, except in the cities and large towns, which are defcribed under their respective names. The chief manufactures are carried on by the Indians; these confit chiefly of leather, woollen and cotton fluffs, and earthen ware; in the fabrication of which, they are faid to be peculiarly ingenious. The Indians and Negroes are forbidden, under the fevereft penalties, to intermarry; for division between thefe two claffes, is the greateft inftrument, in which the Spaniards truft for the prefervation of the colonies. Peru is governed by a viceroy, who is abfolute; but it being impoffible for him to fuperintend the whole extent of his government, he delegates a part of his authority to the feveral audiences and courts, established at different places throughout

throughout his territories. At Lima ere is a treatury court for receiving a fifth of the mines, and certain takes paid by the Indians, which belong to the king of Spain. There are certain waters in this country, which in their courfe turn into flone; and fountains of liquid matter, called coppey, refembling pitch and tar, and used by feamen for the fame purpole. On the coast of Guagaquill and Guatimala are found a certain fpecies of fnails, which yield the purple dye to celebrated by the ancients, and which the moderns have ppofed to have been loft. The fhell that contains them is fixed to rocks. watered by the fear It is of the fize of a large nut. Various methods are ufed to extract the purple matter from the animal. There is no colour that can be compared to this, either in luftre or permanence. Here is also found a new fubftance, called the Platina, and which may be confidered as an eighth metal. In its native flate it is mixed with gold and iron, and this at first gave rife to a fufpicion that it was nothing more than a combination of these two metals; but late experiments of chymifts fully prove, that it is a pure and fimple metal, with properties peculiar to itfelf. It cannot be affected by any fimple acid, or by any known folvent, except the aqua regia; it will not tarnish in the air, neither will it ruft; it unites to the fixedness of gold, and to the property it has of not being furceptible of deftruction, a hardness almost equal to that of iron, and a much greater difficulty of fution. It is of an intermediate colour, between that of iron and filver; it can be forged and extended into thin plates ; and when diffolved in aqua regia, it may be made to affume, by precipitation, an infinite diverfity of colours; and Count Milby has fucceeded in varying these precipitates so much, that he has a picture painted, in the colouring of which there is fcarce any thing but platina made use of. Upon the whole, from confidering the advantages of the platina, we cannot but conclude that this metal deferves, at least, from its superiority to all others, to share the title of king of metals, of which gold has to long been in poffeffion. The Peruvian bark, fo famous at prefent for curing intermittent fevers, is likewile found here. The tree from in the narroweft part of the Strait hotuqui guolida

PER

PET

which it is taken grows upon the flope of mountains, and is about the fize of a common cherry tree. It is diffinguished into three kinds; the red, yellow, and the white; but the red is found to be the best and most efficacious, The Jefuits carried this bark to Rome as early as 1639; but the natives are fuppofed to have been acquainted with its medicinal qualities many ages before.

PERUVIANS, the aboriginal inhabitants of Peru, in S. America, who were the most civilized of any Indians on the continent. 1013.001

PETAGUEL, a territory of S. America, in Brafil, bounded N. by Deleg E. by the S. Atlantic Ocean; S. by the captainfhip of Rio Grande; and W. by Tupuy. It contains mines of filver. PETAPA, one of the plealantelt towns of Guatimala, in New-Spain. It is fituated at the western extremity of the valley of Mexico, 25 miles S. E. of Guatimala. There is a rich fugar plantation in its vicinity.

PETAWONTAKAS, an Indian nation formerly in alliance with the Hurons.

PETER's Bank, St. a large fishing ground off, the S. end of Newfoundland Ifland, and extends from Cape Race to St. Peter's Ifland, oppofite Placentia, St. Mary and Trepaffy Bays. It is 11 degrees of latitude in breadth on the W. fide. From St. Peter's Ifland it decreafes as it approaches Race Point. It lies W. of the Great Bank, and has on the S. at a confiderable diftance, Green and Whale Banks, which are among the fmalleft on the coaft. It has from 45 to to fathoms water on it. dista with

PETER's Bay, St, on the S. coaft of Cape Breton Ifland, having St, Peter's Ifland at its mouth.

PETER's Fort, St. on the Ifland of Martinico, in the Weft-Indies. N. lat. 14. 44. W. long. 61. 21.

PETER's Harbour, St. on the N. coaft of the island of St. John's, in the Gulf of St. Lawrence, about 8 leagues W. of East Point. Welt of it are Anguille Bay and Port Chimene.

PETER's Haven, St. on the E. coaft of Labrador, lies round the S. Epoint of Sadel Bay. N. lat. 56. 30. W. long. 601 42.00 oft of Latroise towne sen PETER's Ifland, a fmall ille on the W, coalt of St. John's Island, near to, and N. by W. of, Governor's Ifland, tween

ween Ne Ifland. PETER the fouth Ifland, lie of Fortun of, the S. lat. 46. 4 PETER in the W gin Gord PETER end of Sy a very cor the fifher PETER extremity ftands on broad, w St. Peter name, all is about loufe. greateft 1 Before th fiftery wi PETEI rence rive S. and E. plain, th fmaller, r Mafquine lake. T miles abo Kingfton PETEI lies on Su fax and I PETEI Labrado igand of name. PETEI the botto Its branc bafco. eaftern bi flood the ter, and 1 bar. PETER in Beauf PETE branches joins in I 94. 22. named P PETE Pennfyly. the flope the fize of is diffine red, yelhe red is fficacious, k to Rome natives are ted with its s before. al inhabitwho were ans on the

S. Ameri-Dele; E. S. by the and W. by f filver. It is fiity of the S. of Guaar planta-

ian nation Hurons. ge fifning troundland be Race to centia, St. t is 14 deon the W. nd it de-Point. It and has on ce, Green among the from 45 to

S. coaft of St. Peter's Ifland of S. N. lat.

the Qulf ues W, of Anguille

e E. coaft E point of W. long, ille on the

l, near to, r's Ifland, Strait hotween eween New-Brunfwick and St. John's

PET

Island. PETER's Island, St. or St. Pierre's, on the fouthern coaft of Newfoundland Island, lies S. S. W. of the S. E. point of Fortune Bay, and near to, and S. E. of, the S. point of Miquelon Island. N. Island, ac, W. Jong, Sc. 17.

lat. 46. 46. W. long, 56. 17. PETER's, St. one of the Virgin Ifles, in the Weff-Indics, dependent on Virgin Gorda.

PETER's, St. a harbour at the W. end of Sydney or Cape Breton Island, is a very commodious place for carrying on the fifthery.

PETER's, St. a town at the fouthern extremity of Cape Breton Ifland. It fands on an ifthmus about half a mile broad, which feparates the harbour of St. Peter from the great lake of that name, also caffed Lake Labrador. It is about to miles N. E. of Point Touloufe. To this harbour veffels of the greateft burden can come with fafety. Before the American revolution, a great fafhery was carried on here.

PETER, Lake St. a part of St Lawrence river, into which empty from the S. and E. Sorel river from Lake Champlain, the river St. Francis, and fome fmaller rivers, from the N. W. The Mafquinonge, Omachis, &c. enter the lake. The centre of the lake is 68 miles above Quebec, and 205 N. E. of Kingfton, at the mouth of Lake Ontario.

PETER's Mountain, in Pennfylvania, lies on Sulquehannah river, between Halifax and Harrifburg, in Dauphin co.

PETER'S, St. a river on the coaft of Labrador, about 4 leagues from the island of Bellille, in the traits of that same.

PETER, 5t. and St. Paul, a river at the bottom of the gulf of Campeachy. Its branches form an ifland, called Tabafco. The bar at the mouth of the eaftern branch admits finall veffels. At flood there is from 2% to 3 fathoms water, and very good anchorage within the bar.

PETER's, St. a parifh of S. Carolina, in Beanfort diffrict.

PETER's, St. one of the N. weftern branches of Millippi river, which it joins in lat. about 45, 6. N. and long. 94. 22. W. N. B. For other places named Peter or Peter's. See Pierre. PETERS, a township of Franklin co.

Pennfylvania.

429

PETERBOROUGH, a post-town in Hillfborough co. New Hampfhire. It was incorporated in 1760, and contains 861 inhabitants. It is 73 miles W. by S. of Portfmouth, 18 wefterly of Amherft, 16 E. of Keene, and 366 from Philadelphia. N. lat. 42. 51. W. long. 71. 52.

PETEREBURG, a township of New-York, in Rensielaer co. E. of the village of Troy, incorporated in 1793. In 1796 there were 512 of the inhabitants qualified electors.

PETERSBURG, a post-town of Pennfylvania, in York co. 2 miles north of the Maryland line. It contains a Roman Catholic church, and about 18 houfes. It is 25 miles fouth-weft of York-Town, 59 northerly of the Federal City, and 113 welt by fourth of Philadelphia. N. lat. 39. 42. 30. W. long. 77. 4. PETERSBURG, a fimall town of Kentucky, fituated in Woodford co. on the E. fide of Kentucky river, 19 miles W. S.W. of Lexington, and 15 fouth-foutheaft of Frankfort. It has a tobacco warehoufe, and a few dwelling-houfes. PETERSBURG, a post town of Virfituated in Dinwiddie co. on the foutheast bank of Appamatox river, just be-low the falls, about 25 miles fouth of Richmond. It contains about 300 houfes. built irregularly. The Free Mafon's Hall is a handfoine building; there are feveral tobacco warehouses, flores of dry goods, and fome few neat and commodicus dwelling-houfes. This town is a corporation, and comprehends the village of Blandford, in Prince George's co. and Powhatan in Chefterfield co. on the opposite fide of the river. It contains 2,828 inhabitants, including 1,265 flaves. The fituation of the town is low and rather unhealthy. From the infpector's books it appears, that on an average for the laft 10 years, the quantity of tobacco received here has confiderably exceeded 20,000 hhds. per annum; and for the last three years the quantity of flour made in this town and within an hundred yards of it, has exceeded 38,000 barrels; at other mills within a few miles, 16,000 barrels per annum; to this add the flour made at the feveral country mills, and brought to this place for fale, the whole quan-tity may fafely be flated to exceed 60,000 barrels per annum. The whole exports exports of this town, valued at the ufual peace prices, amount to 1,389,300 dolls. befides the value of peach and apple brandy, whifkey, &c. not included. The Indian princes, Pocahontas, the daughter of king Powhatan, from whom defcended the Randolph and Bowling families, formerly refided at this place. It is 80 miles W. by N. of Norfolk, 559. S. by W. of Alexandria, and 303 fouth-well by fouth of Philadelphia. N. lat. 37. 14. W. long. 78. 8.

PETERSBURG, a very flourishing post-town of Georgia, in Elbert co. in a pleasant and healthful fituation, on the point of land formed by the confluence of Broad with Savannah river. Several respectable merchants are settled in this town. It is 15 miles from Elberton, 20 N. by E. of Washington, 50 above Augusta, 73 N. of Louisville, and 836 from Philadelphia. N. lat. 33. 46. W. long. 81. 32.

PETERSHAM, a flourishing and pleafant township in Worcester co. Massachusetts, formerly called by the Indians *Nichewaug*; fitnated 28 miles N. W. of Worcester, and 66 W. of Boston. Swift river, a branch of Chickopee river, passes through this town. The soil is rich and fertile, and here are large and excellent orchards.

PETIT ANSE, a village on the north fide of the island of St. Domingo, 21 leagues fouth of Cape François.

PETITCODIAK, a river which falls into an arm of the Bay of Fundy, called Chegnecto Channel. The Indians have a communication from the head of it with St. John's river, by a portage acrofs to the head of Kennebecfius.

PETIT-GOUFRE, or the Little Whirlpool, in Miffifippi river, is 31 miles from Fort Rotalie, and 4 miles from Bayouk Pierre, or Stony river.

PETIT GUAVES, or Goave, a jurifdiction, town, and bay, on the N. coaft of the S. peninfula of the ifland of St. Domingo, and uear the head of the Bay or Bite of Leogane. The jurifdiction contains 5 parifhes, and is the unhealthieft place in the colony, the inhabitants being conflantly fubject to fevers, occafioned by the badneis of the waters. Its dependencies, however, are healthy, and are remarkable for the culture of coffee. Its exports from January 1, 1789, to December 31, of the fame year, were 27,090 lb. white fugar-655,187 lb. brown

fugar-807,865 lb. coffee-50,053 lb. cotton, and aro lb. indigo. The value of duties on exportation of the above, was 4,127 dollars 97 cents. The town lies on the E. fide of the bay, 21 leagues weftward of Grand Guave, and 141 W. by S. of Port-au-Prince. N. lat. 18. 27. W. long. from Paris, 75. 14. Some writers call the great bay, which is commonly called the Bay, Bight, or Bite of Leogane, by the name of Petit Guaves. PETIT PORT, on the W. fide of Newfoundland Island, towards the S. end; is about 51 leagues N. of Cape Ray, and one S. of Anguille Cape. N. lat. 47. 52. 30. W. long. 59. 15.

PETIT PORT, on the coaft of Peru, otherwife called *Portete*, or *Little Port*, lies a flort way northward of the equator, and about 5 leagues to the S. E. within the baylfrom Cape François to Cape Paífado on the S. by W. There is anchorage in 5 fathoms, and plenty of frefh water near the head land, which is high. It is neceffary to found, on account of the fand-banks, called the *Portetes*.

PETIT TERRE Island, near Defeada, in the West-Indies. N. lat. 36. 14. W. long. 61. 11.

PETITE RIVERE, a finall town in the French part of the ifland of St. Domingo, close to the Spanish division line, 14 leagues N. by N. W. of Varettes, and separated from it by the river Artibonite; 10 leagues E. by N. of St. Marc, and as far N. W. of Mirebalais. N. lat. 19. 8. W. long. from Paris, 74. 48.

74. 48. PETIT TROU, is on the north fide of the fouth peninfula of the island of St. Domingo, on the point of land which forms the east fide of the entrance into the Bay of Baradaires; $4\frac{1}{2}$ leagues weltward of Anse a Veau, and 19 easterly of Jeremie.

PETIT TROU, a fmall cove on the fouth fide of the ifland of St. Domingo, S. by W. of the mouth of Neybe river, and about 5 leagues N. E. of Beate Ifland. Small barks come to this place from St. Domingo city, to fetch the meat, lard, and fowls derived from the chafe.

PETTQUOTTING, a river of the N. W. Territory, which empties into Lake Erie, from the fouth, near Huron river.

PEYTONSBURG, the chief town of Halifax co. Virginia, having a courthouse

houfe and 5 which are o PHILADI land co. Ver Orwell. It PHILADE ly cultivated ed W. by D gomery; N which fepar S. and S. I which divid Jerfey. It and is divid the banks of is an excell which the f are fupplied delphia, its

43/. PHILADI Pennfylvani the governm fituated in th name, on th Delaware, 1 It lies in lat. 8. 45. W. f 120 miles fr the courfe of bout 55 or 6c tion. A 7. this city; 1 Trenton; a tons can go Delaware. Penn, the fi of the provi fettled by which arriv ing years, a ftant and re to fo great a a century, : the first perfe pean parenti tain 6,000 tants, in th ground plot lquare, abor two E. and part of the i ware and S miles in a ri ence. In th ment, it was

on both river for the conve gation, and

to,053 lb. The value he above, The town 1 leagues 1 r41 W. . lat. 18. r4. Some ch is comor Bite of Guaves. e of Newi S. end; lape Ray, M. lat.

of Peru, ittle Port, eequator, E. within Cape Pafis anchor- γ of frefh th is high. ccount of tetes. Defeada, . 16. 14-

town in f St. Dorifion line, Varettes, iver Arti-J. of St. lirebalais. om Paris,

orth fide of ind of St. nd which rance into gues wefteafterly of

ve on the Domingo, ybe river, Beate Iflthis place fetch the i from the

of the N. pties into ear Huron

f town of a courthoule PHI

house and g or 6 other houses, three of which are ordinaries or taverns. PHILADELPHIA, a township in Rutland co. Vermont, about 15 miles E. of Orwell. It contains 39 inhabitants. PHILADELPHIA, a populous and highly cultivated co. of Pennfylvania, bound-ed W. by Delaware co. N. W. by Montgomery; N. E. by Poquafin Creek, which feparates it from Buck's co. and S. and S. E. by the river Delaware, which divides it from the State of New-Jerfey. It contains about 89,600 acres, and is divided into 12 townships. On the banks of Schuylkill, in this county, is an excellent guarry of marble, from which the ftone-cutters of Philadelphia are fupplied. It contains, bendes Philadelphia, its capital, 11,871 inhabitants, of whom 114 are flaves.

431. PHILADELPHIA, the metropolis of Pennfylvania, and the prefent feat of the government of the United States, is fituated in the county to which it gives name, on the western bank of the river Delaware, which is here a mile broad. It lies in lat. 39. 56. 54. N. and long. 75. 8. 45. W. from London; diffant about 120 miles from the Atlantic Ocean, by the course of the bay and river, and about 55 or 60 in the fouth-eastward direction. A 74 gun fhip can come up to this city; floops go 35 miles farther to Trenton; and boats that carry 8 or 9 tons can go 100 miles farther up the Delaware. It was laid out by William Penn, the first proprietary and founder of the province, in the year 1683, and fettled by a colony from England, which arrived from that and the preceding years, and was increafed by a conftant and regular influx of foreigners, to fo great a degree, that in lefs than a century, and within the lifetime of the first perfon born within it of European parents, it was computed to contain 6,000 houfes, and 40,000 inhabitants, in the city and fuburbs. The ground plot of the city is an oblong fquare, about one mile N. and S. and two E. and W. lying in the narroweft part of the ifthmus between the Delaware and Schuylkill rivers, about s miles in a right line above their confluence. In the beginning of this fettlement, it was expected that the fronts on both rivers would be first improved for the convenience of trade and navigation, and that the buildings would

extend gradually in the rear of each, until they would meet and form one town, extending from E. to W. But it was foon found that the Delaware front was alone fufficient for quays and landing-places. The buildings now occupy a fpace not exceeding 3 miles in length from N. to S. and in the most extended part do not reach a mile from the Delaware. The city is interfected by a great number of ftreets, croffing each other at right angles. Of these there were originally 9, which extended from the Delaware to the Schuylkill; thefe were croffed by 23, running N. and S. The E. and W. Areets, except High freet, are named after the trees first found by the colony on their arrival in the country, viz. Vine, Saffafras, Mulberry, Chemut, Walnut, Spruce, Pine, and Cedar; which laft is the fouthern boundary of the city. The freets running N. and S. receive their names from their numerical order, beginning at Delaware river; Front is Firft, then Second, and foon to Thirteenth ftreet, whence the numerical order ceases from Delaware front, and begins at Schuylkill in the fame order, as Firft, Second, &c. to the Eight-ftreet, between which and Thirteenth-freet, is Broadftreet, fo named from its being the wideft in the city. The number of fquares in the original plan was 184; but as feveral of the fquares have lately been interfected by new fireets, their number now amounts to 304; and feveral of these are again interfected by lanes and alleys. Broad-street is III feet wide; High-freet 100; Mulberry, 60; and the other freets in the original plan 50 feet wide. Most of the city is well payed with neatfeot paths of brick, furnished with common fewers and gutters; io that the fireets are, in general, kept very clean and neat. Befides the freets already mentioned, there are feveral others not laid down in the original plan, as Water, Dock, Cherry, Penn, Prune, &c. Water-ftreet is only so feet wide, and extends from the Northern Liberties acrofs the Dock, to Pine-ftreet, parallel to the courfe of the Delaware, and between it and Frontftreet. The fpace occupied by it was intended in the original plan to ferve only as a cart-way to accommodate the wharves and ftores, fo that the river thould be open to the view from Frontfreet.

firet. It is now built with lofty houfes except a very few vacancies here and there) throughout the whole front, and commodious wharves are extended into the river, at which the largest ships that use the port can lie in fafety, to receive and discharge their cargoes; and are defended from the ice, in winter, by the piers, made of logs, extending into the river, funk with stone, and filled with earth, fo as to be equally firm with the main land. Dock-fireet was formerly a fwamp, with a finall ffream running through the middle of it. It is from 90 to 100 feet wide, and winds north westward in a ferpentine track, through feveral ftreets. It is slanted on each fide with a row of Lombardy poplars, and promifes to be one of the pleafantes ftreets in the city. No lefs than 662 lamps of two branches each, difpoted at convenient diffances, in all parts of the city, are lighted every night, and are estimated to confume annually, nearly 9,000 gallons of oil. The houles in the city and fuburbs, are generally of brick, three ftories high, in a plain neat ftyle, without much dif-play of ornament. The general height of the ground on which the city flands, is nearly 40 feet above the Delaware; but fome of the fireets are confiderably lower, particularly Water freet ; feve-ral flores in which have fometimes received much damage when the river happened to be raifed by a high flood, and a ftrong fouth-east wind. Here are 27 places of public worthip, viz. 5 for Friends or Quakers, 6 for the Prefbyterians and Seceders, 3 for Episcopalians, g for Roman Catholics, 2 for German Lutherans, 2 for Methodifts, 1 for German Calvinifts, 1 for Swedish Lutherans, which is the oldest church in town, 1 for the Moravians, 1 for Baptifts, 1 for Africans, and a Jewish fynagogue. The first Pretbyterian church is finished with a degree of elegance that would .do honour to any city in Europe. The roof is supported in front by fix pillars, finified in the Corinthian order; but as it frands in an obfcure place, on the fouth fide of Market-street, it is feen to difadvantage. The German Lutheran church, which was built not many years fince, was unfortunately buint in the winter of 1795. The new building, now nearly finished, is 108 feet by 48; and when completed will

be one of the handlomest churches in the United States. Mr. D. Taneberger, a member of the Society of the United Brethren, at Letiz, a man of extraordinary mechanical genius, completed and erected a large organ for this church, but it received much injury when the roof and infide of the building were confumed, before the pipes could be difengaged. Chrift Church flands on the weft fide of Second-fireet, between High and Mulberry fireets. It is an old Gothic ftructure, and is ornameneed with a handfome freeple, and furnished with a chime of bells. The fecond Prefbyterian church, at the corner of Mulberry and Third ftreets, is also ornamented with a handfome fteeple. The Epifcopalian churches are furnifhed each with an organ, as are the German, and two of the Roman Ca-tholic churches. The African church is a large, neat building. It is fup-plied with a negro clergyman, who has been lately ordained by the bifhop. They are of the Episcopalian order. The other public buildings are, a Statehoufe and offices, two city court houfes, a county court-house, an university, the philosophical society's hall, a public library, an hospital, dispensary, an almshouse, a gaol, three incorporated banks, two dramatic theatres, a medical theatre, a laboratory, an amphitheatre, 3 brick market houses, and one which is to be crected in Front-ftreet, in the Northern Liberties, a fish market, a house of correction, and a powder magazine which contains often upwards of 50,000 quarter cafks of gun-powder. The flate house flands on the S. fide of Chefnut-ftreet, between Fifth and Sixth freets, and was erected about the year 1753; and confidering the infancy of the colony, the architecture is much admired. The flate-house garden occupies a whole fquare; it is a fmall neat place, ornamented with feveral rows of trees and gravel walks, and inclosed by a high brick wall on three fides, and the state-house, &c. on the other, Pottersfield, formerly a public burying ground, is now converted into a public walk, and planted with rows of Lombardy poplars on each fide. When the trees are grown, and the ground levelled, it will be one of the most pleafant promenades in the vicinity. The legislature of the United States

States hold building in ftate house of the yard, the ftate-ho new court-h Philosophic: keeps his m philosophic collection of be found in cies of bird Opposite the Philadelphi to the bes Iquare. T ginated with corporated the collectic augmented: wards of 11 feum and 1 paratus.] week, exce who has an ing may he to great adv nished with ger, witho for any boc and perufe Those who read in, ma library, by for the ret moderate fi proprietors and each i amually, making ner is annexed of books, Efq. to the longing to markably pearance. a nich ove ftatue of D William B It is of wh Italy, and The publ fquare, for It is a holl built of fte the aparts as a preca the largeft ing of the

wirches in aneberger, he United extraordipleted and is church, when the ding were ald be difnds on the , between It is an irnameneed I furnished The fecond : corner of s, is alfo ne fteeple. s are furas are the loman Cacan church It is fupman, who the hifhop. lian order. ire, a Stateurt-houfes, iverfity, the a public liy, an almfated banks, edical theahitheatre, 3 ne which is et, in the market, a wder maupwards of the S. fide r Fifth and ed about the the infancy ure is much garden oct is a fmall with feveral walks, and vall on three &c. on the rly a public inverted into d with rows n each fide. wn, and the one of the in the vicif the United States

PHI

States hold their feffions in an elegant building in the N. W. corner of the flate house yard. In the N. E. corner of the yard, adjoining the left wing of the flate-house, is the town-hall or new court-house; S. of which is the Philosophical hall. Here Mr. Peal keeps his muleum, by permission of the philosophical fociety. It is the largest collection of natural curiofities that is to be found in America. In it are 400 fpecies of birds, fome living animals, &c. Opposite the Philosophical hall is the Philadelphia library : thefe add much to the beauty and grandeur of the Iquare. The Philadelphia library originated with Dr. Franklin, and was incorporated in 1742, fince which time the collection of books has been greatly augmented. At present, it contains upwards of 12,000 volumes; belides a mufeum and a valuable philosophical apparatus. It is open every day in the week, except Sunday; and any perfon who has an inclination or tafte for reading may here indulge or improve either to great advantage. The library is furnifhed with tables and feats; and a ftranger, without any introduction, may call for any book he wants, and fit down and perule it as long as he pleases. Those who prefer their chambers to read in, may receive books out of the library, by leaving a deposit, as fecurity for the return of them, and paying a moderate fum for the use of them. The proprietors amount to feveral hundreds, and each fubieriber pays ten shillings annually, for defraying expences and making new additions. To the library is annexed a rare and valuable collection of books, the bequeft of James Logan, Efq. to the public: The building belonging to the Library Company is remarkably elegant; and has a fine appearance. In front of the building, in a nich over the door; is a handfome statue of Dr. Franklin, the donation of William Bingham, Efq. to the company. It is of white marble, was executed in Italy, and is faid to have cost gool. The public gaol ftands in the next fquare fouth of the ftate-house yard. It is a hollow fquare, 100 feet in front, built of ftone, three ftories high. All the apartments are arched with ftone, as a precaution against fire; and it is the largest, strongest, and neatest building of the kind in the United States.

To the goal is annexed a work-houfe, with yards to keep the fexes apart, and criminals from the debtors. There are alfo apartments lately added for the folitary confinement of criminals. The whole is fecurely inclosed by ftone walls. The market-houfe, in High-fireet, is perhaps exceeded by none in the world, in the abundance, neatness and variety of provisions, which are exposed for fale every Wednefday and Saturday. Butchers' meat and vegetables may be had any other day, except Sunday. It extends from Front to Fourth-ftreet, and is supported by 300 pillars. The new theatre in Chefnut-ftreet, near the state-house, is large and convenient. It was finished in 1793. Further weft, is a fpacious building, intended for the accommodation of the Prefident of the United States, but is not occupied by him! Opposite to the new theatre is the amphitheatre; wherein feats of horsemanship are, at certain seafons, performed with great dexterity, for the amulement of the citizens. It is a large commodious building. The univerfity ftands on the weft fide of Fourthfreet, between High and Mulberry ftreets. It was formed by the union of two literary institutions, which had previoufly exifted a confiderable time in Philadelphia, one defignated by the above name; the other, by that of the college, academy and charitable fchools of Philadelphia. They now conftitute a very respectable seminary! It was incorporated in 1791. The philosophical apparatus; which was before very complete, has been lately increafed to the value of feveral hundred pounds. The funds of the university produce annually, a revenue of about 2,365l. The aggregate number of fludents, in the feveral fchools, is, on an average, about 510. And the number usually admitted to degrees in each year, about 25. The Friends' academy and Young Ladies' academy, are also respectable and uleful establishments. The chief literary and humane focieties are the American philosophical fociety; the college of phylicians ; the fociety for promoting political inquiries; the Pennfylvania hospital; the Philadelphia dispenfary; the Pennfylvania fociety for the abolition of flavery; the fociety for alleviating the mileries of prilons; the Pennfylyania fociety for the encourage-

Ee

ment

ment of manufactures and ufeful arts ; the Philadelphia fociety for the information and affifance of emigrants, and two other focieties of the fame kind; one for the relief of German, and another for the relief of Irifh emigrants; and an humane, an agricultural, marine, and various charitable locieties. Here is a Grand Lodge of Free and Accepted Mafons, and 8 fubordinate lodges. The Infurance Company of N. America, lately eftablished here, is in high repute, and infure houfes, goods, &c. against fire, on very reasonable terms. Few cities in the world of the fame population and riches as Philadelphia, are better provided with ufeful institutions, both public and private. There are also a sufficient number of academies for the inftruction of both fexes. Almost every religious fociety has one or more schools under its immediate direction, where children belonging to the fociety are taught to read and write, and are furnished with books and flationary articles. In the city and fuburbs are to rope-walks which manufacture about Soo tons of hemp annually-13 breweries, which are faid to confume 50,000 bufhels of barley yearly-6 fugar-houles-7 hair-powder manufactories in and about town-2 rum diffilleries, and one rectifying diffillery -three card manufactories. The other manufactories are, 15 for earthen-ware -6 for chocolate-4 for multard-3 for cut-nails, and one for patent-nailsone for steel-one for aqua-fortis-one for fal-ammoniac, and glauber-falts-one for oil colours-11 for brushes-2 for buttons-one for Morocco leather, and one for parchment; befides gun-makers, copper-finiths, hatters, tin plateworkers, coach-makers, cabinet-makers, and a variety of others. The public mint, at which the national money is coined, is in this city. The great number of paper mills in the State enable the printers to carry on their buline's more extensively than is done in any other place of America. There are 31 printing-offices in this city; four of these publish each a daily gazette; two others publish gazettes twice a week; one of these is in the French language ; belides two weckly papers, one of which is in the German language. The other offices are employed in printing books, pamphlets, &c. The catalogue

рнт

434

PHI

of books for fale in this city, contains upwards of 300 fets of Philadelphia editions, befides a greater variety of maps and charts than is to be found any where elfe in America. The pleafure-carriages within the city and liberties, according to enumeration, are as follow, viz. two wheeled carriages, 553; light waggons, 80; coaches, 137; phaetons, 22; chariots, 35; and coachees, 33; the whole amounting to 307 four-wheeled carriages. The roads are good, and becoming better; ftage-coaches perform the journey from this city to Lancatter in 11 hours, on the new turnpike road : the diffance is 58 miles. This city is governed by a mayor, recorder, 15 aldermen, and 30 common council-men; according to its prefent charter, granted in the year 1789. The mayor, recorder, 8 aldermen, and 16 common council men make a quorum to transact busines; they have full power to conftitute and ordain laws and ordinances for the governing of the city; the mayor, recorder, and aldermen are juftices of the peace, and justices of over and terminer. They hold a court four times a year, to take cognizance of all crimes and mildemeanors committed within the city; two aldermen, appointed by the mayor and recorder, hold a court on the forenoon of Monday and Thursday of every week, to judge of all matters which are cognizable before a justice of the peace. The trade of Pennfylvania is principally carried on from this city, and there are few commercial ports in the world, where thips from Philadelphia may not be found in fome feafon of the year. The number of veffels which entered this port in 1786, was 910; in 1787, 870; in 1788, 851; in 1793, 1,414, of which 477 were fhips; in 1793, 1,620, viz. fhips, 158; barks and inows, 26; brigs, 450; schooners, 506; floops, 480. Clearances, 1,789. It is not mentioned how many of these were coafting veffels. The number of veffels built in 1795, was 31, of which 23 were fhips and brigs. In the year 1792, Philadelphia fhipped 420,000 barrels of flour and middlings; in 1794, 300,751. The value of the exports from the State in the year ending September 30, 1791, was 3,436,092 dollars 58 cents; 1792, 3,820,662 dollars ; 1793, 6,958,836 dollars ; 1794, 6.643,092 dollars ; 1795, 11,518,260 11,518,260 autumn of 1 fpring follo merce of P months. 1 fioned fome exportation been carried thence to H The environ fant, and fit ward are K on Delawar Germantow with 2 Ger fort, another 7 miles, be the fouth is rough, abo Schuylkill, botanical g In the weft, of ground h a public bo to a lift p deaths in t of Philadel August 1,1 births amou to 1,497. phia was v the yellow common via and in that 5000 inhabi of a commit the citizens in diminif weeks after the trade of manner inc neffes. It humane at in this city 4000 crim Philadelphi September, ber, 1790, death. In in this city ing; and t tants may Philadelphi Paffamaque most part o States; 34 fouth-welt of New-Yo more ; 278

022.9

y, contains Philadelphia variety of o be found rica. The he city and numeration. rheeled car-80; coachariots, 35; amounting ages. The ing better; ourney from hours, on : diftance is verned by a sen, and 30 ording to its e year 1780. lermen, and ke a quorum re full power s and ordihe city; the men are jufces of over L court four izance of all committed en, appointder, hold a Ionday and judge of all ple before a e trade of carried on re few comwhere fhips be found in The number his port in 70; in 1788, ch 477 were thips, 158; rigs, 450 ; 80. Clearntioned how ting veffels. It in 1795, e fhips and Philadelphia f flour and 751. The he State in D, 1791, was its ; 1792, 6,958,836 llars ; 1795, 11,518,260

PHI

11,518,260 dollars. The fickness in the autumn of 1793, and the embargo in the fpring following, interrupted the commerce of Philadelphia for nearly five months. The existing war has occafioned fome extraordinary articles in the exportation of late; coffee, &c. have been carried to Philadelphia, and from thence to Hamburg, as neutral ports. The environs of the city are very pleafant, and finely cultivated. In the northward are Kenfington, near the fuburbs on Delaware, noted for thip-building; Germantown, a populous, neat village with 2 German churches; and Frankfort, another pretty village, both within 7 miles, befides many country feats. In the fouth is Derby, a finall pleafant borough, about 7 miles diftant; and, on Schuylkill, 4 miles from the city, the botanical garden of Meffrs, Bartrams. In the weft, on the fame river, 18 acres of ground have been lately defined for a public botanical garden. According to a lift published of the births and deaths in the feveral religious focieties of Philadelphia, it appears that from August 1, 1792, to August 1, 1793, the births amounted to 2, 511, and the deaths to 1,497. In the year 1793, Philadelphia was vifited with a fevere fcourge, the yellow fever, which raged with uncommon violence for above 3 months, and in that fhort fpace fwept off nearly 5000 inhabitants. The humane efforts of a committee of health, appointed by the citizens, were highly instrumental in diminishing the calamity. A few weeks after this diforder ceafed to rage, the trade of the city was reftored in a manner incredible to any but eye-witneffes. It is an honourable proof of the humane attention paid to the prifoners in this city that of 4060 debtors, and 4000 criminals, who were confined in Philadelphia goal between the 28th of September, 1780, and the 5th of September, 1790, only twelve died a natural death. In 1794, there were 9000 houses in this city, and 400 which were building; and the prefent number of inhabitants may be effimated at about 55,000. Philadelphia is 728 miles fouth-weft of Paffamaquoddy, which is the eaflernmost part of the fea-coast of the United States ; 347 fouth-welt of Bofton ; 222 fouth-welt of Hartford ; 95 fouth-welt of New-York; 102 north-east of Baltimore ; 278 north-easterly of Richmond ; 110

144 north-easterly of Washington's city and 945 north-east by north of Savannah in Georgia. See *Pennfylvania*, for an account of several other particulars relating to this city.

PHILIP, a large island in Lake Superior, in the territory of the United States. It lies towards the fouth fide of the lake, and fouth-eaft of Itle Royal.

PHILIP's, St. a parish of S. Carolina, fituated in Charleftown district.

PHILIP, St. a fort which commands the entrance of Maranhao harbour, on the coaft of Brazil.

PHILIP, St. a point within the harbour of Port-Royal, S. Carolina.

PHILIPPEAU, an ifland on the north fide of Lake Superior ; N. of HeRoyal.

PHILIPPEAU, a bay on the north fhore of the gulf of St. Lawrence, near the Straits of Bellifle, and partly formed by iflands which project fouthward on its eaft part, and extend towards the weft. The eaft part of the bay lies in lat. 31. 20. north, and long, 35. 40. weft. PHILIPPINA, 3 finall town of the province of Guatzmala, in New-Spain, fituated on a bay of the N. Pacifie Oceans N. lat. 12. 50. weft long, 91. 305

PHILIPSBURG, a town of New-Jerfey, fituated in Suffex co. on the eaft bank of Delaware river, oppofite to Eafton in Pennfylvania. It is 41 miles north-weft of Trenton.

PHILLIPSBURGH, or Philipflown, township of New-York, in Dutchess co. on the east fide of Hudson's river, 28 miles above New-York, near the fouth end of Tappen Bay. It contains 2,079 inhabitants, including 25 flaves. In 1796, there were 347 of the inhabitants electors. In this township is a filver mine, which yields virgin filver.

PHILLIPS' Academy. See Andwer and Exeter.

PHILOPOLIS, a fettlement in Luzerne co. Pennfylvania, 12 or 14 miles weftward of Mount Ararat, and at the head of the weftern branch of Tunkhanock Creek, about 45 miles fouth-east of Athens, or Tioga Point. N. lat. 47. 40. weft long. 75. 33.

PIANKATUNK, a finall river of Virginia, which empties eaftward into Chefapeak Bay, opposite Gwin's Island. It is navigable 8 miles for finall crait.

PIANKASHAWS, or Pyankishas, Vermillions and Mascontins, are tribes of Indians in the N. W. Territory, who E e 2 refide refide on the Wabafh and its branches, and Illinois river. These with the Kickapoos, Mufquitons and Quiatauons, could together furnish about 2000 warriors, 20 years ago.

PIARA, on the coaft of S. America, lies 13 or 14 leagus from Payta, in lat. 7. N. and is the first town of any note. A river which washes it, falls into the bay of Chiroper 3 but as it abounds with shoals, it is little frequented.

PIC, River du, empties into Lake Suerior, in lat. 48. 36. 31. and long. 89. 41. 6. The Grand Portage is in lat. 48. 41. 6.

PIC DE L'ETOIL, le, or Pic de l'Alwerdi, as it is named in Bougainville's map, a fmall high ifland, fhaped like a fugar-loaf, lying a little to the northward, and in fight of Aurora Iifland; difcovered by the fore-named navigator in May 1768.

PICA, a harbour on the coaft of Peru, where there is high and fteep land; is leagues N, of Lora river, and 5 fouth of Tarapaca, or as it is called by British feamen, *Carapoucha*.

PICARA, a large province of S. America, in New-Granada; bounded on the E, by the Andes.

PICAWEE, Indian Towns in the N.W. Territory, on Great Miami river, 75 miles from it's mouth, where it is only 30 yards broad, although navigable for loaded batteaux 50 miles higher.

PICKERSCILL's Cove, is within Chriftmas Sound, on the fouth coaft of Terra del Fuego, at the fouthern extremity of S. America.

PICKERSGILL'S Ifland, is off Cape Dilappointment, in S. Georgia, in the S. Atlantic Ocean. S. lat. 54. 42. W. long. 36. 58.

PICKERSVILLE, the chief town of Washington District, in S. Carolina. PICOLATA, a fort on the river St. John, in East-Florida, 27 miles from St. Augustine, and 3 from Poopora Fort.

PICOLET Point, on the north fide of the illand of St. Domingo, forms the W. boundary of the bay which fets up to Cape Francois. In time of war, fhips have often been taken under the cannon of Picolet.

PICOSA, or Pifana, mountains on the coaft of Peru, which ferve to direct mariners. They are high hills within land, extending about 7 leagues, between Colanche river, and Solango

Iflands; and lie fouthward of the equator.

PICTOU, a fmall ifle, river, bay, and fettlement in the N. E. part of the province of Nova-Scotia, and on the fouthern fide of the Straits of Northumberland, at the fouthern extremity of the Gulf of St. Lawrence. The ifland lies in the narroweft part of the ftrait, a little way north-weft of the mouth of the river of its name ; 8 miles fouth of Bear Cove in the island of St. John's, and 58 easterly of the mouth of Bay Verte. The bay or harbour of this name feems to be of confiderable extent. East river, which falls into Pictou harbour, fupplies the country with coals, from the mines on its banks; the ftreams of lefs note which empty into the bay, are St. Mary's, Antigonifh, Liverpool, Turket, Mulguideboit, and Siffibou rivers. The fettlement of Pictou is fertile, populous, and increasing in importance. A good road is cut, cleared, and bridged to Halifax, 68 miles diftant fouth by weft. This fettlement is now called Tinmouth; which fee.

PIERCE's Ifland. The main channel of Pifcataqua river, in New-Hampfhire, lies between Pierce's and Seavey's Iflands; on each of which batteries of cannon were planted, and entrenchments formed in 1775. The ftream here is very contracted; the tide rapid; the water deep, and the fhore hold and rocky on each fide; fo that in the fevereft winters the river is never frozen.

PIERE, an island in Illinois river, about 47 miles above the Piorias wintering-ground. A *fleche*, or arrow-flone is obtained by the Indians from a high hill on the weffern fide of the river, near the above island; with this flone the natives makes their gun-flints, and point their arrows. Above this island are rich and fertile meadows, on the eastern fide of the river, and continue feveral miles.

PIERMONT, a township in Grafton co. New-Hampshire, on the east bank of Connecticut river, 6 miles southward of Haverhill, and 5 northward of Orford. It was incorporated in 1764, and contains 426 inhabitants.

PLEROUAGAMIS, an Indian nation who inhabit the N. W. banks of Lake St. John, in Lower Canada.

PIERRE, St. a fmall defert ifland near the coaft of Newfoundland, which is only

only fit for c lat. 56. 27. ceded to th 1763. PIERRE. ifland of Ma fituated on a of the ifland Royal. It dence of m bufinefs. I down, yet 2000 houfe is fituated ftrand, but port of th it by a rive on a low h from a final road, which and unloadi of accels ; thipping tal capital of th PIERRE which empl weft, about St. Anthon delightful many of th grow fpont here in gre under load grapes, and covered w vegetables with usefu

> nard, and g eggs. On from its m For other Peter. PIGEON

ern branch the State c Little Pige confluence ton river, of Nolachu the French Pigeon riv Great Iron PIGEO1

chuletts. PIGEOT fortificatic and good in the iflar Indies.

of the equa-

r, bay, and of the proin the fouorthumbernity of the ie ifland lies ftrait, a litouth of the uth of Bear n's, and 58 Bay Verte. name feems Eaft river, rbour, fup. s, from the cams of lefs bay, are St. ool, Turket, rivers. The ;, populous, . A good bridged to ath by weft. d Tinmouth;

iain channel Hampfhire, rey's Iflands; of cannon nénts formhere is very ; the water id rocky on rreft winters

inois river, Piorias winarrow-ftone from a high e river, near is ftone the ts, and point s ifland are n the eaftern inue feveral

in Grafton e eaft bank niles fouthorthward of ted in 1764,

ts. Idian nation nks of Lake

rt ifland near d, which is only PIG

only fit for curing and drying fifh. N. lat. 56. 37. W. long. 45. 57. It was ceded to the French by the peace of 1763.

PIERRE, St. the first town built in the ifland of Martinico in the Weft Indies, fituated on a round bay on the weft coaft of the ifland, 5 league fouth of Fort Royal. It is a port of entry, the refidence of merchants, and the centre of bufinefs. It has been 4 times burnt down, yet it cont ins at prefent about 2000 houfes. The anchorage ground is fituated along the fea-fide on the ftrand, but is very unhealthy. Another port of the town is feparated from it by a river, and the houses are built on a low hill, which is called the fort, from a finall fortrels which defends the road, which is commodious for loading and unloading thips, and is likewife eafy of accels; but in the rainy feafon the thipping take thelter at Fort Royal, the capital of the ifland.

PIERRE, St. a river in Louifiana, which empties into the Miffifippi, from weft, about 10 miles below the Falls of St. Anthony. It paffes through a most delightful country, abounding with many of the neceffaries of life, which grow fpontaneoufly. Wild rice is found here in great abundance, trees bending under loads of fruits, fuch as plums, grapes, and apples. The meadows are covered with hops, and many other vegetables; while the ground is ftored with useful roots, as angelica, spikenard, and ground-nuts, as large as hens' eggs. On its east fide, about 20 miles from its mouth, is a coal-mine. -N.B.For other places named PIERRE, fee Peter.

PIGEON, the name of two fouth-weltern branches of French Broad river, in the State of Tennefiee. The mouth of Little Pigeon is about 25 miles from the confluence of French Broad with Holfton river, and about 3 below the mouth of Nolachucky. Big Pigeon falls into the French Broad 9 miles above Little Pigeon river. They both rife in the Great Iron Mountains.

PIGEON, a hill on Cape Ann, Maffachuletts. See Agamenticus.

PIGEON, a finall illand, whole ftrong fortifications command and fecure, fafe and good anchorage in Port Royal Bay, in the illand of Martinico, in the Weft-Indies.

d.

PIKELAND, a township in Chefter co. Pennsylvania.

PILAYA, a jurifdiction of La Plata. S. America. See Paspaya, its most common name.

PILDRAS, St. on the E. fhore of the Gulf of Campeachy, in the Gulf of Mexico. N. lat. 21. 4. W. long. 90. 35.

PILES. GROVE, a township in Salem co. New-Jersey.

PILGERRUH, or Pilgrim's Reft, was a Moravian fettlement of Chriftian Indians, on the fcite of a forfaken town of the Ottawas; on the hank of a river, 20 miles north-wefterly of Cayahoga, in the N, W. Territory, near Lake Erie, and 240 miles N, W. of Pittfburg.

PILGRIM'S *ifland*, on the S. eaftern fhore of St. Lawrence river, and below the Ifland de Coudres.

PILLAR, Cape, at the W. end of the Straits of Magellan, 6 leagues N. of Cape Defenda. S. lat. 52. 45. W. long. 76.40.

PILOT MOUNTAIN, or Ararat. See Surry County, N. Carolina.

PILOTO, or Salinas del Piloto, upright craggy rocks on the W. coaft of Mexico, S. E. of Cape Corientes; where there is good anchorage, and fhelter from N. W. and W. and S. W. winds. There are fall pits near this place.

PILOT-TOWN, in Suffex co. Delaware, lies near the mouth of Cool Spring Creek, which falls into Delaware Bay, near Lew fton, and 6 miles N. W. of Cape Henlopen.

PIMENT, Port, a village on the S. W. coaft of the S. peninfula, of the ifland of St. Domingo, 44 leagues N. W. of Les Coteaux, between which are two coves affording anchorage; that nearest Coteaux, is called Ansle a Damaffin. Port Piment is nearly eight leagues E, by S. of Tiburon.

PINAS Ifland, on the coast of the Gulf of Honduras, is fituated off Trivigillo Bay.

PINAS Point, the eaftern point of Panama Bay. N. lat. 6. 15. W. long. 80, 30. The port of this name is on the fame S. W. coaft of the Ifthmus of Darien, near the point; 12 leagues N. by W. of Port Quemanda, and 7 from Cape Garachina. The coaft, all the way fouthward, to Cape Gorientes, abounds with pine-trees; hence the name.

PINCHINA, one of the Cordillerat in S. America. M. Baugier found the cold of this mountain, immediately un-E e 3 der

11. 7

der the equator, to extend from 7 to 9 degrees under the freezing point every morning before fun-rife.

PINCKNEY, an island on the coast of South-Carolina.

PINCKNEY, a diffrict of the upper country of S. Carolina, lying W. of Camden and Cheraw diffricts; fubdivided into the counties of York, Chefter, Union, and Spartanburgh. It contains 25,870 white inhabitants; fends to the State legiflature, 9 reprefentatives, and 3 fenators; and in conjunction with Wafhington, fends one member to Congreis. It was formerly part of Camden and Ninety-Six diffricts. Chief town, Pinckneyville.

PINCKNEYVILLE, a post-town of S. Carolina, and capital of the above dif trift, in Union co. on the S. W. fide of Broad river, at the mouth of Pacolet. It coatains a handfome court-houfe, a gaol, and a few compact boufes. It is 75 miles N. W. of Columbia, 56 from Lincolntown, in N. Carolina, and 716 from Philadelphia.

PINE, Cape, on the S. coaft of the Ifland of Newfoundland, is about eight leagues weftward of Cape Race. N. lat. 46. 42. W. long. 53. 20. PINE Creek, in Northunberland co.

PINE Creek, in Northunberland co. Pennfylvania, a water of the W. branch of Sufquehannah river. Its mouth is about 12 miles weftward of Lycoming Creek, and 40 N. W. of the town of Northumberland.

PINES, a fmall ifland on the N. coaft of Terra Firma, S. America, about 43 leagues E. of Porto Bello, and forms a good harbour, with two other fmall iflands, and the main land. N. lat. 9. 32. W. long. 18. 15. The *River of Pines* is 5 mites from the above named harbour, and 27 eafterly of Allabrolies river. Its mouth has 6 feet water, but within there is 3 fathoms a confiderable way up.

PINES, Pinez, or Pinas, a fmall uninhabited ifland, feparated from the S. W. part of the ifland of Cuba, in the Weft-Indies, by a deep ftrait. It is about 25 miles long, and 15 broad, and affords good pafturage. It is 6 leagues from the main, but the channel is impaffable, by realon of fhoals and rocks, N. lat, 21. 30. W. long. 83. 25.

PINTARD'S Sound, on the N. W. coaft of N. America, fets up in an eaftern direction, having in it many intall

illands. Its mouth extends from Cape Scott, on the fouthern fide, in lat. 50. 56. and long 128. 57. W. to Point Difappointment, in lat. 52. 5. and long. 128. 50. W. It communicates with the Straits de Fuca; and thus the lands on both fides of Nootka Sound, from Cape Scott to Berkeley's Sound, (oppofite Cape Flattery, on the eaftern fide of the Straits de Fuca) are called by Capt. In: graham, Quadras Ifles.

PINTCHLUCO River, a large branch of the Chata Uche, the upper part of Appalachicola river.

PIORIAS Fort and Village, Old, in the N. W. Territory, on the western shore of Illinois river, and at the fouthern end of Illinois Lake; 210 miles from Miffifippi river, and 30 below the Crows Meadows river. The fummit on which the flockaded fort flood, commands a fine prospect of the country to the eastward, and up the lake, to the point where the river comes in at the northend; to the weftward are large meadows. In the lake (which is only a dilatation of the river, 191 miles in length, and 3 in breadth) is great plenty of fifh, and in particular, flurgeon and picannau. The country to the weftward is low and very level, and full of fwamps, fome a mile wide, bordered with fine meadows, and in fome places the high land comes to the river in points, or narrow necks. Here is abundance of cherry, plum, and other fruit trees. The Indians at the treaty of Greenville, in 1795, ceded to the United States a tract of 12 miles square at this fort. N. lat. 40. 53. W. long. 91. 12. 30.

PIORIAS Wintering Ground, a trace of land in the N. W. Territory, on the S. E. fide of Illinois river, about 40 miles above, and N. E. of the Great Cave, on the Miffinppi, opposite the mouth of the Miffiouri, and 27 below the island Pierre. About a quarter of a mile from the river, on the eastern fide of it, is a meadow of many miles long, and 5 or 6 miles broad. In this meadow are many fmall lakes, communicating with each other, and by which there are passages for fmall boats or cances; and one leads to the Illinois river.

PIORIAS, an Indian nation of the N. W. Territory, who with the Mitchigamias could furnish 300 warriors, 20 years ago. They inhabit near the fettlements in the Illinois country. A tribe of of this nam Miffifippi, It could fur 170 warrion igamias. T

PIRAUG America, Point Negi PISCA,

ence of Lin bour and fi round it is neighbouris fruit and y quarter of but being y in 1682, it fituation, a It is 1404 14. W. low PISCAD

rocks on t 48. fouth, Attico an PISCAL of Callao, of Callao the largeft

de Rhoda Chaucai I Pisca Pisca

County, M PISCA lands in t to compr pames of

> Pisca Jerfey, fr Rariton r It has 2, flaves. Brunfwice beth- Te

PISCA Prince G on the of weftward Mount M fouth of is 16 mi borough and 67 S

Pisco of Peru, leagues Chinca The roa hold the

from Cape at. 50. 56. int Difaplong. 128. with the e lands on from Cape (opposite fide of the Capt. In:

rge branch or part of

Old, in the eftern fhore uthern end rom Miffithe Crows t on which mmands a o the eaftthe point the northarge meamly a dilain length, nty of fifh, and picanreftward is of fwamps, with fine s the high points, or undance of ruit trees. Greenville, d States a fort. N. 2. 30. id, a trace ory, on the , about 40 the Great ppofite the 1 27 below uarter of a Itern fide of is long, and is meadow municating hich there or canoes; river. on of the N. : Mitchiga+ arriors, 20 ear the fetry. A tribe

of

of this name inhabit a village on the Miffifippi, a mile above Fort Chatres. It could furnifh about the fame period 170 warriors of the Piorias and Mitchigamias. They are idle and debauched. PIRAUGY, a river of Brazil, S. America, S. S. E. of Rio Grand, and Point Negro.

PISCA, a handfome town in the audience of Lima in Peru, with a good har bour and fpacious road. The country round it is fertile, and it fends to the neighbouring fettlements quantities of fruit and wine. It formerly flood a quarter of a league farther to the fouth, but being deftroyed by an earthquake, in 1622, it was removed to its prefent futation, about half a mile from the fea. It is 140 miles fouth of Lima. S. lat. 14. W. long. 73. 35.

PISCADORES, or Fifters, two great rocks on the coaft of Peru, in lat. 16. 48. fouth, near the broken gap between Attico and Ocona.

PISCADORES, rocks above the town of Callao, in Peru; 5 leagues N. N. W. of Callao Port. They are 6 in number; the largeft is welt of the port of Ancon de Rhodas, and 3 leagues fouth-east of Chaucai Port.

PISCATAQUA. See Pafcataqua.

PISCATAQUA Head. See York County, Maine.

PASCATAQUA, the ancient name of lands in the Diffuict of Maine, fuppofed to comprehend the lands known by the names of Kittery and B.rwick.

PISCATAWAY, a township of New-Jersey, fituated in Middlesex co. on-Rariton river, 6 miles from its mouth. It has 2,261 inhabitants, including 218 flaves. It is $3\frac{1}{2}$ miles N. E. of New-Brunswick, and 14 south-west of Elizabeth-Town.

PISCATAWAY, a fmall post town of Prince George's co, Maryland; fituated on the creek of its name which runs westward into Patowmac river, opposite Mount Vernon in Virginia, and 14 miles fouth of the Federal City. The town is 16 miles fouth-west of Wpper Marlborough, 16 north of Port Tobacco, and 67 S. W. by S. of Baltimore.

PISCO, a noted harbour on the coaft of Peru, in the province of Los Reyes, 6 leagues from the port of Chinca; Lorin Chinca lying half way between them. The road is fafe and capacious enough to hold the navy of France. The town is

inhabited by about 300 families, most of them meffizoes, mulattoes, and negrocs; the whites being much the smalless number. It has 3 churches, and a chapel for Indians; lies about half a mile from the sea, and 123 miles south of Lima. The ruins of the ancient town of Pisca are still visible, extending from the sea fore to the New town. It was defiroyed by an earthquake and inundation on Oft. 19, 1680. The sea, at that time, retired half a league, and returned with such fury, that it overflowed almost as much land beyond its bounds. S. lat. 13. 36. W. long. 76, 15.

PISS-POT, a bay on the fouth flore of the ftraits of Magellan, in the Long Reach, 8 leagues W. by N. of Cape Notch. S. lat. 53. 14. W. long. 75. 12.

PISTOLET, a large bay at the northern end of Newfoundland, fetting up from the Straits of Bellifle. Its weltern fide is formed by Cape Norman, and its eaftern point by Burnt Cape; 3 leagues apart.

PITCAIRN'S *Ifland*, in the S. Pacific Ocean, is 6 or 7 miles in length and a in breadth. It has neither river nor harbour; but has fome mountains which may be feen 15 leagues off to the S. E. All the S. fide is lined with rocks. S. lat. 25. 2. W. long. 133. 21. The variation of the needle off this illand, in 1767, was 2. 46. E.

PITON Point, Great, the S.W. point of the island of St. Lucia, in the West-Indies, and the most westerly point of the island. It is on a kind of a peninfula, the northern part of which is called Point Chimatchin.

PITT, a county of N. Carolina, in Newbern diffrict, bounded N. E. by Beaufort, and S. W. by Glatgow. It contains 8,275 inhabitants, including 2,367 flaves. Chief town, Greenville.

PITT, Fort, formerly Fort du Quefne. See Pitt/burg.

PITTSBOROUGH, or Pitt/burg, the capital of Chatham co. N. Carolina, is fituated n a rifing ground, and contains a court-houle, gaol, and about 40 or 50 houfes. The country in its environs is rith and well cultivated; and is much reforted to from the maritime parts of the State in the fickly months. The Hickory Mountain is not far diftant, and the air and water here are as pure as any in the world. It is 26 miles fouthweft of Illiborough, 36 weft of Ra-E e 4 leigh, 54 north-weft of Fayetteville, and 505 from Philadelphia.

PITTSBURG, a poft-town of Pennfylvania, the capital of Alleghany co. fituated on a beautiful plain running to a point. The Alleghany, which is a beautiful clear ftream, on the north, and the Monongahela, which is a muddy fream. on the fouth, uniting below where Fort du Quesne stood, form the majestic Ohio; which is there a quarter of a mile wide; 1,188 miles from its confluence with the Miffifippi, and 500 above Limestone, in Kentucky. This town was laid out on Penn's plan, in the year 1765, on the eastern bank of the Monongahela, about 200 yards from Fort du Queine, which was taken from the French, by the British, in 1760, and who changed its name to Fort Pitt, in honour of the late Earl of Chatham. It contains between 1 50 and 200 houfes, a gaol, court-houfe, Prefbyterian church, a church for German Lutherans, an academy, two breweries, and a diffillery. It has been lately fortified, and a party of troops flationed in it. By an enumeration made Dec. 1795, it appears that there were then 1,353 inhabitants in this borough ; the number has confiderably increased fince. The hills on the Mononganela fide are very high, extend down the Ohio, and abound with coals. Before the revolution, one of these coal-hills, it is faid, took fire and continued burning 8 years; when it was effectually extinguished by part of the hill giving way and filling up the crater. On the back fide of the town, from Grant's Hill, (fo called from his army's being here cut to pieces by the Indians) there is a beautiful profpect of the two rivers, wafting along their fepa rate freams till they meet and join at the point of the town. On every fide, hills covered with trees, appear to add fimplicity and beauty to the fcene. At the diffance of 100 miles up the Alleghany is a finall creek, which, in fome places, boils or bubbles forth, like the waters of Hell Gate, in New-York State, from which proceeds an oily fubftance. deemed by the people of this country, fingularly beneficial, and an infallible cure for weakness in the ftomach, for rheumatic pains, for fore breafts in women, bruifes, &c. The oil is gathered by the country people and Indians, who boil it and bring it to Pittfburg for fale;

· Applica. 1

and there is fcarcely a fingle inhabitant who does not poffeis a bottle of it, and is able to recount its many virtues, and its many cures. The navigation of the Ohio, in a dry feafon, is rather troublefome from Pittfburg to the Mingo-Town. about 75 miles; but from thence to the Miffifippi there is always water enough for barges carrying from 100 to 200 tons burden, fuch as are used on the river Thames, between London and Oxford, viz, from 100 to 120 feet keel. 16 to 18 feet in breadth, 4 feet in depth. and when loaded, drawing about a feet water. During the feation of the floods in the fpring, veffels of 100 or 200 tons burden may go from Pittiburg to the fea with fafety, in 16 or 17 days, although the distance is upwards of 2,000 miles. It is 178 miles W. by N. of Carlifle; 303 in the fame direction from Philadelphia; 283 N. W. by N. of Alexandria, in Virginia; and 445 from Fort Washington, in the N. W. Territory. N. lat. 43. 31. 44. W. long. 80. 8.

PITTSFIELD, a pleafant post town of Maffachuletts, fituated on the west line of Berkshire co. 6 miles N. of Lenox, 38 W. of Northampton, 140 W. of Bol¹ ton, and 40 N. E. of Albany. This township, and those N. and S. of it, on the banks of Housatonic river, are in a rich vale from one to seven miles wide. It was incorporated in 1761, and contains 1,992 inhabitants The place of worthip is a very handsome edifice, with a bell and cupola, from which there is a charming prospect.

PITTSFIELD, a township of New-Hampthire, fituated in Rockingham co. It was incorporated in 1782, and contains 888 inhabitants. It was taken from Chichefter, on Suncook river, N. E. of Concord.

PITTSFIELD, the porth-eafternmoft towninip of Rutland co. Vermont, conraining 49 inhabitants. It has Chittenden townthip on the S. W. and Philadelphia, in Addison co. on the N. W.

PITTSFORD, a township of Vermont, in Rutland co.

PITT's Grove, a village in Salem co. New Jerfey.

PITTQUOTTING, an Indian fettlement in the N. W. Territory, at the mouth of Huron river, which empties into Lake Erie.

PITT's Ifland, on the N. W. coaft of N. America,

V. of Bofy. This of it, on er, are in ven miles in 176 thandfome ola, from of Newgham co, and convas taken

of Lenox,

vas taken river, N.

ont, con-Chittennd Phila-N. W. Vermont,

alem co.

in fettley, at the empties

. coaft of America, PLA

N. America, lies near the main land, about half way from Dixon's Entrance to Prince William's Sound, and between Crofs Sound and Port Banks.

PITTSTOWN, a post town of the Diftrict of Maine, fituated in Lincoln co. on Kennebeck river, 5 miles below Hallowell Hook, 22 N. by W. of Witcasset, 70 N. by E. of Portland, 187 N. by E. of Boston, and 547 from Philadelphia. It contained, in 1790, 605 inhabitants. The western part called *Cobifey* or *Cobefey*, has an Episcopal church, with an annual income of 28 guineas, given by Dr. Gardiner for the support of an Episgopal minister.

PITTSTOWN, a post-town of New-Jersey, in Hunterdon co. on the west head waters of Rariton river, 10 miles E. by N. of Alexandria on Delaware river, 32 northerly of Trenton, and 58 N. N. E. of Philadelphia.

PITTSTOWN, a township of New-York, in Rensselater co. It is bounded southerly by Rensselaterwyck and Stephentown, and northerly by Schastekoke and Cambridge. In 1790 it contained 2,447 inhabitants, including 33 flaves; 419 of its inhabitants, in 1796, were electors.

PITTSYLVANIA, a county of Virginia, between the Blue Ridge, and the tide waters; bounded S. by the State of N. Carolina, and N. by Campbell co. It contains 11,252 inhabitants, including 5,932 flaves.

PIURA, the capital of a jurifdiction of the fame name in Peru, and was the first Spanish feitlement in that country; founded in 1531, by Don Francisco Pizarro, who also built the first church in it. It contains about 1,500 inhabitants. The houses are generally of one ftory, built of unburnt bricks, or of a kind of cane, called quincas. The climate is hot and dry. S. lat. 5. 11. W. long. 80. 5.

PLACENTIA Bay, on the S. coaft of Newfoundland Ifland, opens between Chapeau-Rouge Point weftward, and Cape St. Mary's on the E. $15\frac{1}{2}$ leagues apart; lying between lat. 46. 53. 30. and 47. 54. N. and between long. 54. 1. and 55. 21. 30. W. It is very fractious, has feveral iflands towards its head, and forms a good harbour for fhips; and is frequented by fuch vefiels as are bound either into the gulf or river of St. Lawrence. The port-town, which gives name to the bay, is on the eaftern fhore;

67 leagues to the E: of the island of Cape Breton ; 40 miles W. by S. of St. John's, and in lat. 47. 15. N. and long. 55. 13. W. The harbour is fo very capacious, that 1 50 fail of thips may lie in fecurity, and can fifh as quietly as in any river. The entrance into it is by a narrow channel; which will admit but one thip at a time. Sixty fail of thips can couveriently dry their fill on the Great Strand, which lies between 2 (teep hills, and is about) miles long. One of the hills is teparated from the firand, by a final brook which runs out of the channel, and forms a fort of lake, called the Little Bay, in which are caught great quantities of falmon. The inhabitants dry their fifh on what is called the Little Strand. The French had formerly a fort called St. Louis, fituated on a ridge of dangerous rocks, which contracts the entrance into the harbour. This ridge must be left on the starboard, going in.

PLAIN du Nord, a town on the north fide of the Island of St. Domingo, fituated at the fouth-east corner of Bay de l'Acul, and on the road from Cape Francois to Port de Paix, nearly 5 leagues west by fouth of the Cape, and 13 S. E. by E. of Port de Paix.

PLAINFIELD, a township of Massachusetts, co. of Hampshire. It was incorporated in 1785, and contains 453 inhabitants. It is 120 miles west by north of Boston.

PLAINFIELD, a township of Northampton co. Pennsylvania.

¹^JLAINFIELD, a township in the N. W. corner of Cheshire co. New-Hampshire, on the east bank of Connecticut river, which separates it from Hartland in Vermont. It was incorporated in 1761, and contains 1,024 inhabitants.

PLAINFIELD, a township in the S. E. part of Windham co. Connecticut, on the east fide of Quinabaug river, which divides it from Brooklyn and Canterbury. It is about 14 miles north-east of Norwich, has two Prefbyterian churches, an academy, and was fettled in 1689.

PLAISANCE, a town on the middle of the neck of the north peninfula of the ifland of St. Domingo; 12 leagues S. W. of Cape Francois, and 7 north of Les Gonaves.

PLANTAIN Garden River, at the eaft end of the ifland of Jamaica, and N. by W. of Point Morant. There is a kind

of bay, at its mouth ; and on it, within land, is the town of Bath.

PLASTOW, or *Plaiflow*, a townfhip in the fouth-eaftern part of Rockingham co. New-Hampfhire, feparated from Haverhill in Maffachuffetts, (of which it was formerly a part) by the fouthern State line. It was incorporated in 1749, and contains 521 inhabitants; 12 or 14. miles fouth-weftward of Exeter, and 30 fouth-weft of Portfmouth.

PLATA Cays, or Keys, a large fandbank from 10 to 14 leagues north of the north coaft of the illand of St. Domingo. It is nearly 10 leagues in length, at weft by north, and from 2 to 6 miles in breadth. The east end is nearly due north of Old Cape Francois.

PLATA, an ifland on the coast of Quito, in Peru, 4 or 5 leagues W. N. W. from Cape St. Lorenzo, and in lat. 1. 10. fouth. It is 4 miles long, and 11 broad; and affords little elfe than grafs and finall trees. The anchoring places are on the east fide near the middle of the ifland.

PLATA, River de la, is one of the largeft rivers on this globe, and falls into the S. Atlantic Ocean between Capes St. Anthony fouthward, and St. Mary on the northward, which are about 150 miles apart. It acquires this name after the junction of the Parana and Paraguay; and feparates Brazil from the Defert Coaft. Its navigation, although very extensive, is rather dangerous, on account of the number of landy iflands and rocks in its channel, which are perhaps difficult to avoid, by reason of the currents and different fets of the tide, which they produce. For these and other reafons, thips feldom enter this river, unlefs urged by neceffity; efpecially as there are many bays, harbours, and ports on the coaft where veffels can find good and fafe anchorage. The water is fweet, clears the lungs, and is faid to be a fpecific against rheums and defluxions; but is of a petrifying quality. See Paraguay, for a more particular account. Cape St. Anthony is in lat. 36. 32. fouth, and long 56. 34. weft.

PLATA, a city of Peru, in S. America, in the province of Charcas, built in 1539. It ftands on a fmall plain, environed by eminences, which defend it from all winds. The air in fummer is very mild; nor is there any confiderable difference throughout the year, except in the winter months, viz. May, June, and July, when tempefts of thunder and lightning and rain are frequent ; but all the other parts of the year the air is ferene. The houses have delightful gardens planted with European fruit trees, but water is very fcarce in the city, It has a large and elegant cathedral, adorned with paintings and gildings, a church for Indians, an hofpital, and z nunneries; and contains about 14,000 inhabitants. Here also is an university and two colleges, in which lectures on all the fciences are read. In its vicinity are mines of filver in the mountain of Porco; which have been neglected fince those of Potoff were discovered. It is feated on the river Chimbo, 500 miles S E. of Cuico. S. lat 19. 16. weft long. 63. 40. The jurifdiction of this name is 200 leagues in length, and 100 in breath, extending on each fide of the famous river La Plata. In winter the nights are cold but the days moderately warm. The frost is neither violent nor lafting, and the mows very inconfiderable.

PLATE, Monte de, a mountainous fettlement near the centre of the ifland of St. Domingo, towards its eaftern extremity, 15 leagues north of the mouth of Macoriz river, and 16 to the northcaft of the city of St. Domingo. It was formerly a flourishing place, and called a city; but the whole parish does not now contain above 600 fouls. Two leagues to the N. E. of it is the wretched lettlement of Boya, to which the cacique Henri retired, with the small remnant of Indians, when the cruelties of the Spaniards, in the reign of CharlesV. had driven him to a revolt. There does not now exitt one pure defcendant of their race.

PLATE, Point, the north point of the entrance into Port Dauphin, on the E, coaft of the ifland of Cape Breton, or Sydney; and 3 leagues louth-weft by fouth of Cape Fumi, which is the fouthweft boundary of the harbour of Achepe,

PLATE, *Port de*, on the N. coaft of the ifland of St. Domingo, is overlooked by a white mountain, and lies 22 leagues W. of Old Cape Francois. It has 3 fathoms water at its entrance, but diminifles within; and is but an indifferent harbour. The bottom is in fome parts fharp rocks, capable of cutting the cables. A vefiel muft, on entering, keep very close to the point

point of th when in, port. Th ly abound copper. It is unh the inhab ter of a ra and abou PLATI fide of the 3 leagues is opposit league fro of Bomba Mole. 1 Paris, 75 PLATT mont, wh at Shelbu PLATE the island lin's Cliff PLATT thip in C on the we plain, lyin about 300 and near Quebec in of the to wide from ing tract loam, we proportio tillage. cent for f which ev view. Set and the w prefent co tants, was a houfe for and gaol, general fe in a year; every kin among the building, may here traveller h of a fea-p and a ph 1799, it c cluding 1 123 of th tors.

PLAY (Canada, li

in the E, breton, or h-weft by the fouthf Achepe; oaft of the lcoked by agues W. 3 fathoms tharbour. arp rocks, A vefiel loie to the point

endant of

int of the

PLA

point of the breaker, near the eaftern fort; when in, the anchors in the middle of the port. The canton of Port de Plate greatly abounds in mines of gold, filver and copper. There are also mines of plafter. It is unhealthy, from the custom which the inhabitants have of drinking the water of a ravin. It has a handsome church and about 2,500 inhabitants.

PLATE Forme, La, a town on the S. fide of the N. peninfula of St. Domingo, 3 leagues W. of point du Paradis, which is opposite the settlement of that name, a league from the sea; 22 leagues S. by E. of Bombarde, and 13 S. E. by S. of the Mole. N. lat. 19. 36. W. long. from Paris, 75. 40.

PLATTE, La, a finall river of Vermont, which falls into Lake Champlain at Shelburne.

PLATFORM, a bay on the N. coaft of the island of Jamaica, eaftward of Dunklin's Cliff.

PLATTSBURGH, is an extensive townthip in Clinton co. New-York, fituated on the western margin of Lake Champlain, lying northerly of Willfborough, about 300 miles north of New-York city, and nearly that diffance foutherly of Quebec in Canada. From the fouth part of the town the mountains trund away wide from the lake, and leave a charming tract of excellent land, of a rich loam, well watered, and about an equal proportion fuitable for meadow and for tillage. The land rifes in a gentle afcent for feveral miles from the lake, of which every farm will have a delightful view. Several years ago, this township, and the whole county indeed, which at prefent contains feveral thousand inhabitants, was a wildernefs; now they have a houfe for public worthip, a court houfe and gaol, the courts of common pleas and general leffions of the peace fit here twice in a year; they have artizans of almost every kind among them, and furnish among themfelves all the materials for building, glass excepted. Polite circles may here be found, and the genteel traveller be entertained with the luxuries of a fea-port, a tune on the harpfichord, and a philosophical convertation. In 1799, it contained 458 inhabitants, including 13 flaves. In 1796 there were 123 of the inhabitants qualified electors.

PLAY Green, or Puscacogan, in Upper Canada, lies near the north shore of Win-

nipeg Lake, in lat. 53. 53. and long. 97. 54.

PLEASANT Point, a north-eafterly head-land in Merry Meeting Bay, diftrict of Maine, and in Lincoln co. See Merry Meeting Bay.

PLEASANT Point, the eaftern boundary of the mouth of Hawk's, or Sandwich river, in the harbour of Chebucto, on the fouthern coaft of Nova-Scotia.

PLEASANT River, a finall village where is a post-office on the fea-coast of Washington co. District of Maine, and at the head of Narraguagus Bay; 16 miles N. E. of Goldsborough, and 32 W. by S. of Machias.

PLEIN River, the northern head water of Illinois river. It interlocks with Chicago river, a water of Lake Michigan. Forty miles from its fource is tha place called Hid-Ifland; 26 miles farther it paffes through Dupage Lake; and 5 miles below the lake, and fourhward of Mount Juliet, it joins Theakiki river, which comes from the eaftward. Thence the united ftream affumes the name of Illinois. The land between these branches is rich, and intermixed with fwamps and ponds.

PLUCKEMIN, a town or village of fome trade, in Somerfet co. New-Jeriey, 28 miles north of Princeton, and about 18 S. W. of Brunfwick. It derived its fingular name from an old Irifhman noted for his address in *taking in* people.

PLUE, Lac la, or Rainy Lake, lies W. by N. of Lake Superior, and E. by S. of the Lake of the Woods, in Upper Canada. The Narrows are in north 49 3' 2" lat. 48 - 50 7 49 Fort Lac la Plue Island Portage -50 At the Barrier -7 5I W. Longitude 8 30 95

PLUMB Island, on the coast of Maffachufetts, is about 9 miles long. and about half a mile broad, extending from the entrance of Ipiwich river on the fouth, nearly a north courfe to the mouth of Merrimack river, and is feparated from the main land by a narrow found, called Plumb Ifland river, which is fordable in feveral places at low water. It confifts for the most part of fand, blown into ludicrous heaps, and crowned with bufhes bearing the beach plum. There is however, a valuable property of faltmarsh, and at the S. end of the island, are 2 or 3 good farms. On the N. end ftand

and the light-houses, and the remains of a wooden fort, built during the war, for the defence of the harbour. On the fea fhore of this ifland, and on Salifbury beach, the marine Society, and other gentlemen of Newbury-Port, have humanely crefted feveral fmall houses, furmifhed with fuel and other conveniences, for the relief of mariners who may be fhipwrecked on this coaft. The N. end lies in lat. 43, 4. N. and long, 70. 47. W. See Newbury-Port.

PLUME *ifland*, on the N. E. coaft of Long-Ifland, in the State of New-York, is annexed to Southhold in Suffolk co. It contains about 800 acres, and fupports 7 familes. It is fertile, and produces wheat, corn, butter, cheefe, and wool. It is three-fourths of a mile from the eaftern point of Southhold. This ifland, with the fandy point of Gardner's Ifland, form the entrance of Gardner's Bay.

PLUMB Point, Great, on the S. coaft of the island of Jamaica, forms the S. E. limit of the peninfula of Port-Royal, which shelters the harbour of Kingston. Little Plumb Point lies westward of the former, towards the town of Port-Royal, on the fouth fide of the peninfula.

PLUMSTEAD, a polt-town of Pennfylvania, fituated on the W. fide of Delaware river, 36 miles N. of Philadelphia, and 13 S, by W. of Alexandria, in New-Jerfey.

PLYMOUTH, a maritime county in the eaftern part of the State of Maffachufetts, having Maffachufetts Bay to the N. E. Brittol co. S. W. Barnitaple co, S. E. and Norfolk co. N. W. It is fundivided into 15 townships, of which Plymouth is the chief; and contains 4,240 houfes and 29,535 inhabitants. Within the counties of Plymouth and Briftol, there are now in operation, 14 blaft, and 6 air furnaces, 20 forges, 7 ditting and rolling mills, befide a number of trip-hammer fhops, and an almost incredible number of nail-fhops, and others for common imithery. These furnaces, supplied from the neighbouring mines, produce annually from 1,500 to 1,500 tons of iron ware. The forges, on an average, manufacture more than 1,000 tons annually, and the flitting and rolling mills, at least 1,500 tons. The various manufactures of these mills, have given rife to many other branches in iron and fteel, viz. cut and hammered nails, fpades and fhovels, card teeth.

PLY

faws, fcythes, metal buttons, cannon balls, bells, fire arms, &c. In these counties are also manufactured hand-bellows, combs, fheet-iron for the tin manufacture, wire, linfeed oil, fnuff, flone and earthen ware. The iron-works, called the Federal Furnace, are 7 miles from Plymouth harbour.

PLYMOUTH, a fea-port town in Maffachusetts, shire town of the county of Plymouth, 42 miles S. from Bofton ; a post-town and port of entry ; bounded northerly by Kingston, and a line extending across the harbour to the Gurnet; westerly by Carver; foutherly by Wareham and Sandwich, and eafterly by the fea. The township is extensive, containing more than 80 fquare miles. It is about 16 miles in length, and more than 5 miles in breadth. The number of inhabitants, by the cenfus of 1791, was 2,995. The Town, or principal fettlement, which contains more than two-thirds of the inhabitants, is on the north-easterly part of the township, near a fiream called the Town Brook, which flows from a large pond, bearing the name of Billington-Sea, One main street croffes the stream, and is interfected by three crofs ftreets, extending to the fhore : another ftreet runs wefterly on the north fide of the brook. The town is compactly built, and contains about 200 dwelling-houfes, (the greater part of which are on the north fide of the Town Brook) a handfome meeting-house, court-house, and gaol. There are two precincts; one includes the town, and the districts of Hobbs? Hole, and Eel River; the other is at Monument Ponds, a village lying about 7 miles S. from the town, beyond the high lands of Monument. The foil near the coaft is generally good; the refidue of the township is barren, and notwithstanding the antiquity of the fettlement, is yet a forest. The wood is principally pine, though there are many tracts covered with oak. The harbour is capacious, but fhallow, and is formed by a long and narrow neck of land, called Salt boufe Beach, extending foutherly from Marshfield, and terminating at the Gurnet Head, and by a finaller beach within, running in an opposite direction, and connected with the main land near Eel river, about 3 miles from the town. There is a light-houle on the Gurnet, and on Sultboufe bunfe Bee erected an Society of tion and t There is which ex wharves,

The p is the cod 2,000 tor men annu ing veffel 2 brigs ; ployed in filhing v Southern The expo ment of t were very 8,000 or now refp ceeded 7 they amon Formerly fold at Bo most who and confid lately bee ported fro of the fo conveyed The lo

habitants for indepe veffels we The men them, wer fervice, in lives : a g phans we guifhed ; went to d of poverty few years have reve things. . terprifing to those w vived; th the place a former per repair, ma a spirit of is apparen plated: a other wor Brook. week to B an aquedu

, cannon In thefe hand-belin manuftone and s, called iles from 466 n in Mafcounty of Softon ; a bounded line exthe Gurtherly by I eafterly extenfive, re miles. and more : number of 1791, principal ore than is on the hip, near k, which aring the ne main is interextending 18 wefterk. The contains he greater orth fide handfome und gaol. includes of Hobbs her is at ing about eyond the The foil ood; the rren, and of the fete wood is are many e harbour 1 is formneck of extendield, and Head, and running connected ver, about here is a d on Saltbouft PLY

bunge Beach is placed one of the huts erected and maintained by the humane Society of Maffachufetts, for the reception and relief of fhipwrecked mariners. There is a breach in the inner beach, which exposes the fhipping, even at the wharves, during an eafterly ftorm.

The principal bufinefs of the town is the cod fiftery, in which are employed 2,000 tons of fhipping, and about 300 men annually. There are a few coalting veffels belonging to the place, and 2 brigs; and 10 or 12 fchooners, employed in foreign trade. Many of the fifting veffels make voyages to the Southern States, in the winter feafon. The exports, which, at the commencement of the prefent federal government, were very inconfiderable, not exceeding 8,000 or 9,000 dollars annually, are now respectable. In 1795, they exceeded 70,000 dollars, and in 1796, they amounted to near 130,000 dollars. Formerly the produce of the fifhery was fold at Bofton, or Salem; it is now almost wholly exported from the town, and confiderable quantities of fifh/have lately been purchased at Boston, and exported from Plymouth. The proceeds of the foreign voyages, are generally conveyed to Bofton for a market.

The loffes and fufferings of the inhabitants of Plymouth, during the war for independence, were extreme. Their veffels were almost all captured or lost. The men who used to be employed in them, were difperfed in the fea and land fervice, in which many of them loft their lives : a great number of widows and orphans were left destitute ; bufiness languifhed; houfes, ftores, and wharves went to decay, and a general appearance of poverty and oppreffion prevailed. A few years of peace and good government have reverfed this melancholy ftate of things. A young, industrious, and enterprifing race of feamen has fucceeded to those who are gone : bufinefs has revived; the navigation and commerce of the place are more refpeStable than at any former period; the houfes are in good repair, many new ones are erected, and a fpirit of enterprize and improvement. is apparent. An academy is contemplated: a valuable flitting-mill, and other works, are erected on the Town Brook. A stage, which goes twice a week to Bofton, is well fupported; and an aqueduct for bringing fresh water to

the houfes of the inhabitants is more than half completed. The township abounds with ponds and fireams. More than 100 ponds appear on the map lately taken by a Committee of the town, and transmitted to the Secretary's office. Billington Sea is about 2 miles from the town, and covers near 300 acres. From the ftream, flowing from this pond, the aqueduct will be fupplied. South Pond is much larger. Further fouth is Halfway Pond and Long Pond. Near Sandwich line is the Great Herring Pond. To Billington Sea, Halfway Pond, and the Great Herring Pond, alewives refort in their feason in great The Great Herring Pond abundance. has been contemplated as a refervoir for the projected canal acrofs the ifthmus between Buzzard and Barnstable Bays. Many of the ponds abound with white and red perch, pike, and other fresh water fifh; and in the numerous brooks which run into the fea in different parts of the township, are found excellent trout. These ponds and ftreams are often the fcenes of amulement for parties of both fexes in the fummer featon.

At the village of Monument Ponds and Eel river, and in fome other parts of the township, many of the inhabitants are farmers. In the Town, the gardens are numerous and well cultivated, and when aided by the aqueduct, will be productive equal to the wants of the inhabitants.

The fituation of the town is pleafant and healthful. The easterly winds of the Spring, however, are diffreffing to perfons of tender habits, and are uncomfortable even to the robuft. The market is not regularly supplied. Fuel, fifh, poultry, and wild fowl are plentiful and cheaper, perhaps, than in any other fea port of the fize. The people are fober, friendly, and industrious. It is the first lettlement in New-England, and is peopled, principally, by the defcendants of the ancient flock. But few foreigners are among them. The rock on which their forefathers firft landed, was conveyed, in 1774, from the fhore to a fquare in the centre of the town. The fentimental traveller will not fail to view it ; and if he is paffing to Cape Cod, he will pause a moment at Clampudding Pond, about 7 miles from the town, where the people in ancient days, when travelling from the Cape to attend the courts of Plymouth,

446

Plymouth, ufed to fit and regale themfelves with the clams and pudding which they brought with them. A few miles further fouth, on the fame road, are the *farifice rockt*, which are covered with the dry limbs of trees and pine knots, heaped upon them by the Indians as they pafs by, in obfervance of an ancient ufage, the origin of which is uncertain.

The cheapne's of living, the plenty of fuel, and the convenient mill-feats which are to be found in Plymouth, will probably render it, at fome future period, a confiderable manufacturing town. Domeftic manufactures are now very general there. Fifhery and foreign commerce at prefent engage almost all the active capital of the town, but the contingencies to which they are exposed may lead to fome other fources of employment and profit.

In the three last quarters of 1796, the exports were as follow :

Strata & Farries

historie en ana a his	dollars.
Second quarter	56,243
Third ditto	36,634
Fourth ditto	36,006

In the first quarter of the prefent year (1797) they amounted only to 11,466 dollars. This diminution has been produced by the apprehensions excited by the depredations of the French on the commerce of the United States.

PLYMOUTH, a town of New-York, in Onondago co. lately laid out and named by E. Watfon, Elq. a native of Plymouth, New-England. The town lies about 12 miles fouth-east of Geneva, on a beautiful declivity on the east fide of Seneca Lake, and commands a charming and extensive view of the whole lake. The town plat is on the fpot formerly called Apple-Town, and was the head-quarters of the Seneca Indians. who were conquered and difperfed by Gen. Sullivan, in his western expedition in 1779. The fituation is healthful and pleafant, well watered by copious living fprings. Twenty houses were build-ing here in 1796, and as the new State-road, from the Cayuga, interfects the town, a ferry established, and another town laid out on the oppofit fide of the lake, it promifes fair to become a confiderable and very Editions vi L

thriving village. It is well watered by copious fprings.

PLYMOUTH, a town in Litchfield co. Connecticut.

PLYMOUTH, a post-town of New-Hamphire, fituated in Grafton co. at the mouth of Baker's river, on its S. fide, where it falls into the river Pemigewaffet; 45 miles N. of Concord, 71 northwefterly of Portfmouth, and 445 N. E. of Philadelphia. The township was incorporated in 1763, and contains 625 inhabitants.

PLYMOUTH, the name of two townhips in Pennfylvania, the one in Luzerne co. the other in that of Montgomery.

PLYMOUTH, a finall post-town of N. Carolina, on the fouth fide of Roanoke river, about 3 miles above Albemarle Sound. It is 23 miles fouth-west by S. of Edenton, and 463 fouth by west of Philadelphia.

PLYMOUTH, a fettlement on the fouth peninfula of the island of St. Domingo, and in the dependence of Jeremie.

PLYMOUTH-TOWN, in the ifland of Tobago, in the Weft-Indies. N. lat. 10. 10. W. long. 60. 32.

PLYMPTON, a township in Plymouth co. Massachusetts, 45 miles S. E. of Boston. It was incorporated in 1707, and contains 956 inhabitants.

POCAHONTAS, a town in Chefferfield co. Virginia, within the jurifdiction of Petersburgh in Dinwiddie co. It probably dérives its name from the famous princes Pocahontas, the daughter of king Powhatan.

POCKREKESKO, a river of New-Britain, N. America.

POCOMOKE, an eastern water of Chesapeak Bay, navigable a few miles. On its eastern fide, about 20 miles from its mouth, is the town of Snow Hill.

POCOTALIGO, a village of S. Carolina, 15 miles from Combahee ferry, and 67 from Charleftown.

POGE, Cape, the N. E. point of Chabaquiddick Island, near Martha's Vineyard, Massachietts. From Holmes's Hole to this cape the course is S. E. by E. 31 leagues distant. In the channel between them there are 11 and 12 fathoms water. N. lat. 41. 25. W. long. from Greenwich, 70. 22.

POINT, a township in Northumberland co. Penniylvania.

POINT

POINT Bofton ha long. 70. POINT or north within th It was c 1796. POINT Paffamag New-Bru POINT fouth fide 2 leagues nales rive POINT South-Ki of the we in Rhode fouth-wei W. long. POINT loupe, has about 20 POIAU

niards Vo mountain which be 1 545, and years; bu has not be of burnin of a conic in Mexic who are i tance of 5 the Peak ways cove adorned v other tree make the tiful. It city of Me POKON ton co. Pe

of Eafton Wyoming POLAN co. Distri

POLLIF island, abo ference, a the High remarkable failors required

POMAL diction of the proving

watered

hfield co.

of New.

ts S. fide, migewaf-71 north-45 N. E. hip was

tains 625 wo town-

of Mont-

wn of N. Roanoke Ibemarle -weft by by weft

on the l of St. dence of

ifland of N. lat.

lymouth . of Bof-707, and

Chefterjurifdicie co. It 1 the fadaughter

New-Bri-

water of tw miles. iles from v Hill. S. Caroterry, and

t of Chaa's Vine-Holmes's S. E. by channel id 12 fa-W. long.

humber-

POINT

POL

POINT Alderton, the S. W. point of Boston harbour. N. lat. 42. 20. W. long. 70. 54.

POINT-AU FER, a place near the head or northern part of Lake Champlain, within the limits of the United States. It was delivered up by the British in 1796.

POINT le Pro, the eastern limit of Passanaquoddy Bay, on the coast of New-Brunswick.

POINTE des Pieges, a cape on the fouth fide of the fland of St. Domingo, 2 leagues west of the mouth of Pedernales river.

POINT Juditb, in the township of South-Kingstown, is the south extremity of the western shore of Narraganset Bay in Rhode-Island. It is 9 miles southfouth-west of Newport. N. lat. 41. 24. W. long. 71. 28.

W. long. 71. 28. POINT Petre, in the island of Guadaloupe, has strong fortifications, and lies about 20 miles from Fort Louis.

POJAUHTECUL, called by the Spaniards Volcan de Orizaba, a celebrated mountain in Mexico, or New-Spain, which began to fend forth finoke in 1545, and continued to do fo for 20 years; but for two centuries paft, there has not been observed the smallest fign of burning. The mountain, which is of a conical figure, is the highest land in Mexico, and is deferied by feamen who are fleering that way, at the diftance of 50 leagues; and is higher than the Peak of Teneriffe. Its top is always covered with fnow, and its border adorned with large cedars, pine, and other trees of valuable wood, which make the profpect of it every way beautiful. It is 90 miles eastward of the city of Mexico.

POKONCA, a mountain in Northampton co. Pennfylvania, 22 miles N. W. of Easton, and 26 fouth-easterly of Wyoming Falls.

POLAND, a township in Cumberland co. District of Maine.

POLLIPLES *Island*, a fmall rocky island, about 80 or 100 rods in circumference, at the northern entrance of the High Lands in Hudion's river: remarkable only as the place where failors require a treat of perfons who have never before paffed the river.

POMALACTA, a village in the jurifdiction of the town of Guafantos, in the province of Quito, famous for the

ruins of a fortress built by the Yncas, or ancient emperors of Peru.

POMFRET, a township in Windfor co. Vermont, containing 710 inhabitants. It is 11 miles W. of the ferry on Connecticut river, in the town of Hartford, and 64 north-east of Beanington.

POMFRET, a post-town of Connecticut, in Windham co. It is 40 miles E. by N. of Hartford, 66 S. W. of Bofton, and 264 N. E. of Philadelphia; and contains a Congregational church, and a few neat-houles. The township was first fettled in 1686 by emigrants from Roxbury. It was part of the Majbamoquet purchase, and in 1713 it was erected into a township. Quinabaug river separates it from Killingly on the east. In Pomfret is the famous cave, where General Putnam conquered and flew the wolf.

POMPTON, in Bergen co, New-Jerfey, lies on Ringwood, a branch of Paffaik river, about 23 miles north-weft of New-York city.

POMPEY, a military township in Onondago co. New-York, incorporated in 1794. It comprehends the townships of Pompey, Tully, and Fabius, together with that part of the lands called the Onondago Refervation; bounded northerly by the Genefice road, and westerly by the Onondago Creek. In 1796, there were 179 of the inhabitants qualified electors.

PONPON. See Edifle River, South-Carolina.

PONTE di Dio. See Atoyaque.

PONTCHARTRAIN, a lake of Wefts Florida, which communicates eaftward with the Gulf Mexico, and weftward with Miffilippi river, through Lake Manrepas and Ibberville river. It is about 40 miles long, 24 broad, and 18 feet deep. The following creeks fall into it on the N. fide, viz. Tangipaho, a and Le Comble, 4 feet deep ; Chefuncta, 7; and Bonfouca, 6; and from the peninfula of Orleans, Tigahoc, at the mouth of which was a imail poft. The Bayouk of St. John alfo communicates on the fame fide. The French inhabitants, who formerly relided on the N. fide of this lake, chiefly employed themfelves in making pitch, tar and turpentine, and raifing flock, for which the country is very favourable. See Maurepas. publications, bic

PONTCHARTRAIN

N

148

PONTCHARTRAIN, an ifland in Lake Superior, fouth by weft of Maurepas Island, and north-west of Hocquart Ifland.

PONTEQUE, or Pontique, a point on the W. coast of Mexico, 10 leagues N. by E. of Cape Corientes, between which is the bay de Valderas. To the weftward of it are two imall islands of its name, a league from the main. There are also rocks, called the rocks of Ponteque, 20 leagues fouth-welt of the port of Matanchel.

POPA MADRE, atown of S. America; in Terra Firma, 50 miles east of Carthagena. N. latitude 10. 15. west longitude 74: 32.

POPAYAN, a province of S. America, in New Granada, about 400 miles in length and 300 in breadth. The counry is unhealthy, but vaft quantities of gold are found in it. It is ftill mostly in possession of the native Americans.

POPAYAN, the capital of the above province, and a bifhop's fee, inhabited chiefly by creoles. It is 220 miles N. E. of Quito.

POPLAR Spring, in the north-weltern part of Ann Arundel co. Maryland, near a brook, 3 miles foutherly of the welt branch of Patapico river, on the high road from Baltimore to Frederickftown, about 27 miles weft of Baltimore, and Ar N. W. of Armapolis.

POPLIN, a township of New-Hampthire, in Rockingham do. 12 miles wel-terly of Exeter, and 26 wetterly of Portf-mouth. It was incorporated in 1764, and contains 493 inhabitants.

Poousoomsuck, ariver of Vermont, which runs a foutherly courfe, and falls into Connecticut river /in the township of Barnet, near the Lower bar of the 15 mile falls. It is 100 yards wide, and noted for the quantity and quality of falmon it produces. On this river, which is fettled 20 miles up, are fome of the beft townfhips in the State.

POQUE CHOUDIE, a low flat point between the gut of Chepagan and the village of Caraquet, on the fouthern fide of Chaleur Bay. It is about 4 leagues diftant from the gut, in a fouth-weft direction. The island of Caraquet, at the fame distance from the gut, lies in a welt direction from the main. The village is about 3 leagues in extent; its having Fort George and Navy Ifland plantations, &cc. has a church, and a on the weft, and Wood's Ifland eaft-ANA STREEP PACT

number of inhabitants, all Roman Ca. tholics. The oytter and cod-fifheries are carried on here.

PORCAS, Ilhade, or Ifland of Hogs; lies eaftward of St. Sebaftian's Ifland, on the coaft of Brazil, and 20 miles caftward of the Bay of Saints.

PORCAS, Morro de, or Hog's Strand, on the weft coaft of New Mexico, is northward of Point Higuerra, the fouthweft point of the peninfula which forms the bay of Panama. From thence thips ufually take their departure, to go fouthward for the coaft of Peru.

.Porco, a jurifdiction of S. America. in the province of Charcos, beginning at the welt end of the town of Potofi, about 25 leagues from the city of La Plata, and extending about 20 leagues.

PORCO, a town in the above jurifdiction, weft of the mines of Potofi. S. lat. 19. 40. W. long. 64. 50.

PORCUPINE, Cape: See Blow-medown.

PORPOISE, Cape, on the coaft of York co. Diffrict of Maine, is 7 leagues N. by E. of Cape Neddock, and f fouthweft of Wood-Ifland. It is known by the highlands of Kennebunk; which lie to the north-weft of it. A veffel that draws to feet water will be aground at low water in the harbour here. It is fo narrow that a vefiel cannot turn round ; is within 100 yards of the fea, and fecure from all winds, whether you have anchor or not.

PORT of Spain, the capital of the ifland of Trinidad, in the Weft Indics, fituated on the weft fide of the ifland. .

PORTAGE, Point, on the east coaft of New-Brunfwick, and in the fouth-weft part of the Gulf of St. Lawrence, forms the N. limit of Miramichy Bay, as Point Ecoumenac does the fouth.

PORT AMHERST, a bay on the foutheastern coaft of Nova-Scotia, fouth-weft of Port Roleway, and 17 miles N. E. of Cape Sable.

PORT ANGEL, a harbour on the W. coaft of Mexico, about half way between St. Pedro and Compostella. It is a broad and open bay, having good an-chorage, but bad landing. N. lat. 13. 12. W. long. 97. 4.

PORT ANTONIO, in the north-eaftern. part of the illand of Jamaica, lies W. by N. of the north-east point; ward.

vard. feet ; a commod would b only 36 ron, in S into the of Tite PORT the illan from G POR the ifla entranci from C PoR? fea-port Bight (the iflat which i is the f time of ble tra with t tomb o fequen good v de Ma years, bafons becom The ju its ex Dec. follow 44,711 lbs. c 1 37,9 hides, of 8, duties tion w fine to the re 1791. place count of th The i wouk the pr betwe of St. throu Bani, Princ leagu it 14 to P 1. 银行行 ٠

Ca-

eries

logs,

caft-

and,

o, is outh-

orms Mips

outh-

rica,

otofi,

f La

ues.

fdic-

S.

1-me-

ft of

gues

n by

ch lie

that

nd at

t is fo

und;

ecure

nchor

f the

hdies,

aft of

-welt

Point

outh-

1-weft

N. E.

e W.

tween

16.0

od an-

. 13.

h-eaf-

naica,

point;

Ifland

eaft-

ward.

d. .

ward. It is capable of holding a large fleet ; and if it were fortified and accommodated for refitting fhips of war, would be of great importance, as it is only 36 leagues wefferly of Cape Tiburon, in St. Domingo, and opens directly into the Windward Paffage. The town of Titchfield lies on this bay.

PORTA Maria, in the N. E. part of the illand of Jamaica, is fouth-easterly from Gallina Point.

PORTA Port, on the N. W. fide of the illand of Newfoundland; the fouth entrance into which is 10 or 12 leagues from Cape St. George.

PORT au Prince, a jurifdiction and fea-port, at the head of the great Bay or Bight of Leogane, in the welt part of the ifland of St. Domingo. The town, which is feated on the head of the bay, is the feat of the French government in time of peace, and a place of confidera-ble trade. Though fingularly favoured with the east winds, it was long the tomb of the unhappy Europeans, in con-fequence of the difficulty of obtaining good water. By the exertions of M. de Marbois, who refided here about 5 rears, in conftructing fountains, public basons, and airy prisons, the place has become far more healthy and defireable. The jurifdiction contains 6 parifhes, and its exports from January 1, 1789, to Dec. 31, of the fame year, were as follow: 2,497,321 lbs. white fugar; 44,716,226lbs.brown fugar; 17,829,424 lbs. coffee; 1,878,999 lbs. cotton; \$ 37,951 lbs. indigo; other articles, as hides, molaffes, fpirits, &cc. to the value of 8,2481 livres. The total value of duties on the above articles on exportation was 189,945 dolls. 46 cents. This fine town was nearly burnt down by the revolting negroes, in Nov. and Dec. 1791. It is only fit for a fhipping place for the produce of the adjacent country, and for that of the rich plains of the Cul de Sac to the northward. The ifland of Gonave to the weftward would enable a fquadron to block up the port. The line of communication between Port au Prince and the town of St. Domingo, is by the ponds, and through the towns of Neybe, Azua, Bani, &c. The diftance from Port au Prince to St. Domingo city being 69 leagues caft by fouth ; for they reckon it 14 leagues from the guard El Fondo to Port au Prince. To thorten this

way a little, and particularly to rended it lefs difagreeable, one may crofs the Brackifh Pond in a canoe. Port au Prince is 7 leagues east by north of the town of Leogane, and about 50 fouth by east as the road runs, from Port de Paix. N. lat. 18. 34. W. long. from Paris 74. 45.

Paris 74. 45. PORT BANKS, on the north-welt coaft of N. America, lies fouth eaft of Pitt's Ifland, and north-weft of Point Bukarelli.

PORT CABANAS, on the northern fide of the fland of Cuba, lies E. by N. of Bahia Hondu, and weftward of Port Mariel.

PORT DAUPHIN, a bay on the eaftern coaft of Cape Breton Island, about 18 leagues S. by W. of Cape Raye in Newfoundland.

PORT DE PAIX, a jurifdiction and fea-port, on the north fide of the ifland of St. Domingo, towards the weftern end, and opposite the ifland of Tortue, 4 leagues diffant. The jurifdiction contains 7 parifhes; the exports from which, from Jan. 7, 1789 to Dec. 37, of the fame year, were as follows 331,900 lbs. white fugar; 515,500 lbs. brown fugar; 1,957,618 lbs. coffee; 35,154 lbs. cotton; 29,181 lbs. indigo. The duties on exportation of the above amounted to 9,407 dollars 60 cents. It is 30 leagues north of St. Mark, 17 E. by N. of the Mole, and 194 weftward of Cape Francois. N. lat. 19, 54. W. long. from Paris 75, 12.

long. from Paris 55. 12. PORT DE LA CHAUDIERE, on the Se coaft of the ifland of St. Domingo, lies at the eaftern entrance of the Bay of Occa, which is 18 leagues W. by S. of the city of St. Domingo. This port is large, open, and deep enough to admit veffels of any burden.

PORT DESIRE, a harbour on the E. coaft of Patagonia, S. America, where veifels fometimes touch in their paffage to the South Sea. It is about 150 miles N. E. of Port St. Julian. S. lat. 47. 6. W. long. 64. 14.

PORT DU PRINCE, a town on the northern coaft of the island of Cuba, having a good harbour. The town fands in a large meadow, where the Spaniards feed numerous hards of cattle.

PORT EGMONT, on the N. coaft of one of the Falkland Ifles, and towards the W. end of that coaft. It is one of the most extensive and commodious. If f harbours 450

harbours in the world; fo that it has been afferted that the whole navy of Great-Britain might ride fecurely in it. Commodore Byron difcovered this excellent harbour in 1775, on being fent to take poffeffion of the islands for the British government.

PORTER, a lake of Nova-Scotia, which empties itself into the ocean; 5 leagues eastward of Halifax. It is 15 miles in length, and half a mile in width, with iflands in it.

PORTERFIELD, a small settlement in York co. District of Maine.

PORTERO, a river of Peru, which empties into the fea at the city of Baldivia.

PORT JULIAN, or Port St. Juhan, a harbour on the E. coaft of Patagonia, in S. America, 150 miles S. by W. of Port Defire. It has a free and open entrance, and falt is found near it. The continent is not above 100 leagues broad here. Befides falt ponds, here are plenty of wild cattle, horfes, Peruvian theep, and wild dogs, but the water is bad. S. lat. 49. 10. W. long. 68. 44.

450. PORTLAND, a post-town and port of entry, in Cumberland co. District of Maine. It is the capital of the diffrict, and is fituated on a promontory in Cafco Bay, and was formerly a part of Fal-mouth. It is 50 miles S. by W. of Wifcaffet, 223 N. by W. of Bofton, and 469 N. E. of Philadelphia. In July, 1786, this part of the town, being the most pupulous and mercantile, and fituated on the harbour, together with the iflands which belong to Falmouth, was incorporated by the name of Portland. It has a most excellent, fafe, and capacious harbour, which is feldom or never completely frozen over. It is near the main ocean, and is easy of access. The inhabitants carry on a confiderable fo-reign trade, build fhips, and are largely concerned in the fifhery. It is one of the most thriving commercial towns in the Commonwealth of Massachusetts. Although three-fourths of it was laid in afhes by the British fleet in 1775, it has fince been entirely rebuilt, and contains about 2300 inhabitants. Among its public buildings are 3 churches, 2 for Congregationalifts, and 1 for Epifcopalians, and a handfome court-houfe. A light-house was crected in 1790, on a nt of land called Portland Head, at the entrance of the harbour. It is a

ftone edifice, 72 feet high, exclusive of the lanthorn, and ftands in lat. 44. 2. N. and long 69. 52. W. The following directions are to be observed in coming into the harbour. Bring the light to bear N. N. W. then run for it, allowing a fmall diftance on the larboard hand ; and when abreaft of the fame, then run N. by W. This courfe will give good anchorage from half a mile, to a mile and a half. No variation of the compafs is allowed. The works crected in 1795, for the defence of Portland, confift of a fort, a citadel, a battery for 10 pieces of cannon, an artillery-ftore, a guard-houfe, an air furnace for heating fhot, and a covered way from the fort to the battery.

PORTLAND Head, in Cafeo Bay, in the Diffrict of Maine, the promontory on which the light-house above described flands. From the light house to Alden's Ledge, is 4 leagues S. S. E. High water in Portland harbour, at full and change, 45 minutes after 10 o'clock. See Portland.

PORTLAND Point, on the fouth coaft of the island of Jamaica, and the most foutherly land in it, lie in lat. 17. 48. N. and long. 77. 42. W.

PORTLOCK's Harbour, on the N. W. coaft of N. America, has a narrow entrance compared with its circular form within. The middle of the entrancelies in lat. 57. 43. 30. and long. 136. 42. 30. W

PORT Marquis, a harbour on the coaft of Mexico, in the North Pacific Ocean, 3 miles eaftward of Acapulco, where thips from Peru frequently land their contraband goods. N. lat. 17. 27. W. long. 102. 26.

PORTO Bello, a fea-port town of S. America, having a good harbour on the northern fide of the Ifthmus of Darien, in the province of Terra Firma Proper, nearly opposite to Panama on the fouthern fide of the ifthmus. It is fituated close to the fea, on the declivity of a mountain which furrounds the whole harbour. It abounds with reptiles in the rainy feafon, and at all times is very unhealthy; and is chiefly inhabited by people of colour, and negroes. It was taken by Admiral Vernon in 1742, who demolifhed the fortifications. But it is now ftrongly fortified. N. lat. 9. 34. 35. W. long. 81, 52. See Darien and Panama.

PORT the Carac ca, 6 le habited tors. PORT

America coaft of t a great n ful attac lat. 10. PORT on the n 300 mile 186 N. merly a

taken by caneers, recovere fprings (PORT

lands, in

the Span 40 bros fquare n of the lands: a woods, fruitful the oth watered healthy which f tle here fiderabl contain only 6 then re

head o 1,515 tle; S quinta ton; quinta bacco, Por

> that n fmall ifland ed by harbo where utmof built, the fo ted a inacce ever,

Rico, 1

PORTO

t was

who

it is

35.

Pa-

RTO

12.4

the Caraccas, in Terra Firma, S. America, 6 leagues from Leon; chiefly inhabited by fifhermen, failors, and factors.

POR

PORTO Cavalle, a fea-port town of S. America, in Terra Firma, and on the coaft of the Caraccas. The British loft a great many men here, in an unfucceffful attack by fea and land, in 1743. N. lat. 10. 20, W. long. 64. 30.

PORTO del Principe, a fea-port on the north coaft of the ifland of Cuba. 300 miles S. E. of the Havannah, and 186 N. W. of Baracoa. It was formerly a large and rich town, but being taken by Capt. Morgan, with his buccaneers, after a ftout reliftance, it never recovered itfelf. Near it are feveral fprings of bitumen.

Porto RICO, one of the Antille Iflands, in the Weft-Indies, belonging to the Spaniards, about 100 miles long, and 40 broad, and contains about 3,200 fquare miles. It is so leagues S. S. E. of the island of St. Domingo. The lands are beautifully diversified with woods, vallies, and plains, and are very fruitful; yielding the fame produce as the other iflands. The ifland is well watered by fprings and rivers, but is unhealthy in the rainy feafons. Gold, which first induced the Spaniards to fettle here, is no longer found in any confiderable quantity. In 1778, this ifland contained 80,660 inhabitants, of which, only 6,530 were flaves. There were then reckoned upon the fland, 77,384 head of horned cattles \$3,195 horfes; 1,515 mules; 49,058 head of finall cattle; 5,861 plantations, yielding 2,737 quintals of fugar ; 1,163 quintals of cotton; 19,556 quintals of rice; 15,216 quintals of maize ; 7,458 quintals of tobacco, and 9,860 quintals of molafies.

PORTO Rico, or St. Juan de Porto Rico, the capital town of the island of that name, above deferibed, ftands on a fmall island, on the north fide of the ifland of Porto Rico, to which it is joined by a cauleway, extending acrois the harbour, which is very fpacious, and where the largest veffels may lie in the utmoft fecurity. It is large and well built, and is the fee of a bifhop; and the forts and batteries are fo well fituated and ftrong, as to render it almost inacceffible to an enemy. It was, however, taken by Sir Francis Drake, and af-

PORTO Cabello, a maritime town of | terwards by the Earl of Cumberland. It is better inhabited than moft of the Spanifh towns, being the centre of the contraband trade carried on by the British and French, with the king of Spain's fubjects. In 1615, the Dutch took and plundered this city ; but could not re-tain it. N. lat. 18. 20. W. long. 65. 35.

PORTO Santo, an ifland on the coaft of Peru, a league W. N. W. of the port and City of Santo or Santa, nearly opposite to the port of Ferol, a league diftant northerly, and 9 N. W. of Guanape Ifland.

PORTO Santo, a port fituated in the mouth of the river of its name, on the coaft of Peru, N. N. E. of Point Ferol, and 6 leagues S. E. of Cape de Chao or Chau, and in lat. 8. 47. S.

PORT Paix. See Port an Paix.

PORTO Seguro, a captainship on the coaft of Brazil, in S. America, bounded E. by the government of Rio dos Hilios ; N. by the South Atlantic Ocean; S. by Spiritu Santo, and weft by the coun-try of the Tupick Indians. The country is very fertile.

Porto Seguro, the capital of the above captainship, is feated on the top of a rock, at the mouth of a river, on the fea-coaft, and inhabited by Portu-

guefe. S. lat. 17. W. long. 38. 50. PORT Penn, a town of Newcastle co. Delaware, on the weft fhore of Delaware river, and feparated from Reedy Island on the east by a narrow channel. It contains about 30 or 40 houfes, and lies 50 miles below Philadelphia. See Penn and Reedy Ifland.

PORT Royal, an island on the coast of South-Carolina, is feparated from the main land on the weft by Broad river. It confifts of about 1000 acres of excellent land; and on it flands the town of Beaufort. It has an excellent harbour, fufficient to contain the largeft fleet in the world. It is 6 leagues N. E. I E. of Tybee light-house, at the mouth of Savannah river. N. lat. 32. 12, W. long. 80. 54. At Port Royal Entrance it is higher water at full and change a quarter paft 8 o'clock.

PORT Royal, in Nova Scotia. See Annapolis Royal.

PORT Royal, a post-town of Virginia, feated on the fourth bank of Rappahannock river, in Caroline co. It is laid out on a regular plan, and contains about 200 houfes which make a handfome ap-Ff 2 pearance,

POR

155

pearance, being built of brick. Here are 3 churches, viz. for Epifcopalians, Prefbyterians, and Methodiats. It is 22 miles fouth-eaft of Fredericksburg, 53 above Urbanna, and 330 fouth-weft of Philadelphia. N. lat. 32. 13. W. long. 77. 34.

PORT Royal, on the S. fide of the illand of Jamaica, formerly called Puerta de Caguaya, once a place of the greateft wealth and importance in the Weft-Indies, is now reduced by repeated ca-lamities to 3 ftreets, a few lanes, and about 200 houfes. It contains, however, the royal navy-yard, for heaving down, and refitting the king's thips; the naval hospital, and barracks for a regiment of foldiers. The fortifications are kept in excellent order, and vie in Arength, it is thid; with any fortrefs in the British dominions. The excellence of the harbour, and its fituation, were fo alluring, that it was not until the town had been 3 times entirely defroyed, (first by a terrible earthquake, the oth of June 1692; then by a great fire, 10 years after, and laftly, by a hurricane in 1782, the most terrible on record) that the inhabitants could be prevailed upon, to relinquish this ill-fated spot. After this laft calamity, they refolved to remove to the opposite fide of the Bay, where they built Kingfon, now the capi-tal of the island. In the harbour of Port Royal, veffels of 700 tons can lie clofe along fhore. N. lat. 18. 36. W. long. 76. 45.

PORT Royal, a town and harbour in the ifland of Martinico, in the Weft-Indics; which, with St. Peter's, are the chief places of the ifland. N. lat. 14. 36. W. long. 61. 9.

PORT Royal, in the ifland of Otaheite.

PORT Royal, an island and harbour. in the fouth-well part of the Gulf of Mexico, at the bottom of the Bay of Campeachy. The harbour is 18 leagues S. W. by S. of Champetan; and the island, 3 miles long and s broad, lies weft of the harbour.

PORT St. John, a fmall town in the province of Nicaragua, in New-Spain, at the mouth of a river on the N. Pacific Ocean. The harbour is fafe and rapacious, and is the fea-port of the city of Leon, 30 miles to the S. E. N. lat. 12 10. W. long. 87.38.

452. PORTSMOUTH, the metropolis of New-

POR

Hampfhire, and the largeft town in the State, and its only fea-port, is fituat-ed about two miles from the fea, on the fouth fide of Pifeataqua river. It is the fhire town of Rockingham co. and its harbour is one of the fineft on the continent, having a fufficient depth of water for veffels of any burden. It is defended against storms by the adjacent land, in fuch a manner, as that thips may fecurely ride there in any feation of the year; nor is it ever frozen, by reafon of the firength of the current, and narrownefs of the channel. Befides, the harbour is fo well fortified by nature, that very little art will be necelfary to render it impregnable. Its vici-nity to the fea renders it very convenient for naval trade. A light-house, with a fingle light, ftands on Newcaftle Ifland, at the entrance of the harbour, in lat. 43. 5. north, and long. 70. 41. weft. Ships of war have been built here; among others, the America, of 74 guns, launched November, 1782, and prefented to the king of France, by the Con-grefs of the United States: Portfinouth contains about 640 dwelling-houfes, and nearly as many other buildings, befides those for public use, which are 3 Congregational churches, r Episcoal church, 1 for Univerfalifts, a State-houfe, a market-houfe, 4 fchool-houfes, a workhouse, and a bank. The exports for one year, ending September 30, 1794, amounted to the value of 153,865 dollars. A fettlement was begun here in 1623, by Captain Malon and other merchants, among whom Sir F. Gorges had a fhare. They defigned to carry on the fiftery, to make falt, trade with the natives, and prepare lumber. As agriculture was only a fecondary object, the fettlement failed. The town was incorporated in 1633. It is 10 miles fouth-westerly of York, in the District of Maine, 22 northerly of Newbury-Port, 65 N. N. E. of Bofton, and 411 N. E. by N. of Philadelphia.

PORTEMOUTH, a township of good land on the N. end of Rhode-Ifland, Newport co. containing 1,560 inhabitants, including 17 flaves, on the road, from Newport to Briftol.

PORTSMOUTH, a finall fea-port town of N. Carolina, in Casteret co. on the N. end of Core Bank, near Ocrecock. Inlet. Its chief inhabitants are fifthermen and pilots. 153.PORT ing, and i co. Virgi of Eliza mile dift: conftitute contains inhabitar III miles foutherly PORT W. fide the We Rupert's and the PORT land, an a little fmall ft its nam N. bank Point, It conta Epifcop and a v tobacco brated It is s o from Baltim Philade POR POR lies bet degree W. los iflands

on thei

Fernan

ines.

of the

the laf

drawn

vres, (

Befide

receiv

cocoa

coffee

S. co:

Ifland

the at

of Lo

city (

tain

COMP

quan The

Po

Po

453. PORTEMOUTH, a pleafant, flourifhing, and regularly built town in Norfolk co. Virginia; fituated on the weft fide of Elizabeth river, appointe to and a mile diffant from Norfolk; both which confitute but one port of entry. It contains about 300 houfes, and 1,702 inhabitants, including 616 flaves. It is 311 miles E. by S. of Peterfburg and 300 foutherly of Philadelphia. See Norfolk. PORTEMOUTH, a town on the N.

PORTSMOUTH, a town on the N. W. fide of the ifland of Dominica, in the Weft-Indies; fituated on Prince-Rupert's Bay, between the falt-works and the coaft.

PORT Tobacco, a post town of Maryland, and capital of Charles co. firuated a little above the confluence of two fmall ftreams which form the creek of its name, which empties through the N. bank of the Patownac, at Thomas's Point, about 4 miles below the town It contains about 80 houses, and a large Epifcopal charch, not in good repair, and a warehouse for the inspection of tobacco. In the vicinity are the celebrated cold waters of Mount Mitery. It is 52 miles S. W. of Annapolis, 9 from Allen's Fresh, 83 S. S. W. of Baltimore, and 184 S. W. by S. of Philadelphia.

PORTUGAL Paint. See Tortue.

PORTUGUESE America, or Brazil, lies between the equator and the 3 sth degree of S. lat. and between 35 and 60 W. long. On the coaft are three fmall iflands, where thips touch for provisions on their voyage to the South Seas, viz. Fernando, St. Barbaro, and St. Catherines. See Brazil, Since the difcovery of the mines of Brazil, that is, within the laft 60 or 70 years, Portugal has drawn from Brazil 2,400 million of livres, or 100 millions of pounds fterling. Befides these large fums of money, the receives from Brazil large quantities of cocoa, fugar, rice, train-oil, whale-bone, coffee, and medicinal drugs.

POTATOE, a bay fo named, on the S. coaft of the island of St. Christopher's Island, in the West-Indies.

POTOSI, a town of Peru, fituated in the archbishopric of Plata, and province of Los Charcos, 75 miles S. E. of the city of La Plata. The famous mountain of this name is known all over the commercial world, for the immenfe quantities of filver it has produced. The mines in its vicinity are now much

exahufted, although still very rich ; an the town which once contained 90,000 inhabitants, Spaniards and Indians, (of which the latter compoled above four-fifths) does not now contain above 25,000. The principal mines are in the northern part of the mountain, and their direction is from N. to S. The most intelligent people of Peru have observed that this is the general direction of the richest mines. The fields round Potofi are cold, barren, and beau little elfe than oats, which feldom ripen. but are cut up and given for forage in the blade; and provisions are brought here from the neighbouring provinces. It is 300 miles S. E. of Arca, lat. 21. S. and long. 77. W.

.

POTTERS, a township of Pennsylvania, fituated on Susquehanna river. See Northumberland County. POTTERSTOWN, bin Hunterdon co.

POTTERSTOWN, in Hunterdon co. New-Jerfcy, is about 5 miles E. of Lebanon, and about 22 N. W. of New-Brunfwick.

POTTSCROVE, a polt-town of Pennfylvania, fituated on the N. bank of Schuylkill river, 47 miles S.E. of Reading, and 37 N. W. of Philadelphia.

POUGHKEEPSIE, a post-town of New-York, and capital of Durchefs co. delightfully fituated a mile from the E. bank of Hudíon's river, and contains a number of neat dwellings, a court-house, a church for Prefbyterians, one for Epilcopalians, and an academy. Here is allo a printing-office. It is about 28 miles N. W. of Danbury, in Connecticut, 84 N. of New York city, 81 S. of Albany, and 180 N. E. by N. of Philadelphia. The townflip is bounded foutherly by Wappinger's Kill, or Creek, and wefterly by Hudíon's river. It contains 2,529 inhabitants, including 429 electors, and 199 flaves.

POULTNEY, a fmall river of Vermont, which falls into Eaft Bay, together with Caftleton river, near Col. Lyons's iron works.

POULTNEY, a confiderable and flourifhing township of Rutland co. bounded westerly by Hampton in New-York, which adjoins Skeensburgh on the west. It contains 4, 151 inhabitants.

POUMARON, or Pumaron, a river on the coaft of Surinam. S. America, whole E.point is Cape Naffau, or Cape Drooge.

POUNDRIDGE, a township in West Chefter co. New-York, bounded fouth-Ff 3 erly

· · · in the ituaton the It is + and on the pth of It is jacent thips feation n, by urent, Beied by necel s vicienient with a Ifland. in lat. weft. here : guns, refent : Con mouth is, and bendes Conhurch, afe, a workts for 1794-5 dolhere in other Forges carry e with As object, m was miles Diffrict vburynd 411 f good Ifland,

habite road

on the recock

DUTH,

erly by the State of Connecticut, eafterly and northerly by Salem, and wefterly by Bedford and Mahanus river. It contains 1,062 free inhabitants, of whom 141 are electors.

POWELL'S Greek, in the State of Tenneffee, rifes in Powell's Mountain, runs S. westerly, and enters Clinch river, through its northern bank; 38 miles N. E. of Knoxville. It is faid to be navigable in boats 80 miles.

POWHATAN, the ancient name of James river in Virginia.

• POWHATON, a county of Virginia, bounded N. by James river, which feparates it from Goochland, and fouth by Amelia co. It has its name in honour of the famous Indian king of its name, the father of Pocahontas. It contains 6,822 inhabitants, including 4,325 flaves. The court-house in the above county is 27 miles from Carterfville, 20 from Cumberland court-house, and 310 from Philadelphia.

POWNAL, a flourishing township in the fouth-west corner of Vermont, Bennington co. fouth of the town of Bennington. It contains 1,746 inhabitants. Mount Belcher, a portion of which is within the town of Pownal, stands partly in 3 of the States, viz. New-York, Vermont, and Massichusetts. Mount Anthony, alfo, one of the most remarkable mountains in Vermont, lies between this and Bennington.

POWNALBOROUGH, the fhire town of Lincoln co. Diffrict of Maine, is fituated on the eaft fide of Kennebeck river, and is a place of increating importance, and contains a Congregational church, and feveral handfome dwelling-houfes. The flourithing port and poft-town of Wifcaffet is within the townfhip of Pownalborough. This town was incorporated in 1760, and contains in all 2,055 inhabitants. It is 13 miles north of Batharo N. E. of Portland, 171 N. by E. of Bofton, and 525 N. E. of Philadelphia.

Powow, a finall river of Effex co. Maffachufetts, which rifes in King⁴⁰on in New-Hampfhire. In its courfe, which is S. E. it paffes over feveral falls, on which are mills of various kinds, and empties into Merrimack river, 7 miles from the fea, between the towns of Salifbury and Amefbury, connected by a convenient bridge, with a draw, acrofs the river. It is navigable a mile from

its mouth, and many veffels are built on its banks. See Almfbury and Salifbury. POYAIS, a town of N. America,

POYAIS, a town of N. America, fituated on the welk fide of Black river, in the province of Honduras, about 110 miles W. N. W. of Secklong, and 55 fouth of Cape Cameron, which forms the north point of the entrance of the river in the Sea of Honduras.

PRAIRIE de Rocher, la, or The Rock Meadows, a fettlement in the N. W. Territory, on the east fide of the Misfisippi; fituated on the east fide of a stream which empties into the Misfispi, rz miles to the fouth. It is 15 miles N. W. of Kaskaskias village, and 5 N. E. by E. of Fort Chartres. About 20 years ago it contained 100 white inhabitants and 80 negroes.

PRAIRIE, La, a populous little village, with narrow dirty freets, on the river St. Lawrence in Canada, 18 miles north of St. John, and 9 fouth-weft of Montreal.

PRASLIN Port, is on the N. fide of the islands of the Arfacides, in S. lat. 7. 25. E. long. from Paris 155. 32. ; difcovered and entered by M. de Surville, Oft. 12, 1769. The islands which form this port are covered with trees, and at high water are partly overflowed. The artful natives entrapped fome of Surville's men in an ambufcade, in confequence of which 30 or 40 of the favages were killed. The inhabitants of thefe islands are in general of the negro kind, with black woolly hair, flat nofes, and thick lips.

PRESCOTT, a fmall plantation in Lincoln co. Diffrict of Maine, which, together with Carr's plantation, has 159 inhabitants.

PRESQUE Ife, a fmall peninfula, on the fouth eaft thore of Lake Erie, almost due fouth of Long Point on the oppofite fide of the lake; 15 miles from Fort Bœuf, and 60 N. by W. of Venango, on Allegany river. The garrifon about to be crected by the United States at Prefque Ifle, will be upon a very commanding fpot, just opposite the en-trance of the bay. The town commences 30 yards weft of the old British fort, leaving a vacancy of 600 yards for a military parade and public walk. The town, which is now building, will extend nearly 3 miles along the lake and z mile back. It lies in lat. about 42. 10. N.

PRESTON,

PREST co. Conne Norwich, Shetucket incorporat inhabitant Here are and a foci PRESU

berland c

fed by Se

Cafco Ba Bay. PRINC ginia, be tide-wate bitants, i cademy i into a co den Sydn at which miles fr so from ! adelphia PRIN ington's PRIN Georget taining 3,418 al fends 4 to the S PRIN of Calv erly of eafterly Macka PRIM town d 11,762 whites, reprefer State le PRI ginia, l walhes breadt inhabi this r Bland church for Fr ings.

meetin

Seem 1

ful co

ton h

fumm

PRESTON, a town in New-London eo. Connecticut, 6 or 8 miles eaft of Norwich, from which it is divided by Shetucket river. The townfhip was incorporated in 1687, and contains 3,435 inhabitants, who are chiefly faimers. Here are two Congregational churches, and a fociety of Separatifts.

PRESUMSCUT, a fmallriver of Cumberland co. Diffrict of Maine, which is fed by Sebacook Lake, and empties into Cafco Bay, east of Portland. See Cafco Bay.

PRINCE EDWARD, a county of Virginia, between the Blue Ridge and the side-waters. It contains \$,100 inhabitants, including 3,986 flaves. The academy in this county has been erected into a college, by the name of " Hampden Sydney College." The court-houle, at which a poft-office is kept, is 28 miles from Cumberland court-houle, so from Lynchburg, and 358 from Philadelphia.

PRINCE EDWARD's Ifles. See Wafbington's Ifles.

PRINCE FREDERICK, a parifh in Georgetown dittrict, S. Carolina, containing 8,135 inhabitants; of whom 3,418 are whites, and 4,685 flayes. It fends 4 reprefentatives and one fenator to the State legiflature.

PRINCE FREDERICK, the chief town of Calvert co. Maryland; 3 miles foutherly of Huntingtown, and 6 northcalterly of Benedict, by the road to Mackall's ferry.

PRINCEGEORCE, a parish of Georgetown district, S. Carolina, containing 11,762 inhabitants; of whom 5,031 are whites, and 6,651 flaves. It fends 5 reprefentatives and one fenator to the State legislature.

PRINCE GEORGE, a county of Virginia, bounded N. by James river, which walkes it about 35 miles. The medium breadth is 16 miles. It contains 8,173 inhabitants, including 4,519 flaves; of this number 1,200 are refidents in Blandford. There are 5 Epifeopal churches in the county, one meeting for Friends, and feveral Methodift meetings. The Baptifts have occasional meetings, and to this feft the negroes feem particularly attached. It is a fruitful country, and abounds with wheat, corn, flax, cotton, and tobacco. Cotton here is an annual plant; and in fummer, molt of the inhabitants appear. in outer garments of their own manufacture. The timber confifts of oaks of various kinds, and of a good quality, fufficient to build a formidable navy. and within a convenient diffance of navigation. It has all the different fpecies known in the eaftern States, and others which do not grow there. Here is alfo abundance of wild grapes, flowering fhrubs, farfaparilla, fnake-root, and ginfeng. Apples are inferior in fpirit and tafte to those in the eastern States ; but peaches have a flavour unknown in those States. The almond and fig will grow here in the open air, if attended to. Immenfe quantities of pork and bacon are cured here, and indeed form the principal food of the inhabitants. Veal is excellent; mutton indifferent : poulsry of every kind in perfection and in abundance. The winters are fhort and generally pleafant; and the country cannot be confidered as unhealthy.

PRINCE GEORGE, a county of Maryland, on the weffern fhore of Chefapeak Bay, fituated between Patowmac and Patuxent rivers, and is watered by numerous creeks which empty into thofe rivers. The eaftern corner of the territory of Columbia, borders upon the weft part of this county. It contains 21,344 inhabitants, of whom 11,176 are flaves.

PRINCE OFWALES, Cape, is remarkable for being the moft wefterly point of the continent of N. America, and the eaftern limit of Behring's Straits, between Afia and America; the two continents being here only about 39 miles apart. The mid channel has 28 fathoms water. N. lat. 65. 46. W. long. 168. 15.

PRINCE OF WALES, Fort, in New North Wales, N. America, a factory belonging to the British Hudson's Bay Company, on Churchill river. The mean heat here is 18 7

Leaft heat 45 Greateft heat 85

It lies in lat. 58.47. 30. N. and long. 94. 7. 30. W.

PRINCE OF WALES *Mand*, in the S. Pacific Ocean, is about 20 leagues long, and W. 10 S. diftant 48 leagues 110m Otaheite, or King George's Ifland. S. lat. 15. and W. long. 151: 53. at the W. end. The variation of the needle in 1766, was 5. 30. E.

PRINCE RUPERT'S Bay, on the N. F f 4

rica. river, 110 d 55 urms f the Rock . W. Miffiof a fippi, s N. N.E. vears tants t viln the miles eft of ide of at. 7ville. form nd at The Sur-:onferages thefe kind. and n in hich, 8 1 59 a, on Imoft

ilt an

t 42.

polite

Fort

ango,

m a-

States

e en-

iences

fort,

for a

The

ll ex-

and z

406

W. coaft of the ifland of Dominics, one of the Caribbee Iflands, where there is excellent fhelter from the winds. It is deep, capacious, and fandy, and is the principal bay in the ifland. It is of great advantage in time of a war with France, as a fleet may here intercept all their Weft-India trade. On this bay is fituated the new town of Portfmouth, N. of which is a cape called Prince Rupert's Head.

PRINCE'S BAY, on the S. fide of Staten Ifland, in New-York State.

PRINCESS ANN, a maritime county of Virginia, bounded E. by the Atlantic Ocean, and W. by Norfolk co. It contains 7,793 inhabitants, of whom 3,202 are flayes.

PRINCESS ANN, a post-town of Maryland, on the eaftern fhore of Chefapeak bay in Somerfet co. on the E. fide of Monokin river, 9 miles S.E. of Bal-timore, and 178 S. by W. of Philadelphia. It contains about 200 inhabitants. PRINCETON, a township of Maffachufetts, in Worcefter co. 15 miles N. by Weft of Worcefter, and 52 W. by N. of Bofton. The township contains 19,000 acres of elevated hilly, but ftrong, and rich land, adapted to grafs and grain. Excellent beef, butter, and cheete, are its principal productions. The manfion-house and farm of his Honour Lieut. Governor Gill, one of the most elegant fituations, and fineft farms in the commonwealth, is in this town, and adds much to its ornament and wealth. A handfome Congregational church has lately been erected, on a high hill, and commands a most extensive and rich prospect of the furrounding country. Wachulett Mountain, the most noted in the State, is in the north part of the township. Here, as in many other towns, is a valuable focial library. Princeton was incorporated in 1759, and contains 1,016 inhabitants.

PRINCETON, a post-town of New-Jerfey, fituated partly in Middlefex, and partly in Somerfet counties. Naffau Hall College, an infitution which has produced a great number of eminent fcholars, is very pleatantly fitueted in the compact part of this town. Here are about 80 dwelling-houfes, and a brick Prefbyterian church. The college edifice is a handfome ftone building, of 180 feet by 54, four ftories high, and ftands on an elevated and healthPRI

and delightful profpect. The eftablishment, in 1796, confifted of a prefident, who is also profeffor of moral philofophy, theology, natural and revealed; history, and eloquence; a professor of mathematics, natural philosophy, and aftronomy; a professor of chymistry, which subject is treated in reference to agriculture and manufactures, as well as medicine : belides thefe, two tutors have the instruction of the two lowest claffes. The choice of the claffical books, and the arrangement of the feveral branches of education, of the lectures, and of other literary exercifes, are fuch, as to give the fludents the beft opportunity for improvement, in the whole Encyclopedia of fcience. The number of fludents is from 70 to 90, belides the grammar fchool. The annual income of the college at prefent, by the fees of the fludents, and otherwife, is about froco currency a year. It has, befides, funda, in poffeffion, through the extraordinary liberality of Mr. James Leflie, of New-York, and Mrs. Efther Richards of Rahway, to the amount of 10,000 dolls. for the education of poor and pious youth for the ministry of the gofpel; and the reversion of an eftate in Philadelphia for the fame purpole, of between 200/and £300 per annum, a legacy of the late Mr. Hugh Hodge, a man of eminent piety, which is to come to the college at the death of a very worthy and aged widow. The college library was almost wholly dettroyed during the late war; but out of the remains of that, and by the liberal donations of feveral gentlemen, chiefly in Scotland, it has collected one of about 2,300 volumes. There are belides this, in the college, two libraries belonging to the two literary focieties, into which the fludents have arranged themsclves, of about 1,000 volumes; and the library of the prefident, confifting of 1,000 volumes more, is always open to the fludents. Before the war, this college was furnished with a philosophical apparatus, worth £ 500, which (except the elegant orrery conftructed by Mr. Rittenhouse) was almost entirely destroyed by the British army in the late war. Princeton is 13 miles N. E. of Trenton, 18 S.W. of Brunfwick, 53 S. W. of New-York, and 42 N. E. of Philadelphia. N. lat. 40. 22. 12. W. long. 74. 34. 45.

PRINCETON,

PRINCE N. Carolin rough, 35 Philadelph PRINCI ginia, bou

by Patow

from Ma inhabitant

PRINC

PRINC

fort diffri

on the N.

eaftward

At its m

gue, Rof Captain 1 half of la exclutive which w PRO. PROS of Main Buckftor miles be PROS of Nova Ifland es of St. N PROT northern Hampfh 1769, 1 PRO into Na of Rho branche Maffach Provid. miles fr oyiters, PRO Ifland ! N. and co. on flips, a 82 flav

> iea; fe Narray dence being long a in the Roger

> and the

its exc

aboved

1 W.

PRO

PRINCETON, a small post-town of N. Carolina, 3 miles from Murfreeborough, 35 from Halifax, and 419 from Philadelphia,

PRO

PRINCE WILLIAM, a county of Virginia, boundeft W. by Faquier, and E. by Patowmac river, which divides it from Maryland. It contains 11,615 inhabitants, of whom 4,704 are flaves.

PRINCE WILLIAM, a parifh in Beaufort diffriet, S Carolina,

PRINCE WILLIAM'S Sound, fituated on the N. W. coaft of N. America, lies eaftward of the mouth of Cook's river. At its mouth are three iflands, Montague, Rofe, and Kay. It was judged by Captain Cook to occupy a degree and a half of latitude, and two of longitude, exclusive of its arms and branches, which were not explored.

PRO. See Point le Pro.

PROSPECT; Frankfort, in theDiffriet of Main, is now to called. It adjoins Buckfton on Penoblcot river, and is 16 miles below Orrington.

PROSPECT Harbour, on the S. coaft of Nova-Scotia, has Cape Sambro and Idand eattward, and is a leagues N. E. of St. Margaret's Bay.

PROTECTWORTH, a township in the northern part of Cheshire co. New-Hampshire. It was incorporated in 1769, and contains 210 inhabitants.

PROVIDENCE, a river which falls into Narragantiet bay on the W. fide of Rhode Illand. It rifes by feveral branches, part of which come from Maffachuletts. It is navigable as far as Provid nce for fhips of 900 tons, 30 miles from the fea. It affords fine fifh, oysters, and lobsters.

PROVIDENCE, a county of Rhode-Island State, bounded by Massachusers N. and E. Connecticut W. and Kent co. on the fourh. It contains 9 townships, and 24, 391 inhabitants, including 2 staves. Its chief town is Providence, and the town of Scituate is famous for its excellent cannon foundery.

PROVIDENCE, the chief town of the above county, fituated 30 miles N. by W. 5 W. from Newport, and 35 from the ica; feated at the head of navigation of Narraganfet Bay, on both fides of Providence river the two parts of the town being connected by a bridge 160 feet long and 22 wide. It is the oldeft town in the State, having been fettled by Roger Williams and his company in PRO

1636; and lies in lat. 47. 49. N. and long. 71. 23.W. 44. miles S. by W. of Botton, and 291 north-east of Philadelphia. Ships of almost any fize fail up and down the channel, which is marked out by ftakes, crected at points of fhoals and beds lying in the river, fo that a ftranger may come up to the town with-out a pilot. A thip of 950 tons, for the East-India trade, was lately built in this town, and fitted for fea. In 1764, there were belonging to the county of Provi-dence 54 fail of veffels, containing 4,320 tons. In 1790, there were 129 vellels, containing 11,942 tons. This town fuffered much by the Indian war of 1675. when a number of its inhabitants removed to Rhode-Ifland for thelter. In the late war, the cafe was reverfed a many of the inhabitants of that island removed to Providence. The public buildings are an elegant meeting house for Baptifts, 80 feet iguare, with a loft and beautiful steeple, and a large bell caft at the Hope Furnace in Scituate ; a meeting-houfe for Friends and Quakers ; 3 for Congregationalifts, one of which, lately erected, is the most elegant perhaps in the United States; an Epifcopal church; a handfome court-houfe, 70 feet by 40, in which is deposited a library for the use of the inliabitants of the town and country; a work-houfe; a mark-t-houfe, 80 feet long and 40 wide, and a brick ichool house, in which 4 schools are kept. Rhode Island college is established at Providence. The elegant building erected for its accommodation, is lituated on a hill to the eaft of the town; and while its elevated fituation renders it delightful, by commanding an extensive variegated prospect, it furnishes it with a pure, falubrious air. The edifice is of brick, 4 ftories high, 1 50 feet long, and 46 wide, with a projection of 10 feet each fide. It has 48 rooms for ftudents, and 8 larger ones for public uses. The roof is flated. It is a flourishing feminary, and contains upwards of 60 ftudents. It has a library containing between 2 and 3000 volumes, and a valuable philosophical apparatus. The houtes in this town are generally built of wood, though there are fome brick buildings which are large and elegant. At a convenient diftance from the town, an hospital for the finall-pox and other difeafes has been erected. There are two fpermaceti works, a number of diffilleries, fugarhoufes,

mive lifhdent, lofouled ; # of and iftry, ce to ell as utors weft xoks, veral ures, fuch, pormber is the ne of of the 1000 funds inary New-Is of lolls. pious fpel ; 'hilatween cy of in of o the v and was e late that. veral t has Imes. llege, litedents 1,000 prefimore, lefore with \$ 500, con-Imoft my in es N. wick. N. E.

. 12.

TON,

boufes, and other manufactories. Several forts were crefted in and near the town during the war, which, however, are not kept in repair. It has an extenfive trade with Maffachufetts, Connecticut, and part of Vermont ; with the Weft-Indies, with Europe, and lately with the Eaft-Indics and China. A bank has alto been established here, and a cotton manufactory, which employs zoo hands; with which is connected a mill for spinning cotton, on the model of Sir R. Arkwright's mill. It is crefted at Pawtucket Falls, in North-Providence, and is the first of the kind built in America. The exports for one year, ending Sept. 30, 2794, amounted to the value of 643,373 dollars. It contains 6,380 inhabitants, including 48 flaves.

PROVIDENCE, North, a township of Rhode-Island, in Providence co, north of the town of Providence; fouth of Smithfield, and separated from the State of Massachusetts on the east by Pawtucket river. It contains 1071 inhabitants, including 5 flaves.

PROVIDENCE, a township of New-York, fituated in Saratoga county, taken from Galway, and incorporated in 1796

PROVIDENCE, Upper and Lower, townships in Delaware co. Pennfylvania.

PROVIDENCE, a township in Montgomery co. Pennsylvania.

PROVIDENCE, one of the Bahama Iflands, and the fecond in faze of thole fo called ; being about 36 miles in length and 16 in breadth. N. lat. 24. 58. W. long. at its eaft part. 77. 21. It was formerly called *Abaco*, and is frequently named *New Providence*. Chief town, Naffau.

PROVIDENCE, an uninhabited island on the coast of Honduras, 11 miles long and 4 broad. It has a fertile foil, wholefome air, and plenty of water; and might be easily fortified. It is feparated from the continent by a narrow channel. He are neither ferpents nor venomous reptiles. N. lat. 13. 26. W. long. 80. 45.

PROVINCE, an island in Delaware river, 6 miles below Philadelphia. It is joined to the main land by a dam.

PROVINCE-TOWN is fituated on the hook of Cape Cod, in Barnftable co. Maffichuletts, 3 miles north-welt of Race Point. Its harbour, which is one of the beft in the State, opens to the fouthward, and has depth of water for PUE

any fhips. This was the first port entered by the English when they came to settle in New-England, in 1620. It to fettle in New-England, in 1020. It has been in a thriving and decaying flate many times. It is now rifing, and contains 454 inhabitants; whole fole de-pendence is upon the cod-fiftery, in which they employ 20 fail, great and fmall. Ten of their veffels, in 1790. took 11,000 quintals of cod-fifh. They are to expert and fuccetsful that they have not loft a vefiel or a man in the bufinefs, fince the war. The houfes, in numers, ince the war. I he houses, in number about 90, ftand on the inner fide of the cape, fronting the fouth-eaft. They are one ftory high, and fet upon piles, that the driving fands may pais under them; otherwife they would be buried in fand. They raife nothing from their lands, but are wholly dependent on Boston, and the towns in the vi-cinity, for every vegetable production. There are but 2 horses and 2 yokes of oxen kept in the town. They have about 50 cows, which feed in the fpring upon beach grafs, which grows at intervals upon the fhore; and in fummer they feed in the funken ponds and marfhy places that are found between the fand-hills. Here the cows are feen wading, and even fwimming, plunging their heads into the water up to their horns, picking a fcanty fubliftence from the roots and herbs, produced in the water. They are fed in the winter on fedge, cut from the flats.

PRUCREOS, a cape on the coaft of New-Spain, in the South Sea.

PRUDENCE, a finall island, nearly as large as Canonnicut, and lies N. of it, in Narraganiet Bay. It belongs to the town of Portfimouth, in Newport co. Rhode-Island. The north end is nearly opposite to Briftol on the east fide of the bay.

PUAN, or Green Bay, has communication eaftward with Lake Michigan ; which fee, alfo Green Bay.

PULBLA DE LOS ANGELOS, the prefent capital of the province of Tlaicala, or Los Angelos. See Angelos.

PUEBLO NUEVO, or Newtows, at the hottom of the gulf of Dolce, on the W. coaft of Mexico. It is 7 leagues N. by W. of Baia Honda, or Deep Bay. The ifland of this name is opposite the town and mouth of the river of its name, in the bottom of Fresh Water bay, in lat. about 8. 50. N. and long. 83. 28. W. PUERTO, PUER

PUERTO, the Italian name for port. Names of this description, adopted by the Spaniards, will be found under Port or Porto.

t en.

camé

It ying

and

e de-

/s in

t and

790, They

they n the

rs, in inner

-eaft.

upon país d be

thing

epen-

tion.

es of

ve a-

pring

nter-

niner

: feen

iging

their

from

the

er on

ift of

ly as

of it.

o the

t co.

early

of the

nuni-

gan ;

pre-

lcala,

N, at

n the

ts N. The

town

e, in

a lat.

. w.

RTO,

é

and ween

PUNA, an ifland near the bay of Guyaquil, on the coaft of Peru, about 12 or 14 leagues long from E. to W. and 4 or broad. There is an Indian town of the fame name, on its fouth fide, having about 20 houfes, and a finall church. The houfes all ftand on pofts 10 or 12 feet high, with ladders on the outfide to go up to them.' From the ifland San-ta Clara in the bay of Guyaquil to the weftermost point of the ifland, called Punta Arena, is 7 leagues N. N. E. S. lat. 3. 17. W. long. 81. 6. PUNJO Bay, in East-Florida, See

Chatham Bay. PUNTA Fort, one of the largest batteries or caftles, and the fecond in order, at the mouth of the harbour of the Havannah in the ifland of Cuba. It is alfo called Mefa de Maria, or the Virgin Mary's Table

PUNTA, and PUNTA BRAVA, towns of Mexico. See Angelos.

PUNTA DE PEDRAS, a cape on the north-western extremity of the peninfula of Yucatan, in New-Spain.

PUNTA ESPADA, the S. E. point of the ifland of St. Domingo ; 65 leagues, following the turnings of the coaft, eaftward of Nifao, and 16' leagues from Cape Raphael. The fouth-eaftern part of the ifland confifts chiefly of extensive rich plains.

PUNTA GORDA, a peninfula on the fouth fide of the island of Guba, S. E. of Ifle de Pinos, 90 weft of the gulf of Xagua, and 70 east of Bohia de Corles.

PUNTA NEGRILLO, the western point of the island of Jamaica.

PURIFICATION, a town of New-Mexico, 14 leagues from the weft coaft, and maintains a fifthery near the low lands of Chametla.

PURYSBURG, a handfome town of S. Carolina, fituated in Beaufort diffrict, on the eaftern fide of Savannah river, 37 miles from the ocean, and 20 from the town of Savannah. It contains between 40 and 50 dwelling-houfes, and an Episcopal church. It took its name from John Peter Pury, a Swifs, who lettled a colony of his countrymen here about the year 1733, with a view to the culture fof filk. The mulberry-trees are yet standing, and Some attention is ftill paid to the making of fik.

O U

PUTAWATAMES, or Pointostamies, Indians, who inhabit between St. Jo. feph's and Detroit, and can fumith about 500 warriors. There are two tribes of this name, the one of the river of St. Joseph, and the other of Huron. They were lately hoffile; but at the treaty of Greenville, August 3. 1795, they ceded lands to the United States ; who in return paid them a funn in hand, and engaged to pay them in goods to the value of 1000 dollars a year for ever.

PUTNEY, a thriving town in Windham co. Vermont, on the weft fide of Connecticut river, fouth of Weftminfter. Inhabitants 1848.

Q

UADRAS Ifles, on the N. W. Coaft of N. America, lie between Pintard's Sound and the Straits de Fuca. Nootka Sound lies among these islands. In 1792, two Spanish schooners, and his Brittannic Majefty's thip Difcovery, and brigantine Chatham, pafied through this channel; but the former firft; hence Capt. Ingraham called the illes by the name of the Spanish commander.

QUAMPEAGAN Falls, at the head of the tide on Newichwanock river, which joins Piscataqua river 10 miles from the fea. The natives give the Falls this name, because fifh was there taken with nets. At these falls are a fet of faw and other mills; and a landing place, where great quantities of lumber is rafted on fcows. Here the river has the English name of Salmon Falls river, from the plenty of falmon there caught. In the memory of people who lived 50 years ago, these fifh were to plenty as to be ftruck with fpears on the rocks; but none now alive remember to have feen any there. The faw mills where the dam croffes the ftream are the fure destruction of that fpecies of fifh. Tom-cod or froft-fifh. finelts and ale-wives abound here. The place called Salmon Falls is covered with uleful mills. Above thefe we meet with the Great Falls, where fawmills are continued to great advantage. On many places from Quampegan to the

mills for boards and corn.

QUAKER Town, in Buck's co. Pennfylvania, lies 25 miles N. W. of Newtown, and 33 N. N. W. of Philadelphia.

QUAREQUA, a place fituated in the Gulf of Darien. Here Vafques Nunez met with a colony of negroes ; but how they had arrived in that region, or how long they had refided in it, are not recorded by the Spanish historians.

QUEBEC, the capital, not only of Lower Canada, but of all British America, is fituated at the confluence of the rivers St. Lawrence and St. Charles, or the Little river, about 320 miles from the fea. It is built on a rock, which is partly of marble and partly of flate. The town is divided into Upper and Lower. Near it is a fine lead mine. This city contained in the year 1784, 6472 inhabitants. At the time when the city was founded, in 1608, the tide, it is faid, reached the foot of the rock ; but fince that time the river has funk to far, that a large fpot of ground is left dry, and on this a large fuburb is built, which is flyled the Lower Town, which stands at the foot of a rocky precipice, about 48 feet high. The houfes in the lower town, (as also those in the Upper) are of ftone, ftrong, and well built, and chiefly inhabited by merchants, being conveniently near their bufinefs. The fortifications are extensive but irregular. The natural fituation of the town renders its defence eafy. If attacked by thips from the river, their guns cannot injure the works of the upper town, though the thips themfelves would be liable to great injury from the cannon and bombs from these elevated ramparts. The lower town is defended by a platform flanked with two baffions, which at high water and fpring tides are almost level with the furface of the water. A little above the baftion, to the right, is a half baftion, cut out of the rock; a little higher a large battery; and higher still a fquare fort, the most regular of all the fortifications, and in which the Governor relides. The paffages which form a communication between thefe works are extremely rugged. The rock which feparates the upper from the lower town, extends, with a bold and freep front, a confiderable diftance weftward, along the river St. Lawrence. The lower town is well QUE

the pond, from whence it iffues, are | fupplied with water, which is fometimes fcarce in the upper town. This city was belieged by the British in 1711. without fuccels; but was taken by them in September, 1759, when the brave Gen. Wolf, who commanded the army of beliegers, loft his life. In December, 1775, it was attacked by the Americans under the command of the brave General Montgomery, who was flain, and his army repulfed. N. lat. 46. 48. 39. W. long. 71. 12. 6. QUEECHY, ariver of Vermont, which

empties into Connecticut river at Hartland.

QUEEN ANNE, a fmall town of Prince George co. Maryland, fituated on the W. fide of Patuxent river, acrofs which a wooden bridge is built. The town is fmall, but is faid out in a regular plan, at the foot of a hill. Here are a few ftores and two ware-houfes for the infpection of tobacco. It is about 22 miles E. N. E. of the city of Wafhington, 13 S. W. of Annapolis, and 30 S. by W. of Baltimore.

QUEEN ANNE'S, a co. of Maryland, bounded wefterly by Chefapeak Bay, and N. by Kent co. It contains 15,463 inhabitants, including 6,674 flaves. Chief town, Centerville. Kent Island belongs to this county; 14 miles in length, from N. to S. and 61 in breadth, from E. to W. It is low, but fertile land, and its eaftern fide is bordered with falt marfh.

QUEEN Charlotte's Islands, on the N. W. coaft of N. America, extend from lat. 51. 42. to 54. 18. N. and from long. 129. 54. to 133. 18. W. from Greenwich. They are named Walhington Ifles by American navigators.

QUEEN's, the middle county of Long-Ifland, New-York. Lloyd's Neck, or Queen's Village, and the iflands called the Two Brother's and Hallett's Iflands, are included in this county. It is about 30 miles long, and 12 broad, and contains 6 townships, and 16,014 inhabitants, including 2,309 flaves. Jamaica, Newtown, Hampftead, in which is a handfome court-houfe, and Oyfter-Bay, are the principal towns in this county. The county court-houle is 8 miles from Jamaica, to from Jericho, and ao from New-York.

QUEEN's, a county of Nova-Scotia, comprehending a part of the lands on the cape, on the S. fide of the Bay of Fundy.

Argyle, Fundy, dians ref fettled cl England called (by Qui fides the the Fre the Nor Roleway grants f QUE ington c by Wet erly by 1,080 electors QUE Maryla fide of of Cent napolis QUE lies on agara, above t QUE QUI dlefex . New-B QUI of the bited ; hippin which quipa. lat. I of the the vol QU Chili, Qu Mohes fachui Frenc Sutto therly about ing, Qu fetts, tree, weit of Ph feat

Unite

Fundy.

Fundy. The fettlements are as follow: Argyle, on the fourh fide of the Bay of Fundy, where a few Scotch and Acadians refide: next to this, is Yarmouth, fettled chiefly by emigrants from New-England; Barrington, within the ifland called Cape Sable, fettled originally by Quakers from Nantucket. Befides thefe are Port Raifoir, fo called by the French, and originally fettled by the North Irifh; Liverpool and Port Rofeway, fettled and inhabited by emi-

OUI

imes

city

711.

by

the

i the

De-

the

wae

lat.

hich lart-

n of

ated

crofs

The

zular

e are

s for

bout /afh-

id 30

land.

Bay,

19462

aves.

es in

adth,

ertile

dered

e N.

from

from

from

bing-

ong-

K, 08

called

ands.

about

con-

habi-

laica,

is a

Bay,

unty.

from

from

cotia,

is on

xy of

andy.

grants from New-England. QUEENSBURY, a township in Washington co. New-York, bounded easterly by Westfield and Kingsbury, and southerly by Albany county. It contains 2,080 inhabitants, of whom rss are electors.

QUEENSTOWN, in Queen Anu's co. Maryland, a finall town on the eaftern fide of Chefter river, 6 miles fouth-weft of Centerville, and nearly 20 E. of Annapolis.

QUEENSTOWN, in Upper Canada, lies on the weft fide of the Straits of Niagara, near Fort Niagara, and 9 miles above the falls.

QUESNE, Fort du. See Philfburgh. QUIBBLETOWN, a village in Middlefex co. New-Jerfey, 6 miles north of New Brufwick.

QUIBO, an illand in the mouth of the bay of Panama. It is uninhabited; but affords wood and water to fhipping.

QUILCA, a rich valley in Peru, on which flands the ancient city of Arequipa. The port of Quilca is in about lst. 17. 8. fouth, 10 leagues north-weft of the finall river of Xuly, and 6 from the volcano of Arequipa.

QUILLOTA, a small jurifdiction of Chili, in S. America.

QUINABAUG, a river formerly called Mohegan, which rifes in Brimfield, Maffachufetts, and is joined at Oxford by French river, which has its fource in Sutton, Worcefter co. It runs a foutherly courfe, and emptics into Shetuck et, about three miles above Norwich Landing, in Connecticut.

QUINCY, a polt-town of Maffachufetts, in Norfolk co. taken from Braintree, to miles foutherly of Bofton, 9 weit of Hingham, and 360 north-east of Philadelphia. In this town, is the feat of the prefent Prefident of the United States. See Braintyse. QUINEPAUCE, or East River, in Connecticut, runs a foutherly course, and empties into the north-east corner of New-Haven harbour.

QUINSIGAMOND, Werceffer, or Long Pond, is a beautiful piece of water in the form of a crefcent, about 4 miles in length and from 60 to 200 rods broad. It is fituated on the line between the towns of Worcefter and Shrewfbury, but the greater part of it is in the latter. It is interfperied with a number of islands, one of which is upwards of 200 acres in extent.

QUISPICHANCHS, a jurifliction in the diocele of Culco, and kingdom of Peru, beginning at the fouth-gates of Quito, and firetching from eaft to weft about ao leagues. The lands of this jurifliction belong, in general, to the gentry of Culco, and produce plenty of wheat, maize and firnits. Here are alfo manufactures of baize and coarle woollen fluffs. Part of the jurifdiction borders on the forefts inhabited by wild Indians, and produces great quantities of cocoas an herb greatly ufed by the Indians working in the mines.

QUITAPAHILLA, a branch of the Swetara, which falls into the Sufquehannah at Middleton.

QUITO, a province of Peru, in S. America, having an exceeding temperate air, occafioned by its elevated fituation. The plain of Quito may be confidered as the bafe of the Andes, and is higher above the fea than the top of the Pyrenees in Europe. It is pretty well cultivated, and the towns and villages are populous; and the northern parts abound with gold. The province is about 400 miles long and 200 broad. Its chief towns are Quito and Payta.

QUITO, chief town in the above province, is next to Lima in population, if not fuperior to it. Some authors fay it contains ?5,000 inhabitants. It is an inland city, and having no mines in its neighbourhood, is chiefly famous for its manufactures of cotton, wool, and flax, which fupply the kingdom of Peru. South lat. 0. 13. weft long. 77. 50. It was fwallowed up by an earthquake, April 24, 1755, and has been rebuilt.

QUIVA, a province of California, thinly inhabited, and but little known. QUIXOS, a district of Peru, in South-America.

RABY,

Bur Rich

mara thailun R in

RABY, a fmall township of N. Hampfnire, in Hillsborough co. about 65 miles W. by S. of Portsmouth, and 47 N. W. of Boston. It was incorporated in 1760, and contains 338 inhabitants.

RACE, Cape, the S. E. point of Newfoundland Ifland, in the N. Atlantic Ocean, 4 leagues fouth of Cape Ballard. N. lat. 46. 43. W. long. 52. 49. The Virgin Rocks, much dreaded by mariners, are about 20 leagues to the S. E. of Cape Race.

RACE Point, the north-weftern extremity of Cape Cod, Maffachuletts, a league N. W. of Provincetown. When within a mile of this point, with a fair wind and tide of flood, your courfe to Bofton is N. W. by W. diftance 15 leagues. A number of huts are erected here on the loofe fands by those who come from Provincetown to fifth in boats.

RADNOR, a finall pleafant town of Delaware co. Pennfylvania. This place was originally called *Amflel*, by the Dutch, who began to build here.

RADNOR, a town of S. Carolina, 10 miles S. W. of Edmondfbury, and 32 N. E. of Puryfburg.

RAGGED Harbour, on the east coast of Newfoundland, is a part of Catalina Bay. Many eraggy rocks lie about the entrance of it, both within and without; fo that it is very dangerous to enter. It is a leagues northward of Catalina harbour. There is good water at the head of the harbour.

RAIMOND, a cape on the fouth fide of the fouth peninfula of the ifland of St. Domingo; 2 leagues weft of Point Baynet and 11 weft of Cape Marechaux. It has the cove Petite Anfe on the eaft, and that of Brefiliere on the weft.

RAINY Ifland River, a fmall river of the N. W. Territory; having a northwest course, and empties into Illinois river, about half way between the Little Rocks and Illinois Lake, and 255 miles from the Missifippi. It is 15 yards wide, and is navigable 9 miles to the rocks.

RAINY, or Long Lake, lies eaft of the Lake of the Woods, and weft of Lake Superior. It is faid to be nearly 100 miles long, and in no part above 20 miles wide.

RAN

RALEIGH, the prefent feat of go, vernment of N. Carolina; fituated in Wake co. about 10 miles from Wake court-house. In December, 1791, the general affembly of the State appropriated f10,000 towards creeting public buildings, and named it after the cele-brated Sir Walter Raleigh, under whole direction the first fettlement in N. America was made at Roanoke Island, in Albemarle Sound. The ftate-houfe, a large handfome building, has been lately finished, and cost £6000. Several other buildings have been erected, and a number of dwelling-houfes. The fituation is healthy. Its remotenefs from navigation is the greatest difadvantage. It is 61 miles north by eaft of Fayetteville, 147 from Petersburg in Virginia, and 448 fouth-weft of Philadelphia.

RAMADA, a maritime town of Granada, in S. America. Near it is a copper-mine. N. lat. 11.10, W.long.72.20,

RAMSAY'S Mills, in N. Carolina, are fituated at the confluence of Deep, with the north-welt branch of Cape Fear river; about 35 miles fouth-welterly of Hillfborough, and 55 S. E. of Guildford court-houfe.

RANAI, one of the Sandwich Islands, in the North Pacific Ocean, north of Tahoorowa, and north-weft of Mowee and Owhyhee. It has about 24,000 inhabitants. It abounds with yams, fweet potatoes, and taro, but has few plantains or bread-fruit trees.

RANCHEIRA, a town of Terra Firma, in the province of New Granada. N. lat. 11, 34. W. long. 72.

RANCHENO, a imall island on the coaft of New Mexico, in lat. 7. 14. N. It is near the island of Quibo, and affords timber fit for mafts.

RANDOLPH, a township of Massachufetts, formed of the south precinct of Braintree, in Norfolk co. in the year 1793. It is 15 miles south by east of Boston.

RANDOLPH, a county of Hillfborough diffriet, N. Carolina, bounded north-eaft by Orange, and north-weft by Guildford. It contains 7,276 inhabitants, including 452 flaves. Its courthoufe is 585 miles from Philadelphia. RANDOLPH, a county of Virginia, bounded north by Monongalia, and fouth by Pendleton. It contains 951 inhabitants, including 19 flaves. Chest river. river, the hela river 1 fide of the RANDO co. Vermo Thetford tains 892 RANDO Vermont, 1780.

RAPHA ton, or di Spanish pa Its bound part of th The air r and falub in a hollo garrifon the fmug Atalaye, very) the Spanish co the town parifhes a town of S erly of C of St. De RAPH. the ifland eaft limit tant in th or Cape ! lat. 19. 30. W. phael, or to Punta of the if leagues, RAPH Pennfylv RAPI nia, whi

RAPT Bay. RAPF

river of

Ridge, a

north-w

Chefape

Stingray

of Falme

al, Leed

It afford

Hole, ar

burg, I

11 leag

northwi

river, the eaftern branch of Monongahela river rifes here, on the north-weft fide of the Alleghany mountains.

Take

the

opri-

cele-

vhofe

Ime-

l, in

oufe,

been

ieve-

Ated.

The

enefs

ifad-

eaft

rg in

hila-

Gra-

COD-

1.20.

lina,

eep,

Fear

ly of

uild -

inds,

th of

owee

o in-

ams,

a few

rna,

N.

the

. N.

d af-

chu-

at of

year

ft of

libo-

nded

-weft

habi-

ourt-

phia.

rinia,

and

951 Cheat

river,

RANDOLFH, a township in Orange co. Vermont, the fourth town west of Thetford on Connecticut river. It contains 892 inhabitants.

RANDOM, a township in Effex co. Vermont, west of Brunswick, granted in 1780.

RAPHAEL, a fertile and healthy canton, or diffrict, the westernmost in the Spanish part of the island of St. Domingo. Its boundary to the north is formed in. part of the French parish of Gonaives. The air round St. Raphael is very cool and falubrious, but the town which is in a hollow, is very hot. It has a little garrifon which ferved as a check on the imuggling trade with the French. Atalaye, (that is the centinel or difcovery) the westernmost town of all the Spanish colony, is 11 leagues S. W. of the town of St. Raphael, both which parifhes are annexed to Hinche. The town of St. Raphael is to leagues foutherly of Cape Francois, and 72 N. W. of St. Domingo city, as the road runs.

RAPHAEL, Cape St. at the eaft end of the island of St. Domingo, is the foutheaft limit of Samana Bay, 7% leagues diftant in that direction from Cape Samana or Cape Rezon, which last is fituated in lat. 19. 15. 40. N. and long. 71. 33. 30. W. from Paris. From Cape Raphael, or Cape of the Round Mountain, to Punta Espada, the fouth-east point of the island, the country is level 16 leagues, by a breadth nearly equal.

RAPHOE, a township in Lancaster co. Pennsylvania.

RAPID Ann, a finall river of Virginia, which joins the Rappahannock, about to miles above Fredericksburg.

RAPID River, a water of Hudfon's Bay.

RAPPAHANNOCK, a large navigable river of Virginia, which rifes in the Blue Ridge, and runs about \$30 miles from north-weft to fouth-eaft, and enters into Chefapeak Bay between Windmill and Stingray points. It waters the towns of Falmouth, Frederickfburg, Port Royal, Leeds, Tappahannock and Urbanna. It affords 4 fathoms water to Hobbs's Hole, and 2 from thence to Frederickfburg, 110 miles from its mouth. It is \$1 league from Gwin's Iflands, and 6 morthward of New Point Comfort. A

fingle lump of gold ore has been found near the falls of this river, which yielded 17 dwt. of gold, of extraordinary ductility. No other indication of gold has been difcowered in its neighbourhood. RAFFO Rappo, a bay in the ifland of Mowee, one of the Sandwich Iflands.

RARITON River, in New-Jerfey, is formed by 2 confiderable ftreams, called the N. and S. branches; the fource of the one is in Morris co. that of the other in Hunterdon co. It paffes by Brunfwick and Amboy, and mingling with the waters of the Arthur Kull Sound, helps to form the fine harbour of Amboy. At Rariton Hills, through which this river paffes, is a fmall cafcade, where the water falls 15 or 20 feet, very romantically between two rocks. Oppofite to Brunswick, the river is fo thallow, that it is fordable at low water for horfes and carriages; but a little below it deepens to fast, that a 20 gun ship may ride fecurely at any time of tide The tide rifes fo high, that large shallops used to pais a mile above the ford; fo that it was no uncommon thing to fee veffels of confiderable burthen riding at anchor, and a number of large river craft lying above, fome dry, and others on their beam-ends for want of water, within gun fhot of each other. Copper ore has been found on the upper part of this river; and in the year 1754, the ore of this mine fold for £62 fterling per ton, being of inferior quality to that on Paffaik river.

RARITON, a town fituated between the mouth of the north branch of the above river, and Boundbrook, 5 miles weft-north-weft of Boundbrook, and 12 north-weft of Brunfwick.

RATTLE-SNAKE Iflands lie at the western end of Lake Frie.

RAWDON, a town of Nova-Scotia, 40 miles from Halifax, containing about 50 or 60 houfes.

RAWAY, or Bridgetown, a lively commercial village of Middlefex co. New-Jerfey, on Raway river, 4 or 5 miles fouth-weft of Elizabeth-Town, and 75 from Philadelphia. It contains a Prefbyterian church, and about 50 or 60 houfes.

RAYMOND, a township of New Hamhire, in Rockingham co. 12 or 14 miles westerly of Exeter, and 32 from Portsmouth. It was incorporated in 1764, and contains 727 inhabitants.

RAYMOND,

RAYMOND, or Raymondtown, & fetement in Cumberland co. District of Maine, 142 miles N. N. E. of Bofton, and contains 345 inhabitants A ftream from Songo Pond, after paffing through part of Greenland, Waterford, and Ottifield, falls into the north-eafterly part of Sebago lake in this fettlement. The and is generally level, except one large hill, named Rattleinake Hill, from its abounding with these reptiles. Here are fome fwells of good land, but the greater part of the growth is pine and whiteoak, and the land is hard to fubdue.

RAYNHAM, a township of Maffachufets, in Briftol co. taken from Taunton, and incorporated in 1731. It contains 1094 inhabitants. A confiderable part of the town lies upon a circular bend of Taunton river, which is between 7 and 8 rods wide, and affords great plenty of herrings and other fifh, but fo unfavourable is it, in this place, to feining or fift-ing, that the exclusive privilege of fifting is annually fold for lefs than twelve fhillings, while the fame privilege in Bridgewater and Middleborough, (towns which bound this; the former on the eaft, the latter on the north) is annually fold for £250. Belides the great river, there are feveral useful fireams, upon which are 6 faw-mills, 3 griftmills, s furnace, a forge, and fullingmill. There are numerous ponds in this township, of which Nippaniquit or Nippahonset is 2 miles long, and one in breadth. Here alewives, in millions, annually refort and leave their fpawns. An excellent kind of iron ore, and various kinds of fifh are found here. Befides the usual bufiness of husbandry and mechanics, numbers are here employed in the manufactories of bar-iron, hollow ware, nails, iron for veffels, iron fhovels, pot-afh, fhingles, &c. The first forge fet up in America was introduced into this town by James and Henry Leo-nard, natives of England, 1652. This nard, natives of England, 1652. forge was fituated on the great road, and is ftill in employ by the family of Leonards of the our generation; a family remarkable for longevity, promotion to public office, and a kind of hereditary attachment to the iron manufacture. King Philip's hunting-houfe flood on the northern fide of Fouling Pond, which is 11 miles from the forge. In the winter featon the Indian monarch

Philip and the Leonards lived on fuch good terms, and fuch was Philip's friendfhip and generofity, that as foon as the war broke out in 1675, which ended in the death of the king and the ruin of his tribe, he gave out firict orders to all his Indians. never to hurt the Leonards. Before Philip's war, Foculing Pond was two miles long, and iths of a mile wide, Now, the water is almost gone, and the large tract it once covered, is grown up to a thick fet fwamp of cedar and pine. The foil of this pond has also a prolific virtue in generating ore. Copious beds of ore, in this part of the country, are ufually found in the neighbourhood of pine fwamps, or near to foils natural to the growth of pine or cedar. In this place there has been almost an inexhauftible fund of excellent ore, from which the forge has been fupplied and kept going for more than 80 years, be-fides great quantities carried to other works, and yet here is ore ftill. Though, like other things in a fate of youth, it is weak and incapable of being wrought into iron of the beft quality.

REAT

the benefit of fifh.

RAZOIR, Port, at the S. W. extre-mity of the coaft of Nova-Scotia, and

N. E. of Cape Negro. RAZOR Ifland, is 4 leagues S. of the mouth of Rio Janeiro Bay, or Santa Cruz Point, on the coaft of Brazil, S. America

READFIELD, a township in Lincoln co. Diftrict of Maine, 8 miles from Hallowell, which bounds it on the E. and the eaftern branch of Androfcoggin river feparates it from Sterling on the W., It is N. of Winthrop, and was joined with it in the enumeration of 1790. It is 190 miles N. E. of Bolton.

READING, a township of Connecticut, Fairfield co. S. of Danbury, adjoining.

READING, a large township of Mas-fachusetts, in Middlesex co. 14 miles N. of Bofton. It was incorporated in 1644, and contains 1,802 inhabitants.

READING, a township of Vermont, Windior co. W. of Windsor, adjoining. It contains 747 inhabitants.

READING, a post-town, and the capital of Berks co. Pennfylvania ; fituated on the N. E. fide of Schuylkill river, 40 miles S. W. of Bethlehem, 28 E. of Lebanon, (where the canal com-mences which joins the waters of the relided at Mount Hope, probably for | Swetara Creek with shole of Schuylkill river)

river) and is a flourif and inhabi contains al buildings ? an elegant erected in one for R house for for the pul of the toy 100 feet with a ftr to turn a and tranfp of fifh. fulling-mi the whole naces, and ber 1795 county fo bridge ove on the hig diftant to READI Pennfylva READI Hunterdo W. by about II READ' ifland of J tween Hol It is abou depth. Sl in from ground fc winds, ex into the b 59. 47. REALI Nicaragu plain, on its name, W. of L bour. I pital, fur but the p neighbou is in pitc 12. 17. RECE Brazil, a that coaff RECO ritory, i Wabafh Greenvil mati. I

RAY

, and merote out ath of dians, Before s two wide. nd the wn up pine, rolific s beds y, are ood of atural n this inexfrom ed and s, beother lough, ath, lit rought extrea, and of the a Cruz Ameincoln n Hal-E. and coggin on the id was ion of Bofton. Aicut, in ng. f Mafmiles ated in tants.

d the

te capilituated river. 28 E. 1 comof the huylkill river)

irmont,

oining.

REC

river) and 54 N. W. of Philadelphia. It I and barracks with curtains, and con is a flourishing town, regularly laid out, and inhabited chiefly by Germans. contains about 600 houfes. The public buildings are a ftone gaol, a court-houfe, an elegant church forGerman Lutherans, erected in 1793, a church for Calvinifts, one for Roman Catholics, a meetinghouse for Friends, and a large edifice for the public offices. In the vicinity of the town is a remarkable fpring, 100 feet square, and 140 feet deep, with a ftream iffuing from it fufficient to turn a mill. The water is clear and transparant, and affords abundance of fifh. In the neighbourhood are 10 fulling-mills and feveral iron-works. In the whole county of Berks are 5 furnaces, and as many forges. In November 1795, £12,000 was voted by the county for building a ftone arched bridge over the Schuylkill at this town, on the high road to Harrifburg, 53 miles diftant to the weft by fouth.

READING, a township in York co. Pennsylvania.

READINGTOWN, or Riddentown, in Hunterdon co. New-Jerfey, 17 miles N. W. by W. of New-Brunfwick, and about 11 eaftward of Lebanon.

READ's Bay, a road for thips in the island of Barbadoes, about half way between Hole-Town and Speight's . Town. It is about half a mile over, but more in depth. Ships may anchor here in fafety, in from 6 to 12 fathoms water, the ground foft ooze, and defended from all winds, except the W. which blows right into the bay. N. lat. 13. 7. W. long.

59. 47. REALEGO, a town in the province of Nicaragua, New-Spain; fituated on a plain, on the eaftern bank of a river of its name, near its mouth, 30 miles N. W. of Leon, to which it ferves as a harbour. It has 3 churches, and an hof-pital, furrounded by a very fine garden; but the place is fickly, by reafon of the neighbouring swamps. Its chief trade is in pitch, tar, and cordage. N. lat. 12. 17. W. long. 87. 36.

RECEIF, a harbour on the coaft of Brazil, and is the ftrongeft place on all

that coaft. S. lat. 8. 10. W. long. 35.35. RECOVERY, Fort, in the N. W. Territory, is fituated on a branch of the Wabash river, about 23 miles from Greenville, and 98 N. by W. of Cincinmati. It confifts of two block-houles REE

tains 60 men.

460

RED, a river of the State of Tenneffee, a water of Cumberland river, with which it mingles its waters at the north bend, about 2 miles N. W. of Clarkfville. It is boatable a confiderable diftance.

RED, a principal branch of Kentucky river, which heads and interlocks with a main branch of Licking river, and flows, in a S. W. courfe, into Kentucky river, about 9 miles above Boonfborough. It is 60 yards wide at the mouth.

RED, a weltern branch of Miffifippi river, in lat. 31. N. Here, it is faid, Ferdinando de Soto died, at a place called Guacoyi, May 21, 1542. See Rouge River.

RED Bank, on the S. E. fide of Dalaware river, in the town of Woodbury, in Gloucefter co. New-Jerfey. The fituation is elevated, and the fort built here during the war, ftood 1,900 yards from Fort Ifland, and about 7 miles fouth of Philadelphia. It coft the British 400 men, killed and wounded, before they could reduce the garrifon, in 1777.

RED Hook, in Dutchefs co. New-York, where a post-office is kept, is on the eaft bank of Hudfon's river, 21 miles S. of Hudion, and 116 N. of New-York.

REDONDO, a rock between Montferrat and Nevis, Caribbee Iflands. It is about a league in circuit, of a round form, where is neither culture nor inhabitants. N. lat. 17. 6. W. long. 61. 35.

REEDSBOROUGH, or Read/borough. the fouth-easternmost township of Bennington co. Vermont. It contains 64 inhabitants.

REEDY Island, in Delaware river, 50 miles below Philadelphia. It is 20 miles from Bombay Hook, and is the rendezvous of outward-bound fhips in autumn and fpring, waiting for a favourable wind. The course from this to the sea is S. S. E. fo that a N. W. wind, which is the prevailing wind in these featons, is fair for veffels to put out to fea. There is a fecure harbour here, at Port Penn, where piers have been crected by the State of Pennfylvania. The island is about 3 miles long, and not more than one fourth of a mile wide. It was formerly banked in, but is now under cultivation, and is overflowed in high tides. There is a channel on each fide of the

Gg

ifland:

ifland ; but veffels, especially large ones, choose to keep the eastern fide.

REELFOOT, a small navigable river of the state of Tenneffee, which empties into the river Mifflippi, about 35 miles fouth of the Ohio. It is 30 yards wide 7 miles from its mouth. One of its branches rifes on the borders of Kentucky.

REEMSTOWN, or Reamflowm, a fmall town of Lancaster co. Pennsylvania; fituated on a stream which empties into Calico Creek, a water of Conditoga, which falls into the Susquehannah. It contains about 40 houses, and is 16 miles N. E. of Lancaster, and 62 N.W. by N. of Philadelphia.

REGOLETS, the name of the paffage from the northern part of the Gulf of Mexico into lake Pontchartrain, which has communication, through Maurepas Lake and the Gut of Ibberville, with Miffifippi river; or the general name of the ifles in the inner part of the channel into that lake. The diffance from Lake Pontchartrain through the Regolets is to miles, and between 3 and 400 yards broad, and lined with marshes on each fide. On the S. fide of the Regolets, and near to the entrance from the gulf, there is a large paflage into the Lake Borgne, or Blind Lake; and by fome creeks that fall into it, fmall craft may go as far as the plantations on the Miffifippi, and there is a paffage between the Lakes Borgne and Pontchartrain; but either by this, or that of the Regolets, 6 and fometimes 7 feet is the deepeft water through. Near the entrance at the eaft end of the Regolets, and on the north fide, are principal mouths of Pearl river. From the Regolets to the Bay of St. Louis is 18 miles.

REHOBOTH, a township of Massachufetts, in Bristol co. on a branch of Providence river, a few miles from Providence, in Rhode-Island, and 44 miles N. by W. of Boston. It was called Saconet by the Indians; was incorporated in 1645, and contains 4,710 inhabitants.

REISTERSTOWN, in Baltimore co. Maryland, 10 miles fouth-eaft of Weftminiter, and nearly 16 north-wefterly of Baltimore.

RENOWE's Harbour, on the east coast of Newfoundland Island, is about 21 miles from Cape Race Its entrance is rather dangerous, but it is a good har-

bour to fifh in; and is much frequented by boats and fhallops, in the fifthing feafon. Half a league from the S. point is a high rock, called Renowe's Point ; which may be feen, in a clear day, 3 leagues off.

RENSSELAER, a county of the State of New York, bounded north by Wafhington co. fouth by Columbia, eaft by part of the States of Maffachuletts and Vermont, and weft by Hudfon's river. It contains eight townfhips, viz. Troy, Greenbufh, Schodack, Stephentown, Peterfburg, Hofick, Pittftown, and Schaftecoke. In 1796, there were 3,500 of the inhabitants qualified electors.

RENSSELAERVILLE, or *Renfelaer*wick, a townfhip of Albany co. New-York, bounded foutherly by Columbia co. and wefterly by Hudfon's river. In 1790, it contained 2,771 inhabitants ; in 1796, it had 548 inhabitants who were electors. In this town, nearly oppofite to the city of Albany, is a medicinal fpring, which combines most of the valuable properties of the celebrated waters of Saratoga.

RESOLUTION Bay, or Madre de Dios, is under the higheft land on the W. fide of St. Chriftina, one of the Marquefas Iflands. S. lat. 9. 52. W. long. 139.9.

RESOLUTION, Cape, near the eaftern entrance of Hudion's Straits. N. lat. 61. 29. W. long. 65. 16.

RESOLUTION Ifland, at the eaft end of Hudion's Straits. N. lat. 62. W. long. 65.

RESOLUTION Ifland, a final ifland, one of the Society Ifles; fo called from the fhip Refolution. S. lat. 17. 24.W. long. 141. 15.

REVEL's, a fmall ifland in the Atlantic Ocean, close to the east coast of Northampton co. Virginia.

REY, Cape, or Point, on the N. coaft of S. America, is 40 leagues W. by N. of Cape Three Points, and is N. by E. of Bocca del Drago.

REYES, Angra dos, on the S. E. coaft of Brazil, in S. America, lies weftward of Rio Janeiro, and 53 leagues weft of Cape Frio. It affords good anchorage.

RHINEBECK. See Rbynbeck.

RHODE ISLAND is one of the fmalleft of the United States; its greateft length being 47 miles, and its greateft breadth 37; or about 2,300 fquare miles.

ning oint int : Y. 3 State afh-A by and iver. roy, own, and were d elar-Newmbia . In ants ; who y opmedioft of brated Dios.

ated

V. fide quefas 39.9. eastern N. lat.

aft end 2. W.

ifland, d from 24.W.

Atlanoaft of

I. coaft . by N. . by E.

: S. E. es weftleagues Is good

of the greateft greateft fquare miles.

RHO

miles. It is bounded N. and E. by the commonwealth of Maffachufetts; S. by the Atlantic Ocean, and W. by Connecticut. These limits comprehend what is called Rhode-Island and Providence Plantations; divided into 5 counties, viz. Newport, Providence, Washington, Briftol, and Kent, which are fubdivided into 30 townships, containing 68,825 inhabitants, of whom 948 are flaves. Narraganset Bay makes up from S. to N. between the main land on the E. and W. and embofoms many fertile iflands, the principal of which are Rhode-Ifland, Canonnicut, Prudence, Patience, Hope, Dyer's, and Hog Iflands. Block-Ifland is the fouthernmoft land belonging to the State. The harbours are Newport, Providence, Wickford, Patuxet, Warren, and Briftol. Rhode-Island, from which the State takes half its name, lies between lat. 41. 28. and 41. 42. N. and between long. 71. 17. and 71. 27. W. from Greenwich; being about 15 miles long from N. E to S. W. and about 31 broad, on an average. It is divided into 3 townthips, Newport, Portfmouth, and Middletown. Perhaps no ifland in the world exceeds this in point of foil, climate, and fituation. In its most flourishing state it was called by travellers, the Eden of America. But the change which the ra-vages of war, and a decrease of business have effected, is great. Between 30,000 and 40,000 fheep are fed on this ifland, befides neat cattle and horfes. The State is interfected in all directions by rivers; the chief of which are Providence and Taunton rivers, which fall into Nafraganiet Bay; the former on the weft, the latter on the east fide of Rhode-Island. Rhode-Island is as healthy a country as any in America. The winters, in the maritime parts of the State are milder than in the inland country; the air being foftened by a fea-vapour, which also enriches the foil. The fummers are delightful, especially on Rhode-Ifland, where the extreme heats which prevail in other parts of America, are allayed by cool and refreshing breezes from the fea. The rivers and bays fwarm with fifh, to the amount of more than 70 different kinds; the markets are alive with them. Oyfters, lobfters, and other shell-fish, abound in Narraganiet Bay. Travellers are generally agreed, that Newport is the bell filhRHO

467

market in the world. This State pro-duces corn, rye, barley, eats, and in fome parts wheat, fufficient for home confumption; and the various kinds of graffes, fruits, and culinary roots and plants in great abundance, and in perfection; cyder is made for exportation. The north-western parts of the State are but thinly inhabited, and are more rocky and barren than the other parts. The tract of land lying between North and South Kingftown on the eaft, and Connecticut on the weft, called Shannock country, or Purchafe, is excellent grazing land, and is inhabited by a number of wealthy farmers, who raife fome of the finest neat cattle in New-England, weighing from 1,600 to 1,800 weight. They keep large dairies, and make butter and cheefe of the beft quality, and in large quanties for exportation. Iron ore is found in great plenty in feveral parts of the State. The iron-works on Patuxet river, 12 miles from Providence, are supplied with ore from a bed 41 miles diftant, which lies in a valley, through which runs a brook. The brook is turned into a new channel, and the ore-pits are cleared of water by a ffeam engine. At this ore-bed are a variety of ores, curious flones, and ochres. In the township of Cumberland is a copper mine mixed with iron, frongly impregnated with load-frone, of which fome large pieces have been found in the neighbourhood. No method has yet been discovered to work it to advantage. Abundance of lime-ftone is found in this State, particularly in the county of Providence; of which large quantities of lime are made and exported. This lime-ftone is of different colours, and is the true marble of the white, plain, and variegated kind. It takes as fine a polifh as any flone in America. There are feveral mineral fprings in this State; to one of which, near Providence, many people refort to bathe, and drink the water. Newport and Providence are the chief towns of this State. The flave-trade, which was a fource of wealth to many of the people of Newport, and in other parts of the State, has happily The town of Briftol been abolifhed. carries on a confiderable trade to Africa, the West-Indies, and to different parts of the United States. But by far the greatest part of the commerce of Rhode-Ifland, is at prefent carried on by Ggi

the

the inhabitants of the flourishing town of Providence, which had, in 1791, 129 of Providence, which had, in 1791, 129 fail of veffels, containing 11,942 tons. The exports from the State are flax-feed, lumber, horfes, cattle, beef, pork, fifh, poultry, onions, butter, cheefe, bar-ley, grain, fpirits, cotton and linen goods. The imports confift of European and W. India goods, and logwood from the Bay of Honduras. Upwards of 600 vef-fels eater and chee annually of the diffe fels enter and clear annually at the dif-ferent ports in the State. The amount of exports from this State to foreign countries, for one year, ending Sept. 30, 1791, was 470,131 dolls. 9 cents; in 1792, 698,084; in 1793, 616,416; and in 1794, 954,573 dollars. The inhabi-tants of this State are progressing rapidly in manufactures. A cotton manufac-tory has been crected at Providence. Jeans, fuftians, denims, thickfets, velvets, &c. &c. are here manufactured and fent to the fouthern States. Large quantities of linen and tow cloth are made in different parts of this State for exportation. But the most considerable manufactures in this State are those of iron ; fuch as bar and fheet iron, fteel, nailrods, and nails, implements of hufbandry, ftoves, pots, and other household utenfils, the iron-work of fhipping, an-chors, bells, &c. The conftitution of this State is founded on the charter granted by Charles II. in 1663; and the frame of government was not effentially altered by the revolution. The legiflature of the State confifts of two branches : a fenate or upper house, composed of ten members, befides the governor and deputy-governor, called in the charter. affiftants; and a house of representatives, composed of deputies from the feveral towns. The members of the legiflature are chosen twice a year; and there are two fellions or this win May, and viz. on the first Wednefday in May, and the first in October. This are two feffions of this body annually, State was first fettled from Maffachufetts. Mr. Roger Williams, a minister, who came over to New-England in 1631, was charged with holding a variety of errors, and was on that account forced to leave his houte, land, wife, and children, at Salem, in the dead of winter, and to feck a refidence without the limits of Maffachufetts. Governor Winthrop advifed him to purfue his courie to Nehiganfet, or Narraganfet Bay, which he did, and fixed himfelf

at Secunk or Seekhonk, now Rehoboth. But that place being within the bounde of Plymouth colony, Gov. Winflow, in a friendly manner, advifed him to re-move to the other fide of the river, where the lands were not covered by any patent. Accordingly, in 1636, Mr. Williams and four others croffed Seekhonk river, and landed among the Indians, by whom they were hofpitably received, and thus laid the foundation of a town, which, from a fenfe of God's merciful providence to him, he called Providence. Here he was foon after joined by a number of others, and, though they were fecured from the Indians by the terror of the English, yet they, for a confiderable time, fuffered much from fatigue and want; but they enjoyed liberty of confcience, which has ever fince been inviolably maintained in this State. So little has the civil authority to do with religion here, that no contract between a minister and a fociety (unless incorporated for that purpose) is of any force. It is probably for these reasons, that fo many different fects have ever been found here; and that the Sabbath and all religious inftitutions, have been more neglected in this, than in any other of the New-England states.

RHODE-ISLAND Light Houfe was erected in 1749, in Beaver Tail, at the fouth end of Canonnicut Ifland, for the fafety and convenience of veffels failing into the Narraganfet Bay and harbour of Newport. The ground the lighthoufe ftands upon is about 12 feet above the furface of the fea at high water. From the ground to the top of the cornice is 58 feet, round which is a gallery, and within that ftands the lantern, which is about 11 feet high, and 8 feet diameter, High water at full and change, 37 minutes after 7 o'clock. N. lat. 41. 28. W. long. 71. 24.

W. long. 71. 24. RHODE River, the wefternmoft water of the N. W. branch of Cape Fear river, in N. Carolina.

RHONDE. See Ronde.

RHYNEECK, or Rhinebeck, a pofttown of N. York, fituated in Dutchels co. on the E. fide of Hudfon's river, opposite to Kingkon; 18 miles north of Poughkeepfie; 103 north of New-York, and 198 N. by E. of Philadelphia. The township contains 3,662 inhabitants, of whom 542 are electors, and 421 flaves. It is bounded foutherly by Clinton.

Clinton, very curi overed a by the In County. RIALE New Spa Nicaragu is a good by reafon is 60 mil Nicaragu 89. 10. RICH. ifland of end, and St. Law John and This cap in the Fr it was t fifting. northwar vifta. RICH. part of th chorage river and RICHI fituated i go town 229 of i RICH townfhip Miffifcor RICH Camden by Cong by Wat Kerfhaw contains \$,479 ai RICH vania, i RICH formerly plain. RICH iflands i 12 leagu vieres, 1 ment of 100 of t 71. 7. RICH fmall fo on the r its jund oppofite

Clinton, and northerly by Beekman. A very curious cavern has been lately difovered at a place in this town, called by the Indians, Sepafcot. See Dutchefs County.

RIALEXA, or Rialeno, a town of New Spain, fituated on a finall river in Nicaragua, 5 miles from the fea, where is a good harbour. It is unwholefome by reason of marshes in the vicinity. It is 60 miles W. of Leon, and the Lake Nicaragua. N. lat. 12 25. W. long. 89. 10.

RICH, Cape, on the W. fide of the ifland of Newfoundland, towards the N. end, and in the N. E. part of the gulf of St. Lawrence, having the ifle of St-John and other fmall ifles to the north, This cape or point uled to be omitted in the French maps, feemingly becaufe it was the bounds of their privilege of fishing, which extended from hence northward, and round to Cape Bonavifta.

RICHARDSON'S Bay, on the S. E. part of the illand of Jamaica. The anchorage within it is between Morant river and Two Mile Wood.

RICHFIELD, a township of N. York, fituated in Otlego co. taken from Otlego township, and incorporated in 1792; 129 of its inhabitants are electors,

RICHFORD, the north-easternmost township of Franklin co. Vermont; on Miffifconi river.

RICHLAND, a county of S. Carolina, Camden district ; bounded S, and S. W. by Congaree and Broad rivers, and eaft by Wateree river, which divides it from Kershaw and Clermont counties. It contains 3,930 inhabitants; of whom 1,479 are white, and 1,437 flaves.

RICHLAND, a township of Pennfylvania, in Buck's co.

RICHLIEU, the French name given formerly to the outlet of Lake Champlain. See Sorel.

RICHLIEU Mands, a clufter of small islands in the river St. Lawrence, about 12 leagues above the town of Trois Rivieres, at the boundary of the govern-ment of Montreal. There are nearly 100 of them. N. lat. 46. 22. W. long. 71. 7.

RICHLIEU, the name of an ancient fmall fortification built by the French, on the north bank of the river Sorel, at its junction with the river St. Lawrence. opposite the islands of Richlieu.

RICHMAN'S Island, on the coaft of Cumberland county, Diffrict of Maine, about northerly four leagues from Wood Ifland, and a league weft of Portland. Few vefiels put in here, except coafters. There is a funken ledge S. E. half a mile from the north-east end of the ifland, which only fhews itfelf when the wind blows fresh : but you need not go fo near the island. Wood Island is in lat. 43. 50. N. and long. 69. 57. W.

RICHMOND, a township on the west line of the State of Maffachufetts, in Berkshire co. 17 miles W. by S. of Lenox, and 150 miles weft of Bofton. Iron ore of the first quality is found here, but as it lies deep it is raifed at a great expense. Ore of indifferent quality is found in many places. It abounds with lime-ftone, coarfe, white, and clouded marble. The town was incorporated in 1775, and contains an iron-work, 3 grift-mills, a fulling-mill, 2 faw-mills, and 1255 inhabitants.

RICHMOND, a township of Cheshire co. New-Hampfhire; fituated on the Maffachuletts line, about 11 miles eaft of Connecticut river, and 97 W. by S. of Portfmouth, It was incorporated in 1752, and contains 1380 inhabitants.

RICHMOND, a township in Washington co. Rhode-Island, separated from Hopkinton on the welt by Ward's river a branch of Paucatuck river. It is about 19 miles west of Newport, and contains 1760 inhabitants.

RICHMOND, a county of New-York. comprehending all Staten-Ifland, Shooters-Island, and the Islands of Meadow. on the weft fide thereof. It is divided into the townships of Castletown, Northfield, Southfield, and Weftfield. It contains 3,835 inhabitants; of whom 488 are electors, and 7 59 flaves. See Staten-Island.

RICHMOND, a county of N. Carolina, fituated in Fayette district, bounded fouth, by the State of S. Carolina, and north, by Moore co. It contains 5055 inhabitants, including 583 flaves. Chief town, Rockingham. The court-houfe, at which a post-office is kept, is 20 miles from Anfon court-house, 56 from Fay-etteville, and 563 from Philadelphia.

RICHMOND, a county of Virginia, bounded N. and N. E. by Weftmore-land, and S. and S. W. by Rappahannock river, which feparates it from Eflex

Gg3

God's called after lough ns by , for from ed lir fince State. to do A beunlefs of any afons, e ever bbath e been r other was at the for the failing arbour light-

both.

unde

v, in

o re-

river,

y any

Mr.

Seek-

e In-

tably

ation

water. ie corallery, which meter, 37 mi-1. 28.

above

ft wae Fear

1 poftutchefs river, orth of .York, elphia. inhabi-'s, and erly by linton,

fex co. It contains 6,985 inhabitants, of whom 3,984 are flaves. The courthoufe, where a post-office is kept, is 273 miles from Philadelphia.

470

RICHMOND, the prefent feat of government of the State of Virginia, is fituated in Henrico co. on the north fide of James's river, just at the loot of the falls, and contains between 400 and 500 houses, and nearly 4,000 inhabitants. Part of the houses are built on the margin of the river, convenient for bufinefs ; the reft are upon a hill which overlooks the lower part of the town, and commands an extensive prospect of the river and adjacent country. The new houses are well built. A large statehouse, or capitol, has lately been erected on the hill. This city likewife boafts of an elegant statue of the illustrious Washington, which was formed at Paris. The lower part of the town is divided by a creek, over which is a convenient bridge. A bridge between 300 and 400 yards in length, has been thrown actols James's river, at the foot of the fall, by Col. Mayo. That part from Manchester to the island is built on 15 boats. From the island to the rocks was formerly a floating bridge of rafts; but the enterprifing proprietor has now built it of framed log piers, filled with ftones. From the rocks to the landing at Richmond, the bridge is continued on framed piers filled with ftones. The bridge connects the city with Manchefter; and as the paffengers pay toll, it produces a handfome revenue to Col. Mayo, who is the fole proprietor. The public buildings, befides the state-house, are an Epifcopal church, a court-house, gaol, a theatre, and 3 tobacco ware-houses. The falls above the bridge are 7 miles in length. A noble canal is cutting, and nearly completed on the north fide of the river, which is to terminate in a bafon of about two acres, in the town of Richmond. From this bafon to the wharves in the river, will be a land carriage of about a mile. The expence is estimated at £30,000 Virginia currency. The opening of this canal promifes the addition of much wealth to Richmond. Veffels of burden lie at City Point, 20 miles below, to which the goods from Richmond are fent down in boats. It is 626 miles from Bolton, 374 from N. York, 176 from Baltimore, 278 from of Princeton.

Philadelphia, 247 from Fayetteville, 497 from Charletton, and 662 from Savannah. N. lat. 37. 40. W. long. 77. 50.

RICHMOND, a county of the Upper diffrict of Georgia, in which is fituated the city of Augusta. It is separated from S. Carolina on the E. by Savannah river, and contains \$1,317 inhabitants, of whom 4,116 are flaves.

RICHMOND, a town of the ifland of St. Vincent's, in the Weft-Indies. It is feated at the head of a deep bay, on the weftern fide of the ifland. Chateaubelair river runs on the fouth fide of the town, which gives name to the bay. Another river empties into the bay on the north fide of the town.

RIDGEFIELD, a poft-town of Connecticut, in Fairfield co. 10 miles fouthweftward of Danbury, 78 fouth-weft of Hartford, 51 north-eaft of Kingfbridge, in the State of New-York, and 161 north-eaft of Philadelphia. The townfhip of Ridgefield was called by the Indians *Caudotowa*, or high land. It well answers the name, for though it is 14 miles from the Sound, it affords a good prospect of it, and of Long Island. Of the latter, 40 miles in length is vifible, and vefiels may be feen as they pass up the Sound. It was settled in 1709.

RIDLEY, a township in Delaware co. Pennsylvania.

RIGO Ifland, near the north-weft part of the ifland of Porto Rico, in the Weft-Indies, behind which is the principal harbour of the main ifland.

RIMAC, a river of Peru, which paffes through the city of Lima, and falls into the fea 6 miles below that city.

RINDGE, or Ringe, a town in the county of Chefhire, New-Hampfhire, It lies upon the Maffachufetts line about 80 miles wefterly of Portfmouth, and 70 north-weft of Bofton. Was incorporated in 1768. In 1775, it contained 542, and in 1790, 1143 inhabitants. In this township are thirteen natural ponds of water of different fizes, in which are pickerel, perch, trout, eels, &c. In this township, northerly, is a mine lately difcovered, which contains a kind of ochre of a Spanish brown. One half of the water of this town runs. to the Merrimack, the other to Connecticut river.

RINGO'S-TOWN, in Hunterdon co. New-Jerfey, lies about 15 miles N. W. of Princeton.

RIOB the provi of its ow manufa all the n Several 1 gold and RIO I lies 14 t where a N. N. The bar 4.or 5 1 RIO norther town is Rio, from w its nam trance i wide an RIO S. Am tor, ru North § Marth Brazil, los Rey RIO vince i Firma. RIO lies 10 Cather R10 Paragi RIO divition

chief t RIO chorag the ifla Honda RIC city o church ated w 24. 1 It con and is it alfo Rn almoft dividi that c into t ward

> RI Terri

RIP RIOBAMBA, a jurifdiction of Peru, in the province of Quito, having a capital of its own name. The productions and manufactures of this province excel

all the reft of the provinces of Peru. Several parts of it are full of mines of gold and filver. RIO Bueno, in the island of Jamaica,

lies 14 miles eaftward of Martha Brae, where a thip may lie, bringing the point N. N. W. in 8 or 9 fathoms water. The bank is steep. Eastward of this, 4.or 5 miles is Dry Harbour.

R10 Grande, a captainship in the northern division of Brazil, whole chief town is Tignares.

R10, Grande, a large river of Brazil, from whence the above captain hip has The Portuguele fay its enits name. trance is difficult and dangerous, though wide and deep enough further in.

R10 Grands, a river of Terra Firma, S. America, which rifes near the equator, runs eaftward, and falls into the North Sea, between Carthagena and St. Alfo the name of a river of Martha. Brazil, which falls into the fea at Natal los Reyes.

RIO de la Hacha, a town and province in the northern division of Terra Firma.

R10 de Patas, on the coaft of Brazil, lies 10 leagues to the fouthward of St. Catherine.

R10 de la Plata. See Plata River,

Paraguay, and Buenos Ayres. R10 de la Plata, a province in the S. division of Paraguay, in S. America, Its chief town is Buenos Ayres.

R10 de Puercos, a harbour or anchorage ground on the northern fide of the island of Cuba, fouth-west of Bahia Honda.

RIO Janeiro, a rich and populous city of Brazil, having many elegant churches and handfome buildings, fitu. ated within a large and wide bay, in lat. 24. 15. fouth, and long. 43. 30 weft. It contains about 200,000 inhabitants, and is a place of confiderable trade. It it also called St. Sebaftian.

RIO Real, a river of Brazil, running almost parallel with that of St. Francis, dividing the captain hip of Seregipe from that of Todos los Santos, and empties into the ocean 41 leagues to the northward of the bay of that name,

RIPPACANOE Creek, in the N. W. Territory, is a wettern branch of Wa-

bafh river. The Kickapee Indian town lies near it. Its mouth is 20 miles above the Lower Weau towns.

RIPTON, a township in Addison co. Vermont, 22 miles eaft of Lake Cham. plain.

RISTIGOUCHE River, on the nor" thern fide of Chaleur Bay, is 2 leagues from Weft-Nouville, and runs a weft courfe in general. It is navigable for thips and brigs 7 leagues from its mouth, and abounds with falmon and wild fowl. Many falmon fifheries are carried on here to confiderable advantage.

RIVANNA, a finall north-weft branch of James's river in Virginia, whole head waters unite a few miles north of Charlottefville, and empties into James's river, about 2 miles above Elk Island. It is navigable for canoes and batteaux to its interfection with the fouth-weft mountains, which is about 22 miles; and may eafily be opened to navigation through these mountains, to its fork above Charlottefville.

RIVERHEAD, a township of New. York, fituated in Suffolk co. in Long-Ifland. It was taken from the townthip of Southold, and incorporated in 1792; 244 of its inhabitants are qualified electors.

RIVER of the Weft, in the north-weft part of N. America, empties into the ocean in about lat. 43. 17. 30. north, and long 122. 30. weft. It is little known, except near its mouth.

RIVIERE, Grande, in Lower Canada, empties into the ocean through the northern flore of Chalcur Bay, about 6 leagues weft north-weft of Cape Defpair. Here is'a confiderable cod-filhery

ROANOKE Inlet, on the coaft of N. Carolina, leads into Albemarle Sound'. N. lat. 35. 56. W. long. 76. 14

ROANOKE Mand is on the fouthern fide of Albemanle Sound. The north point of the ifland is about 7 miles weft of Roanoke Inlet.

ROANOKE, a long and rapid river, is formed by a principal branches, Staunton river, which rifes in Virginia, and Dan river, which rifes in N. Carolina. The low lands on this river are fubicet to inundations. It is navigable only for fhallops, nor for thefe, but about 60 or 70 miles, on account of falls, which in a great measure obstruct the water communication with the back country. It empties by feveral mouths into the S Gg4 W. end

50. pper ated ated vanabi-

409

van-

It , on Cha-1 fide

id of

o the > the Con-

outh-

eft of idge, 161 own-

e Int well is FA

good Of

ifible, ifs up 0.

re co.

It part n the prin-

paffes s into

in the pfhire. about a, and incormtainitants. atural es, in i, cels, y, is a ontains

brown. m runs > Con-

lon co. N. W. AMBA, W. end of Albemarle Sound. The planters on the banks of this river, are fuppofed to be the wealthieft in North-Carolina. The lower part of this river was formerly called *Mozattoe*.

ROANOKE *River*, *Little*, empties into Staunton river from the north, about 15 miles above the junction of Dan and Staunton rivers.

ROARING *River*, a boatable water of Tenneffee State, which runs north-wefterly into Cumberland river, 12 miles fouth-weft of the mouth of Obas river

ROBERDEAU, a finall fort which was erected in Bald Eagle, or Sinking Spring Valley, in Pennfylvania, during the late war. It was crected for the protection of those who then worked at the lead mines. But the Indian war raging around them, they were forced to abandon the enterprize. See Bald Eagle Valley:

ROBERT Bay, on the east coast of Newfoundland, separated from Spanish Bay by a very narrow neck of land; and about E. N. E. 4 miles about the point from Port Grave.

ROBERT Bay, a gulf or bay of the ifland of Martinico in the Weft-Indies, and one of the fineft natural harbours that can be imagined, being able to contain the largeft fleet with fuch convenience, that the fhips may ride near enough the fhore to reach it with a plank. It is about a leagues in depth, and is formed by the Point of the Galleons on the weft, and Point Rofe on the eaft.

ROBERTSON, a new county of Tenneffee.

ROBESON, a county of N. Carolina, fituated in Fayette diffrict, and bounded fouth-weft by the State of S. Carolina. It contains 5326 inhibitants, including 533 flaves. Chief town, Lumberton.

ROBIN HOOD'S Bay, on the east coast of Newfoundland, is frequented by finall veffels, as they can fish here to advantage. It is not far from Trinity Harbour, and near to Fox Islands.

Roca Iflands, a cluster of uninhabited iflands off the north coaft of Venezuela, in Terra Firma, about 40 leagues northweft by weft of Tortugas.

ROCA PARTIDO, a fmall island in the North Pacific Ocean, S. E. from La Mesa, and W. from the isle La Nublada; and in about lat. 16. 35. N. and long. 128. W. ROCHE, Cape de la, on the N. fide of the island of St. Domingo, is about five leagues weft of Old Cape Francois. ROCH, Riviere à la, a river of the

ROCH, Riviere à la, a river of the N. W. Territory, which runs a S. W. course, and empties into the Missifisppi 95 miles above the Iowa Rapids.

ROCHER, la prairie du, or Rock Meadows, on Miffifippi river, 3 miles below the fpot where Fort Chartres flood.

ROCHESTER, the north-westernmost township of Windsor co. Vermont, and contains 215 inhabitants.

ROCHESTER, a township of Massachusetts, Plymouth co. 53 miles southward of Boston. It was incorporated in 1686, and contains 2,644 inhabitants.

ROCHESTER, a confiderable township in Strafford co. New-Hampshire, on the W. fide of the northern branch of Pifcataqua river, 22 miles north westerly of Portsmouth, and 40 S. by E. of Middleton. It was incorporated in 1722, and contains 2,857 inhabitants.

ROCHESTER, a township in Ulfter co. New-York, extending W. to Delaware river. It is about 12 miles S. W. of Esopus, and contains 1628 inhabitants, of whom 228 are electors, and 281 flaves.

ROCKAWAY, a finall post-town in Morris co. New-Jerfey, on the S. fide of the river of its name, 15 miles N. by W. of Morristown, 21 S. E. of Newton, and 123 N. E. by N. of Philadelphia.

ROCKBRIDGE, a mountainous county of Virginia, bounded N. by Augusta, and S. by James river, which divides it from Botetourt co. It contains 6,548 inhabitants, of whom 682 are flaves. The Natural Bridge, fo elegantly defcribed by Mr. Jefferson, in his Notes on Virginia, is in this county.

ROCK FISH, a north-weftern branch of James river, in Virginia, at the mouth of which is fome indifferent marble, generally variegated with red, blue, and purple. It forms a large precipice, which hangs over a navigable part of the over. None of the marble has ever yet been worked.

ROCKFORD, a post town of N. Carolina, 573 miles from Philadelphia.

ROCKHILL, a township of Buck's co. Pennsylvania.

ROCKINGHAM, one of the five counties into which the State of New-Hampfhire is divided. It lies on the S. E., part of the State; having the Atlantic Ocean on the S. E. the county of Hillfborough borough c and the fi It is about the embras of the contain inhabitan Exeter, i Rock

moft toy mont, is Connecti from W contains

Roci diftriat, Cafwell banks o county, land. erected ore is fo ty. It cluding Roc Richmo ed on of Gre court-l houfes. rough, Philad Roc Virgin

and fo 7,449 Roo feat of is fitua river, and at

N. W of Str S. W Ro Frence eafter miles fouther

eaft by

years habit Ro town

Main New mefb Re mile

, elt...

ROC

borough on the W. Strafford on the N. and the flate of Maffachufetts on the S. It is about 60 miles long, and 30 broad. It embraces the only fea-port, and moft of the commercial towns in the flate. It contains 46 townships, and 43,169 inhabitants. Chief towns, Portfimouth, Exeter, and Concord.

ROCKINGHAM, the north-eafternmoft township in Windham co. Vermont, is fituated on the west bank of Connecticut river, which separates it from Walpole, in New-Hampshire. It contains 1235 inhabitants.

ROCKINGHAM, a county of Salifbury diffrict, N. Carolina, bounded eaft by Cafwell and weft by Stokes. On the banks of the Dan, which waters this county, are large tracts of fertile low land. A furnace and forge have been erected on Troublefome Creek. Iron ore is found in many parts of the county. It contains 6, 187 inhabitants, including 1, 100 flaves.

ROCKINGHAM, the chief town of Richmond co. N. Carolina. It is feated on an eminence, about 6 miles eaft of Gkeat Pedee river, and contains a court-houfe, gaol, and a few dwellinghoufes. It is 74 miles from Hillfborough, 40 from Bethania, and 536 from Philadelphia.

ROCKINGHAM, a mountainous co. of Virginia, bounded north by Shenandoah, and fouth by Augusta. It contains 7.449 inhabitants, including 772 flaves.

7,449 inhabitants, including 772 flaves. ROCKINGHAM, a poft-town and the feat of the courts of the above county, is fituated on a branch of Shenandoah river, and contains a court-houfe, gaol, and about 30 houfes. It is 108 miles eaft by north of the Sweet Springs, 25 N. W. by N. of Staunton, 52 S. W. of Strafburg, in Pennfylvania, and 262 S. W. of Philadelphia.

ROCKY Meadows, called by the French La Prairie du Rocher, on the eaftern fide of the river Miffifippi, 12 miles northerly of Kafkafkias, and 3 foutherly of Fort Chartres. About 20 years ago, it contained 100 white inhabitants, and 80 negroes.

ROCKEMECKO, or Rockomefbo, a township in Lincoln co. District of Maine. In 1790, the plantations of New Sandwich; Livermore, and Rockomesbo, contained 400 inhabitants.

ROCKONCAMA, a pond of about a New-market, Winchefter, mile in circumference, in the centre of town, York and Lancafter.

Long Hland, New-York State, between Smithtown and Iflip. It is continually ebbing and flowing; rifing gradually for feveral years, until it has arrived to a certain height; and then falls more rapidly to its loweft bed.

ROCKY Point, on the fouth fhore of Lake Erie, lies 80 miles from the bay of Sandufky.

ROCKY, a fmall river of N. Carolina, which empties into Yadkin river.

ROCKY Mount, or Franklin Court-Houfe, in Virginia, where is a post office, is 25 miles from Martinsburg, 40 from Liberty, and 133 from Philadelphia.

ROCKY *River*, in the N. W. Territory, falls into the eaft fide of Miffifippi river, about 70 miles below the mouth of Mine river. A lead mine extends from the mouth of this river on the banks of the Miffifippi, more than 100 miles upwards.

miles upwards. Roco Grande, an ifland on the coaft of the Spanifh Main, in the W. Indies. N. lat. 11. 5. W. long 67. 39. RODNEY, Point, on the N. W. coaft

RODNEY, Point, on the N. W. coalt of N. America, is the N. point of Norton Sound. Sledge Island is S. E. H. of it 4 leagues, between which and the continent is anchorage in 7 fathoms. This point has its name in honour of the celebrated Admiral, Lord Rodney. N. lat. 64. 30. W. long. 166. 3.

RODRIGUES Key, on the coaft of Florida, a pretty large mangrove ifland, one of the Tortugas, lying off Key Largo, and bears from Tavernies' Key N. N. E. $\frac{1}{2}$ E. 5 miles. The roots of the trees are always overflowed. N. lat, 25. W. long. 81. 17.

ROEBUCK Ifand, at the eaflern extremity of Lake Ontario. See Foreft Island.

ROGERS' Road, fo called from the perfon under whole direction it was made, in 1790. It leads through Clinton cb. in New-York State into Canada; and is much ufed in winter, when paffing the lakes is often dangerous, and always uncomfortable.

ROGERSVILLE, the chief town of Hawkin's co. Tenneffee. The road from Knoxville to Philadelphia, 652 miles paffes by Rogerfville, Rofs's Furnace, Abingdon, Englifh's Ferry, on New River, Big Lick; Peytonfburg, Rockbridge, Lexington, Staunton, New-market, Winchefter, Fredericktown, York and Lancafter.

ROLAND'S

ide of t five f the W. fifippi *Mea*below

faffaouthted in tants.

nmoft

, and

Piffterly Mid-

m the

1722, er co.

Iware

fEfo.

ts, of laves.

wn in

N. by

wton,

phia.

ounty

gufta, ides it 6, 548

laves.

tes on

ranch

at the

blue,

ipice,

s ever

Caro-

luck's

coun-

S. E.

lantic

Hill

rough

ROLAND'S Table, on the main Land of the E. coaft of the diftrict of Gafpee, in Lower Canada, and W. part of the Gulf of St. Lawrence, is a flat mountain, which fhews itfelf off to feaward; appears above feveral others, and ferves to find out Ifle Percée, or Pierced Ifland, 5 miles from Cape Gafpee. The Ifland of Bonaventura is 3 miles beyond it.

ROLLING Fork, a main fouthern branch of Salt river in Kentucky. The towns of Lyftra and Bealfburg fland on this river.

ROMAN, Cape, on the coaft of South-Carolina. From hence to Charleston light house the course is W. S. W. 4 W. 21 leagues. N. lat. 33. 5. W long. 79. 30.

79. 30. ROMAN, Cape, on the coaft of Florida, is 201 leagues N. W. by N. of Cape Sable, the S. W. point of the peninfula of Florida.

ROMAN Cape, on the north coaft of Terra Firm, is the north point of the peninula which is the east limit of the Gulf of Veneruela. Near to it on the north, are a number of rocks, and due north of it is the island of Orua, or Aruba, belonging to the Dutch, 8 or 9 leagues distant.

leagues diftant. ROMANO, or Romano Cayo, a finall ifland off the north fhore of the ifland of Coba. It is long and narrow, and at the eaftern extremity of that clutter of ifles called the King's Garden.

ROME, a post-town of New-York, Herkemer co. on Mohawk river, 8 miles west of Whitestown, and 376 miles from Philadelphia. This township was taken from Steuben, and incorporated in 1796. Fort Stanwix, called also New Fort Schuyler, is in this town.

ROMNEY, the chief town of Hampfhire co. Virginia, contains about 70 dwelling-houtes, a brick court-houfe, and a ftone gaol. It is fituated on the weftern bank of the S. W. branch ef Patownae river, 50 miles W. by N. of Wincheffer, 25 N. E. by N. of Moorfields, and 18 S. W. of Old-Town, in Alleghany co. Pennfylvania. It is a poft rown, and is 242 miles W. by S. of Philadelphia.

ROMOPACK, a village in Bergen co. New Jerfey, on Romopack river, 15 or 20 miles north of Patterson.

New-York State, Onondago co. be-

ROS

tween Seneca and Cayuga Lakes. The high road to the ferry at Cayuga Lake runs through its northern part. It was incorporated in 1794; and has within its juri/diction the townfhips of Junius and Galen, together with the lands lying weft of Hannibal and Cato, north of the townfhip of Galen, and S. of Lake Ontario, and that part of the lands referved to the Cayuga nation of Indians, weft of Gayuga Lake. In the year 1796, 123 of its inhabitants were electors.

BONDE, or *Rhonde Island*, one of the Grenadines, dependant on the island of Grenada, in the Weft Indies; fituated about mid-way between Cariacou and the north end of Grenada, about four leagues from each. It contains about goo acres of excellent land, which are wholly applied to pasturage, and the cultivation of cotton.

ROFE Ferry, a ferry acrofs a bay in the town of New London, in Connecticut; 4 miles S. W. by W. of New-London city, on the polt-road to New-Haven. The bay fers up from Long Ifland Sound, between Millftone Point and Black Point in Lyme. In Auguft, 1796, a bridge 500 feet long, was built acrofs this ferry, 2 miles above Millftone Point, where the water is 18 feet deep. The bridge is 24 feet broad, with a fliding draw.

ROQUE, Cape, on the coaft of Brazil, north-weitward of Cape St. Augustine. S. lat. 6. 20. W. long. 37. 30.

ROSA, a cape in the island of St. Domingo, E. N. E. 1 E. of Cape Dame Marie, the weftern point of the island, diftant about 7 leagues.

Rosa, or St. Rofe's, an extensive bay on the coaft of Weff Florida, firetching about 30 miles to the north eaft, and is from 4 to 6 miles broad. The bar before it has only 7 or eight feet water, where deepeft ; but within there is 16 or 17, as far as the Red Bluff on the main land. The peninfula between this bay and that of Penlacola, on the weft, is from 1 to 3 or 4 miles broad. It is generally a very poor, fandy foil, producing, in fome places, large pines and live oak. The largest river that falls into the bay is Chacta-Hatcha, or Peariver, which runs from the north-eaft, and enters the eaftern extremity of the bay through feveral mouths, but fo fhoal that only a finali boat or canoe can parts them.

them. M 25 league party of th RosA, the mouth so miles | a mile bro end of the a large ft the deepe and the and the boats or [ROSA weftern Natchez Millifipp above N ROSE Dominic now cal ated in leagues is on a fide of t viz. W and Cha Rofeau from C moftly of an it than se pied by of the 1,000 61. 27 Ro ments on the fide of looked of St. to con the m flaves W.o or Ja the a ventu of inc breed gold Jayn were Chri whic nam R port

them. Mr. Hutchins ascended it about 25 leagues, where he round a small party of the Coussiac Indians.

Rosa, or Rofe Ifland, extends along the mouth of the above bay, and is about 50 miles long, and no where above half a mile broad. The channel at the eaft end of the ifland is 10 choaked up with a large fhoal, in fome places dry, that the deepeft water is only 4 or 5 feet; and the channel between Rofe Ifland and the main is barely fufficient for boats or pettiaugers.

ROSALIE, Fort, is fituated in the weftern territory of Georgia, in the Natchez country, on the east fide of the Millifuppi, in lat. 31. 40; 243 miles above New-Orleans.

ROSEAU, the capital of the island of Dominico, in the West-Indies. It is now called Charlottetown, and is fituated in St George's parifh, about feven leagues from Prince Rupert's Bay. It is on a point of land on the fouth-weft fide of the ifland which forms two bays, viz. Woodbridge's Bay on the north, and Charlotteville Bay to the fouthward. Rofeau is about half a mile in length from Charlotteville to Rofeau river, and moftly two furlings in breadth, but is of an irregular figure. It contains more than 500 houses, besides cottages occupied by negroes. Whilft in poficifion of the French, it contained upwards of 1,000 houfes. N. lat. 15. 25. W. long. 61. 27.

ROSE, St. or Jayna. The eftablishments in the plain of St. Role, and thole on the banks of the Jayna, on the fouth fide of the ifland of St. Domingo, are looked upon as depending on the city They are reckoned of St. Domingo. to contain, at leaft, 2,000 perions; for the most part people of colour, free and The river Jayna is 3 leagues flaves. W. of that city. The parish of St. Role or Jayna, which has in its dependency the ancient rich population of Bonaventure, is now reduced to a handful of individuals, whole employment is the breeding of cattle or the washing of gold fand. Towa ds the fource of the Jayna, and near the town of \$t. Role, were the celebrated gold mines of St. Chriftopher; in the neighbourhood of which Columbus erected a fort by the name of St. Chriftopher.

ROSEWAY, Port, a populous feaport town, on the fouth east coast of Indies. 475

Nova-Scotia, north-east by east of Cape. Negro and Harbour.

ROSEWAY Island lies at the mouth of Port Wager, on the fouth-east coast of Nova-Scotia.

Rosia, Cape in Penoblcot Bay, Diftrict of Maine.

Rosiers, Cape, the fouth limit of the mouth of the river St. Lawrence; from whence it is 90 miles across to the north fhore, measuring by the west end of the island of Anticosti.' This is the easternmost point of the district of Gaspee, in Lower Canada. It has Florell Isle and Cape Gaspee on the south. N. lat. 48. 56. W. long. 63. 40.

ROSSIGNOL, Port, on the fouthern coaft of Nova-Scotia, a harbour to the fouth-weft of Port de L'Heve.

ROSSIGNOL, a confiderable lake in Nova-Scotia, between Liverpool and Annapolis. The Indians (ay it is the main fource of Liverpool and Petit rivers. It has been a place of refort for the Indians, on account of the favourable hunting grounds upon it.

ROTTERDAM, or Anamocoe Ifle, one, of the Friendly Iflands, fituated on the north of Amiterdam Ifle; remarkable for its fertility and the peaceable difpofition of the inhabitants.

ROTTERDAM, New, a new fettlement on the north fide of Oneida Lake, in the State of New-York.

ROUGE, Cape or Red Cape, on the N. fide of the itland of St. Domingo, in the W. Indies, lies 4 leagues weftward of Point Itabellica

ROUGE *River*, in Louifiana, is fo called from its waters being of a red colour, and faid to tinge those of the Mifflippi in the time of the floods. It rifes in New-Mexico, and, after running about 600 miles, joins the Mifflippi 187 mics above New-Orleans, 564 miles below Fort Rofalie; 30 miles from its mouth it receives Noir, or Black river. Near 70 leagues up Rouge river the French had a confiderable poft called Natchitoches. It was a frontier to the Spanish fettlements, being 20 miles from Fort Adayes.

ROUGE Chapeau, or Red Hat, a cape on the coaft of N. America. N. lat. 46. 51. W. long. 55. 26.

ROUND Bay, a fine bay, with good anchorage, fituated on the weft fide of the ifland of St. Lucia, in the Weft-Indies.

ROUND

ds lynorth S. of f the ion of in the were of the nd of uated 1 and t four about h are i the ay in necti-New-New-Long Point guft, built ftone deep.

The

Lake

t was

within

unius

razil, Itine.

flid-

Doame and,

bay

hing

nd is t beater, 16 or nain bay t, is geduclive into iver. enbay hoal pars

icm.

ROUND, Cape, on the coaft of Labrador in N. America.

ROUND Heads, Indians inhabiting on Riviere aux Tetes Bowles, or Round Head river, in N. America. Warriors. 3,000.

ROUND Island, a fmall island on the coaft of Weft-Florida, lies 5 miles north from, and oppofite to the middle of Horn Island, and is well timbered.

ROUND Rock, one of the Virgin Hands, north of Ginger Ifland. N. lat. 18. 10. W. long. 62. 53.

ROWAN, one of the most populous counties of N. Carolina, in Salisbury diffrict ; bounded north by Iredell, and fouth by Cabarrus. It contains 1 5,828 inhabitants, including 1742 flaves.

Rows, a township in the north-weftern corner of Hampfhire co. Maffachufetts ; bounded north by the State of Vermont, and 130 miles north-weft of Bofton. It is watered by Deerfield river, and contains 443 inhabitants.

ROWLEY, a township of Massachu-fetts, Effex co. having Newbury on the north-east and contains two parishes, be-fides a fociety of Anabaptists. The inhabitants, 1772 in number, are mostly farmers. Near its bounds with Newbury, fome fpecimens of black lead have been difcovered, and it is thought there is a confiderable body of it, which may be, hereafter, an object of confequence. It is 5 or 6 miles north by welt of Ipfwich, and 26 north by east of Boston, and was incorporated in 1639.

Roxas, Haite de, the heights in the diffrict of Bayaguana, in the middle of the eastern part of the island of St. Domingo, are fo called. Here Valverde faw, after having long fought for it in yain, a little quadruped, which in form and fize refembled a fucking pig of a fortnight old, except that its fnout was a little longer. It had but very little hair, which was as fine as that of the stogs called Chinefe. The town of Bayaguana is about 4 leagues fouth eaft by east of Baya.

ROXBOROUGH, a township of Pennfivania, fituated in Philadelphia coun-

ROXBURY, a pleafant town in Norfolk co. Maffachufetts, one mile fouth west of Boston. The township is now divided into 3 parifhes, and was fettled

RUA

town has lately been connected with Bofton harbour by a canal. The Rev. John Elliot, the Apoftle of the Indians. was the first minister who fettled here. He translated the Bible and other pious books, into the Indian language ; and founded many religious focieties among the Indians. Those of Natick and Masspee, few in number, remain to this day. He died in 1670, after being paftor 60 years.

ROXBURY, a township in the weffern part of Orange co. Vermont, having only 14 inhabitants.

ROXBURY, a township of Morris co. New-Jerfey, on Musconecunk river, 25 miles from its confluence with the Delaware, and 45 miles north of Trenton. Near it is a mineral fpring.

Roxo, a cape near the S. W. part of Porto Rico Island, and due fouth of Cape Rincon. N. lat. 18. 11. W. long. 67. 53.

ROYAL Bay, is a fhort distance to the east foutherly of Boon's Point, at the north part of the island of Antigua in the Weft-Indies.

ROYAL Ide, a small fertile island in the river St. Lawrence; 60 miles below Lake Ontario. The French fort on it was taken by Gen. Amherft, in 1760,

ROYAL's River, in Cumberland co. Maine, empties into Cafco Bay, in the township of North-Yarmouth.

ROYALTON, a township in Windfor co. Vermont, north-weft of Hartford, on White river, and contains 748 inhabitants.

ROYALSTON, a township of Maffachuietts, Worcefler, 40 miles northweft by north of Worcefter, and 70 north-west of Boston. It was incorporated in 1665, and contains 1,130 inhabitants. Miller's river runs through this town from the eaft.

RUATAN, or Rattas, an island in the Bay of Honduras, 8 leagues from the Molquito fhore, and about 200 weft by fouth of the illand of Jamaica. It is 30 miles long and 13 broad, naturally fortified with rocks and shoals, except the entrance into the harbour, which is fo narrow that only one thip can pais it at a time; the harbour is one of the finest in the world, and can afford fafe anchorage for 500 fail of thips. It was totally uninhabited until 1742, when the in 1630. In the 3 parishes are 2,226 British under the command of Major inhabitants. The first parish in this Crawford, began a settlement, in order

to protect cure a tra atimala, but it w 17. 6. W RUGE about 12 the weft Creek. ed, in M ments, at to prever RUIS the eafter and in 1 with the rie du-R inhabita RUM Hampfh RUM Peru, ft thrown merly in chincha RUM N. lat. RUM New-H co. on t about 7 mouth, waffet. and col RUN coaft of betwee to the fouth. Rui of the Great Bay, a Bueno Rι townfl It con Ru of the Indies winds dy. ifland Portfi Ru Hudf fituat on th tweet

to protect the log-wood cutters, and fecure a trade with the Spaniards of Guatimala, for cochineal, indigo, &c. but it was foon abandoned. N. lat. 17. 6. W. long. 88. 12.

RUGELEY's Mills, in S. Carolina, are about 12 miles north of Camden, near the westernmost branch of Lynche's Creek. Here General Greene retreated, in May, 1781, to wait for reinforcements, after his repulse at Camden, and to prevent fupplies reaching it.

RUISSEAU, Grand, a fettlement on the eaftern fide of the river Miffifippi, and in the N. W. Territory, which, with the villages of St. Philip and Prairie du-Rochers, contained, in 1792, 240 inhabitants.

RUMFORD. See Concord, in New-Hampfhire.

RUMI-RAMBA, a plain near Quito in Peru, full of large fragments of rocks, thrown thither from a volcano, formerly in the famous mountain of Pichincha.

RUM Key, one of the Bahama Islands. N. lat. 23. 52. W. long. 74. 17.

RUMNEY, or Romney, a township of New-Hampfhire, fituated in Grafton co. on a north branch of Baker's river, about 7 or 8 miles north-weft of Plymouth, on the weft fide of the Pemigewaffet. It was incorporated in 1767, and contains 411 inhabitants.

RUNAWAY Bay, on the north-weft coaft of the island of Antigua; fituated between the fort on Corbizon's Point to the north, and Fort Hamilton to the fouth. Off it lie rocks and fhoals.

RUNAWAY Bay, on the north coaft of the ifland of Jamaica, weftward of Great Laughlands river and Mumby Bay, and 9 or 10 miles eaftward of Rio Bueno.

the north-westernmost RUPERT, township of Bennington co. Vermont. It contains 1033 inhabitants.

RUPERT'S Bay, at the N. W. end of the island of Dominica, in the West-Indies, affords good fhelter from the winds, and is deep, capacious and fan-It is the principal bay of the dy. ifland, and on it is erected the town of Portfmouth.

RUPERT's Fort, at the bottom of Hudson's Bay, in North America, is fituated on a river of the fame name, on the east fide of James's Bay; between Slade river on the north, and Pipe clay is found here, which has been

Nodway river on the fouth. N. lat. 51. 50. W. long. 80. 5.

RUPERT's Illand, the most westerly of the four islands in the straits of Magellan, which form the S. fide of Royal Reach.

RUSSELL, a co. of Virginia, bounded north by Greenbrier, and fouth by Lee county. Before Lee was crected out of this county, it contained 3338 inhabitants, including 190 flaves.

RUSSELL, a township in Hampshire co. Maffachufetts, 15 miles weft of Springfield, and 108 weft by fouth of Bofton. It was incorporated in 1792.

RUTHERFORD, a county of Morgan diffrict, N. Carolina, bounded north by Burke and fouth by the State of S. Carolina. In 1790 it contained 7808 inhabi tants, including 614 flaves; but a ne county has been lately formed out of it. RUTHERFORD-TOWN, the capital of the above county. It contains a courthoufe, a gaol, and a few dwelling houfes. RUTHSBOROUGH, a village in Queen Anne's co. Maryland, on Tuckahoc Creek, 6 miles S. E. of Centerville, and 71 N. W. of Greenfborough.

RUTLAND, a county of Vermont, bounded north by Addison co. east by Windfor, fouth by Bennington, and weft by New-York. Otter Creek, and other ftreams, water this county. It, has alfo numerous lakes or ponds, well ftored with fifth ; the chief of thefe, are Lakes Bombazon, and St. Auftin; the former in Hubberton and Caftleton, and the latter in Wells. It contains 25 townships, and 15;565 inhabitants. Here are 14 forges, 3 furnaces, and a flitting-mill.

RUTLAND, a post-town of Vermont, and capital of the above county, on Otter Creek, 55 miles from the mouth of that creek in Lake Champlain; miles northerly of Bennington, 45 W. by N. of Windfor, and 359 N. E by N. of Philadelphia. This town and Windfor, are to be alternately the feat of government for the State. It contains a Congregational church, a courthouse, and about 60 houses. N. lat, 43. 34. 30. W. long. 72. 50. 30. The mean heat here, according to Dr. Williams, is 43 6

Leaft heat

Greatest heat

21

92 The township contains 1407 inhabitants. wrought

with : Rev. dians, here. er piuage ; ieties. Natick ain to being

eftern aving

is co. 21, 25 e Denton.

art of th of long.

re to it, at tigua

nd in elow on it 760,

d co, a the

ndfor i, ou abi-

affaorth-

70

rpo-

nigh

l the

the

t by

\$ 30

for-

the

s fo

t at

neft

an-

was

the

ajor

der

to

'n

in-

478

wrought into crucibles that prove very durable.

RUTLAND, a township of Maffachufetts, Worcester co. 14 miles N. W. of Worcester, and 56 W. of Boston. The town was incorporated in 1722, and contains 1072 inhabitants.

RYE, a township in New Hampshire, on the sea-coast of Rockingham co. opposite the Isle of Shoals, and 8 miles S. of Portsmouth. It was incorporated in 1719, and contains \$65 inhabitants. The coast affords excellent falt hay.

RYE, a township of New-York, West-Chefter co. on Long-Island Sound; 36 miles N. E. from New-York city. It contains 986 inhabitants, of whom 154 are qualified electors, and 123 flaves.

RYE, a township in Cumberland co. Pennsylvania.

RYEGATE, the S. eafternmost townfhip of Caledonia co. Vermont, and feparated from Bath in New-Hampfhire on the eaft, by Connecticut river. It contains 187 inhabitants.

·S

MAR STATE

the Marine 1

SABA, one of the Caribbee Iflands, in the Weft-Indies, belonging to the Dutch, about 12 miles in circumference. It is 13 miles N. W. of St. Fuffatia, and 30 S.W. of St. Bartholomew. N. lat. 17. 39. W. long. 63. 17. SABA, Little, one of the finaller Virgin Iflands, fituated to the fouth of St. Thomas, and belongs to the Danes.

SABLE, Cape, the fouth-westernmost point of the province of Nova-Scotia. N. lat. 43. 24. W. long. 65. 39. Variation of the needle, in 1787, 12. 15. W.

SABLE, Cape, the S.W. point of the peninfula of Florida; 33 leagues E. N. E. 2 E. of the S.W. point of the Dry Tortuga Shoals. N. lat. 24. 57. W. long. 81. 52.

SABLE, Great and Little, two rivers emptying into Lake Champlain from the well fide. Great Sable River is not far from the Saranac, and is fcarcely 60 yards wide. On this ftream are remarkable falls. The whole defcent of the water is about 200 feet, in feveral pitches, the greateft of which is 40 feet perpendicular. At the foot of it the water is unfathomable. A large pine has been feen, in a freshet, to pitch over endwife, and remain feveral minutes under water. The fiream is confined by high rocks on either fide, a space of 40 feet; and the banks at the falls are at leaft as many feet high. In a frefhet; the flood wood frequently lodges, and in a few minutes the water rises to full banks, and then burfts away its obfructions, with a most tremendous crafhing.

SABLE, an island fouth-east off Cape Breton 35 leagues. It is narrow, dreary, and barren. N. lat. 44. 15. W. long. 60. SABLE Point, on the welt fide of the

ifland of Newfoundland. N. lat. 50. 24. W. long. 57. 35.

SABLES, Riviere aux. See Black River, a water of Lake Ontario.

SACATECOLULA, or Lacateculula, on the weft coaft of Mexico, 12 miles from Limpa river. There is a burning mountain near the town of the fame name. The volcano of St. Salvadore, is more northerly about 30 miles, and 12 eaftward of Bernal.

SAC, Grande Riviere du Cul de, a river of the ifland of St. Domingo, which rifes in Montagne de la Selle, by two branches; takes a femicircular courfe of 12 leagues, and runs weftward into the fea, about two leagues northward of Port au Prince.

SACKVILLE, a township of Nova-Scotia, Cumberland co. on Chegnecto Bason, called by the French Beau Basin, and Tintamare, and the N. fide of the River au Lac.

SACO Falls, fituated on Saco river, are 5 miles from the fea. The river is here divided by Indian Ifland, confifting of about 30 acres of land, and on each fide of it tumbles over a precipice of rocks, and mixes with the tide. The prospect from the east fide of the island is very fullime and majeftic. From the beginning of the falls, to the tide below, the difference of height is above 40 feet. There are many corn and faw-mills; on the falls, and below the ifland is a fine bason, where veffels take in their cargoes. Salmon Falls are 10 miles above this.

SACO River is one of the three largest rivers in this district. 'The principal part of its waters fall from the White Mountains. Its course, some distance from its fource, is southwardly; it then fuddenly bends to the east, and crossing into the District of Maine; and then makes a large bend to the N. E: and S. W. 9. W. en Fryeburg general c Great an it from th ble for fh from the by Indian road. the bran erected h from 40 can com the lum boards mills be this rive poife. allow a to país, bar, ar the mai of any year, a fure. fmall n pool, v fave th thể bra the ma and va fea, a Offipe it; an bee ri Hamp its con fource Mour thefe Conn rivers the a ket, new Whi to ai Ellis gave bank bloo ome S Por opp \$rn alfo nak onfined ace of ills are refhet; s, and to full bftruccrafh-

Cape lreary, ig. 60. of the it. 50.

Black

ula, on s from mounname. more eaft-

de, a ningo, le, by ircular ftward north-

Novagnecto Bafin, of the

er, are is here ing of h fide rocks, ofpect Very egin-, the feet. mills ; l is a their miles argeft ncipal White ftance t then roffes then

and W.

S. W. embracing the fine township of Fryeburg, in the county of York. Its general course thence to the feats S. E. Great and Little Offipee rivers fall into it from the weft. This river is navigable for thips to Saco Falls, about 6 miles from the fea. Here the river is broken by Indian Ifland, over which is the poftroad. A bridge is thrown over each of the branches. A number of mills are erected here, to which logs are floated from 40 or 50 miles above; and veffels can come quite to the mills to take in the lumber. Four million feet of pine boards were annually fawed at thefe mills before the war. The mouth of this river lies 4 miles E. of Cape Porpoife. There is a bar which will not allow a veffel of above 100 tuns burden to pais, if fully loaded. Without the bar, and between Fletcher's Neck and the main land, is a pool, wherein veffels of any fize may lie at all feafons of the year, and take in their ladings at pleafure. On the weft fide of the river a fmall neck of land divides it from the pool, which might be eafily cut, and fo fave the hazard of paffing the bar. On the branches of this river, as well as on the main fream, are a great many mills and valuable works: 30 miles from the fea, a finall ftream, iffuing from Little Offipee pond, in New-Hampfhire, joins it; and 20 miles further up Great Offiee river, from another pond, in New-Hampfhire, fwells the Saco, and impels its courfe. Proceeding up the Saco, its fource is found on the fide of the White Mountains, in New-Hampfhire. From these mountains the waters run into Connecticut, Saco, and Androfcoggin rivers. Saco river meanders through the ancient Indian village of Peckwalket, 60 miles from the fea. In 1775, a new river burft into the Saco, from the White Mountains, and ftill continues to aid Saco and a branch of it, called Ellis's river. A mixture of iron ore, gave the waters a red colour for a few days, and the people on the upper banks had a report, that the river was bloody, which they confidered as an ill

SAC

omen to the public concerns. SACRAMENT, St. the S. wefternmoft Portuguele fettlement in Brazil, being oppolite to Buenos Ayres, on the fouthern fide of the river La Plata. It is alfo called Sacraments Coloniz, and was taken by the Spaniards in 1762, after a

month's fiege ; but by the treaty of peace it was reftored.

SACRIFICES Ifland, on the weft coaft of New Mexico, is about 3 miles weftward of a finall ifland ealled the Watering Ifland, and 32 miles from Coiula river.

SADDLE-BACK, an island in Hudfon's Bay. N. lat. 67. 7. W. long. 68. 13. It lies nearly due west of Terra Nieva.

SADDLE River, a village in Bergen co. New-Jerfey.

SADSBURY, a township in Chefter co. Pennsylvania.

SAGADAHOCK was formerly the name of Kennebeck river, in the Diffrict of Maine, after it receives Androicoggin river. See Kennebeck river, and Merry Meeting Bay.

SAGADAHOCK, a great part of the Diftrict of Maine was formerly fo called. In the grant by King Charles II. to his brother the Duke of York, this territory was defcribed in the following manner: " All that part of the main. land of New-England, beginning at a certain place called St. Croix, adjoining to New-Scotland in America, and from thence extending along the fea coaft, to a certain place called Pimaquin, or Pemaquid, and foup the river thereof to its furtheft head as it tends to the northward. and extending from thence to the river Quenebec, and fo up by the fhorteft course to the river of Canada northward." This tract was called the Duke of York's Property, and was annexed to the government of New-York. Ar the revolution, in 1688, it reverted to the crown.

SAGAMOND, a river of the N.W. Territory, which has a fouth-east course, and enters Illinois river, 30 miles below Demi Quian river, and 135 from the Missifippi. It is 100 yards wide at its mouth, and is navigable for small boats or canoes upwards of 180 miles.

SAGATUCK River, a fmall river of Connecticut, which rifes in Ridgefield, in Fairfield co. paffes through Reading and Wefton, and running louthward, leparates Fairfield from Norwalk, aud empties into a harbour of its own name in Long-Ifland Sound.

SAGANUM, or Sagana Bay, in the fouth-weft part of Lake Huron, is about 80 miles in length, and 18 or 20 miles broad. Around it live the Chippeway Indiana.

SAGENDAGO,

.....

SAI

weft of Fort Anne. SAGG HARBOUR, a poft-town and port of entry in the State of New-York, Suffolk co. at the eaft end of Long-Ifland. It contains a Prefbyterian church and about 50 houies. The whale fiftery from this harbour produced 1000 barrels of oil annually. Its exports in 1784 amounted to the value of 6762 dollars. It is 12 miles N. W. of Southampton, 107 E. of New-York, and 202 N. E. by E. of Philadelphia.

SAGUANA, a bay in the north-eaft corner of the Gulf of Mexico, on the coaft of Florida, having numerous ifles on both fides; Cayos del Pagoi on the fouth-eaft, and Farellon de Pagoi on the north-weftward.

SAGUENAI, or Sagueny, a large river of Canada which riles from Lake St. John, and after purfuing an eafterly courfe above 100 miles, empties through the weft bank of the river St. Lawrence, at the town and harbour of Tadouffac. It is about three quarters of a mile wide at its mouth, and is from 80 to 90 fathoms deep, but higher up it is wider; and the narrowness of the channel greatly increases its rapidity, though it is navigable for the largest veffels 25 leagues from its mouth. The harbour, called Port Tadouffac, can afford convenient anchorage for 25 fail of thips of war, and is well fecured from all winds and ftorms. It is deep, of a circular form, and furrounded at a distance with very high rocks, except at the entrance. fmall ftream empties into it, fufficient to water a fleet. The country in the vicinity abounds with marble.

SAGUENAY River, Little, a river of Labrador, which runs fouthward, and empties into the St. Lawrence a fhort way eaftward of the Seven Ifles, and weftward of Balon river, N. lat. 50. 18. W. long. 65.

SAILING Cowe, on the fouth fide of the ifland of Newfoundland, in the great bay wherein is fituated the bay of Trepaffi. It is 6 miles N. of Cape Pine.

SAIL Rock. See St. Ambrofe. ST. ANN, Cape, on the fouth fide of the river St. Lawrence, near its mouth, and on the north coaft of the diffrict of Gafpee, in Lower Canada ; fontherly of Cape Chat. N. lat. 48, 29. W. long, 63-43. ST. ANNE's, a fettlement on the eaff coaft of Cape Breton Island, which has a harbour.

ST. ANNE's Iflands, 3 iflands fituated in the bay of St. Louis de Maraguan, on the coaft of Brazil, S. America.

SAINTS, two iflands near Guadaloupe Ifland. Sec Zaintes.

SAL, La, a river of New Spain. See Culiacan.

SAL, Rio Lagra de, or River of the Salt Lake, on the coalt of Brazil, about 39 miles fouth weft of Salgado river.

SALT BAY, or Baia Saluda, called alfo Salina, is 30 miles north of Cape Tontoral, on the coaft of Chili, and on the S. Pacific Ocean. It has a good fhip-road, which is much reforted to by coafting veffels, for loading falt as well as other produce. Good frefh water may be had near the road.

SALADA, an ifland in the Weft-Indies, whole north-east point lies in lat. 10. 59. N. and long. 64. 12. W.

SALADA, or Sait River, on the coaft of Peru, is within the harbour of Pinas, on the N. Pacific Ocean.

SALAGUA, Port, on the weft coaft of New Mexico, is near the rough headland called San Tiago, and 8 leagues from the Valley of Colima. Here are two good harbours called Las Calletas, or the Creeks, where many fhips may ride. That to the north-weft is very fafe, and land-locked againft all winds, though fmaller than the other. Between Salugua and the White Rock (which joins the head-land) is the port of St. Tioga.

SALAMANCA de Bacalar, a fmall but flourifhing town of Mexico, on the east fide of the ifthmus which joins the peninfula of Yucatan to the continent. It contains about 120 houses, with a bad fort and a small garrifon, to prevent contraband trade. N. lat. 17. 2. W. long. 90. 30.

SALAMANIE Riviere, a river of the N. W. Territory, which empties into the Wabafh from the N. N. E. 14 miles below the river, on the oppofite fide called Ecor a Amelins, and 265 miles above Poft St. Vincent. It rifes by two branches, which unite about 35 miles from its mouth, which lies in lat. 41, 3. 30 N. and long. 86. 25. W.

SALEM, a Moravian fettlement in the N. W. Territory, fituated on Mufkingum river. It was forlaken in 1782, and and plund allies of t SALEM N. W. Te eaft branc miles from fite fide of of Pittfbu acres of la Moravian pole of pi gion amor SALEM of Chrifti and near I of Lake I the weft dwellingis high lan chapel wa built than SALEM bounded (by Delaw 9 townshi are genera have larg befides, f produce f other grai to intermi kers have terians 4. baptifts 3 one. It Alloway runs into miles for tions of c SALEM and capit branch of from its c It contain one for Q ifts; a c 100 hour brick, a There is a and fo fa den can s weft of B of Wood fouth of SALEM leans co. phremago

> SALEM ham co.

and plundered hy the Indians, who were allies of the British army.

SALEM, a Moravian fettlement in the N. W. Territory, fituated on the north-eaft branch of Monongahela river; 5 miles from Gnadenhutten, on the oppofite fide of the river, and 78 miles weft of Pittfburg. Congress granted 4,000 acres of land to the United Brethren, or Moravians, Sept. 1, 1788, for the purpole of propagating the Christian religion among the heathen.

SALEM, New, a Moravian fettlement of Chriftian Indians, on Huron river, and near Pettquotting, on the fouth fide of Lake Erie. The plantations are on the weft bank of the river, and the dwelling-houfes on the east fide, which is high land. In June, 1786, their new chapel was confectated, and is better built than that at Pillgerruh.

SALEM, a county of New-Jerfey bounded eaft by Cumberland, and weft by Delaware river. It is divided into 9 townships; those on Delaware river are generally excellent for pafture, and have large dairies. The land affords, befides, fine banked meadows, which produce flax, Indian corn, wheat, and other grain; but the people are fubject to intermittent fevers. Here the Quakers have 4 meeting-houles, the Prefbyterians 4, the Episcopalians 2, the Anabaptifts 3, and the German Lutherans one. It contains 10,437 inhabitants. Alloway Creek, in this county, which runs into the Delaware, is navigable 16 miles for fhallops, with feveral obstructions of draw-bridges.

SALEM, a post-town of New-Jerfey, and capital of Salem co. fituated on a branch of Salem Creek, about 31 miles from its confluence with Delaware bay. It contains a meeting-house for Baptifts, one for Quakers, and one for Methodifts; a court house, gaol, and about 100 houses, most of them built with brick, and many of them elegant. There is a wooden bridge over the creek, and fo far veffels of 40 or 50 tons burden can go up. It is 20 miles northweft of Bridgetown, II fouth by weft of Woodftown, and 37 fouth-weft by fouth of Philadelphia.

SALEM, a township of Vermont, Orleans co. at the fouth end of Lake Memphremagog.

SALEM, New, a township in Rockingham co. N. Hampire, in the fouth-weft

corner of the county, adjoining Plaftow, and divided from Methuen by the Maffachufetts line. It was incorporated in 1750, and contains 1218 inhabitants : diftant 42 miles from Portfmouth.

SAL

SALEM, a port of entry and post-town of Maffachufetts, and the capital of Effex co. 4 miles north-weft of Marblehead, 19 north by eaft of Bofton. and 365 north-east by north of Phila. delphia. It is the fecond town for fize in the Commonwealth, containing (in 1790) 928 houfes and 7921 inhabitants. and, except Plymouth, the oldeft, was fettled in 1628, by Governor Endicot. and was called by the Indians, Naumkeag. Here are a fociety of Quakers. an Episcopal church, and 5 Congregational focieties. The town is fituated on a peninfula, formed by two fmall inlets of the fea, called North and South rivers. The former of these paffes into Beverly harbour, and has a drawbridge acrofs it, built many years ago at private expence. At this place fome part of the fhipping of the town is fitted out; but the principal harbour and place for bufinels is on the other fide of the town, at South river, if that may properly be called a river which depends on the flowing of the fea for the water it contains. So fhoal is this harbour, that veffels which draw more than 10 or 12 feet of water, must be laden and unladen at a diftance from the wharves by the affiftance of lighters. Notwithftanding this inconvenience, more navigation is owned, and more trade carried on in Salem, than in any port in the Commonwealth, Bofton excepted. The fifhery, the trade to the Weft-Indies, to Europe, to the coaft of Africa, to the East-Indies, and the freighting bufinefs from the fouthern States, are here all purfued with energy and fpirit. A bank was eftablished and incorporated here in 1792. The enterprife of the merchants of this place is equalled by nothing but their indefatigable in-dustry and severe economy. This latter virtue forms a diffinguishing feature in the character of the people of this town. Some perfons of rank, in former times, having carried it to an unbecoming length, gave a character to the people in general, of a difgraceful parfimony. But whether this reproach was ever juftly applied in fo extensive a measure or not, nothing can be more injurious

coaft inas, aft of leadgues are etas. may very inds,

ween

hich St.

ic caff

th has

uated

guan.

loupe

See

f the

about

alled

Cape

good

to by

well

water

t-In-

1 lat.

nd on

er.

mall t the i the ient. th a pre-. 2.

the

into niles fide niles two iles 41. the cin-

82, and time ; for it may justly be faid of the inhabitants of Salem at this day, that, with a laudable attention to the acquifition of property, they exhibit a public fpirit and hospitality, alike honourable to themselves and their country. A general plainnefs and neatnefs in drefs, buildings and equipage, and a certain ftillnefs and gravity of manner, perhaps in fome degree peculiar to commercial people, diffinguish them from the citizens of the metropolis. It is indeed to he wilhed that the fober industry here fo univerfally practifed, may become more extensive through the Union, and form the national character of Federal Americans. A court-house, built in 1786, at the joint expense of the county and town, forms a principal ornament, and is executed in a ftyle of architecture that would add to the elegance of any city in the Union. The fupreme judicial court holds a term here the fecond Tuefday of November, the courts of common pleas and feffions, the fecond Tuefday of March and September. A manufactory of duck and fail-cloth was lately inftituted here, and is profecuted with much fpirit. The melancholy delution of 1692, refpecting witchcraft, originated in this town, in the family of the Rev. Mr. Paris, the then minister, and here was the principal theatre of the bloody bufinefs. At the upper end of the town, at a place called, from the number of executions which took place there, Gallows Hill, the graves of the unhappy fufferers may yet be traced. Though this unfortunate and difgraceful butinefs was chiefly transacted here, it is we'l known that the leading people, both of church and State, in the colony, took an active part in it. Unjust therefore and highly abfurd it is to fix a peculiar odium on the town of Salem for what was the general weaknefs or crime of the country. The town of Salem is connected with Beverly by Effex bridge, upwards of 1500 feet in length, crected in 1789. It is high water here, at full and change, 3c minutes after II o'clock. The works for the defence of the harbour confift of a fort and citadel. A gate remains

walls. Salem village; see Danvers. inouth, lie Salinas N. lat. 42. 30. W. long. 70. 50. SALEM, a township in Well-Chefter coming to load falt.

to be made, and fome repairs to the

SAL

co. New York, bounded eafterly and foutherly by the State of Connecticut, and westerly by Poundridge and Bedford townships and Croton river. It contains 1453 inhabitants; of whom 202 are electors, and 19 flaves.

SALEM, a township on the E. bounds of Washington co. New York, bounded westerly by Argyle, and southerly by Albany co. It contains 2,186 inhabitants; of whom 368 are electors, and 22 flaves.

SALEM, the name of two townships of Pennfylvania, the one in Luzerne co. the other in that of Weftmoreland.

SALEM, a post-town of North-Carolina, Stokes co. on the W. fide of Wack. Creek, which, with other ftreams, forms the Gargalis, and empties into Yadkin river. It contains above 200 houfes, regularly built, and chiefly occupied by tradefinen. A paper-mill has been erected here by the Moravians, which is very ufeful. The Moravians formed this fettlement in 1766. It is 16 miles S. E. of Ararat or Pilot mountain, 35 N. E. by N. of Salifbury, and 531 S. W. by W. of Philadelphia.

SALEM, the chief town of Surry co. in Salifbury diffrict, North-Carolina.

SALFORD, Upper and Lower, two townships in Montgomery co. Pennsylvania.

SALGADO, a river on the S. coaft of Brazil, 13 leagues N. E. of Rigo Lagoa de Sal, or Salt Eake river. It is navigable only for fmall boats, but the harbour is very good, lying behind the fands.

SALENAS, on the west fliore of the Gulf of Mexico, lies northward of Panuco river, and nearly under the tropic of Cancer. W. long. 99. 30.

SALINAS, Cape, on the coaft of Terra Firma, lies oppolite the N. W. point of the illand of Trinidad, which forms the paflage called the Gulf of Paria; 30 leagues S. or S. by W. from Cape Tres Puntas, or Three Points.

SALINAS Gulf, on the weft coaft of Mexico, N. W. of the ifland of Cano, which is N. N. W. of Cape Baruco. The ifland Cano is in lat. 8, 40. N.

SALINAS, Great, or Salt Bay, on the coaft of Brazil, is fouth-eaft of Cape Cors. The entrance into the harbour is in lat. 3. 40. fouth, and N. E. from its mouth, lie Salinas Shoals, or Baxos de Salina. It is a noted harbour for fhips coming to load falt.

SALINAS,

SALIN/ Peru, bet Guaco, w of the Ro moft of t harbour at SALINA of the iflan N. N. W. which laft the city of SALIN/ fhore of t miles, but fand 12 m a mile in large fhips the harbo be attende

the N. E. SALINE The Saline weft bank mouth of Genevieve which is from a fall It is near kafkias vi

SALINA of the iflar of the poi SALISB

> Carolina, ties of Ro gomery, S Cabarras, bounded 1 and S. by ore is foun have been pig, baramount ; cultivated wealthy.

tants, of

SALISB

diffrict, an Rowan co Creek, al with Yad houfe, gaa is a flouri fine count of the Mo W. of Ha borough, ville, and N. lat. 33

482

SAL

ous than to continue it at the prefent

ly and cticut, Beder. It whom

bounds boundutherly 6 inhars, and

vnships rne co. d.

-Caro-Wack. , forms Yadkin houles, pied by s been which formed 6 miles ain, 35 S. W.

rry co, blina. , two ennfyl-

coaft of Lagoa vigable bour is ls. of the of Pae tropic

of Terpoint h forms Paria ; n Cape

coaft of Cano, Baruco. N. , on the of Cape harbour from its axos de or fhips

LINAS,

SAL

SALINAS, a harbour on the coaft of Peru, between Partridge Strand, and Guaco, which diffance is an miles north of the Rock called Maltefi, the outermost of that group of rocks. This harbour affords nothing but shelter.

SALINAS, a point on the fouth coaft of the ifland of St. Domingo, has to the N. N. W. the celebrated bay of Ocoa, which laft is r8 leagues W. S. W. of the city of St. Domingo.

SALINAS Shoals, due north from the fhore of the north coaft of Brazil 12 miles, but are joined to it by a reef of fand 12 miles in length, and about half a mile in breadth; and on which no large fhips mult venture. They lie off the harbour of Salinas; and ought to be attended to by fhips that come out to the N. E. from that harbour.

SALINE, a hamlet, commonly called The Saline, in Louifiana, fituated on the weft bank of the river Miffifippi, at the mouth of a creek, 4 miles below St. Genevieve. Here all the falt is made which is ufed in the Illinois country, from a falt fpring which is at this place. It is near 9 miles S. W. by S. from Kafkafkias yillage.

SALINAS, a bay near the S. E. point of the island of Martinico, and westward of the point fo called.

SALISBURY, a fertile diffrict of N. Carolina, which comprehends the counties of Rockingham, Guilford, Montgomery, Stokes, Surry, Iredell, Rowan, Cabarras, and Mecklenburg. It is bounded N. by the State of Virginia, and S. by the State of S. Carolina. Iron ore is found in feveral parts, and works have been erected which manufacture pig, bar-iron, &c. to a confiderable amount; tobacco of good quality is cultivated here, and the planters are wealthy. It contains 66,480 inhabitants, of whom only 8,138 are flaves.

SALISBURY, the capital of the above diftrict, and a poft-town, is fituated in Rowan co. on the N. W. fide of Cane Creek, about 5 miles from its junction with Yadkin river. It contains a court houfe, gaol, and about 100 houfes. It is a flourifhing place, in the midft of a fine country, and lies about 25 miles S. of the Moravian fettlements, 211 W. S. W. of Halifax, 110 W. S. W. of Hill(borough, 144 N. W. by W. of Fayetteville, and 567 S. W. of Philadelphia. N. lat. 35. 47. W. long. 80, 17. SAL

482

SALISBURY, a township in Effex co. Maffachusetts; is divided into two parifhes. The most ancient fettlement in this town is in the lower parish, at which place the general court of the former province of Massachusetts Bay was fometimes held. The part of the town at prefent most flourishing, is a point of land formed by the junction of Here Merrimack and Powow rivers. is a village very pleafantly fituated on the bank of the Merrimack, where, before the revolution war, fhip-building was carried on to a confiderable extent, which, though now much decreafed, is ftill not wholly laid afide; and this, with its auxiliary trades, and fome little navigation, owned and fitted here, give the place a very lively and bufy appearance. The continental frigate Alliance, was built at this place, under the direction of Mr. Hacket, a very respectable naval architect. It is between 3 and 4 miles northerly of Newbury-Port, and 46 N. E. of Bofton. It was incorporated in 1640, and contains 1780 inhabitants. See Powow River.

SALISBURY, a township of Vermont, on Otter Creek, in Addison co. Trout Pond, or lake Dunmore, 5 miles long, and 2 broad, is in this town. It contains 446 inhabitants, and is 15 miles E. by N. of Mount Independence.

SALISBURY, a confiderable agricultural township in Hillsborough co. New-Hampshire. It is fituated on the west fide of Merrimack river, at the mouth of Blackwater river, and opposite to Canterbury; 10 or 12 miles northerly of Concord. It was incorporated in 1768, and contains 1372 inhabitants.

SALISBURY, the Wiatiac of the Indians, is the north-wefternmost township of Connecticut, Litchfield co. having Massachusetts N. and New-York weft. Here are several forges and ironworks, and a paper-mill. During the late war several pieces of cannon were cast in this town.

SALISBURY, a town of Delaware, Newcaftle co. on the north fide of Duck Creek, on the fouth line of the county; 91 miles S. E. of Noxtown, and 12 N. W. of Dover.

SALISBURY, the name of two townfhips in Pennfylvania, the one in Lancafter co. the other in that of Northampton.

SALISBURY, a post-town of Mary-H h a land, SAL

land, fituated on the eaftern shore of | of the island of Jamaica, eastward of Chefapeak Bay, in Somerfet county, between the two principal branches of Wicomico river. It contains about 30 houses, and carries on a confiderable lumber trade. It is 5 miles fouth of the Delaware State line, 20 N. W. of Snow-Hill, 15 S.W. of Vienna, a port of entry, and 163 S. by W. of Philadelphia.

SALISBURY, a finall town of Virginia, 26 miles from Alexandria, 20 from Leefburg, and 182 from Philadelphia.

SALISBURY, an ifland at the weft end of Hudfon's Straits, eaft of Nottingham Ifland. N. lat. 63. 29. W. long. 76.47.

SALISBURY Point forms the north fide of the mouth of Merrimack river, or Newbury harbour, in Maifachufetts. N. lat. 42. 49. W. long. 70. 54.

SALLAGUA, a harbour on the weft coaft of New Mexico, which affords good anchorage. N. lat. 18. 52. See Salagua.

SALMON, Fall, the name of Pifcataqua river from its head to the Lower See Pascataqua Falls at Berwick. River.

SALMON Falls, in Saco river, on the line between the Diffrict of Maine and the State of New-Hampshire, 10 miles above Saco Falls. The number of faw-mills on the river has neither deftroyed or leffened the quantity of falmon in it. The mill-dams do not extend across the river, and there is a curiofity in feeing the exertion of thefe fifh in making their way up the falls : when the fun thines clear in the morning, they are frequently feen engaged in this enterprife, moving from one rock to another, and refting on each, in fpite of the cataract which oppofes their progress, until they have gained the ftill waters above.

SALMON Point, on the east coast of the ifland of Newfoundland, and N. E. of Claune Point, which is the north entrance into Conception Bay.

SALT Island, one of the fmaller Vir. gin Itles, and weft of Cooper's Ifland. N. lat. 21. 30. W. long. 71. 3.

SALT Island, on the fouth coast of the island of Jamaica, off Old Harbour, and N. N. E. of Portland Point.

SALT Key, a fmall island in the W. Indies. N. lat. 11. 30. W. long. 71. 3.

Port Royal.

SALT Lake, in the State of New-

York. See Onondago Lake. SALT River, in Kentucky, is formed by three principal branches, and empties through the fouth east bank of the Ohio, by a mouth 80 yards, according to others, 150 yards wide; 20 miles below the Rapids. It is navigable for boats about 60 miles. It has good lands on its head waters, but they are low and unhealthy; for 25 miles from its month, the land on each fide is level and poor, and abounds with ponds. Between Salt and Green rivers there are two fprings of bitumen, which, when analyzed, is found to be amber.

SALT River, on the north thore of the illand of Jamaica, is nearly due fouth from Point Galina.

SALT River, the arm of the fea which feparates the ifland of Gaudaloupe, in the West-Indies into two parts, and communicates with the ocean on both fides of the ifland. It is two leagues in length ; 15 or 16 paces broad. The navigation is hazardous, nor will it admit veffels above 25 tons.

SALTA, a town of South-America, two-thirds of the way from Buenos Ayres to Potofi ; where immenfe numbers of dattle winter, and are fattened on their way to Potofi.

SALTA, a town of South America, in the province of Tucuman, 58 miles fouth of St. Salvador. It contains two churches, four monasteries, and about 400 houses. It is a place of great refort on account of the large quantities of corn, meal, wine, cattle, falt, meat, fat, hides, and other commodities, which are fent from this place to most parts of Peru. S. lat. 25. 20. W. long. 66. 30.

SALTASH, a township of Vermont, Windfor co. 12 miles weft of Windfor, It contains 106 inhabitants,

SALT Lick Town lies 18 miles below the fource of Big Beaver Creek, and 34 above the Mahoning town. See Big Beaver Creek.

SALT Petre Creek, in Baltimore co. Maryland, falls into Gunpowder river on the western fide ; 14 miles E. N. E. of Baltimore, in north lat. 39. 20. ; and nearly 2 miles north-wefterly from the western point of Gunpowder Neck.

SALT SPRING River, in the N. W. SALT Pond Bay, on the fouth coaft | Territory, rifes near the E, line of the NewNew Jerfe fouth-eafty below the r ly 30, by 1 the Great and 10 mi fpring, wh SALUD which rife lina, and, Broad rive bia, and f SALUT of the S. Domingo Caves, as ftraight li lat. 18. 6 SALVA vince of near the h foot of a part of th A little a river, whi river Leo and is 63 tero. S. l SALV Mexico, on a rive has few h N. fide of the Char dians. 1 ftands, ar indigo, w tle. N. SALV. in S. An Bay, is Saints, v This cit and com high and one fide, the other manner i has very pulous, parison, Brazil. made in 15. W. SALV town of which r Bayamo

of the te

ward of

f New-

formed d empc of the cording b miles able for s good they are es from is level ponds. here are h, when

hore of ue fouth

the fea Gaudavo parts, ocean on is two is broad. nor will

Buenos fe numfattened

America, 58 miles ains two d about reat reuantities t, meat, s, which parts of 66.30. Vermont, Windfor.

and 34 See Big

more co. der river E. N. E. zo.; and from the leck. e N. W. he of the NewNew Jerfey Company's lands, and runs fouth-eaftward into Ohio river, 10 miles below the mouth of the Wabath, and nearly 30, by the courfe of the river, above the Great Cave. It runs above 56 miles; and 10 miles from its mouth is the falt fpring, which gives name to the river.

SAL

SALUDA, a river of S. Carolina, which rifes on the borders of N. Carolina, and, taking a S. E. courfe, joins Broad river at the township of Columbia, and forms the Congarce.

SALUT, Port, lies on the S. W. fide of the S. peninfula of the ifland of St. Domingo; about 14 leagues from Les Caves, as the road runs, and only 7 in a ftraight line S. W. of that town. N. lat. 18. 6. W. long. 76. 20. SALVADORE, St. a town in the pro-

SALVADORE, S. a town in the province of Tucman, in S. America, and near the borders of Peru. It lies at the foot of a high mountain, which forms part of the eaftern chain of the Andes. A little above the town is a confiderable river, which afterwards empties into the river Leon. It has about 300 houfes, and is 63 leagues N. of St. Jago del Eftero. S. lat. 24. 22. W. long. 66. 27.

SALVADOR, St. a fmall city of New-Mexico, in the province of Guatimala, on a river 12 miles from the ocean. It has few houfes, and little trade. On the N. fide of it, are lofty mountains, called the Chantales, inhabited by poor Indians. In the bottom, where the town fands, are plantations of fugar-canes and indigo, with a few farms for rearing cattle. N. lat. 13. 5. W. long. 90. 3.

SALVADORE, St. the capital of Brazil, in S. America, called alfo the city of the Bay, is within the fpacious Bay of All Saints, which is full of fruitful ifles. This city, which has a noble, fpacious, and commodious harbour, is built on a high and fteep rock, having the fea upon one fide, a lake forming a crefcent on the other. The fituation makes it in a manner impregnable by nature, and it has very ftrong fortifications. It is populous, magnificent, and beyond comparison, the most gay and opulent, in all Brazil. Vaft quantities of fugar are made in its neighbourhood. S. lat. 13. 15. W. long 37. 55. See All Saints Bay. SALVADORE DE BAYAMO, St. a

salvadore de BAYAMO, Sr. a town of the island of Cuba, on a river which runs into the head of the bay of Bayamo, about 30 miles N. W. by W. of the town. SAM

SALVADORE, St. or Guanabani, or Cat Ifland; which fee.

SALVAGE, a dry rock off Cape Ann, on the coaft of Maffachufetts. When it bears S. E. 2 leagues diftant, you have 6 leagues N. W. to Newbury-Port bar, and N. & W. 11 leagues to Portfmouth. N. & E. 8 leagues to Idle of Shoals.

SALVATEON de Yguey, a finall town in the ifland of St. Domingo, 28 leagues E. of the city of St. Domingo. It is famous for its fugar-works and luxuriant paftures, in which a vaft number of cattle feed. It is also called *Higuey*, or *Alta Gratia*; which fee.

SAMANA, a large bay at the E. end of the island of St. Domingo. It opens to the N. E. between Cape Samana, which is also called Cape Refon or Cape Grondeur) on the N. and Cape Raphael fouth-eaft of the former, 7 leagues apart. Its mean breadth is about five leagues, and its length 20 leagues. Some mariners reckon Pointe d'Icaque, or Icaque Point, as the fouthern point of the bay, which comes after Cape Raphael, and is only 13 leagues from the head of the bay, and lies in lat. 19. 2. N. and long. 71. 35. W. of Paris. This bay long. 71. 35. W. of Paris. offers a fafe shelter to the stoutest squa-Lying to the windward of the drons. Lying to the windward of the ifland, it has the advantage over all the other places as a maritime poft, which lenders it capable of protecting the whole gulf of Mexico, to which it is in reality a key. The entrance is difficult, and very narrow; because from the fouthern fide of its opening, runs a breaker, which advances in a point towards Port Banifter, and between which, and the northern coaft, nature has placed the rock or fhallow, called the Rebels. This rock narrows the entrance, fo that between it and the land, forming the N. fide, in the interior of the bay, there is little more than 800 fathoms. Thus a battery on fhore, and another on the rock, the Rebels would, by their crofs fire, completely defend the entrance against even the smallest veficis; and a battery on the other fide of the Rebels would effectually prevent, any vefiel from entering between it and the breakers. See Old Cape Francois.

SAMBA BAY, or Zamba, on the N. coaft of the Spanish Main, or Terra Firma, in S. America, is W. of St. Martha's river.

Hh 3

SAMBALLAS,

SAMBALLAS, a rocky point remarkably long and low, on the N. fide of the Ifthmus of Darien, which is fo guarded with rocks and fhoals, that it is very dangerous coming near it. N. lat. 9. 40. W. long. 78. 43.

SAMBALLAS, a multitude of fmall iflands, scattered at very unequal diftances fome only 1, fome 2, fome 3, and fome 4 miles from the fhore, and from each other, extending a confiderable diftance along the northern fhore of the Ifthmus of Darien, and with the adjacent country, its hills and forefts of perpetual verdure, form a charming profpect from the fea. There are na-vigable channels between most of the iflands, through which thips may pais, and range the coaft of the ifthmus; the fea between them and the fhore being navigable from one end to the other, and affords every where good anchorage in firm fandy ground, with good landing either on the iflands or the main. Most of these islands are low, flat, and fandy, covered with a variety of trees, and abound with shellfifh of feveral kinds. Some of them afford fprings of fresh water, and convenient careening places. The long channel between the Samballas Iflands and the ifthmus is from 2 to 4 miles in breadth, extending from Point Sambal-las to the Gulf of Darien and the coaft of the ifthmus, full of fandy bays, with many fireams of water.

SAMBOROUGH, Cape and Island, on the S. coaft of Nova-Scotia, and weftward of Chebucto bay and harbour, on which is a light-house for the direction of ships, in lat. 44. 30. N. and long. 63. 32. W. High water at full and change at 8 o'clock.

SAMGANOODHA, or Samnanoodha, a harbour on the N. E. fide of Oonalafhka Ifland, on the N. W. coaft of N. America, 10 miles E. of Egoofhak bay. Ships can lie here landlocked from all winds in 7, 6, and 4 fathoms water. It abounds with hallibut, falmon, &c. N. lat. 53. 55. W. long. 166. 30. 15. SAMILITAM, ariver on the W. coaft of New Mexico, 12 miles from Point Artela on one fide, and 6 farther to Copalita river. At its mouth is an Indian town, where a fhip's company may find provisions and frefh water.

SAMPTOWN, a village in Middlefex co. New-Jerfey, 21 miles N. E. of Quibbletown, above 13 S. wefterly of Elizabethtown.

SAMPSON, a co. of Fayette diftrict, N. Carolina, bounded N. by Johnson co. and S. by Bladen. It contains 6,065 inhabitants, including 1,183 flaves. The court house, where a post-office is kept, is 36 miles from Fayetteville, 23 from Crofs Roads, near Duplin court-house; and 543 from Philadelphia.

SAMPUTA, a town of Mexico. See Angelos.

SAMBALLET Point, near the mouth of the river Darien, and N. W. of the Island of Pines. It is 12 miles eastward of Port Scrivan.

SANBORNTOWN, a township of New-Hampshire, Strafford co. fituated on the point of land at the confluence of Winnipisiogee and Pemigewasser rivers. It was incorporated in 1760, and contains 1587 inhabitants. In this town is the appearance of an Indian fortress, consolution of 5 distinct walls, one within the other. Some pieces of baked earthen ware have been found here, from which it is supposed that the Indians had learned the potter's art.

ed the potter's art. SANCOTY Head, the E. point of Nantucket Island, on the coaft of Massachusetts. N. lat. 41.15. W. long.69.58.

SANCTOS BAHIA, or Saint's Bay, on the coaft of Brazil, where the land lies due E. and W. for 20 leagues. The city of Saints or dos Sanctos is fituated on an ifland called Amiaz, on the W. fide of the entrance into the harbour, as alfo the town of St. Vincent. S. lat. 24. W. long. 45. 15.

SANDGATE, a mountainous townfhip of Bennington co. Vermont, 13 miles N. of Bennington. It contains 773 inhabitants.

SAND-HILL Bay, is on the N. fide of the peninfula, at the S. E. end of the ifland of St. Christopher's, in the W. Indies.

SANDISFIELD, a hilly township in Berkshire co. separated from Litchfield co. in Connecticut by the south State line; 22 miles S. by E. of the shire-town, and 135 W. by S. of Boston. It was incorporated in 1762, and contains 1581 inhabitants.

SANDOWN, a township in Rockingham co. New-Hampshire, was taken from Kingston and incorporated in 1756; and contains 561 inhabitants.

SANDUSKY, fort in the N. W. Territory, fituated on the fouth fide of the bay bay of th end of L SANDU weftern fi ed like lake by 4 Its length 7 miles. this lake mile and fmall riv The fort lat. 41. . SAND of the 1 near a bi tween w! purfues a into the Lake. peace at have ced land 6 m where a miles fo Sanduík with let gentle al it is larg SAND ern part north of incorpor inhabita SAND town at Barnftal breadth of Plyn Bofton. of hous and a p through bitants : the pro from B: Indian was fit Manna near th There Sandwie called b the feco is an I Pond, i wich, a village, along f

end of Lake Erie.

SAN

SANDUSKY Lake, or Bay, at the fouthwestern fide of Lake Erie, is a gulf shaped like a fhoe, and entered from the lake by a very thort and narrow firait. Its length is 17 miles, its greateft breadth 7 miles. From the north-weft part of this lake, there is a portage of only a mile and a quarter to Portage river, a fmall river which runs into Lake Erie. The fort flands opposite to the gut. N. lat. 41. 51. W. long. 83. 3. 30.

SANDUSKY River, a navigable water of the N. W. Territory, which rifes near a branch of the Great Miami, between which is a portage of 9 miles. It purfues a north-east course, and empties into the fouth-weft corner of Sandufky The Indians, by the treaty of Lake. peace at Greenville, August 3, 1795, have ceded to the United States a tract of land 6 miles fquare upon Sandufky Lake, where a fort formerly flood, and two miles square at the Lower Rapids of Sandusky river. It is a confiderable river, with level land on its bank, its ftream gentle all the way to its mouth, where it is large enough to receive floops.

SANDWICH, a township in the northern part of Strafford co. N. Hampfhire, north of Winnipifiogee Lake. It was incorporated in 1763, and contains gos inhabitants.

SANDWICH, Maffachuletts, a posttown at the bottom of Cape Cod, in Barnstable co. It extends the whole breadth of the cape, and is 18 miles S.E. of Plymouth, and about 59 miles S. of Bofton. There is a little decent group of houses, on the east fide of the cape, and a pretty fiream of water running through it? Incorporated 1639; inhabitants 1991. It is near the place where the proposed canal is to commence from Barnstable to Buzzard's bay. The Indian town Kitteaumut, or Katamet, was fituated on Buzzard's bay; and Mannamit was the name of a place near the bottom of Buzzard's bay. There is a place on the fame bay, on Sandwich fide, called Pokefet, ufually called by the Indians Poughkeeffe. It is the fecond parifi in Sandwich. There the fecond parifli in Sandwich. is an Indian territory, called Herring Pond, in the neighbourhood of Sandwich, about 5 miles N. W. from this village, and fo extending from thence/ rizon than when the is below it. The

bay of the fame name, at the fouth-weft | cluded within the township of Plymouth. It contains about 120 fouls, one half of whom are mixed. The Indian name of this territory is not generally known. They appear to have been confidered as a diffinct tribe, now known by the name of the Herring Pond Indians.

8 A N

SANDWICH, New, a plantation in Lincoln co. Diffrict of Maine, containing 297 inhabitants.

SANDWICH Islands, a group of islands in the South Sea, difcovered by Captain Cook, who gave them the above name in honour of the Earl of Sandwich, under whole administration they were first vifited. They confift of IT illands, extending in lat. from 18. 54. to 22. 15. N. and in long. from 1 50. 54. to 160. 24. W. They are called by the natives Owhyhee, Mowee, Ranat, Morotinnee, Tahowrowa, Morotoi, Waohoo, Atooi, Neeheehow, Oreehoua, and Tahoora; all inhabited, except Morotinnee and Tahoora. Belides thefe, the natives fpeak of another, lying to the weft-fouth-weft of Tahoora; which is low and fandy, and vifited only for the purpole of catching turtle and fea-fowls. As they do not know of any others, it is probable that none exift in their neighbourhood. An account of each inhabited island will be found in its proper place. The climate differs very little from that of the Weft-India iflands in the fame latitude. Upon the whole, perhaps, it may be more temperate; nor are there any traces of those violent winds and hurricanes which render the ftormy months in the West-Indies fo dreadful. There is also more rain at the Sandwich Ifles, where the mountainous parts being generally enveloped in a cloud, fucceffive fhowers fall in the inland parts, with fine weather, and a clear fky, at the fea fhore. Hence it is, that few of those inconveniences to which many tropical countries are fubject, either from heat or moisture, are experienced here. The winds, in the winter months, are generally from east-fouth east to north east. The tides are very regular, ebbing and flowing 6 hours each. The flood comes from the ealtward; and it is high water at the full and change of the moon, 45 minutes paft 3. Their greateft rife is 2 feet 7 inches, and the water is always 4 inches higher when the moon is above the hoalong thore to Monument Ponds, all in- vegetable productions are nearly the fame Hh4

Eliza-

liftria. ohnfon 16,065 s. The s kept, 3 from houfe;

. See

mouth of the :s eaft-

New-

on the

Wins. It ontains is the conhin the arthen which learnint of Maffa-69.58. ay, on nd lies The

tuated he W. our, as at. 24.

town_ nt, 18 intains

fide of the ifndies. hip in chfield State town, t was \$ 1581 kingtaken

d in nts. Terof the bay

fame as at the other illands in this ocean. | The taro root is of a fuperior quality. The bread-fruit trees thrive not in fuch abundance as in the rich plains of Otaheite, but produce double the quantity of fruit. The fugar-canes are of a very unufual fize, iome of them meafuring 11 inches and a quarter in circumference, and having 14 feet eatable. There is also a root of a brown colour, shaped like a yam and from 6 to 10 pounds in weight, the juice of which is very fweet, of a pleafant taffe, and an excellent fubftitute for fugar. The inhabitants are undoubtedly of the fame race that poffeffes the iflands fouth of the equator ; and in their perfons, language, cultoms and manners, approach nearer to the New-Zealanders than to their lefs diftant neighbours, either of the Society or Friendly Iflands. They are in general above the middle fize, and well made. They walk very gracefully, run nimbly, and are capable of bearing very great fatigue; although, upon the whole, the men are lowewhat interior, in point. of firength and activity, to the Friendly Iflanders, and the women lefs delicately formed than those of Otaheite. Their complexion is rather darker than that of the Otaheitans, and they are not altogether fo handfome a people. , However, many of both fexes have fine open countenances; the women in particular have good eyes and teeth, with a fweetnefs and fenfibility of look, that render them very engaging. Their hair is of a b: ownifh black; neither uniformly fraight, like that of the American Indians; nor uniformly curling, as among the negroes of Africa. There is one peculiar characteriftic of this great nation, and which is also prevalent in the Friend ly Islanders, that even in the handfomest faces there is a fullnefs of the poftril, without any flatness or spreading of the nofe. This may probably be the effect of their usual mode of falutation, which is by prefling the ends of their noles together. The fame fuperiority that is observed among the higher ranks, through all the other islands, is found here. The chiefs are, almost without exception, perfectly well formed ; whereas the lower fort, befides their general inferiority, are fubject to all the variety of make and figure that is feen in the populace of other countries." Tattooing the body is much practifed here. The

natives rife with the fun, and, after enjoying the cool of the evening, retire to eft a few hours after fun-fet. Their inftruments of war are spears, daggers, clubs, and flings. The dagger is a weapon peculiar to themfelves. It is from r to a feet long, made of heavy black wood refembling ebony, tharpened at one or both ends, and fecured to the hand by a ftring, Its ule is to ftab in close fight, and it is well adapted to the purpole. They have also the knife or faw, with which the New-Zealanders cut up their flaughtered enemies. For defensive armour they wear firong mats, which are not eafily penetrated with fuch weapons as their's.

SANDWICH, or Hawkes River, is two miles within Chebucto Harbour, in Nova-Scotia.

SANDWICH, a fmall river at the bottom of Barnstable Bay, in Barnstable co. Maffachufitts.

SANDY Bay, at the E, end of the ifland of Jamaica; fouthward of Mulatto river, and 6 miles N. of Mauchaneel Harbour.

SANDY Bay, at the N. W. extremity of the fisme ifland, W. of Stoddard Bay, and E. of Green Ifland. Little Sandy Bay, on the S. E. part of the ifland is about a league W. of Point Morant. Sandy Cays lie off the entrance of Port Royal Harbour.

SANDY Cove, to the north-weftward round the point of Cape Ann, on the coaft of Maffachufetts, and lies between two head-lands. N. lat. 42. 45. W. long, 70. 30.

SANDY Harbour, on the E. fide of the ifland of St. Lucia, near the S. E. point of the ifland, where a fmall river empties into the ocean.

SANDY Hill, a fmall delightful village in New-York State, two miles north of Fort Edward, on a high hill, overlooking Hudfon's river from the eaft.

SANDY Hook, or Point, in the townfhip of Middleton, in New-Jerfey, forms a capacious harbour, thence and from the inlet paffes to New-York, about 25 miles diffant. From Montauk Point, on Long-Ifland, to the Hook, is S. W. by W. $\frac{1}{2}$ W. 14 leagues, and then W. by S. 22 leagues. The pilots are obliged to keep a good and iufficient whaleboat ready at the Hook. High-water, at full and change, 37 minutes after 6 o'clock. The light-houfe, on the north point

21

Ì

er en-

tire to

tir in-

ggers,

Weg-

rom r

wood

me or

nd by

fight,

rpole.

with

) their

ve ar-

ch are

apons

is two

n No-

e bot-

le co.

of the

Mu-

ucha-

remi-

ddard

Little

of the

Point

e en-

tward

n the

tween

. W.

of the

point

emp-

illage

rth of

luok-

own-

orms

from

ut 25

oint,

w.

W.

blig-

hale-

ater,

ter 6

north

point

point of the Hook, lies in lat. 40. 30. N. and long. 74. 2. W. At the first difcovery of America, few or no cod-fifh were to be found fouthward of the banks of Newtoundland, and Sable Ifland. About to years ago they were difcovered off Sandy Hook, and they have ever fince become more plenty on the fifting grounds off the Neverlink, in 6, 7, and 8 iathoms water.

SANDY Ifland, a small ifland off the welt coaft of the island of Antigua, about two miles from the thore.

SANDY Point, the S. eaftern extremity of Barnstable co. Maffachufetts ; called Point Care, by Gofnold. The courfe to Nantucket light-houfe, is S. S. W. 3 leagues. N. lat. 41. 24. W. long. 69. 35. SANDY Point, in the ifland of Toba-

go N. lat. 11. 6. W. long. 60. 37.

SANDY Point, the most westerly point of the ifland of St. Chriftopher's; called alfo Beltates Point.

SANDY Point, near the fouth-east part of the ifland of St. Lucia, and forms the fouthern limit of Sandy Harbour.

SANDY Point, near the fouth-east point of the island of Antigua, on the larboard fide of the opening into Willoughby Bay.

SANDY Point, the north east point of Nantucket Ifland, on the coaft of Maffachufetts. N. lat. 41. 23. W. long. 70.

SANDY Point, a town of the ifland of St Christopher's, on the fouth-west fide of the ifland, in St. Anne's parifh, and in Fig-tree Bay. It is a port of entry, and is defended by Charles Fort, and Brimftone Hill, both near the town.

SANDY River, in Kentucky. See Big Sandy River.

SANDY River, in the diffrict of Maine. rifes in Cumberland co. confifts of many fmall branches ; runs a N. E. courfe, and empties into Kennebeck river, at the N. W. corner of the township of Norridgewalk.

SANDY River, the plantations in Lincoln co. diffrict of Maine, of this name, in 1790, were as follow :

the second days	Inhabitants.
Mouth of Sandy river	327
Sandy river No. 1	494
No. 2	130
and 7 mile Brook 5	350
25 mile Pond and ? Titcomb Town	264

SANDY River Old Town. See Titcomb. Martin Martin

SANDYSTON, a township of New-Jerfey, Suffex co. on Delaware river, at the foot of the Blue Mountains, about 11 miles above Walpack, and about as far N. W. of Newton, It contains 519 inhabitants, including 26 flaves.

SANFORD, a poft-town of the diffrict of Maine, nine miles from Waterbury court-house, 15 from Berwick, and 447 from Philadelphia. It is in York co. o8 miles N. of Bofton, and the townfhip contains, in all, 1802 inhabitants.

SANFORD, a township of New-York, Dutchefs co. There are 239 of the inhabitants qualified electors.

SANGALLAN, or Gallan Cape, called Cangallan by the British feamen; is fituated on the coaft of Peru, N. N. W. of the island of Labos, and 3 miles N. W. of Carette Ifland, On the S. fide of the cape is a very good harbour, much frequented by the coaffing thips from Panama and Lima. Off this cape it is very bluftering and ftormy.

SANGERFIELD, a township of New-York, fituated in Herkemer co. which contains 1459 inhabitants, of whom 238 are electors. This town was divided by act of the legiflature, 1797.

SANGUAY, a famous mountain in the eastern chain of the Andes, in the jurifdiction of Macas, in the province of Quito. It is of a prodigious height, and the greatest part of the whole furface covered with fnow. From its fummit iffues a continual fire, and the explofions are fometimes heard at Quito, though 135 miles diftant. The country adjacent to this volcano, is totally barren, occasioned by the enormous quantity of ftones and cinders ejected from the mountain.

SAN Juan de Las Lanos, a town of S. America, at the foot of the mountains of Popayan, which is watered by a head branch of Oronoko river.

SANPINK Creek. See Trenton, New-Jerfey.

SAN Miguel de Ibarra, a jurifdiction of Peru, in the province of Quito, containing 8 parifies. Mott of the farms have plantations of fugar-canes and cot-The farms fituated in a lefs hot ton. part of the jurifdiction are fown with maize, wheat and barley. Here are alto great numbers of goats, but not many theep. The Indians here weave a confiderable

a confiderable quantity of cloth and cotton. The mines of falt here have fome mixture of nitre, which renders it not to proper for falting meat ; and accordingly that made at Guyaquil is preferred, though much dearer. Near the village of Mira, are great numbers of wild affes, which increase very faft, and are not eafily caught. They have all the fwiftness of horses, and ascend and defcend hills and mountains with eafe. But the most remarkable circumstance related of these animals is, that as foon as they have carried the first load, their celerity and dangerous ferocity leave them, and they foon contract the flupid look and duliness peculiar to all the affinite species.

SAN Miguel de Ibarra, the capital of the above juridiction. It ftands on a darge plain between two rivers. The parish church is a large and elegant dructure, and well ornamented. It contains 3 convents, a college, a nunnery; and about 12,000 fouls. N. lat. 0, 25. weft long. 76. 20.

SANSONATE Port, or Sanfonette, on the weft fide of New-Mexico, 21 miles from the river Maticaloe. Point Remedios is the fouthern limit or opening of the port.

SANTA, a rapid river, flowing through a valley of the fame name in Peru, about 230 miles N. of Lima. It is near a quarter of a league broad at the place where it is ufually forded, which is near the town of the fame name, forming five principal ftreams, which run during the whole year with great rapidity. The welocity of the current, even when the waters are low, has been found to be a deague and an half in an hour.

SANTA, a town of Peru, fituated on the banks of the river of the fame name on the road from Paita to Lima, and about 230 miles north of that city. It is inhabited by 50 poor families, confifting of Indians, mulattoes, and meftizoes. S. lat. 8. 57. 36. wet long. 79. 30. It was originally built on the feacoaft, from which it is now half a league diffant, and was large and populous, but being pillaged by the English in 1685, it was abandoned.

SANTA BARBARY, on the fouth fide of the eaft end of the ifland of Curacoa, in the W. Indies, is the best harbour in the ifland, where the Dutch have a town and fort.

无法病

SANTA CLARA, an island in the bay of Guyaquil, on the northern part of the coaft of Peru. From this island to Punto Aren, the westernmost point of Puna Island, is 7 leagues E. N. E. S. lat. 3. 30. west long. 80, 36.

SANTA CRUZ, a Danish Island in the West Indies; See St. Croix.

SANTA CRUZ, a confiderable town in the itland of Cuba, having a good harbour at the bottom of the bay of Matanzas, 63 miles eaft of the Havannah. N. lat. 23. 11. weft long. 81. 5.

SANTA CRUZ, or St. Croix, a large ifland lying in the Pacific Ocean, 1850 leagues welt of Lima, in fouth lat. 10. 15. fouth-east of the island of Arfacides, difcovered by Medina in 1595s and fince by Carteret in 1767, and by him called Egmont Island. It is reckoned to be go or soo leagues in circumterence. Great and unprovoked cruelties were committed upon these friendly and hospitable Islanders by Mendana's men, for which Mendana caufed two of his principal officers to be beheaded, and another to be hanged. The natives of this island are as black as the negroes of Africa, their hair woolly, and stained with different colours. Their faces and bodies are tattaooed. . Their only covering is a leaf of a certain tree, their ornaments, arms, and boats, are not unlike those of the inhabitants of Tierra Auftral. The country is fertile and very populous, abounding in eatable roots, 6 or 7 fpecies of bananas, plenty of cocoa trees, almonds, nuts, chefnuts, a fort of apple, fugar-canes, ginger, bread-fruit, &c. Hogs, geele, fowls, partridges, ring and turtle doves, herons, iwallows, and a great variety of birds; and on the coaft a great plenty and variety of fifh. There are here no noxious infects, which are common in other iflands of the torrid zone. In a word, the island of Santa Cruz, and others of the fame group, offer the most valuable refources to navigators who traverse the Great Pacific Ocean, south of the line.

SANTA CRUZ de la Sierra, a large jurifdiction in the kingdom of Peru, but thinly inhabited by Spaniards. I he miffions of Paraguay are in this jurifdiction.

SANTA CRUZ de la Sierra, the capital of the above jurildiction, fituated at the foot of a mountain, on the banks of the the ima north-e ders of ed; the ed with which t of grai unculti quantit 19. 25 SAN in N. long. 1 SAN of S. Gulf. SAN of the Ameri and the thecit banks facrific offered great 1 73. 5. SAN coaft c Ferol. city o which SAL of Da league above admit of St. Thet from accoul bourh advan low, lat. 7 SA north ofar SA Terra by R thage SA above was f much fleets cient falt p the t

the finall river Guapay, about 56 miles north eaft of La Plata, and near the borders of Paraguay. It is thinly inhabited; the houles are of ftone, thatched ed with palm leaves. The valley, in which the city ftands, produces all kinds of grain and fruits, and the woods and uncultivated mountains afford great quantities of honey and wax. S. lat. 19. 25. weft long. 62. 30.

SANTA FE, a town of New Mexico, in N. America. N. lat. 35. 32. weft long. 106. 35. SANTA FE Bay, on the north coaft

SANTA FE Bay, on the north coaft of S. America, weftward of Comana Gulf.

SANTA FE DE BAGOTA, the capital of the province of New Granada, in S. America, is the fee of an archbifhop, and the feat of an university. Near to the city is the lake *Guatavvita*, upon the banks of which the favages formerly facrificed to their idols; to whom they offered much gold, and other things of great value. N. lat. 3. 58. weft long. 73: 5.

SANTA Island or Holy Island, on the coaft of Peru, is opposite to the port of Ferol. It is 3 miles from the port and city of Santa, and as far from Ferol, which is eaftward of it.

SANTA Maria, a river of the Ifthmus of Darien, which is navigable 8 or 9 leagues, and fo far the tide flows; but above that its two branches will only admit cances. It empties into the Gulf of St. Michael in the Pacific Ocean. The town of its name is about 6 leagues from its mouth; and is confiderable on account of the gold mines in its neighbourhood, which are worked to great advantage, but the country about it is low, woody, and very unhealthy. N. lat. 7. 30. weft long 82. 20.

SANTA Port, on the coaft of Peru, is north-eaft of Santa Island, in the mouth of a river of the same name.

SANTA MARTHA, a province of Terra Firma, S. America, bounded east by Rio de la Hacha, and west by Carthagena.

SANTA MARTHA, the capital of the above province, and the fee of a bifhop, was formerly very populous, but is now much decayed, occafioned by the Spanish fleetenet touching there, as they anciently used to do. There are large falt ponds four and an half miles from the town, from which good falt is ex-

tracted and fent to the neighbouring provinces. It ftands near the fea, at the foot of a prodigious mountain, whole fummit is generally hid in the clouds, but in clear weather, when the top appears, it is covered with fnow. In fome places in the vicinity are gold mines, and in others precious ftones of great value.

SAN

491

SANTA Port, on the coaft of Peru, and on the S. Pacific Ocean, lies N. E. of Santa Island, at the mouth of a river of the fame name.

SANTEE, a navigable river of S. Cardlina, the largeft and longeft in that State. It empties into the ocean by two mouths, a little fouth of Georgetown, which laft lies in lat. 33. 27. N. and long. 79. 24. W. About 120 miles in a direct line from its mouth, it branches into the Congaree and Wateree; the latter, or northern branch, paffes the Catabaw nation of Indians, and bears the name of Catabaw river, from this fettlement to its fource.

SANTO ESPIRITU, a captainfhip of Brazil, bounded N. by the captainfhip of Seguro, and S. by that of Rio Janeiro, from which laft the river Parayba feparates it, and after a long course from W. to E. empties into the ocean, in lat. 27. 30. S. This government is the most fertile, and beft furnished with all forts of provisions of any in Brazil; having alfor an incredible quantity of fifh and game. Its low lands being interfected by, a great number of rivers, are very fruitful; and the high grounds, are covered with forefts of large trees. Here it may be noticed that there are three rivers in Brazil, called Parayba, or Paraiba, viz. one which gives its name to a captainfhip already defcribed; the fecond is that above mentioned, and the third empties into the ocean between Cape St. Vincent, and Rio de la Plata.

SANTO ESPIRITU, the capital of the above captainfhip, and indeed the only town in it, is fituated on the fouth fide of a large bay on the eaftern coaft of Brazil, about 9 miles from the fea. It has a caftle in ruins, but no fortifications, and contains about 900 inhabitants. Here are two monalteries and a college. The port is a finall bay, opening to the eaft, interfected with many finall iflands. On the top of a mountain, at fome diffance from the town, is a large white tower, called, by the Portugueie, Noftra

t bay nt of nd to nt of S.

1 the

town

good

Ma-

nah.

arge 1850 10. faci-5955

d by

eck-

um-

ruel-

ndly

na's

oof

ded.

ives

Toes

ined

and

COV-

or-

un-

erra

and

able

enty

uts,

ger,

wls,

he-

of

nty

no:

1 in

ln a

and

noft

vho

uth

rge ru, ds. this

at of the 492

Noftra Senhora de Pena, and near it a fmall church, furrounded with a wall. At the foot of the mountain, are still to be feen the inclancholy remains of a place once called Villa Veja, or the Old City. 8. lat. 20. 36. W. long. 39. 56. SANTO 5, a town in the captainfnip of

St. Vincent, in Brazil; feated on a river 9 miles from the fea, which is there a mile broad, and five fathoms deep. It is defended by a rampart on the fide next the river. It is also guarded by two caftles, one on the fouth fide, and the other in the middle of the town, which contains 2 to inhabitants. It has a parifh church, a monaftery, and a college. S. lat. 24. 26. W. long. 42. 30.

SAONA, or Gaone, a fmall ifland near the S. E. part of the ifland of St. Do. mingo. It is about 8 leagues from E. to W. and 2 from N. to S. which becomes still lefs in the narrowest part. Its circumference is nearly 25 leagues. It lies eaft of St. Catherine Island; and it is not much above a league from Little Palm Tree Point, to that which advances from the north of the Saona. At each of its extremities, E. and W. is a mountain, and there is a third at a point about the middle of the fouthern fide. These mountains at once fhelter and water it, and temper the air. The Indians called this ifland Adamanoy, and had a particular cacique, who was fovereign of the ifland, independent of those of St. Domingo. His fubjects devoted themfelves to commerce with the Spaniards, to agriculture, to cultivation of grain and fruits. They furnished enough for the confumption of the city of St. Domingo, and for provisioning feveral expeditions going from that port. Some Caffilians having cauled the cacique to be eaten by a dog, this act of cruelty became the caule of a quarrel, and the Spaniards having exterminated the unfortunate inhabitants, formed fettlements on their little ifland. It is furrounded with banks and breakers, except at the weftern part; but there is a paffage for finall barks, between its north fide, and the main of the ifland of St. Domingo. The island and its port are a shelter for the mariners failing in this part, who here find water, wood, and wild cattle, all which are in abundance. It is impoffible to have an idea of the vaft quantities of birds, and particularly of wood pigeons, that are feen here, The east-

ern point of the ifland lies in lat. 18. o.

meríh.

of Bal have re

impreg

dients and m

tain ru

calcare

is cove or rath

or fix

or con

inches we fee

mently

water

is faid

than t

matte

bafis (

ral idl

is, th

the m found

flows little

Peopl

they

by w water

expen SA

Spain

SA

co. 1

brand

fords

conta

20 h

ming

S. A

S. la

eaft

iflan

St. /

SI

Sout

the f

nort

of M

fout

the i

Pedr

Poir

16,

S

SI

SI

SA

N. and long. 71. 11. W. of Paris, SAPA, St. Michael de, a village in the valley of Arica, in the province of Charcos, in Peru. It is a final place, but famous for the quantity of Guinea pepper produced in its vicinity. It will not thrive in mountainous parts, but is cultivated in the vallies. The inhabitants of this village fell annually no lefs than 80,000 crowns worth of it. S. lat. 17. 30. W. long. 78. 10.

SAPELO, a village of Georgia, in Liberty co. opposite to the found and ifland of that name, and about 6 miles fouth of Sunbury.

SAPONIES, Indians who inhabit on a north branch of Suiquehannah river. Warriors 30. See Munfays.

SARAMACHA, a river in the Dutch province of Surrinam.

SARANAC, a river of New-York, which paffes through Plattfburg, and empties into Lake Champlain from the weft. It has been explored nearly 30 miles, and there found equal in fize to the mouth. It abounds with falmon, hafs, pike, pickerel, trout, &c. At the mouth of the river, falmon are found in fuch plenty, that it is usual to take 400 or 500 a day, with spears, and small They are caught from fcoop-nets. May till November.

SARATOGA, a county of the State of New-York, bounded E. and N. by Hudfon's river, which feparates it from Renffelaer and Washington counties, and fouth by Mohawk river. It has been effablished fince 1790, and is divided into 8 townships, viz. Greenfield. Ballftown, Charlton, Half Moon, Milton, Saratoga, Galway and Stillwater. In 1796, 3,270 of the inhabitants were qualified electors.

SARATOGA, or Saraghtoga, a townthip of New-York, fituated in Saratoga co. on the W. fide of Hudion's river 56 miles N. of Albany. It contains few houfes in a compact state. In 1790. when it belonged to Albany co. it contained 3,071 inhabitants; and there were here in 1796, 542 qualified electors. It will ever be diffinguished in hiftory, for being the place at which Gen. Burgoyne was obliged to furrender his army, in 1777. This town is also famous for its medicinal waters, called the Saratoga Springs. They are 10 miles from Balltown, in a fhallow vale or marin.

8. 9.

n the

e of

lace,

linea

will

ut is

abit-

) lefs

S.

, in

and

niles

on a

iver.

utch

ork

and

the

30

e to

non,

the

d in

400

mall

rom

e of

ud-

rom

ties,

has

di-

eld,

Ail-

ter.

vere

wn-

oga ve r

few

90,

on-

iere

ors.

ry,

en.

his

fathe

iles

er As, marfh', in feveral respects refembling that of Ballftown. These waters appear to have received as ftrong, if not ftronger, impregnation of the fame kind of ingredients that enter those of Ballftown, and may be a ftream of the fame fountain running through the fame kind of calcareous earth. One of these springs is covered over by a natural cretacious, or rather calcareous pyramid, about five or fix feet high. This hollow pyramid, or cone, has a hole in the top about fix inches over. If we lo k into this hole we fee the mineral water boiling vehemently like a pot over the fire; the water is neverthelefs intenfely cold, and is faid to be, in every respect, smarter than that at Ballftown. The calcareous matter extends for feveral rods from the bafis of this pyramid. There are feveral idle ftories related of this fpring ; one is, that it overflows at certain ftages of the moon. This is not true. As this is found to be falfe, they tell you it overflows once a year; but this has as little foundation in truth as the other. People who live at these springs think they mult relate fomething marvellous by way of enhancing the value of the waters, and reconciling you to the great expense attending these visits.

SARDO, a cape on the coaft of New-Spain, and in the North Sea.

SARECTO, the chief town of Duplin co. N. Carolina, fituated on the N. E. branch of Cape Fear giver, which affords water for rafts to the town. It contains a court-houfe, gaol, and about 20 houfes. It is 130 miles above Wil mington, to the north.

SARENA, on the coaft of Chili, in S. America, on the South Pacific Ocean. S. lat. 29. 40. W. long, 71. 15.

SARINHAYM, a river on the foutheast coast of Brazil, and opposite to the island of Alexo, which is west of Cape St. Augustine.

SARMIENTO Islands, Pedro de, in the South Pacific Ocean, are thought to be the fame as the Duke of York s Islands, northward of the weft end of the ftraits of Magellan. They lie in about lat. 50. fouth, and are about 80 in number.

SARONILLA, or Serranella, fhoals off the island of Jamaica, 25 leagues W. of Pedro Shoals, and 37 W. of Portland Point. The middle of them lie in lat. 25, 10. N. and long. 80. 45. W. SASKACHAWAN, or Safkafrawen, 2

\$-46.

river of N. America, which runs eaftward, and has communication, by thort portages, with Nelfon's river, which empties into Hudfon's Bay.

SASSAFRAS, a finall navigable river of Maryland, which rifes in Delaware State, and runs weftward into Chefapeak Bay. It feparates Kent co. from that of Cecil, and has the towns of Fredericktown, Georgetown, and Saffafras on its banks. The latter is 5 miles E. by N. of Georgetown, and about 3 S. of Warwick.

SATILLA, Great and Little, two rivers of Georgia, which fall into the' ocean, in Camden co. between the Alatamaba and St. Mary's rivers.

saucon, Upper and Lower, townthips in Northampton co. Pennfylvania,"

SAUKIES, or Saikies, an Indian tribe refiding at Bay Puan, in the N.W. Ter-, ritory, near the Minomanies ; which fee.

SAUNDERS *Ifland*, in the S. Atlantic Ocean, one of the imall iflands which furround the two chief of the Falkland Ifles.

SAUNDERS Island, in South Georgia, and in the S. Atlantic Ocean, is about 13 leagues north of Cape Montagues' S. lat. 57. 59. W. long. 26. 54.

SAUNDERS Island, or Sir Charles Saunders' Island, called by the natives Tapoamanao, in the S. Pacific Ocean, is reckoned one of the Society Islands. When Port Royal Bay, at Otaheite, is S. 70. 45. E. diffant 61 miles, this illand bears S. S. W. S. lat. 17. 28. W. long. 151. 4. It is about two leagues long.

SAURA Lower Town, is fituated on the fouth fide of Dan river, in N. Carolina. It was formerly the chief town of the Saura Indians.

SAURA Upper Town, in the fame State, an ancient and well peopled town of the Saura Indians; fituated in Stokes co. on the fouth fide of Dan river.

SAUTEURS, le Morne des, or Leaper's Hill, a precipice nearthe river Sauteurs, at the north end of the ifland of Grenada. After the year 1650 the French gradually exterminated the Charaibes; near this place they butchered 40 of them on the fpot; and 40 others, who had efcaped the fword, threw themfelves headlong into the fea from this precipice, and miferably perifhed. A beautiful young girl, of 12 or 13 years of age, who was taken alive.

alive, became the object of difpute between two of the French officers, each claiming her as a lawful prize, when a third of thole white favages put an end to the conteft, by fhooting the girl through the head.

SAVAGE, a fmall river of Maryland, which runs fouthward through Alleghany co. and empties into the Patowmac, welf of George's Creek. Its mouth is 21 miles fouth-welf of Fort Cumberland, and 48 fouth-eaft of the mouth of Cheat river. Boats carrying 10 tons can reach Alexandria in 4 or 5 days, but will take double the time to return.

SAVAGE Creek, a finall bay on the north-weft coast of Newfoundland, near the weftern entrance of the bay of Mouco, and ao leagues N. E. of Cape Ferrol.

SAVAGE Island, in the S. Pacific Ocean, is about 33 miles in circuit, and is inhabited by favages. It is overrun with bushes, and has no port. S. lat. 10, 2, W. long. 160, 30.

29. 2. W. long. 169. 30. SAVAGE Ifland, Great, in Hudson's Straits. N. lat. 62. 25. W. long. 70. High water, at full and change, at ten o'clock.

SAVAGE Ifland, Lower, in the fame fraits, has high water at full and change at nine o'clock. N. lat. 61. 48. W. long. 66. 20.

SAVAGE Point, Upper, on the north fide of Hudson's Straits, fouth-east of Cape Charles, and the north-west point of an inlet up into the land, so as to form the island of Good Fortune.

SAVAGE's Poff, at the Rock Landing ten miles below the Falls of Oconee river.

SAVAGE Sound, a paffage in the north part of the Welcome Sea, in Hudfon's Bay, into Repulse Bay. It is but little known.

SAVANNAH, a bay at the eaft end of the ifland of Antigua, near the fouth-eaft part of Green Ifland, on the fouth fide, a little weftward of Indian Creek.

SAVANNAH Channel, towards the fouth-east point of the fouth fide of the island of Jamaica; a short way west of Port Morant Harbour; between them is Fisherman's river.

SAVANNAH, a port of entry and pofttown of Georgia, and formerly the metropolis of the State; fituated in Chatham co. on the fouth fide of the river Savannah, on a high fandy bluff, 17 AV

miles from the ocean. The town is regularly built, in the form of a parallelogram, and, including its fuburbs, contained, in 1787, about 2300 inhabitants, of whom about 80 or 90 are Jews. More than two-thirds of this town was confumed by fire in the fall of 1796. The exports for one year, ending the 30th of September, 1794, amounted to the value of 263,830 dollars. This city was bravely defended by the British general Prevoft, against a superior force, headed by Count d'Eftaing and General Lincoln. The allies made a fatal and unfucceisful attack on the 18th of October, 1779, when they were obliged to retreat, after having from 1000 to 1200 men killed and wounded. It is 129 miles N. by E. of St. Mary's, 132 S. W. by S. from Augusta, and 925 in a like direction from Philadelphia. N. lat. 32. 3. W. long. 81.,24.

SAVANNAH River divides the State of Georgia from that of S. Carolina, and purfues a course nearly from northweft to fouth-eaft. It is formed chiefly of two branches, the Tugelo and Keowee, which fpring from the mountains, and unite under the name of Savannah, 15 miles north-weft of the northern boundary of Wilkes co. It is navigable for large veffels 17 miles up to Savannah, and for boats of 100 feet keel to Augusta. After rising a fall just above this place, it is paffable for boats to the mouth of Tugelo river. After it takes the name of Savannah, at the confluence of the Tugelo and Keowee, it receives a number of tributary ftreams, from the Georgia fide, the principal of which is Broad river. Tybee Bar, at the entrance of Savannah river, has 16 feet water at half tide. Tybee lighthouse lies in lat. 32 N. and long. 81. 10. W. and from thence to Port Royal is 6 leagues N. E. J. E. The flood in this fiver was fo great in Feb. 1796, that the water role 35 feet above its ordinary level. In Augusta, the streets were plied by boats which could carry fifteen tons.

SAVANNAH River, Little, falls into the gulf of Mexico, north-weft of St. Joseph's Bay.

SAVANNAH la Mar, at the eaft end of the island of St. Domingo, is a fettlement on the fouth fide of the bay of Samana, opposite the city of Samana on the north fide, and lies between the Bay Bay of port) a its gove at the than 10 4 wide of Sam gun in tain mc age her Shallow gation and the tant. SAV of the i county, vesiels. ed by dation partly i to 70 h Point \ N. lat. SAV N. coa called and th to the i SAV gia, 64 north c SAV co. Ma SAW of N. (ton, IC Philad SAW the we fize, al fmall (can on miles 1 SAX north in N. manch may be so mil SAX in S. (Conga wefter SAX ties in fter. SAL ticut,

TPC

elo-

:on-

abi-

WS.

was

96.

the

1 to

ci-

tifh

rce,

gral

and

De-

to

100

129

S:

in

N.

ite

na,

th-

fly

-05

18,

h,

m

a-

a-

el

ift

ts

it

he

e,

s,

of

at

6

t-

٥.

is

is

10

y

ne

n

0

t.

d

١.

f

R

e

y

Bay of Pearls, (which is an excellent port) and the Point of Icaque. It has its governor and rector, and is fituated at the end of a plain, which is more than 10 leagues from eafl to weft, and 4 wide from north to fouth. The city of Samana and this town were both begun in 1756, and together do not contain more than 500 fouls. The anchorage here is only fit for fimall veffels. Shallows and breakers render the navigation very dangerous between this and the point of Icaque, 4⁴/₂ leagues diftant.

SAVANNAH la Mar, on the fouth fide of the ifland of Jamaica, in Cornwallis county, has a good anchorage for large vefiels. It was almost entirely deftroyed by a dreadful hurricane and inundation of the fea, in 1780. It is now partly rebuilt, and may contain from 60 to 70 houfes. It bears from Bluefield's Point W. by N. $\frac{1}{2}$ N. about 3 leagues. N. lat. 18, 12. W. long. 78. 6.

SAVERIO, a cape or point on the N. coaft of S. America, on that part called the Spanish Main. Between it and the island Barbarata is the opening to the island of Bonaire.

SAVILLA, St. a fmall town of Georgia, 64 miles fouth of Savannah, and 65 north of St. Mary's.

SAVOY, a new townflip, in Berkfhire co. Maffachufetts, incorporated in 1797. SAWYER'S Ferry, a finall post-town of N. Carolina, 14 miles from Nixonton, 10 from Indiantown, and 482 from Philadelphia.

SAWYER's, or Afferadores, Island, on the weft coaft of Mexico; is of a fmall fize, and has on its fouth-eaft fide a fmall creek of its name, which boats can only enter at high water. It is 12 miles from the Bar of Realejo.

SAXAPAHAW, the upper part of the north weft branch of Cape Fear river, in N. Carolina. It is formed by Aramanche and Deep rivers, and it is faid may be made navigable for boats about 50 miles.

SAXEGOTHA, a village or fettlement in S. Carolina, on the fouthern bank of Congaree river; about 48 miles northwefterly of Augusta, in Georgia.

SAXTON'S River, in Vermont, empties into the Connecticut at Weftminfter.

SAYBROOK, a post town of Connec- from the fea render it very l ticut, Middlefex co. on the weft fide of lat. 7. 50. W. long. \$2. 5.

SCH

Connecticut river, acrofs which is a ferry, on the road leading to New-London. It is 36 miles east of New-Hasven, 18 weft of New-London, and arg north-east of Philadelphia. This is the most ancient town in the State, having been fettled by Mr. Fenwick in 1634who gave it its prefent name in honour of Lord Say and Seal and Lord Brook.

SCARBOROUGH, a township of the District of Maine, situated in Cumberland co. on the sea coast, between Pepperelborough and Cape Elizabeth. It was incorporated in 1658; contains 2235 inhabitants; and lies 213 miles northerly of Boston.

SCARBOROUGH Cove, in the harbour of Chebucto, on the fouthern coaft of Nova-Scotia, is on the middle of the weft fide of Cornwallis Ifland. It is g or 6 furlongs broad, and nearly the fame in depth.

SCARBOROUGH, a town and fort in the island of Tobago, in the W. Indies, SCARSDALE, a township in Weft-Chefter co. New-York, bounded weftterly by Bronx river, and southerly by the town of East-Chefter. It contains 281 inhabitants, of whom 33 are electors. See New Rachelle.

SCATARI, a finall uninhabited island on the eastern coast of Cape Breton Island. It is about 6 miles long and 2 broad. It ferves as a shelter to a bay from the east and fouth, which lies fouthward of Miray Bay, called Menadou, or Panadou Bay. N. lat. 46. 3-W. long. 59. 35. It was formerly called Little Cape Breton.

SCAUYACE, a river of New-York, which iffues from the north-east corner of Seneca Lake, and separating the township of Romulus from that of Junius on the north, empties into Cayuga lake.

SCHACTECOKE, or Scaghtikoke, a town/hip of New-York, in Renffelace. co. lies north of the town/hip of Renffelaerwick, on Hudfon's river. In 1796, 275 of the inhabitants were electors.

SCHACADERO, a finall village on the Ifthmus of Darien; on the E. fide of the mouth of the river Santa Maria, on a rifing ground, open to the gulf of St. Michael. It has a fine rivulet of frefh water, and ferves as a place of refrefhment to the miners. The frefh breezes from the fea render it very healthy. No

SCHLOSSER

SCHLOSSER Fort, or Slufber, in the State of New-York, is fituated on the eastern fide of Niagara river, near the celebrated falls, on the north bank of a bend of the river, and opposite to the N. W. end of Navy Ifland.

SCHODACK, or Sbudack, a township in Rensfelaer co. New-York, taken from Renffelaerwick township, and incorporated in 1795. It is 14 miles E. of Albany; and, in 1796, there were 377 of its inhabitants electors.

SCHOEN-BRUNN, or the Beautiful Spring, one of the easternmost fettlements of the Moravians on Mufkingum river. See Gnadenhutten. This fettlement of Chriftian Indians was eftablifhed in 1772, on a tract of land granted by the Delaware tribe. In 1775, the chapel, which could contain 500 people, was found too fmall for the hearers, who came in great numbers. It was fituated about 30 miles from Gekelmuckpechuenk, 70 from Lake Eric, and 75 W. from Friedenstadt. It had a good fpring, a small lake, good planting grounds, much game, and every other convenience for the fupport of an Indian colony. It appears that a large fortified Indian town formerly flood here; fome ramparts and the ruins of three Indian forts being still visible. The Delawares granted to the Christian Indians all the tract from the entrance of Gekelmuckpechuenk Creek into the Muskingum to Tuscarawi. This thriving fettlement was deftroyed in 1782, when the Huron Indians carried the mhabitants to Sandufky; and when thefe peaceable Indians were permitted to return to reap their harvest, they were cruelly butchered by the American fettlers, while praifing God and forgiving their enemies. Congress granted 4000 acres of land here to the fociety of the United Brethren, for the purpose of propagating the golpel, on September 3, 1788.

SCHOHARIE, a county of New-York, taken from those of Albany and Otfego, and incorporated in 1795. The land is variegated with hills; is in general fertile and well watered by Schoharie, Cobus Kill, and feveral other freams. The county is bounded north by Montgomery, fouth by Ulfter, E. by Albany, and W. by Otfego. By a law paffed 17th March, 1797, this county was divided into the fix following towns, above Reading, 85 or 90 miles to its

SCH

viz. Schoharie, Middleberg, Blenheim, Briftol, Coblefkill, and Sharon.

SCHOHARIE, the principal town in the above co. is on Schoharie creek or river, and is one of the wealthieft inland farming towns in the State. The inhabitants are Dutch, and before its divifion in 1797, were 2073 in number. It is between 30 and 40 miles weftward of Albany.

SCHOHARIE River runs a northerly course of about 80 miles from the Kaats' Kill Mountains, and empties into Mohawk river at Fort Hunter. The western branch of this river is called Cobus Kill. On the E. fide of Cobus is the fettlement of its name. The towns and fettlements on Schoharie were, in 1796, as you proceed from S. to N. Batavia, Fountain's Town, Schoharie, Smith's Town, and Fox Town.

SCHOODUCK. See Frenchman's Bay, and Scoodick.

SCHUYLER, Fort, New, in the townthip of Rome, ftands on the W. fide of a bend of Mohawk river, about 7 miles weftward of Whiteftown.

SCHUYLER, Fort, Old, is on the fouth fide of Mohawk river, 4 miles E. N. E. of the compact part of Whiteftown, and 20 above the German Flats. Here were, in 1796, 35 compact houses, fituated partly in each of the townships of Whitestown and Frankfort. In 1790, there were but three fmall huts here.

SCHUYLER, a township of New-York, Herkemer co. between Mohawk river and Canada Creek, 20 miles above the town of German Flats. In 1796, according to the State cenfus, it contained 1219 inhabitants, of whom 222 were electors. It was incorporated in 1792. This town was divided by act of the legiflature in 1797.

SCHUYLER's Lake, in New-York State, is 10 miles W. of Lake Otlego. It is 9 miles long, and 4 or 5 broad.

SCHUYLKILL, a river of Pennfylvania, which rifes N. W. of the Kittatinny Mountains, through which it paffes into a fine champaign country, and runs, from its fource, upwards of 120miles in a fouth-east direction, and passing through the limits of the city of Philadelphia, falls into the Delaware, oppofite Mud Ifland, 6 or 7 miles below the city. It will be navigable from mouth,

mouth, ton is c falls, a with t There acrois it and lyin of Phila falls in Reading Schuylk Scio Ohio in States, than eit hocking navigati barges i only 4 ble wat Throug the mof the Ohi moft ext tions th try. P are here pidity w Canada, countrie an immo The flou for expc between will find and thef The Oh price th commod ported fi the Wei pense, ri latter ; place of be 1 of and muc Lake. 7 tle, no w places, overflows natural r coal mir free-ftone joining t lat. 38.4 miles bel to its fou SCIPI Onondag

heim,

wn in ek or nland inhadivit. It urd of

herly aats' Moweftobus s the s and 796, avia-

Bay,

de of

the man pact the ankthree

ork, river the acined were 792. the ork

ego. lva. ittapaffand 120paffgof are, low

uth,

SCI

mouth, when the canal begun at Norriton is completed. This will pass by the falls, and also form a communication with the Delaware above the city. There are 4 floating bridges thrown across it, made of logs fastened together, and lying upon the water, in the vicinity of Philadelphia. Little Schrylkill river falls into this river from the north, at Reading. On the head waters of Schuylkill are quantities of coal.

SCIOTA River, which falls into the Ohio in the territory of the United States, N. W. of the Ohio, is larger than either the Muskingum or Hockhocking, and cpens a more extensive navigation. It is paffable for large barges for 200 miles, with a portage of only 4 miles to the Sandusky, a boatable water which falls into Lake Erie. Through the Sandufky and Sciota lies the most common pass from Canada to the Ohio and Miffifippi; one of the most extensive and useful communications that are to be found in any country. Prodigious extensions of territory are here connected; and from the rapidity with which the western parts of Canada, Lake Erie, and the Kentucky countries are fettling, we may anticipate an immense intercourse between them. The flour, corn, flax, and hemp, raifed for exportation in that great country between the Lakes Huron and Ontario, will find an outlet through Lake Erie and these rivers, or down the Miffifippi. The Ohio merchant can give a higher price than those of Quebec for these commodities; as they may be tranfported from the former to Florida and the Weft India iflands, with lefs expenfe, rifk and infurance, than from the latter; while the expenfe from the place of growth to the Ohio will not be $\frac{1}{2}$ of what it would be to Quebec, and much less than even to the Oneida Lake. The ftream of the Sciota is gentle, no where broken by falls. At some places, in the spring of the year, it overflows its banks, providing for large natural rice plantations. Salt fprings, coal mines, white and blue clay, and free-flone, abound in the country ad-joining this river. Its mouth is in N. lat. 38.40. W. long. 83. 30. about 300 miles below Pittsburg, and is navigable to its fource in canoes.

SCIPIO, a post-town of New-York, Onondago co. on the E, fide of Cayuga 497

Lake, 14 miles fouth-east of Geneva, so S. W. by W. of Onondago, and 46 a N. W. by N. of Philadelphia. This township was incorporated in 1794, and comprehends in its jurifdiction the townthip of Sempronius, together with that part of the lands referved to the Cayuga nation of Indians, on the E. fide of the Cayuga Lake; fouth of a weft line drawn from the fouth-wefterly corner of the township of Aurelius, in the E. bounds of the faid refervation to the faid Cayuga Lake. The county courts of Onondago co., are held at Manlius and Scipio alternately. The lands are very fertile. The courts are at prefent held in the pleafant village of Aurora, on the bank of Cayuga Lake.

SCITUATE, a township of Maffachufetts, on the bay of that name, in Plymouth co. 28 miles fouth-east of Boston. It was incorporated in 1637, and contains 2856 inhabitants. Scituate harbour is N. W. of Marshfield Point, and S. S. E. of the Haddock Rock. and about 16 miles northward of Plymouth, in the direction of the land. A mill-pond in this town being fuddenly drawn off by a breach in the dam, in the winter feafon, fome years ago, exhibited a matter of fpeculation to many of the inhabitants. The fwine of the neighbourhood rooted up houfe fwallows in great quantities, from the fpot which the water had left, which they ate greedily. Swallows have been found in feveral other places ; at Egg Har-bour, in New-Jerfey, in a marfhy place, a large cedar being blown down, a vaft number of fwallows were found in the mud of the root.

SCITUATE, a township of Rhode-Island, Providence co. between Foster and Johnston. It contains 2315 inhabitants. It is 27 miles N. W. of Newport, and 11 S. W. by W. of Providence. On the line which separates the town from Kent co. S. is the foundary for cannon and bells, called Hope Furnace. SCODICK, or Schudick, a river of Washington co. District of Maine. It is properly an arm of the inner bay of Passanauoddy. De Mons and Champlaine called it Etchemins. Its main source is near Penobscot river, to which

the Indians have a communication; the carrying place across is but 3 miles. Scoodick lakes lie in a chain between Scoodick and Penobicot rivers.

Ιi

SCOTCH

SCOTCH Plains, a village in Effex co. New-Jerfey, on a N. E. branch of Rariton river, between Weftfield and Turky; 11 miles W. of Elizabeth Town, and as far northward of New-Brunfwick.

SCOTLAND Neck, a village of N. Carolina, where is a post-office, 396 miles from Philadelphia.

SCOTLAND, New. See Nova-Scotia. SCOTLAND River, in the island of Barbadoes, is fearcely deferving notice, otherwise than being almost the only rivulet in the island, except St. Joseph's river, another small brook. It rifes in St. Andrew's parish, and falls into Long Bay on the eastern side of the island, 24 miles N. W. of St. Joseph's river.

SCOTT, a new county of Kentucky. SCOTS Bay, on the fouth-weft coaft of the ifland of Dominica, towards the fouthern extremity of the ifland. It lies in St. Martin's parifh, having Scots Head on the fouth, and Vaughan's Point on the N.

SCOTS Cove, on the fouth-well part of the island of Jamaica.

SCOWHEGAN Falls, in Kennebeck river, in the Diftrict of Maine, are near the town of Canzan. Boats cannot pass this fall.

SCRIVAN, a good habour on the E. fide of the Ifthmus of Darien, but fo full of rocks at the entrance, that none can pais it with fafety, but fuch as are acquainted there. It is 3 leagues W. of Sanballet Point, and 17 E. of Porto Bello. N. lat. 9. 40. W. long. 78. 49.

SCRIVEN, a new county in the lower District of Georgia.

SCROON Lake, in the State of New-York, lies W. of Lake George, and is a dilatation of the eaftern branch of Hudion's river. In fome maps it is called Scaron. A finall but rapid ftream enters into it, which, in Montgomery co. runs under a hill, the bafe of which is 60 or 70 yards diameter, forming a most curious and beautiful arch in the rock, as white as fnow. The fury of the water and the roughness of the bottom, added to the terrific noife within, has hitherto prevented any perfon from paffing through the chafm.

SCRUB Island, one of the fmaller Virgin Islands, fituated to the W. of Virgin Gorda, and E. of the N. end of Tortula, on which it depends. N. lat. 18. 25. W. long. 62. 57.

SCOTOR -

SEABROOK, a township of N. Hampshire, in Rockingham co. on the road from Portsmouth to Newbury Port; about 16 miles southerly of the former, and 6 northerly of the latter. It was formerly part of Hampton; was incorporated in 1768, and contains 715 inhabitants.

SEAKONNET Point and Rocks, the S. extremity of the eastern shore which forms the entrance of Narraganset Bay, in the State of Rhode-Island; about 6 miles east-fouth east of Newport.

SEAL Mand, Machias, on the coaft of the Diffrict of Maine. From thence to Grand Manan Ifland the courfe is E. N. E. two leagues; and to Matinicus Ifland W. S. W. 26 leagues. N. lat. 44. 27. W. long. 66. 52. SEAL River, in New North Wares,

SEAL River, in New North Wales, runs E. to Hudfon's Bay, into which it empties eaftward of Moole river.

SEA OTTER Sound, on the N. W. coaft of N. America, lies fouth-eafterly of the Hazy Iflands. N. lat. 55. 18. W. long. 133. 47. 30.

SEARSBURGH, a township of Vermont, Bennington co. 12 miles E. of Bennington.

SEAVEY'S Island. See Pascataqua river.

SEBACO, an ifland on the W. coaft of Mexico, 12 miles N. of Point Mariat, and 45 N. E. of Quicara.

SEBACOOK, or Sebago, a pond or lake of the Diffrict of Maine, 18 miles N. W. of Portland, is equal in extent to 2 large townships, and is connected with Long Pond on the N. W. by Sungo, or Songo river. The whole extent of these waters is nearly 30 miles north-wett and fouth-eaft.

SEBARIMA, one of the principal mouths of Oronoko river that is navigable for thips.

SEBASCODEAGAN Island. See Hartfwell.

SEBASTACOOK, a river of the Diffrict of Maine, that rifes in lakes nearly N. from its mouth; and in its windings receives brooks and fmall fireams for the fpace of 150 miles, and joins the Kennebeck at Taconnet Fall, where Fort Halifax was erected in 1754. The fall is eighteen miles from Fort Weftern, which was built in 1753. Its numerous fireams abound with fmall fifh, as alewives, &c.

as alewives, &c. SEBASTIAN, Cape, St. the eaflern point

62109 43

amp-

road

Port ;

rmer,

was

incor-

5 in-

the S.

which

Bay,

iout 6

coaft

hence

rie is

atini-

Vales,

which

. W.

afterly

8. W.

Ver-

E. of

raqua

coaft

Ma-

or lake

es N.

it to 2

d with

igo, or f thefe

h-wett

incipal

s navi-

Harpf-

Diffrict

rly N.

ndings

ns for

ns the where

Wef-

Its nu-

ll fifh,

eaflern

point

The

N.

point, of the Gulf of Darien, on the coaft of the Spanish Main, is ao leagues from the weltern point of Cape Tiburon. Here was formerly a city, which was abandoned on account of its unwholefome fituation.

SEBASTIAN, Cape St. on the coaft of California. N. lat. 43. W. long. 126. SEBASTIAN, St. See Rio Janeiro. SEBASTIAN, St. a town of Tetra Firma, on the eaftern fide of the Gulf of Darien.

SEBASTIAN Ifland, St. on the coaft of Brazil, is S. W. by W. from the bay of Angra dos Reys; to the caftward of which are feveral other iflands of less note. The city of Sebaftian is large and handlome, and the capital of the province of Rio Janeiro, being feated at the mouth of the river of that name. St lat. 22, 54. W. long: 45. 13.

22. 54. W. long: 45. 11. SEBASTIAN River, St. or Spanifs Admiral's Creek, on the E. coaft of Eaft-Florida, has a communication with Indian river. Opposite this river the admiral of the Plate Fleet perifhed in 1715. The reft of the fleet, 14 in number, were loft between this and the Beach yard.

SEBASTIAN de la Plata, a finall place in the jurifdiction of Popayan, in the province of Quito, fix miles northeaft of Popayan. It ftands on a large plain on the bank of the river Galli, and is fubject to earthquakes. There are filver mines in its vicinity. N. lat. 3.44. W. long. 74. i.

SEBOU, or Sibou, imail iflands on the coaft of Cape Breton ifland, off the fouth point of Port Dauphin.

SECAS ISLANDS, or Dry Iflands, on the W. coaft of New-Mexico, are within Bahia Honda, or Deep Bay, and 12 miles from Point Chiriqui, the limit of the bay.

SECHURA, a town of Peru, ten leagues fouth of Piura, fituated on the bank of a river of its own name, a league from the ocean. It contains about 400 families, all Indians; chiefly employed in fifting or driving of mules. They are remarkably ingenious, and generally fucceed in whatever they apply themfelves to. The Defert of Sechura is a frightful wafte of land, extending 30 leagues to the town of Morope; which iee. S. lat. 5, 32. 33. W. long. 79. 42.

W. long. 79. 42. SECKLONG, a town of New-Spain, on the Molquito thore, on the N. wel-

10109 03

tern fide of Golden river; about 100 miles from Cape Gracias a Dios, at the mouth of the river.

SED, Cafe, a promontory on the N. fide of the island of Caba, and 18 leagues from the Havannah.

SEDCWICK, a township of the Diftrist of Maine, Hancock co. on Nafkeag Point, which bounds Penobscot on the N. E. It extends up to the town of Penobscot, and is 315 miles N. E. of Boston.

SEEKHONK River is the name of that part of Pawtucket river below Pawtucket Bridge and Falls; from which to its mouth at Fox Point, in the town of Providence, is a little more than four miles. Over it are two bridges, conhecting Providence in Rhode Ifland with the State of Maffachuletts, viz. India bridge, and three-fourths of a mile above that Central bridge. See Pawtucket.

SEEWEE Bay, or Bull's Harbour, on the coaft of S: Carolina, lies nearly at an equal diftance fouth-weft of Cape Roman, and north eaft of Charlefton Entrance, having feveral ifles which form the bay.

SEGOVIA, New, a finall city in the jurifilicit nof Guatimala; in New-Spain, 30 miles north of New-Granada. It has feveral gold mines in its neighbourhood, though the city is finall and thinly inhabited. N. lat. 12, 42, W. long. 87, 31.

SEGUATANEIO. See Chequetan. * SEGUINE IAand, or Segum, on the coaft of the Dustrict of Maine, is one of the fouthernmost islands in Cafco Bay; between Cape Small Poinr and George Town. There is a light-house on this island which contains a repeating light, fo constructed as to disappear once every minute and a half, which diffinguishes it from Portland light, N. lat. 43. 56 W. long. 69. 70.

SEGURA de la Frontera, a large town in the province of Tlateala, and kingdom of Mexico, feventy miles welt of Xalappa, and in the road from Vera Cruz to Mexico. The furrounding country has a temperate air, and is remarkably fruitful, producing large quautities of corn and truits, particularly grapes. N. lat. 19. 28. W. long. 1900, 10.

SEMINOLES, a division of the Creek nation of Indians. They inhabit the 1 i 2 flat.

1 上海

500

flat, level country on the rivers Apala-

chicola and Flint. See Calos. SEMPRONIUS, a township of New-York, nearly in the centre of the county of Onondago, is 20 miles fouth-east from the ferry on Cayuga Lake. It is within the jurifdiction of the townfhip of Scipio.

SENECA, a town of New York, Onondago co. lately laid off into freets and fquares, on the north fide of Seneca Falls. The enterprifing proprietors are erecting flour and faw mills, of the beft kind, on this never failing ftream ; and from its central fituation, both by land and water, between the eaftern and western countries, being at the carrying place, it promifes a rapid increase. The proprietors have expended large fums of money, not only in creeting mills, but in building a convenient bridge acrofs Seneca river, and are now co-operating with the enterprising Gen. Williamfon in making a good waggon-road to Geneva.

SENECA Creek, in Maryland, has two branches; one of which is called Little Seneca. It empties into Patowmac river, about 19 miles N. W. of the mouth of Rock Creek, which feparates George Town from Washington city.

SENECA, Lake. See Canada Sago Lake.

SENECA River, in the State of New-York, rifes in the Seneca country ; runs eastwardly, and in its passage receivesthe waters of Seneca and Cayuga lakes, (which lie north and fouth 10 or 12 miles apart; each is between 30 and 40 miles in length, and a mile in breadth) and empties into the Onondago river, 14 miles below the falls, at a place called the Three Rivers. The river is boatable from the lakes downwards. Within half a mile of the river is the famous Salt Lake. See Onondago County, and Military Town/bips.

SENECAS, a tribe of Indians, one of the Six Nations. They inhabit on Geneffee river, at the Geneffee Caftle. The tribe confifts of about 1780 fouls. They have two towns of 60 or 70 fouls each, on French Creek in Pennfylvania, and another town on Buffaloe Creek, and two finall towns on Alleghany river.

SENTER Harbour, in the north-weft part of Lake Winnipifeogee.

SEPARATION Bay, in the Straits of Magellan, is 3 leagues within Cape Pil- | miles from the Miffifippi. Its mouth is

SE 9

lar, at the weft end of the ftraits, and lies W. of Tuefday Bay. SERENA, La. See Coquimbo.

SEREGIPPE, a captainfhip of Brazil, fo named from a river of the fame name, running through the middle of it, and falling into the Atlantic Ocean in lat. 11. 12. fouth. It is bounded north by the river St. Francis, and fouth by that of Todos los Santos. It produces fugar and tobacco in confiderable quantities.

SEREGIPPE, the capital of the above captainfhip, with a harbour on the S. Atlantic Ocean, 40 leagues N. E. of St. Salvadore. It is fituated on a rifing ground on the north fide of Vazabaris river, 33 miles from the fea. It is very inconfiderable ; but has fome filver mines in its neighbourhood. S. lat. 11. 20. W. long. 31. 2.

SERRANA, an isle between Jamaica and the coaft of Nicaragua, which took its name from one Serrana, who parted with the fleet from Spain, in the time of Charles V. and was fhipwrecked on the rocks of this ifland; but having gained the fhore by fwimming, he found there neither herbs, trees, nor water, and went over all the island, which is about 6 miles in circuit, without finding any thing to quench thirft or fatisfy hunger. Preffed at laft with extreme hunger, he caught fome crabs on the fhore, which were his food for fome days; and then feeing large turtles which came afhore, he caught fome of them. Having lived for three years in this manner, on crabs and turtles, and drank nothing but rain-water which he gathered in turtle-fhells, he difcovered another companion in miffortune, who had also been shipwrecked. This companion was fome comfort to him, and they lived four years together; at the end of which time, a vefiel coming near the island, carried them both to Spain. The laft of these died on the way thither ; but Serrana was carried to Germany, and prefented to Charles V. as a kind of prodigy, for all his body was overgrown with hair like a bear, and his beard came down to his waift. The emperor befrowed on him 4800 ducats to be paid in Peru; but he died on his way to Panama, as he was going to receive them.

SESEME Quian, a river of the N. W. Territory, which empties through the weftern bank of Illinois river, about 120 40 yards

on it is w SEVI north co go. T Monte They I and pro SEVE of the i from th cofti, a one of 1 the Ind bour fo SEVI of thor to Chei polis ci the bay SEVI Wales, courfe,

to yard

vern H York F SEV.I milton . accordi

habitan SEVI foundec north fi little to and th by the hipwre

Seville ancient the can SEW

the coa

of Cap

row if

tween (trance I N. E. e SEYI fouth e mingo, to St. by nort

of the l the four is not t Efquiv the fan feveral hip.

the lat

to vards wide; and the land bordering on it is very good. It is boatable 60 miles.

SEVEN Brothers, fmall iflands on the north coaft of the island of St. Domingo. They lie opposite the mouth of Monte Chrift river, or Grand Yaqui. They have occasioned feveral wrecks, and prove a fhelter to privateers.

SEVEN Mands Bay, on the north fide of the river St. Lawrence; 25 leagues from the W. end of the island of Anticofti, and in lat. 50. 20. N. It was one of the French pofts for trading with the Indians, and has a very fecure harbour for thips in any wind.

SEVERN, a fmall river of Maryland, of thort courfe, which runs fouth-eaft to Chefapeak Bay. It paffes by Annapolis city on the N. and empties into the bay about two miles below the city.

SEVERN, a river of New South Wales, which purfues a north-eafterly course, and enters Hudson's Bay at Severn Houfe, which is 160 miles east of York Fort.

SEVIER, a county of Tenneffee, Hamilton Diffrict. In 1795 it contained, according to the State cenfus, 3578 inhabitants, including 129 flaves

SEVILLA Nueva, a town which was founded by the famous Efquivel, on the north fide of the ifland of Jamaica; a little to the weftward of Mammee Bay and the fpot which had been honoured by the refidence of Columbus, after his shipwreck in 1503. It is now called Seville Plantation ; and the ruins of the ancient town are ftill visible in some of the cane fields.

SEWEE Bay, or Bull's Harbour, on the coaft of S. Carolina, is fouth-weft of Cape Carteret. The long and narrow island called Racoon Keys is hetween Cape Carteret Island and the entrance to this harbour, which is at the N. E. end of Bull's Ifland. See Seewee.

SEYBO, or Seyvo, a fettlement in the fouth east part of the island of St. Domingo, on the upper road from Higuey to St. Domingo city; 18 leagues welt by north of the former, and 24 N. E. of the latter. It is also 12 leagues north of the little island of St. Catherine, on the fouth coaft of the main island. is not that founded in 1502, by John of Esquivel, but a settlement formed in the fame canton about 60 years ago by feveral graziers, and has a place of worthip.

augmented, but is now falling to decay. The parish contains more than 4000 perions; the greateft part of whom are graziers or herdimen, free negroes, or people of colour.

SHAFTSBURY, a confiderable and flourishing township of Vermont. It has Arlington on the north, and Bennington on the fouth, and contains 1999 inhabitants.

SHAG Island, near the entrance into Christmas Sound, on the fouth coaft of the island of Terra del Fuege. The entrance to Port Clerke in this found is just to the north of fome low rocks which lie off a point of Shag Ifland.

SHALLOW Ford, is that part of Tenneffee river which is 1200 yards broad ; 12 miles above the Whirl. It lies between Chatanuga and Chickaugo rivers, which fall in from the fouth-eaft.

SHALLOW Water, Point, on the N. W. coaft of N. America, lies in lat. 63. N. Betweep this point and Shoal Nefs, which is 3 degrees of lat. to the fouthward, Capt. Cook did not explore the coaft, on account of the fhallow water he met with.

SHAMBE, a fmall river of Weft Florida, which empties into Penfacola Bay. It admits shallops fome miles up, and boats upwards of 50 miles.

SHAMOKIN, a former Moravian fettlement, a little below the town of Sunbury, in Pennfylvania.

SHAMOKIN Creek runs weftward into Sufquehannah river, a mile fouth of Sanbury, in Pennfylvania.

SHANNOCK Country. See Rhode-Island State.

SHAPLEIGH, a to - nihip of the Diftrict of Maine, on the W. line of York co. at the head of Moufom river. It was incorporated in 1785, contains 1329 inhabitants, and lies 108 miles N. of Bofton.

SHARON, a township of Vermont, Windfor co. eaftward of Royalton, and westward of Norwich on White river. It contains 569 inhabitants.

SHARON, a township of Massachufetts, Norfolk co. 10 miles fouth-welterly of Bofton. It was taken from Stoughton, and incorporated in 1765. It contains 1994 inhabitants.

SHARON, a township of Connecticut, in Litchfield co. bounded eath by Cornwall, from which it is feparated by Towards the year 1780 it had Houfatonic river, and weft by the Ii 3

errana fented y, for h hair own to ved on Peru; na, as N. W. gh the ut 180 outh is

1 yards

and

razil.

ame,

n lat.

th by

r that

fugar

ties.

above

he S.

E. of

rifing

ibaris

i very

mines

. 20.

maica

took

parted

me of

m the

rained

there

went

miles

ing to

refied

aught

re his

; large

aught

· three

d tur-

-water

ls, he

mif-

vreck-

com-

years

me, a

arried

f thefe

and

line of New-York State. It is about is miles N. W. of Litchfield.

502

SHARON, a village in Georgia, about g miles from Savannah. In this place, juft at the clofe of the war, Gen. Wayne was attacked in a furious manner by a body of Cherokee Indians, headed by a Britifh officer. They fought hand to hand manfully, and took 2 pieces of artillery. But Gen. Wayne, at the hasard of his own life, gained the victory SHARON, a new town in Schoharie co. New-York, incorporated in 1797. SHARKSTOWN, in Queen Anne's co. Maryland. See Kent County.

SHARPSBURG, a poft town of Maryland, Wafhington co. about two miles from Patowmac river, and nearly oppofite to Shepherdflown, in Virginia, at the mouth of Shenandoah river. It contains a church, and about 2 50 houfes. It is 9 miles N. N. W. of William's port, 69 W. by N. of Baltimore, and 281 W. S. W. of Philadelphia.

SHAWANEE, and Shawanon; the former the Indian, and the latter the French name of Cumberland river, in the State of Tenneffee. It is also called Shawanoe.

SHAWANESE, or Shawannes, an Indian nation, great numbers of whom have joined the Creek confederacy. They have 4 towns on the Tallapoofe river, containing 300 warriors; and more are expected to remove thither. By the treaty of peace, Aug. 3, 1795, the United States agreed to pay to this tribe a fum in hand, 'and 1000 dollars a year for ever, in goods. They inhabit alfo on Scioto river, and a branch of the Mulkingum, and have their hunting-grounds between Ohio river and Lake Erie. They are generally of a finall fize, rather handfome in their features, and are very cheerful and crafty people. Counfelling among their old people, and dancing among their young men and women, take up a great part of their time.

SHAWANGUNK, a townfhip in Ulfter co. New York; bounded eafterly by Newburgh and Marlborough, and foutherly by Montgomery and the Platte Kill. It contains 2128 inhabitants; of whom 323 are electors, and 350 flaves. It is 20 miles from Gothen, and 12 from New Paltz. SHAWSHEEN, a confiderable fiream of Maffachufetts, which rifes in Bedford, Middlefex co. and, paffing through

Billerica, Tewkfbury and Andover, difcharges itfelf into Merrimack river.

SHEBA Ifland. See Saba: SHECATICA, a bay of very irregular fhape and breadth, on the coaft of Labrador, N. America; having an ifland of its name at its mouth. It is fituated between lat. 51. 14. and 51. 28. N. and between long. 58. 16. and 52. 22. W.

SHECHARY, a lake of New North Wales, formed like a bow. It receives Churchill river from the fouth-weft and at its N. E. end has communication with Berbazon Lake, which lies due N. and fouth. At the fouth end of the latter, the waters of both lakes run E. under the name of Seal river, which empties into Hudfon's Bay at Churchill Fort, between Button's Bay on the N. and Cape Churchill on the fouth-eaft. Both lakes are long and narrow.

SHEDIAC, a harbour on the eaftern coaft of New-Brunfwick, and on the W. fide of the Gulf of St. Lawrence; 53 miles fouth-east of Miramichi Bay. SHEEPSCOT, of Sheep/cut, a fmall river of the Diftrict of Maine; which emp! ties into the ocean to the E. of Kennebeck, and is navigable 20 or 30 miles. On the W. fide of this river is the excellent port called Wiscasset, in the township of Pownalborough. Newcastle township is at the head of navigation on this river, and extends from Sheepfcot to Damarifcotta river. The compact part, which is a post-town, is to miles N. E. of Wilcaff.t. Sheepfoot har-bour has high water, at full and changes 45 minutes after 10 o'clock; depth, 9 fathoms.

SHEEP'S Cove, on the eaft coaft of Newfoundland, lies between Bay Robert and Port Grave.

SHEFFIELD, a township in the northern part of Caledonia co, Vermont.

SHEFFIELD, a polt-town of Maffachufetts, Berkfhire co. 30 miles foutheaft of Hudion in the State of New-York, 145 weft-fouth-weft of Bofton, and 257 north-eaft of Philadelphia. It was incorporated in 1733, and contains 1,899 inhabitants. Honfatonic river, which is nine rods in breadth, paffes through it from north to fouth, which with its branches fopply water for feveral mills and iron works. South Mountain extends the whole length of the town, along the eaft fide of the river.

SRELBURNE, a township of Vermont, Chittenden Chitten Champ north. contain SHE Gratio incorpo inhabit SHE fhire c Green SHE at the from H part of tained populo Barrin of. Ha SHE SHE Long lies 3 It is : and 7 ful fpo was in 201 in ors. theep When larboa about bay v fate a SHI bound by R inhab town, SH which ning miles lat. 3 throu ble a dered imall will of th SH Wine the S is ch Dute SH the 1 CO. 6 Chittenden co. on the caft fide of Lake Champlain. It has Burlington on the north, and Charlotte on the fouth, and contains 380 inhabitants.

SHE

SHELBURNE, an interior township in Grafton co. New-Hampshire. It was incorporated in 1769, and contains 35 inhabitants.

ular

La-

land

ated

and

w.

orth

eives

and

ation

e N.

nE.

hich

chill

e N.

eaft.

iftern

1 the

ince;

spy.

I tiv-

emp:

Ken-

niles.

e ex-

1 the

caftle

on on

picot

npact

miles

har-

anges

th, 9

ift of

r Ro-

orth-

Aaffa-

outh-

New-

ofton.

i. It

ntains

river,

paffes

which

for fe-

Noun-

f the

mont,

enden

ver.

the

SHELBURNE, a township in Hampfaire county, Maffachusetts, adjoining Greenfield.

SHELBURNE, a town of Nova Scotia, at the head of a bay which runs up from Port Rofeway, at the fouth-welt part of the province. In 1783, it contained 600 families, but is now lefs populous. It is 18 miles north-eaft of Barrington, and 88 fouth-welt by fouth of Hahfax.

SHELBY, a new county of Kentucky,

SHELTER Ifland, at the east end of Long Ifland, in Suffolk co. New-York, lies 3 leagues weft of Gardner's Ifland. It is about 5 miles from east to weft, and 7 from north to fouth. It is a fruitful fpot, containing about 8000 acres; was incorporated in 1788, and contains 203 inhabitants, of whom 34 are electors. Confiderable numbers of cattle, fheep and poultry are raifed here. When you leave Shelter Ifland on your larboard hand, and run weft by north about 5 or 6 miles, you will open a large bay where 100 fail of veffels may lie fafe and anchor in 3 or 4 fathoms.

SHENANDOAH, a county of Virginia, bounded north by Frederick, and fouth by Rockingham. It contains 10,510 inhabitants, including 512 flaves. Chief town, Woodflock.

SHENANDOAH, a river of Virginia, which rifes in Augusta co. and after running a north cast courie of about 200 miles, it joins the Patowmack in about lat. 38, 4. just before the latter bursts through the Blue Ridge. It is navigable about 100 miles; and may be ren dered so nearly its whole course at a small expense. When this is done, it will hear the produce of the richest part of the State.

SHENANDOAH Valley, extends from Winchefter, in Virginia, to Carlifle and the Suiquehannah, in Pennfylvania, and is chiefly inhabited by Germans and Dutch.

SHEPHERDSFLELD, a plantation of the Diftrict of Maine, in Cumberland co. containing 330 inhabit ints. SHEPHERDSTOWN, or Shipherdfburg, a poft-town of Virginia, fituated in Berkley co. on the fouth fide of Patowmack river. Its fituation is healthy and agrecable, and the neighbouring country is fertile and well cultivated. It contains about 2000 inhabitants, moftly of German extraction. It lies at the month of Shenandoah river, oppofite to Shapfburg; 10 miles eaft by fouth of Martinfburg, and \$78 fouth-weft by weft of Philadelphia.

SHI

SHERBURNE, in Maffachuletts; sce. Nantucket.

SHERBURNE, a township of New-York, Herkemer co. By the State cenfus of 1796, it contains 483 inhabitants, of whom to are electors.

of whom any are electors. SHETUCKET, a river of Connecticut, which is formed by the junction of Willomantic and Mount Hope rivers, and after running eaft a few miles, purfues a fouthern courfe, and uniting with Quinabaug river, empties into the Thames in the fouth part of the townthip of Norwich.

SHIMENE Port, on the north fide of the island of St. John, in the gulf of St. Lawrence. Its entrance, welt of St. Peter's harbour, is very narrow; but the balon within is very fpacious.

SHINING Mountains, in the northweft part of North-America, are little known. It is conjectured that they terminate in about lat. 47. or 48. N. where a number of rivers rife, and empty themi-lives either into the North Pacific Ocean, into Hudfon's Bay; into the waters which lie between them, or into the Atlantic Ocean. They are called alfo the Mountains of Bright Stones, on account of the immedie number of large cryftals, fhooting from the rocks, and iparkling in the rays of the fun, fo as to be feen at a great diffance.

SHIP *Ifand*, lies between Horn and Cat Ifland, on the coaft of Welt-Florida, and is about 10 miles fouth of the Bay of Biloxi. It is 9 miles long and 2 broad; produces pine trees and grafs, and has a tolerable well of water in it.

SHIPPANDSTOWN, in Virginia, on the fourh fide of the Patowmack, 40 or 50 miles from Alexandria.

SHIPPENSBURG, a post-town of Penafylvania, Cumberland co, on a branch of Conedogwinnet Creek, which empties into the Sufquehannah; and contains about 60 houses, chiefly built of Kone. I i 4 It is 21 miles north by east of Chamberburg, a like diffance fouth-west of Carlisle, and 146 west of Philadelphia.

SHIRLEY, a township of Massachufetts, in the north-west part of Middlefex co. 41 miles N. W. of Boston. It was incorporated in 1753, and contains 677 inhabitants.

SHIRLEY, a township of Pennsylvania, fituated in Huntingdon county.

SHOALS, Ifles of, are γ in number, fituated on the coalt of New-Hampfhire; and to thefe the celebrated Capt. John Smith gave his own name, but the ingratitude of man has denied his memory that fmall honour. The Ifle of Shoals to the Dry Salvage Rock, the courfe is S. $\frac{1}{2}$ W. 8 leagues; to Portfmouth N.N. W. 3 leagues; to Newbury-Port Bar S. W. 7 leagues; to York harbour N. $\frac{1}{2}$ E. 5 leagues. N. lat. 42. 59. W. long. 70. 33.

SHOENECK, a Moravian fettlement in Pennfylvania, near Nazareth ; begun in 1757.

SHOREHAM, a township of Vermont, Addison co. on the east fide of Lake Champlain, having Orwell on the south and Bridport on the N. a little N. E. of Ticonderoga. Itcontains721inhabitants.

SHREWSBURY, a post-town of New-Jerfey, Monmouth co. on the fea board, having Middletown on the N. Freehold W. and Dover fouth-weft. North river divides it from Middletown, and is navigable a few miles. This town is 15 miles north-east by east of Monmouth court-houfe, 14 fouth-east of Middletown Point, 49 eafterly of Trenton, 33 fouth-east by east of Brunswick, and 79 east-north-east of Philadelphia. The compact part of the town is pleafant, and contains an Epifcopal and a Prefbyterian church, and a meeting-houle for Friends. On the fide of a branch of Navefink river, in this town, is a remarkable cave, in which are 3 rooms, arched with a foft porous rock, through which the moifture flowly exudes, and falls in drops on the fand below. The townthip contains 4,673 inhabitants, including 212 flaves. Much genteel company from Philadelphia and New-York refort here during the fummer months, for health and pleafure.

SHREWSBURY, a township of Vermont, in Rutland co.' between Clarendou on the west, and Saltash on the cast, and contains 333 inhabitants.

SIE

SHREWSEURY, a township in York co. Pennfylvania.

SHREWSBURY, a township in Worcefter co. Massachuletts; 6 miles east of Worcester, and 40 west by south of Boston. It was incorporated in 1727, and contains 963 inhabitants.

SHUBENACADIE, a river of Nova-Scotia, which rifes within a mile of the town of Dartmouth, on the E. fide of Halifax harbour, and empties into Cobequid Bay, taking in its courfe the Slewiack and Gay's rivers. 'The great lake of the fame name lies on the E. fide of the road which leads from Halifax to Windfor, and about feven miles from it, and 21 miles from Halifax.

SHUTESBURY, a township of Massachusetts, Hampshire co. on the east fide of Connecticut river, about 16 miles N. E. of Northampton, and 90 W. by N. of Boston.

SIARA; or Seara, a town on the N. E. coaft of Brazil, in the captainfhip of its name. S. lat. 3. 30. W. long. 39. 50. Andrew Vidal, of Negreiros, was chief magistrate of this city in the year 1772, in the 124th year of his age, and difcharged his duty as a judge to entire fatisfaction; and died 2 years after, in full possession of his mental powers. In 1773, 189 of his descendants were alive.

SIBALDES, iflands on the coaft of Patagonia, in S. America. S. lat. 50. 53. W. long. 59. 35.

W. long. 59: 35. SIBAU Iflands, on the coaft of Cape Breton Ifland, lie off the fouth point of Port Dauphin, and afford good anchorage.

SICCA PUNTO, or Dry Point, on the north coaft of S. America, on the Spanish Main, is the north-weit limit of Triefte Bay, and foutherly of the island of Curacao.

SICHEM, formerly a fettlement of the Moravians, on the east line of New-York State; 25 miles E. S. E. of Kingfton, on Hudfon's river.

SIDNEY, a township of New-York State, on the north line of Pennsylvania, opposite to the mouth of Chenengo river; having Susquehannah for its north and eastern boundary.

SIDELING *Hill*, a range of hills which lie in the north-weftern part of Maryland, between Alleghany and Wafhington counties, which are divided by the creek of the fame name.

SIERRE MADRE, See Andes. SILVER

SIL upon river ; low la are ful and fal dicular variou the gro tends 1 from h nearly appear berry, hrubs which tancé. ancien races, treffes ftructe litary : be the who fo hopes SIM 3 larg the Al on the land; mouth of the Alatar batter Jekyl gun th is abo two to fruitfu trees, old In ifland bar or W. 1 SIM St. Sir St. Sir its wh SIM cut, ir Hartfe here. SIN branch SIN the fo numbe parati Sinepu

SILVER Bluff, a confiderable height upon the Carolina fhore of Savannah river; perhaps 30 feet higher than the low lands on the opposite fhore, which are fubject to inundations in the fpring and fall. This steep bank rifes perpendicularly out of the river, discovering various firata of earth. The furface of the ground upon this bluff, which extends nearly two miles on the river, and from half a mile to a mile in breadth, is nearly level, and a good fertile foil, as appears by the vaft oaks, hickory, mulberry, black walnut, and other trees and thrubs left flanding in the old fields, which are fpread abroad to a great diftance. Here are various veftiges of the ancients ; as Indian conical mounts, terraces, areas, &c. as well as traces of fortreffes of regular formation, as if constructed after the modes of European military architects ; which fome fuppofe to be the ancient camps of the Spaniards, who formerly fixed themfelves here, in hopes of finding filver.

SIMON'S, ST. the easternmost of the 3 large iflands lituated at the mouth of the Alatamaha river in Georgia, having on the N. N. E. Little St. Simon's Ifland; and between these is the eastern mouth of the river. The fouthern end of the island is near the N. mouth of the Alatamaha. It formerly had a ftrong battery erected here, for the defence of Jekyl Sound, in which 10 or 12 forty gun thips may ride in fafety. This island is about 45 miles in length, and from two to four in breadth, has a rich and fruitful foil, full of oak and hickory trees, intermixed with meadows and old Indian fields. In the middle of the island is the town of Frederica. The bar or entrance of St. Simon's is S. by W. 19 leagues from Tybee Inlet.

SIMON's Fort, St. at the fouth end of St. Simon's Ifland, is 9 or 10 miles from St. Simon's Bar; and is remarkable for its white appearance,

SIMSBURY, a township of Connecticut, in Hartford co. 14 miles N. W. of Hartford. Copper ore has been found here.

SINEMAHONING, a N. wefternmoft branch of Sufguehannah river.

SINEPUXENT, a very long bay on the fouth-east coast of Maryland; a number of long and narrow iflands feparating it from the Atlantic Ocean. Sinepuxent Inlet, is in about lat. 38, 10. | fouth-eaft of Annapolis.

30. N. and nearly 12 miles eaft of the town of Snowhill.

505

SING-SING, an inconfiderable village on the east, fide of Haverstraw Bay, in Weft-Chefter co. 35 miles N. of New-York city.

SINICA, confiderable Cherokee a town, on the banks of Keo wee river. The houses on the east fide are on an elevated fituation, and command a de lightful and extensive prospect of the whole settlement. The inhabitants, about 500 in number, can muster 100 warriors.

SINKING Spring Valley. See Bald Eagle Valley.

SINO, or Sinu, a bay on the N. coaft of Terra Firma, South-America. There is also a town of the same name on the fide of the Gulf of Morofquillo, about 66 miles N. E. of St. Sebaftian, and 40. S. W. of Tolu.

Stous, or Sioux, a powerful nation of Indians, confifting of three different tribes, which can furnish 9,500 warriors; the Sious, who inhabit the head waters of the Miffifippi and Miffouri, 3,000 warriors; the Sious of the Meadows, 2,500, and the Sious of the. Woods, 4,000. The two laft inhabit on the head and weftern waters of the Milfilippi, and the iflands of Lake Superior.

SIPSEY's, a branch of Tombeckbee river, in Georgia, which runs a fouthwelt by fouth course. Its mouth is in about lat. 31. 55. N. and 40 miles N. by W.of the upper mouth of Alabama river.

Sir Charles Hardy's Island, in the S. Pacific Ocean, was discovered in 1767, by Captain Carteret. It is low, level, and covered with wood. S. lat. 4. 41. W. long. 154. 20.

SIR Charles Saunder's Island, in the fame ocean, and difcovered by the fame navigator, is about two leagues in length from E. to W. S. lat. 17. 28. W. long. 151. 4.

SIRIUS, a fmall ifland in the fame ocean, discovered by Lieutenant Ball, in 1792. It is about 18 miles in circuit. S. lat. 10. 52. W. long. 162. 30.

SISAL, on the north coaft of Yucatan, in the Gulf of Mexico, is 4 leagues weft of Linchanchee, and 8 eaft of Cape Condecedo. It is the highest look out on the whole coaft.

SISSIBOU, in Nova-Scotia, lies on the east fide of St. Mary's Bay, 28 miles

SISTER'S

Noraft of Bof-

and

lova-

f the

de of

obe-

lewi-

lake

de of

x to

m it,

affa-

t fide

s N.

y N.

e N.

ip of

· 50. chief

772, dif-

ntire

r, in

. In

live.

Pa-

53.

Cape

nt of

hor-

n the

pan-

t of

fland

f the

lew-

ing-

ork

ania,

engo its

hich

ary-

ingthe

VER

York

SISTER's Ferry, a village in S. Carolina, as miles from Coolawatchie, and 102 from Charlefton.

506

SIX MENS' Bay, on the weft fide of the ifland of Barbadoes, towards the N. end. It lies between Sunderland Fort to the fouth, and Six Mens' Fort to the N.

SIX NATIONS, a confederacy of Indian nations fo called by the British and The French call them Americans. Iroquois. Formerly they were called the Five Nations, five only being joined in that alliance; but they now confift of fix nations, and call themfelves Aganuschioni, that is, the United People, Some call them Mingos; others Ma-quais. These fix nations are the Mobazuks, Oncidas, Onondagas, Senecas, Cayugas, and Tufcaroras. The latter joined the confederacy 70 years ago. In the late war with G. Britain, they were allies of that power, and in 1779 they were entirely defeated by the troops of Congress, and their towns all deftroyed. They new live on grounds called the State Refervations, which are interme-diate fpaces fettled on all fides by white people. In their prefent cramped fitua-tion, they cannot keep together a great while. They will probably quit the United States and retire over the lakes Ontario and Erie. All the Mohawks and the greater part of the Cayugas, have already removed into Canada. The number of fouls in all the fix nations was, in 1796, 4,058. The Stockbridge and Brotherton Indians, who now live among them, added, make the whole number, 4, 508, of whom 760 live in Canada, the reft in the United States. By a treaty made in 1794, between the United States on the one part, and the Six Nations and their Indian friends refiding with them, on the other part, it was flipulated that " the fune of 4,500 dollars should be expended aunually and forever, in purchasing cloathing, domeffic animals, implements of hufbandry, and other utenfils, and in compenfating ufeful artificers who shall re-fide among them, and be employed for their benefit." This allowance is under the direction of a fuperintendant, and is not distributed for any private purpoles. It is apportioned among them according to their numbers, in order to which, there is annually taken an exact cenfus of all these Indians. In 1796, the Friends, commonly called Quakers, in their be

nevolence and zeal to promote the welfare of these Indians, raised a fund to fupport a number of their fociety, who offered to go and refide among them, with a view to promote their civiliza-tion, moral improvement, and real welfare. A committee of their fociety was appointed to accompany these friends to humanity, and they were actually on the fpot, and commenced their work of charity in July of this year. The State of New-York have taken these Indians under their protection, and appointed commiffioners to take care that they receive no wrong from interefted individuals.

SKE

minatio

ment.

far the

institu

conver

parts

there w

claffes

belles

fophy.

tion h

is lefs

of the

to the

Bonda

Subfe

Cafb

Houf

Lot f

Houli

pro

inte

deb

of 1

pu

pre

col

occ

den

the

Du

fefl

and

Eu

rtig chi

hai

tee

Lega

A

-103/26

And

ty of of th

the 1

for 1

the 1

an a

250

dinai

The

in th

clafs

the '

the (

Cafh

98

Book

SKANEATETES, a lake in Onondaga county, New-York, 14 miles long from fouth-east to north-weft, and little more than one mile wide where broadeft. It waters the military townships of Marcellus and Sempronius, and fends its waters northerly to Seneca river.

SKENECTADY, an ancient and refpectable town in Albany co. New-York, 16 miles north-weft of Albany city, pleafantly fituated in a vale bordered with hills to the fonthward and eaftward, on the margin of Mohawk river. The houses, about 1 50 or 200 in number, are compactly built, chiefly of brick, on regular freets, in the old Dutch ftile, on the fouth fide of the river : few of them are elegant. The public buildings are a Dutch and a Prefbyterian church. The windings of the river, through the town and fields which are often overflowed in the fpring, afford a rich and charming prospect about harveft time. This town, being at the foot of navigation, on a long river which paifes through a very fine country rapidly fettling, it would be natural to conclude, would embrace much of its commerce; but originally knowing no other than the fur trade, which, fince the revolution, has almost ceased, and having taken no advantage of its happy fituation for other commerce, the place has confiderably decayed. The chief bufinels of this town now is to receive the merchandize from Albany, and put it into batteaux to go up the river, and forward to Albany the returns from the back country. See Mohawk River. Union College was eftablished and incorporated here in 1794, and is under the direction of 24 truffees. It took its name from the union of various denominations

SKE	and a state	255
minations of Christians in it	s eftabli	h-
ment. The Dutch were, h	owever.	by I
far the most liberal benefad	tors to t	his
institution. It is well fitua conveniency of the northern	ted for	the
conveniency of the northern	and weft	ern
parts of the State. In]	une, 17	96,
there were 40 students, div	ided int	P 4
claffes, viz 1 languages, 2	quitory	ilo
belles lettres, 3 mathematic fophy. The annual expen	e of edu	10-
tion here, including board,	tuition.	Sec.
is lefs than 100 dollars. I	he prop	erty
of the college confifts in vari	ous artic	les,
to the following amount, vi	Z.	222
Bonds and mortgages, 7	dolls.	cts.
producing an annual }	21,301	6
	Louis and	part
Subscriptions, and other 7	an march	linas I
debts due on the books }	4,983	10
of the treasurer J Cash appropriated for the 7	they along a	gant.
purchase of books	1,356	45
House and lot for the?	g Title Constant	in the second
prefident	3,500	g er en ar Lind Sair
Lot for the fcite of the ?		
college	3,250	1.00
Houle and lot heretofore	. Since	. Walter
occupied for the aca-	ALC: NO	
demy, a donation from >	5,000	ball i
the confiftory of the Dutch church	1	They'd
Books, &c. in the pol-)	Sec. Sec.	12:24
feffion of the truftees, (13°
and on the way from	2,381	99
Europe	gan su can na canàite	
Cafh appropriated by the	and the second	in ai
regents for the pur-	anide :	1.11
chale of books in the >	400	R 491
hands of the commit-	d dampil	14.0
tee Targer by Abraham 7	1 H C 14	14.
Legacy by Abraham } Yates, jun. Elq. of }	250	iller B
Albany	ant failtaire	IL IN
- The Design of the Section	APT PERTING	Server L
	1 TO 7 LONG (1)	

· Market The State State State And 1,604 acres of land. The faculty of the college confided, in 1797 of the prefident and one tutor; and the falary of the former with an house for his family is 1100 dollars, and of the latter 665 dollars per annum, with an additional allowance at prefent of 2 50 dollars, on account of the extraordinary price of the necessaries of life: There were, in 1797, 37 students, eight in the clafs of languages, twenty in the clafs of hiltory and belles lettres, fix in the clais of mathematics, and three in the clais of philolophy. . The course of,

ftudies is, the first year Virgil, Cicero's orations, Greek Testament, Lucian, Roman antiquities, arithmetic and Englifh grammar-ihe fecond year, geo. graphy and the ule of the globes, Rothe American revolution, Xenophon, Horace, criticilin and eloquence-the third year, the various branches of mathematics, and vulgar and decimal fractions, and the extraction of the roots, geometry, algebra, trigonometry, navigation, mentiuration, Xenophon continued, and Homer-and the fourth and laft year, natural philosophy, the conftitution of the United States and of the different States, metaphylics, or at leaft that part which treats of the philolophy of the human mind, Horace continued, and Longinus : and during the course of these fludies, the attention of the clasfes is particularly required to elocution and composition in the English language, A provision is also made, for substituting the knowledge of the French language instead of the Greek, in certain cases, if the funds fhould hereafter admit of inftituting a French professorship. The library confilts of about 1000 volumes, and £ 500 is appropriated to the purchale of a philolophical apparatus. The township of Skenectady contains 3,472 inhabitants; of whom 683 are electors, and 381 flaves. It is bounded eafterly by Half Moon and Water-Vliet, and foutherly by the north bounds of the manor of Renflelaerwick.

SK

507

SKENESBOROUGH, now called Whitghall, is a growing township in the northeast corner of the Sate of New-York, fituated on Wood Creek, on the fouth fide of South Bay. This is a place through which moft of the communication and trade between the counties on Lake Champlain and Hudfon's river It has, however, very bad waaffes. ter, and is unhealthy in fummer. It is about 8 miles east by north of Fort George, and 6 north by east of Fort Ann. The fortifications here were de-Broyed by Gen. Burgoyne, in July, 1777.

SKIPPACK, a township in Montgomery county, Pennfylvania.

SKIPTON, a village on the north fide of Patowma'c river, about 11 miles foutheast of Fort Cumberland, and 28 foutherly of Bedford in Pennfylyania.

SKITIKISS, a bay of about 8 leagues extent on the east fide of Washington's Ifles.

vel-

i to who

em,

iza.

wel-

on

k of

itate

ians

nted

re-

livi-

laga

ron

nore

It

Mar-

its

ref-

ork,

city,

lered

eaft-

iver.

um-

rick,

utch

few

uild-

erian

iver,

h are

ord a

har-

e foot

paiapid-

con-

com.

other

e re-

hav-

py fi-

place

chief

ceive

d put

, and

n the

iver.

ncor-

er the

k its

deno-

ations

was ends

Ifles, on the N. W. coaft of N. America, northward of Cumberland Harbour. The opening is in lat. about 53. 15.

SKUPPERNONG, a finall river of N. Carolina. A canal was finished in 1790, which connects the waters of this stream with the lake in Dismal Swamp, on the fouth fide of Albemarle Sound.

SKUTOCK Hills, in Hancock co. Diftrict of Maine, lie north-north-east of the harbour of Gould/borough. In failing from Mount Defert to Gould/borough, you muft fleer north-north-east for these hills, which are more remarkable than any in the eastern country. There are five of them, and at a distance they appear round.

SLABTOWN, a village in Burlington co. New-Jerfey, about half way between Burlington and Mount Holly, 4 or 5 miles from each.

SLAUGHTER Creek, a fhort fiream on the east fide of Chefapeak Bay, Dorchefter county, Maryland.

SLAVE Lake and River, in the northweft part of N. America. The lake is extensive and gives rife to M'Kenzie's river, which empties into the Frozen Ocean, and receives the river of its name from the weft end of Athapefcow Lake; befides many other rivers from various directions. Slave river runs a northweft by north courfe, and is a mile wide at its mouth. The latitude of Slave Lake is 61. 26. N. and the centre of the lake is in about long. 115. weft. The northern bay is 40 leagues deep, and 6 fathoms water. The Dog-ribbed Indians inhabit the north shore of this lake.

SLEARING Ifland, on the coaft of Newfoundland.

SLOKUM'S Ifland is the third of the Elizabeth Iflands in magnitude, being about 5 miles in circuit. It lies off Buzzard's Bay, in Barnstable co. Maffachusetts, and west of Tinker's Island.

SLUSHER, Fort. See Schloffer.

SMALL Point, on the coalt of Lincolu co. Diffict of Maine, forms the eaft limit of Cafco Bay, and lies N. E. of Cape Elizabeth, the weftern limit.

SMITH, a township in Washington county, Pennsylvania.

SMITHFIELD, a fmall post-town of Virginia, on Pagan Creek, which empties into James's river, in Isle of Wight so. It is \$5 miles south-east of Richmond, and 364 south-south-west of Phi-

SMI

ladelphia. The creek is navigable for veffels of 20 tons.

SMITHFIELD, a post-town, and the capital of Johnson co. N. Carolina, on the east fide of Neus river, on a beautiful plain, about 100 miles north-west of Newbern, 25 from Raleigh, and 473 from Philadelphia.

SMITHFIED, a township of Pennsylvania, Philadelphia county.

SMITHFIELD, Upper and Lower, twotownships in Northampton co. Pennfylvania.

SMITHFIFLD, a township of Rhode-Island, Providence co. having the State of Maffachusetts on the north, and Cumberland on the N. E. Here are extenfive orchards; and great quantities of ftone-lime are made, and transported to Providence and other places. It contains 3171 inhabitants, including 5 slaves.

SMITH'S Cape, the north point of the entrance into a fea called the New Difcovered Sea, and the S. W. point of the island formed by that fea or found, which communicates with Hudfon's Straits! It is on the east fide of Hudfon's Bay. N. lat. 60. 48. W. long. 80. 55.

SMITH'S Ifland, on the coaft of N. Carolina. See Cape Fear, and Bald Head.

SMITH's Ifland, the fouthernmoft of the range of illands, in the Atlantic Ocean, along the coaft of Northampton and Accomack counties, Virginia. It is near the S. point of Cape Charles, Here thips frequently come to anchor to wait for pilots to conduct them into Chefapeak Bay.

SMITH'S *lifes*, the range of iflands which line the above coaft. They were fo named in 1608, in honour of Captain John Smith, who landed on the peninfula, and was kindly received by Accomack, the prise of the peninfula, part of which ftill bears his name.

SMITH'S Ifland, a finall island at the eaft end of the island of Antigua, and in Exchange Bay. Also the name of an island in the S. Pacific Ocean, difcovered by Lieutenant Ball, in the year 2790. S. lat. 9. 44. W. long. 161. 54.

SMITH'S Point is the fouthern limit of the mouth of Patowmack river, on the weft fide of Chefapeak Bay, oppofite to the northern head land, called Point Lookout, and in about lat. 37, 54. north.

SMITH'S

SMI Staun SMI Newfo by Ca SMI co. D weft fi tains g SMI Suffol 52 mi and 14 thip is erly b Sound Brook mick. whom SM Brunf near about SM E. Fl bluff branc miles about al, ar bited quies, Turn SN. the fo in lat The ! oppof SN town Word of P throu Bay, Here and g cipall

ports

Septe

of 4,

Horn

ming

W. 0

co. D

the V

Sidne

N. V

So

SN

Smith's, or Staunton River. See Staunton River, in Virginia. SMITH's Sound, on the east coast of

for

the

OB

Iti-

veft

73

yl-

WO

nn-

de-

ate

en-

s of

to

ins

the

)if-

the

nd,

n's

ud-

ng,

N.

ald

t of

ntic

oton

It

les,

hor

into

inds

vere

tain

nin-

ccu-

part

t the

d in

fan

ered

790.

imit

, 00

ppo-

alled

37.

TB'S

Newfoundland Ifland, is bounded north by Cape Bonaventure.

SMITHTOWN, a plantation in Lincoln co. Diffrict of Maine, fituated on the west fide of Kennebeck siver, and contains 521 inhabitants.

SMITHTOWN, a finall post-town of Suffolk co. Long-Ifland, New-York, 52 miles S. cafterly of New-York city, and 147 from Philadelphia. The town-Map is bounded foutherly by Iflip, wefterly by Huntington, northerly by the Sound, and cafterly by the patent of Brookhaven, including Winne-commick. It contains 1052 inhabitants, of whom 167 are electors, and 166 flaves. SMITHVILLE, the chief town of Brunfwick co. N. Carolina, fituated near the mouth of Cape Fear river, about 30 miles fouth of Wilmington.

SMYRNA, New, a thriving town in E. Florida. It is fituated on a fhelly bluff on the weft bank of the fowth branch of Molquito river; about 10 miles above the Capes of that river, about 30 miles north of Cape Canaveral, and in lat. 28. porth. It is inhabited by a colony of Geeeks and Minorquies, eftablished not long fince, by Dr. Turnbull.

SNAKE Indians, a tribe who inhabit the fouth-wettern fide of Miflouri river, in lat, about 47. N. and long. 107. W. The Shevetoon Indians inhabit on the opposite fide of the river.

SNOWHILL, a port of entry and polltown of Maryland, and the capital of Worcefter co. fituated on the S. E. fide of Pokomoke river, which empties through the eaftern fhore of Cheiapeak Bay, about 12 miles to the fouth-weft. Here are about 60 houfes, a court-houfe, and gaol, and the inhabitants deal principally in lumber and corn. The cxports for one year, ending the 30th of September, 1794, amounted to the value of 4,040 dollars. It is 16 miles from Horntown, in Virginia, 82 S. of Wilmington, in Delaware, and 158 S. by W. of Philadelphia.

SNOWTOWN, a fettlement in Lincoln co. Diffrict or Maine; fituated between the Weft Ponds, 7 or 8 miles W. of Sidney, opposite to Vaffalborough, and N. W. of Hallowell.

SOCANDAGA, or Sagendaga, the W.

soc

branch of Hudion's river, runs a fouth and fouth east course, and about 15 miles from its mouth, takes a north-east direction, and joins that river about 12 or 15 miles W. by North of Fort Edward. SOCIETY Iflands, a clufter of islands in the S. Pacific Ocean. To thefe iflands Capt. Cook was directed by Tupia, in 1769; and he gave them this name in honour of the Royal Society. They are fitnated between the latitodes of 16. 10. and 16. 55. S. and between the longitudes of 1 50. 57. and 1 52 W. They are feven in number; Huabeine, Ulietea, Otaba, Bolabola, Mourooa, Toobaee, and Tabooyamanoo or Saunders fland, which is here included, as being The foil, the fubject to Huaheine. productions, the people, their language, religion, cultoms, and manners are fo nearly the fame as at Otaheite, that little need be added to the account which has already been given. Nature has been equally bountiful in uncultivated plenty, and the inhabitants are as luxurious and as indolent. A plaintain branch is the emblem of peace, and changing names the greatest token of friendship. Their morais are differently constructed, though ferving the fame purposes. It is customary to give their daughters to ftrangers who arrive amongft them ; but the pairs mult be five nights lying near each other, without prefuming to take any other liberty. On the fixth evening, the father of the young woman treats his guest with food, and informs his daughter, that fhe must that night receive him as her hufband. The ftranger must not express the leaft diflike, fhould the partner allotted to him be ever to difagreeable; for this is confidered as an unpardonable affront, and is punified with inftant death.

SOCONUSCO, a province of New-Spain, having Chiapa on the N. Guatimala on the E. the N. Pacific Ocean on the S. and Guaxaea on the W. It is about 90 miles long, and almost as broad. It does not produce much corn, but great quantities of cocoa and indigo.

SOCONUSCO Port, on the W. coaft of New-Mexico, capital of the province of Soconusco, in which are the mountains of this name. N. lat. 15, 12. W. long. 98. 16,

SOCORA, an island on the coaft of South-America.

Sonus, Great, a gulf connected with the

.....

the fouth fide of Lake Ontario; by a short and narrow entrance. It is about 9 miles long, and 4 broad, and has an island in the eastern part. The town called Sodus, stands on the west fide, near the S. W. part of the bay, or gulf; about 24 miles north of Geneva, 35 fouth-westward of Oswego Fort, and 200 east of Niagara.

SOIL Cove, a fettlement on Defert Ifland in the Diffrict of Maine.

SOLANGO, an ifland on the coaft of Peru; 21 miles N. by W. from Colanche river, and 12 fouth of Port Callo.

SOLAR, Morro or Cape Solar, on the coaft of Peru, is 6 miles N. by W. of the rocks of Pachacama off the port of Gallao.

SOLDIER'S Gut, on the N. E. coaft of the Island of St. Christopher's, in the W. Indies, eastward of Half Moon Bay, and also eastward of Christ Church.

SOLEBURY, a township in Buck's co. Pennsylvania.

SOLIDAD, la, or the Defert, a cloifter of bare-footed Carmelites; fituated on a hill 3 leagues N. W. of the city of Mexico, incloied with a high ftone wall feven leagues in compais. The hill, on which the monaftery ftands, is furrounded with rocks, in which they have dug caves for oratories. Here are gardens and orchards 2 miles in compais, filled with the choiceft European fruit trees. The provincial Chapter of the Order is sheld here.

SOLODAD Port, on the E. fide of the eaflernmoth of the Falkland Islands, was formerly called Port Louis. The inner part of the harbour lies in the 57th degree of W. long, and in S. lat. 51. 50. SOLIMOES. See Madera kiver.

SOLOMON'S Ifles, or Land of the Arfacides, a group of islands concerning the existence of which, there has been much dispute, lie about 1,850 Spanish leagues W. of the coaft of Peru, in the vicinity of New-Guinea, between 154. and 160, E. long. from Paris, and between 6. and 12. S. lat. They were firft discovered by Mendana, in his firth voyage in 1567. Herrera, in his de-feription of these islands, reckons 18 principal ones belonging to the group, from 50 to 300 leagues in circumference, befides many of a fmaller fize. The air of these islands is falubrious, the foil fertile, the inhabitants numerous, and of different shades from white to black.

The principal of these islands are, St. Isabella, (which see) St. George, St. Mark, St. Nicholas, Florida, the island of Palms, &c.

SOLON, a military township of New-York, Onondago eo. about 35 miles N. W! from Susquehannah river, and 37 fouthward from Lake Onelda. It is under the jurifdiction of the town of Homer, which was incorporated in 1794.

SOMBAVERA Mands, in the West-Indies. See Sombrero.

SOMBELLO Point, weftward of the Gulf of Darien, is 5 miles northward of Francifco river.

SOMBRERA, Sombaverd, or Somblero, a finall defert island in the West-Indies, about 18 miles N. W. of Anguilla. It is about a league each way, and is thus called by the Spaniards, from its refemblance to a hat. N. lat. 18. 38. W. long. 63. 37. It is dependant on Barbuda.

SOMELSDYK, Fort, a Dutch fort at the confluence of the rivers Commewine and Cottica; the latter being an arm of Surrinam river.

SOMERS Ifles. See Bermuda.

SOMERS, a township of Connecticut, on the north line of Tolland co. which separates it from the State of Massachufetts. It contains about 1200 inhabitants, and is 24 miles N. E. of Hartford.

SOMERSET, a township in Washington county, Pennsylvania.

SOMERSET, a townflip of Vermont, Windham county, 10 or 12 miles northeaft of Bennington.

SOMERSET, a post-town of Massachuletts, Bristol co. and on Taunton river. It was incorporated in 1790, and contains 1151 inhabitants. It is 9 miles easterly of Warren in Rhode-Island, 52 foutherly of Boston, and 311 northeast of Philadelphia.

SOMERSET, a well cultivated county of New Jerley, on the north fide of the great road from New-York to Philadelphia. The foil, efpecially on Rariton river and its branches, is good, and produces good crops of wheat, of which great quantities are annually exported. It is divided into 6 townfhips, which have 3 churches for Piefbyterians, 5 for the Dutch reformed, 1 for Dutch Lntherans, and one for Anabaptifts. It contains 12,296 inhabitants, including 1810 flaves.

SOMERSET, the capital of the above county;

county Millfto houfe, 23 mil N. E. SOM bounde and W waters 15,610 flaves. county It was luntary tions ; legacie SON fylvani and for land, i SON ford cc Portfin It was it lies porate thund May, SOI Maine unite from ! rifes i Amar called ftream for at pids, venien head. Wate throus falling throug other length Green So divific Amer So bay o Sol Chan about river long. by th of th

St . St.

nd

w.

N.

37

mlo-

..

A-

the

of

se-

eftn-

ay,

ds,

lat.

de-

at

ine

n of

ut,

nich

hu-

bit-

ord.

ng-

ont,

rth-

iffa-

nton

and

\$ 9

and, rth-

anty

the

hila-

ari-

and

hich

rted.

hich

5 tor

Ln-It

ding

bove

ity;

county; fituated on the welt fide of Millitone river. It contains a court-houfe, gaol, and about 30 houfes. It is \$3 miles northerly of Trenton, and 72 N. E. by N. of Philadelphia.

SOMERSET, a county of Maryland, bounded east by the State of Delaware and Worcefter county, and weft by the waters of Chefapeak Bay. It contains 15,610 inhabitants, including 7,070 flaves. Washington Academy, in this county, was inftituted by law in 1779. It was founded, and is fupported by vo-luntary fubfcriptions and private donations; is authorifed to receive gifts and legacies, and to hold 2,000 acres of land. SOMERSET, a new county of Pennfylvania, bounded north by Huntingdon and fouth by All-ghany co. in Maryland, and is divided into 5 townships.

SOMERSWORTH, a township of Strafford co. New-Hampfhire, 19 miles from Portfmouth, containing 943 inhabitants. It was taken from Dover, from which it lies adjoining to the N. E. and incorporated in 1754. A dreadful form of thunder and lightning happened here in May, 1779.

SONGO River, in the Diffrict of Maine, is formed by two branches which unite in Raymondtown, about 3 miles from Sebago Pond. The longeft branch rifes in Greenland, about 3 miles from Amarifcoggin river, where is a pond called Songo Pond, 2 miles long. This ftream, which purfues a foutherly course for at least 70 miles, is fo free from rapids, that timber may be brought conveniently from within a few miles of its head. The other branch comes from Waterford and Suncook, and palles through a number of fmall ponds; then falling into Long Pond, it proceeds through Brandy Pond, and meets the other branch. It is boatable its whole length, 25 miles. See Orangetown or Greenland and Sebogo Pond.

SONORA, a fubdivision of the South division of New-Mexico, in North-America. Chief town, Tuape.

SONSONATE, a fea-port town and bay on the coaft of Mexico.

SORREL River, the outlet of Lake Champlain, which, after a course of about 69 miles north, empties into the river St. Lawrence, in lat. 46. 10. and long. 72. 25. W. Sorrel Fort, built by the French, is at the weftern point of the mouth of this river.

SOTOVENTO, a name applied to the Leffer Antiles, in the West-Indies. Among thefe, the chief may be reckon-ed Trinidad, Margaretta, Curafiou, and Tortugas.

SOTOVENTO Lobos, or Leeward Island of Sea Wolves or Seals, on the coaft of Peru, is 7 leagues from the Barlevento Lobos, or Windward Island of Sea Wolves. It is about 6 miles in circuit, and 15 miles from Cape Aguja. SOUBYAWAMINECA, a Canadian fet-

tlement, in lat. 47. 17. 30. N.

SOUTH, a fhort river of Anne Arundel co. Maryland, which runs eafterly into Chefapeak Bay. Its mouth is about 6 miles fouth of Annapolis city, and is navigable in veffels of burden 10 or 12 miles.

SOUTH Amboy, a township of New-Jersey, Middlefex co. and contains 2,626 inhabitants, including 183 flaves.

SOUTH-AMERICA, like Africa, is an extensive peninsula, connected with North-America by the Ifthmus of Darien, and divided between Spain, Portugal, France, Holland, and the Aborigines, as follows: Spain claims Terra Firma, Peru, Chili, and Paraguay; the Portuguese, Brazil ; the French Cayenne; the Dutch, Dutch Guiana; and the Aborigines, or original natives, Amazonia and Patagonia.

SOUTHAMPTON, See South Hampton, SOUTH Anna, a branch of North Anna river, in Virginia, which together form Pamunky river.

SOUTHBOROUGH, a small township in the eastern part of Worcester co. Maffachufetts, incorporated in 1727, contains 840 inhabitants, and is 30 miles W. by S. of Boffon.

SOUTH Branch Houje, a station of the Hudion's Bay Company, in North-America, fituated on the eaftern fide of Salkalhawan river.

SOUTH-BRIMFIELD, a township of Maflachufetts, Hampfhire co. about 35 miles S. E. of Northampton, and 80 wefterly of Bolton. It was incorporated in 1762, and contains 606 inhabitants.

SOUTHBURY, a town of Connecticut, Litchfield co. 20 miles N. E. of Dan-

bury, and 51 N. W. of Hartford. SOUTH East, a township of New-York, fituated in Dutchels corbounded foutherly by Weft-Chefter co. and wefterly by Fredericktown. It contains 921 unhabitants ;


inhabitants; of whom 261 are electors, nearly completed, which, by effimation, will coff aco.coc dollars; and the com-

SOUTH-CAROLINA, one of the United States of America; bounded N. by North-Carolina; E, by the Atlantic Ocean; S. and S. W. by Savannah river, and a branch of its head waters, called Tugulo river, which divides this State from Georgia. It lies between 32 and 35 N. lat. and between 78 and 81 W. long. from London. It is in length about 200 miles, in breadth 125; and contains 2000 miles, in breadth 125; and contains 20,000 fquare miles. It is divided into 9 diffricts. Charlefon, Beaufort, and Georgetown conflictute what is called the Lower Country, and contain 19 parifies, and 28,694 white in-habitants; fend to the legislature 70 reprefentatives, and 20 fenators, and pay taxes to the amount of £28,081 : 5 : 11. Ninety-Siz, Wajkington, Pinckney, Cam-den, Orangeburg, and Gheraw diffricts, are comprehended in the Upper Country, and contain 23 counties, and 110,902 white inhabitants; fend to the legiflature 54 representatives, and 17 fenators, and pay taxes to the amount of £8,390:2:3. The great inequality of representation is obvious; attempts have been made by the Upper diffricts, to remedy this evil, but hitherto without effect. By a late arrangement the name of county, is given to the fubdivision of those districts only, in which county courts are established. In the Lower diffricts, the fubdivitions are called parifhes, and made only for the purpole of electing the members of the State legislature. The total number of inhabitants in 1790, 249,073, of whom 107,094 were flaves. This State is watered by many navigable rivers, the principal of which are Savannah, Edifto. Santee, Pedee, and their branches. The Santee is the largest river in the State. Those of a fecondary fize, as you pals from N. to S. are Wakkamaw, Black, Cooper, Afhepoo, and Combahee rivers. In the third clafs are comprehended those rivers which extend but a fhort distance from the ocean, and ferve, by branching into numberless creeks, as drains to carry off the rain water which comes down from the large inland fwamps, or are merely arms of the fea. The tide in no part of the State, flows above 25 miles from the fea. A canal of 21 miles in length, connecting Cooper and Santec rivers, is

will coft 400,000 dollars ; and the company are allowed to raife a toll of ao per cent. on the fum actually expend-ed. Another canal is foon to be begun to unite the Editto with the Affiley. It is alfo in contemplation to make a waggon road from the fettlements in S. Ca-rolina, over the mountains to Knoxville, in Tennefice; and a fum of money has her voted for that purpole. The only harbours of note, are those of Charlet-ton, Port-Royal, and Georgetown. The climate is different in different parts of the State. Along the fea-coaft, bilious difcafes and fevers of various kinds are prevalent between July and October. The probability of dying is much greater between the 20th of June and the 20th of October, than in the other eight months in the year. One caufe of these difeases, is, a low marshy country, which is overflowed for the fake of cultivating rice. The exhala-tions from thefe ftagnated waters, from the rivers, and from the neighbouring ocean, and the profuse perspiration of vegetables of all kinds, which cover the ground, fill the air with moifture. This moisture falls in frequent rains and copious dews. From actual observation, it has been found that the average annual fall of rain, for ten years, was 43 inches, without regarding the moifture that fell in fogs and dews. The great heat of the day relaxes the body, and the agreeable coolness of the evening invites to an expolure to thele heavy dews. But not only does the water on the low grounds and rice fwamps become in a Idegree putrid, and emit an unwholefome vapour, but when it is dried up or drawn off from the furface of the ground, a quantity of weeds and grafs which have been rotted by the water, and animals and fifh which have been deftroyed by it, are exposed to the intense heat of the fun, and help to infect the air with a quantity of poilonous effluvia. Within the limits of Charlef-ton, the cafe is very different, and the danger of contracting difeafes arifes from indolence and excels. Though a refidence in or near the fwamps is very injurious to health, yet it has been fatisfactorily afcertained, that by removing three miles from them, into the pine land which occupies the middle ground between the rivers, an exemption from autumnal

\$12





autumnal fevers may be obtained. The difagreeable effects of this climate, experience has proved, might in a great measure be avoided, by those inhabitants whole circumftances will admit of their removal from the neighbourhood of the rice fwamps, to healthier fituations, during the months of July, August, September and October; and in the worft fituations, by temperance and Violent exercife on horfeback, care. chiefly, expolure to the meridian rays of the fun, fudden fhowers of rain, and the night air, are too frequently the caufes of fevers and other diforders. Would the fportfinen deny themfelves, during the fall months, their favourite amufements of hunting and fifting, or confine themfelves to a very few hours, in the morning or evening-would the industrious planter visit his fields only at the fame hours-or would the poorer class of people pay due attention to their manner of living, and observe the precautions recommended to them by men of knowledge and experience, much fickness and many distressing events might be prevented. The upper country, fituated in the medium between extreme heat and cold, is as healthful as any part of the United States. Except the high hills of Santee, the Ridge, and fome few other hills, this country is like one extensive plain, till you reach the Tryon and Hogback Mountains, 220 miles north-west of The elevation of thefe Charleston. mountains above their bafe, is 3840 feet, and above the fea-coaft, 4640. There is exhibited from the top of these mountains an extensive view of this State, North Carolina, and Georgia. And as no object intervenes to obstruct the view, a man with *telescopic* eyes might difeern veffels at sea. The mountains weft and north-west rife much higher than these, and form a ridge, which divides the waters of Tenneffee and Santee rivers. The fea-coaft is bordered with a chain of fine fea iflands, around which the fea flows, opening an excellent inland navigation, for the conveyance of produce to market. North of Charleston harbour, lie Bull's, Dewee's and Sullivan's illands, which form the north part of the harbour. James' ifland lies on the other fide of the harbour, opposite Charleston, containing about 50 families. Further fouth-weft is John's ifland, lar-

ger than James's; Stono river, which forms a convenient and fafe harbour, divides these islands. Contiguous to John's island, and connected with it by a bridge, is Wadmelaw; east of which are the finall ifles of Keywaw and Simmon. Between thefe and Edifto Ifland. is N. Edifto Inlet, which alfo affords a good harbour for veffels of eafy draft of water. South of Edifto Ifland is S. Edifto Inlet, through which enter, from the northward, all the vefiels bound to Beaufort, Asheepoo, Combahee, and On the fouth-weft fide of St. Coofaw. Helena Ifland lies a clufter of iflands. one of the largest of which is Port Royal. Adjacent to Port Royal lie St. Helena. Ladies Island, Paris Island, and the Hunting Iflands, 5 or 6 in number, bordering on the ocean, fo called from the number of deer and other wild game found upon them. All these islands, and some others of less note, belong to St. Helena parifh. Croffing Broad river, you come to Hilton Head, the most fouthern fea ifland in Carolina. Weft and fouth-weft of Hilton Head, lie Pinck-ney's, Bull's, Dawfufkies', and fome fimaller iflands, between which and Hilton Head, are Calibogie river and found. which form the outlet of May and New The foil on these islands is gerivers. nerally better adapted to the culture of indigo and cotton than the main, and lefs fuited to rice. The natural growth is the live oak, which is fo excellent for fhip timber; and the palmetto or cabbage tree, the utility of which, in the conftruction of forts, was experienced during the late war. The whole State, to the diftance of 80 or 100 miles from the fea, generally fpeaking, is low and level, almost without a ftone, and abounds more or lefs, efpecially on and near the rivers, with fwamps or marfhes, which, when cleared and cultivated, yield, in favourable feafons, on average, an annual income of from 20 to 40 dollars for each acre, and often much more: but this species of foil cannot be cultivated by white men, without endangering both health and life. These swamps do not cover an hundredth part of the State of Carolina. In this diffance, by a gradual afcent from the fea-coaft, the land rifes about 190 feet. Here, if you proceed in a W. N. W. course from Charleston, commences a curioufly uneven country. The traveller is constantly afcending

13 - 27/3

Kk

frolic. If a pretty high fea were fud-denly arrefted, and transformed into fand-hills, in the very form the waves existed at the moment of transformation, it would prefent the eye with juft fuch a view as is here to be feen. Some little herbage, and a few fmall pines, grow even on this foil. The inhabitants are few, and have but a fcanty fubfiftence on corn and fweet potatoes, which grow here tolerably well. This curious country continues till you arrive at a place called the Ridge, 140 miles from Charleston. This ridge is a remarkable tract of high ground, as you approach it from the fea, but level as you advance N. W. from its fummit. It is a fine high, healthy belt of land, well watered, and of a good foil, and extends from the Savannah to Broad river, in about 6. 30. W. long. from Philadelphia. Beyond this ridge, commences a country exactly refembling the porthern States, or like Devonshire in England, or Languedoc in France. Here hills and dales, with all their verdure and variegated beauty, present themselves to the eye. Wheat fields, which are rare in the low country, begin to grow common. Here Heaven has beftowed its bleffings with a most bounteous hand. The air is much more temperate and healthful than nearer to the fea. The hills are co-vered with valuable woods, the vallies watered with beautiful rivers, and the fertility of the foil is equal to every vegetable production. This by way of diffinction, is called the Upper Country, where are different modes, and different articles of cultivation; where the manners of the people, and even their language have a different tone. The land still rifes by a gradual ascent ; each succeeding hill overlooks that which immediately precedes it, till, having advanced 220 miles in a N. W. direction from Charleston, the elevation of the land above the fea-coaft, is found by menfuration to be 800 feet. Here commences a mountainous country, which continues rifing to the western terminating point of the State. The foil may be divided into four kinds; first, the pine barren, which is valuable only for its timber. Interfperied among the pine barren, are tracts of land free of timber and every kind of growth SOU

or defcending little fand-hills, which but that of grafs. These tracts are nature seems to have difunited in a called Savannas, constituting a second, kind of foil, good for grazing. The third kind is that of the fwamps and low grounds on the rivers, which is a mixture of black loam and fat clay, producing naturally canes in great plenty, cyprefs, bays, loblolly pines, &c. In these swamps rice is cultivated, which conftitutes the ftaple commodity of the State. The high lands, commonly known by the name of oak and hickory lands, conftitute the fourth kind of foil. The natural growth is oak, hickory, walnut, pine, and locuft. On thefe lands, in the low country, are cultivated Indian corn principally; and in the back country, befides thefe, they raise tobacco in large quantities, wheat, rye, barley, oats, hemp, flax, and cotton. From experiments which have been made, it is well afcertained that olives, filk, and madder may be as abandantly produced in South-Carolina, and we may add in Georgia alfo, as in the fouth of France. There is little fruit in this State, especially in the lower parts of it. They have oranges, which are chiefly fonr, and figs in plenty, a few limes and lemons, pomegranates, pears, and peaches; apples are fcarce, and are imported from the northern States. Melons, especially the water melon, are raifed here in great perfection. The river fwamps, in which rice can be cultivated with any tolerable degree of fafety and fuccefs, do not extend higher up the rivers than the head of the tides ; and in effimating the value of this fpecies of rice land, the height which the tide rifes. is taken into confideration, those lying where it rifes to a proper pitch for overflowing the fwamps being the most The beft inland fwamps, valuable. which conftitute a fecond species of rice land, are fuch as are furnished with referves of water. Thefe referves are formed by means of large banks thrown up at the upper parts of the fwamps, whence it is conveyed, when needed, to the fields of rice. At the diftance of about 110 miles from the fea, the river fwamps terminate, and the high lands extend quite to the rivers, and form banks, in fome places, feveral hundred feet high from the furface of the water, and afford many extensive and delight ful views. These high banks are interwoven

woven v ent colo quarries cryftals, lead, fu The fw tide, are cotton, i yielding acre. dations country mode of On the i 40 or 5 much fa No whi thinks it for h has no overfeet more th he can cles cul fpecies. with th groes ; hemp, of cott equal t was cu by ma fince t Now th improv rice fx will no middle numers fonally is not produc and for tion. corn, I a little there **fpeaki** depend northe themie the pk dian 1 rye, ba for foc hemp, From found wine r

210

ond.

The

and

h is

lay,

len-

&c.

ited.

dity

om-

and

cind

bak,

On

cul-

and

they

leat,

lave

that

t as

ina,

s in

ittle

the

ges,

i in

me-

ples

the

ally

in :

nps,

any

:efs,

Vers

efti-

rice

rifes

ring

for

noft

ips,

rice

re-

are

own

ips,

, to

iver

inds

orm

red

ter,

ht-

ter-

ven

of

cot-

woven with layers of leaves, and different coloured earth, and abound with quarries of free-ftone, pebbles, flint, cryftals, iron ore in abundance, filver, lead, fulphur, and coarfe diamonds. The fwamps, above the head of the tide, are occasionally planted with corn, cotton, and indigo. The foil is very rich, yielding from 40 to 50 bufhels of corn an acre. It is curious to obferve the gradations from the fea-coaft to the upper country, with respect to the produce, the mode of cultivation, and the cultivators. On the iflands upon the fea-coaft, and for 40 or 50 miles back, and on the rivers much farther, the cultivators are allflaves. No white man, to fpeak generally, ever thinks of fettling a farm, and improving it for himfelf, without negroes : if he has no negroes, he hires himfelf as overfeer to fome rich planter, who has more than he can or will attend to, till he can purchase for himself .. The articles cultivated are corn, rye, oats, every species of pulse, and potatoes, which, with the imall rice, are food for the negroes; rice, indigo, cotton, and fome hemp, for exportation. The culture of cotton is capable of being increafed equal to almost any demand. The foil was cultivated, till lately, almost wholly by manual labour. The plough, till fince the peace, was fcarcely ufed. Now the plough and harrow, and other improvements are introduced into the rice fwamps with great fuccefs, and will no doubt become general. In the middle fettlements, negroes are not fo numerous. The mafter attends perfonally to his own bufinefs. The land is not properly fituated for rice. It produces tolerable good indigo weed, and fome tobacco is raifed for exporta-The farmer is contented to raife tion. corn, potatoes, oats, rye, poultry, and a little wheat. In the upper country, there are but few negroes; generally fpeaking, the farmers have none, and depend, like the inhabitants of the northern States, upon the labour of themielves and families for fublishence ; the plough is used almost wholly. Indian corn in great quantities, wheat, rye, barley, oats, potatoes, &c. are raifed for food; and tobacco, wheat, cotton, hemp, flax and indigo, for exportation. From late experiments it has been found that vines may be cultivated, and wine made to great advantage: inake

SOU root, pink root, and a variety of medicinal herbs grow fpontaneoully; alfo, ginfeng on and near the mountains. This country abounds with precious ores, fuch as gold, filver, lead, black lead, copper and iron; but it is the miffortune of those who direct their purfuits in fearch of them, that they are deficient in the knowledge of chymistry, and too frequentlymake use of improper menstruums in extracting the respective metals. There are likewife to be found pellucid stones of different hues, rock cryftal, pyrites, petrified fubstances, coarfe cornelian, marble beautifully variegated, vitreous fione and vitreous fand; red and yellow ochres, which, when roafted and ground down with linfeed oil, make a very excellent paint ; alfo, potter's clay of a most delicate texture, fuller's earth, and a number of dye-ftuffs, among which is a fingular weed which yields four different colours, its leaves are furprifingly flyptic, ftrongly refembling the tafte of alum; likewife, an abundance of chalk, crude alum, fulphur, nitre, vitriol, and along the banks of rivers large quantities of marle may be collected. There are also a variety of roots, the medicinal effects of which it is the barbarous policy of those who are in the fecret to keep a profound myftery. The rattle-fnake root, fo famous amongst the Indians for the cure of poiion, is of the number. The next is the venerial root, which, under a vegetable regimen, will cure a confirmed lues. Another root, when reduced to an impalpable powder, is fingularly efficacious in deftroying worms in children. There is likewife a root, an ointment of which, with a poultice of the fame, will in a fhort space of time discuss the most extraordinary tumours, particularly what is termed the white fwelling ; this root is very fcarce. There is another root, a decoction of which, in new milk, will cure the bloody dyfentery; the patient must avoid cold, and much judgment is requifite in the portion to be administered. There is also a plant, the leaves of which, being bruifed, and ap plied to the part affected, relieves rheumatic pains; it occasions a confiderable agitation of the parts, attended with most violent and acute pains, but never fails to procure immediate eafe. There

boiled

is also a plant, the leaves of which have a most foetid fmell; these leaves being Kk 2

e*6

boiled, and any perfon afflicted with cutaneous complaints, once bathing therein, will be radically cured. There is a root, which acts as an excellent purge, and is well calculated for the labouring part of mankind, as it is only neceffary to chew it in its crude ftate, and it requires no manner of aid to facilitate its operation. An equally efficacious and fimple purge is obtained from a weed, the stalk of which is red, is about 3 feet high, and the flower white; the leaves run from the bottom of the stalk in opposite and corresponding lines; the feed is about the fize of a wheat grain, globular in the centre, and oblate at both ends; it is full of oil, and taftes like a walnut kernel : 20 grains of this, chewed and fwallowed, is, in point of mildnefs and efficacy, equal to any rhubarb; and the pleafantnefs of its tafte, as a deception to weak ftomachs, appears to have been a defign of Providence : in its operation it refembles caftor oil. A very lovereign remedy is extracted from the bark of a tree, which may be used to great advantage in the difeafes incident to this climate. Every climate, fome believe, has its peculiar difeafe, and every difeafe its peculiar antidote under the fame climate. In addition to the above is another fpecies of bark, of a fweet and naufeous tafte; the tree grows contiguous to a very powerful chalybeate fpring; the bark, when fufficiently mafficated, operates as a very potential purge and emetic, and in the hands of a skilful chemist may be rendered very ferviceable. In this country is a tree which bears a large pod, inclosing a kind of mucilage, the juice of which is very tharp; the bark fmells like tanned leather, and when prepared like hemp, makes the very beft of cordage. Alfo another tree, which bears an ear like a corn-cob, covered with berries, containing a large proportion of oil. There is likewife a very fingular tree, which affords a most superb shade ; it produces a round ball, which, in the heat of fummer, opens and enlarges a number of male infects, which become very troublefome wherever they lodge: this happens generally fome diftance from their parent tree. The hand of nature never formed a country with more natural advantages, or bleffed it with a more ferene or healthful climate. It

SOU

fine fruit country, and is peculiarlyadapted to the growth of vines, the olive, filk, and coffee trees, and the production of cotton. It is a perfect garden of medical herbs, and its medicinal fprings are not inferior to any in Europe. The ironworks, known by the name of the Æra Etna iron-quork, are fituated in York county, within two miles of the Catawba river. Within the compass of two miles from the furnace, there is an inexhauftible quantity of ore, which works eafy and well in the furnace. The metal is good for hanimers, gudgeons, or any kind of machinery and hollow ware, and will make good bar-iron. Some trial has been made of it in fteel, and it promites well. Nothing is neceffary for preparing the ore for ule, but burning. The ore confifts of large rocks above the furface ; the depth not yet known. In the cavities between, lie an ochre and feed ore. It is faid there will be no occasion to fink shafts or drive levels for 50 years to come. The Æra furnace was built in 1787the Ætna in 1788. The nearest landing at prefent (1795) is Camden, 70 miles from the furnace. The proprietors of the works, and feven others, have obtained a charter to open the Catawba to the N. Carolina line, and a charter from N. Carolina to open the river 80 miles higher in that State, and it is expected that boats will come within 40 miles of the works this fummer, (1795) as there are boats already built for the purpole which are to carry 30 tons, and in the course of another fummer will be brought within two miles of the works. The works are within two miles of the river, and the creek can be made navigable to the works. Mr. William Hill, one of the principal proprietors of these works, has contriv-ed a method, by means of a fall of water, of blowing all the fires both of the forges and furnaces, fo as to render unneceffary the use of wheels, cylinders, or any other kind of bellows. The machinery is fimple and cheap, and not liable to the accident of freezing. In the middle, and efpecially in the upper country, the people are obliged to manufacture their own cotton and woollen cloths, and most of their husbandry tools; but in the lower country, the inhabitants, for thefe articles, depend almost entirely on abounds with game of all kinds, is a very their merchants. La accounts from the - the inte that co that th good ft made, a way; t habit of nufactu great i The wo the mer State fu the bef live oal are of be buil much middle feamen is not much # nufactu bids fa is to be tice of Caroli the Ca as Frei mation grating ed pap fay, th profita mills, lumber ing wl of val the wo bufhel South will m in the double nefs at dollar a grea 2. In therin a co mild a ably and f when hides pair (price. now and th the bi

the interior parts of this State inform, that cotton, hemp and flax are plenty; that they have a confiderable flock of good fheep; that great exertions are made, and much done in the household way; that they have long been in the habit of doing fomething in family manufactures, but within a few years paft great improvements have been made. The women do the weaving, and leave the men to attend to agriculture. This State furnishes all the materials, and of the best kind, for ship building. The live oak, and the pitch and yellow pines, are of a superior quality. Ships might be built here with more eafe, and to much greater advantage, than in the middle and eaftern States. A want of feamen, is one reafon why this bufinefs is not more generally attended to. So much attention is now paid to the manufacture of indigo, in this flate, that it bids fair to rival that of the French. It is to be regretted, that it is ftill the practice of the merchants concerned in the Carolina trade, to fell at foreign markets the Carolina indigo of the first quality, as French. The fociety for the information and affiftance of perfons emigrating from other countries, in a printed paper, which bears their fignature, fay, that "A monied capital may be profitably employed, 1. In erecting mills, for making paper, for fawing lumber, and efpecially for manufacturing wheat flour. There are hundreds of valuable mill feats unimproved, and the woods abound with pine trees. Α bushel of wheat may be purchased in South Carolina for half a dollar, which will make as good flour as that which in the vicinity of proper mills fells for double that price. Such is the cheapnefs and fertility of the foil, that half a dollar a bufhel for wheat would afford a great profit to the cultivators thereof. 2. In tanning and manufacturing leather-Cattle are raifed with fo much eafe, in a country where the winters are both mild and thort, that hides are remark-ably cheap. The profits of tanners and fhoe-makers muft be confiderable, when it is a well known fact, that the hides of full grown cattle, and a fingle. pair of fhoes fell for nearly the fame price. 3. In making bricks-Theie now fell for 9 dollars a thouland, and the call for them is fo great, that the bricklayers are not fully fupplied.

4. In making pot-afh-The afhes that might be collected in Charlefton, and from the woods burnt in clearing new lands in the country, would furnish the means of carrying on the manufacture of pot-afh to great advantage." Gentlemen of fortune, before the late war, fent their fons to Europe for education. During the war and fince, they have generally fent them to the middle and northern States. Those who have been at this expense in educating their fons, have been but comparatively few in number, fo that the literature of the State is at a low ebb. Since the peace, however, it has begun to flourish. There are feveral refpectable academies in Charleston, one at Beaufort, on Port Royal Island, and feveral others in different parts of the State, Three colleges have lately been incorporated by law, one at Charleston, one at Winnf. borough, in the diffrict of Camden, the other at Cambridge, in the diffrict of Ninety-Six. The public and private donations for the fupport of these three colleges, were originally intended to have been appropriated jointly, for the erecting and supporting of one respect-able college. The division of these donations has fruftrated this defign. Part of the old barracks in Charlefton has been handsomely fitted up, and converted into a college, and there are a number of fludents ; but it does not yet merit a more dignified name than that of a respectable academy. The Mount Sion college, at Winnfborough, is fupported by a refpectable fociety of gentlemen, who have long been incorporated. This institution flourishes and bids fair for ufefulnefs. The college at Cambridge is no more than a grammar school. That the literature of this State might be put upon a respectable footing, nothing is wanting by a fpirit of enterprize among its wealthy inhabitants. The legiflature, in their feffion in January, 1795, appointed a committee, to enquire into the practicability of, and to report a plan for, the eftablishment of fchools in the different parts of the State. Since the revolution, by which all denominations were put on an equal footing, there have been no disputes between different religious fects: They all agree to differ. The upper parts of this State are fettled chiefly by Prefbyterians, Baptifts and Methodifts. From the moft probable

Kk3

510

the religious denominations of this State, as to numbers, may be ranked as follows : Prefbyterians, including the Congregational and Independent churches, Epilcopalians, Baptifts, Methodifts, &c. The little attention that has been paid to manufactures, occasions a vast confumption of foreign imported articles; but the quality and value of their exports generally leave a balance in favour of the State, except when there have been large importations of negroes. The amount of exports from the port of Charleston, in the year ending Nov. 1787, was then eftimated, from authentic documents, at 505,2791. 198. 5d. fterling money. The number of veffels cleared from the cuftom-house the same year, was 947, meafuring 62,118 tons ; 735 of thefe, meafuring 41,531 tons, were Americans ; the others belonged to Great Britain, Spain, France, the United Netherlands, and Ireland. The principal articles exported from this State, are rice, indigo, tobacco, fkins of various kinds, beef, pork, cotton, pitch, tar, rofin, turpentine, myrtle wax, lumber, naval ftores, cork, leather, pink root, fnake root, ginleng, &c. In the most fucceffful featons, there have been as many as 140,000 barrels of rice, and 1,300,000 pounds of indigo exported in a year. From the 1 5th Dec. 1791, to Sept. 1792, 108, 567 tierces of rice, averaging 550lb. nett weight each, were exported from Charleston. In the year ending Sept. 30, 1791, the amount of exports from this State was 2,693,267 dolls. 97 cents, and the year ending September, 1795, to 5,998,492 dollars 49 cents. Charlefton is by far the most confiderable city on the lea-coast, for an extent of 600 miles. From it are annually exported about the value of two millions and a half of dollars, in native commodities; and it fupplies, with imported goods, a great part of the inhabitants of North-Carolina and Georgia, as well as those of S. Carolina. The harbour thereof is open all the winter, and its contiguity to the Weft-India if ands gives the merchants fuperior advantages for carrying on a peculiarly lucrative commerce. A waggon road of fifteen miles only is all that is wanted, to open a communication with the inhabitants of Tenneffee. Knoxville, the capital of that State, is 100 miles nearer to Charleston than to any the letter

SOU

probable calculations, it is supposed that | other confiderable fea-port town on the Atlantic Ocean. The reformation in France occafioned a civil war between the Protestant and Catholic parties in that kingdom. During these domestic troubles, Jasper de Coligni, a principal commander of the protestant army, fitted out 2 fhips, and fent them with a colony to America, under the command of Jean Ribaud, for the purpose of fecuring a retreat from profecution. Ribaud landed at what is now called Albemarle river, in North- Carolina. This colony, after enduring incredible hardfhips, were extirpated by the Spaniards. No further attempts were made to plant a colony in this quarter, till the reign of Charles II. of England.

> SOUTHERN STATES; the States of Maryland, Virginia, Kentucky, North-Carolina, Tenneffee, South-Carolina, and Georgia, bounded N. by Pennfylvania, are thus denominated. This diffrict of the Union contains upwards of 1,900,000 inhabitants, of whom 648,439 are flaves, which is thirteen fourteenths of the whole number of flaves in the United States. The influence of flavery has produced a very diftinguishing feature in the general character of the inhabitants, which, though now difcernible to their difadvantage, has been foftened and meliorated by the benign effects of the revolution, and the progress of liberty and humanity. The following may be confidered as the principal productions of this division-tobacco, rice, indigo, wheat, corn, cotton, tar, pitch, turpentine and lumber. In this diffrict is fixed the permanent feat of the general government, viz. the city of Wafhington.

> SOUTHFIELD, a township of New-York, Richmond co. bounded northerly by the north fide of the road leading from Van-Duerson's Ferry to Richmond Town and the Fish-Kill; easterly by Hudson's river. It contains \$55 inhabitants.

> SOUTH Georgia, a clufter of barren islands in the S. Atlantic Ocean to the E. of Cape Horn, the fouthern point of S. America; in lat. about 54. 30. fouth, and long. 36. 30. W. One of these is faid to be between 50 and 60 leagues in length.

South Hadley, a township of Massachusetts, Hampthire co. on the E. bank of Connecticut river, 12 miles northerly of Sprin ampton, incorport inhabita South H neticut navigati were be 1795in lengt thefe lo a confid up and (already great va doubtle nature : moft ad pofes, i alfo ope Miller' 25 mile fide of Sou betwee N. Ca habita court-l 25 from ladelp Sou Hamp fouthe rates fouth-W. 0 from 3742; SOI fachu from 1 It wa tains W. (weft 1 So York clude Sagg mean fmall tants flave bour 95 F Sc Peni othe S t he

1 in

veen

s in

offic

ipal

fit-

th a

land

fe-

Ri-

AI-

This

ard-

Spa-

lade

till

s of

rtb-

and

nia,

t of

000

ves,

the

ited

has

ure

abi-

e to

ned

s of

li-

nay

uc-

in-

tch,

ria

ne-

afh-

PW.

rly

ing

ond

by

ha-

ren

the

t of

th,

e is

i in

ffa-

nk

rly

ot

of Springfield, 6 fouth-east of Northampton, and 90 weft of Bofton. It was incorporated in 1753, and contains 759 inhabitants. The locks and canals in South Hadley, on the east fide of Connecticut river, made for the purpole of navigating round the falls in the river, were begun in 1793, and completed in The falls are about three miles 1795. in length; and fince the completion of thefe locks and canals, there has been a confiderable increase of transportation up and down the river. Some mills are already erected on these canals, and a great variety of water works may, and doubtlefs will, foon be erected here, as nature and art have made it one of the most advantageous places for these purpofes, in the United States. Canals are alfo opening by the fame Company, at Miller's Falls, in Montgomery, about 25 miles above thefe, and on the fame fide of the river.

SOUTH Hampton, a co. of Virginia, between James's river and the State of N. Carolina. It contains 12,864 inhabitants, including 5993 flaves. The court-house is 36 miles from Norfolk, 25 from Greenville, and 399 from Philadelphia.

SOUTH Hampton, a township of New-Hampshire, Rockingham county, on the fouthern line of the State, which separates it from Massachusters; 25 miles fouth-west of Portsmouth, and fix N. W. of Newbury Port. It was taken from Hampton, and incorporated in \$742; and contains 448 inhabitants.

SOUTH Hampton, a township of Maffachusetts, Hampshire co. and separated from East Hampton by Pawtucket river. It was incorporated in 1753, and contains 829 inhabitants, about 9 miles S. W. of Northampton, and 109 southwest by west of Boston.

SOUTH Hampton, a township of New-York, Suffolk co. Long Island. It includes Bridgehampton, formerly called Saggaboneck, and Mecoxe; and, by means of Sagg Harbour, carries on a fmall trade. It contains 3408 inhabitants, of whom 431 are electors, and 146 flaves. It is 12 miles from Sagg Harbour, 18 from Suffolk court-house, and 95 E. of New-York.

SOUTH Hampton, two townships of Pennfylvania, the one in Buck's co. the other in that of Franklin.

SOUTH Hampton, a township in the

eaftern part of Nova-Scotia, and in Halifax co. It was formerly called Tatmagouche, and is 35 miles from Onflow.

SOUTH Hempflead, a township of New-York, Queen's co. Long Island, had its name altered in 1796 by the legislature into Hempstead. The inhabitants, 3826 in number, have the privilege of oystering, fishing, and clamming, in the creeks, bays, and harbours of North Hempstead, and they in return have the fame right in S. Hempstead. Of the inhabitants 575 are electors, and 326 flaves.

SOUTH Hero, or Grand Island, in Lake Champlain. See Hero.

SOUTHHOLD, or Soutbold, a townfhip of New-York, Suffolk co. Long-Ifland. It includes Fifher's Ifland, Plumb Ifland, Robin's Ifland, Gull Iflands, and all that part of the manor of St. George on the north fide of Peaconock, extending weftward to the eaft line of Brook Haven. It contains a number of parifhes, and houfes for public worfhip, and 3219 inhabitants; of whom 339 are electors, and 182 flaves. It was fettled in 1640, by the Rev. John Young and his adherents, originally from England, but laft from Salem in Maffachufetts.

SOUTH Huntington, a township in Westmoreland co, Pennsylvania.

SOUTHINGTON, the fouth-wefternmoft township of Hartford co. Connecticut, 20 miles fouth-weft of Hartford, and 22 north of New-Haven.

SOUTH King flon, a township of Rhode-Island, Washington co. on the western fide of Narraganset Bay. It contains 4,131 inhabitants, including 135 flaves.

SOUTH Mountain, in New-Jerfey. See New-Jerfey.

SOUTH Mountains, a part of the Alleghany Mountains, in Pennfylvania. Near this mountain, about 14 miles from the town of Carlifle, a valuable copper mine was difcovered in Sept. 1795.

SOUTH KEY, a fmall island, one of the Bahamas, in the West-Indies. N. lat. 22. 21. W. long. 74. 6.

SOUTH SEA, now more usually diftinguished by the name of *Pacific Otean*, was so named by the Spaniards, after they had passed over the mountains of the Ifthmus of Darien or Panama, from north to south. It might properly be K k 4 named

named the Western Ocean, with regard to America in general; but from the Ifthmus it appeared to them in a fouthern direction. In the beautiful islands in this ocean, the cold of winter is never known; the trees hardly ever lofe their leaves through the constant fucceffion of vegetation, and the trees bear fruit through the greatest part of the year. The heat is always alleviated by alternate breezes, whilft the inhabitants fit under the fhadow of groves, odoriferous, and loaded with abundance. The fky is ferene, the nights beautiful, and the fea, ever offering its inexhauftible ftores of food, and an eafy and pleafing conveyance.

SOUTH THULE, or Southern Thule, in the S. Atlantic Ocean, is the most fouthern land which has at any time been discovered by navigators. S. lat. 59. 34. W. long. 27. 45.

SOUTHWICK, a township of Maffachufetts, in the S. W. part of Hamp-fhire co. 1 io miles S. W. by W. of Bofton, and 12 S. W. of Springfield. It was incorporated in 1770, and contains 841 inhabitants.

SOUTH WEST Point, in Tennefice, is formed by the confluence of Clinch. with Tenneffee river, where a blockhouse is crected.

SOUTH WASHINGTON, a town of N. Carolina, on the N. E. branch of Cape Fear river, which is navigable thus far for boats. It is 23 miles from Crofs Roads near Duplin court-houfe, and 36 from Wilmington.

Souroux, an Indian village in Louifiana, on the W. fide of Miffifippi river, opposite to the Nine Mile Rapids, 22 miles below Wiespincan river, and 28 above Riviere a la Roche. N. lat. 41. 50.

Sow and PIGS, a number of large rocks lying off the fouth-west end of Catahunk Island, one of the Elizabeth Islands, on the coaft of Maffachufetts.

SPAIN, New. See Mexico. SPANIARDS Bay, on the east coast of Cape Breton Ifland, is round the point of the fouth entrance into Port Dauphin, to the fouthward of which is Cape Charbon. Its mouth is narrow, but it is wider within till it branches into two arms, both of which are navigable 3 leagues, and afford fecure harbouring. N. lat. 46. 20. W. long. 58. 29.

SPANISH AMERICA' contains im-

SPA

menfe provinces, most of which are very fertile. 1. In North-America, Louifiana, California, Old Mexico or New Spain, New Mexico, both the Floridas. 2. In the West-Indies, the island of Cuba, Porto Rico, Trinidad, Margaretta, Tortuga, &c. 3. In South-America, Terra Firma, Peru, Chili, Tucuman, Paraguay, and Patagonia. These extenfive countries are deferibed under their proper heads. All the exports of Spain, most articles of which no other European country can fupply, are effimated at only 80,000,000 livres, or 3,333,9331. fterl. The most important trade of Spain is that which it carries on with its American provinces. The chief imports from theic extensive countries confift of gold, filver, precious ftones, pearls, cotton, cocoa, cochineal, red-wood, fkins, rice, medicinal herbs and bark's, as faffafras, Peruvian bark, &c. Vanilla, Vicunna wool, fugar, and tobacco. In 1784, the total amount of the value of Spanish goods exported to America, was 195,000,000 reales de vellon; foreign commodities, 238,000,000 r. d. v. The imports from America were valued at 900,000,000 r.d.v. in gold, filver, and precious ftones; and upwards of 300,000,000 in goods. In the Gazeta de Madrid, 1767, (Feb. 20) it was flated, that the exports to America (the Indies) from the following 12 harbours, Cadiz, Corunna, Malaga, See ville, St. Lucar, Santander, Canaries, Alicante, Barcelona, Tortofa, Gipon, St. Sebastian, amounted, in 1785, to 767,249,787 r. d. v. the duties paid on these exports amounted to 28,543,702 r. d. v. The imports, both in goods and money, from America and the W. India islands, amounted in the fame year to 1,266,071,067 r. d. v. and the duties to 65,472,195 r.d. v. The profits of the merchants from the whole American trade was valued at 5,000,000 dollars.

SPANISH Creek, is at the head of St. Mary's river in Florida.

SPANISH Main, that part of the coaft of America, which extends from the Mofquito fhore, along the northern coaft of Darlen, Carthagena, and Venezucla, to the Leeward Ifles.

SPANISH' River, a river and fettlement in Cape Breton Ifland, and the prefent feat of government.

SPANISHTOWN, or St. Jago de la Ve-

ga, in t capital fituated about (tains al 5000 in of colo governo is acco palace. the cou judicial la Vega SPAI flore o which I SPAI Suffex a SPAR ney diff Six, S. habitan and 86 tatives, legiflat miles f ville, a SPE. Newfor limit o SPE of the N. par thips called trade i It is ir Fort a S. and half th long. SPE Worce from 1753, and li Worce field, a SPE of Che SPI fide of the N and re and a La Tr SPI called the W

are

ou-

New

das, Cu-

itta,

nan,

ex-

nder

s of

ther

efti-

Tics

The

nun-

ious

eal,

rbs

irk.

and

t of

to l

vel-

000

rica . in

and

In

20)

me-

12

Sea

ies,

on.

to

on

702

ods

W.

me

the

ro-

ole

200

St.

aft

the

ern

/e-

le-

the

Ve-

a,

tant

ga, in the county of Middlefex, is the capital of the ifland of Jamaica. It is fituated on the banks of the river Cobre, about 6 miles from the fea, and contains about 5 or 600 houfes, and about 5000 inhabitants, including free people of colour. It is the refidence of the governor or commander in chief, who is accommodated with ²a magnificent palace. Here the legiflature fits, and the court of chancery and the fupreme judicial courts are held. See Jago de la Vega.

SPARHAWK's Point, on the northern flore of Piscataqua river, abreast of which ships can anchor in 9 fathoms.

SPARTA, a post-town of New-Jersey, Suffex co. 117 miles from Philadelphia.

SPARTANBURGH, a county of Pinckney diffrict, formerly in that of Ninety-Six, S. Carolina, containing 8800 inhabitants, of whom 7907 are whites, and 866 flaves. It fends two reprefentatives, and one fenator, to the State legiflature. The court-house is 30 miles from Pinckney, 35 from Greenville, and 746 from Philadelphia.

SPEAR Cape, on the eaft coaft of Newfoundland Island, and the fouth-east limit of St. John's Bay.

SPEIGHT'S TOWN, on the W. fhore of the island of Barbadoes, towards the N. part; formerly much reforted to by fhips from Brittol, and from thence called Little Brittol; but most of the trade is now removed to Bridgetown. It is in St. Peter's parifh, having Sandy Fort and Margaret's Fort about a mile S. and Haywood's Fort on the N. at half the diftance. N. lat. 10. 9. W. long. 57. 21.

SPENCER, a flourishing township in Worcester county, Massachusetts, taken from Leicester, and incorporated in 1753, and contains 1322 inhabitants, and lies 11 miles fouth-westward of Worcester, on the post-road to Springfield, and 58 S. W. of Boston.

SPESUTIE, a finall ifland at the head of Chefapeak Bay.

SPIRITU SANTO, a town on the S. fide of the island of Cuba, oppolite to the N. W. part of the cluster of isles and rocks called Jardin de la Reyna, and about 45 miles north-westerly of La Trinidad.

SPIRITU SANTO, or Tampay Bay, called also Hillsborough Bay, lies on the W. coast of the peninsula of EastFlorida; has a number of fhoals and keys at its mouth, and is 9 leagues N. N. W. $\frac{1}{2}$ W. of Charlotte Harbour, and 56 S. E. by S. $\frac{1}{2}$ E. of the bay of Apalache. N. lat. 27. 36. W. long. 82. 54.

SPIRITU SANTO, a town of Brazil, in S. America. It is fituated on the feacoaft in a very fertile country, and has a finall caftle and harbour. S. lat. 20. 10. W. long. 41.

SPIRITU SANTO, a lake towards the extremity of the peninfula of E. Florida; fouthward from the chain of lakes which communicate with St. John's river.

SPLIT ROCK, a rocky point which projects into Lake Champlain, on the W. fide, about 56 miles N. of Skeenfborough, bears this name. The lake is narrow, and no where exceeding two miles from Skeenfborough to this rock, but here it fuddenly widens to 5 or 6 miles, and the waters become pure and clear.

SPOTSWOOD, a finall town of New-Jerfey, Middlefex co. near the W. fide of South river, which empties into the Rariton in a S. E. direction. The fituation is good for extensive manufactories, and there is already a paper-mill here. It is on the Amboy flage-road, 9 miles fouth-east of Brunswick, and 10 weft by fouth of Middleton Point.

SPOTSYLVANIA, a county of Virginia, bounded N. by Stafford, and E. by Caroline county. It contains 11,252 inhabitants, of whom 5933 are flaves.

SPRINGFIELD, a township of Vermont, Windfor co. on the W. side of Connecticut river, opposite to Charleston, in New-Hampshire. It has Weathersfield N. and Rockingham on the S. and contains 1097 inhabitants.

SPRINGFIELD, a polt-town of Maffachufetts, Hampfhire co. on the eaft fide of Connecticut river; twenty miles fouth by east of Northampton, 97 weftfouth-weft of Bolton, 28 north of Hartford, and 250 north-east of Philadelphia. The township of Springfield was incorporated in 1635 or 1645. It contains 1 574 inhabitants, a Congregational church, a court-houfe, and a number of dwelling-houfes, many of which are both commodious and elegant. The town lies chiefly on one long fpacious ftreet, which runs parallel with the river. A ftream from the hills at the eaftward of the town, falls into this itreet

threet, and forms two branches, which take their courfe in oppolite directions, one of them running northerly and the other foutherly along the eaftern fide of the fireet, and afford the inhabitants, frombone end to the other, an eafly fupply of water for dometic ufes. Here a confiderable inland trade is carried on ; and there is alfo a paper-mill. The fuperintendant and fome of the principal workmen now in the armoury here, were originally manufacturers in Bridgewater, which is famous for its iron-works.

SPRINGFIELD, a township of New-York, Otsego co. 12 miles N. of Otsego, and between it and the lake of that name. It is 61 miles W. of Albany, has a good foil, and increases in population.

SPRINGFIELD, 2 township of New-Jersey, Burlington co. of a good soil and famed for excellent cheese, some farmers make 10,000lbs. in a season. The inhabitants are principally Quakers, who have 3 meeting-houses. The chief place of the township, where business is transacted, is a village called Job's-town, so miles from Burlington, and 18 from Trenton. In this township is a hill 3 miles in length, called Mount Pisgah, which furnishes stone for building. Here is also a grammar school.

SPRINCFIELD, a townfhip in Effex county, New Jerfey, on Rahway river, which furnithes fine mill-feats; 8 or 10 miles N. W. of Elizabeth Town. Turf for firing is found here.

SPRINGFIELD, the name of 4 townfhips of Pennfylvania, viz. in Buck's, Fayette, Delaware, and Montgomery counties.

SPRUCE Creek, urges its winding courfe through the marfhes, from the mouth of Pitcataqua river, 5 or 6 miles up into Kittery, in York co. Diffrict of Maine.

SPURWING, a river of the District of Maine, which runs through Scarborough, to the westward of Cape Elizabeth, and is navigable a few miles for vessels of 100 tons.

SQUAM, a lake, part of which is in the township of Holderness, in Graston co. New-Hampshire; but the one half of it is in Strafford co. It is about 5 miles long, and 4 broad.

SQUAM, a fhort river of New-Hampfhire, the outlet of the above lake, which runs a fouth-weftern courfe, and

jeins the Pemigewaffet at the town of New-Chefter, and 10 miles above the mouth of the Winnipifeogee branch.

SQUAM Beach, on the fea-coaft of New-Jerfey, between Barnegat Inlet and Cranbury New Inlet,

SQUAM Harbour, on the N. E. fide of Cape Ann, Maffachusetts. When a veffel at anchor off Newbury-Port Bar, parts a cable and loses an anchor with the wind at N. E. or E. N. E. if she can carry double-reefed fails, she may run S. S. E. 5 leagues, which course, if made good, will carry her a little to the eastward of Squam Bay. Squam (*Pidgeon Hill*) lies in lat. 42.40. N. and long. 70.36.

SQUARE HANDKERCHIEF, (Mouchoir Quarré) an island of fome extent in the Weft-Indies, which lies between lat. 21. 5. and 21. 24. N. and between long. 70. 19. and 70. 49. W.

SQUEAUGHETA Creek, in N. York, a N. head water of Alleghany river. Its mouth is 19 miles N. W. of the Ichua Town.

STAATESBURGH, in N. York State, lies on the east fide of Hudson's river, between Rhynbeck and Poughkeepsie; about 31 miles south of Hudson, and 80 northward of New-York city.

STAEBROECK, a town of Dutch Guiana, in South-America, on the east fide of Demarara river, a mile and a half above the post which commands its entrance. It is the feat of government and the depository of the records. The flation for the shipping extends from the fort to about two miles above the town. They anchor in a line from two to four abreaft.

STAFFORD, a county of Virginia, bounded north by Prince William co. and east by the Patowmac. It contains 9,588 inhabitants, including 4,036 flaves.

STAFFORD, a township of Connecticut, in Tolland co. on the fouth line of Massachusetts, 12 or 15 miles north-east of Tolland. In this town is a furnace for casting hollow ware, and a medicinal spring, which is the refort of valetudinarians.

STAFFORD, New, a township of New-Jersey, in Monmouth co. and adjoining Dover on the south-west. It consists chiefly of pine barren land, and contains 883 inhabitants.

STAGE Island, in the District of Maine,

lies

lies fout iflands, confifting improver for being England not now STAM in Benn nington 272 inha land. STAM ticut, Fa called N Long-If Congreg

and abo

It is 10

44 fout

E. of N

Philadel merly c: tled in : STAN in Ulfte and inc habitan STAN of Main land co rivers. and cor N. W. ton. STAI Dutche and inc STAL Kentuc about 1

and 52 It conta and abo STA New-Y

of Ron

waters

tion wi

ville, 4

ftreet, : the Un The B tempt 1 STA

Maine, nebeck STA Addife . fide ien a Bar, with f she may fe, if tle to Juam

Mouxtent ween ween

. and

lork, river. f the

State, river, epfie ; , and

Guift fide a half s ennment The from ve the m two

ginia, m co. ntains 4,036

onnecline of th-eaft urnace dicinal letudi-

Newoining confifts ontains

Maine, lies STA

lies fouth of Parker's and Arrowfike | Ferrifburg. It contains 40 inhabiiflands, on the N. fide of Small Point, confifting of 8 acres not capable of much improvement; and is only remarkable for being the first land inhabited in New England, by a civilized people. It is not now inhabited.

STAMFORD, a township of Vermont, in Bennington co. it corners on Bennington to the fouth-eaft, and contains 272 inhabitants, and has good intervale land.

STAMFORD, a post-town of Connecticut, Fairfield county, on a small ftream called Mill river, which empties into Long-Ifland Sound. It contains a Congregational and Episcopal church, and about 45 compact dwelling-houfes. It is 10 miles fouth weft of Norwalk ; 44 fouth-west of New-Haven; 44 N. E. of New-York; and 139 N. E. of Philadelphia. The township was formerly called Rippowams, and was fettled in 1641.

STAMFORD, a township of N. York, in Ulfter co. taken from Woodftock, and incorporated in 1792. Of its inhabitants, 127 are electors.

STANDISH, a township of the District of Maine, on the weft line of Cumberland co. between Prefumfcut and Saco rivers. It was incorporated in 1785, and contains 716 inhabitants; 18 miles N. W. of Portland, and 163 N. of Bofton.

STANFORD, a township of N. York, Dutchels co. taken from Washington, and incorporated in 1793.

STANFORD, the capital of Lincoln co. Kentucky; fituated on a fertile plain, about 10 miles fouth-fouth-east of Danville, 40 fouth by welt of Lexington, and 52 fouth-fouth-east of Frankfort. It contains a ftone court houfe, a gaol, and about 40 houfes.

STANWIX, Old Fort, in the State of New-York, is fituated in the township of Rome, at the head of the navigable waters of Mohawk river. Its foundation was laid in 1759, by Gen. Broadftreet, and built upon by the troops of the United States, during the late war. The British made an unfuccessful attempt to take it in 1777.

STARKS, a plantation in Lincoln co. Maine, fituated on the W, fide of Kennebeck river, near Norridgewalk.

STARKSBOROUGH, a township in

STE tants.

STATEN Island, lies 9 miles S. W. of the city of New York, and conftitutes Richmond county. The island is about 18 miles in length, and at a medium 6 or 7 in breadth, and contains 3835 inhabitants. On the fouth fide is a confiderable tract of level good land; but the island in general is rough, and the hills high. Richmond is the only town of any note, and that is an inconfidera-ble place. The inhabitants are chiefly descendants of the Dutch and French : and are noted for their holpitality to ftrangers, and love of their native fpot.

STATEN Land, an ifland at the extremity of S. America, about 30 miles in length and 12 in breadth. It lies to the eaftward of the E. point of Terra del Fuego, and from which it is feparated by Strait le Maire. The centre of the island is in lat. about 54. 30. S. and long. 64. 30. W.

STATESBURG, a post-town of S. Carolina, and the capital of Clermont co. fituated on the E. fide of Beech Creek, which unites with Shanks Creek, and empties into the Wateree, a few miles below the town. It contains 10 or 12 houses, a court-house and gaol. It is 20 miles S. by E. of Camden, 100 N. by W. of Charletton, and 663 S. W. of Philadelphia.

STAUNTON, a post-town of Virginia, and the capital of Augusta co. It is fituated on the S. E. fide of Middle river, a water of Patowmack, a little to the N. of Maddifon's Cave. It contains about 160 houfes, mostly built of ftone, a court-houfe and gaol. It is 93 miles from the Sweet Springs, 100 miles S. W. by S. of Winchefter, 126 W.N.W. of Richmond, and 287 from Philadelphia.

STAUNTON, a small river of Virginia, which rifes on the W. fide of the Blue Ridge, and breaks through that mountain in lat. about 37. 8. N. and uniting with Dan river forms the Roanoke, above the Occoneachy Iflands, about 100 miles from its fource. It is also called Smith's river.

STAUSEE, Fort, just above the Falis of Niagara, and 8 miles above Queen's Town.

STEADMAN's Creek, in the State of Addifon co. Vermont, 12 miles E, of New-York. The main fork of this creek

Fort Schloffer.

524

STEEP ROCKS, a curious ledge of perpendicular shelly rocks, which form the W. bank of Hudson's river, with fome interruptions, for 12 or 13 miles from the Tappan Sea, to within 11 miles of New-York city. Some of these ledges are from 150 to 200 feet high. As you pais down the river from the Tappan Sea, by these rocks, the profpect on every fide is enchanting. On the N. of the Tappan Sea, a fine broad bay opens to view, fkirted with high bills; on the S. the river lies under the eye as far as it diftinguishes objects; on the W. are the Steep Rocks, before described; and on the E. a fine cultiwated country.

STEPHENS, a cape, S. W. of Cape Denbigh, on the N. W. coaft of North-America, and is at the S. E. part of Norton Sound. Stuart's Ifland is oppofite to it. N. lat. 63. 33. W. long. 162. 19. Between this and Shoal Nefs is thoal water.

STEPHENS, a fort river of Vermont, which empties into Connecticut river, from the N. W. in the town of Barnet.

STEPHENS, St. a parifh of Charlefton district, S. Carolina; containing 2733 inhabitants, of whom 226 are whites.

STERLING, a plantation in Lincoln co. Diffrict of Maine; N. W. of Hallowell, and at no great diffance. It contains 166 inhabitants.

STERLING, in Worcefter co. Maffachufetts, was formely a parish of Lancafter, called Chockfet, incorporated in 1781; fituated 12 miles N. E. of Worcefter, and 46 W. of Bolton, and contains 1428 inhabitants. Near the neck of land which divides Waushacum Ponds, on the S. fide, was formerly an, Indian fort, of which the veftiges are nearly difappeared. On this fpot was the palace and royal feat of Sholan, fachem of the Nafhaways, proprietor of Nafhawogg.

STEUBEN, a small fort in the N.-W. Territory, fituated at the Rapids of the Ohio, a fhort diftance above Clarkfville.

STEUBEN, a new county of New-York, taken from that of Ontario; being that part of Ontario county, bounded by the Pennfylvania line on the S. by the N. bounds of the fix range of

creek empties into Niagara river, above | townships on the N. by the pre-emption line on the E. and by the Indian line on the W.

> STEUBEN, a township of N. York, in Herkemer county; taken from Whiteftown, and incorporated in 1792. In 1796 the towns of Floyd and Rome were taken off of this township. Of its inhabitants 417 are electors. The N. western branch of Mohawk river rifes here; and the centre of the town is about 12 miles N. E. of Fort Schuyler, and 32 N. W. of the mouth of Canada Creek.

> STEVENS, a fhort navigable river of the Diftrict of Maine. It rifes within a mile of Merry Meeting Bay, with which it is connected by a canal lately opened. See Georgetown.

> STEVENSBURG, a post-town of Virginia, fituated on the road from Philadelphia to Staunton. It contains about 60 houfes; the inhabitants are mostly of Dutch extraction. It is 10 miles N. by E. of Strafburg, 87 N. E. by N. of Staunton, 45 S. W. by S. of Williamfport, and 200 S. W. of Philadelphia.

> STEVENTOWN, W. Chefter county, New York is bounded wefterly by York Town, and northerly by Dutchefs co. It contains 1297 inhabitants, of whom 178 are electors.

> STEPHENTOWN, a township of good land in New York, in Renffelaer co. between Lebanon and Scoodack. It is about 14 miles fquare, and lies 20 miles E. of Albany. Of its inhabitants 624 are electors. The timber on the low land is pine, hemlock, beech, birch, afh, maple. On the hills, pine, hemlock, black and white oak, walnut and poplar.

> STEWART'S Islands, in the South Pacific Ocean, a clufter of five islands discovered by Capt. Hunter, in 1791; and fo named in honour of Admiral Keith Stewart, S. lat. 8. 26. W. long. 163.18.

> STEY Point, on the Labrador coaft, and N. Atlantic Ocean. N. lat. 58. W. long. 61, 40.

STILL WATER, a township of New York, Albany co. bounded eafterly by Cambridge, and foutherly by Schachtekoke and Anthony's Kill. It contains 3071 inhabitants; of whom 459 are electors, and 61 flaves. The village of Stillwater; in this township, is fituated on the W. bank of Hudson's river; 12 miles

STI

miles from Cohoez Bridge, 12 from Saratoga, 25 N. of Albany, and 12 from Ballitown Springs. A canal is begun at this place to lead the water of the Hudion to the mouth of the Mohawk, 14 miles below.

STINKING *Iflands*, on the eaft coaft of Newfoundland Ifland. N. lat. 49. 28. weft long. 52. 50.

STISSIK Mountain, lies between the State of Connecticut and Hudfon's river, and near it the Mahikander Indians formerly refided.

STOCKBRIDGE, a township in Windfor co. Vermont, on White river, and contains 100 inhabitants.

STOCKBRIDGE, a post-town of Maffachusetts, Berkshire co. 44 miles W. by N. of Springfield, 141 west of Boston, 249 north-east of Philadelphia, and 25 miles east-by-south of Kinderhook, in New-York. The township is the chief of the county; was incorporated in 1739, and contains 1,336 inhabitants.

STOCEBRIDGE, New, a tract of land 6 miles fquare, lying in the fouth-east part of the Oneida Refervation, in the State of New-York, inhabited by the Indians, 300 in number, who, fome years fince, removed from Stockbridge, Maffachufetts, and from this circumstance are This called the Stockbridge Indians. tract was given to these Indians by the Oneidas, as an inducement to them to fettle in their neighbourhood; and is 7 miles fouth-east of Kahnonwolohale, the principal village of the Oneidas. These Indians are under the paftoral care of a missionary, the Rev. Mr. Sarjeant, whole pious labours have been attended with confiderable fuccefs. They are generally industrious, efpecially the women, and employ themfelves in agriculture, and breeding of cattle and fwine. Their farms are generally inclosed with pretty good fences, and under tolerable cultivation. In the fall of 1796; almost every family fowed wheat; and there was a fingle inftance this year, of one of the Indian women, named *Effber*, who wove 16 yards of woollen cloth; who is here mentioned as an example of industry, and as having led the way to improvements of this kind. There is little doubt but her example will be followed by others. Their dividend of monies from the United States, amounting to about 300 dollars, has hitherto 525

been expended in creeting a faw-mill, and fupporting an English school.

STOCK Creek, a branch of Pelefon river. See Walbington County, Virginia. STOCKPORT, a village in Northamp-

ton co. Pennfylvania, on the weft fide of the Popaxtunk branch of Delaware river. From this place is a portage of about 18 miles to Harmony, on the east branch of the river Sufquehannah.

STOBDARD, a township of New-Hampshire, Cheshire co. distant from Portsmouth 99 miles, and about 15 or 18 miles east of Walpole on Connecticut river. It was incorporated in 1774, and contains 701 inhabitants.

STODHART Bay, near the north-weft point of the ifland of Jamaica, is to the eaft of Sandy Bay, and between it and Lucea harbour.

STOKES, a county of Salifbury diftrict, North-Carolina; bounded eaft by Rockingham, and welt by Surry, and contains 3,528 inhabitants, including 787 flaves. Iron ore is found here in confiderable quantities, and works have been erected on Iron Creek, which manufacture confiderable quantities. Chief town, Germantown.

STOKES, the chief town of Montgomery co. N. Carolina, near Yadkin river. It contains a court house, gaol, and about 20 houses.

STONE Arabia, a village and fine tract of country fo called, in Montgomery co. New-York, on the north fide of Mohawk river, between 50 and 60 miles weftward of Albany. This fettlement was begun by the Germans in 1709. The land from the river rifes on a beautiful and gradual afcent for four miles, and the principal fettlement is on a wide foreading hill, at that diftance from the river. The foil is excellent, and the people induftrious and thriving. It fuffered much from the Indians in the late war, particularly in 1780.

STONEHAM, a township of Massachufetts, in Middlefex co. which was incorporated in 1725, and contains 381 inhabitants. It is about 10 miles north of Boston.

STONE Indians, inhabit fouth of Fire Fort, on Affenebayne river, North America.

STONE Mountain, between the States of Tenneffee and Virginia. The Virginia line interfects it in lat. 36. 30. N. from thence to the place where Watauga rivee

line

from

792.

kome of its e N. rifes n is ryler, inada

rer of hin a which ened.

'hilaibout noftly is N.

Vir-

N. of iamíia.

unty, y by chefs

is, of

good r co. It is miles

block, pop-

\$ 624

flands 791 ; miral long.

South

coaft,

New

ly by

ichte-

ntains

9 are

age of

uated

r; 13

miles

\$26

river breaks through it. See Tenneffee.

STONE Island, on the eaft coaft of Newfoundland, is near Cape Broyle, and is one of the three islands which lie off Caplin Bay.

STONES, is a boatable water of Tenneffee, which runs north-wefterly into Cumberland river, fix miles north-eaft of Nafhville.

STONES Fort Gut, on the fouth-weft fide of the ifland of St. Chriftopher's; eaftward of Old Road Bay, and between that and Bloody Point. There is a fort on a point of land, on the weft fide.

STONEY Hill, in Baltimore co. Maryland, is 5 or 6 miles north-wefterly of Whetstone Fort, at the mouth of Baltimore harbour, and 2 miles south-east of Hooks-Town.

STONEY Point, in Orange co. New-York, a finall peninfula, projecting in a confiderable bluff from the weft bank of Hudfon's river into Haverftraw bay; about 40 miles north of New-York city, juft at the fouthern entrance of the high lands. In the capture of this fortrefs, the brave Gen. Wayne diffinguifhed himfelf.

STONEY Mountains, in the northwelf part of N. America, extend from the fouthward to the northward, and in a north-welfern direction, from lat. 48. to 68. north. The northern part of this range is called the Mountains of Bright Stones.

STONEY River, called by the French Bayouk Pierre, empties into the Miffifippi 4 miles from Petit Goufre, and 10 from Louifa Chitto. From the mouth of what is called the fork of this river, is computed to be 21 miles. In this diffance there are feveral quarries of ftone, and the land has a clayey foil, with gravel on the furface of the ground. On the north fide of this river the land in general, is low and rich; that on the fouth fide is much higher, but broken into hills and vales; but here the low lands are not often overflowed: both fides are fhaded with a variety of uleful timber.

STONINGTON, a post-town and port in New-London co. Connecticut; 14 miles east by fouth of New-London city, and 251 N. E. of Philadelphia. The harbour fets up from the Sound, oppofite to Fisher's Island. The town is feparated from Rhode-Island by the E.

line of the State; and was fettled in 1658. Here are 6 places of public worthip; and the number of inhabitants, in 1790, was 5,648.

STONO Inlet, on the coaft of South-Carolina, is to the fouthward of the channel of Charlefton, at the N. E. corner of John's Ifland, which is bounded by Stono river on the weftward. It is 6 miles from the S. channel of Charlefton, and from this inlet to that of North Edifto, the course is fouth-weft by weft $\frac{1}{2}$ weft, diftant 11 miles.

STORM Cape, in the firaits of Northumberland, is the northern limit of the mouth of Bay Verte, and forms the fouth-east corner of the province of New-Brunswick.

STOUENUCK, a township in Cumberland co. New-Jersey.

STOUGHTON, called by the Indians, Pakemitt, or Pontipog, or Punkapaog, (that is taken from a spring that ariseth out of red earth) a township in Nortolk co. Maffachusetts, incorporated in 1726. It is bounded E. by Braintree, W. by Sharon, and is 15 miles fouthwardly of Bolton. It contains 16,000 acres of land, and 1,994 inhabitants. Iron ore is found here of an excellent quality, and there is a rolling and flitting mill, which manufacture confiderable quantities of steel and iron. Great quantities of charcoal, baskets and brooms, are fent from thence to Bofton. Early in the war a large quantity of gun-powder, of an excellent quality, was made in this town, for the American army, from falt-petre, the produce of the towns in its vicinity.

STOW, a township of Massachusetts, Middlefex co. incorporated in 1683, and contains 801 inhabitants, and is 25 miles N. W. of Boston.

STOW, a township of Vermont, Chittenden co. about 25 or 30 miles east of Burlington.

STOWE Creek, one of the feven townfhips into which Cumberland co. in New-Jerfey, is divided.

STRABANE, two townships of Pennfylvania; the one in York co. the other in that of Washington.

STRAFFORD, a township in Orange co. Vermont, west of Thetford, adjoining, having 845 inhabitants.

STRAFFORD, a county of New-Hampfhire, bounded N. and N. W. by Grafton ; S. E. by Rockingham, and eaft by the the Diftr townfhip and has the Pife other ftr fides the pee. It of whom Dover a STRA rate the the N.] and lies 35. E. STRA Shenand of the n and con theran houfes. Staunto

> STRA Pennfyl and in cultivan 60 houf brick. Strafbut through Lancatt STRA

chefter,

delphia.

tucky, i STR, co. Ne eaft bar Cockbu berland Amono corpora inhabiti over.

STR.

Connec fide of 2 place neat an miles fo E. of 1 ladelph the Cup in 163 chufett STR STR fhip of

Rockin 1693, the Diffrict of Maine. It contains 25 | lies on the road from Portfmouth to townfhips, almost wholly agricultural, and has no fea port. The branches of the Pifcataqua and Merrimack, and other ftreams water this county; befides the lakes Winnipifeogee and Offipee. It contains 23,601 inhabitants, of whom 22 are flaves. Chief towns, Dover and Durham.

STRAITS of Beering or Bhering; feparate the N. W. part of N. America from the N. E. coaft of Afia. Beering's Ifland lies in lat. 55. N. and long. 164. 35. E.

STRASBURG, a poft town of Virginia, Shenandoah co. on the north-weft branch of the north fork of Shenandoah river, and contains a handfome German Lutheran church, and about 60 or 70 houfes. It is 77 miles N. E. by N. of Staunton, 18 fouth-fouth weft of Winchefter, and 210 fouth-weft of Philadelphia.

STRASBURG, a town of Lancafter co. Pennfylvania; fituated on an eminence, and in the centre of a fertile and well cultivated country, and contains about 60 houses, feveral of which are built of brick. It is about 7 miles west from Strafburg Gap, where the road leads through the mountains, 8 miles east of Lancaster, and 58 welt of Philadelphia.

STRASBURG, a fettlement in Kentucky, near the Bullit Lick.

STRATFORD, a township in Grafton co. New Hampfhire; fituated on the east bank of Connecticut river, between Cockburn township N. and Northumberland on the mouth of the Upper Amonooluck on the fouth. It was incorporated in 1773, and contains 146 inhabitants. It is 58 miles above Hanover.

STRATFORD, a pleafant post-town of Connecticut, in Fairfield co. on the W. fide of Stratford river, which contains 2 places for public worthip, and feveral neat and commodious houles. It is 14 miles fouth-weft of New-Haven, 20 N. E. of Norwalk, and 169 N. E. of Philadelphia. The township of Stratford, the Cupheag of the Indians, was fettled in 1638, principally from Maffachuchufetts.

STRATFORD River. See Houfatonic. STRATHAM or Streatham, a townthip of New-Hampshire; intuated in Rockingham county. Incorporated in 1693, and contains 882 inhabitants. It

Exeter; 12 miles west of the former, and 4 eaft of the latter.

STRATTON, a township of Vermont, Windham co. about 15 miles N. E. of Bennington, having 95 inhabitants.

STRAWBERRY Gap, a pais in the mountains on the road from Philadelphia to Lancaster 42 miles west of the former, and 16 fouth-east of the latter,

STRAWBERRY River, falls into Lake Ontario; and is thus named from the great quantity of large fruit of that name growing on its banks.

STROUDS, a ftage on the new road from Lexington in Kentucky, to Virginia. It is 17 miles N. E. of Lexington, and 9 from Holden.

STROUDWATER. See Cafco Bay. STUART'S Ifland, on the N. W. coaft of N. America, is about 6 or 7 leagues in circuit, about 17 leagues from Cape Denbigh on the continent. N. lat. 63. 35.

STUART TOWN, in Grafton co. New-Hampfhire, is fituated on the caftern bank of Connecticut river, between Colebrook on the fouth, and a tract of 2,000 acres on the north, belonging to Dartmouth college.

STUMSTOWN, a fmall town of Pennfylvania, Dauphin co. on a branch of Little Swatara. It contains about ao houses, and a German Lutheran and Calvanist church united. It is 24 miles E. N. E. of Harrisburg, and 89 N. W. by W. of Philadelphia.

STURBRIDGE, a township in the S. W. corner of Worcefter co. Maffachufetts, containing 28,929 acres, divided from Woodstock and Union on the fouth, in Connecticut by the State line, and on the north by Brookfield. It was incorporated in 1738, and contains 1704 inhabitants. The butter and cheefe made here have obtained high credit in the markets. It is 70 miles fouth-weft by weft of Bofton, and 22 fouth-weft of Worcefter.

STURGEON Creek. See Kittery.

STYX, a fmall branch of Patowmac river where it is called Cohongoronto. It rifes in the Laurel Thickets, in the Alleghany mountains; runs north, and empties opposite to Laurel Creek.

SUCCESS, a bay also called Good Suc_ cefs, on Terra del Fuego, or the weftern thore of Strait le Maire. S. lat. 54. 50, W. long, 65, 25, Cape Success, on

the

i in blic ints,

uth-

the

COT-"

nded lt is rleforth weft orth-

the e of lum-

f the

ians, baog,

rifeth rtolk 726.

by ly of

es of n ore ality, mill,

juanlantis, are

ly in wder, de in

from ns in

fetts, 1683, is 25

Chitaft of

towno. in

Penn-

other

range djoin-

lamp-

Graf-

aft by

the

the point of this bay, lies in lat. 55. 1. S. and long. 65. 27. W.

SUCC 255, a township of New-Hampshire, in Grafton co. N. E. of the White Mountains on the east line of the State, incorporated in 1773.

SUCK Creek empties into Tenneffee river from the fouth-fouth-eaft, at the Suck, or Whirl, were the river is contracted to the breadth of 70 yards. It is a few miles north from the Georgia north-line. See Tenneffee, and Shallow Ford.

SUCKLING *Cape*, on the N. W. part of N. America; off which, and to the N. E. end of Kaye's Island, is a muddy bottom with from 43 to 27 fathoms water. The fouth welt point of Kaye's Island is in lat. 59.49. N. and long. 143. 2. W.

SUDBURY, a county of New Brunfwick, on the W. fide of St. John's river, towards its mouth.

SUDBURY, a township of Vermont, in Rutland co. having Orwell on the west. It contains 258 inhabitants.

SUDBURY, Eaf, a township of Maffacturetts, Middlefex co. on the postroad 19 miles west of Boston. It was incorporated in 1780, and contains 801 inhabitants.

SUDBURY, Weft, or Sudbury, a townthip weft of Eaft-Sudbury, and 25 miles weft of Bofton. It was incorporated in 1639, and contains 1,290 inhabitants.

SUDBURY Canada, in York co. Diftrict of Maine, is fituated on the fouth fide of Androscoggin river, and southward of Andover. In 1796, it was crected into a township called Bethel, and has two parishes.

SUE, La, a powerful nation of Indians inhabiting weftward of Lake Superior, and the Miffifippi. Warriors io,000.

SUER, Fort le, in Louifiana, is on the weftern bank of the Miffifippi, and eafterly of Fort L'Huillier, on St. Peter's river.

SUFFIELD, a pleafant post town of Connecticut, Hartford county, having a handfome church and fome respectable dwelling-houses. It is on the west bank of Connecticut river, on the great post-road from Boston to New-York, to miles south of Springfield, 17 N. of Hartford, and 232 N. E. of Philadelphia. This township was purchased of two Indian fachems for £30, and in 1670, was granted to Major John Pyncheon, by the affembly of Maffachufetts.

SUFFOLK, a county of Mafiachuletts, fo named from that in England, in which governor Winthrop lived, before he emigrated to America. It contained in 1790, 23 townfhips, 6,335 houfes, 13,038 families, 44,875 inhabitants. In 1793, the county was divided; and now the new county, Norfolk, comprehends all the towns except Bofton, Chelfea, Hull, and Hingham. Suffolk was conftituted a county, May 10, 1643. See Maffachufetts and Bofton.

SUFFOLK, aco. of N. York, L. Ifland, is about 100 miles long, and 10 broad, & comprehends all that part of the State bounded eafterly and foutherly by the Atlantic Ocean, northerly by the Sound, and wefterly by Lloyd's Neck, or Queen's Village, Cold Spring harbour, and the east bounds of the township of Oyfter Bay; the line continued fouth to the Atlantic Ocean, including the Ifle of Wight, now called Gardner's Ifland, Shelter Ifland, Plumb Iflands, Robin's Island, and the Gull Islands. Fisher's Island also belongs to it. It contains 16,440 inhabitants, of whom 1,098 are flaves. There are 9 townfhips, and 2,609 of the inhabitants are electors. Suffolk county court-houfe, is 15 miles from Southampton, 27 from Sagg Harbour, and 80 from New-York city.

SUPFOLK, a post-town of Virginia, in Nanfemond co. on the east fide of the river Nanfemond. It contains a court-house, gaol, and about 40 houses. The river is thus far navigable for veffels of 250 tons. It is 28 miles west by fouth of Portsmouth, 83 E. S. E. of Petersburgh, 110 south-east of Richmond, and 386 from Philadelphia.

SUFFRAGE, a townfhip of N. York, fituated in Otfego co. on the north fide of Sufquehannah river; taken from Unadilla, and incorporated in 1796.

SUGAR Creek, or Caefar's Creek, a confiderable branch of Little Miami river.

SUGAR Hill, a ragged eminence, the top of which overlooks and commands the whole works of Ticonderoga, where the waters of Lake George empty into Lake Champlain, and opposite to Fort Independence, in the State of Vermont. Gen.

Gen. Bu this hill, ed inaccei St. Clair 1777. SUGAR Hampfhir after a f into Conn oppofite to mont.] of uniting with Con rimack ri SUGAR fide of J leagues to SUGAR empties in SULLI co. New inhabitan SULLI trict of] Frenchma of Goldíb nobicot, 645 nort township Waukeagi SULLI in Wash contained 8,457 int flaves. SULLI iflands w Charleftor is about 7 ton. SULPH fouthern 1 in Kentu another b creek. N SULPH IAes. SULPH tain in the for exhala of ashes. of an enor mouths i depth is-1 SUMA fylvania, the E. fid empties i riton, T Philadelp

-

Gen. Burgoyne made a lodgment on this hill, which the Americans effeemed inacceffible; and thus forced Gen. St. Clair to abandon the fort in June, 1777.

SUGAR River, in Chefhire co. New-Hampfhire, rifes in Sunapee lake, and, after a fhort courfe wefterly, empties into Connecticut river, at Clermont, and opposite to Afhcutney mountain in Vermont. There is a ftrong expectation of uniting this river, by a fhort canal, with Contocook, which falls into Merrimack river at Boscawen.

SUGAR-LOAF Bay, on the north east fide of Juan Fernandes Island; 100 leagues to the west of the coast of Chili. SUGAR, a river of Veragua, which

empties into the Bay of Honduras.

SULLIVAN, a township of Cheshire co. New-Hampshire, containing 220 inhabitants.

SULLIVAN, a post-town of the Diftrict of Maine, Hancock co. and on Frenchman's Bay, 12 miles north-west of Goldsborough, 38 W. S. W. of Penobscot, 310 north-east of Boston, and 645 north-east of Philadelphia. The township contains 504 inhabitants. See Waukeague.

SULLIVAN, a county of Tennessee, in Washington district. In 1795, it contained, according to the State census, 3,457 inhabitants, of whom 777 were slaves.

SULLIVAN'S *Island*, one of the three iflands which form the north part of Charlefton harbour, in S. Carolina. It is about 7 miles fouth-east of Charlefton.

SULPHUR Creek, Little, one of the fouthern upper branches of Green river in Kentucky; and lies fouth-weft of another branch called Bryant's Lick creek. Near this is a fulphur fpring.

SULPHUR Islands. See Margaret's Isles.

SULPHUR Mountain, a noted mountain in the island of Guadaloupe, famous for exhalations of fulphur, and eruptions of ashes. On the E. fide are 2 mouths of an enormous fulphur pit; one of these mouths is 100 feet in diameter; the depth is unknown.

SUMANYSTOWN, a village of Pennfylvania, in Montgomery co. fituated on the E. fide of Great Swamp creek, which empties into the Schuylkill above Norriton. It is 33 miles N. W. by N. of Philadelphia. SUMNER, a county of Tenneffee, in Mero diffrict. According to the State cenfus of 1795, it contained 6,370 inhabitants, of whom 1,076 were flaves.

SUN

SUNAPEE, a lake and mountain in Chefhire co. New-Hampfhire. The lake is about 8 or 9 miles long, and 3 broad, and fends its waters through Sugar river weft, 14 miles to Connecticut river. The mountain ftands at the fouth end of the lake.

SUNBURY, a county of the Britifh province of New-Bruniwick. It is fituated on the river St. John, at the head of the Bay of Fundy; and contains & townfhips, viz. Conway, Gage-Town, Burton, Sunbury, St. Anne's, Wilmot, Newton, and Maugerville. The 3 laft of thefe were fettled from Maffachufetts, Connecticut, &c. The lands are generally pretty level, and tolerably fertile, abounding with variety of timber.

SUNBURY, the chief town of Northumberland co. Pennfylvania; fituated near where Fort Augusta was erected, on the E. fide of Susquehannah river, just below the junction of the E. and W. branches of that river, in lat. about 40. 52. N. It is regularly laid out, and contains a court-house, brick gaol, a Prefbyterian and German Lutheran church, and about 100 dwelling-houses. Here the river is about half a mile broad, and at the ferry opposite Northumberland, about a mile higher, is ‡ths of a mile. It is about 76 miles above Reading, and 120 N. W. of Philadelphia.

SUNBURY, a port of entry and posttown of Georgia, beautifully fituated in Liberty co. at the head of St. Catharine's Sound, on the main, between Medway and Newport rivers, about 15 miles S. of Great Ogeechee river. The town and harbour are defended from the fury of the fea by the N. and S. points of St. Helena and St. Catharine's Iflands ; between is the bar and entrance into the found: the harbour is capacious and fafe, and has water enough for thips of great burden. It is a very pleafant healthy town, and is the refort of the planters from the adjacent country, during the fickly months. It was hurnt during the late war, but has fince been rebuilt. An academy was established here in 1788, which has been under an able inffructor, and proved a very uleful institution. It is 40 miles S. of Savannah, and 974 from Philadelphia.

Lł

SUNCOOK,

John Maffa-

uletts.

id, in

before Itained houfes. nts. In ; and ompre-Bofton. Suffolk ly 10, on. Ifland, oad, & e State by the Sound, :k, or arbour, ifhip of fouth ng the rdner's Illands. flands. it. It whom townints are -houfe, 17 from v-York irginia, fide of

tains a houles. for vefles weft b. E. of f Richia. York, rth fide a from 796. *Creek*, a Miami

ice, the nmands , where pty into to Fort ermont. Gen. 530

SUNCOOK, a finall plantation in York co. Diffrict of Maine, which with Bromfield contains 250 inhabitants.

SUNDERLAND, a township of Vermont, Bennington co. 16 miles N. E. of Bennington, and contains 414 inhabitants. A lead mine has been lately diffeovered in this township.

SUNDERLAND, a townthip of Maffachufetts, fituated in Hampfaire co. on the F. fide of Connecticut river, about to miles N. of Hadley and roo W. of Bofton. There is here a handfome Congregational church, and 73 houfes, lying chiefly on one fituet. It was incorporated in 1718, and contains 462 inhabitants.

SUPAY URCO, or Devil's Hill, areimarkable eminence in the province of Quito, in Peru, between the vallies of Chugui pata, and those of Paute. It has its name from a fabulous flory of enchantment, propagated by a fuperflitious Spaniard. It is thought to contain rich mines.

SUPERIOR, Lake, formerly termed the Upper Lake, from its northern fituation. It may justly be termed the Cafpian Sea of America, and is fuppoled to be the largest body of fresh water on the globe. According to the French charts it is 1,500 miles in circumference. A great part of the coaft is bounded by rocks and uneven ground. It is fituated between 46. and 50. N. lat. and between 84. 30. and 92. W. long. The water is very clear, and transparent. If the fun fhines bright, it is impoffible through this medium to look at the rocks at the bottom, above a minute or two. Although the water, at the furface, is much warmed by the heat of the fun, yet, when drawn up at about a fathom depth, it is very cold. Storms are more dreadful here than on the ocean. There are many iflands in this lake; two of them have each land enough, if proper for cultivation, to form a confiderable province; especially Ifle Royal, which is not les than too miles long, and in many places 40 broad. The natives suppose these islands to be the relidence of the Great Spirit. Many rivers empty their waters into this mighty refervoir; of these, one is called Nipegon, another Michipicooton; which are deforibed under their refrective heads. This lake difcharges its waters from the S. E. corner through SUP

the Straits of St. Marie, which are about 40 miles long, into Lake Huron. Lake Superior, although about 40 rivers empty into it, many of which are large, yet it does not appear that one-tenth part of the waters which it receives, is difeharged by the abovementioned firait : great part of the waters evaporate; and Providence doubtlefs makes use of this inland fea to furnifh the interior parts of the country with that fupply of vapours, without which, like the interior parts of Africa, they must have been a mere defert. A number of tribes live around Lake Superior, but little is known respecting The following extract from the them. journal of a late traveller will be acceptable to the curious.

" Mr. M, about the year 1790, departed from Montreal with a company of about 100 men, under his direction, for the purpose of making a tour through the Indian country, to collect furs, and to make fuch remarks on its foil, waters, lakes, mountains, manners and cuftoms of its inhabitants as might come within his knowledge and obfervation. He purfued his route from Montreal, entered the Indian country, and coaffed about 300 leagues along the banks of Lake Superior, from thence to the Lake of the Woods, of which he took an actual furvey, and found it to be 36 leagues in length; from thence to the lake Ounipique, of which he has alfo a description. The tribes of the Indians which he paffed through, were called the Maskego tribe, Shepeweyau, Cithiniftinee, Great Belly Indians, Beaver Indians, Blood Indians, the Black feet Tribe, the Snake Indians, Offnobians, Shiveytoon Tribe, Mandon Tribe, Paunees, and feveral others, who in general were very pacific and friendly towards him, and are great admirers of the beft hunting horles, in which the country abounds. The horfes prepared by them for hunters, have large holes cut above their natural noftrils, for which they give as a reason, that those prepared in this manner will keep their breath longer than the others, which are not thus prepared : from experience, knowledge is gained, and the long practice of this cuftom, confequent on these trials, must have convinced them of the truth and utility of the experiment; otherwife we can hardly fuppole

h are e Huabout which r that nich it aboveie waloubtto furountry rithout Africa, t. A ke Susecting om the be ac-1790, mpany direca tour collect on its nanners might bferva-Montry, and ing the ence to he took o be 36 to the s alfo a Indians e called itbinifver Inack feet nobians, , Paugeneral towards of the e counared by oles cut which ofe prep their which n expeand the afequent invinced of the hardly fuppole

horfes in this manner, if fome advantage was not derived from the measure. In purfuing his route, he found no difficulty in obtaining a guide to accompany him from one nation to the other, until he came to the Shining Mountains, or Mountains of Bright Stones, where, in attempting to pals, he was fruftrated by the hoftile appearance of the Indians who inhabit that part of the country. The confequence of which was, he was disappointed in his intention and obliged to turn his back upon them. Having collected a number of Indians, he went forward again, with an intention to force his way over those mountains, if neceffary and practicable, and to make his way to Cook's river, on the N. W. coaft of America, fuppofed by him to be about 300 leagues from the mountains ; but the inhabitants of the mountains again met him with their bows and arrows, and fo fuperior were they in numbers to his little force, that he was obliged to flee before them. Finding himfelf thus totally difappointed in the information he was in hopes to obtain, he was obliged to turn his back upon that part of the country for which his thirfting heart had long panted. Cold weather coming on, he built huts for himfelf and party in the Offnobian country, and near to the fource of a large river, called the Offnobian river, where they tarried during the continuance of the cold feason, and until some time in the warmer months. Previous to his departure from Montreal, he had fupplied himfelf with feveral kinds of feeds, and before his huts he laid out a fmall garden, which the natives observing, called them flaves, for digging up the ground, nothing of that kind being done by them, they living wholly on animal food; bread is unknown to them; to fome he gave fome remnants of hard bread, which they chewed and fpit out When again, calling it rotten wood. his onions, &c. were fomewhat advanced in their growth, he was often furprized to find them pulled up; determining therefore to know from what

cause it proceeded, he directed his men

to keep watch, who found that the In-

dian children, induced by motives of

curiofity, came with flicks, thruft them

through the poles of his fence, to afcer-

SUP

fuppofe they would torture their beft

SUR

things of the white men were, and in what manner they grew, &c. The natives of this country have no fixed or permanent place of abode, but live wholly in tents made of buffaloe and other hides, and with which they travel from one place to another like the Arabs; and to foon as the feed for their horfes is expended, they remove their tents to another fertile fpot, and fo on continually, fcarcely ever returning to the fame ipots again."

SURINAM, a province or district in South America, belonging to the Dutch. See Dutch Guiana.

SURINAM, a beautiful river of South-America, and in Dutch Guiana; three* quarters of a mile wide at its mouth ; navigable for the largeft veffels 12 miles, and for fmaller veffels 60 or 70 miles further. Its banks, quite to the water's edge, are covered with evergreen mangrove trees, which render the profpect very delightful. The entrance is guarded by a fort and two redoubts, but not of any great ftrength. At 6 miles up, the Commanwine falls into it, and on the point of land between the two rivers are the forts. The town of Surinam is in lat. 6. 10. N. and long. 55. 22. W. The best anchorage is under Zelandia Fort.

SURRY, a county of N. Carolina, in Salifbury diffrict; bounded eaft by Stokes, and west by Wilkes. It contains 7,191 inhabitants, including 698 flaves. The Moravian fettlements of Wachovia are in this county. Near the river Yadkin is a forge, which manufactures bar-iron. The Ararat or Pilot Mountain, about 16 miles north-weft of Salem, draws the attention of every curious traveller in this part of the State. It is difcernible at the diftance of 60 or 70 miles, overlooking the country below. It was anciently called the Pilot, by the Indians, as it ferved them for a beacon, to conduct their routes in the northern and fouthern wars. On approaching it, a grand difplay of nature's workmanship, in rude dreis, is exhibited. From its broad bale, the mountain rifes in eafy ascent, like a pyramid, near a mile high, to where it is not more than the area of an acre broad; when, on a fudden, a vast stupendous rock, having the appearance of a large caftle, with its battlements, crects its perpendicular tain and fatisfy themfelves, what the height to upwards of 300 feet, and ter-

Llz

minates

532

minates in a flat, which is generally as level as a floor. To afcend this precipice, there is only one way, which, through cavities and fiffures of the rock, is with fome difficulty and danger effected. When on the fummit, the eve is entertained with a vaft, delightful prospect of the Apalachian mountains, on the north, and a wide, extended level country below, on the fouth ; while the Areams of the Yadkin and Dan, on the right and left hand, are difcovered at feveral diftant places, winding their way, through the fertile low grounds, towards the ocean.

SURRY, a county of Virginia, bounded north by James river, which fepa-rates it from Charles City county, eaft by Ifle of Wight, and weft by Prince George's county. It contains 6,227 inhabitants, of whom 3,097 are flaves. SURRY, a township of New-Hamp-thire, in Cheshire county, containing. 448 inhabitants. It lies eaft of Walpole, adjoining, and was incorporated in 1769.

SUSQUEHANNAH River, rifes in Lake Uftayantho, in the State of New-York, and runs in fuch a ferpentine courfe that it croffes the boundary line between the States of Pennfylvania and New-York, three times. It receives the Tyoga river in N. lat. 41. 57. Afterwards it proceeds fouth-east to Wyoming, without any obstruction by falls, and then fouthwelt over Wyoming falls, till, at Sunbury, in lat. 41. it meets the weft branch of Sufquehannah, which is navigable 90 miles from its mouth. From Sunbury the river is paffable with boats to Har-rifburg and Middleton on the Swatara. About 15 miles above Harrifburg, it receives the Juniatta, from the north-weft, proceeding from the Alleghany mountains, and flowing through a broken country. Hence it takes its courfe about fouth-eaft, until it falls into the head of Chefapeak Bay, just below Havre de Grace. It is about a mile wide at its mouth, and navigable only 20 miles. the navigation being obstructed beyond that by the Rapids. The inland navigation between Schuylkill and Sulquehannah, will bring by water to Philadelphia, the trade of a most fertile country of about 1000 miles fquare, or 6,000,000 acres of land. If this can be accomplifhed, an inland navigation may be eafily made to the Ohio and to Lake | capable of beneficial improvements, as

Erie, which would at once open a communication with above 2,000 miles extent of western country, viz. with all the great lakes, together with the countries which lie on the waters of Miffifinpi, Miffouri, and all their branches. The water communication between Schuvlkill and Sufguehannah, which is the foul of all this, will be about 60 miles, as the navigation muft go, although the diffance on a line is only 40 miles. This tract is cut by two creeks. the Quitapahilla and the Tulpehoken, These two creeks lead within 4 miles of each other ; the level of their head waters is nearly the fame, and the fpace between them makes the height of land, or, as it is commonly called, the crown land between the two rivers, which is nearly on a plain, and the bottom of the canal, through which the navigation must pais, will no where rife more than so feet above the level of the head waters of the two creeks above mentioned, nor fo much as 200 feet above the level of the waters of Sufquehanbah or Schuylkill. The Company, inflituted the 29th of Sept. 1791, has a capital of 1000 fhares at 400 dollars each, payable. at fuch time as the Company fhall di-The work is already commenrect. ced. Coal of an excellent quality is found on feveral parts of this river, particularly at Wyoming.

SUSSEX, the north-westernmost co. of New-Jerfey. It is mountainous and healthy, and has feveral iron mines: and works have been erected for the manufacture of bar and pig iron. It produces excellent crops of wheat; and in no part of the State are greater herds of cattle. The produce is floated down the Delaware, in boats and rafts. Here are 5 Prefbyterian churches, 2 for Anabaptifts, 1 for German Lutherans, and 1 for Quakers. It contains 12 townfhips; the chief of which are Newton, Greenwich, Hardyston, Knowl. town, and Oxford. The population is 19, 500 including 439 flaves. It is bound. ed N. E. by the State of New-York, N. W. by Delaware river, which feparates it from Northampton co. in Penafylvania, and fouth eaft and fouth by Morris and Hunterdon counties. Paulin's Kill is here navigable for fmall craft 15 miles. The Musconetcony, which divides the county from Hunterdon, is is the Peau above-ment house in thi weft of Har in Pennfyly fhen, in Ne of Philadel place is cal SUSSEX. ed N. E. b Dinwiddie. tants, inclu

SUSSEX. ware State. the State (Delaware Ocean, and tains 20,4 4,025 flave north-easter town, Geor SUTTON thire, Hillf inhabitants town, and SUTTON Maffachufe Bofton, and cefter. It w contains 2, 10 grift m mills, a pa trip-hamme ax-makers. work at na making po feng and th common y-(eaftern part riofity. Bo June, alth fouth. SWALLO Ocean, S. 1 162. 30.; 1722.

SWAMSA tinguish it called Exet New Ham through Sa and a conf fording ma bles over a and meets t bour, in th Exeter. Brentwood a third of 1 ie the Pequeft or Pequafet, between the above-mentioned rivers. The courthoufe in this county is 13 miles fouthweft of Hamburg; 38 N, E. of Eafton, in Penufylvania; 41 fouth-weft of Gofhen, in New-York; and 108 N. by E. of Philadelphia. The village at this place is called Newton.

com-

s ex-

h all

oun-

lifip-

ches.

ween

ch is

it 60

', al-

ly 40

eeks,

sken.

les of

wa-

e be-

land,

rozun

ich is

of the

ation

than

I wa-

oned,

level

h or

ituted

tal of yable

ill di-

men-

ity is

river,

co. of

and

uines;

i. It

heat ;

reater

loated

rafts.

2 for

erans,

18 12

New-

nowl.

ion is

k, N.

fepa-

Pena-

uth by

Paul-

l craft

which

on, is its, as

is

SUSSEX, a county of Virginia; bounded N. E. by Surry, and fouth-weft by Dinwiddie. It contains 10,554 inhabitants, including 5,387 flaves.

SUSSEX, a maritime county of Delaware State, bounded weft and fouth by the State of Maryland, north-eaft by Delaware Bay, eaft by the Atlantic Ocean, and north by Kent co. It contains 20,488 inhabitants, including 4,025 flaves. Cape Henlopen is the north-eaftern part of the county. Chief town, Georgetown.

SUTTON, a township of New Hampshire, Hillsborough co. containing 520 inhabitants. It was first called Perrystown, and was incorporated in 1784.

SUTTON, a township in Worcester co. Maffachusetts, 46 miles W. S. W. of Bofton, and 10 miles S. by E. of Worcefter. It was incorporated in 1718, and contains 2,642 inhabitants. Here are 10 grift mills, 6 faw-mills, 3 fullingmills, a paper-mill, an oil-mill, and 7 trip-hammers. There are 5 fcythe and ax-makers, one hoe-maker, feveral who work at nail-making, and 6 works for making pot-ath. Here are found ginfeng and the cohufh-root. The cavern, commonly called Purgatory, in the foutheaftern part of the town, is a natural curiofity. Bodies of ice are found here in June, although the descent is to the fouth.

SWALLOW Island, in the Pacific Ocean, S. lat. 10. E. long. from Paris, 162. 30.; discovered by Roggewein, 1722.

SWAMSCOT, or Great River, to diftinguish it from another much lefs, also called Exeter River, rifes in Chafter, in New Hampshire, and after running through Sandown, Poplin, Brentwood, and a confiderable part of Exeter, af fording many excellent mill feats, tunbles over a fall 20 or 30 rods in length, and meets the tide from Piscataqua harbour, in the centre of the township of Exeter. The smaller river rifes in Brentwood and joins Great river about a third of a mile above Exeter. Here are caught plenty of alewives and fom oyfters. Swamicot is the Indian nam of Exeter.

SWE

SWAN *Ifland*, in the Diffrict of Maine, divides the waters of Kennebeck river, three miles from the Chops of Merry-Meeting Bay. It is feven miles long, and has a navigable channel on both fides, but that to the eaft is moftly ufed. It was the feat of the fachem Kenebis The river itfelf probably took its name from the race of Sagamore of the name of Kenebis.

SWANNANO, the eaft head water of French Broad river, in Tepheffee. Allo the name of a fettlement within tout 60 miles of the Cherokee nation.

SWANNSBOROUGH, the chief town of Onflow co. Wilmington diftrict, N. Carolina.

SWANSEY, a township in Cheshire co. New-Hampshire, adjoining Chestersfield on the E. 97 miles westerly of Portsmouth. It was incorporated in 1753, and contains 1157 inhabitants.

SWANSEY, a township in Bristol co. Massachusetts, containing 1784 inhabitants. It was incorporated in 1667, and lies 52 miles southerly of Boston.

SWANTON, a township of Vermont, Franklin co. on the E. bank of Lake Champlain, on the fouth side of Mischifcoui river. This township has a cedar fwamp in the N. W. part of it, towards Hog Island. The Mischifcoui is navigable for the largett boats 7 miles, to the falls in this town.

SWANTOWN, in Kent co. Maryland, is about 3 miles S. eafterly of Georgetown.

SWEDESBOROUGH, afmall post-town of New Jerley, Gloucester co. on Racoon Creek, 3 miles from its mouth, in Delaware river, 11 S. by W. of Woodbury, 17 N. by E. of Salem, and 20 foutherly of Philadelphia.

SWEDISH AMERICA. The Swedes had anciently fettlements on Delawareriver, and the Swedish church in Philadelphia is the oldeft in that city. The only American fettlement they have now, is the finall island of Bartholomew, or Barthelemi, in the Weft-Indies, which is about 30 miles in length, and the fame in breadth. It was obtained from France in 1785, and gave rife to the Swedish Weft-India Company.

SWEET SPRINGS, in Virginia, 30 miles E. by N. of Greenbriar, 93 weft of Staunton, and 380. S. W. of Phila-L 1 3 delphia.

delphia. In the fettlement around thefe fprings, a post-office is kept.

SWETARA, or Swatara, a river of Pennfylvania, which falls into the Sufquehannah from the N. E. about 7 miles S. E. of Harrifburg.

SYDNEY, or Cape Breton Island; which fee.

-SYDNAY, in Lincoln co. District of Maine, is 37 miles from Pownalborough, 98 from Hallowell, and 203 from Bofton. SYMSBURY. See Sim/bury.

SYPOMBA, an ifland on the coaft of Brazil, in S. America, about 7 leagues N. E. of St. John's Ifland, and N. W. from a range of iflands which form the great Bay of Para.

\mathbf{T}

AAWIRRY, one of the two fmall iflands within the reef of the ifland of Otaheite, in the South Pacific Ocean. Thefe iflands have anchorage within the reef that furrounds them.

TABAGO, an ifland in the Bay of Panama, about 4 miles long, and 3 broad. It is mountainous, and abounds with fruit trees. N. lat. 7. 30. W. long. 60. 16.

TABASCO, an island in the S. W. part of the Gulf of Mexico, and at the bottom of the Gulf of Campeachy, is about 36 miles long, and about 7 broad ; and on it is built the town of Tabafco, in lat. 17. 40. N. and long. 93. 39. W. It is the capital of a rich province of its name, and is fituated at the mouth of the river Grijalva, 90 miles E. of Espirito Santo, and 160 S. E. of Mexico. It is not large, but is well built, and is confiderably enriched by a conftant refort of merchants and tradefinen at Chriftmas. 'The river Grijalva divides itfelf near the fea into two branches, of which the western falls into the river Tabafco, which rifes in the mountains of Chiapa, and the other continues' its courfe till within 4 leagues of the fea, where it fubdivides and feparates the ifland from the continent. Near it are plains which abound with cattle and other animals, particularly the mountain cow, fo called from its refembling that creature, and feeding on a fort of mois found on the trees near great rivers.

TABOGUILLA, or Little Tabago, in

TAL

Tabago, and near it. The channel between them is narrow but good, through which thips pais to Point Chama or Nata.

TABOOYAMANOO, a fmall island in the South Pacific Ocean, Subject to Huaheine, one of the Society Iflands.

TACAMES, a bay on the coaft of Peru, in lat. about 1. 6. N. and 3 leagues to the N.E. of Point Galera.

TACHIFI Point, on the coaft of New Mexico, is 18 miles from the town of Pomaro.

TACONNET Fall. See Fort Halifax. TACUNGA. See Latacunga.

TADOUSAC, a fmall place in Lower Ganada, at the mouth of the river Saguenay, or Sagaenai on the north fhore of the river St. Lawrence. Here a confiderable trade has been carried on with the Indians, they bringing their furs and exchanging them for European cloths, utenfils and trinkets. It is 98 miles below Quebec. N. lat. 48. W. long. 67. 35. See Saguenay River.

TAENSA, a fettlement in Weft-Florida, on the eaftern channel of the great Mobile river, on a high bluff, and on the fcite of an ancient Indian town, which is apparent from many artificial mounds of earth and other ruins. It is about 30 miles above Fort Conde, or city of Mobile, at the head of the bay. Here is a delightful and extensive prospect of fome flourishing plantations. The inhabitants are mostly of French extraction, and are chiefly tenants. The myrica inodora, or wax-tree, grows here to the height of 9 or 10 feet, and produces excellent wax for candles.

TAGAPIPE, a caffle erected on a point of land in the Bay of All Saints, in Brazil. It is pretty confiderable, and adds greatly to the ftrength of St. Salvadore.

TAGO, Sant, or Tiago Point, on the weft coaft of New Mexico, is between, Salagua and the White Rock.

TAHOORA, or Taboorowa, one of the fmalleft of the Sandwich Iflands, 3 leagues from the fouth-west part of Mowee. N. lat. 20 38. W. long 1 56. 33.

TALAHASOCHTE, a confiderable town of the Seminole Indians, fituated on the elevated east banks of the Little river St. John, near the bay of Apalache, in the Gulf of Mexico, about 75 miles from the Alachua favanna. Here are the bay of Panama, a fimaller island than | near 30 habitations constructed of frame werk.

work, and cypreis tree willa, and house. T fome canor trunks of enough to these they and huntin iflands, an Florida; and go to to Cuba, liquors, c

> TALAI great nort or Mobile the high l runs thro Oakfuske tion and i until it where it thence th to Little the Coof fome, ne this river 15 or 20 and falut er part o TALA

confifting Eaft Flo the head ly fepara er, eaft I and wel from th Swamp, Atrikes th of the (State of Indian c has beer price of makes a fince the TAL.

Creeks, tory, o river, d Apalac is alfo (TAL Georgi

lat. abo river en island a

T A L work, and covered with the bark of the cypreîs tree, afcer the mode of the Cufcowilla, and a fpacious and neat councilhoufe. Thefe Indians have large handfome cances, which they form out of the trunks of cypreîs trees, fome capacious enough to hold 20 or 30 wartiors. In thefe they defeend the river on trading and hunting expeditions on the fea-coaft, iflands, and keys, quite to the Point of Florida; and fometimes crofs the Gulf and go to the Bahama Iflands, and even to Cuba, and bring returns of fpirituous

liquors, coffee, fugar, and tobacco. TALAPOOSEE, or Tallapoofee, the great north-east branch of the Alabama or Mobile river, in Florida. It rifes in the high lands near the Cherokees, and runs through the high country of the Oakfuskee tribes in a westwardly direction and is full of rocks, falls, and fhoals, until it reaches the Tuckabatches, where it becomes deep and quiet; from thence the courfe is weft about 30 miles to Little Tallafie, where it unites with the Coofa, or Coofa Hatcha. At Coolfome, near Otaffe, a Muscogulge town, this river is 300 yards broad, and about 15 or 20 feet deep. The water is clear and falubrious. In most maps, the lower part of this river is called Oakfuskie.

TALASSEE, or Tallaffee, a county confifting of a tract of land bounded by Eaft-Florida on the fouth, from which the head water of St. Mary's river partly feparates it; north by Alatamaha river, eaft by Glynn and Camden counties, and westerly by a line which extends from the western part of Ekanfanoka Swamp, in a N. E. direction till it Arikes the Alatamaha river, at the mouth of the Oakmulgee: It is faid that the State of Georgia had extinguished the Indian claim to this tract of land, but it has been given up to the Indians as the price of peace; for which that State makes a claim for 50,000l. with inte eft. fince the treaty, upon the United States.

TALASSEE, a town of the Upper Creeks, in the Georgia weftern terri tory, on the fouth fide of Talapooleriver, diftant about 3 days journey from Apalachicola on Chata Uche river. It is also called Big Talasse.

TALBERT'S *Ifland*, on the coaft of Georgia, the north point of which is in lat. about 30. 44. N. where St. Mary's river empties into the ocean between this island and Amelia island on the N.

TALBOT, an island on the coast of East-Florida. The fands at the entrance of Naffau lie three miles off the fouth east point of Amelia Island, and from the N. E. point of Talbot Island.

TALBOT, a county of Maryland, on the eaftern fhore of Chefapeak Bay, bounded E. by Choptank river, which divides it from Caroline county, and fouth by the fame river, which feparates it from Dorchefter. It contains 13,084 inhabitants, of whom 4,777 are flaves. The foil is rich and fertile.

TALCAGUAMA, a cape on the coaft of Chili, 11 leagues N. E. of the island of St. Mary, and 2 northward of Port St. Vincent.

TALCAGUAMA Port, is 6 miles within the above point of its name, and is one of two good roads in the bay of, Conception.

TALLOW Point, a mark for anchoring in the harbour of Port Royal, on the fouth coaft of the Island of Jamaica.

TALOO Harbour, on the N. fide of the illand of Eimeo, in the South Pacific Ocean. S. lat. 17. 30. W. long. 150.

TAMALEQUE, an inland city, in the province of St. Martha, on the coaft of Terra Firma. It is fituated on the banks of Magdalena river, and carries on a trade on that river from New Granada to Carthagena, from whence it is diftant above 150 miles.

TAMAR, Cape, is the N. W. point of a large bay and harbour on the north thore of the Straits of Magellan, within the cape. The fouth-east point of the bay is named Providence. S. lat. 52. 51. W. long. 75.40.

TAMARIKA, an island on the coaft of Brazil, northward of Pernambuco, and about 24 miles in length. It is 2 miles N. of Pornovello, and has a harbour and good frefh water. S. lat. 7. 56. W. long. 35. 5.

TAMATAMOUE, called by the Spaniard's Villa de las Pulmas, a town of Santa Martha, in Terra Firma, S. America; fituated on the eaftern bank of Santa Martha river, about 28 miles above Teneriffe.

TAMBO Land, on the coaft of Peru, extends about 9 miles from Cape Remate to Playa de los Perdrices, or the Partridge Strand, about 9 miles. There is clear and good anchorage upon this ftrand, under a row of high, ridgy, and fandy hills. On making them from the L14 fea.

d in Ina-Pegues New 'n of fax. ower · Safhore conwith and oths, miles long. Plorigreat n the which ounds thout ity of Here ect of he instrac-The s here i proon a jaints, e, and r. Salon the tween,

of the

ds, 3

irt of

6. 33.

erable

tuated

Little

lache,

miles

re are

frame

work,

be.

ugh

or

fea, they refemble a covey of partridges just rifing ; hence the name of the coaft.

TAMMANY'S, St. a village onDan river in Virginia, 15 miles from Gill's Bridge, 7 from Mecklenburg court-house, 42 from Halifax court-house, in North-Carolina, and 398 from Philadelphia.

TAMMANY, Fort St. or St. Mary's, at the mouth of St. Mary's river, on the S. line of Georgia. See St. Mary's.

TAMMATA-PAPPA, a low illand of the N. Pacific Ocean, faid to be near the Sandwich Islands.

TAMOU Island, one of the small islets which form part of the reef on the E. fide of Ulietea Island, one of the Society Islands.

TAMPA. See Spiritu Santo.

TAMWORTH, a township in the northern part of Strafford co. New-Hampshire. It was incorporated in 1766, and contains 266 inhabitants.

TANBANTY Bay, on the coaft of Brazil, has a good road, fheltered by the fands that lie off within 3 miles of the fhore. It is one of those places between Point Negro and Point Luena.

TANEYTOWN, a finall post-town of Maryland, in Frederick co. between Piney Run and Pine Creek, on which are a number of mills and fome iron-works. It lies 27 miles N. by E. of Frederickstown, and 121 W. S. W. of Philadelphia. — TANELA, or *Tonela*, a tract of thore on the west coast of Mexico, on the N. Pacific Ocean, commencing near the Sugar Loaf Hill, about 6 miles within the land, bearing N. E. and S. W. with the burning mountain of Lacatecolula, about 18 miles up the river Limpa.

TANGOLA, an ifland in the N. Pacific Ocean, and on the west coast of New Mexico; affording good anchorage and plenty of wood and water. It is about 60 miles westward of Guatimala. It is also named *Tangolatango*.

TANGUEY, or Tonguey, on the coaft of Chili, in the S. Pacific Ocean, is 30 miles from Limari, and in lat. 30. 30. N.

TANSA, a branch of the river Mobile, 3 leagues below the Alabama branch.

TAOO, the most foutherly of the Eriendly Islands, in the South Pacific Ocean, is about 10 leagues in circuit, and so elevated as to be feen at the diftance of 12 leagues.

TAOUKA, an illand in the S. Pacific Ocean, one of the Society Iflands. S. lat. 14. 30. W. long. 145. 9.

TAP

TAPANATEPEQUE, a town of Guaxaca, and audience of Mexico. It ftands at the foot of the mountains Quelenos, at the bottom of a bay in the South Sea; and is reprefented as one of the pleafanteft places in this country, and the beft furnified with fielh, fowl and fifh, being contiguous both to the fea and a river, amidit rich farms, each of which being flocked with between 1000 and 4000 head of cattle. Here are delightful walks of orange, lemon, citron, fig and other fruit trees.

TAPARICA, a long ifland on the weft fide of the entrance into the Bay of All Saints, in Brazil. See *Bahia*.

TAPAYO, a town of S. America, on the fouth bank of Amazon river, eafterly from the mouth of Madeira river.

TAPPAHANNOCK, a post-town and port of entry of Virginia, in Effex co. between Dangerfield on the north and Hoskin's creek on the south, and on the south-west bank of Rappahannock river, 54 miles from Richmond, 67 from Williamsburg, and 263 from Philadelphia. It is also called *Hobbes' Hole*; which fee. It is laid out regularly, on a rich plain, and contains about 100 houses, an episcopal church, a courthouse, and gaol; but is rather unhealthy. The exports for one year, ending Sept. 30, 1794, amounted to the value of 160,673 dollars.

TAPAYOS. See Tapuyes.

TAPPAN, a town of New-York, in the fouth-eaft part of Orange co. about 4 miles from the north bank of Hudion's river, and at the fouth end of the Tappan fea. Here is a reformed Proteftant Dutch church. Major Andre, adjutantgeneral of the British army suffered here as a fpy, Oct. 2, 1780; having been taken on bis way to New-York, after concerting a plan with major-general Arnold for delivering up Weft Point to the British.

TAPPAN Sea, or Bay, a dilatation of Hudíon's river, in the State of New-York, opposite the town of Tappan, and 35 miles north of New-York city; immediately fouth of and adjoining Haverstraw Bay. It is 10 miles long and 4 wide; and has on the north fide fine quarries of a reddish free flone, used for buildings and grave-flones; which are a fource of great wealth to the proprictors. See Steep Rocks.

TAPUYES,

TAPI Gderable in S. A conquer fpread 1 to the V number ed by t TAR Spain. pital. TAR Carolin Tarriv 140 fre of Fav S. by and 4 contair and ga of the and In export TA teen iv bifhop about greate The t in fom that it and every but e yas. count runs 1 of wl walke of the T ble ri a fo Waf ville. N. 9 feet 40 m or fl miles roug com of 1 prace navi that bran mile т

fiderable nation of the native Brazilians, in S. America, that have not yet been conquered by the Portuguefe. They fpread themfelves a great way inland to the W. and are divided into a great number of tribes or cantons, all governed by their own kings.

TARAHUMARY, a province of New Spain, 1200 miles diftant from the capital.

TARBOROUGH, a post-town of N. Carolina; fituated on the W. fide of Tarriver, about 85 miles from its mouth, 140 from Ocrecock Inlet, 110 N. by E. of Fayetteville, 37 S. of Halifax, 112 S. by W. of Petersburg in Virginia, and 420 S. W. of Philadelphia. It contains about 50 houfes, a court-houfe and gaol. Large quantities of tobacco, of the Petersburg quality, pork, beef, and Indian corn are collected here for exportation.

TARIJA, or Chichas, one of the fourteen jurifdictions belonging to the archbishopric of Plata, in Peru. It lies about 90 miles fouth of Plata, and its greatest extent being about 105 miles. The temperature of the air is various : in fome parts hot, and in others cold; fo that it has the advantage of corn, fruits This country abounds and cattle. every where in mines of gold and filver; but efpecially that part called Choca-Between this province and the yas. country inhabited by the wild Indians, runs the large river Tipuanys, the fands of which being mixed with gold, are washed, in order to separate the grains of that metal,

TAR, or Pamlico River, a confidera ble river of N. Carolina, which purfues a fouth-east course, and paffing by Washington, Tarborough and Greenville, enters Pamlico Sound in lat. 35. 22. N. It is navigable for veffels drawing o feet water to the town of Washington, 40 miles from its mouth; and for icows or flats carrying 30 or 40 hhds. 50 miles farther to the town of Tarborough. According to the report of a committee, appointed by the legiflature of N. Carolina, to inquire into the practicability of improving the inland navigation of the State, it is fuppofed that this river, and Fifny Creek, a branch of it, may be made navigable 40 miles above Tarborough.

TAPUYES, or Tapayos, the most con- | Maffachufetts, lies about 3 leagues N. N. W. of Holmes's Hole, in Martha's Vineyard. It is high water here at full and change, two minutes after ten o'clock ; 5 fathoms water.

TARRYTOWN, a confiderable village in Phillips's Manor, New York, on the E. fide of Hudson's river, 30 miles N. of New York city, Under a large tree, which is fhewn to travellers as they pafs the river, is the fpot where the unfortunate Major Andre was taken; who was afterwards executed at Tappan.

TARSTOWN. See Lewisburg, Pennfylvania.

TARTE's Rapids, La, on the river Ohio, lie 40 miles above the mouth of the Great Kanhaway. See Obio.

TATMAGOUCHE, or Tatamagouche, a place in Nova-Scotia, on a fhort bay which fets up foutherly from the Straits of Northumberland; about 25 miles from Onflow, and 21 from the ifland of St. John's. See Southampton. It has a very good road for vefiels, and is known alio under the names Tatamaganabou.

TATNAM Cape, the eaftern point of Haye's river, in Hudson's Bay. N. lat. 57. 35. W. long. 91. 30.

TATOO-E-TEE, an island in the S. Pacific Ocean, one of the Ingraham Ifles, called/by Capt. Ingraham Franklin, and by Capt. Roberts, Blake. It lies 7 or & leagues W. by N. of Nuoheeva.

TAUMACO, an island about 1250 leagues from Mexico, where De Quiros stayed ten days. One of the natives named above 60 iflands round it. Some of the names follow, viz. Manicola, Chicayano, larger than Taumaco, and about 300 miles from it; Guatopo, 150 miles from Taumaco; Tucopia, at 100, where the country of Manicola lay. The natives had, in general, lank hair; fome were white, with red hair; iome mulattoes, with curled hair; and fome woolly like negroes. De Quiros observes that in the bay of Philip and James, were many black ftones, very heavy, fome of which he carried to Mexico, and upon affaying them, they found filver.

TAUNTON, a river which empties into Narraganfet Bay, at Tiverton, opposite the N. end of Rhode-Island. It is formed by feveral ftreams which rife in Plymouth county, Maffachufetts. TARPAULIN Cove, on the coaft of | Its course is about 50 miles from N. E. Its

enos. Sea ; fantbeft ring tiver, being 4000 htful ; and

uaxands

weft f All rica,

river, deira 1 and x co. and n the river, from adel-Hale ; y, on

100

ourt-

heal-

iding

value

k, in

ibout

lon's

Tapeftant tanthere been after neral int to on of New-, and imaver-

opri-YES,

und 4

d for

h are

fine

TEA

to S. W. and it is navigable for finall | E. fhore of Northampton co. Virginia, vefiels to Taunton.

TAUNTON, a post-town of Massachufetts, and the capital of Briftol co. fituated on the W. fide of Taunton river, and contains 40 or 50 houfes, compactly built, a church, court-houfe, gaol, and an academy, which was incorporated in 1792. It is 36 miles S. by E. of Bolton, 21 E. of Providence, 24 northerly of Bedford, and 312 N.E. of Philadelphie. The township of Taunton was taken from Raynham, and incorporated in 1639, and contains 3804 inhabitants. A flitting-mill was erected here in 1776, and for a confiderable time the only one in Maffachufetts, and was then the best ever built in America. The annual production of 3 mills now in this township is not lefs than 800 tons of iron; about 50 tons are cut, and 300 hammered into nails, and the remainder is wrought into. fpades and shovels; of which last article 200 dozen are rolled annually. Mr. Samuel Leonard rolled the first shovel ever done in America. This invention reduces the price one half. Wire-drawing, and rolling theet-iron for the tin-manufacture, are executed here. There is also a manufactory of a fpecies of ochre, found here, into a pigment of dark yellow colour.

TAUNTON Bay, in the District of Maine, is fix miles from Frenchman's

Bay. TAVERNIER Key, a finall ifle, one of the Tortugas, 2 miles from the S. W. end of Key Largo, and 5 N. E. of Old Matacombe. To the northward of this last island is a very good road.

TAWANDEE Creek, in Northumberland co. Pennfylvania, runs N. E. into the E. branch of Susquehannah, 12 miles S. E. of Tioga Point.

TAWAS, an Indian tribe in the N.W. Territory, 18 miles up the Miami of the Lake. Another tribe of this name, inhabit higher up the fame river, at a place called the Rapids.

TAWIXTWI, The English, or Picque-Town, in the N. W. Territory, is fituated on the N. W. bank of the Great Miami, 35 miles below the 5 mile portage, to the Miami of the Lake, and 68 S W. by S. of Miami Fort. It was taken in 1752 by the French. N. lat. 40. 41. W. long. 84. 48.

TEM

and N. by E. of Parramore Island.

TECOANTEPEC, or Tecuantepeque, or Teguantepeque, a large bay on the W. coaft of New-Mexico, on the fouth fide of the Ifthmus from the Bay or Gulf of Campeachy, in the S. W. part of the Gulf of Mexico; and bounded W. by Point Angelos. The port town of its name, lies in lat. 15. 28. N. and long. 96: 15. W.

TEHUACAN, a city of New Spain, 120 miles S. E. of Mexico.

TEKY Sound, on the coaft of Georgia, to the fouth of Savannah river, is a capacious road, where a large fleet may anchor in from 10 to 14 fathoms water, and be land-locked, and have a fafe entrance over the bar of the river. The flood tide is generally 7 feet.

TELICA, a burning mountain on the W. coaft of New Mexico, feen at N. N. E. over the ridge of Tofta. It is one of the range of volcanoes which are feen along the coaft from Fort St. John's to Tecaantepeck, and is 18 miles from Volcano del Vejo, or Old Man's Burning Mountain; and there are two others between them, but not fo eafily difcerned, as they do not often emit imoke.

TELLICO Block-Houfe, in Tenneffee, stands on the north bank of Tenneffee river, immediately opposite the remains of Fort Loudon; and is computed to be 900 miles, according to the course of the river, from its mouth, and 32 miles fouth of Knoxville in Tenneffee. It was creeted in 1794, and has proved a very advantageous military poft. It has lately been eftablished, by the United States, as a trading post with the Indians.

TELLIGUO, Great, in the State of Tenneffee, was fituated on the east fide of the Chota branch of Tenneffee river, about 25 miles N. E. of the mouth of Holfton river, and 5 fouth of the line which marked Lord Granville's limits of Carolina. This was a British factory, eftablished after the treaty of Westminfter, in 1729.

TELLIGUO Mountains, lie fouth of the above place, and feem to be a part of what are now called the Great Iron Mountains, in the lateft maps.

TEMPIE, a place in New Galicia, 200

leagues N. W. of the city of Mexico. TEMP a township of New Hampthire, Hillfborough co. north of New TEACHES, a finall island close to the | Ipswich, and 70 miles westerly of Portsmouth.

mouth. and cor TEN oppolit of this French TEN W. pa contair granter king I raganf in 176 Bofton TE Ocean Lient. long. about covere the co inhab remar TI and] ed on er Sa with the c fouth Tene one from partl Т the l leag T navi calle furd larg the I lat. 100 to la nun ther cuit Ohi It i den its bro abl the pla the thr

mouth. It was incorporated in 1768, | land Mountain, is 250 miles; and the and contains 520 inhabitants.

TEMPLE Bay, on the Labrador coaft, opposite Belle Ifle. A British fettlement of this name was deftroyed by the French, in October, 1796.

r. le

of

10

ıy

ts

ζ.

n,

a,

a.-

ly

r,

3 -

he

he

Ň.

is

re

18

na

3 -

18

3-

e,

2e

18

to

of

28

It

а

1.6

d

s.

of

le

r,

of

ie

ts

¥.,

3.

of

of

143

10

UB.

f-

TEMPLETON, a township in the N. W. part of Worcefter co. Maffachufetts, containing 950 inhabitants. It was granted as a bounty to the foldiers in king Philip's war, and was called Narraganfet No. 6, until its incorporation in 1762. It is 63 miles W. by N. W. of Bofton, and 28 N. by W. of Worcefter.

TENCH's Ifland, in the South Pacific Ocean, was discovered in 1790, by Lient. Ball, and lies in let. 1. 39. S. and long. 151. 31. W. It is low, and only about 2 miles in circuit, but is entirely covered with trees, including many of the cocoa-nut kind. It abounds with inhabitants, and the men appear to be remarkably fout and healthy.

TENERIFFE, a town of Santa Martha and Terra Firma, in S. America, fituated on the eaftern bank of the great river Santa Martha, below its confluence with Madalena, about 135 miles from the city of Santa Martha, towards the fouth the road from which capital to Teneriffe is very difficult by land, but one may go very eafily and agreeably from one to the other partly by lea, and partly by the above mentioned river.

TENNANT's Harbour, on the coalt of the Diffrict of Maine, lies about three leagues from George's Iflands.

TENNESSEE, a large, beautiful, and navigable river of the State of Tenneffee, called by the French Cherokee, and abfurdly by others Hogohegee river, is the largeft branch of the Ohio. It rifes in the mountains of S. Carolina, in about lat. 37. and purfues a courfe of about 1000 miles, fouth and fouth west-nearly to lat. 34. receiving from both fides a number of large tributary freams. It then wheels about to the north in a gircuitous courfe, and mingles with the Ohio, nearly 60 miles from its mouth. It is navigable for veffels of great burden to the Muscle Shoals, 250 miles from its mouth. It is there about three miles broad, full of fmall ifles, and only paffable in fmall boats or batteaux. From these shoals to the Whirl, or Suck, the place where the river is contracted to the breadth of 70 yards, and breaks through the Great Ridge, or Cymber539

TEN

excellent. The highest point of navigation upon this river is Tellico-Block-Houfe, 900 miles from its mouth according to its meanders. It receives Holfton river 22 miles below Knoxville, and then running W. 15 miles receives the Clinch. The other waters which empty into Tenneffee, are Duck and Elk rivers, and Crow Creek, on the one fide ; and the Occachappo, Chickamauga and Hiwaffee rivers on the fouth and foutheastern fides. In the Tennessee and its upper branches are great numbers of fifh, fome of which are very large and of an excellent flavour. The river to which the name Tenneffee was formerly confined, is that part of it which runs northerly, and receives Holfton river 20 miles below Knoxville, The Coyeta, Chota, and Chilawee Indian towns are on the west fide of the river; and the Talaffe town on the east fide.

TENNESSEE, one of the United States of America, and, until 1796, called the Tenneffee Government, or Territory of the United States South of the Ohio. It is in length 400 miles, and in breadth 104; between lat. 35. and 36. 30. N. and long. 81. 28. and 91. 38. W. It is bounded N. by Kentucky and part of Virginia; E. by North-Carolina; S. by Georgia; W. by the Miffifippi. It is divided into 3 diffricts. viz. Washington, Hamilton, and Mero, which are fubdivided into 13 counties, viz. Washington, Sullivan, Greene, Carter, Hawkins, Knox, Jefferion, Sevier, Blount, Grainger, Davidson, Sumner, Robertion, and Montgomery. The first four belong to Washington diffrict, the next five to that of Hamilton, and the four latter to Me-The fwo former diffricts ro district. are divided from the latter, by an uninhabited country of 91 miles in extent ; that is, from the block-houles, at the point formed by the junction of the river Clinch with the Tenneffee, called South-Weft Point, to Fort Blount upon Cumberland river, through which there is a waggon road, opened in the fummer of 1795. There are few countries to well watered with rivers and creeks, The principal rivers are the Miffifippi, Tenneffee, Cumberland, Holfton, and Clinch. . The tract called the Broken Ground, fends immediately into the Miffifippi,

\$40

Miffifippi, the Wolf, Hatchee, Forked-Deer, Obian or Obean, and Reelfoot ; which are from 30 to 80 yards wide at their mouths; most of the rivers have exceedingly rich low grounds, at the extremity of which is a fecond bank, as on most of the lands of the Miffifippi. Befides thefe rivers, there are feveral fmaker ones, and innumerable creeks, fome of which are navigable. In fhort, there is hardly a fpot in this country, which is upwards of 20 miles diftant from a navigable fream. The chief mountains are Stone, Yellow, Iron, Bald, and Unaka, adjoining to one another, from the eastern boundary of the State, and feparate it from N. Carolina; their direction is nearly from N. E. to S. W. The other mountains are Clinch and Cumberland. It would require a volume to defcribe the mountains of this State, above half of which is covered with those that are uninhabitable. Some of these mountains, particularly the Cumberland, or Great-Laurel Ridge; are the most stupendous piles in the United States. They abound with ginleng and coal. The caverns and cafcades in thele mountains are innumerable, The Enchanted Moun-tain, about two prijes fouth of Brais Town, is famed for the curiofities on its rocks. There are on feveral rocks a number of impreffions refembling the tracks of turkies, bears, horfes, and human beings, as visible and perfect as they could be made on fnow or fand. The latter were remarkable for having uniformly fix toes each; one only excepted, which appeared to be the print of a negro's foot. By this we muft fuppofe the originals to have been the progeny of Titan or Anak. One of theie tracks was very large, the length of the foot 16 inches, the diftance of the extremes of the outer toes 13 inches, the proximate breadth behind the toes 7 inches, the diameter of the heel-hall 5. One of the horfe tracks was likewife of an uncommon fize, the transverse and conjugate diameters, were 8 by to inches; perhaps the horfe which the Great Warrior rode. What appears the moft in favour of their being the real tracks of the animals they represent, is the circumftance of a horfe's foot having apparently flipped feveral inches, and 'recovered again, and the figures having all the fame direction, like the trail of a 904

company on a journey. If it be a lufus natura, the old dame never sported more ferioufly. If the operation of chance, perhaps there was never more apparent defign. If it were done by art, it might be to perpetuate the remembrance of fome remarkable event of war, or engagement fought on the ground. The valt heaps of ftones near the place, faid to be tombs of warriors flain in battle, feem to favour the fupposition. The texture of the rocks is foft. The part on which the fun had the greatest influence, and which was the most indurated, could easily be cut with a knife, and appeared to be of the nature of the pipe ftone. Some of the Cherokees entertain an opinion that it always rains when any perfon vifits the place, as if fympathetic nature wept at the recollection of the dreadful cataftrophe which those figures were intended to commemorate. The principal towns are Knoxville, the feat of government, Nafhville, and Jonefborough, befides 8 other towns, which are as yet of little importance. In 1791, the number of inhabitants was estimated at 35,691. In November, 1795, the number had increased to 77,262 perfons. The foil is luxuriant, and will afford every production, the growth of any of the United States. The usual crop of cotton is Soolbs. to the acre, of a long and fine ftaple; and of corn, from 69 to 80 bufhels. It is afferted, however, that the lands on the imall rivers, that empty into the Mislifippi, have a decided preference to thole on Cumberland river, for the production of cutton, rice. and indigo. Of trees, the general growth is poplar, hickory, black and white walnut, all kinds of oaks, buckeye, beech, fycamore, black and honey locuft, afh, horn-beam, elm, mulberry, cherry, dogwood, faflafras, poppave, cucumber tree, and the fugar tree. The undergrowth, especially on low lands, is cane; fome of which are upwards of 20 feet high, and fo thick as, to prevent any other plant from growing. Of herbs, roots, and fhrubs, there are Virginia and Seneca Inakeroot, ginfeng, angelica, fpice-wood, wild plum, crab-apple, fweet annife, red-bud, ginger, fpikenard, wild hop and grape vines. The glades are covered with wild rye, wild pats clover, buffaloe grafs, ftrawberries and pea-vines. On

the hill in fome found 1 thefe ar feet cli fuch a States. with a among buffalo cat-fifh ed upw ern wa than th the fan to the 1 and he cool ar contigu this Sti weftern tains t render the pr indigo. both f There this is the in thole 1 which near t the fo he the remar on th The fpring parts (Saline. tricts fine fti ration upon about furnac mines on Fre ore pr The ver m canno them that g mine tracte people impre in v fai

ed

of

NC

by

e-

nt

he

ar

15 P-is

ad

38

ut le

he

it

te

at

ſ-

١.,

4

3-

1. :t

ie

it

٤.

đ

f

f

3

2

-

ŝ

the hills, at the head of rivers, and are numerous; and in the course of in fome high cliffs of Cumberland, are found majeftic red cedars; many of these are four feet in diameter, and 40 feet clear of limbs. The animals are fuch as are found in the neighbouring States. The sivers are well flocked with all kinds of fresh water fish; among which are trout perch, cat-fifh, buffaloe-fifh, red-horfe, cels, &cc. Some cat-fifh have been caught which weighed upwards of 100 pounds: the weftern waters being more clear and pure than the eaftern rivers, the fifh are in the fame degree more firm and favory to the taffe. The climate is temperate and healthful; the fummers are very cool and pleafant in that part which is contiguous to the mountains that divide this State from N. Carolina; but on the weftern fide of the Cumberland Mountains the heat is more intenfe, which renders that part better calculated for the production of tobacco, cotton and indigo. Lime-ftone is common on both fides of Cumberland Mountain. There are no ftagnant waters; and this is certainly one of the reasons why the inhabitants are not afflicted with thole bilious and intermitting fevers, which are fo frequent and often fatal, near the fame latitude on the coaft of the fouthern States. Whatever may be the caufes, the inhabitants have been remarkably healthy fince they fettled on the waters of Cumberland river. The country abounds with mineral fprings. Salt licks are found in many parts of the country. [See 'Campbell's Salines.] Iron ore abounds in the diftricts of Washington and Hamilton, and fine ftreams to put iron-works in operation. Iron ore was lately difcovered upon the fouth of Cumberland river, about 30 miles below Nafhville, and a furnace is now erecting. Several lead mines have been difcovered, and one on French Broad has been worked; the ore produced 75 per cent in pure lead. The Indians fay that there are rich filver mines in Cumberland Mountain, but cannot be tempted to difcover any of them to the white people. It is faid that gold has been found here; but the mine from which that metal was extracted is now unknown to the white people. Ores and fprings ftrongly impregnated with fnlphur are found in various parts. Saltpetre caves it, in the public councils of N. Carolina,

the year 1796, feveral tons of faltpetre were feat to the Atlantic markets. This country furnishes all the valuable articles of the fouthern States. Fine waggon and faddle horfes, beef cattle, ginfeng, deer-fkins and furs, cotton, hemp, and flax, may be transported by land ; allo iron, humber, pork and flour may be exported in great quantities, now that the navigation of the Miffinppi is opened to the citizens of the United States. But few of the inhabitants underftand commerce, or are poffeffed of proper capitals; of course it is as yet but badly managed. However, being now an independent State, it is to be hoped that the eyes of the people will foon be opened to their true intereft, and agriculture, commerce and manufactures will each receive proper attention. The Prefbyterians are the prevailing denomination of Chriftians; in 1788, they had 23 large congregations, who were then fupplied by only 6 minifters. There are also fome Baptifts and Methodifts. The inhabitants have paid great attention to the interests of fcience: befides private fchools, there are 3 colleges eftablished by law; Greenville in Green's co. Blount at Knoxville. and Washington in the county of that name. Here is likewife a " Society for promoting Ufeful Knowledge." A tafte for literature is daily increasing. The inhabitants chieflyemigrated from Pennfylvania, and that part of Virginia that lies weft of the Blue Ridge. The anceftors of these people were generally of the Scotch nation; fome of whom emigrated first to Ireland, and from thence to America. A few Germans and Englifh are intermixed. In 1788, it was thought there were 20 white perfons to one negro; and the disproportion is thought to be far greater now. This country was included in the ad charter of king Charles II. to the proprietors of Carolina. In a fubfequent division, it made a part of N. Carolina. It was explored about the year 1745, and fettled by about 50 families in 1754; who were foon after driven off or deftroyed by the Indians. Its fettlement re- commenced in 1765. The first permanent fettlement took place pear Long-Ifland of Holfton, and upon Watauga, about 1774; and the first appearance of any perions from

544/

TEN

was in the convention of that State in 1776. In the year 1780, a party of about to families, under the guidance and direction of James Robertson, (unce Brig. Gen. Robertion of Mero diffrict) paffed through a wilderness of at least oo miles to the French Lick, and there founded Nafhville. Their nearest neight bours were the fettlers of the infant State of Kentucky, between whom and them, was a wilderness of 200 miles. From the year 1784, to 1788, the government of N. Carolina over this country was interrupted by the affumed State of Frankland; but in the year 1789, the people returned to their allegiance. In 1789, N. Carolina ceded this territory to the United States, on certain conditions, and Congress provided for its government. A convention was held at Knoxville, in 1796, and on the 6th of Feb. the conftitution of the State of Tennelfee was figned by every member of it. Its principles promife to enfure the happinefs and profperity of the people. The following are the diftances on the new road from Nafhville in Davidson co. to Fort Campbell, near the junction of Holfton with the Tenneffee. Miles. Fro

m Nashville to Stoney -river	9
Big Spring -	ō
Cedar Lick -	4
Little Spring	6
Barton's Creek	4
Spring Creek	5
Martin's Spring -	5
Blair's Spring	5
Buck Spring	12
Fountaines	8
Smith's Creek	6
Coney River	11
Mine Lick	9
. Falling Creek	9
War Path -	7
Bear Creek	18
Camp Creek	8
King's Spring	16
Grovet's Creek	7
The foot of Cumb. Mount.	2
Through the mountain	
to Emmery's river, a	
branch of the Pelefon	11
To the Pappa Ford of the	
Peleion or Clinch river	12
To Campbell's Station	6.52
near Holftein -	10
To the Great Ifland	100
To Abingdon in Wash co.	35
To Richmond in Virginia	310
Total	.635

By this new road, a pleafant paffage may be had to the weftern country with carriages, as there will be only the Cumberland mountain to pafs, and that is eafy of afcent; and beyond it, the road is generally level and firm, abcunding with fine fprings of water. The Indian tribes within and in the vicinity of this State are the Cherokees and Chickafaws.

TENSAW, a fettlement near Mobile Bay, inhabited by 90 American families, that have been Spanish subjects fince 1783.

TEOMENISTA Creek, runs foutherly about 28 miles, then wefterly 6 miles, and empties into Alleghany river about 18 miles from its mouth, and nearly 5 below the Hickory town.

TEPEASA, a town of Mexico. See Angelos.

TEQUAJO, or Tiquas, a province of Mexico, according to fome Spanish travellers, being about lat. 37. where they found 16 villages.

TEQUEPA, a part of the coaft of New-Mexico, about 18 leagues N. W. of Acapulco.

TEQUERY Bay, on the fouth-east part of the coast of the island of Cuba, between Cape Cruiz, and Cape Maizi, at the east end. It affords good anchorage and fhelter for ships, but is not much frequented.

TERMINA, Laguna, or Lake of Tides, lies at the bottom of the Gulf of Campeachy, in the fouth-weft part of the Gulf of Mexico. It is within Triefte and Beef Island, and Port Royal Island. The tide runs very hard in, at most of the channels between the island; hence the name.

TERRA Blanca, a town of Mexico. See Angelos.

TERRA de Latraton, that is, the Ploughman or Labourer's Land, the name given by the Spaniards to Labrador or New-Britain, inhabited by the Efquimaux.

TERRA del Fuego Island, or Land of Fire, at the fouth extremity of S. America, is feparated from the main on the N. by the Straits of Magellan, and contains about 42,000 fquare miles. This is the largeft of the illands fouth of the Straits, and they receive this name on account of the valt fires and finoke which the first difcoveries of them perceived. The island of Staten Land lies on the east. They are all barren and mountainous a mountain feveral fo. variety o and iflan hills. H and a fp very we fmall che in fome ed with duck as loggerhe is here 1 with its the fea and ther TERI the mof rica, 1,4 breadth and 12 W. lon tic Ocer by the i Amazon Pacific from be difcover vided in rien, C ela, Con Popaya Bello,] an. I vince it Panam Sea, Po chief ri ta, Ma The c norther fultry c month fealon is alm der, ra cipitat ty, th pearan the co and thi fo imp that i about is extr this c parts the co poffib.

542

1316

·福祉的

Marker.

all.

127.22

Sec. A

4156

思生.

1.14

的风险

mountainous ; but there have been found feveral forts of trees and plants, and a variety of birds on the lower grounds and iflands that are fheltered by the hills. Here are found Winter's bark, and a species of arbutus which has a very well tafted red fruit of the fize of fmall cherries. Plenty of cellery is found in fome places, and the rocks are covered with very fine muscles. A species of duck as large as a goofe, and called the loggerhead duck at the Falkland Iflands, is here met with, which beats the water with its wings and feet, and runs along the fea with inconceivable velocity; and there are also geefe and falcons.

TERRA FIRMA, or Caftile del Oro, the most northern province of S. America, 1,400 miles in length, and 700 in breadth; fituated between the equator and 12 N. lat. and between 60 and 82 W. long. bounded N. by the N. Atlantic Ocean, here called the North Sea, E. by the fame ocean and Surinam, S. by Amazonia and Peru, and W. by the N. Pacific Ocean. It is called Terra Firma from being the first part of the continent difcovered by the Spaniards, and is divided into Terra Firma Proper, or Darien, Carthagena, St. Martha, Venezuela, Comana, Paria, New Granada, and Popayan. The chief towns are Porto Bello, Panama, Carthagena, and Popayan. The principal bays of this province in the Pacific Ocean, are those of Panama and St. Michael, in the North Sea, Porto Bello, Sino, Guiara, &c? The chief rivers are the Darien, Chagre, Santa, Maria, Conception, and Oronoko. The climate here, efpecially in the northern parts, is extremely hot and fultry during the whole year. From the month of May, to the end of Nov. the feafon called winter by the inhabitants, is almost a continual fuccession of thunder, rain and tempefts, the clouds precipitating the rain with fuch impetuofity, that the low lands exhibit the appearance of an ocean. Great part of the country is confequently flooded ; and this, together with the excellive heat, fo impregnates the earth with vapours, that in many provinces, particularly about Popayan and Porto Bello, the air is extremely unwholefome. The foil of this country is very different, the inland parts being very rich and fertile, and the coafts fandy and barren. It is impoffible to view without admiration, the

perpetual verdure of the woods, the huxuriancy of the plains, and the towering height of the mountains. This country produces corn, fugar, tobacco, &cc. and fruits of all kinds. This part of S. America was difcovered by Columbus in his third voyage to America. It was fubdued and fettled by the Spaniards about the year 1514, after deftroying, with great inhumanity, feveral millions of the natives.

TERRA FIRMA Proper, or Darien, a fubdivision of Terra Firma. Chieftowns, Porto Bello, and Panama. See Darien.

TERRA Magellanica. See Patagonia. TERRA Nieva, near Hudion's Straits, is in lat. 62. 4. N. and long. 67. W. whigh water, at full and change, a little before 10 0'clock.

TERRITORY North-West of the Obio, or North-Western Territory, a large part of the United States, is fituated between 37 and 50 N. lat. and between 81. 8. and 98. 8. W. long. Its greateft length is about 900 miles, and its breadth 700. This extensive tract of country is bounded north by part of the northern boundary line of the United States; east by the lakes and Pennfylvania; fouth by the Ohio river; weft by the Miffinppi. Mr. Hutchins, the late geographer of the United States, estimates that this tract contains 263,040,000 acres, of which 43,040,000 are water ; this deducted, there will remain 220,000,000 of acres, belonging to the Federal Government, to be fold for the difcharge of the national debt; except a narrow ftrfp of land bordering on the fouth of Lake Erie, and ftretching 120 miles weft of the weftern limit of Pennfylvania, which belongs to Connecticut. But a fmall portion of thefe lands is yet purchafed of the natives, and to be disposed of by Congress. Beginning on the meridian line, which forms the western boundary of Pennfylvania, feven ranges of townfhips have been furveyed and laid off by order of Congress. As a north and fouth line firikes the Ohio in an oblique direction, the termination of the 7th range falls upon that river, 9 miles above the Mufkingum, which is the first large river that falls into the Ohio. It forms this junction 172 miles below Fort Pitt, including the windings of the Ohio, though, in a direct line, it is but 90 miles. That part of this territory in which the Indian title is extinguished, - and TER

and which is fettling under the government of the United States, is divided into five counties as follows :-

Counties.	an.
Washington,	Bus
Hamilton,	190
St. Clair,	1017
Knox,	
Wayne,	. do

When erected. 1788 July 26th. 1790 Jan. 1790 April 27th. 1793 June 20th. 1796.

2d.

These counties have been organized with the proper civil and military officers. The county of St. Clair is divided into three diffricts, viz. the diffrict of Cahokia, the diffrict of Prairie-du-rochers, and the district of Kaskaskias. Courts of general quarter feffions of the peace, country courts of common pleas, and courts of probate, to be held in each of these districts, as if each was a diftinct county; the officers of the county to act by deputy, except in the diftrict where they refide. The principal rivers in this territory are Mufkingum, Hockhocking, Sciota, Great and Little Miami, Blue and Wabash, which empty into the Ohio; Au Vafe, Illinois, Ouifconfing, and Chippeway, which pay tribute to the Miffifippi, befides a number of finaller ones. St. Lewis, Kennomic, St. Joseph's, Bar-bue, Grand, Miami of the Lakes, Sandusky, Cayahoga, and many others which pass to the lakes. Between the Kafkafkias and Illinois rivers, which are 84 miles apart, is an extensive tract of level, rich land, which terminates in a high ridge, about 15 miles before you reach the Illinois river. In this delightful vale, are a number of French villages, which, together with those of St. Genevieve, and St. Louis, on the western fide of the Misflifippi, contained, in 1771, 1273 fencible men. The number of fouls in this large tract of country, has not been afcertained. From the best data the author has received, the population may be estimated, five years ago, as follows :

Indians, (fuppofe)	65,000	1792.
Ohio Company purchafe,	2,500	do.
Col. Symmes'fettlements,	, 2,000	do.
Galliopolis, (French fettlements) opposite the Kanhawy river,	Replective str	do.
Vincennes and its vici- nity, on the Wabafh,	f 1,500	do.
the second second with the state of the second s	Contraction of the local division of the loc	

Carry over 72,000

Source and

TER

Brought over 72,000 Kafkafkias and Cahokia, 680 17904 At Grand Ruiffeau, vil- 7 lage of St. Philip, and 140 do. Prairie-du-rochers,

Total 72,920

In 1790, there were in the town of Vincennes, about 40 American families and 31 flaves, and on the Miffifippi, 40 American families and 73 flaves, all included in the above eftimate. On the Spanish or western fide of the Missifippi, there were, in 1790, about 1800 fouls, principally at Genevieve, and St. Louis. The lands on the various rivers which water this territory, are interfperfed with all the variety of foil which conduces to pleafantness of fituation, and lays the foundation for the wealth of an agricultural and manufacturing people. Large level bottoms, or natural meadows, from 20 to 50 miles in circuit, are found bordering the rivers, and variegating the country in the interior parts. These afford as rich a foil as can be imagined, and may be reduced to proper cultivation with very little labour. The prevailing growth of timber, and the most useful trees, are maple or fugar-tree, fycamore, black and white mulberry, black and white walnut, butternut, chefunt; white, black, Spanish, and chefnut oaks, hickory, cherry, buckwood or horfe chefnut, honey-locuft, elm, cucumber trees, lynn tree, gum tree, iron wood, afh, afpin, faflafras, crab-apple tree, paupaw or cuftard apple, a variety of plum trees, nine bark fpice, and leather wood bufhes. White and black oak, and chefnut, with most of the above-mentioned timbers, grow large and plenty upon the high grounds. Both the high and low lands produce great quantities of natural grapes of various kinds, of which the fettlers univerfally make a fufficiency fer their own confumption, of rich red wine. It is afferted in the old fettlement of St. Vincent, where they have Irad opportunity to try it, that age will render this wine preferable to most of the European wines. Cotton is faid to be the natural production of this country, and to grow in great perfection. The fugar maple is the most valuable tree, for an inland country. Any number of inhabitants may be forever fupplied with a fufficiency of fugar, by preferving

Perving a fe family. A pounds of 1 is very tri water abou fmall and 1 other purpo as if by art in any of Very little any part of are no fwar dily drained meadow la frequent, t no where h They are c with a hea well adapte rye, indigc munication the fea, wi lowing dire the Scioto Erie, and fcribed und paffage up to the port leads to the towmack. will probal the executi for opening ters. 3. T falls into Thore, betv the Scioto tion from t 18 miles pe ters of Jan communic: Mufkingu be more uf portation fight and v ly, for the modities, the Chefap er than the ladelphia thick fettle vania *. Ohio and that fuit markets, 1 * A gen

a great trav nion that t ohimerical.

\$44

TER

Perving a few trees for the use of each ; family. A tree will yield about ten pounds of fugar a year, and the labour is very trifling. Springs of excellent water abound in this territory; and fmall and large ftreams, for mills and other purpoles, are actually interfperfed, as if by art, that there be no deficiency in any of the conveniencies of life. Very little wafte land is to be found inany part of this tract of country. There are no fwamps but fuch as may be readily drained, and made into arable and meadow land; and though the hills are frequent, they are gentle, and fwelling no where high or incapable of tillage. They are of a deep rich foil, covered with a heavy growth of timber, and well adapted to the production of wheat, rye, indigo, tobacco, &c. The communication between this country and the fea, will be principally in the 4 following directions . The route through the Scioto and Mufkingum to Lake Erie, and fo to the river Hudfon ; defcribed under New-York head. 2. The paffage up the Ohio and Monongahela to the portage above mentioned, which leads to the navigable waters of the Patowmack. This portage is 30 miles, and will probably be rendered much lefs by the execution of the plans now on foot for opening the navigation of those waters. 3. The Great Kanhaway, which falls into the Ohio from the Virginia thore, between the Hockhocking and the Scioto, opens an extensive navigation from the fourh-east, and leaves but 18 miles portage from the navigable waters of James' river, in Virginia. This communication, for the country between Mufkingum aud Scioto, will probably be more used than any other for the exportation of manufactures, and other fight and valuable articles, and efpecially, for the importation of foreign commodities, which may be brought from the Chefapeak to the Ohio much cheaper than they are now carried from Philadelphia to Carlifle, and the other thick fettled back counties of Pennfylvania *. 4. But the current down the Ohio and Miffifippi, for heavy articles that fuit the Florida and Weft-India markets, fuch as corn, flour, beef, lum-

A gentleman of much observation, and a great traveller in this country, is of opinion that this communication, or route, is chimerical. 545

ber, &c. will be more frequently loaded than any fireams on earth. The diftance from the Scioto to the Miffifippi, is 800 miles ; from thence to the fea, is goo. This whole courfe is eafily run. in 15 days; and the paffage up those rivers is not fo difficult as has ulually been reprefented. It is found, by late experiments, that fails are used to great advantage against the current of the Ohio; and it is worthy of obfervation, that in all probability fteam boats will be found to do infinite fervice in all our extensive river navigation. No country is better flocked with wild game of every kind. . The rivers are well ftored with fifh of various kinds, and many of them are of an excellent quality. They are generally large, though of different fizes; the cat-fifh, which is the largest, and of a delicious flavour, weighs from 6 to 80 pounds. The number of old forts, found in this western country, are the admiration of the curious, and a matter of much fpeculation. They are mostly of an oblong form, fituated on ftrong, well chofen ground, and contiguous to water. When, by whom, and for what purpole, thefe were thrown up, is uncertain. They are undoubtedly very ancient, as there is not the leaft visible difference in the age or fize of the timber growing on or within these forts, and that which grows without; and the oldeft natives have loft all tradition respecting them. The posts eftablished for the protection of the frontiers, and their fituation, may be feen on the map. By an ordinance of Congress, paffed on the 13th of July, 1787, this country, for the purpoles of temporary government, was erected into one district, fubject, however, to a division, when circumstances shall make it expedient. The ordinance of Congress, of July 13th, 1787, article 5th, provides that there shall be formed in this territory, not lefs than three, nor more than five States; and the boundaries of the States thall become fixed and effablished as follows, viz. the weftern State in the faid territory fhall be bounded on the Miffifippi, the Ohio and Wabafh rivers ; a direct line drawn from the Wabafh and Post Vincents due north to the territorial line between the United States and Canada, and by the faid territorial line to the Lake of the Woods and Mif-The middle State shall be filippi. Mm bounded bounded by the faid direct line, the Wa- | Miami river, running into the Ohioa bath from Poft Vincents to the Ohio; where commences the portage between by the Ohio by a direct line drawn due the Miami of the Ohio, and St. Mary's north from the mou h of the Great Miariver, which is a branch of the Miami mi to the faid territorial line, and by of the lake; thence a wefterly course to the faid territorial line. The eaftern State shall be bounded by the last mentioned direct line, the Ohio, Pennfylvania, and the faid territorial line : Provided however, and it is further underftood and declared, that the boundaries of the'e 3 States shall be subject fo far to be altered, that if Congress hereafter mail find it expedient, they fhall have authority to form 1 or 2 States, in that part of the faid territory which lies N. of an E. and W. line drawn through the foutherly bend or extreme of Lake Michigan; and when any of the faid States shall have 60,000 free inhabitants therein, fuch State shall be admitted by its delegates into the Congress of the United States, on an equal footing with the original States in all refpects whatever; and shall be at liberty to form a permanent conftitution and State goverment; provided the constitution and government to to be formed thall be republican, and in conformity to the principles contained in these articles; and so far as it can be confiftent with the general interest of the confederacy, fuch admiffion fhall be allowed at an earlier period, and when there may be a lefs number of free inhabitants in the State, than 60,000. See the Map. The fettlement of this country has been checked, for feveral years paft, by the unhappy Indian war, an amicable termination of which took place on the 3d of August, 1795, when a treaty was formed at Grenville, between Major Gen. Anthony Wayne, on the part of the United States, and the Chiefs of the following tribes of Indians, viz. the Wyandots, Delawares, Shawanoes Ottawas, Chippewas, Putawa-times, Miamis, Eel river, Weeas, Kickapoos, Plan Kashaws and Kaskaskias. By the third article of this treaty, the Indians cede to the United States, for a valuable confideration, all lands lying eastward and fouthward of a line " beginning at the mouth of Cayahoga river, and running thence up the fame to the portage between that and the Tulcarawas branch of the Mufkingum; thence down that branch to the croffing place above Fort Lawrence; thence westerly to a fork of that branch of the great !

\$46

Fort Recovery, which flands on a branch of the Wabalh, then fouth-wefte ly in a direct line to the Ohio, fo as to intericct that river opposite the mouth of Kentucky or Catawa river." Sixteen tracts of land of 6 and 12 miles fquare, interfperfed at convenient diftances in the Indian country, were, by the fame treaty, ceded to the United States, for the convenience of keeping up a friendly and beneficial intercourfe between the parties. The United States, on their part, " relinquish their claims to all other Indians lands northward of the river Ohio. eaftward of the Miflifippi, and weftward and fouthward of the Great Lakes and the waters uniting them, according to the boundary line agreed on by the United States and the king of Great Britain, in the treaty of peace made between them in the year 1783. But from this gelinquifhment, by the United States, the fellowing tracts of land are explicitly excepted. 1ft. The tract of 1.50,000 acres near the rapids of the Ohio river, which has been affigned to Gen. Clark, for the ule of himfelf and his war iors. 2d. The poft of St. Vincents on the river Wabafh, and the lands adjacent; of which the Indian title has been extinguished. 3d. The land at all other places in poffeffion of the French people and other white fettlers among them, of which the Indian title has been extinguished, as mentioned in the third article;, and 4th. The post of. Fort Maffac, towards the mouth of the Ohio. To which feveral parcels of land fo excepted, the faid tribes relinquifh all the title and claim which they or any of them may have." Goods to the value of 20,000 dolls. were delivered the Indians at the time this treaty was made; and goods to the amount of 9, 500 dolls. at first coft in the U. States, are to be delivered annually to the Indians at fome convenient place northward of the Ohio. A trade has been opened, fince this treaty, by a law of Congress, with the forementioned tribes of Indians, on a liberal footing, which promifes to give permanency to this treaty, and fecurity to the frontier inhabitants.

TES

TESTIGOS, iflands near the coaft of New Andalulia, in Terra Firma, on the fouth. fouth coal Weft-Indi the east er lie betweet Teltigos. TETER the island Iflands. S TETHY cific Ocea Venus in 1 17. 4. W TETZI TEUSI Indian vi Alleghany miles nort and 14 E. TEWK Wamefit, Maflachul cord river mack riv ton. It contains TEWK Jeriey, H of Leban bury cont ing 268 f THAM formed b Little, or Landing, for veffels thus far t the Than 14 miles, its weft t Ifland So of New-THAT mile east Ann, on forms th fetts Bay Annligh and long THEA of Illino of Fort : rich and it receiv and from affumes maps it T'HE' caft cor

fouth coaft of the Caribbean Sea, in the West-Indies. Several finall islands at the east end of the island of Margarita lie between that ifland and those called Teftigos. N. lat. 11. 6. W. long. 61.48.

TETEROA Harbour, on the W.fide of the island of Ulietes, one of the Society Iflands. S. lat. 16. 51.W. long. 151.27.

TETHUROA, an island in the S. Pacific Ocean, about 24 miles from Point Venus in the ifland of Otaheite. S. lat. 17. 4. W. long. 149. 30.

TETZEUCO, a brackish lake in Mexi-See Mexico. 80.

TEUSHANUSHSONG-GOGHTA, an Indian village on the northern bank of Alleghany river, in Pennfylvania, 5 miles north of the fouth line of the State, and 14 E. S. E. of Chatoughque Lake.

TEWKSBURY, called by the Indians, Wamefit, or Pawtukett, a township of Maffachufetts, Middlefex co. on Concord river, near its junction with Merrimack river, 24 miles northerly of Bofton. It was incorporated in 1734, and contains 958 inhabitants.

TEWESBURY, a township of New-Jerfey, Hunterdon co. The townships of Lehanon, Readington, and Tewkfbury contain 4,370 inhabitants, including 268 flaves,

THAMES River, in Connecticut, is formed by the union of Shetucket and Little, or Norwich rivers, at Norwich Landing, to which place it is navigable. for veffels of confiderable burden; and thus far the tide flows. From this place the Thames purfues a foutherly courfe 14 miles, paffing by New-London on its weft bank, and empties into Long-Ifland Sound ; forming the fine harbour of New-London.

THATCHER'S Mand, lies about a mile east of the fouth-east point of Cape Ann, on the coast of Massachusetts, and forms the northern limit of Maflachufetts Bay; and has 2 light-houfes. Cape Ann light-house lies in lat. 43.36. north, and long. 70. 47. weft.

THEAKIKI, the eaftern head water of Illinois river, rifes about 8 miles S. of Fort St. Joseph. After running thro' rich and level lands, about 112 miles, it receives Plein river in lat. 41. 48. N. and from thence the confluent ftream affumes the name of Illinois. In fome maps it is called Huakita.

THETFORD, a township in the fouthcaft corner of Orange co. Vermont, on THO

the western bank of Connecticut river about to miles north of Dartmouth College, and contains 862 inhabitants.

THOMAS's Bay, on the W. coaft of the island of Antigua. It affords fome fhelter from the S. and S. E. winds.

THOMAS Island, St. or the Danes Mand, is the largeft and most northerly of the Virgin Iflands, in the Weft-Indies, and is about 9 miles long and 3 broad. It has a fandy foil and is badly watered, but enjoys a confiderable trade, efpecially in time of peace, in the contraband way; and privateers in time of war fell their prizes here. A large battery has been erected for its defence, mounted with 20 pieces of cannon. N. lat. 18. 12. W. long. 64. 51. It has a fafe and commodious harbour, and lies about 30 miles eaft of the illand of Porto Rico.

THOM'AS Ifland, St. on the weft coaft of New-Mexico. N. lat. 20. 10. weft long. 113. 5.

THOMAS, St. a town of Guiana in S. America, fituated on the banks of the Oroonoko. N. lat. 75. W. long. 62. 36.

THOMAS, Port St. a harbour of the bay of Honduras, on the Spanish Main ; from which goods are fhipped to Europe.

THOMAS, St. the chief town of New-Andalufia, or Paria, in the northern division of Terra Firma.

THOMAS, St. a parifh of Charleston diffrict, in S. Carolina. It contains 3,836 inhabitants; of whom 197 are whites, and 3,405 flaves.

THOMASTOWN, a post-town of the Diffrict of Maine, Lincoln co. on the weft fide of Penobscot Bay, and about 4 leagues from Franklin Ifland, at the mouth of the river St. George, which divides this town from Warren and Cufhing, to the weftward. A confiderable river in the fouth-east part of the township is called Wessowessgeeg. From the hill of Madambettocks may be feen iflands and lands to a great diftance; and near it there is thought to be plenty of iron ore; but no attempts have been made to afcertain its quality. The grand staples of Thomastown are lime and lumber. Limeftone is very common, and fpots of land, or rather rock, of fix rods fquare, are frequently fold for 100 dollars. There are now about 35 kilns erected, each of which, on an average, will produce 200 fifty gallon cafks. Thefe kilns, if burned only Mm 2 three

fouth.

three times a year, (though many are five or fix times) will furnish about 21,000 cafks; which neat, atter all expenies, about 6 shilling a cask. Too much attention being paid to this bufinels, prevents a due cultivation of the lands. There are now owned on the river 12 brigs, fchooners, and floops, equal to about 1,100 tons, employed in foreign and coafting voyages. On the river, and its feveral ftreams, are a number of tide and other grift and faw mills, which afford great profit to their owners. A fort with a number of cannon, and a regular garrifon of provincials, was formerly stationed about 5 miles below the head of the tide. Few veltiges of the fort now remain; but in place of it an elegant building was crected in 1794, by the Hon. Henry Knox, Eiq. The fettlement of Thomastown began about 1720, in 1777 it was incorporated, in 1790 it contained 801 inhabitants ; and it was computed to contain in 1796 above 1,200. There are here no public schools constantly kept, though there are feveral private ones throughout the year. There are two churches, the one for Baptifts, who are the moft numerous, and the other for Congregationalifts. Here is also a focial library. The compact part of the town is 7 miles foutherly of Camden, 7 east of War-ren, 39 N. E. by E. of Wiscasset, 215 N. E. of Bofton, and 564 N. E. of Philadelphia.

THOME, St. or St. Themas, a plain in the centre of the ifland of St. Domingo, in the Weff-Indies, on the fouth fide of the first chain of the mountains of Cibao, near which Artibonite river takes its rife. It is contiguous to the north of that of St. John of Maguana. The fort of St. Thomas was erected here, near the head of the Artibonite, by Christopher Columbus to protect the mines against the Indians. There is now no vestige of the fort remaining.

THOMPSON, a township of Windham to. in the north east corner of Connecticut; having the town of Killingly on the fouth, the State of Rhode-Island east, and that of Massachusetts on the north; from which lass it receives Quinabaug and Five-mile rivers.

THOPICANOS, a fmall river of the N · W. Territory, which runs fouthward to Wabash river, into which it enters a few miles caftward of Ouixtanon.

THORNTON, a township of New-Hampshire, in Gratton co. at the head of Merrimack river, which contains 385 inhabitants. It was incorporated in 1781.

1 50

CH

THOULOUSE, Port, on the S. coaft of the island of Cape Breton, near the entrance of the Strait of Fronfac or Canfo, lies between the guli called Little St. Peter and the islands of St. Peter. It was formerly called Port St. Peter, and is 60 miles weft of Gabaron Bay.

THOUSAND Ides are fituated in St. Lawrence, or Iroquois river, a little north of Lake Ontario.

THOUSAND Lakes, a name given to a great number of fmall lakes near the Miffilippi, a little to the N. E. of St. Francis river, which is about 60 miles above St. Anthony's Falls. The country about these lakes, though but little frequented, is the beft within many miles for hunting; as the hunter feldom fails returning loaded beyond his expectation. Here the river Miflifippi is not above 90 yards wide.

THREE Brothers, three islands within the river Essequibo, on the E. coast of S. America.

THREE *Islands Bay*, or *Harbour*, on the E. coaft of the island of St. Lucia, in the Weft-Indies.

THREE Points, Cape, on the coast of Guiana, in S. America. N. lat. 10. 38. W. long. 61. 57.

THREE Rivers, in Canada. See Trois Rivieres.


THREE Sifters, three fmall isles on the W. shore of Chefapeak Bay, which lie between West river and Parker's island.


THRUM Cap, in the S. Pacific Ocean, a finall circular ifle, not more than a mile in circumference, 7 leagues N. 62° W. from Lagoon ifland. High water, at full and change, between 11 and 12 o'clock. S. lat. 18. 35. W. long. 139. 48.


THULE, Southern, an island in the S. Atlantic Ocean, the most foutherly land ever discovered; hence the the name. Solat. 59. 34. W. long. 27. 45.

THURMAN, a township in Washington county, New York; taken from Queensburg, and incorporated in 1792.

THUNDER Bay, in Lake Huron, lies about half way between Sagana Bay and the N. W. corner of the lake; it is about 9 miles across either way; and is thus







thus called from heard there. . TROGA Point coaft of New-N land, 8 leag. from TIANADERH

River. TIAOGU, an about 150 miles river.

TIBER Creek, cuns foutherly th ington, and enriver. Its fourlevel of the tide i of which, and th may be convey houfe, and to the

TIBERON, Co on the S.W. part fula of the illand forms the N. W Tiberon.

TIBERON, OF lage on the S. W St. Domingo. the cape of its na Point Burgau on three-fourths apa a river, falls in at the western fide ftands on the hig to its courfe al leagues fouth of 4 from Jeremie, and the road from Le in lat. 18, 20. 30 52. 40. W. The beron, from Jan. 1 the fame year, we -377,800lbs bro coffee-13,6721bs digo-and fmall able amount To exportation, 2,46

TIBERON, a fo village above men French, the 2 of 1 TICKLE Harbo

of Newfoundland, Bonaventura Port

TICKLE Me & British feamen to bay of Terra Firm Darien, at the N. rocks, having goo lauding. The er on one fide, and t (the range of white thus called from the thunder frequently heard there.

TROGA Point, or Cape, on the weft coaft of New-Mexico, is a rough head

land, 8 leag. from the valley of Colima. TIANADERHA River. See Unadilla River.

TIAOGU, an ancient Indian town, about 150 miles up the Suiquehannah river.

TIBER Creek, a finall ftream which runs foutherly through the city of Wafhington, and empties into Patowmac river. Its source is 236 feet above the level of the tide in the creek ; the waters of which, and those of Reedy Branch, may be conveyed to the Prefident's houfe, and to the capitol.

TIBERON, Cape, a round black rock on the S.W. part of the fouthern penin-fula of the ifland of St. Domingo, and forms the N. W. limit of the bay of Tiberon.

TIBERON, or Tiburon, a bay and village on the S. W. part of the illand of St. Domingo. The bay is formed by the cape of its name on the N. W. and **P**oint Burgau on the S. E. a league and three-fourths apart. The ftream, called a river, falls in at the head of the bay, on the western fide of the village ; which ftands on the high road, and, according to its courfe along the fea fhore, 10 leagues fonth of Cape Dame Marie, 20 from Jeremie, and 32 by the winding of the road from Les Cayes. The cape is in lat. 18. 20. 30. N. and in long. 76. 52. 40. W. The exports from Cape Tiberon, from Jan. 1, 1789, to Dec. 31, of the fame year, were 1 coolbs white fugar -377,800lbs brown fugar-600,002lbs coffee-13,672lbs cotton-1,088lbs in-digo-and fmall articles to a confiderable amount Total value of duties on exportation, 2,465 dollars 76 cents.

TIBERON, a fort, near the town or village above mentioned; taken by the French, the zift March, 1795.

TICKLE Harbour, on the east coaft of Newfoundland, filteen leagues from Bonaventura Port.

TICKLE Me Quickly, a name given by British seamen to a fine, little, fandy bay of Terra Firma, on the Ifthmus of Darien, at the N. W. end of a reef of rocks, having good anchorage and fafe landing. The extremity of the rocks on one fide, and the Samballas Iflands

on the other fide, guard it from the fea, and fo form a very good harbour. It is much frequented by privateers.

TICONDEROGA, in the State of New-York, built by the French in the year 1756, on the north fide of a peninfula, formed by the confluence of the waters iffuing from Lake George into Lake Champlain. It is now a heap of ruins, and forms an appendage to a farm. Its name fignifies Noify, in the Indian language, and was called by the French Corillor. Mount Independence, in Addifon co. Vermont, is about 2 miles S.E. of it, and leparated from it by the narrow firait which conveys the waters of Lake George and South river into Lake Champlain. It had all the advantages that art or nature could give it, being defended on 3 fides by water furrounded by rocks, and on half of the fourth by a fwamp, and where that fails, the French erected a breast-work 9 feet This was the first fortress athigh. tacked by the Americans during the revolutionary war. The troops under Gen. Abercrombie were defeated here in the year 1758, but it was taken the year following by Gen. Amherst. It was furprifed by Cols. Allen and Arnold, May 10, 1775, and was retaken

by Gen. Burgoyne in July, 1777. TIERRA Aufral del Espiritu Santo, called by Bougainville, The Archipelago of the Great Cyclades, and by Captain Cook, The New Hebrides, may be confidered as the eaftern extremity of the vaft Archipelago of New Guinea .--Thefe islands are fituated between the latitudes of 14° 29' and 20° 4' S. and be-tween 169° 41' and 170° 21' E. long. from Greenwich, and confift of the following iflands, fome of which have received names from the different European navigators, and others retain the names which they bear among the natives ; viz. Tierra Auftral del Espiritu Santo, St. Bartholomew, Mallicollo, Pic de l'Etoile, Aurora, Ifle of Lepers, Whitfuntide, Ambrym, Paoon, Shepherds Ifles, Sandwich, Erromango, Immer, Tana, Erronan, Annetom, Apce, Three Hilis, Montagu, Hinchmbrook, and Erromanga. Quiros, who first difcovered thefe illands, in 1606, defcribes them, as " richer and more fertile than Spain, and as populous as they are fertile; watered with fine rivers, and pro-(the range of which begins from hence) | ducing filver, pearls, nutmegs, mace, Mm 3

pepper,

pepper, ginger, ebony of the first quali-ty, wood for the construction of veffels, and plants which might be fabricated into tail cloth and cordages, one fort of which is not unlike the hemp of Europe," The inhabitants of these islands, he deferibes, as of feveral different races of men; black, white, mulatto, tawny, and copper-coloured ; a proof, he fuppofes, of their intercourfe with various people. They use no fire-arms, are employed in no mines, nor have they any of those means of destruction which the genius of Europe has invented. Induftry and policy feem to have made but little progrefs among them : they build neither towns nor fortreffes; acknowledge neither king nor laws, and are divided only into tribes, among which there does not always fublift a perfect harmony. Their arms are the bow and arrows, the fpear and the dart, all made of wood .- Their only covering is a garment round the waift, which reaches to the middle of the thigh. They are cleanly; of a lively and grateful difposition, capable of friendship and instruction. Their houses are of wood, covered with palm leaves. They have places of worfhip and burial. work in ftone, and polifh marble, of They which there are many quarries. make flutes, drums, wooden spoons, and from the mother of pearl, form chiffels, fciffars, knives, hooks, faws, hatchets, and fmall round plates for necklaces. Their canoes are well built and neatly finished. Hogs, goats, cows, buffaloes, and various fowls and fifh, for food, are found in abundance on and about these islands. Added to all these and many other excellenties, thefe iflands are reprefented as having a remarkably falubrious air, which is evinced by the healthy, robust appearance of the inhabitants, who live to a great age, and yet have no other bed than the earth. Such is the description which Quiros gives of these islands, in and about which he fpent fome months, and which he represents to the King of Spain as " the most delicious country in the world; the garden of Eden, the inexhauftible fource of glory, riches, and power to Spain." . On the north fide of the largest of these islands, called Espiritu Santo, is a hay, called San Felipe and Sant-Yago, which, lays Quinos, " penetrates 20 leagues into the in Luzern co.

country; the inner part is all fafe, and may be entered with fecurity, by night as well as by day. On every fide, in its vicinity, many villages may be diftinguifhed, and if we may judge by the imoke which rifes by day, and the fires that are feen by night, there are many more in the interior parts." The harbour in this bay, was named by Quiros, La Vera Cruz, and is a part of this bay, and large enough to admir 1000 veffels. The anchorage is on an excellent bottom of black fand, in water of different depths, from 6 to 40 fathoms, between two fine rivers.

TIGNARES, the chief town of the captainship of Rio Grande in Brazil.

TIMMISKAMAIN Lake, in Lower-Canada, is about 30 miles long and 10 broad, having feveral finall iflands. Its waters empty into Utawas river, by a fhort and narrow channel, 30 miles N. of the N. part of Nepifing lake. The Indians named Timmifcamaings refide round this lake.

TINICUM, two townships of Pennfylvania; the one in Buck's county, the other in that of Delaware.

TINKER'S *Ifland*, one of the Elizabeth Iflands, on the coaft of Maffachufetts, off Buzzard's Bay, 8 miles from the main land of Barnftable county. It is the fecond in magnitude, and the middle one of the 3 largeft. It is about 3 miles long from north to fouth, and about a mile and a half broad from eaft to weft; and between this and Nafhawn Ifland is a channel for floops and fmall veffels, as there is alfo between it and Slocum's Ifland, about a mile farther to the weftward.

TINMOUTH, a township of Nova-Scotia on the castern coast. It was formerly called Pictou, and lies about 40 miles from Truro. See Pictou.

TINMOUTH, a township of Vermont, Rutland c. and contains 935 inhabitants,

TINSIGNAL, a rich filver mine in the province of Cotta Rica; which fee.

TINTA, a jurifdiction in the empire of Peru ; wherein is the famous filver mine called Condonoma. See *Cancas*.

TINTAMARE, a river of Nova-Scotia, which is navigable 3 or 4 miles up for finali veficis.

TINTO, a river of Terra Firma, 20 leagues to the cafe of Cape Honduras.

TIOGA, a township of Pennsylvania, in Luzern co.

TIOGA,

ht

in

if-

he

les

ny

Ir-

ni-

iis

00

el-

of

15,

he

:r-

10

Its.

1 a

of

n-

de

n-

he

3-

u-

m

It

he

ut

nd

aft

h-

nd

it

r-

2-

25

ut

it,

he

of

ne

a,

or

10

8.

4.

TIDGA, aco. of New-York, boundad east by Otlego, welt by Ontario north by Onondago, and fouth by the State of Pennfylvania. It contains the towns of Newtown, Union, Chemung, Owego, Norwich, Jerico, and Chenengo, in which are 1,165 electors, according to the State cenfus of 1796. The courts of common pleas and general feifions of the peace for the county are held on the first Tuesdays in May, October, and February, in every year, alternately, at Chenengo, in the town of Union, and at Newtown Point, in the town of Chemung. Some curious bones have been dug up in this county. About 12 miles from Tioga Point, the hone or horn of an animal was found, 6 feet 9 inches long, 21 inches round, at the long end, and 15 inches at the finall end. It is incurvated nearly to an arch of a large circle. By the prefent fate of both the ends, much of it must have perifhed ; probably 2 or 3 feet from each end.

TIOGA Point, the point of land formed by the confluence of Tioga river with the east branch of Sulquehannah river. It is about 51 miles foutherly from the line which divides New-York State from Pennfylvania, and is about 1 50 miles N. by W. of Philadelphia, and 20 S. E. of Newtown. The town of Athens stands on this point of land. TIOGA River, a branch of the Sufquehannah, which rifes in the Allegha. ny Mountains, in about lat. 42. and running eaftwardly, empties into the Sufquebannah at Tioga Point, in lat. 41. 57. It is navigable for boats about 50 miles. There is faid to be a practicable communication between the fouthern branch of the Tioga, and a branch of the Alleghany, the head waters of which are near each other. The Seneca Indians fay they can walk 4 times in a day, from the boatable waters of the Alleghany, to those of the Tioga, at the place now mentioned.

TIOUGHNIOGA River. See Chenengo River.

TLOOKEA, an illand in the South Pacific Ocean, one of those called George's Iflands. S. lat. 14. 27. W. long. 144. 56.

TIPUANY's River. See Tarija.

TISBURY, a fmall fifting town on the fouth fide of the ifland of Martha's Vineyard, 9 miles from Chilmark, and

97 from Bolton. The township was incorporated in 1671, and contains 1143 inhabitants. It is in Duke's count Maffachufetts, and in 1796 the easterly

part was incorporated into a leparate

TIT

townfhip. TISCAN, a village of Ovenca, and department of Alanfis, in Quito, in South-America, which was entirely deftroyed by an earthquake, but the inhabitants cicaped, and removed to a fafer fituation. The marks of this dreadful convullion of nature are ftill vifible.

TITICACA, an ifland of S. America, in the South Pacific Ocean, near the coalt of Peru.

TITICACA, or Chucuito, a lake of Charcas, in Peru; and is the largeft of It all the known lakes in S. America. is of an oval figure, with an inclination from N. W. to S. E. and about \$0 leagues in circuit. The water is, in fome parts, 70 or 80 fathoms deep. Ten or twelve large, befidee a greater number of imaller streams fall into it. The water of this lake, though neither falt nor brackish, is muddy, and has fomething to naufeous in its tafte, as not to be drank. One of the most splendid temples in the empire was erected on an ifland in this lake, by the Yncas. The Indians, on feeing the violent rapacity of the Spaniards, are thought to have thrown the immense collection of riches in the temple, into this lake. But thefe valuable effects were thrown into an. other lake, in the valley of Orcos, 6 leagues S. of Cuico, in water 23 or 24 fathoms deep. Towards the S. part of Titicaca Lake, the banks approach one another, to as to form a kind of bay, terminating in a river, called El Defaguadero, or the drain; and afterwards forms the Lake of Paria, which has no visible outlet. Over the river El Defa guadero ftill remains the bridge of rufh es, invented by Capac-Yupanqui, the fifth Ynca, for transporting his army to the other fide, in order to conquer the provinces of Collafuyo. The Defagua dero is here between 80 and 100 yards in breadth, flowing with a very impetuous current, under a fmooth, and, as it were, fleeping furface. The Ynca, to overcome this difficulty, ordered 4 very large cables to be made of a k nd of grais, which covers the lofty heaths and mountains of that country, and by the Indians called Ichu : fo that thefe cables Mm 4

were

were the foundation of the whole ftrueture. Two of these being laid across the water, fascines of dry juneira, and totora, two species of rushes, were fastened together, and laid across the cables. On this again the two other cables were laid, and covered with fimilar. fascines securely fastened on, but of a finaller fize than the first, and arranged fo as to form a level furface. And by this means the Ynca procured a fafe palfage for his army. This bridge of rufhes, which is about five yards broad, and one yard and a half above the furface of the water, is carefully repaired, or rebuilt, every fix months by the neighbouring provinces, in purfuance of a law made by that Ynca; and fince often confirmed by the kings of Spain, on account of its vaft ufe, it being the channel of intercourfe between those provinces on each fide the Defaguadero.

TIVERTON, a townfhip of Rhode-Ifland, in Newport co. having the caffern Paffage and part of Mount Hope Bay on the W. and N.W. the State of Malfachufetts on the N. and E. and Little-Compton townfhip on the fouth. It contains 2,453 inhabitants, including 25 flaves. It is about 13 miles N. N. E. of Newport.

TIZON, a river in the N. W. part of S. America, 600 miles from New-Spain. In a journey made thus far, in 1606, the Spaniards found fome large edifices) and met with fome Indians who fpoke the Mexican language, and who told them, that a few days journey from that river, towards the N. was the kingdom of Tollan, and many other inhabited places, whence the Mexicans migrated. It is, indeed, confirmed by Mr. Stewart, in his late travels, that there are civilized Indians in the interior parts of America. Beyond the Miffouri, he met with powerful nations, who were courteous and hospitable, and appeared to be a polished and civilized people, having regularly built towns, and enjoying a state of fociety not far removed from the European; and indeed to be perfectly equal wanted only iron and ficel

TLASCALA, or Los Angelos, a province of New-Spain. See Angelos.

TOA, one of the two rivers, Bajamond being the other, which empty into the harbour of Porto Rico, in the island of that name in the West-Indics.

TOAHOUTU, one of the two fmall

TOB

istands to the N. eastward of the S. end of Otaha Island, one of the Society Islands, in the S. Pacific Ocean.

TOAMENSING, two townships of Pennsylvania; the one in Montgomery co. the other in that of Northampton.

TOBAGO, an island in the Weft-Indies, which, when in the hands of the Dutch, was called New Valcheren, is. about 10 leagues to the N. of Trinidad. and 40 S. of Barbadoes. Its length is about 32 miles, but its breadth only about 12, and its circumference about So miles. The climate is not fo hot as. might be expected to near the equator ; and it is faid that it lies out of the courte of those hurricanes that have fometimes. proved fo fatal to the other Weft-India. Iflands. It has a fruitful foil, capable of producing fugar, and indeed every thing elie that is raifed in the West-India Iflands, with the addition (if we may believe the Dutch) of the cinnamon, nutmeg, and gum copal. It is. well watered with numerous fprings ; and its bays and rivers are fo disposed. as to be very commodious for all kinds. of fhipping. The value and impor-tance of this ifland, appears from the extensive and formidable armaments. fent thither in support of their different. claims. It feems to have been chiefly poffeffed by the Dutch, who defended their pretentions against both England. and France, with the most obstinate perseverance. By the treaty of Aix la. Chapelle, in 1748, it was declared neutral; though by the treaty of 1763, it. was yielded up to Great Britain; but. in June, 1781, it was taken by the French, and ceded to them by the treaty of 1783; and captured by the British in 1793. N. lat. 11. 16. W. long. 60. 30.

TOBAGO Island, Little, near the N. E. extremity of Tobago Island, in the Weit Indies. It is about two miles long, and one broad.

TOBY'S Creek, and eaftern branch of Alleghany river, in Pennfylvania: its iouthern head water is called Little Toby's Creek. It runs about 55 mi es in a W.S. W. and W. courfe, and enters the Alleghany about 20 miles below Fort Franklin. It is deep enough for batteaux for a confiderable way up, thence by a fhort paffage to the W. branch of Suiquehannah, by which a good communication is formed between. Ohio

fylvania.

nel

etye

of

ery

n-

he

is.

ıd,

is

ly

ut

as,

r ;,

rie

les.

lia.

ble

гу

Æ-

Ne

a-

is.

3 ;

ed.

ds.

r--

ne

ts.

nt;

ly.

d

ıd,

te

la

1-

it.

at.

e.

e

e:

٠,

I.,

c

8

f

8

e

\$

-

v

r

,

8.1

n,

24

TOCAYMA, a city of Terra Firma, and in New Granada.

TOGOSAHATCHEE Creek, a water of Oakmulgee river, in Georgia.

TOLLAND, a county of Connecticut, bounded N. by the State of Maffachufetts, S. by New-London co. E. by Windham, and W. by Hartford co. It is fubdivided into g townships, and contains 13,106 inhabitants, including 47 flaves. A great proportion of the county is hilly, but the foil is generally ftrong and good for grazing.

TOLLAND, the chief town of the above county, was incorporated in 1715, and is about 18 miles N. E. of Hartford. It has a Congregational church, courthouse, gaol, and 20 or 30 houses, compactly built, in the centre of the town. TOLU, a town of Terra Firma, S. America, with a harbour on a bay of the N. Sea. The famous balfam of the fame name comes from this place ; 114 miles S. W. of Carthagena. N. lat. 9. 36. long. 75. 22.

TOMACO, a large river of Popayan, and Terra Firma, S. America, about 9 miles N. E. of Galla Ifle. About a league and a half within the river is an Indian town of the fame name, and but finall, the inhabitants of which commonly fupply fmall veffels with provisions, when they put in here for refreshment.

TOMAHAWK Island, on the east coast of Patagonia, is 24 miles N. E. of Seal's Bay

TOMBA River, on the coaft of Peru, is between the port of Hilo and the river of Xuly or Chuly. There is anchorage against this river in 20 fathoms, and clean ground. Lat. 17. 50. S.

TOMBIGBEE River, is the dividing line between the Creeks end Chactaws. Above the junction of Alabama and Mobile rivers, the latter is called the Tombigbee river, from the fort of Tombigbee, fituated on the weft fide of it, about 96 miles above the town of Mo-The fource of this river is reck. bile, oned to be 40 leagues higher up, in the country of the Chickafaws. The fort of Tombigbee was captured by the British, but abandoned by them in 1767. The river is navigable for floops and schooners, about 35 leagues above the town of Mobile : 130 American fami-

Ohio, and the eaftern parts of Penn- lies are fettled on this river, that have been Spanish subjects since 1783.

TON

TOMINA, a jurifdiction in the archbishopric of La Plata in Peru. It begins about 18 leagues S. E. from the city of Plata; on its eaftern confines dwell a nation of wild Indians, called Chiriguanos. It abounds with wine, fugar and cattle,

TOMISCANING, a lake of N. America, which fends its waters fouth-eastward through Ottawas river, into Lake St. Francis in St. Lawrence river. The line which feparates Upper from Lower Canada, runs up to this lake by a line drawn due north, until it firikes the boundary line of Hudion's Bay, or New-Britain.

TOMPSONTOWN, a village of Pennfylvania, in Mifflin co. containing about a dozen houses. It is 22 miles from Lewistown.

TOM's Creek, in New Jerley, which feparates the towns of Dover and Shrewfbury.

TONDELO, a river at the bottom of the Gulf of Campeachy, in the S. W. part of the Guit of Mexico; 15 miles due weft of St. Annes, and 24 eaft of Guafickwalp. It is navigable for barges and other veffels of from 50 to 60 tons.

TONEWANTO, the name of a creek and Indian town, in the north-weftern part of New-York. The creek runs a westward course and enters Niagara river oppofite Grand Ifland, 8 miles N. of Fort Erie. It runs about 40 miles, and is navigable 28 miles from its mouth. The town stands on its S. fide, 18 miles from Niagara river. Also the Indian name of Fishing Bay, on Lake Ontario.

TONGATABOO, one of the Friendly. Iflands, in the S. Pacific Ocean, about 60 miles in circuit, but rather oblong, and wideft at the eaft end. It has a rocky coaft, except to the N. fide, which is full of fheals and iflands, and the fhore is low and fandy. It furnishes the best harbour or anchorage to be found in these islands. The island is all laid out in plantations, between which are roads and lanes for travelling, drawn in a very judicious manner for opening an easy communication from one part of the island to another. S. lat. 21. 9. W. long. 174. 46. Variation of the needle, in 1777, was 9. 53. E.

TONICAS. See Point Coufee.

TONTI, an island at the mouth of Lake Lake D'Urfe, at the eaftern extremity of Lake Ontario, is within the Britifh territories; 11 miles N. E. of Point au Goelans, and 12 W. of Grand Ifland, having feveral ifles between it and the latter.

TONTI, or Tonty, a river which empties through the N. thore of Lake Erie; 22 miles W. by N. of Riviere a la Barbue.

TONTORAL, Cape, on the coaft of Chili, in S. America, 25 leagues to the N. of Guafca, and in lat. 27. 30. S.

TOOBAUAI, one of the Society IAands, in the S. Pacific Ocean, not more than 5 or 6 miles acrois in any part. S. lat. 23, 25. W. long. 149. 23.

TOOSCHCONDOLCH, an Indian vil-Jage on the N. W. coaft of N. America, of confiderable importance in the furtrade; fituated on a point of land between two deep founds. N. lat. 53. 2. W. long. 131. 30.

TOOTOOCH, a fmall low island in Nootka Sound, on the N. W. coaft of North-America, on the eastern fide of which is a confiderable Indian village; the inhabitants of which wear a garment apparently composed of wool and hair, moftly white, well fabricated, and probably by themselves.

TOPIA, a mountainous, barren part of New-Bifcay province in Mexico, North-America; yet mott of the neighbouring parts are pleafant, abounding with all manner of provisions.

TOPSFIELD, a township of Massachusetts, Effex co. containing 780 inhabitants. It is 8 miles westerly of Ipswich, and 39 N. by E. of Boston.

TOPSHAM, a township of Vermont, in Orange co. west of Newbury, adjoining. It is watered by fome branches of Wait's river, and contains 162 inhabitants.

TOPSHAM, a township of the District of Maine, in Lincoln co. 32 miles in eircumference, and more than 25 miles is washed by water. It is bounded on the N. W. by Little river; N. by Bowdoin, and Bowdoinham; E. by Cathance and Merry Meeting Bay; S. and S. W. by Amarifcoggin river, which feparates it from Bruntwick in Cumberland county. The inhabitants amount to 826 fouls, and they live in such easy circumstances, that none have ever been fo poor as to folicit help from the pa rift. It was incorporated in 1764. A

few English attempted to fettle here in the end of the last, or beginning of the prefent century. These were cut off by the natives. Some families ventured to fettle in this hazardous fituation in 1730; from which period, until the peace of 1763, the inhabitants never felt wholly secure from the natives. It is 37 miles S. by W. of Hallowell, and 156 N. by E. of Boston 1 and is nearly in lat. 44. N. and long. 70. W.

TORBAY, a town on the eaftern coaft of Nova-Scotia; 22 miles S. W. of Roaring Bull Island, and 100 N. E. of Halifax.

TORBER, a village on the fouth fide of the fouth peninfula of the ifland of St. Domingo; 3 leagues N. W. of Avache Ifland.

TORMENTIN Gape, on the W. fide of the Straits of Northumberland, or Sound, between the island of St. John's and the E. coast of Nova Scotia, is the N. point of the entrance to Bay Vert. It is due well from Governor's Island, on the S. E. coast of the island of St. John's. In fome maps this point is called Cape Storm.

TORONTO, a British settlement on the north-western bank of Lake Ontario, 53 miles N. by W. of Fort Niagara. N. lat. 44. 1. W. long. 79. 10.

TORRINGTON, or Bedford's Bay, on the fouthern coaft of Nova-Scotia, and its entrance is at America Point, about 3 miles N. of the town of Halifax. It has from 10 to 13 fathoms at its mouth, but the bay is almost circular, and has from 14 to 50 fathoms water in it. A prodigious fea fets into it in winter.

TORRINGTON, a township of Connecticut, in Litchfield co. 8 miles N. of Litchfield.

TORTOISES, the River of, lies 10 miles above a lake 20 miles long, and 8 or 10 broad, which is formed by the Mifflippi in Louifiana and Florida. It is a large fine river, which runs into the country a good way to the N. E. and is navigable 40 miles by the largeft boats.

TORTUE, an island on the N. fide of the island of St. Domingo, towards the N. W. part, about 9 leagues long from E. to W. and 2 broad. The W. end is nearly 6 leagues from the head of the bay of Moffique. The free-booters and buccaniers drove the Spaniards from this island in 1632; in 1638, the Spaniards loured To Harbo coaft o league cape o and th the gu To

it, is i of St. To the W ra Fir about about

the gr

W. 1 weft of from the are m north To Chili,

is the quimb Pajary round fhips over a called fhelte or 30 200 t

To water is ca

tugas

miards maffacred all the French colony ; and in 1639, the buccaniers retook Tortue. In 1676, the French took polfeffion of it again.

ed

in

he

lt

is

d

y

A

of

of

de

øf

a.,

dé

or

°s.

he

t.

d,

t.

is

DI

a-

a -

on

١d

ut

It

h,

38

A

n-

of

10

8

he

It

he

nd

eft

of

he

m

nd

he

18

m

da

TORTUGAS, Dry, fhoals to the weftward, a little foutherly from Cape Florida, or the S. Point of Florida, in South-America. They are 134 leagues from the bar of Penfacola, and in lat. 24. 32. N. and long. 83. 40. W. They confift of 10 imall iflands or keys, and extend E. N. E. and W. S. W. 10 or II miles; most of them are covered with bushes, and may be feen at the diftance of four leagues. The fouth weth key is one of the imalleft, but the mott material to be known, is in lat. 24. 32. N. and long. 83. 40. W. From the S. W. part of this key, a reef of coral rocks extends about a quarter of a mile; the water upon it is visibly difcoloured.

TORTUGAS HARBOUR, Turtle's Harbour, or Barrace de Tortugas, on the coaft of Brazil, in S. America, is 60 leagues at E. S. E. from the point or cape of Arbrasec, or Des Arbres Sec, and the shore is flat all the way from the guif of Maranhao.

TORTUGAS, an illaud fo named from the great number of turtle found near it, is near the N. W. part of the illand of St. Domingo. See *Tortue*.

TORTUGAS, or Sal Tortuga, is near the W. end of New-Andalufia and Terra Firma. It is uninhabited, although about 30 miles in circumference, and abounding with falt. N. lat. 11. 36. W. long. 65. It is 14 leagues to the well of Margaritta Ifland, and 17 or 18 from Cape Blanco on the main. There are many illands of this name on the north coaft of South-America.

TORTUGAS Point, on the coaft of Chili, and in the South Pacific Ocean, is the fouth point of the port of Coquimbo, and 7 or 8 leagues from the Pajaros Iflands. Tortugas road is round the point of the fame name, where fhips may ride in from 6 to 10 fathoms, over a bottom of black fand, near a rock called the Tortugas. The road is well fheltered, but will not contain above 20 or 30 fhips fafely. Ships not more than 200 tons burden may careen on the Tortugas rock.

TOSQUIATOSSY Creek, a north head water of Alleghany river, whole mouth is east of Squeaughta Creek, and 17

miles north-westerly of the Ichua Town; which fee.

TOTOWA, a place or village at the Great Falls in Paflaik river, New-Jerfey,

TOTTERY, a river which empties through the fouth-eaftern bank of the Ohio, and is navigable with batteaux to the Ouafiato Mountains. It is a long river, and has few branches, and interlocks with Red Creek, or Clinche's river, a branch of the Tenneffee. It has below the mountains, effectially for 15 miles from its mouth, very good land.

TOULON, a township of New-York, in Ontario co. In 1796, 93 of the inhabitants were electors.

TOWERHILL, a village in the townfhip of South-Kingftown, Rhode-Ifland, where a poft-office is kept. It is 10 miles wett of Newport, and 282 from Philadelphia.

TOWNSHEND, a township of Windham co. Vermont, west of Westminster and Putney, containing 676 inhabitants.

TOWNSHEND, a township of Middlefex co. Maffachusetts, containing 993 inhabitants. It was incorporated in 1732, and lies 45 miles northward of. Boston.

TOWNSHEND, a harbour on the coaft of the Diftrict of Maine, where is a bold harbour, having 9 fathoms water, fheltered from all winds. High water, at full and change, 45 minutes after 10 o'clock.

TRACADUCHE, now *Carleton*, on the northern fide of Chaleur Bay, is about 5 leagues from the great river Cafquipibiac in a S. W. direction, and is a place of confiderable trade in cod-fifth, &c. Between the township and the river Cafquipibiac, is the finall village of Maria.

TRANQUILLITY, a place in Suffex co. New Jerfey, 8 miles foutherly of Newtown.

TRAP, a village in Talbot co. Maryland; about 6 miles S. E. of Oxford.

TRAP, The, a village of Pennfylvania, in Montgomery co. having about a dozen houfes, and a German Lutheran and Calvinit church united. It is 9 miles from Morriftown, 11 from Pottfgrove, and 26 from Philadelphia.

TRAP, a village of Maryland, in Somerfet co. fituated at the head of Wicomico Creek, a branch of the river Wicomico, 7 miles fouth-weft of Salifbury, and 6 north of Prince's Ann.

TRAPTOWN,

TRAPTOWN, a village of Maryland, in Frederick co. fituated on Cotoctin Creek, between the South and Cotoctin Mountains, and 7 miles fouth wefterly of Fredericktown.

TRAVERSE Bay, Great, lies on the N. E. corner of Lake Michigan. It has a narrow entrance, and fets up into the land fouth-eaftward, and receives Traverferiver from the E.

TREADHAVEN Creek, a finall branch . of Choptank river.

TREASURY Islands, form a part of Mr. Shortland's New-Georgia, (Surville's Archipelago of the Arfacides) lying from 6. 38. to 7. 30. S. lat. and from 155. 34. to 156. E. long. from Greenwich. See Arfacides, &c.

TRENCHE MONT River, a fmall tiver of the island of St. John's, in the Gulf of St. Lawrence. It emptics into the fea 3 or 4 leagues to the westward of the eastern extremity of the island.

TRECOTHIC, a township in Grafton co. New-Hampshire, incorporated in 1769.

TRENT, a finall river of N. Carolina, which falls into Neus river, at Newbern. It is navigable for fea veffels, 12 miles above the town, and for boats 20. See Neus.

TRENTON, is one of the largeft towns in New-Jerfey, and the metropolis of the the State, fituated in Hunterdon co. on the E. fide of Delaware river, oppofite the falls, and nearly in the centre of the State from N. to S. The river is not navigable above thefe falls, except for boats which will carry from 500 to 700 bufnels of wheat. This town, with Lamberton, which joins it on the fouth, contains between 200 and 300 houses, and about 2,000 inhabitants. Here the leg flature flatedly meets, the fupreme court fits, and most of the public offices are kept. The inhabitants have lately erected a handfome court-houle, 100 feet by 30, with a femi-hexagon at each end, over which is a baluftrade. Here are alto a church for Epifcopalians, one for Prefbyterians, one for Methodifts, and a Quaker meeting-house; - In the neighbourhood of this pleafant town, are a great many gentlemen's feats, finely fituated on the banks of the Delaware, and ornamented with tafte and elegance. Here is a flourishing academy. It is 12 miles S. W. of Princeton, 30 from .

Brunfwick, and 30 N. E. of Philadelphia. N. lat. 40. 15. W. long. 74. 15.

TRENTON, a finall poft-town of the Diffrict of Maine, Hancock co. 12 miles W. by S. of Sullivan, 31 N. E. by E. of Penobfcot, 286 N. E. of Bofton, and 633 N. E. of Philadelphia. This town is near Defert Ifland; and in a part of it called *The Narrows*, were about 40 families in 1796.

TRENTON, the chief town of Jones^{*} county, N. Carolina, fituated on the S. fide of Trent river. It contains but few houfes, befides the court-houfe and gaol. It is 521 miles from Philadelphia.

TREPASSI Bay, or Trefpaffes Bay, and Harbour, on the fouth fide of Newfoundland Ifland, near the S. E. part, and about 21 miles to the N. weftward of Cape Race, the S. E. point of the ifland. The harbour is large, well fecured, and the ground good to anchor in.

TRIANGLE Ifland, a finall ifland, one of the Bahamas. N. lat. 20. '51. W. long. 69. 53.

TRIANCLE Sheals, lie to the weftward of the peninfula of Yucatan, near the E. fhore of the Bay of Campeachy, nearly W. of Cape Condecedo. N. lat, 17. 5. W. long. 111. 59.

TRIESTE Bay, on the coaft of Terra Firma, is nearly due fouth from Bonair Island, one of the little Antilles, to the east of Curaffou Island.

TRIESTE Island, a finall island at the bottom of the Gulf of Campeachy, weftward of Port Royal Island, about 3 leagues from E. to W. The creek which feperates it from Port Royal Island is fearcely broad enough to admit a cance. Good fresh water will be got by digging 5 or 6 feet deep in the falt fand; at a less depth it is brackish and fait, and at a greater depth than 6 feet it is falt again.

TRINIDAD, a fmall ifland in the S. Atlantic Ocean, due E. off Spirity Santo, in Brazil. S. lat. 20. 30. W. long, 41. 20. It is also called Trinity.

TRINIDAD, or Trinidada Ifland, near the coaft of Terra Firma, at the north part of S. America. It partly forms the Gulf of Paria, or Bocca del Drago, and is much larger than any other upon. the coaft. It is 36 leagues in length, and 18 or 20 in breadth, but the climate is rather unhealthy, and little of it is cleared.

Amer

Newf

53.3

TR

cleared. The current fets fo frong along the coaft from E. to W. as to render most of its bays and harbours useles. It produces sugar, fine tobacco, indigo, ginger, a variety of fruit, fome cotton, and Indian corn. It was taken by Sir Walter Raleigh, in 1595, and by the French in 1676, who plundered the ifland, and extorted money from the inhabitants. It was captured by the British in February, 1797. It is fituated between 59. and 62. W. long. and in 10 N. lat. The N. E. point lies in lat. 10. 28. N. and long. 59: 37. W. The chief town is St. Joseph.

•

TRINIDAD, LA, a town of Mexico, in the province of Guatimala, on the banks of the river Belen, 12 miles from the fea; but the road is almost impassible by land. It is 70 miles S. E. of Guatimala, and 24 east of La Conception. N. lat. 13. W. long. 91. 40.

TRINIDAD, LA, on the north coaft of the Ifthmus of Darien, lies eaftward of Bocca del Toro, and fome clufters of fmall iflands, and S. W. of Porto Bello and Fort Chagre. N. lat. 8. 30. W. long. 81. 30.

TRINIDAD, or La Sonfonate Port, a town on a bay of the Pacific Ocean, about 65 miles S. E. of Petapa, and 162 from the town of Guatimala. All the goods that are fent from Peru and Mexico to Acaxatla, about 12 miles from it, are brought to this port. It is 9 miles from the town to the harbour, which is much frequented, and is a place of great trade; being the neareft landing to Guatimala for fhips that come from Peru, Panama, and Mexico.

TRINIDAD, LA, one of the fea ports on the fouth part of the ifland of Cuba, in the Weff-Indies; fituated N. W. from the weft end of the groupe of iflands called Jardin de la Reyna. N. lat. 21. 40. W. long. 80. 50.

TRINIDAD, LA, an open town of Veragua, and audience of Mexico, in N. America.

TRINIDAD Channel, has the island of Tobago on the N. W. and that of Trinidad on the fouth.

TRINIDAD, or Trinity, a town of New-Granada, and Terra Firma, in S. America, about 23 miles N. E. of St. Fe.

TRINITY Bay, on the call fide of Newfoundland Ifland, between lat. 47. 53. 30. and 48. 37. N.

TRINIT' Port, a large bay of Martinico Island, in the West-Indies, formed on the south-east by Point Caravelle.

TRINITY Ide, lies near the coaft of Patagonia, in S. America, eaftward of York Islands. S. lat. 50. 37.

TRINITY *II*., the north-eafternmost of the finall islands on the fouth-east coast of the peninfula of Alaska, on the N. W. coast of N. America, N. E. of Foggy Islands.

TRIO, a cape on the coaft of Brazil, S. America.

TRISTO, a bay on the north coaft of S. America, is W. S. W. of the river Turiano. It has good anchorage and is well fheltered from the fwell of the fea.

TRIVIGILLO Bay, in the Gulf of Honduras, or fouth fhore of the Gulf of Mexico, is within the ifland of Pines. Dulce river lies a little to the weft.

TROCADIE, a fmall island on the N. coaft of the island of St. John's, lying off the mouth of Shimene Port, and in the Gulf of St. Lawrence.

TROIS *Rivieres*, a bay at the eaft end of the above-mentioned Ifland of St. John's, and weft of Cape Breton Ifland. Three ftreams fall into it from different directions; hence its name. N. lat. 46. 5. W. long. 62. 15.

TROIS Rivieres, or the Three Rivers. or Treble River, a town of Lower Canada, fettled by the French in 1610; and is fo called from the junction of three waters a little below the town, where they fall into the river St. Lawrence. The town ftands on the northern bank of the St., Lawrence, at that part of the river called Lake St. Pierre. It is but thinly inhabited; is commodioully fituated for the fur trade, and was formerly the feat of the French government, and the grand mart to which the natives reforted. It is pleafantly fituated in a fertile country, about 50 miles fouth-west of Quebec. The inhabitants fouth-weft of Quebec. are mostly rich, and have elegant, well furnished houses, and the country round wears a fine appearance. N. lat. 46. 51. W. long. 75. 15.

TROMPEAUR, Cape, del Enganna, or Falfe Cape, is the eafternmoft point of the island of St. Domingo. N. lat. 18. 25. W. loug. from Paris 71.

TROPIC Kers, are fmall iflands or rocks, on the north of Crab Ifland, and off the eaft coaft of Porto Rico Ifland, A number of tropic birds breed here, which

which are a fpecies never feen but between the tropics.

TROQUOES, a bay at the fouthern extremity of the eaftern part of Lake Huron, leparated from Matchudoch Bay on the N. E. by a broad promontory.

TROQUQUA, an island on the north coaft of S. America, in the mouth of a fmall bay near Cape Seco, a short way S. E. from the east point of the bay or river Taratura.

TROU JACOB, on the fouth fide of the island of St. Domingo. From this to Cape Beate, or Cape a Foux, the shore is rocky.

TROU, LE, a fettlement in the northern part of the French division of the island of St. Domingo. It is 51 leagues E. of Ouanaminthe, and 2 S. E. of Limonade. N. lat. 19. 35. W. long. from Paris 74. 22.

TROY, a post-town of New-York, Rensilelaer co. 6 miles north of Albany, 3 S. of Lansinburg city, and 271 from Philadelphia. The township of Troy is bounded E. by Petersburg, and was taken from Rensilelaerwyck township, and incorporated in 1791. In 1796, 550 of the inhabitants were electors. Seven years ago, the scitte of the flourishing village of Troy was covered with flocks and herds, and the spot on which a fchool, containing 160 scholars, is now erected, was then probably a scheepfold. The school is under the direction of 3 schoolmasters, and is a very promising feminary.

TRURO, a town of Nova-Scotia, fituated in Halifax co. at the head of the Bafin of Minas, oppofite to, and 3 miles foutherly of, Onflow; 40 miles N. by W. of Halifax, and 40 from Pictou. It was fettled by the North-Irifh, fome Scotch, and the defcendants of North-Irifh. Through this town runs the river called by the Indians Shubbenacadie, navigable for boats to within 9 miles of Fort Sackville.

TRURO, a township of Massachusetts, fituated in Barnstable county, lies between lat. 41. 57. and 42. 4. N. and between long. 70. 4. and 70. 13. W. It is on the easternmost part of the peninfula of Cape Cod, 57 miles S. E. of Boston, in a straight line, but as the road runs it is 112, and 40 from the courthouse of Barnstable. It is the *Pamet* of the Indians, and and after its fettlement in 1700 was some time called

Dangerfield; it was incorporated under its prefent name in 1709, and contains 1,193 inhabitants. Only one family of Indians remained a few years fince, and lived on Pamet Point. In the valley called Great Hollow, a creek fets up from the bay, at the mouth of which is a tide harbour. The other landing . places are of small note. Pamet Harbour is about 100 yards wide at the mouth, but is wider within ; and if repaired would be of public utility. It lies above 3 leagues S. E. of Cape-Cod harbour. The hill on which the meeting-house frands branches from the high land of Cape-Cod, well known to feamen. The mountain of clay in Truro, in the midst of fandy hills, feems to have been placed there by the God of Nature, to ferve as a foundation for a light-house, which if erected might fave the lives of thousands, and millions of property. The foil of Truro is, in most places, fandy, like Provincetown; and the inhabitants derive their principal fubfiftence from the fea, which here abounds with vaft variety of fish. Great part of their corn and vegetables are procured from Bofton and the neighbouring towns. Two inhabitants of Truro, Captains David Smith and Gamaliel Collings, were the first who adventured to Falkland Iflands in purfuit of whales. This voyage, which was crowned with fuccels, was undertaken in 1774, by the advice of Admiral Montague of the British navy. The whalenien of Truro now vifit the coaft of Guinea and Brazil. Many of the mafters of fhips em-. ployed from Boston and other ports, are natives of Truro. The elderly men and finall boys remain at home to cultivate the ground; the reft are at fea 2ds of the year. The women are generally employed in fpinning, weaving, knitting, &c.

TRUXILLO, a bay, harbour, and town, at the bottom of St. Giles's Bay, on the coaft of Honduras, in the gulf of that name. The bay is about 6 miles broad, being deep and fecure, and defended by a caffle; but it has little The town ftands about a league trade. from the North Sea, between two rivers, the mouths of which, with fome iflands before them, form the harbour. The country is exceedingly fruitful in corn and grapes, and notwithstanding the heat of the climate, very populous. The heat of the climate, very populous. city is defended by a thick wall towards

8:8

wards the fea, and is inacceffible but by a narrow, fleep afcent. The caffle joins to the wall, and stands on a hill. Behind the city are high mountains. It lies 300 miles N. E. of Amapalla. N. lat. 15. 20. W. long. 85. 56.

ns

of

nd

ey

iş

g

r-

he

e-

It

od

:t-

gh

a-

0,

to

of

3

ve

of

in

11 2

:i-

10

ac

0-

11-

0,

iel

ed

s.

th

he

ho

ro

a-

n--

re

nd

ite

he

y-

:c.

nd

y,

of

es

e-

tle

ue

rs,

dø

he

m

he

he

:0-

ds

TRUXILLO, the first diocese in the audience of Lima, in Peru.

TRUXILLO, a bay or harbour, and one of the principal cities of the province of the fame name in Peru, is 11 leagues from Chocope, and 80 N. W. of Lima; and according to Ulloa, the city lies in lat. 8 6. 3. S. and long. 77. 30. W. It flands in the valley of Chimo, on a finall river, about half a league from the fea; is furrounded with a brick wall, and from its circuit may be claffed among cities of the third order. Two leagues to the northward is the port of Guanchaco, the channel of its trade. The houfes make an elegant appearance, being generally of brick, with flately balconies and fuperb porticos.

TRUXILLO, or Noftra Seniora de la Paz, a town of New-Granada (Venezuela) and Terra Firma, in S. America, 215 miles fouth of Maracaibo Lake; on the fouthernmost bank of which Lake is a village, called Truxillo, dependent on this city. The city is in lat. 9. 21. N. and long. 69. 15. W.

TRYON Mountains, in N. Carolina, ie N. W. of the town of Salifbury, on the borders of the State of Tenneffee.

TUAPE, the chief town of the divifon of Senora, in New-Mexico.

TUBAI, a fmall island, one of the Society Iflands, in the S. Pacific Ocean, is about 4 or 5 leagues to the N. by W. or N. N. W. from Bolabola. S. lat. 16, 12. W. long. 151.44.

TUCAPEE, on the coaft of Chili, and the W. fide of S. America, is on the S. Atlantic Ocean, 10 leagues N. N. E. from Rio Imperial, and 10 to the illand of Santa Maria, or St. Mary.

TUCKABATCHEES, a town of the Creek nation of Indians.

TUCKAHOC Creek, in Maryland, Talbot co. a branch of Choptank river.

TUCKERTON, the port of entry for the district of Little Egg Harbour, in the State of New-Jerley.

TUCUMAN, a province of S. America, fo called from a tribe of Indians, and in the S. W. division of Paraguay. It is bounded N. partly by Los Chicas, in Peru, and partly by Chace; S. by 6 miles weft of Middletown, and 65

Cayo and Pampas; E. by Paraguay Proper, and Rio de la Plata; and W by St. Jago, in Chili, and the S. end of Chicas; extending itfelf from Rio Vermejo to Rio Quarto, almost from /lat. 24. to 34. fouth, and from E. to W. where broadeft, from the river/Salado to the ridge of the Cordillera, feparating it from Chili, almost from long. 62. to 69. 30. W. The climate is health and temperate. The lands are rich and well cultivated, efpecially towards Chili, with fome defert cantons towards the Magellanic fide. Its two principal rivers are Dolce and Salado, that is, the fweet and falt ones; befides innu-merable imaller ftreams. The natives are fomewhat civilized by the Spaniards, and cover themfelves with their woollen and cotton manufactures, and live in villages.

TUCUYO, a town of New-Granada, and Terra Firma in N. America. It ftands in a valley of the fame name. every where furrounded by mountains. The air is very healthy, and the foil fruitful, and a river divides the place. It is 200 miles S. of Maracaibo city. N. lat. 7. 10. W. long. 68. 36.

TUFTONBOROUGH, a town of New-Hampfhire, in Strafford co. fituated on the N. E. fide of Lake Winipifeogee. adjoining Wolfborough, containing 109 inhabitants.

TUGELO River, in Georgia, is the main branch of Savannah river. The other great branch is Keowee, which joining with the other, 15 miles N. W. of the northern boundary of Wilke's co. form the Savannah. Some branches of the Tugelo rife in the State of Tenneffee. A respectable traveller relates that in ten minutes, having walked his horie moderately, he tafted of Tugelo, Apalachicola, and Hiwaffee rivers.

TUICHTENOONA Creek, in the State of New-York, is 16 miles above Schenectady. E. of the creek is a curious Indian infeription.

TULLY, one of the military townfhips of Onondago co. New-York, having Sempronious on the weft, and Fabius on the eaft. It is within the jurifdiction of Pompey, and lies 29 miles S. E. of the ferry on Cayuga Lake.

TULPEHOCKEN, a branch of the Schuylkill, which empties into that river at Reading. Alfo, the name of a town of Pennfylvania, in Lancaster co. north-

north-weft of Philadelphia. Tulpehocken creek or river, and Quitapabilla, lead within 4 miles of each other. The water communication between Schuvlkill and Sufquehannah muft be formed over a tract of country of about 40 miles in extent, from river to river, in a ftraight line; but about 60 miles as the naviga. tion must go. This tract is cut by the above a creeks. The bottom of the canal, through which the navigation must pais, will not here rife more than go feet above the level of the head waters of the above a creeks; nor fo much as 200 feet above the level of the waters of Sufguehannah or Schuylkill.

TUMBEZ, a town in the road to Lima and Peru, in South-America, 7 leagues from Salto, a place for landing of goods configned to this place, and in lat. 3. 12. 16. S. Near this town is a river of the fame name, which empties into the bay of Guayaquil. It has near 70 cane houfes.

TUMBLING Dam, on Delaware river, is about 22 miles above Trenton.

TUNBRIDGE, a township of Vermont, Orange co. 12 miles west of Thetford. It contains 487 inhabitants.

TUNIA, a city of New-Granada, in Terra Firma.

TUNJA, a town of New-Granada and Terra Firma, in South America. Near it are mines of gold and emeralds. The air is temperate, and the foil fruitful. It is about 30 miles fouth-weft of Truxillo. N. lat. 4. 51. W. long. 72. 10.

TUNKERS. See Ephrata.

TUNKHANNOCK, a township and creek in Luzerne co. Pennsylvania. The creek is adwater of Susquehannah.

TUPINAMENS, the name of a famous nation who inhabited Brazil on its firft difcovery by the Portuguefe. They left their chief abode about Rio de Janeiro, and wandered up to the parts near the Amazon, where the Tapayos are now the defcendants of that brave people. Their migration and hiftory are fully deferibed by Father Dacunha.

TURA Bamba,⁶a. fpacious plain of Peru, in S. America, at the extremity of which ftands the city of Quito. To this plain there is a road from Guayaquil.

TURBET, a township of Penniylvania, on Sulquehannah river. See Northumberland County.

TURIANO, a river on the north-coaft of South America, 3 leagues to the eaft of the iflands Barbarata. Near it is a falt pond which furnifies all the coaft with falt, and there is harbour and road for thips to ride in.

TURKISH Islands, a groupe of little iflands, called alio Ananas, fince they are the iflands of Don Diego Luengo, thus called by him who difcovered them. They are more than 30 leagues north of Point Ifabelique, on the north coaft of the ifland of St. Domingo.

TURKEY, a imall town of New-Jerfey, Effex co. 14 miles north wefterly of Elizabeth-Town, and 179 north-east of Philadelphia.

TURREY Foot, in Youghiogany river, is the point of junction of the great S. Branch, Little Croffings from the foutheaft, and North Branch from the northward. It is 35 miles from the mouth of the river, 22 miles S. S. W. of Berlin, in Pennfylvania, and 36 north eaft of Morgantown. N. lat. 39. 44.

TURKEY Point, a promontory on the north fide of Lake Erie, lies opposite to Presque Isle, on the south fide, about 50 miles across.

TURKEY Point, at the head of Chefapeak Bay, is a point of land formed by the waters of the bay on the north-weft, and thole of Elk river on the fouth-eaft. It is about 151 miles fouth-weft of Elkton, and 44 north-eaft of Annapolis. Here the British army landed, in August, 1777, before they advanced to Philadelphia.

TORKS Iflands, feveral fmall iflands in the Weit Indies, about 35 leagues north-eaft of the ifland of St. Domingo, and about 60 to the fouth-eaft of Crooked Ifland. The Bermudians frequently come hither and make a great quantity of falt, and the hips which fail from St. Domingo commonly pais within fight of them. N. lat. 21. 38. W. long. 71. 5.

TURNER, a township of the District of Maine, Cumberland co. on the west bank of Androscoggin river, which divides it from Green in Lincoln co. It was incorporated in 1786, contains 349 inhabitants, and lies 172 miles north of Boston, and 31 fouth-west of Hallowell.

TURTLE Island, in the fouth Pacific Ocean, is nearly a league long, and not half fo broad. It is furrounded by a reef of coral rocks, that have no foundings without them. S. lat. 19. 49. W. long. 177. 57.

TURTLE Greek, in Pennfylvania, a

fmall ftre E. bank z 2 miles at Pittfby General Indians, way to F where he his army of the arr addrefs a wards G TURT into St. a fufficie veffel tha town of and capa regularly The land faid to be TURY the river lies just o a very go But the ficult, ar Tusc da. See Tusc Pennfylv the S. V miles for Tusc each othe in Uppe about 40 ancient neighbou about 12 wholly c the wall as the fi Built th which Many of cient cu centre o vicinity TUS the Stat ed from 1712, al with wh **fuppolit** fame tri is in th fift of a

finall ftream which empties through the E. bank of Monongahela river, about 12 miles from the mouth of that river, at Pittfburg. At the head of this creek, General Braddock engaged a party of Indians, the 9th of July, 1755, on his way to Fort du Oneine, now Pittfburg, where he was repulfed, himfelf killed, his army put to flight, and the remains of the army brought off the field by the addrefs and courage of Colonel, afterwards General Wathington.

le

y

1,

I.

f

»f

ĸ,

h

əf

j.

1-

h

ft

10

0

rt

1-

y

t,

t.

۱.

8.

t,

k-

ls: :9

>,

<u>t-</u>

y

y

t.

xf

5.

£

ft

j-

E

9 A

۱.

C

÷

3

٢.

u

TURTLE River, in Georgia, empties into St. Simon's Sound, and its bar has a fufficiency of water for the largeft vefiel that fwims. At its mouth is the town of Brunfwick, which has a noble and capacious harbour. The town is regularly laid out, but not yet built. The lands on the banks of this river are faid to be excellent.

TURY, a river on the coaft of Brazil, in S. America, 40 leagues E. S. E. of the river Cayta. The ifland of St. John lies just off the river's mouth, and makes a very good harbour on the infide of it. But the paffage both in and out, is difficult, and no pilots are to be had.

TUSCALOMSA, a river of W. Flori-See Pearl River. da.

TUSCARORA Greek, a fmall ftream of Pennfylvania, which empties through the S. W. bank of Juniatta river, 12 miles fouth-ealtward of Lewistown.

TUSCARORA Villages, lica mile from each other, 4 miles from Queenftown, in Upper Canada, containing together about 40 decayed houses. Veftiges of ancient fortifications are visible in this neighbourhood. The Indian houses are about 12 feet square; many of them are wholly covered with bark, others have the walls of logs, in the fame manner as the first fettlers among white people built their huts, having chimnies in which they keep comfortable fires. Many of them, however, retain the an-cient cuftom of having the fire in the centre of the house. The lands in the

vicinity are of a good quality. TUSCARORAS, a tribe of Indians in the State of New-York. They migrat-ed from North-Carolina, about the year 1712, and were adopted by the Oneidas, with whom they have fince lived, on the fuppolition that they were originally the fame tribe, from an affinity which there is in their language. They now confift of about 400 iouls, their village is between Kahnanwolohale and New Stockbridge, on Tufcarora or Oneida Creek. They receive an annuity of about 400 dollars from the United States.

TUSKARAWI, the ancient name of a head water of Muskingum river. It is alfo called Tufcarawas.

TUTAPAN, a large town on the W. coaft of New-Mexico, in the N. Pacific-Ocean. From the river Sacatulca, the high and rugged land extends N. W. 25 leagues.

TWELVE ISLES, or Twelve Apofles, ifles on the S. fide of Lake Superior, and on the S. fide of the mouth of Weft Bay.

TWENTY MILE Creek, an eaftern branch of Tombigbee river, in Georgia, which runs first a S. by E. course, then turns to the S. W. Its mouth lies in about lat. 33. 33. N. and long. 88. W.

TWENTY FIVE MILE Pond, a fettlement in Lincoln co. Diffrict of Maine. See Titcomb.

TWIGHTWEES, a tribe of Indians, in the N. W. Territory, inhabiting near Miami river and Fort. Warriors 200. See Wawiachtonos.

TYBEE Island, on the coaft of Georgia, lies at the mouth of Savannah river, to the fouthward of the bar. It is very pleasant, with a beautiful creek to the W. of it, where a fhip of any burden may lie fafe at anchor. A light-house ftands on the ifland, 80 feet high, and in lat. 32. N. and long. 81. 10. W. The light house is 7 miles E. S. E. 2 E. from Savannah, and 6 S. W. 1 W. from Port Royal.

TYBOINE, a township of Pennsylvania, in Cumberland county.

TYGART'S Valley, in Pennfylvania, lies on Monongahela river.

TYGER, a limall river of S. Carolina, rifes in the All-ghany Mountains, and taking a S. E. course nearly parallel to Enorce river, empties into Broad river, 5 miles above the Enoree.

TYNGSBOROUCH, a township of Maffachufetts, Middletex co. on Merrimack river, 31 miles north of Bolton.

TYRINGHAM, a township of Moffachuletts, Berkshire co. It contains 1397 inhabitants, lies 14 miles from the thire town, and 140 weft of Bofton.

TYRONE, two townships of Pennsylvania; the one in York co. the other in that of Cumberland. Nn

TYRRET,

ULL

562

TYRREL, a maritime county of Edenton district, N. Carolina; bounded N. by Roanoke river and Albemarle Sound, and fouth by Beaufort. It is generally a low, flat, and fwampy country, and contains 4744 inhabitants, including 176 flaves.

Same There all a second

attentioner. 1 217 a stand 1 a line contraction of the second Same Manda at .

UCAH, Port, on the N. W. Coaft of North-America, is fituated on Washington's Island, south of Port Geyer, and north of Port Sturgis. At its mouth are Needham's Isles. The middle of the entrance of this bay is in lat, 52.25. N.

UCAYALA River, a fouth branch of Amazon river.

UCHE, an Indian town fituated on the Chata Uche river. It is fituated, according to Bartram, on a vaft plain, and is the largest, most compact, and best lituated Indian town he ever faw. The habitations are large, and neatly built ; the walls of the houfes are constructed of a wooden frame, then lathed and plaistered infide and out with a reddish well tempered clay or mortar, which gives thenfythe appearance of red brick walls; and the roofs are neatly covered with cyprefs bark, or fhingles. The town appears populous and thriving, full of youth and young children; and is supposed to contain about 1 500 inhabitants. They are able to mufter 500 gun-men or warriors. Their national language is radically different from the Creek or Muscogulge tongue, and is called the Savanna or Savanuca tongue. It is faid to be the fame or a dialect of the Shawanefe. Although in confederacy with the Creeks, they do not mix with them; and are of importance enough to excite the jealoufy of the whole Mulcogulge confederacy, and are ufually at variance, yet are wife enough to unite against a common enemy to support the interest of the general Creek confederacy.

ULIETEA, one of the Society Islands in the S. Pacific Ocean, is about 7 or 8 leagues from the island of Huaheine, at S. W. by W. There are 9 uninhabited islands weft of it. The fouth end lies in lat. 16. 55 S. and long. 151. 20 W.

ULLOA, or St. John de Ulloa, near the welt shore of the Gulf of Mexico.

Sec. 17 L

ULSTER, a mountainous and hilly county of New-York, containing all that part of the State bounded easterly by the middle of Hudfen's river, foutherly by the county of Orange, wetterly by the State of Pennfylvania, and the weft branch of Delawate river, and northerly by the county of Albany. In 1790, it contained 29,397 inhabitants, including 2,906 flaves. In 1796, there were 4,429 of the inhabitants qualified to be electors. It is divided into 16 townfhips. Chief town, Kingfon. A part of this county and that of Otiego, were erected into a feparate county, January, 1797.

UNI

ULYSSES, one of the military townfhips in Onondago co. New-York, fituated at the fouthern end of Cayuga Lake, having Hector on the weft, and Dryden on the eaft, which laft townfhip is included within the jurisdiction of Ulyffes, which was incorporated in 1794. In 1796, 38 of the inhabitants we've electors.

UMBAGOO, a large lake of New-Hampshire, next in fize to Lake Winipifeogee. It lies in Grafton co. and a small part of it in the Diffrict of Maine.

UNADILLA, a river of the State of New York, called also *Tianaderba*, runs fouthward, and joining the Main Branch, forms Chenengo river.

UNADILLA, a township of New-York, Ottego co. on the northern fide of the main branch of Chenengo river. It is about 110 miles south work of Albany; and, in 1796, 502 of its inhabitants were electors. In the same year, the townships of Suffrage, Otsego, and Butternuts, were taken from this township, and incorporated.

UNAKA Mountain. See Tennessee.

UNAMI, a tribe of the Delaware Indians, confidered to be the head of that nation.

UNDERHILL, atownship of Vermont, Chittenden co. 12 miles east of Coichester, and contains 65 inhabitants.

UNION, a county of South-Carolina, Pinckney diffrict, containing 7,693 inhabitants, of whom 6,430 are whites, and 1,215 flaves. It fends two reprefentatives and one fenator to the State legiflature. Chief town Pinckneyville.

UNION, a rocky township in I olland co. Connecticut, welt of Woodstock, and about 12 miles N. E. of Toiland. UNION, a township of the District of Maine; or

N

N

11

111

Maine.

Maine, Bincoln co. containing 200 inhabitants. It was incorporated in 1786, and lies 200 miles from Boston.

UNI

illy

all

rly

th-

rly

the

and

ln

its,

iere

fied

16

A

go,

ity,

vn-

tu-

Jga

and

hip

94.

110

PW

ini

da

ine.

of

bd,

am

rk,

the

t is

IV ;

inte

the

nt-

Hp,

In-

hat

mt,

101-

na,

in-

tes,

ne-

ate

lle.

ind

ck,

nd.

nt;

of

of

UNION, a post town of the State of New York, Tioga co. on the N. fide of Suspuehannah river, and weft of the mouth of the Chenango, 122 miles S. E. by E. of Williamsburg, on Genefice river, 24 E. N. E. of Athens, or Tioga Point, 92 S. W. of Cooperflown, and 340 N. by W. of Philadelphia. In 1796, there were in the township, 284 of the inhabitants qualified electors.

UNION River, or Plantation, No. 6, in the District of Maine, is fituated in Hancock co. 25 miles N. E. of Penobfcot.

UNION River, in the county of Hancock, District of Maine, empties into Blue Hill Bay, on the E. fide of Penobfcot Bay. Long-Ifland, in this bay, is in lat. 44. 25. and long. 67. 45.

UNION-TOWN, a poft-town of Pennfylvania, Fayette co. on Redftone Creek. It contains a church, a ftone gaol, and a brick court-houfe, and about 80 dwelling-houfes. Near it are two valuable merchant mills. It is the feat of the county courts, and is 14 miles S. by E. of Browniville, where Redftone Creek enters the Monongahela, 58 miles S. of Pittfburg, 24 N. E. of Morgantown, in Virginia, and 327 W. of Philadelphia.

UNITAS, a village of North-Carolina, futuated at the head of Gargal's Creek.

fituated at the head of Gargal's Creek. UNITED STATES. The United States of America occupy, perhaps, the 39th part of the habitable globe, and the 199th part of the whole. They are claffed in three grand divisions.

I. The NEW-ENGLAND, or EASTERN, or Northern States, viz.

VERMONT, NEW-HAMPSHIRE, MASSACHUSETTS, including the DISTRICT OF MAINE, RHODE-ISLAND, and CONNECTICUT. II. The MIDDLE STATES. NEW-YORK, NEW-JERSEY, PENNSYLVANIA, DELAWARE, and NORTH-WEST TERRITORY. III. The Southern States. MARYLAND, VIRGINIA. KENTUCKY, NORTH-CAROLINA.

TENNESSEE, South-Carolina, and Georgia.

Thefe grand divisions, as also the different States, have been already defcribed ; to which we refer the reader. The territory of the United States is in length 1,250 miles, and in breadth 1040, lying between 31. and 46. N. lat. and between 64. and 96. W. long. from London \$ bounded north and east by British America, or the provinces of Upper and Lower Canada, and New-Brunfwick fouth-east by the Atlantic Ocean; fouth by East and West Florida, and west by the river Miffifippi. According to Mr. Hutchins, it contains, by computation, a million of fquare miles, in which are 640,000,000 acres

Deduct for water 51,000,000

Acres of land in the 589,000,000

The largest rivers that border upon, or pais through the United States, are Miffilippi, Ohio, and Tenneffee, on the weft fide of the Alleghany Mountains; and the Alatamaha, Savannah, Santee, Cape Fear, Roanoke, James, Patowmac, Sufquehannah, Delaware, Hudson, Connecticut, Merrimack, Pifcataqua, Androfcoggin, Kennebeck, and Penohícot. whole general couries are from northwest and north, to S. E. and south, and which empty into the Atlantic Ocean. The United States embofom fome of the largest lakes in the world. The most remarkable lie in a chain along their northern boundary upon the Canada line, and are lakes Superior, Michigan, Huron, Erie, Ontario, Champlaine, George, Memphreinagog, Winipifeogee, and Umbagog. The most remarkable fwamps are Ouaquaphenogaw, or Eknanfanoka, nearly 300 miles in circumference, in the State of Georgia; the two Difmals in North-Carolina, of immense extent, each containing a large lake in its centre ... and Buffaloe Swamp, in the north-weffern parts of Pennfylva-The principal mountains in the nia. United States, are, Agamenticus, in Maine; the White Mountains and Monadnock, in New-Hampfhire; Wachuiett, in Maffachusetts ; the Green Mountains, in Vermont; and the Alleghany Mountains, about 900 miles in length, and from 1 50 to 2 50 in breadth. The face of the country, generally speaking, Nn 2

UNI

is agreeably variegated with plains and mountains, vales and hills. New England is an uneven, hilly and rocky country. A broad fpace, including all the branch of the Alleghany Mountains, commencing at Hudfor's river in New-York, and extending circuitoufly fouthwefferly through all the States weftward and fouthward, Delaware excepted, is mountainous. Eaftward of these mountains quite to the fea-coaft, a border of from 60 to 100 miles, and fometimes more, in breadth, is a remarkably level country, and in the fouthern States free of ftone. West of this range of mountains, is a fine, and charmingly diverfified country, well watered, fertile, temperate, and increasing in population with unexampled rapidity. Every fpecies of foil that the earth affords may be found in the United States; and all the various kinds of fruits, grain, pulle, and garden plants and roots which are found in Europe; befides a great vasiety of native vegetable productions. Tobacco, rice, indigo, wheat, corn, cotton, rye, oats, barley, buck-wheat, flax, and hemp, are among the principal productions of the United States. The United States conflitute what may, with strict propriety, be called a REPUBLIC. It confifts of fixteen feparate, independent States, having governors, conftitutions, and laws of their own, united under a general, federal constitution of government, administered by an elective head, and by a proportionate number of reprefentatives of the people from all the States. The merchants of this country carry on an extensive foreign trade with Ruffia, Sweden, Denmark, Hamburgh, United Netherlands, Great-Britain, Auftrian Netherlands and Germany, France, Spain, Portugal, and Italy, in Europe -with Morocco, and feveral other parts of Africa-with China, and various Afiatic countries, and the Eaft-India Iflands-with the Weft-Indies, and the N. W. coaft of North America. The principal articles exported are fifh, lumber, live flock, beef, pork, flour, wheat, Indian corn, tobacco, rice, indigo, flax-feed, pot and pearl afhes, iron, Sec. The exports of the year ending Sept. 30, 1796, amounted to 67,064/097 dollars. Six years before, the value of exports was but about 18 millions of dollars. The tea imported into the UNI

United States in 1791, directly from China, was 2,601,852 lbs. and the prices in Philadelphia 33 per cent. lower than in London, the drawback deducted. The export of falted beef and pork, in 1791, was 66,000 barrels. The fifting trade of the United States is rendered peculiarly important as a means of defence or of annoying the commerce of hoftile nations, from the circumftance that the Republic has not yet adopted a naval effablishment. The fishermen, while that continues to be the cale, may be transmuted by war immediately into a corps of privateersmen, and their fhips into private veffels of war; because the navy of any hoffile nation will fulpend the fiftheries, as long as there is no naval force to oppofe them. The amazing importance of the fifheries to the United States is evident from an infpection of the records of only the two counties of Suffolk and Effex, which comprise the fea-ports of Bofton, Salem, Marblehead, Beverly, Ipfwich, Newbury-Port, Gloucefter, and Haverhill. It appears that there were taken, brought in, and libelled, in the maritime court of thefe two counties, during the late war, 1,005 veffels with their cargoes; and 13 cargoes taken from fuch thips as had been abandoned after capture; making in the whole 1108: It has been flated by a British premier, in the British House of Commons, that the number of veficls belonging to Great-Britain in 1774, was 6,219 fail; of which, 3,908 were Brit-ish built, and 2,311 American built. Thus above a fixth part of all their veffels were brought in as prizes by them into the ports of the United States, with cargoes of great value, composed of every fpecies of military and domeftic fupply, in a feafon of the utmost emergency. It is likewife conjectured by well informed perfons that 55 per cent. of all the captures was made by the people of Maffachufetts. The capital ports for large fhips, in the United States ftand thus ranked, Newport, in Rhode-Island; Portland, in the district of Maine; and New-York. Several important branches of manufactures have grown up and flourished with a rapidity which furprifes; affording an encouraging affurance of fuccels in future attempts. Of these the following are the most confiderable, viz. of Skins-tanned and

and tawe boots, and ry of all ki leather br pets, par bar and f nails, imp pots, and steel and i thip build weights, arms of cabinet v cotton ca manufact tical inft every kind fail-cloth thread. tiles," and rits and printing | paper, p papers, a Hats of both. Refined animals and tallc wares ; 1 lers, fug irons and ule; clos tin wares nary ule Imoaking and hairpainters' nefia, gu factures (ried on a tained to turity,~tl hold man very larg munity. proper h unwarrar is left to dence, by by the A thor. T 13 Chriftian viz. Co Epifcopa Baptifts, Catholic Calvinift ren of th

UNI

TOM

the

ow-

de-

and

rels.

ates

18 3

the

the

not

The

be

war

ers-

ffels

file

ong

pofe the

dent

and

orts

rly,

fter,

here

led,

un-

fels

roes

an-

the

y a e of

fiels

was

irit-

nilt.

vef-

nem

vith

rery

ply,

ICY.

in-

all

ople

orts

ates

de-

im-

ave

lity

211 -

at-

the

ned

and

of

) of

and tawed leathers, dreffed fkins, fhoes, boots, and flippers, harnefs and faddlery of all kinds, portmanteaus and trunks, leather breeches, gloves, muffs and tippets, parchment and glue. Of Ironbar and fheet iron, fteel, nail-rods, and nails, implements of hufbandry, floves, pots, and other household utenfils, the steel and iron work of carriages and for thip building, anchors, fcale beams and weights, and various tools of artificers; arms of all kinds. Of Wood-fhips, cabinet wares, and turnery, wool and cotton cards, and other machinery for manufactures and hufbandry, mathematical inftruments, coopers' wares of every kind. Of Flax and Hemp-cables, fail-cloth, cordage, twine and packthread. Of Clay-bricks and coarfe tiles," and potters' wares. Ardent fpirits and malt liquors. Writing and printing paper, flicathing and wrapping paper, pafteboards, fullers' or prefs papers, and paper hangings. Books. Hats of fur and wool, and mixtures of Women's stuff and filk shoes. both. Refined fugars. Chocolate. Oil of animals and feeds. Soap, fpermaceti and tallow candles; copper and brais wares; particularly utenfils for diffillers, fugar refiners, and brewers; andirons and other articles for household ule; clocks, philolophical apparatus; tin wares of almost all kinds for ordinary ule; carriages of all kinds; inuff, imoaking and chewing tobacco; ftarch, and hair powder; lampblack, and other painters' colours; printers' ink, magnefia, gunpowder. Befides the manufactures of these articles, which are carried on as regular trades, and have at. tained to a confiderable degree of maturity, there is a vaft fcene of houfehold manufacturing, which contributes very largely to the fupply of the community. Religion here is placed on its proper bafis, without the feeble and unwarranted aid of the civil power, and is left to be supported by its own evidence, by the lives of its professions, and by the Almighty care of its Divine Author. The following denominations of Chriftians are more or lefs numerous, viz. Congregationalists, Prefbyterians, Episcopalians, Dutch Reformed Church, Baptifts, Quakers, Methodifts, Roman Catholics, German Lutherans, German Calvinifts, Moravians or United Brethren of the Episcopal Church, Tunkers, UPP

Mennonifts, Universalists, and Shakers There are a few/Jews, and many who reject revealed religion as unnecellary, inconvenient, and fabulous; and plead the fufficiency of natural religion. In 1790, there were about 3,950,000 inhabitants in the United States; 697,697 of whom were flaves. The prefent number is probably above four millions and a half, made up of almost all the different nations of Europe, but principally of the delcendants of the English nation. The military ftrength of this country lies in a well disciplined militia of about 900,000 brave and independent freemen, and an army of about 3 or 4000 men to defend the frontiers of the Union, and to man the feveral fortreffes in the different parts of the United States. The fum voted by Congrefs to support the naval and military eftablishment of the United S ates for 1796, was 1,818,873 dollars. The civil lift is about 300,000 dollars annually. See America, North America, &c.

UNITY, a fettlement in Lincoln co. District of Maine, between the Weft Ponds, 7 or 8 miles W. of Sidney, opposite to Vasiaborough, and 15 miles N. W. of Hallowell. It lies on Sandy river, about 16 miles from its mouth.

UNITY, a township of New-Hampshire, situated in Cheshire county, a few miles north-east of Charleston. It was incorporated in 1764, and contains 538 inhabitants.

UNITY Town, in Montgomery co. Maryland, lies 2 or 3 miles from Patuxent river, 11 from Montgomery courthouse, and 24 northerly of the city of Washington.

UPATCHAWANAN, or Temifcaman, a Canadian fettlement in N. America, in lat. 47. 17. 30. N.

UPPER ALLOWAYS Creek, in Salem co. New-Jerley.

UPPER BALD EAGLE, a township of Pennsylvania, in Mifflin county.

UPPER DISTRICT, a division of Georgia, which contains the counties of Montgomery, Washington, Hancock, Greene, Franklin, Oglethorp, Elbert, Wilkes, Warren, Columbia, and Richmond.

UPPER DUBLIN a township of Pennfylvania, in Montgomery county.

UPPER FREEHOLD, a township of New-Jerfey, Monmouth co. adjoining to Burlington and Middlefer counties N n 3 on the north and fouth-weft, and Freehold on the east. It contains 3442 inhabitants.

566

UPPER GREAT MONADNOCK, in the townfhip of Lemington, in the northeaft corner of Vermont, on Connecticut river.

UPPER HANOVER, a township of Pennfylvania, Montgomery county.

UPPER MARLBOROUGH, a polttown of Maryland, 16 miles fouth-caft of Bladeníburg, 15 north-caft of Pifcataway, and 162 fouth-welt of Philadelphia.

UPPER MILFORD, a township of Pennfylvania, Northampton county.

UPPER PENN'S NECK, a township of New-Jersey, Salem county.

UPPER SAURA, a place in N. Carolina, on Dan river, about 200 m.h.s from Halifax.

UPPER SAVAGE *Mands*, in Hudfon's Bay. N. lat. 62. 32. 30. W. long. 70. 48.

UPTON, a township of Massachusetts, Worcester co. containing 900 inhabitants, dispersed on 13,000 acres of land, favourable for orcharding, pasturage, and grass. It is west of Sherburne in Middlesex co. 15 miles south-east of Worcester, and 38 south-west of Boston.

UPRIGHT Bay, near the weft end of the Straits of Magellan. S. lat, 53. 8. W. long. 75. 35.

URACHO, a river, on the east coast of S. America, is 18 leagues W. N.W. of Caurora river.

URAGUA, a province in the eaft division of Paragnay, in South-America, whole chief town is Los Royes.

URANO, a river on the north coaft of S. America, which enters the ocean abreaft of the westernmost of the Peritas Islands, about three leagues westward of Comana Bay. It only admits small boats and cances. Otchier Bay is to the W. of it.

URBANNA, a finall post-town of Virginia, Middlefex co. on the fouth-weit fide of Rappahannock river, 22 miles from Stingray Point, at the mouth of the river, 73 fouth-east of Frederickfburg, 73 east by fouth of Richmond, 28 from Tappahannock, and 291 from Philadelphia. Wheat is shipped from this to Europe, and Indian corn, &c. to New-England, Nova-Scotia, and the West-Indics.

VAC

URVAIG, or Urvaiga, a province of South America; bounded by Guayra on the north, the mouth of Rio de la Plata on the fouth, the captainry of del Rey on the E. and Parana on the W. from which it is divided by the river of that name. Its extent is from lat. 25. to 33. 20. fouth ; the length from northeaft to fouth-east being foniewhat above 210 leagues, and the breadth from E. to W. where broadeft, 130, but much narrower in other parts. It is divided by the river Urvaiga, or Uruguay into the east and west parts. This river runs above 400 leagues, the upper part with a prodigious noife among rocks and ftones, and falls into the La Plata almost opposite to Buenos Ayres.

USTAYANTHO Lake. See Uifayantha.

UTAWAS, a river which divides Upper and Lower Canada, and falls into Jefus Lake, 118 miles fouth-weft of Quebec. It receives the waters of Timmiskamain 360 miles from its mouth 1 85 miles above it is called Montreal river.

UTRECHT, Now, a township of New-York, King's co. Long-Island. It has a Dutch church, and contains 362 inhabitants; of whom 76 are electors, and 206 are flaves. It is 7 or 8 miles southward of New-York city.

UXBRIDGE, a township of Maffachuletts, Worcester co. 41 miles south-west of Boston. It was taken from Mendon, and incorporated in 1727, and Northbridge was afterwards taken from it. It contains 180 dwelling-houses, and 1308 inhabitants. It is bounded south by the State of Rhode-Island. Not far from Shoe log Pond, in the south-west part of the town, there is an iron mine which is improved to considerable advantage.

v

WACCAS, Cayo, one of the Tortugas, or Florida Keys, to the ealtward of Bahia Honda; the diftance between themis 4 leagues, and the coaft in its direction turns to the northward. On the S. fide of Cayo Vaccas, about 8 miles from the W. end, there are wells of frefr water. A thick range of files go by this name. Bahia Honda is in lat. 24.35.N. VACCA, called alig the Cow 7, or Neat 1, Neat's, coaft of bounds ward. VAC fouth co the iffar 41 leas part a 1 The S. Abacon from Pa foil, wi very ct Spanish with C Afh Ifl it is pr VAC and Bi Newfor S. E. (point h tia on I the ent but th lork u VAL on the It lies Receif ed to th VAI of the VA the Ir city o New-S vernor of Me feated Gulf (illo, a 14. JC VA VA of Ca Amer quicir lat. I VA kill Fi Here his ar 1777: feffior VA town ing a

Neat's, Tongue, a low point on the W. coaft of Chili, in S. America, which bounds the Bay of Tonguey to the weftward.

e of

lyra

e la

del

w.

r or

25.

rth-

pove

1 E.

uch

ided

into

runs

with

and

muft

van-

Up-

into

t of

'im-

ath:

treal

lew-

125 2

abi-

206

bup

chu-

weft

don,

rth-

. It

308

the

rom

part

hich

ige.

igas,

rd of

wern.

sdi-

n the

from

wa-

this

5.N.

at s,

or

VACHE, or Cows Ifland, lies on the fouth coaft of the fouthern peninfula of the ifland of St. Domingo, and is about $A\frac{1}{2}$ leagues long, and in the broadeft part a league and a half, from N. to S. The S. point is 3 leagues E. of Point Abacou; and in lat. 13. 4. N. aud long. from Paris 76. 2. W. It has a very good foil, with 2 or 3 tolerable ports, and lies very conveniently for trade with the Spanifh colonies on the continent, and with Cayenze. The leamen call this Afh Ifland, a corruption from Vafh, as it is pronounged.

VACH ET LE TORREAU, or Cogu and Buil Rocks, on the fouth coaft of Newfoundland Ifland, are about a mile S. E. of Cape St. Mary, which is the point between the deep bay of Placentia on the W. and St. Mary's Bay on the enft. They are fair above water, but there are others near them which lork under water.

VAE's Ifland, Anthony. a finall ifland on the E. coatt of Brazil, in S. America, It lies to the fouthward of the fandy Receif, and opposite to it, which is joined to the continent by a bridge.

VAISSEAUX Island, on the N. fhore of the Gult of Mexico. See Ship Island.

VALADOLID, or Valladolid, called by the Indians Comayagua, is the chief city of the province of Honduras, in New-Spain. It is the feat of the Governor, and is a bifhop's fee, fuffragant of Mexico, fince the year 1558. It is feated on a plain, 30 miles W. of the Gulf of Honduras, 170 S. W. of Truxillo, and 65 S. E. of Merida. N. lat. 14. 10. W. long 51. 21.

VALDIVIA. See Baldivia.

VALENCIA, a town in the province of Caracas, on Terra Firma, South America, about 80 miles N. of Baraquicimeto, and 250 W. of Cumana. N. lat. 10. W. long 67.

VALLEY Forge, a place on Schuylkill river, 15 miles from Phila telphia. Here Gen. Wathington remained with his army, in huts, during the water of 1777_{y} after the British had taken polfeffion of that city.

VALPARAISO, a large and populous rown of Chill, in South-America, having a harbour forming the port of St. Jago, in lat. 33. 2. 36, S. and long. 77. 29. W. It is 390 mike E. of the ifland of Juan Fernandes. It carries on a confiderable trade with the port of Callao.

VANCOUVER'S Fort, in Kentucky, ftands at the junction of the two branches of Big Sandy river, 20 miles N. of Harmar's Station.

VAN DYKES, Jof and Little, two of the imaller Virgin Islands, fituated to the N. W. of Tortola. N. lat. 18. 25. W. long. 63. 15.

VANNSTOWN, in the country of the Cherokees, lies on a branch of Alabama river.

VASE River, Au, empties into the Miffilippi from the N. E. 3 miles below the Great Rock, about 55 N.W. by N. of the mouth of the Ohio, and about the fame diftance N.W. of Fort Maffac. It is navigable into the N. W. Territory about 60 miles, through a rich country, abounding in extensive natural meadows, and numberlefs herds of buffaloc, deer, &c. It is about eight miles above Cape Sr. Antonio.

VASSALBOROUGH, a post-town of the District of Maine, in Lincoln co. on Kennebeck river, half way between Hallowell and Winflow, 204 miles N. by E. of Boston, and 551 from Philadelphia. It was incorporated in 1771, and contains 1240 inhabitants.

VAUCLIN Bay, on the east coast of the island of Martinico. Vauclin Point forms the fouth fide of Louis Bay, on the E. coast of the fame island.

VAVAOO, one of the Friendly Iflands in the S uth Pacific Ocean. It is about two days fail from Ha ace.

VEALTOWN, a village of New-Jerfey, near Baskenridge, about 7 miles fouth wefterly of Morristown.

VEAU, Anfe a, a village on the north fide of the jouth peniniula of the ifland of St. Domingo: 5 leagues W. by N. of Miragoane, $4\frac{1}{2}$ eathward of Petit Trou, and 19 N. E. of Les Cayes.

VEOA, or Conception of la Vega Real, a town in the N. E. part of the ifland of Sr. Domingo, on the road from St. Domingo city to Daxabon. It is intuated near the head of Yuna river, which empties into the bay of Samana ; 12 leagues N. W. by W. of Cotoy, and about 38 eatherly of Daxavon, or Daxabon. It flands on a beautiful plain among the mountains, on the very foot N n 4 where where Guarionex, cacique of the kingdom of Magua, had relided. In 1494, or 1445, the fettlement of this town was begun by Columbus. Eight years after, it had become a city of importance, and fometimes during the year, there were \$40,000 crowns in gold, minted at this place. It was almost destroyed by an earthquake in 1564.

VEGA, St. Jago de la. See Spanifb Town.

VEJAS, or Morro de Vejas, on the coaft of Peru, is about half a league from the ifland of Lobos.

VELA, a cape on the coaft of Terra Firma, S. America, in about lat. 12. N. and long. 72. W. and about 18 leagues N. by E. of the town of La Hacha.

VELAS, or Velafes a port on the weft coaft of New Mexico, is 7 leagues N. W. by N. of the Morro Hermoia, and 8 from St. Catharine's Point.

VELICALA, a town on and near the head of the peninfula of California, near the coall of the N. Pacific Ocean, and northerly from Anclote Point. N. lat. about 20, 35. W. long. 115. 50.

VENANGO Fort. See Fort Franklin.

VENEZUELO, a province of Terra Firma, bounded eaft by Caracas, fouth by New-Granada, weft by Rio de la Hacha, and on the north by the North Sea. It abounds with game and wild beafts, producing plenty of corn twice a year, with fruits, fugar, and tobacco, and the best cocca plantations in America. It fpreads round a gulf of the fame name that reaches near 30 leagues within land; and the middle of this country is occupied by a lake 20 leagues long, and 30 broad, with a circumference of 80, and navigable for veffels of thirty tons. It communicates with the gulf by a ftrait, on which is built the city of Maracaibo, which gives name to both lake and strait, which is defended by feveral forts, which were attacked in the laft century by Sir Henry Morgan and the whole coaft laid under contribution, and Maracaibo raniomed. The province is about 100 leagues in length, and as much in breadth. / It had its name from its finall lagoons, which make it appear like Venice at the entrance of the lake. The Spaniards maf facred above a million of the natives in 1518. In 1550, the country was again depopulated, when a great number of black flayes were brought from Africa,

and was one of the principal epochs of the introduction of negroes into the Weft-Indies. Soon after, a revolt of the negroes was the caufe of another maffacre, and Venezuela became again a defert. At piesent it is faid to contain about 100,000 inhabitants, who live tolerably happy, and raife great numbers of European theep. They cultivate tobacco and fugar, which are famous over all America. They manufacture alfo fome cotton fluffs. It has many populous towns, and its waters have gold fands. Its capital, of the fame name, or Cora, fan is near the fea-coaft, about 50 miles S. E. of Cape St. Roman. N. lat. 10. 30. W. long. 70. 15.

VENEZUELO, a spacious gulf of the same province, communicating by a narrow Arait- with Maracaibo Lake. See the former article.

VENTA de Cruz, a town on the Ifthmus of Darien and Terra Firma. Here the Spanish merchandise from Panama to Porto Bello is embarked on the river Chagre, 40 miles south of the latter, and 20 north of the former. N. lat. 9. 26. W. long. 81. 36.

VENTO Sierra, on the north coaft of S. America, are mountains fo named, behind the land called Punta de Delrio, opposite to Tortugas Island.

VENUS, Point, in Otaheite Island, in the South Pacific Ocean, is the east point of Matavai or Port Royal Bay, and north point of the island. S. lat. 17. 29. W. long. 149. 36.

VERA Cruz, La, the grand port of Mexico, or New-Spain, having a fafe harbour protected by a fort, fituated on a rock of an ifland nearly adjoining, called St. John de Ulloa, in the Gulf of Mexico. It is, perhaps, one of the most confiderable places for trade in the world, being the natural centre of the American treasure, and the magazine for all the merchandize fent from New-Spain, or that is transported thither from Europe. It receives a prodigious quantity of East-India produce by way of Acapulco, from the Philippine Iflands. Most of its houses are built of wood, and the number of Spanish inhabitants is about 3000, mulattoes and mungrels, who call themfelves white. It is rather unhealthy, from the rank bogs around it. N. lat. 19. 12. weft long. 97. 30. It is in the east extremity of the province of Tlascala, or Los Angelos.

gelos. At the Old Town, 15 or 16 miles further weft, Cortez landed on Good Friday, 1518, when, being determined to conquer or die, he funk the fhips that transported his handful of men hicher. La Vera Cruz is 215 miles S. E. of the city of Mexico.

he a.

e-

in

0-

18

0-

er

6

u.

ld

or

50

1e

2

e.

1-

e

12

 \mathbf{r}

d

hf

VERA Cruz, La; an excellent harhour in the Bay of San Felipe Sant-Yago, on the north fide of the Island Espiritu Santo. See Tierra Austral del Espiritu Santo.

VERAGUA, by Ulloa made a province of Terra Firma, in South America, but others have it as a province of Guatimala and New Spain, in N. America; joining on the W. to Cotta Rica; on the E. to Panama; with the North Sea on the north, and the South Sea on the fouth. The coaft was first discovered by Christopher Columbus in 1503, to whom it was granted with the title of Duke, and his posterity still enjoy it. The province is very mountainous, woody, and bar en, but has inexhauftible mines of filver, and fome gold, the duft of the latter being found among the fands of the rivers. Santiago de Veraguas, or Santa Fe, the capital, is but a poor place; and in this province is the river Veragua, on which that town ftands.

VERAGUA, the river above mentioned, empties into the fea 18 leagues to the fouth-eaft of the river or lake of Nicaragua, in lat. 10. 5. N. Here is a very good port; but the ifland at its mouth is foul. The best anchorage is on the west and fouth fides next the main, where faips may ride under shore in from \$ to 9 fathoms, and fast from the north and easterly winds, that are most violent on this coast, Several islands lie off from the coast, both fingly and in clusters, from this to Cape Gracias a Dios; and to the eastward from hence is Chagre river.

VERA Paz, a province of the audience of Guatimala, and New Spain, in N. America. It has the Bay of H nduras and Chiapa on the north, Guatimala on the fouth, Honduras on the eaft, and Soconuica, with part of Chiapa, on the weft. It is 48 leagues long, and 28 hroad. The lands are mountainous, yielding little corn, but abounding in cedar, &c. The principal commodities are drugs, cocoa, cotton, wool, honey, &c. Its capital of the fame name, or

Cobaw, flands on the weft fide of a river which runs into Golfo Dulce, 184 miles E. of Guatimala. N. lat. 15. 10. W. long. 93. 15.

long. 93. 15. VERDE, or Green Ifland, on the N. coaft of S. America, is at the mouth of the river St. Martha.

VERDE Key, one of the Bahama Iflands. N. lat. 22. 12. W. long. 75. 15.

VERDE, PORTO, or Vedra, is on the N. Atlantic Ocean, about 41 leagues S. E. by E. of Rio Roxo. The illand of Blydones is at the entrance of this port, round which fhips may fail on any fide, there being 7 fathoms on the N. where it is fhoaleft, and 20 fathoms on the S. fide, where is the bell entrance into the river. This is a port of good trade, and fometimes large faips put in here. The illands of Bayonne are 5 leagues to the S. of the illand in the mouth of the port.

VERDERONE, or La Bourlarderie, an island on the E. coast of Cape Breton Island. It is 7 or 8 leagues long 3 and at each end is a channel, through which the waters of the Labrador Lakes, in the inner part of Cape Breton Island, discharge into the ocean on the E.

VERE, a parifh of the island of Jamaica, having Manury Bay in it; a very fecure road for shipping.

VERGENNES, a post-town, and one of the most growing and commercial towns of Vermont, in Additon co. on Otter Creek, about fix miles from its mouth in Lake Champlain. It is regularly laid out, and contains a Congregational church, and about 60 houses. In its neighbourhood are feveral mills. It is 115 miles N. of Bennington, 22 S. of Burlington, and 407 N. E. by N. of Philadelphia. The township contained 201 inhabitants in 1790.

VERINA, a finall village, and Spanish plantation of New-Andalusia, and Terra Firma, S. America. Its tobacco is reputed the best in the world. It lies 60 miles E of Cumana.

VERMEJA, or Kermillion Bay, on the north fhore of the Gulf of Mexico, or coaft of Louifiana. It is to the N.W. of Afcenfion Bay, in about lat. 30. N. and long. 92. W.

VERMEJO, or *Bermejo*, an ifland and port on the coaft of Peru, 2 degrees N. and a little W. of Lima. It is 4 leagues from Mongon on the N. and 6 from Guarmey Port on the S.

VERMILLIAS Barreyeras, on the coaft

of Brazil, between the Island of St. John's and Sypomba Island, which are > leagues afunder. Here is a large bay with good anchorage. VERMILLION, Putple, or Red Sea, a

VERMILLION, Putple, or Red Sea, a name given by fome to the gulf of California.

VERMILLION Point, called alfo Long Point, is the peninfula between Bay Puan and Lake Michigan.

VERMILLION River, in the N.W. Territory, runs north-weflward into Illinois river, nearly opposite the S.W. end of Little Rocks, and 267 miles from the Miffifippi. It is 30 yards wide, but fo rocky as not to be navigable.

VERMILLION Indians refide 220 miles up the Miami of the Lake.

VERMONT, one of the United States of America, lies between lat. 42. 44. and 45. north, and between long. 71. 32. and 73. 25. weft. It is bounded N. by Lower Canada; E. by New Hamp thire, from which it is feparated by Connecticut river ; S. by Maffichufetts ; and W. by the State of New-York. No part of the State is nearer than 70 or 80 miles of any part of the ocean. Computing by the latitudes, the length of the State from the fouthern to the northern boundary is 1571 miles : the mean width from E. to W. is about 65 miles : this will give 10,2371 fquare miles of land and water. It is divided into 11 counties, viz. those on Connecticut river from fouth to north are Windham, Windfor, Orange, Caledonia, and Efficx ; in a fimilar direction, along the New-York line, are the counties of Bennington, Rutland, Addition, Chittenden, and Franklin, between which laft and Effex, lies the county of Orleans, on the north line of the State. These are subdivided into upwards of 230 townships, which are generally 6 miles fquare. In each township is a referve of 2 rights of land, of 350 : cres each, the one for the fupport of schools, the other to be given in fee to the first minister who settles in the township. A part of the townships were granted by the governor of New-Hampfhire, and the other part by that of Vermont. In those townships granted by the former, a right of land is referved for the support of the gospel in foreign parts; in those granted by the latter, a college right, and a right for the import of country grammar-fchools, are relerved. In these relervations, h-

beral provision is made for the support of the gospel, and for the promotion of common and collegiate education. Windfor, on the east fide of the Green Mountains; and Rutland, on the west fide; both nearly in the centre of the fettled parts of the State from north to fouth, are, according to an act of the legiflature, to be alternately the feat of government, till about the year 1800. Both are flourithing towns. In 1790, according to the centus then taken, the number of inhabitants in this State was 85,589. This number has fince greatly increased. The people are an industrious, brave, hardy, active, frugal race. The foil is deep, and of a dark colour, rich, moift, warm, and loany. It bears corn and other kinds of grain, in large quantities, as foon as it is cleared of the wood, without any ploughing or preparation; and after the first crops, naturally turns to rich pafture or mowing. The face of the country exhibits very different profpects. Adjoining to the rivers, there are the wide extensive plains of a fine level country. At a fmall distance from them, the land rifes into a chain of high mountains, interfected with deep and long vallies. Defcending from the mountains, the freams and rivers appear in every part of the country, and afford a plentiful fupply of water. Through this State there is one continued range of mountains, which are called the Green Mountains, from their perpetual verdure, and gives name to the State. They extend from Lower Canada S. through the States of Vermont, Maffachufetts, and Connecticut, and terminate within a few miles of the feacoast. Their general direction is from N. N. E. to S. S. W. and their extent is through a tract of country, not less than 400 miles in length. They are generally from 10 to 15 miles in breadth; are much interfected with vallies; abound with fprings and ffreams of water; and are covered with woods. Kellington Peak, one of the highest of the Green Mountains, is 3,454 feet above the level of the ocean. All the fireams and rivers of Vermont rife among the Green Mountains; about 35 of them have an easterly direction, and fall into Connecticut river; about 25 run westerly, and pay tribute to Lake Champlain. Two or three running in the lame direction fall into Hudfon's river. In the north-eafterly parts

D

5

5

,

t

of the State, 4 or 5 ftreams have a northerly direction, and discharge their waters into Lake Memphremagog; from thence through the river St. Francis, they communicate with the river St. Lawrence. The most confiderable on the welt fide of the Green Mountains are Otter Creek, Onion river, La Muille, and Mischiscoui. On the east fide of the Green Mountains, the rivers are not fo large as those on the west, but they are more numerous. The largest are Wantaftiquek, or Welt river, White river and Pooutoomfuck. The earth is generally covered with fnow from the middle of December to the middle of March, and in fome high lands, to the depth of 4 or 5 feet. Since the country has been cleared, the winters have proved milder. Vegetation advances in the fpring with great rapidity. Iron and lead ores of feveral kinds, pipeclay, which has been wrought into durable crucibles, and quarries of white, grey, and variegated marble, have been found in different parts of this State. The trade of Vermont is principally to Bofton, Hartford and New York; to which places the inhabitants export horfes, beef, pork, butter, cheefe, wheat, flour, iron, nails, pot and pearl afhes. Great advantages may accrue to Vermont, from the manufactures of iron. Large quantities of iron-ore are found in feveral of the towns on the weft fide of the Green Mountains. Tinmouth, Rutland, Pittsford, and Shoreham contain great quantities. The ore in these towns is of a reddifh kind, mixed with earth, tinctured with yellow ore. It melts eafily, and p oduces from one-fourth to one leventh of iron. The iron is mostly of the coldinire kind; works eafily, and makes excellent nails. The principal part of the ore hitherto uled, has been brought from a mountain on the weft fide of Lake Champlain, about 4 miles north of Crown-Point. Some grains of pure iron, nearly as big as a pea, have been found in this ore. This ore is fo peculiarly rich, that, when well managed, it will yield four-fevenths of pure iron, but is very hard to melt. In 1792, feveral torges and furnaces were creeted. In Bennington co, they have 1 forge; in Rutland co. 14; in Addition co. 4; and in Chittenden co. 2. In addition to which there are 3 furnaces in Rutland county.

From thefe, great quantities of bar-iron and nails are made. Nature, indeed, feems to have defigned this part of the United States to be the feat of flourishing manufactures of every thing that can be made of iron or ficel. The other chief manufactures are pot and pearl afhes, maple fugar, and fpirits diffilled from grain. Most families manufacture a confiderable part of their cloathing. In no country is common education more attended to. In this refpect the conduct of the people is laudable and exemplary. A charter for a richly endowed univerfity was granted by the legislature of this State, in 1791, to be eftablished at Burlington; and 33,000 acres of land have been referved, in the feveral grants made by this State, for the use of the university. In 1792, the ftate of the militia was as follows : 20 regiments of infantry, divided into 8 brigades, and 4 divisions ; 15 companies of cavalry, and 6 companies of artillery ; the whole computed at 18,500. Vermont fends two reprefentatives to Congreis, and has been fettling only fince about the year 1764. The Indians were never numerous here; and at prefept it is entirely deftitute of them.

VERNON, a place in Soffex co. New-Jeriey, eaft of the fource of Wall Kill, and about 21 miles N. E. of Newtown.

VERNON, Mount, the feat of General Washington. See Mount Vernon.

VERRETTES, a fettlement in the French part of the Island of St. Domingo, on the S. W. bank of Artibonite river; 4 miles S. by E. of the fettlement of Petit Riviere.

VERSAILLES, the chief town of Woodford co. Kentucky; fituated on a fmall ftream which falls into Kentucky river. It contains a court-house, ftone gaol, and about 30 houfes, and lies 13 miles W. by S. of Lexington.

VERSHIRE, a township of Vermont, Orange co. adjoining Fairlee, and containing 439 inhabitants.

VERT Bay, or Green Bay, in the Straits of Northumberland, in N. America, opens to the N. E. opposite St. John's Ifland. The head of the bay approximates within 12 miles of the northeasternmost branch of the Bay of Fundy. It is about to leagues to the N. W. of Tatamagauche Harbour, and ferves in part to feparate the British provinces

provinces of Nova-Scotia and New-Brunfwick,

VESSEL Bay, on the east thore of Lake Champlain, fets up to the N. E. in the township of Charlotte, in Vermont.

VICIOSAS Has, illes of the Bay of Honda, on the coaft of Honduras, or the Spanish Main.

VICTORIA, a town of New Mexico.

• VICTORIA, an island on the coaft of Bazzil, eastward of St. Sebastian's island.

VICTORY, Cape, is the extreme N. W. point of the Straits of Magellan, at the opening to the S. Pacific Ocean. S. lat. 52. 15. W. long. 76. 40.

at. 52. 15. W. long. 76. 40. VICTORY, a township of Vermont, Stuated in Effex co and bounded cast by Guildhall, on Connedicut river.

VIENNA, a port of entry and pofttown of the eaftern fhore of Maryland, Dorchefter county, on the weft lide of Nanticoke river, about 35 miles from its mouth. It contains about 30 houles, but carries on a brifk trade with the neighbouring fea-ports, in lumber, corn, wheat, &c. Its foreign exports in 1794, amounted to 1,667 dollars. It is 15 miles N. W. of Salifbury, 32 S. S. E. of Eafton, and 150 S. S. W. of Philadelphia.

VIENNA, the capital of Greene co. Kentucky; fituated on the north fide of Green river, about 158 miles W.S.W. of Lexington.

VILLA de Moje, a town in the province of Tabaico, 4 leagues from the town of Estape, on Tabasco river.

VILLA Hermofo, a town of Mexico or New-Spain, near the mouth of a river which talls into the Bay of Campeachy, and Gulf of Mexico.

• VILLA Nooa; in Brazil, about 120 miles welt of Porto Seguro, and as far fouth-eaft by fouth of Carlofa.

VILLA Rica, or Ameria, a town of Thafcala or New Spain, in N. America. It funds on the coaft on a fmall river, having an indifferent port, but in a better air than Vera Cruz, 20 leagues north of the latter. A clandelline trade is carried on here between fome of the Spanish merchants on fhore, and the French of St. Domingo and Martinique. VILLIA, La, a town and river of Veragua and Guatimala audience, in New-Spain. It is about 7 leagues from Nata, Bordening on Panama. The river is

sport. Vol.1

very large, and at low water breaks at the mouth as on a flat thore; fo that large thips anchor within cannon thot, but barks of about 40 tons may go up about a league and a half. The harbour is a quarter of a league above the town. About a league to the windward, is a large rock, generally covered with valt numbers of wild fowl.

VINALHAVEN, a township on the cost of the District of Maine, in Hancock co. containing 578 inhabitants. It is fouth east of Deer Island, and 259 miles from Boston.

VINCENTS, Fort, in the N. W. Territory, stands on the cast fide of Wabash river, 150 miles from its mouth. It was erected in the year 1787, in order to repel the incursions of the Wabash Indians, and to fecure the weftern lands from in-truding fettlers. It has 4 finall brafs cannon, and is garrifoned by a Major and 2 companies. The town of Vin-cents contained, in 1797, about 1,500 touls, principally of French extraction. It is 300 miles S. W. of Fort Recovery. N. lat. 39. 15. W. long. 90. 7. They raife Indian corn, and wheat; and tobacco of an extraordinary good quality ; fuperior, it is faid, to that produced in Virginia. They have a fine breed of hories, brought originally by the In-dians from the Spanish settlements, on the weftern ide of the Millilippi. Here are large herds of fwine, and black cattle, and the feitlers deal with the Indians for Jurs and deer-fkins. Hemp of a good quality grows fpoutaneoufly in the low lands of the Wabafh; as do grapes, of which the inhabitants make a fufficient quantity, for their own confumption, of well-tafted red wine. Hops, large and good, are found in many places, and the lands are particularly adapted to the culture of rice. All European fruits thrive well, both here, and in the country bordering on the river Ohio.

VINCENT, St. one of the 14 captainthips of Brazil, in S. America, and the molt foutherly one. The capital is an inconfiderable place, with only about 60 houfes, and the harbour will not receive large veffels. It has 5 or 6 lugar-mills, and lies 76 leagues fouth-weft of Rio Janeiro. S. lat. 23. 40. W. long. 45. 10.

VINCENT, St. a town on the coaft of Brazil; fituated on Amiaz Ifland, in the Bay of All Saints or Sanctos; in which

which island is the city of Dos Sanctos, the island lying on the west fiele of the entrance into the island. S. lat. 24. 15. W. long. 46. 30.

VINCENT, de la Pazes, St. or Onda, a town of Popayan and Terra Firma, in S. America; about 25 miles eaftward of San Sebattian, with a port where canoes from Carthagena and St. Martha unload their merchandize.

VINCENT, a township of Pennsylvania, fituated in Chester county.

VINCENT, St. one of the Caribbee Idands, in the American ocean. It lies between 61. 10. and 61. 18. W. long. and between 13. 5. and 13. 19. N. lat. being about 17 miles long from the east fide of Tyrrel's Bay, the extreme fouthern point of the ifland to Tarraty Point, its northern extremity; and about 10 broad from the mouth of Calonery river, east to Cumberland Bay, at the mouth of Washilabo river on the west. On this island are feveral mountains, which crofs it from north to fouth, from which iffue feveral rivers full of fifh ; among which are 22 capable of turning ingarmills: these mountains are in general of an eafy afcent; the vallies fertile and extenfive, and the clearing the ground has rendered the climate healthy. Of 84,000 acres which the ifland contains, 23,605 are at prefent possessed by British fubjects, and about as much more is fuppofed to be held by the Ch raibes; and the remainder is thought to be incapable of cultivation. This is the only ifland of the Antilles, where the fmall remains of the natives (with a mixture of negro blood) exift in the form of a nation. At the peace in 1763, the British government fold the lands of St. Vincent, as it had those of Tobago, and left the French (whom the fear of confication had not driven away) those they pol feffed, paying a moderate fine, and a yearly rent ftill more moderate. Thefe proceedings encroaching upon the polfeffions of the Charaibes, occasioned their reffitance, which the troops fent against them could not fubdue, and a peace was concluded with them in 1773, and lands affigned them; fince that time St. Vincents has enjoyed internal tranquillity. The number of inhabitants appears to be 1,450 whites, and 11,853 negrocs. St. Vincents is divided into 4 parifhes, St. David, St. Patrick, St. Andrew, and St. George. Its towns are Kingfton,

the capital, and Richmond ; the others are villages or hamlets, at the feveral bays and landing places. The iflands dependent on the St. Vincent's government, are Bequia, containing 3,700 acres ; Union, 2,150 acres ; Canouane, 1,777 acres ; and Muftique, about 1,200 acres. Of the above 11,853 negroes, about 1,400 are employed in the cultivation of there iflands. There are likewife the little iflots of Petit Martinique, Petit St. Vincent, and Ballefeau, each of which produces a little cotton. The total exports in 1789, in 122 veffels, from St. Vincents, amounted in value, according to the current prices in London, to £186,450 : 14 : 8, including exports to the American States, to the value of (9,019:1: 8 fterling. The cargoes confifted of 65,128 cwt. 1 qr. 27lbL fugar; 88,266 gallons rum; 0,656 gallons molaffes; 634 cwt. 1 qr. 5lb coffee ; 761,880 lbs. cotton ; 143 cwt. 24lb. cocoa; belides hides, dying woods, &c. Here they cultivate cinnamon, mango, fefamum, vanilla, China tallowtree, camphor, gum-frorax, Sec. It is about 20 leagues welt of Barbadoes.

VINCENT, Port St. on the coaft of Chili, in the S. Pacific Ocean, is 6 miles N. N. E. of the mouth of the river Biobio, having a fafe harbour, and fecure against all winds but the west, which blows right in. Talcaguama Port is 6 miles to the northward of it.

VINCENTO, a channel which goes in on the weft fide of the channel of Amiaz Ifland, in the Bay of All Saints, on the coaft of Brazil.

VINER'S Ifland, in Hudfon's Bay, lies N. E. of the mouth of Albany river.

VINEYARD, New, 'a plantation in Lincoln co. Diffrict of Maine, on the two north-easternmost branches of Sandy river, about 59 miles N. by W. of Bruntwick, and 37 N.W. of Hallowell.

VINEYARD Sound, on the S. eastern coaft of Maffachusetts, is the firait or passing between the Elizabeth Islands and Martha's Vineyard. The S. W. channel of which, about 7 miles broad, has Gay Head on the S. E. and the Sow and Pigs on the N. W.

VIPER Key, one of the Tortugas, on the coaft of Florida; 5 miles N. eaftward of Duck Key, and 31 E. of Old Matacombe.

VIRGIL, a military township of Onondago co. New-York, having Dryden on

the W. Cincinnatus E. Homer N. and on the S. 230,000 acres of land on Suiquehannah river, ceded to the State of Maffachufetts. It is under the jurifdiction of Homer, which was incorporated in 1794.

VIRGIN GORDA, one of the principal of the Virgin Ifles, in the Weft-Indies. It lies 4 leagues to the E. of Tortula, and of a very irregular fhape. Its greateft length from E. to W. is about 18 miles; is worfe watered than Tortula, and has fewer inhabitants. A mountain which rifes in its centre, is affirmed to contain a filver mine. N. lat. 18. 18. W. long: 64

VIRGINIA, one of the United States, lies between 36. 30. and 40. 30. N. lat. and between 75. 54. and 83. 8. W. long. It is in length 446 miles, in breadth 224; containing about 70,000 fquare miles. Bounded north by Maryland, part of Pennlylvania, and Onio river; weft by Kentucky; fouth by North Carolina, and eaft by the Atlantic Ocean. This State is divided into 82 counties, (and by another division into parishes) which, with the number of inhabitants, according to the cenfus of 1796, are mentioned in the following tables

TABLE.

Weft of the Blue Ridge. Slaves, To: Inhabit: Counties. Ohio 281 5212 Monongalia 4768 154 Walhington 5625 450 Montgomery Wythe 2087 23752 Botetourt Greenbriar 319 6015 Kanawa Hampfhire 454 7346 Berkly 2932 19713 Frederick 19681 42 50 Shenandoah 512 10510 Rockingham 773 7449 Angulta -1222 10886 Rockbridge 682 6548

Between the Blue Ridge and the Tide Waters.

the second se			
Louidoun	nist.	4030	18962
Fauquier		6642	17892
Culpepper		8226	22105
Spotiylvania		\$933	11252
Orange -	(- 1	4421	9921
Louita -		4573	8467
Geochland		4656	9053

 V	1	R	83
338	10.0	6735.	24.5

Countles.	22	slavės.	To. Inhabit
Flavania	4	1466	3921
Albemarle	2	5579	12585
Amherit	3	5296	13703
Buckingham	4	4168	9779
Bedford -		2754	10531
Henry -	4	1551	8479
Pittfylvania	4	2979	11579
Halitax -		5565	14722
Charlotte	2	4816	10078
Prince Edward		3986	8100
Cumberland	-	4434	8152
Powhatan		4325	6823
Amelia 1	5	CARGE L	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1
Nottaway	t	11307	18097
Lunenburg	20	4332	8959
Mecklenburg	1	6762	
Brunfwick	Ŷ	6276	14733

Between James River and Carolina:

Greenfville		3620	6362	i.
Dinwiddie		7334	13934	
Chefterfield	\bullet_{0}	7487	14214	
Prince George		4519	8173	
Surry -		3097	6227	
Suffex -	+	\$387	10554	
Southampton	•	5993	12864	
Ifle of Wight	•	3867	9028	
Nanfemond		3817	9010	
Norfolk -	1	5345	14524	
Princel's Ann	-	2202	7702	

Between James and York Rivers.

Henrico -	- 4	5819	12000	
Hanover -	-	8223	14754	
New-Kent		3700	6239	
Charles City		3141	5518	
James City	-	2409	4070	
Williamfburg York	3	2760	5233	
Warwick	-	990	1690	
Elizabeth City	7 -	1876	3450	

Between York and Rappabannock Rivers.

Caroline -		10292	17489	
King William	-	5151	8128	
King and Quee	n	5143	9377	
Effet -	-	5440	9122	
Midelefex	-	2558	4140	
Gloucetter	-	7063	13498	

Between Rappabannock and Patowmack Rivers.

Fairfax -	-	4574	12320
Prince William		4704	11615
Stafford -	-	4036	9588
King George	-	41 57	7366

	1.1	lownt	b
27	1.16	14203-54	
		ichr	
	V	Velt	n
.A.	N	orth	í
12		anci	
÷.	+	ante	
		1000	

North

Campb

Harrife

Hardy

Pendel Ruffel

Whol

In an ex pected th in all its proceedi tude we colder in ceed nor he the c the Alle between From th latitude verfes ; lers, it in the Their t vegetab multiply the feataneoul latitude Parroqu in the 3 W. wit moft p the featains, t differen great. vapour turers would occaño nels an north. animat breezes

VIR

41

Countica.		slaves.	To. Inhabit.
Richmond	i)iii	3984	6985
Weltmoreland	2	4425	7722
Northumberland	d .	4460	9163
Lancafter	•	3236	5638
Eafte	rn .	Shore.	
Accomac		4262	1 39 59
		3244	6889
New	Con	unties.	e el al degle en se
Campbell	*	2488	7685
Franklin -	.#		6842
Harrifon	4	67	2080
Randolph		19.	951
Hardy .	de la	369	7336
Pendelton		73	2452
Ruffel -	С н	190	3338
million and the second			and the sect of the

Whole number of Inhab. 747,610 Of whom 292,627 were flaves.

In an extensive country, it will be expected that the climate is not the fame in all its parts. It is remarkable that, proceeding on the fame parallel of latitude westwardly, the climate becomes colder in like manner as when you proceed northwardly. This continues to he the cafe till you attain the fummit of the Alleghany, which is the highest land between the ocean and the Millifippi. From thence, defcending in the fame latitude to the Miffifippi, the change reverfes; and, if we may believe travel. lers, it becomes warmer there than it is in the fame latitude on the fea fide. Their teffimony is firengthened by the vegetables and animals which fubfilt and multiply there natural'y, and do not on the fea-coaft. Thus catalpas grow fpontaneoully on the Millifippi, as far as the latitude of 37. and reeds as far as 38. Parroquets even winter on the Scioto, in the 39th degree of listitude. The S. W. winds, east of the mountains, are most predominant. Next to thefe, on the fea-coaft, the N.E. and at the mountains, the N. W. winds prevail. The difference between these winds is very great. The north-eaft is loaded with vapour, infomuch that the falt manufacturers have found that their cryftals would not fhoot while that blows; it occafions a diffreffing chill, and a heavinets and depreffion of the fpirits. The north weft is dry, cooling, elastic and The east and louth east animating. breezes come on generally in the after. | rivers. But the couries of the great

VIR. 575 noon. They have advanced into the country very fenfibly within the memory of people now living. Mr. Jefferson reckons the extremes of heat and cold to be 98 above, and 6 below o, in Farenheit's Thermometer. The months of June and July, though often the hotteft, are the most healthy in the year. The weather is then dry and lets liable to change than in August and September, when the rain commences, and fudden variations take place. On the feacoaft the land is low, generally within 12 feets of the level of the fea, interfected in all directions with falt creeks and rivers, the heads of which form fwamps and marfhes, and fenny ground, cover-ed with water, in wet featons. The uncultivated lands are covered with large trees, and thick underwood. The vicinity of the fea, and falt creeks and rivers, occafion a conftant moifture and warmth of the atmosphere, fo that although under the fame latitude, roo or 150 miles in the country, deep fnows, and frozen rivers frequently happen, for a fhort feafon, yet here fuch occur-rences are confidered as phenomena; for these reasons, the trees are often in bloom as early as the laft of February; from this period, however, till the end of April, the inhabitants are incommoded by cold rains, piercing winds, and tharp frosts, which fubjects them to the inflammatory difeafes, fuch as pleurify and peripneumony. The chief rivers are Roanoke, James's, Nanfemond, Chickahominy, Appamatox, Rivanna, York, Piankatank, Rappahannock, Patowmack, Shenandoah, and the great Kanhaway. Thefe rivers and creeks are described under their respective names. They abound with fifh of various kinds, as flurgeon, fhad, bafs, carp, heepfhead, drum, herrings, perch, catfith, oyfters, crabs, &c. It is worthy notice, that the mountains are not folitary and fcattered confuledly over the face of the country; but commence at about \$ 50 miles from the lea-coaft, are difpofed in ridges one behind another. running nearly parallel with the feacoaft, though wather approaching it as they advance north-eastwardly. See Alleghany Mountains. In the fame direction generally are the veins of lime-ftone, coal, and other minerals hitherto difcovered; and fo range the falls of the great **Fivers**

rivers are at right angles with thefe. James and Patowmack penetrate through all the ridges of mountains eaftward of the Alleghany, which is broken by no water-courfe. It is in fact the fpine of the country between the Atlantic on one fide, and the Miffifippi and St. Lawrence on the other. The paffage of the Patowmack through the Blue Ridge is perhaps one of the molt flupendous fcenes in nature. The mountains of the Blue Ridge, and of these, the Peaks of Ot. ter, are thought to be of a greater height measured from their bale, than any others in Virginia, and perhaps in North-America. From data, which may found a tolerable conjecture, we suppose the higheft peak to be about 400 feet perpendicular, which is not a fifth part of the height of the mountains of South-America, nor one third of the height which would be neceffary in our latitude to preferve ice in the open air unmelted through the year. The ridge of mountains next beyond the Blue Ridge, called the North Mountain, is of the greatest extent; for which reafon they are named by the Indians the The Ouafioto Endleis Mountains. Mountains are 50 or 60 miles wide at the Gap. Thele mountains abound in coal, lime, and free-flone; the fummits of them are generally covered with a good foil, and a variety of timber; and the low, intervale lands are Tich and remarkably well watered. The whole country below the mountains, which are about 1 50, fome fay 200 miles from the fea, is level, and feems from various ap. pearances to have been once, walked by the fea. The land between York and James rivers is very level, and its furface about 40 feet above high water mark. It appears from observation, to have arisen to its present height at dif. ferent periods far diftant from each other, and that at these periods it was washed by the fea; for near Yorktown, where the banks are perpendicular, you first fee a fratum, intermixed with finall shells refembling a mixture of clay and fand, and about 5 feet thick; on this lies horizontally, fmall white fhells, cockle, clam, &cc. an inch or two thick ; then a body of earth fimilar to that first mentioned, 18 mches thick ; then a layer of thells and another body of earth; on this a layer of 3 feet of white shells mixed with fand, on which lay a body

of oyfter thells 6 feet thick, which were covered with earth to the furface. The oyfter fhells are fo united by a very ftrong cement, that they fall only when undermined, and then in large bodies from 1 to 20 tons weight. They have the appearance of large rocks on the fhore. The foil below the mountains feems to have acquired a character for goodneis which it by no means deferves. Though not rich, it is well fuited to the growth of tobacco and Indian corn, and parts of it for wheat. Good crops of cotton, flax and hemp are also raifed ; and in fome counties they have plenty of cyder, and exquisite brandy, distilled from peaches, which grow in great abundance upon the numerous rivers of the Chefapeak. The planters, before the war, paid their principal attention to the culture of tobacco, of which there ufed to be exported, generally, 55,000 hogfheads a year. Since the revolution, they are turning their attention more to the cultivation of wheat, Indian corn, harley, flax and hemp. It is expected that this State will add the article of rice to the lift of her exports ; as it is supposed, a large body of swamp in the easternmost counties, is capable of producing it. Horned or neat cattle are bred in great numbers in the weffern counties of Virginia, as well as in the States fouth of it, where they have an extensive range, and mild winters, without any permanent fnows. They run at large, are not housed, and multiply very faft. " In the lower parts of the State a difeafe prevailed fome years ago among the neat cattle, which proved fatal to all that were not bred there. The oxen, from the more northern States, which were employed at the fiege of Yorktown, in October, 1781, almost all died, fometimes 40 of them in a night, and often fuddenly dropped down dead in the roads. It is faid that the feeds of this difease were brought from the Havanna to South-Carolina or Georgia in fome hides, and that the difeate has progreffed northward to Virginia. Lord Dunmore imported fome cattle from Rhode-Island, and kept them confined in a fmall pafture, near his feat, where no cattle had been for fome years, and where they could not intermix with other cattle, and yet they foon died." The gentlemen, being fond of pleafure, have taken much pains to raife a good breed

breed of 1 it beyond give 100 horfe. H tendency good horf of puttin fpeed:] will perf horfes of among th difcovered abundanc might be Virginia i rals and fo A fingle found, ne river, whi extraordir dication (its neight haway, o ple Creek the fouth the count of lead. times wi rock, whi powder to with a p be worth hitherto a tion yield metal from most cor I oolb. marble, li country. amethyfts difcovered between t rolled in county ar thefe agai according They are other fube lar fervic lieutenant militia in a Colone general o are appoi vation o their com fion. T litary as requires

\$76

16

y

11

13

e

ie.

19

S.

3.4

1e

d

Æ

ş

y d

t

f

e

13

e

0

n n)

١.,

3

p

e

e

n e

e

٢

f

9

1

¢

ŕ

1

ł

breed of horfes, and have fucceeded in it beyond any of the States. They will give 1000l. fterling for a good feed horfe. Horfe racing has had a great tendency to encourage the breeding of good horles, as it affords an opportunity of putting them to the trial of their fpeed: They are more elegant, and will perform more fervice, than the horfes of the northern States. Caves among the mountains, have lately been difcovered, which yield falt-petre in fuch abundance, that 500,000 pounds of it might be collected from them annually. Virginia is the most pregnant with minerals and foffils of any State in the Union. A fingle lump of gold ore has been found, near the falls of Rappahannock river, which yielded 17 dwt. of gold, of extraordinary ductility. No other indication of gold has been discovered in its neighbourhood. On the great Kanhaway, opposite to the mouth of Cripple Creek, and alfo about 25 miles from the fouthern boundary of the State, in the county of Montgomery, are mines of lead. The metal is mixed, fometimes with earth, and fometimes with rock, which requires the force of gunpowder to open it; and is accompanied with a portion of filver, too imall to be worth feparation, under any procefs hitherto attempted there. The proportion yielded is from 50 to 80lb. of pure metal from 100lb. of washed ore. The most common is that of 60 to. the 1 oolb. Copper, iron, black-lead, coal, marble, lime-frone, &c. are found in this country. Cryftals are common. Some amethyfts, and one emerald have been difcovered. Every able bodied freeman, between the ages of 16 and 50, is enrolled in the militia. Those of every county are formed into companies, and these again into one or more battalions, according to the numbers in the county. They are commanded by Colonels and other fubordinate officers, as in the regular fervice. In every county is a county lieutenant, who commands the whole militia in his county, but ranks only as a Colonel in the field. They have no general officers always exifting. Thefe are appointed occasionally, when an invalion or infurrection happens, and their commission ceases with the occafion. The Governor is head of the military as well as civil power. The law requires every militia man to provide | erected into a college by the name of

himfelf with the arms usual in the regular fervice. The interfection of Virginia by fo many navigable rivers, renders it almost incapable of defence. As the land will not fupport a great number of people, a force cannot foon be collected to repel a fudden invation. If the malitia bear the fame proportion to the number of inhabitants now, as in 1782, they amount to about 68,000. This fate is not divided into townfhips, nor are there any towns of confequence, owing probably to the interfection of the country by navigable rivers, which brings the trade to the doors of the inhabitants; and prevents the necessity of their going in queft of it to a diffance. The principal towns, or more properly villages or hamlets, are as follows. On James river, and its waters, Norfolk, Portimouth, Hampton, Suffolk, Smithfield, Williamfburg, Peterfburg, Richmond, the feat of goverment, Manchefter, Charlottesville, New-London. -On York river, and its waters, York, Newcaftle, Hanover .- On Rappanhannock, Urbanna, Port-Royal, Frederickfburg; Falmouth .---On Patowmack, and its waters, Dumfries, Colchefter, Alexandria, Winchefter, and Staunton. There are places, at which, like fome of the foregoing, the laws have faid there shall be towns; but nature has faid there shall not, and they remain unworthy of enumeration. Norfolk will probably become the emporium for all the trade of the Chefapeak Bay and its waters; and a canal of 8 or 10 miles, which is contemplated, and will probably foon be completed, will bring to it all that of Albemarle Sound and its waters. Secondary to this place, are the towns at the head of the tide waters, to wit, Peterlburg on Appamattox, Richmond on James river, Newcastle on York river, Frederickfburg on Rappahannock, and Alexandria on Patowmack. From these the distribution will be to fubordinate fituations of the country. Accidental circumstances, however, may control the indications of nature, and in no infrances do they do it more frequently than in the rife and fall of towns. The college of William and Mary was tounded about the beginning of this cen-tury. See William/burg. The academy in Prince Edward county has been 00 Hampden 578

Hampden Sidney College. There are a number of academies in different parts of Virginia, one at Alexandria, one at Norfolk, one at Hanover, and others in other places. The prefent denominations of Christians in Virginia are Prefbyterians, who are noft numerous, Epilcopalians, Baptifts, and Methodifts. The exports of this State, in the year 1791, ending Sept. 30th, amounted to 3,131,227 dollars; in 1792-3,549,499 dollars; in 1793-2,984,317; in 1794-3,321,494 dol-lars; and in 1796-5,268,615 dollars. In 1790, about 40,000 hhds. of tobac-co were exported ; but its culture has fince declined, and that of wheat taken its place. The greatest quantity of tobacco ever produced in this country, in one year, was 70,000 hhds. in the year 1758. Virginia was fettled permanently, after feveral preceding unfuccefsful attempts, in 1610, being the earlieft effablished of any of the United States.

VIRGIN Iflands, a group of finall iflands in the West-Indies, to the eastward of the Island of Porto Rico, belonging to different European powers. They extend for the space of 24 leagues, from E. to W. and about 16 leagues from N. to S. aud nearly approach the call coaft of Porto Rico. They are every way dangerous to navigators, thought there is a balon in the midft of them of 6 or 7 leagues in length, and 3 or 4 in breadth, in which thips may anchor and be fheltered and land-locked from all winds; which is named the Bay of Sir Francis Drake, from his haying paffed through them to St. Do-mingo. Thole which are occupied and inhabited appear under their respective names; but others are deftitute both of names and inhabitants. The British and Danes posses most of them; but the Spaniards claim those near Porto Rico. The ifland of Virgin Gorda, on which depend Anegada, Nicker, Prickly Pear, Molquito Illands, Camanoes, Dog-Illands, the Fallen City, the Round Rock, Ginger, Cooper's, Salt, Peter's, and Dead Cheft, belong to the Britifh; as alfo Tortola, on which depend loft Van Dykes, Little Van Dykes, Guana, Beef, and Thatch Islands: To the Danes belong St. Thomas's Mand, on which Brafs, Little Saba, Buck Ifland, Great and Little St. James, and Bird Mand are dependent ; with St. Jobn's,

nahorantéh.

to which depend Lavango, Cam, and Witch Iflands; and they have alfo San-ta Ifland, or St. Croix. The Spaniards claim Serpent's Ifland, (called by the British Green Island) the Tropic Keys, Great and Little Paffage Ifland, and particularly Crab Ifland. The booby birds are fo tame on Bird Island, that a man, it is faid, in a fhort time, may catch fufficient in his hand to fupply a fleet. These islands lie about lat. 18. 20. N. and the courfe through them, with due attention, is perfectly fafe at weft by north, and weft-north-weft as far as the welt end of the fourth ifland. Leave this on the ftarboard fide, and the ifland called Foul Cliff, on the larboard, between which there is 16 fathoms, and a free channel to the weftward, before there is any alteration of the courfe; for though there be but fix or feven fathoms in fome places, it is no where fhoaler, and in fome places The there is from 16 to 20 fathoms. ifland of Anguilla, on the north fide of St. Martin's Ifland, is E. S. E. from them.

VIRGIN MARY, Cape, the N. E. point of the entrance of the Straits of Magellan, in the S. Atlantic Ocean, is a fleep white cliff. S. lat. 52. 32. W. long. 67. 54. The variation of the compais, in 1780, was 24. 30. E.

VIRGIN Rocks, off the S. E. part of the coaft of Newfoundland Ifland, 2a leagues S. E. of Cape Race. N. lat. 46. according to others, lat. 46. 30. and these last fay 17 or 18 leagues S. E. by E. of Cape Ballard.

VITTORIA, St. Juan de, a cityof Peru. See Guamanga, its molt common name.

VOLCANIC Island, between Swallow Island and Santa Cruz, about 8 leagues north of the latter, in the Pacific Ocean, in which Mendana, in 1595, faw a volcano, which flamed continually. S. lat. 10. 30.

VOLUNTOWN, a township on the E. line of Connecticut, Windham co. E. of Plainfield, 19 N. E. of Norwich, and 26 S. W. of Providence. It was settled in 1696, having been granted to volunteers in the Narraganset war; hence its name. It was incorporated in 1719. It is 20 miles long, and between three and four broad, and has a large swamp abounding with white pine, sufficient to supply the neighbouring towns with materials for building.

ABA river. which runs a and empties 270 yards w miles from th 1012 miles fpring; fumn able in batte about 3 feet tanon; and further, to t o miles from lage ftands or ties into the The commu and the Illing up Miami thence by lan are high, and are low, the the Wabafh branches of of deftination is remarkabl has been di above Ouiata of the Wab free-ftone, bh are found in copper mine the richest v the bowels of cents and Out WABASH, E. and falls from the Ohi WACHOV

of land in N. the E. fide (head waters confifting of a in Stokes a United Brefl chafed this tr 1751, and ca name of an e in Germany. feparate pari the legiflatu Bethabara, v number of th vania. Saler fettlement, co inhabited by tradelmen.

w.

nd

in-

rds

the

by

t a

ply

at.

:m,

at

25

nd.

and

the

16

eft-

1 of

but

lces

The

fide

rom

E

's of

ean,

32.

1 of

t of

20

lat.

30.

i. E.

eru.

ame.

llow

gues

cean,

vol-

. lat.

ie E.

E. of

1d 26

ed in

teers

ame.

is 20

four

ound-

apply

erials

w.

Ε.

it

ABASH is a beautiful navigable river, of the N. W. Territory, which runs a S. W. and fouthern courfe, and empties into the Ohio; by a mouth 270 yards wide, in lat. 37.41. N. 168 miles from the mouth of the Ohio, and 1012 miles below Pittfburg. In the fpring, fummer, and autumn, it is paff able in batteaux and barges, drawing about 3 feet water, 412 miles, to Ouiatanon; and for large canoes 197 miles further, to the Miami carrying-place, 9 miles from Miami village. This village flands on Miami river, which empties into the S. W. part of Lake Erie. The communication between Detroit and the Illinois and Ohio countries, is up Miami river, to Miami village, thence by land 9 miles, when the rivers are high, and from 18 to 30 when they are low, through a level country to the Wabash, and through the various branches of the Wabash to the places of deftination. The land on this river is remarkably fertile. A filver mine has been discovered about 28 miles above Ouiatanon, on the northern fide of the Wabash. Salt fprings, lime, free-ftone, blue, yellow, and white clay are found in plenty on this river. The copper mine on this river, is perhaps the richeft vein of native copper in the bowels of the whole earth. See Vin. cents and Ouiatanon.

WABASH, Little, runs a courfe S. S. E. and falls into the Wabafh 10 miles from the Ohio.

WACHOVIA, or Dobb's Parift, a tract of land in N. Carolina, fitnated between the E. fide of Yadkin river, and the head waters of Haw and Deep rivers, confifting of about 100,000 acres, partly in Stokes and Surry counties. The United Brethren, or Moravians, purchafed this tract of Lord Granville, in 1751, and called it Wachovia, after the name of an effate of Count Zinzendorf, in Germany. In 1755, it was made a feparate parifh, and named Dobb's, by the legiflature. The fettlement of Bethabara, was begun in 1753, by a number of the Brethren from Pennfylvania. Salem, which is the principal fettlement, commenced in 1766, and is inhabited by a number of ingenious tradefmen. This thriving parish lies 57

about 10 miles S. of Pilot Mountain, and contains 6 churches.

WACHQUATNACH, an ancient Moravian settlement in Connecticut, on Stratford river; 23 miles from its mouth.

WACHUSET Mountain, in the town of Princetown, Maffachufetts, may be feen in a clear horizon, at the diffance of 67 miles, being 2,989 feet above the level of the fea.

WADESBOROUGH, the chief town of Anion co. in Fayetteville diffrict, N. Carolina. It contains a court houfe, gaol, and about 30 houfes, and being feated on a lofty hill, is both pleafant and healthy. It is 76 miles weft by fouth of Fayetteville, and 50 foutheaft by S. of Salifbury.

WADMELAW, an ifland in Charlefton harbour, S. Carolina.

WADSWORTH, a town of New-York, Ontario co. fituated on the east bank of Geneffee river; 4 miles welt of Conefus Lake, and 13 fouth-welt by fouth of Hartford.

WADHAM Iflands; near the N. E. coaft of Newfoundland Ifland. N. lat. 49. 57. weft long. 53. 37.

WAGER'S Strait, or River, in New North Wales, in N. America, lies in lat. 65. 23. N. and is about 2 or 3 miles wide. At 5 or 6 miles within its entrance, it is 6 or 8 leagues wide, having feveral iflands and rocks in the middle. It has foundings from 16 to 30 and 44 fathoms; and the land on both fides is as high (according to Captain Middleton's account) as any in England. Savage Sound, a fmall cove or harbour, fit for thips to anchor in, lies on the northern fhore, 13 or 14 leagues up the ftrait, in long. 87. 18. W. All the country from Wager's Strait to Seal river, is in fome maps called New Denmark. Capt. Monk was fent thither, in 1610, by the king of Denmark, and wintered at a place called Monk's Winter Harbour, in lat. 63. 20. N. which must be a little north of Rankin's When Capt. Ellis was in this Inlet. latitude, the tide ran at the rate of from 8 to 10 leagues an hour. He compares it to the fluice of a mill.

WAITSFIELD, the fouth-easternmost township of Chittenden co. Vermont, containing 61 inhabitants.

Vermont, and empties into Connecticut. river, at Bradford.

WAJOMICK.

.

WAJOMICK, an Indian town on Sufquehannah river, about 400 miles from the fea. In the fpring of 1756, the Indians flot 2 feals here, and they could not fufficiently express their aftonishment at the fight of these animals unknown to them.

WAKE, an inland co. of Hillsborough district, North-Carolina; bounded N. W. by Orange, and E. and S. E. by Johnson. It contains 10,192 inhabitants, including 2,463 flaves. Chief town, Raleigh.

WAREFIELD, formerly Eafl-town and Watertown, a township of Strafford co. New-Hampshire, east of Wolfborough, incorporated in 1774. It contains 640 inhabitants. In the N.E., part is a pond which is the source of Piscataque river.

WAKKAMAW, a beautiful lake, 26 miles in circuit, fituated in Bladen co. North Carolina. The lands on its eaftern fhores are fertile, and the fituation delightful, gradually afcending from the fhores; bounded on the north-welt coaft by vaft rich fwamps, fit for rice. This lake is the fource of a fine river, of the fame name, and runs a foutherly courfe, for 70 or 80 miles, and empties into Winyaw Bay, at Georgetown, in South-Carolina.

WALDEN, a township of Vermont, Caledonia co. having Danville on the fouth-east. It contains only 11 inhabitants.

WALDOBOROUGH, a poft-town and port of entry of the Diffrict of Maine, in Lincoln co. 12 miles S. by W. of Warren, 10 E. by S. of Newcaftle, 20 eaft of Wifcaffet, and 545 north-eaft of Philadelphia. This is the port of entry for the diffrict, lying between the towns of Camden and Northport; and all the fhores and waters from the middle of Damarifeotta river to the fouth-weftern fide of the town of Northport. The townfhip of Waldoborough was incorporated in 1773, and contains 1210 inhabitants.

WALDO Patent, a tract of land forming the fouth-east part of Hancock co. in the Diffrict of Maine, and on the weft fide of Penobscot river and bay.

WALES, New South, a country of vaft extent, but little known, lying round the fouthern part of Hudion's Bay.

WALES, New North, an extensive territory of North-America; having

Prince William's Land on the north, part of Baffin's Bay on the eaft, and feparated from New South Wales, on the fouth by Seal river.

WALES, a plantation in Lincoln eo. District of Maine, 55 miles north-east of Portland, and 180 from Boston. It contains 439 inhabitants.

WALHALDING, the Indian name of an eaftern branch of Muskingum river, at the mouth of which stood Goschachguenk, a Delaware town, and settlement of Christian Indians.

WALLINGFORD, a township of Vermont, Rutland co. east of Tinmouth. It contains 536 inhabitants.

WALLINGFORD, a pleafant post-town of Connecticut, New-Haven co. 13 miles S. W. of Middleton, 13 N. E. of New-Haven, and 195 north-east of Philadel. phia. This township, called by the Indians Coginchauge, was fettled in 1671 ; is divided into two parishes, and contains about 2000 inhabitants. It is 12 miles long, and 7 broad.

WALLKILL, a township of New-York, Ulster co. on the creek of its name, about 15 miles N. by E. of Goshen, 11 west of Newburgh, and 58 N. W. of New-York city. It contains 2,571 inhabitants, of whom 340 are qualified electors, and 103 slaves.

WALNUT Hills, in the weftern territory of Georgia, are fituated on a tract of land formed by Miffifippi river and the Loofa Chitto, and on the north fide of the latter.

WALLOOMSCHACK, a fmall branch of Hoofack river, Vermont.

WALLPACK, a township in Suffex co. New-Jersey, on Delaware river, about 11 miles west of Newtown, and 50 north-west of Brunswick. It contains 496 inhabitants, including 30 flaves.

WALPOLE, a post-town of New-Hampshire, Chefhire co. on the eastern fide of Connecticut river, 11 miles fouth of Charlestown, 14 north-west by north of Keen, 108 west of Portsmouth, and 330 from Philadelphia. The township contains 1245 inhabitants.

WALFOLE, a township of Massachufetts, Norfolk co. on the great road to Providence, and 20 miles south-west of Boston. It was incorporated in 1724, and contains 1005 inhabitants.

WALSINCHAM, Cape, is on the east fide of Cumberland's Ifland, in Hudion's Straits. N. lat. 62. 39. W. long.

77.

77.53. at 12 o WAI fetts, M by nort rated in

tants. WAI

in Henn north fic weft of Wat

> of the WAI

Provide north-w this riv der-nui mile of mill, t with fo

a faw-1 WA Carolin trict, a

few mi Wa Pacific tent fro is abo

Weft fr Ifland WA W. co

miles tains Aaves.

Weft Weft

branch joins i was f

> rador 5. N. 30. V W

W

cetter

Werm weft Benni

> sants. W

77. 53. High water, at full and change at 12 o'clock.

th.

and

on

eo.

t of

on-

: of

ver,

ch-

lent

ler-

ith.

own

iles

ew.

del.

In-

71:

ton-

112

ew.

Go-

IN.

ains

are

erri-

ract

and

fide

inch

CO.

bout

50

tains

lew-

ftern

outh

orth

and

ifhip

chu-

d to

ft of

724,

: caft

Iud-

ong.

77.

es.

its

WALTHAM, a township of Massachufetts, Middlesex co. 11 miles north-west by north of Boston. It was incorporated in 1737, and contains 882 inhabitants.

WALTHAM, or Wefbam, a village in Henrico co. Virginia, fituated on the north fide of James' river, 4 miles northweft of Richmond.

WAMPANOS, an Indian tribe, allies of the Hurons.

WANASPATUCKET River, rifes in Gloucefter, Rhode-Ifland, and falls into Providence river a mile and an half north-wett of Weyboffet bridge. Upon this river formerly ftood the only powder mill in this State, and within one mile of its mouth there are a flittingmill, two paper-mills, two grift-mills with four run of ftones, an oil-mill, and a faw-mill.

WANDO, a fhort, broad river of S. Carolina, which rifes in Charlefton diftrict, and empties into Cooper's river, a few miles below Charlefton.

WANDOAETTE, an ifland in the S. Pacific Ocean, about two miles in extent from fouth-east to north west. It is about to miles at north west by west from the north end of Wateehoo Island.

WANTAGE, a township near the N. W. corner of New-Jerley, Suffex co. 15 miles northerly of Newtown. It contains 1700 inhabitants, including 26 flaves.

WANTASTIC, the original name of Weft river, Vermont.

WAPPACAMO *River*, a large fouth branch of Patowmack river, which it joins in lat. 39. 39. N. where the latter was formerly known by the name of Cohongoronto.

WAPUWAGAN Islands, on the Labrador coast, lie between lat. 50. and 50. 5. N. and between long. 59. 55. and 60. 30. W.

WARD, a township of Massachuletts, Worcester co. 5 miles south of Worcetter, and 55 south-west of Boston, and contains 473 inhabitants.

WARDSBORQUGH, a township of Vermont, Windham co. 12 or 15 miles west of Putney, and 27 north-east of Bennington, and contains 753 inhabitants.

WARDSBRIDGE, a post-town of New-

York, Ulfter co. on the Wallkill, 10 miles north of Gofhen, 36 fouth by weft of Kingfton, and 156 north eaft by north of Philadelphia. It contains about 40 compact houles and an academy.

WARE, a fmall river of Maffachufetts which originates in a pond in Gerry, in Worcefter co. and in Petersham it receives Swift river, and receiving Quaboag river, which comes from Brookfield, it thence affumes the name of Chicabee, and falls into Connecticut river at Springfield. Its course is fouth and fouth-weft.

WARE, a township of Massachuletts, in Hampthire co. incorporated in 1761, and contains 773 inhabitants. It is 15 miles N. E. of Springfield, and 70 miles west-north-west of Boston.

WAREHAM, a township of Massachusetts, fituated in Plymouth co. at the head of Buzzard's Bay, and on the west fide, 60 miles S. by E. of Boston. It was incorporated in 1739, and contains 854 inhabitants. N. lat. 41. 45. W. long. 70. 40.

WARMINSTER, a fmall poft-town of Virginia, fituated on the north fide of James' river, in Amherft co. about 90 miles above Richmond. It contains about 40 houfes, and a tobacco warehoufe. It is 332 miles from Philadelphia, 24 miles from Charlottefville, and 9 from Newmarket. There is alfo a townfhip of this name in Buck's county, Pennfylvania.

WARM Spring, a ridge of mountains bears this name, a part of the Alleghany Mountains, fituated N. W. of the Calf Pasture, and tamous for warm fprings. The most efficacious of these are two fprings in Augusta, near the fources of James' river, where it is called Jackfon's river. They life near the foot of the tidge of mountains, generally called the Warm Spring Mountains, but in the maps Jackion's Mountains. The one is diffinguished by the name of the Warm Spring, and the other of the The Warm Spring iffues Hot Spring. with a very bold ftream, fufficient to work a grift-mill, and to keep the waters of its baton, which is 30 feet in diameter, at the vital warmth, viz. 96° of Farenheit's thermometer. The matter with which there waters is allied is very volatile; its fmell indicates it to be fulphureous, as also does the circumftance of turning filver black. They relieve 003 rheumatifms,

rheumatifins. Other complaints alfo of very different natures have been removed or leffened by them. It rains here 4 or 5 days in every week. The Hot Spring is about fix miles from the Warm, is much fmaller, and has been fo hot as to have boiled an egg. Some believe its degree of heat to be leffened. It raifes the mercury in Farenheit's thermometer to 112 degrees, which is fever heat. It fometimes relieves where the Warm Spring fails. A fountain of common water, iffuing within a few inches of its margin, gives it a fingular appearance. Comparing the temperature of these with that of the hot fprings of Kamtichatka, of which Krachininnikow, gives an account, the difference is very great, the latter raising the mercury to 200 degrees, which is within 12 degrees of boiling water. " Thefe fprings are very much reforted to, in fpite of a total want of accommodation for the fick. Their waters are ftrongeft in the hoteft months, which occasions their being visited in July and August principally. The Sweet Springs, in the county of Botetourt, at the eaftern foot of the Alleghany, are about 42 miles from the Warm Springs.

WARNER, a township of New-Hampshire, Hillsborough co. It was incorporated in 1774, and contains 863 inhabitants.

WARREN, a new county of the Upper Diffrict of Georgia.

WARREN, a county of Halifax diftrict, N. Carolina. It contains 9397 inhabitants, including 4720 flaves.

WARRENTON, a poft town, and the eapital of the above mentioned county, fituated 16 miles E. by N. of Hillfoof rough, 35 weft of Halifax, 54 north of Raleigh, 83 fouth of Peterfourg in Vinginia, and 390 from Philadelphia. The town contains about thirty houfes, and flands in a lofty, dry, and healthy fituation. Europeans, of various nations, refide in and about the town. Here is a reflectable academy, having generally from 60 to 70 fludents.

WARREN, a township of Vermont, Addison co. about 30 miles N. E. by E. of Crown Point.

WARREN, a post-town of the Diftrift of Maine, Lincoln co. adjoining Camden and Thomaston; 33 miles fouth by west of Belfast, 203 N. E. by N. of Boston, and 557 from Philadel-

phia. This township is separated from that of Thomaston, by St. George's river; was incorporated in 1776, and contains 642 inhabitants.

WARREN, a township of Grafton co. New-Hampshire, north-east of Orford, adjoining, incorporated in 1763, and contains 206 inhabitants.

WARREN, a post-town of Rhode-Island, in Briftol co. pleafantly fituated on Warren river and the north-eaft part of Narraganfet Bay, 4 miles north of Briftol, 10 S. S. E. of Providence, and 303 from Philadelphia. This is a flourishing town; carries on a brifk, coafting and Weft-India trade, and is The remarkable for thip building whole township contains 1122 inhabitants, of whom 22 are flaves. Rhode-Island College was first instituted in this town, and afterwards removed to Providence.

WARREN, a new township of Herkemer county, New-York. It was taken from German Flats, and incorporated in 1796.

WARREN, a part of the township of Chenengo, in the State of New-York, on Sulquehannah river, bears this name in De Witt's may.

WARREN, a township of Connecticut, in Litchfield co. between the townships of Kent and Litchfield.

WARREN, a post-town of Virginia, 10 miles from Warminster, 21 from Charlottesville, and 326 from Philadelphia.

WARREN's Point, on the coaft of Nova Scotia, is on the eaft fide of Chebucto Harbour, about two miles eaft of the town of Halifax. It is at the entrance of a creek, which receives Saw-Mill river and other freeams.

WARRINGTON, the name of two townships of Pennsylvania; the one in York co. the other in Buck's co.

WARSAW, or *Waffawo*, an island and found on the coaft of Georgia, between the mouth of Savannah river and that of Qgeechee. 'The island forms, the north fide of Offabaw Sound; being in a north-east direction from Offabaw Island. Warfaw Sound is formed by the northern end of the island of its name, and the fouthern end of Tybee Island.

WARWICK, a county of Virginia, bounded north by York county, and fouth by James' river, which feparates it fron countie State, It con 990 ar WA fetts, i 1763, It is New-I ticut I of Bol W co. R of N: fide ; : The tants, manu town Arkv in A duced tatior of the W Oran Corn New tants flave ١ð hips coun In th ment v land Chel erly tow Phil v field the abo mor Vef this deft on trić lan ed cod eaf mi un

it from Ifle of Wight and Nanfemond counties. It is the oldeft county of the State, having been eftablished in 1628. It contains 1690 inhabitants, of whom 990 are flaves.

iv.

11-

co.

ref.

nd

le-

ed

aft

th

:e,

i a

ft

is

he

11-

e.

in

to

e-

in

of

ŋ¢

t,

78

а,

m

K

of

b.-

of

1-

١.,

0

ń

d

đ

S

50

y

ć

WARWICK, a township of Massachufetts, in Hampshire co. incorporated in 1763, and contains 1246 inhabitants. It is bounded north by the State of New-Hampshire, not far east of Connecticut river, and is 90 miles north-welt of Boston.

WARWICK, the chief town of Kent co. Rhode Ifland, fituated at the head of Narraganfet Bay, and on the weft fide; about 8 miles touth of Providence. The townifnip contains 2493 inhabitants, including 35 flaves. A cotton manufactory has been eftablifhed in this town upon an extensive feale. One of Arkwright's machines was erected here in August, 1795; and the yarn produced answers the most fanguine expectation. This town was the birth-place of the celebrated Gen. Greene.

WARWICK, a township of N. York, Orange co. bounded easterly by New-Cornwall, and fontherly by the State of New-Jersey. It contains 3603 inhabitants, of whom 38g are electors, and 95 flaves.

WARWICE, the name of two townthips of Pennfylvania; the one in Buck's county, the other in that of Lancaster. In the latter is the fine Moravian fettlement called Litiz; which fee.

WARWICK, a post-town of Maryland Cecil co. on the eastern shore of Chefapeak Bay; about 14 miles foutherly of Elkton, 8 N. E. of Georgetown Crofs Roads, and 57 fouth-west of Philadelphia.

WARWICK, a fmall town of Chefterfield co. Virginia; agreeably fituated on the fouth weft fide of James' river, about 7 miles fouth-fouth-eaft of Richmond, and 17 north of Petersburg. Veffels of 250 tons burdens can come to this town. In 1781, Benedict Arnold deftroyed many veffels in the river and on the flocks at this place.

-WASHINGTON, a county of the Diftrict of Maine, and the molt cafferly land in the United States. It is bounded fouth by the ocean, weft by Hancock co. north by Lower Canada, and eaft by New-Brunfwick. It is about 200 miles in length, but its breadth is as yet undetermined. It was crected into a

county in 1759; but has few towns yet incorporated. The coaft abounds with excellent harbours. Although the winters are long and fevere, yet the foil and productions are but little inferior to the other counties. The number of inhabitants in this country, according to the cenfus of 1790, was 2753; but the increafe fince mult have been very confiderable. Chief town, Machias.

WASHINGTON, a maritime county of the State of Rhode-Ifland; bounded N. by Kent, S. by the N. Atlantic Ocean; W. by the State of Connecticut, and E. by Narraganfet Bay. It is divided into 7 townships, and contains 18,075 inhabitants, including 339 staves. Chief town, South-Kingstown.

WASHINGTON, a county of New-York; bounded N. by Clinton county; S. by Renffelaer, S. W. by Saratoga, W. by Herkemer, and E. by the State of Vermont. Until 1784 it was called Charlotte. It contained, in 1790, 14,042 inhabitants, including 742 flaves. In 1796 there were 3370 of the inhabitants qualified electors. It is fubdivided into 12 townfhips, of which Salem is the chief.

WASHINGTON, a county of Pennfylvania; fituated on the S. W. corner of the State; bounded N. by Alleghany county S. by Monongalia county in Virginia, E. by Monongahela river, which divides it from Fayette county, and W. by Ohio co. in Virginia, agreeably diverified with hills, which admit of eafy cultivation quite to their fummits. It is divided into at townfhips, and contains 23,866 inhabitants, including 263 flaves. Mines of copper and iron ore have been found in this county.

WASHINGTON, the capital of the above county, and a post-town, is fituar-ed on a branch of Charter's Creek, which falls into Ohio river, a few miles below Pittfburg. It contains a brick court-houfe, a ftone gaol, a large brick building for the public offices, an 'academy of ftone, and nearly 100 dwelling houfes. It is 22 miles fouth-fouth-weft of Pittfburg; 22 north-weft of Brownfville, 60 miles north by weft of Morgantown, in Virginia, and 325 weft by north of Philadelphia. N. lat. 40. 13. W. long. 80. 6. 40. It is remarkable for its manufactures, for fo young a town. There are 3 other townships of the 004

the fame name in Pennfylvania, viz. in Fayette, Franklin, and Weftmoreland counties. It is dividtivan, Greene, and Hawkius. It con-

WASHINGTON, a county of Mary. land, on the western shore of Chefapeak Bay; bounded north by the State of Pennfylvania, east by Frederick co. from which it is divided by South Mountain, fouth weft by Patowmack river, which divides it from the State of Virginia, and weft by Sideling-Hill-Creek, which feparates it from Alleghany co. This is called the garden of Maryland, lying principally between the North and South Mountains, and includes the rich, fertile, and well culti-vated valley of Conegocheague. Its ftreams furnish excellent mill-feats, and the lands are thought to be the most fertile in the State. Lime-flone and ironore are found here. Furnaces and forges have been crected, and confiderable quantities of pig and bar iron are manufactured. Chief town, Elizabeth Town.

WASHINGTON, a co. of Virginia; bounded E. and N. E. by Wythe, N. W. by Ruffell, S. by the State of North Carolina, and W. by Lee. It is watered by the fireams which form Holfton, Clinch and Powell's rivers. There is a natural bridge in this county fimilar to that in Rockbridge county. It is on Stock Creek, a branch of Pelefon river. It contains 5625 inhabitants, including 450 flaves. Chief town, Abingdon.

WASHINGTON, a diftrict of the Upper Country of South-Carolina, perhaps the moft hilly and mountainous in the State. It lies W. of Ninety-Six diftrict, of which it was formerly a part, and is bounded N. by the State of North-Carolina. It contains the counties of Pendleton and Greenville; has 14,6 rg inhabitants, and fends to the State legiflature 5 reprefentatives and 2 fenators. Chief town, Pickenfville. A number of old defarted Indian towns of the Cherokee nation, are frequently met with on the Keowee river, and its tributary ftreams which water this country.

WASHINGTON, a county of Kentncky, bounded N. E. by Mercer, N. W. by Nelfon, S. E. by Lincoln, and W. by Hardin.

WASHINGTON, a difirict of the State of Tennefice, fituated on the waters of the rivers Holfton and Clinch, and is divided from Mero diffrict on the W.

by an uninhabited country. It is divided into the counties of Washington, Sullivan, Greene, and Hawkins. It contained, according to the State census of 1795, 29,531 inhabitants, including 4003 flaves.

4693 flaves. WASHINGTON, a county of Tenneffee, in the abave diftrict, contained, in 1795, 10,105 inhabitants, inclusive of 978 flaves. Washington college is established in this county by the legislature.

WASHINGTON, a county of the N. W. Territory, crected in 1788 within the following boundaries, the beginning on the bank of the Ohio where the weftern line of Pennfylvania croffes it, and running with that line to Lake Erie; thence along the fouthern fhore of that lake to the mouth of Cayahoga river, and up that river to the portage between it and the Tuscarawa branch of Mnskingum; thence down that branch to the forks of the croffing-place above Fort Lawrence; thence with a line to be drawn wefterly to the portage on that branch of the Big Miami, on which the fort flood which was taken from the French in 1752, until it meets the road from the Lower Shawanele town to Sandufky; thence S. to the Sciota river to the mouth, and thence up the Ohio to the place of beginning.

WASHINGTON, a county of the Upper Diffrict of Georgia, which contains 4552 inhabitants, including 694 flaves. Fort Fidus is fituated in the wefternmoft part of the county, on the E. branch of Alatamaha river. The county is bounded on the N. E. by Ogeechee river. Numbers have lately moved here from Wilkes co. in order to cultivate cotton in preference to tobacco. This produce, though in its infancy, amount. ed to 208,000 lbs. weight, in 1792. Chief town, Golphinton.

WASHINGTON, a township of Vermont, Orange county, 12 miles W. of Bradford, and contains 72 inhabitants.

WASHINGTON, a township of Maffachusetts, in Berkshire co. 7 miles S. E. of Pittsfield, 8 E. of Lenox, and 145 W. of Boston. It was incorporated in 1777, and contains 588 inhabitants.

WASHINGTON, or Mount Vernon, a plantation of Lincoln co. Diffrict of Maine, N. W. of Hallowell, and nine miles from fterling. It confifts of 16,055

16,055 acres of land and water, of which the latter occupies 1641 acres. It contains 618 inhabitants, and was incorporated by the name of *Belgrade* in 1796; which fee.

əf

g

ſ-

'n

of

is

...

١.

n

g

d

5

t

,

n

.

e

t

e t

e

WASHINGTON, a township of New-York, in Dutchess co. bounded southerly by the town of Beckman, and westerly by Poughkeepsie and Clinton. It contains 5189 inhabitants, of whom 286 are electors, and 78 flaves.

WASHINGTON, a township of New-Hampshire, in Cheshire co. first called Camden. It was incorporated in 1776, and contains 545 inhabitants; it is 12 or 14 miles E. of Charlestown.

WASHINGTON, a township of Connecticut, in Litchfield co. about 7 miles S. W. of Litchfield.

WASHINGTON, a port of entry and post-town of N. Carolina, fituated in Beaufort county, on the N. fide of Tar river, in lat. 35. 30. N. 90 miles from Ocrecok Inlet, 40 from the mouth of Tar river, 61 S. S. W. of Edenton, 38 N. by E. of Newbern, 131 N. E. by N. of Wilmington, and 460 from Philadelphia. It contains a court-houfe, gaol, and about eighty houses. From this town is exported tobacco of the Peterfburg quality, pork, beet, Indian corn, peas, beans, pitch, tar, turpentine, rofin, &c. alfo pine boards, fbingles, and oak flaves. About 130 veffels enter annually at the cuftom-house in this town. The exports for a year, ending the 30th of September, 1794, amounted to 33,684 dollars.

WASHINGTON, a post-town of Kentucky, and the capital of Maion county, about three niles S. by W. of the landing at Limestone, on the S. fide of Ohio river. It contains about roo houses, a Prefbyterian church, a handiome court-house and gaol; and is fast increasing in importance. It is 62 miles N. E. of Lexington, 75 N. E. by E. of Frankfort, and 709 S. W. by W. of Philadelphia. N. lat. 38. 40. W. long, 84. 30.

WASHINGTON Court-Houfe, in S. Carolina, is 10 miles from Greenville, and 16 from Pendleton,

WASHINGTON, a polt town of Georgia, and the capital of Wilkes co. 50 miles N. W. by W. of Augusta, 58 N. by W. of Louifville, 28 from Greensborough, and 813 from Philadelphia. It flauds on the western fide of

Kettle Creek, a north branch of Little river, which empties into Savannah river from the eaftward, about 36 miles E. of the town. It is regularly laid out, and contained, in 1788, 34 houses, a court-house, gaol, and academy. The funds of the academy amount to about Sool. fterl. and the number of ftudents to between 60 and 70. On the E. fide of the town, a mile and a half diftant, is a medicinal fpring, which rifes from a hollow tree 4 or 5 feet in length. The infide of the tree is covered with a coat of matter an inch thick, and the leaves around the fpring are incruited with a fubstance as white as fnow. It is faid the be a fovereign remedy for the fcurvy, fcrophulous diforders, confumptions, gout, and every other diforder arising from humours in the blood. This fpring being fituated in a fine healthy part of the State, will, no doubt, be a pleafant and falutary place of refort for invalids from the maritime and unhealthy parts of Georgia, and the neighbouring States. N. lat. 33. 12.

WASHINGTON City, in the territory of Columbia, was ceded by the State of Virginia and Maryland to the United States, and by them effablished as the feat of their government, after the year 1800. This city, which is now building, flands at the junction of the river Patowmack, and the Eaftern Branch, latitude 38.53. N. extending nearly 4 miles up each, and including a tract of territory, exceeded, in point of convenience, falubrity and beauty, by none in America. For although the land in general appears level, yet by gentle and gradual fwellings, a variety of elegant profpects are produced, and a fufficient defcent formed for conveying off the water occationed by rain. Within the limits of the city are a great number of excellent fprings; and by digging wells, water of the best quality may readily be had. Befides, the never failing freams that now run through that territory, may allo be collected for the use of the city. The waters of Reedy Branch, and of Tiber Creek, may be conveyed to the Prefident's house. The source of Tiber Creek is elevated about 236 feet above the level of the tide in faid creek. The perpendicular height of the ground on which the capitol stands, is 78 feetabove the level of the tide in Tiber Creek. The water of Tiber Creek may

WAS

may therefore be conveyed to the capitol, and after watering that part of the city, may be defined to other nfeful purpoles. The Eaftern Branch is one of the fafelt and molt commodious harbours in America, being fufficiently deep for the largest ships, for about 4 miles above its mouth, while the channel lies clofe along the bank adjoining the city, and affords a large and convenient harbour. The Patowmack, although only navigable for fmall craft, for a confiderable diffance from its banks next the city, (excepting about half a mile above the junction of the rivers) will neverthelefs afford a capacious fummer harbour; s an immente number of thips may ride in the great channel, opposite to, and below the city. The fituation of this metropolis is upon the great postroad, equi-diftant from the northern and fouthern extremities of the Union, and nearly to from the Atlantic and Pittflurg, upon the best navigation, and in the midft of a commercial territory, probably the richeft, and commanding the most extensive internal refource of any in America. It has therefore many advantages to recommend it, as an eligible place for the permanent feat of the general government; and as it is likely to be fpeedily built, and otherwife improved, by the public fpirited enterprife of the people of the United States, and even by foreigners, it may be expected to grow up with a degree of rapidity hitherto unparalleled in the annals of cities. The plan of this city appears to contain fome important improvements upon that of the best planned cities in the world, combining, in a remarkable degree, convenience, regularity, elegance of prospect, and a free circulation of air. The politions of the different public edifices, and for the feveral fquares and areas of different thapes as they are laid down, were first determined on the most advantageous ground, commanding the most extenfive profpects, and from their fituation, inceptible of fuch improvements as either ule or ornament may hereafter require. The capitol is fituated on a molt beautiful eminence, commanding a complete view of every part of the city, and of a confiderable part of the country around. The Prefident's honfe flands on a riling ground, polfeffing a delightful water profpect, to-

gether with a commanding view of the capitol, and the most material parts of the city. Lines, or avenues of direct communication, have been devifed to connect the most distant and important objects. Thefe transverse avenues, or diagonal ftreets, are laid out on the most advantageous ground for prospect and convenience, and are calculated not only to produce a variety of charming prospects, but greatly to facilitate the communication throughout the city. North and fouth lines, interfected by/ others running due E. and W. make the distribution of the city into fireets, fquares, &c. and those lines have been fo combined, as to meet at certain given points, with the divergent avenues, fo as to form, on the spaces first determined, the different fquares or areas. The grand avenues, and inch ftreets as lead immediately to public places, are from 130 to 160 feet wide, and may be conveniently divided into foot-ways, a walk planted with trees on each fide, and a paved way for carriages. The other freets are from 90 to 110 feet wide. In order to execute this plan, Mr. Ellicott drew a true meridional line by celeftial obfervation, which paffes through the area intended for the capitol. This line he croffed by another, running due E. and W. which paffes through the fame area. These lines were accurately measured and made the bafes on which the whole plan was executed. He ran all the lines by a transit inftroment, and determined the acute angles by actual measurement, leaving nothing to the uncertainty of the compais. Washington, or the Federal City, is feparated from Georgetown, in Montgomery co. Maryland, on the W. by Rock Creek, but that town is now within the territory of Columbia. It is 42 miles S.W. by S. of Baltimore, 876 from Paffamaquoddy, in the District of Maine, 500 from Boston, 248 from New-York, 144 from Philadelphia, 133 from Richmond, in Virginia, 232 from Halifax, in N. Carolina, 630 from Charlefton, S. Carolina, and 794 from Savannah, in Georgia.

WASHINGTON College, in Maryland. See Cheftertown.

WASHINGTON, Fort, in the Territory N.W. of the Ohio, is fituated on the N. bank of the river Ohio, weftward of Little Miami river, and 45 miles northweft

weft of Cincin WA thip o the fo miles was in 261 it w. Whit which all al ties of tains. W north The point St. Ja Point lat. 5 tends extre 2280 Mage the if follos Skeet Cum Port, Port Cook pofed as th and t him wefte lat. thefe Que difec them three fmal mak Laza v Gul Lab 59. V Lab renc Oua Litt fror V whi weft of Washington, in Kentucky. See Cincinnati.

WASHINGTON, Mount, a finall townthip of Maffachuletts, Berkshire co. in the fouth-west corner of the State, 150 miles fouth west by fouth of Boston. It was incorporated in 1779, and contains 261 inhabitants.

WASHINGTON, Mount, one of the White Mountains of New-Hampfhire, which makes fo majeftic an appearance all along the fhore of the eaftern counties of Maffachufetts. See White Mountains.

WASHINGTON'S Mands, on the north-west coast of North-America. The largest is of a triangular shape, the point ending on the fouthward at Cape St. James's, in N. lat. 51. 58. Sandy Point, at its north east extremity, is in lat. 54. 22. N. Its longitude weft extends from Hope Point, the north-weft extremity 226° 37' to Sandy Point, in 228º 45'. Port Ingraham, Perkins and Magee Sound lie on the weftern fide of the ifland; on the eastern fide are the following ports from north to fouth-Skeetkifs, or Skitkifs Harbour, Port Cummashawa, Kleiws Point, Smoke Port, Kanskeeno Point, Port Geyers, Port Ueah, and Port Sturgis. Capt. Cook, when he paffed this ifland, fupposed it to be a part of the continent, as the weather at the time was thick, and the wind boifterous, which obliged him to keep out at fea, till he made the western cape of the continent in about lat. 55. N. Capt. Dixon difeovered these islands in 1787, and named them Queen Charlotte's Iflands. Capt. Gray difcovered them in 1789, and called them Washington's Islands. There are three principal iflands, befides many fmall ones. It is conjectured that they make a part of the Archipelago of St. Lazarus.

WASKEMASHIN, an ifland in the Gulf of St. Lawrence, on the coaft of Labrador. N. lat. 50. 3. W. long. 59. 55.

WASSAW Island. See Warfaw.

WATAGUAKI Istes, on the coaft of Labrador, and in the Gulf of Sr. Lawrence, lies near the fhore, north eaft of Ouapitougan Iste, and south-west of Little Mecatina, about 10 or 12 leagues from each.

WATAUGA, a river of Tenneffee, which rifes in Burke co. North-Carolina,

and falls into Holftein river, 15 miles above Long-Ifland.

WATCH Point, lies to the northward of Fisher's Island, in Long-Island Sound, and west-fouth-west 7 leagues from Block Island.

WATEHOO, an ifland in the South Pacific Ocean; a beautiful fpot, about 6 miles long and 4 broad. N. lat. 20. 1. W. long. 158. 15.

WATERBOROUGH, a township of the District of Maine, York co. on Mousom, river, 15 miles N. W. of Wells, and 110 from Boston. 1 It was incorporated in 1787, and contains 905 inhabitants.

WATERBURY, a township of Vermont, in Chittenden co. feparated from Duxbury on the fouth-west by Onion, river. It contains 93 inhabitants.

WATERBURY, the north-westernmost township of New-Haven co. Connecticut, called by the Indians Matteluck, It was settled in 1671, and is divided into the parishes of Northbury, Salem, and South-Britain.

WATEREE, a branch of Santee river, South-Carolina.

WATERFORD, a plantation in Cumberland co. Diftrict of Maine, foutheaft of Orangetown, or Greenland.

WATERFORD, a new township in York co. District of Maine, incorporated February, 1797, formerly a part of Waterborough.

WATERFORD, a township of New-Jersey, in Gloucester county.

WATERFORD, a neat village of New-York, in the township of Half Moon; which fee.

WATERLAND, an ifland in the South Pacific Ocean, fo named by Le Maire. S. lat. 14. 46. weft long. 144. 10.

WATERQUECHIE, or Quecky, a finall river of Vermont, which empties into Connecticut river in Hartland.

WATERTOWN, a very pleafant town in Middlefex co. Maffachufetts, 7 miles weft by north-weft of Bofton. Charles river is navigable for boats to this town, 7 miles from its mouth in Bofton harbour. The townfhip contains roor inhabitants, and was incorporated in 1630. That celebrated apoftle of the Indians, the Rev. Mr. Eliot, relates that in the year 1670, a ftrange phenomenon appeared in a great pond at Watertown, where the fifh all died ; and as many as could, thruft themfelves on fhore, and there died. It was effimated that not lefs than so cart-loads lay dead at once round the pond. An eel was found alive in the fandy border of the pend, and upon being caft again into its natural element, it wriggled out again, as faft as it could, and died on the fhore. The cattle, accuftomed to the water, refufed to drink it for 3 days, after which they drank as ufual. When the fift began to come on fhore, before they died, many were taken both by Englift and Indians, and eaten without any injury. WATERTOWN, a townfhip in Litchfield co. Connecticut. It is about 26 miles N. N. W. of New-Haven.

WATER VLIET, an extensive townthip of New-York, Albany county, on the weft fide of Hudfon's river, and includes the village of Hamilton, and the islands in the river nearest the weft fide. It is bounded weft by the manor of Rensfielaerwyck, and contained, in 1790, 7,419 inhabitants, including 707 flaves. In 1796, there were 600 of the inhabitants qualified electors.

WATLAND Ifland, one of the Bahama Iflands in the Weft-Indies. The S. point is in lat. 24. N. and long. 74. weft.

WATSON, Fort, in S. Carolina, was fituated on the N. E. bank of Santee river, about half way between the mouth of the Congaree and Nelfon's Fort, on the bend of the river opposite the Euraw Springs. Its garrifon of 114 men being betieged by Gen. Greene, furrende ed in April, 1781. He then marched with his main force against Camden, higher up the river.

WAUKEAGUE, a village in the townfhip of Sullivan, in the District of Maine, 9 miles from Defert Island.

WAWASINK, a village in New-York, on Rondout Kill, a branch of Walikill, 7 miles weft of New Paltz, and 12 fouthweft of Elopus.

WAWIACHTANOS, and Twichtwees, two Indian tribes, refiding chiefly between Sciota and Wabash rivers.

WAYNE, a new county in the N.W. Territory, laid out in the fall of 1796, including the fettlements of Detroit and Mich.llimakkinak.

WAYNE, a county of Newbern diftrict, N. Caroling; bounded N. by Edgcombe, and S. by Glaigow. It contains 6,133 inhabitants, inclusive of 1,557 flaves.

WAYNE, a township of Pennsylvania, ftuated in Mifflin county. name

river,

and a

Talla

lages

Gene

whof

Wat

ville

fqua

New

Otle

of M

wate

co.

men

Pen

tain

gati

the

deft

bite

der

fett

by

It

wei

fyb

Ch

ftr

Pe

tle

be

we

thi

ha

Ul

H

ro

in

w

ca

in

cÌ

¢

fi

b

þ

U

v

v

W

W

WAYNE, Fort, in the N. W. Territory, is fituated at the head of the Miami of the Lake, near the Old Miami Villages, at the confluence of St. Jofeph's and St. Mary's rivers. It is a fquare fort, with baffions at each angle, with a ditch and parapet, and could contain 500 men, but has only 300, with a6 pieces of cannon. It is 150 miles north by weft of Cincinnati, and 200 weft by fouth of Fort Defiance. The Indians ceded to the United States a track of land 6 miles fquare, where this fort flands, at the late treaty of peace at Greenville.

WAYNESBOROUGH, a post-town of N. Carolina, 24 miles from Kingfton, 50 S. E. from Raleigh, and 498 from Philadelphia.

WAYNESBOROUGH, a post-town in Burke co. Georgia, 30 miles fouth of Augusta, 25 north-east of Louisville. No river of confequence passes near this town; yet being the place where both the superior and inferior courts are held, it is in a prosperous condition.

WEARE, a township of New-Hampfhire, fituated in Hillsborough co. 18 miles fouth westerly of Concord, 60 west of Portsmouth, and 70 north-west of Boston. It was incorporated in 1764, and contains 1,924 inhabitants.

WEATHERSFIELD, a township of Vermont, Windfor co. on the welt fide of Connecticut river, between Windfor on the north, and Springfield on the fouth. Afcutney Mountain lies partly in this township, and in that of Windfor. It is a flourishing town, and contains 1,097 inhabitants.

WEATHERSFIELD, a post-town of Connecticut, pleafantly fituated in Hartford co. on the west fide of Connecticut river, 4 miles S. of Hartford. 11 N. of Middleton, 36 N. by E. of New-Haven, and 218 N. E. of Philadelphia. This town was fettled in 1635 or 1636, by emigrants from Dorchelter in Maffachufetts, and has a fertile and luxuriant foil, It confifts of between 200 and 300 houses, and has a very elegant brick meeting house for Congregationalis. The inhabitants are generally wealthy farmers; and befides the common productions of the country, raile great quantities of onions, which are exported to different parts of the United States, and to the West-Indies.

WEATHERFORD's Place, Charles, an Indian house and plantation of that name.

name, on the eastern fide of Alabama river, above M'Gillivray's fister's place, and a good way below the junction of Tallapoofee and Coofa rivers.

ni

's

re

0

of

ít

x

0

:8

۶f

n

ъź

a

WEAUCTENEAU Towns, Indian villages on Wabash river, destroyed by Generals Scott and Wilkinson in 1791.

WEAUS, or Weeas, an Indian tribe, whole towns lie on the head waters of Wabash river. At the treaty of Green ville they ceded a tract of land, 6 miles fquare, to the United States.

WEAVER'S Lake, in the State of New-York, is 3 miles north-welt of lake Otlego. It is 2 miles long and $1\frac{1}{2}$ broad.

WEBHAMET *River*, in the Diffrict of Maine, is the principal entrance by water to the town of Wells, in York co. It has a barred harbour.

WECHQUETANK, a Moravian fettlement made by the United Brethren, in Pennfylvania, behind the Blue Mountains. In 1760, the Bethlehem congregation purchated 1,400 acres of land for the Chriftian Indians. In 1763, it was deftroyed by white favages, who inhabited near Lancatter; they likewife murdered many of the peaceable Indians fettled here. It was finally deftroyed by the Americans during the late war. It lies about 30 miles north-weft by weft of Bethlehem.

WEISENBERO, a township of Pennfylvania, in Northampton county.

WELCH Mountains, are fituated in Chefter co. Pennfylvania. Befides other ftreams, Brandywine Creek rifes here.

WELCH Track, a fmall territory of Pennfylvania, fo named becaufe first fettled by Welchmen. There are a number of fmall towns in it, as Haverfordweft, Merioneth, &c. It is pretty thickly inhabited by an industrious, hardy and thriving people.

hardy and thriving people. WELCOME, Sir Thomas Roes, or Ne Ultra, a bay or firait in that part of Hudfon's Bay which runs up to the N. round from Cape Southampton, opening between lat. 62. and 63. N. On the welt or north shore is a fair head land, called the Hope by Captain Middleton, in lat. 66. 30. N.

WELLFLEET, a township of Massachuletts, in Barnstable co. situated on the peninfula called Cape Cod; S. E. from Boston, distant by land 105 miles, by water 60, and from Plymouth lightbouse 8 leagues. The harbour is large, indented within with creeks, where vef-

fels of 70 or 80 tons may lie fafe in what is called the Deep Hole. The land is barren, and its timber is fmall pitchpine and oak. Before it was incorporated in 1763, it was called the North Precinel of Eastham, and was originally included in the Indian Skeekeet and Pamet. In 1790, it contained 1117 inhabitants. Since the memory of people now living, there have been in this fmall town 30 pair of twins, belides two births that produced three each. The method of killing gulls in the gullhouft, is no doubt an Indian invention, and also that of killing birds and fowl upon the beach in dark nights. The gull-houfe is built with crotches fixed in the ground on the beach, and covered with poles, the fides being covered with stakes and fea weed, and the poles on the top covered with lean whale. The man being placed within, is not difcovered by the fowls, and while they are contending for and eating the fifh, he draws them in one by one between the poles, until he has collected 40 or 50. This number has often been taken in a morning. The method of killing fmall birds and fowl that perch on the beach, is by making a light ; the prefent mode is with hogs lard in a frying pan; but the Indians are supposed to have used a pine torch. Birds, in a dark night, will flock to the light, and may be killed with a walking-cane. It must be curious to a countryman who lives at a diftance from. the fea, to be acquainted with the method of killing black fish. Their fize is from 4 to 5 tons weight, when full grown. When they come within the harbours, boats furround them, and they are as eafily driven on fhore, as cattle or theep are driven on the land. The tide leaves them, and they are eafily killed. They are a fifh of the whale kind, and will average a barrel of oil each ; 400 have been feen at one time on the fhore. Of late years thefe fifh rarely come into the harbours,

WELLS, a finall, but rapid river of Vermont, which, after a fhort S. E. courfe, empties into Connecticut river, below the Narrows, and in the N. E. corner of Newbury. Its mouth is 40 yards wide.

WELLS, a township of Vermont, Rutland co. between Pawlet and Poultney, and contains 622 inhabitants. Lake St. Austin lies in this township, and and is three miles long, and one broad.

WELLS, a post town of the District of Maine, in York co. fituated on the bay of its name, about half way between Biddeford and York, and 88 miles N. by E. of Bolton, and 441 from Philadelphia. This township is about 10 miles long, and 7 broad ; was incorporated in 1653, and contains 3,070 inhabitants. It is bounded S. E. by that part of the fea called Wells Bay, and N. E. by Kennebunk river, which feparates it from Arundel. The fmall river Negunket, perhaps formerly Oguntiquit, has no navigation, nor mills of any value, but noticed, about 1 50 years ago, as the boundary between York and Wells. "The tide through Pifcataqua bay urges itfelf into the marfhes at Wells, a few miles E. of Negunket, and forms a harbour for fmall veffels. Further E. in this township, the small river Moulum is found coming from ponds of that name about 20 miles from the fea. Several mills are upon the river, and the inhabitants are opening a harbour by means of a canal. Webhamet river is the principal entrance to this town by water.

WELLS Bay, in the township above mentioned, lies between Capes Porpoise and Neddock. The course from the latter to Wells Bar, is N. by E. 4 leagues.

WELL'S Falls, in Delawate river, lie 13 miles N. W. of Trenton, in New-Jerfey.

WENDELL, a township of Massachufetts, in Hampshire co. So miles N. W. of Boston. It was incorporated in 1781, and contains 519 inhabitants.

WENDELL, a township of New-Hampshire, Cheshire co. about 15 miles N. E. of Charlestown, containing 267 inhabitants. It was called Saville, before its incorporation in 1781.

WENHAM, a township of Massachufetts, Effex co. between Ipswich and Beverley; 26 miles N. E. by N. of Boston. It was incorporated in 1643, and contains 502 inhabitants. Here is a large pond, well stored with fish, from which, and its vicinity to Salem, it was, with whimfical piety, called *Enon*, by the first fettlers.

WENMAN, one of the Gallipago Islands, on the coast of Peru, fituated W. of Cape Francisco.

WENTWORTH, a township of New-Hampshire, Grafton co. containing 241 WES

inhabitants. It was incorporated in 1760, and is S. E. of Oxford, adjoining.

WESEL, a village of New-Jerfey, Effex co. on Palaic river, 2 miles northwestward of Acquakenunk, and 5 westward of Hakkeniack.

WEST, or Wantastiquek, a river of Vermont, has its main fource in Bromley, about 3 miles S. E. from the head of Otter-Creek. After receiving 7 or 8 fmaller ftreams, and running about 37 miles, it falls into Connecticut river at Brattleborough. It is the largest of the ftreams on the east fide of the Green Mountains; and at its mouth is about 15 rods wide, and 10 or 12 feet deep. A number of figures, or infcriptions, are yet to be feen upon the rocks at the mouth of this river, feeming to allude to the affairs of war among the Indians ; but their rudenefs and awkwardnefs denote that the formers of them were at a great remove from the knowledge of any alphabet.

WEST RIVER Mountain? in New-Hampfhire, in the township of Chefterfield, lies opposite to the mouth of Weft river; and from this part of Connecticut river to Piscataqua Harbour on the east is 90 miles, the broadest part of the State. Here are visible appearances of volcanic eruptions. About the year 1730, the garrison of Fort Dummer, 4 mi es distant, was alarmed with frequent explosions of fire and finoke, emitted by the mountain. Similar appearances have been observed fince.

WEST Bay, a large bay of Lake Superior, at its wefternmost extremity, having the 12 ifles at its mouth. It receives St. Louis river from the weft.

WEST BETHLEHEM, a township of Washington co. Pennfylvania.

WESTBOROUGH, a township of Maffachufetts, Worcefter co. 34 miles weftlouth-weft of Bofton, and 13 eaft of Worcefter, was incorporated in 1717. Among other fingular occurrences in the Indian wars, the ftrange fortune of Silas and Timothy Rice is worthy of notice. They were fons of Mr. Edmond Rice, one of the first fettlers in this town, and carried off by the Indians on August 8, 1704, the one 9 the other 7 years of age. They loft their mother ongue, had Indian wives, and children by them, and lived at Cagnawaga. Silas was named Tookanowras, and Timothy,

1238.7

mothy, Oughtforongoughton. Timothy | fetts ; fituated in the fouth-weft corner recommended himfelt fo much to the Indians by his penetration, courage, ftrength, and warlike fpirit, that he arrived to be the third of the 6 chiefs of the Cagnaguagas. In 1740 he came down to fee his friends. He viewed the house where Mr. Rice dwelt, and the place from whence he with the other children were captivated, of both which he retained a clear remembrance ; as he did likewife of feveral elderly perfons who were then living, though he had forgot the English language. He returned to Canada, and, it is faid; he was the chief who made the fpeech to Gen. Gage in behalf of the Cagnawagas, after the reduction of Montreal. These men were alive in 1790.

WES

WEST Camp, a thriving village of New-York, containing about 60 houfes, in Columbia co. on the east fide of Hudfon's river, 7 miles above Red Hook, and 13 north of New-York city.

WEST-CHESTER, a county of New-York ; bounded north by Dutcheis co. fouth by Long-Ifland Sound, weft by Hudfon's river, and east by the State of Connecticut. It includes Captain's Iflands and all the iflands in the found, to the eaft of Frogs Neck, and to the northward of the main channel. In 3790, it contained 24,003 inhabitants, including 1419 flaves. In 1796, there were, in its 21 townships, 3,243 of the. inhabitants qualified electors.

WEST-CHESTER, the chief township of the above county; lying partly on the Sound, about 15 miles easterly of New-York city. It was much impoverifhed in the late war, and contains 1203 inhabitants; of whom 164 are electors, and 242 flaves.

WEST CHESTER, the chief town of Chefter co. Pennfylvania, containing about 50 houses, a court-house, stone gaol, and a Roman Catholic church. It is about 25 miles welt of Philadelphia.

WESTERLY, a post-town on the feacoaft of Washington co. Rhode-Island, and feparated from Stonington in Connecticut by Paucatuck river, 36 miles weft by fouth of Newport, and 256 from Philadelphia. The inhabitants carry on a brifk coafting trade, and are extensively engaged in the fisheries. The township contains 2,298 inhabitants, of whom to are flaves.

WESTERN, a township of Maffachu-

of Worcefter co. 18 miles eaft by north of Springfield, 29 in the fame dia from Worcefler, and 73 fouth-well by fouth of Bofton.

WES

WESTERN, Fort, in the Diffrict of Maine, was crected in 17,52, on the east bank of the fmall fall which terminates the navigation of Kennebeck river. It is 18 miles from Taconnet Fall. See Kennebeck River. It is in the townfhip of Harwington, Lincoln co. A company was incorporated in Feb. 1796, to build a bridge over the river at this place.

WESTERN Precincl, in Somerfet co. New-Jerley, contains 1,875 inhabitants, including 317 flaves.

WESTERN Territory. See Territory North-West of the Obio.

WESTFIELD, a township of Vermont; Orleans co. fouth of Jay

WESTFIELD, a pleasant post-town of Maffachufetts, Hampshire co. on the river of this name, in a curious vale, to miles west of Springfield, 34 east of Stockbridge, 52 fouth-weft of Worcefter, 105 welt-fouth-welt of Bolton, and 260 from Philadelphia. It contains a Congregational church, an academy, and about 50 or 60 compact houfes. The township was incorporated in 1660, and contains 2,204 inhabitants.

WESTFIELD, a fmall river of Maffachufetts, which rifes in Berkshire co. and runs nearly a fouth-east courfe through Middlefield, Weltfield, and Weft-Springfield, where it empties into the Connecticut, by a mouth about 30 yards wide.

WESTFIELD, a township of New-York, Washington co. bounded foutherly by Kingbury, and northerly by Whitehall. It contains 2,103 inhabitants, of whom 186 are electors, and 9 flaves. It lies near Lake George.

WESTFIELD, in Richmond co. New-York, is bounded northerly by the Fresh Kill, easterly by Southfield, and wefterly by the Sound. It contains 1151 inhabitants, of whom 131 are electors, and 276 flaves.

WESTFIELD, a fmall town in Effex co. New-Jerfey, containing a Prefbyterian church, and about 40 compact houses. It is about 7 or 8 miles W. of Elizabeth-Town.

WEST-FLORIDA. See Florida. WESTFORD, a township of Vermont, in Chittendon co. N. E. of Colchefter, adjoining, and contains 63 inhabitants. WESTFORD, a townfhip of Maffachufetts, muated in Middlefex co. 28 miles N. W. of Bofton, and contains 1229 inhabitants. In the year 1792, an acadenty was eftablifhed here.

592

WEST-GREENWICH, a township in Kent co. Rhode-Island, containing 2,054 inhabitants, including 10 flaves.

WESTHAM, a fmall town of Virginia, Henrico co. on the N. bank of James' river, 6 miles N. W. by W. of Rich mond. Here Benedict Arnold deftroyed one of the fineft foundaries for cannoh in America, and a large quantity of flores and cannon, in January, 1781.

WESTERMETON, a townhip of Maffielmetts, Hampfhire co. 7 miles wefterly of Northampton, and 109 S. W. by W. of Bofton. It contains 683 inhabitants, and lies on the W. fide of Connecticut river.

WEST Harbour, on the S. coaft of the ifland of Jamaica, is to the N. of Portland Point. There is good anchorage, but exposed to S. and S. E. winds. WEST-HAVEN, a parish of the townfhip of New-Haven, in Connecticut, pleafantly fituated on the Harbour and Sound, 3-miles W. S. W. of the city.

WEST-INDIES, amultitude of illands hetween North and South America, which were fo named at first, on the prefumption that they extended to far as to form a connexion with those of the East-Indies. The fallacy of this fuppolition was foon difcovered; the name, however, has been retained, to prevent confusion in the geographical accounts of the islands. The continent was also fometimes, called by this name, till its natural division being more attended to, it obtained a diffinct appellation. See Caribbee Iflands, and Antilles. They lie in the form of a bow, or femicircle, ftretching almost from the coaft of Florida north, to the river Oronoka, in the main continent of South-America. Such as are worth cultivation, now belong to five European powers, viz. Great-Britain, Spain, France, Holland, and Denmark,

The Britifb claim Jamaica, Grenada, and the Barbadoes, Grenadines, St. Christophers, Dominica, Antigua, St. Vincent,

Nevis. Bermudas. Montferrat. The Bahama Id-Barbuda. ands. Anguilla. Spain claims Cuba. Trinidad. Porto Rico. Margaretta. The French claim St. Domingo, or Guadaloupe. Hilpaniola, St. Lucia. Martinico. Tobago.

WEG


The Dutch claim the islands of St. Eustatia, Curasion, or Cu-Saba, raçoa.


Denmark claims the islands of St. Croix, St. Thomas, and St. John's.


Sweden also possifies The finall island of St. Bartholomew.

The climate in all the Weft-India illands is nearly the fame, allowing for those accidental differences which the feveral fituations and qualities of the lands themfelves produce. As they lie within the tropics, and the fun goes quite over their heads, paffing beyond them to the north, and never returning farther from any of them than about 30 degrees to the fouth, they would be continually fubjected to an extreme and intolerable heat, if the trade winds, rifing gradually as the fun gathers ftrength, did not blow in upon them from the fea, and refresh the air in such a manner, as to enable them to attend their concerns even under the meridian fun. On the other hand, as the night advances, a breeze begins to be perceived, which blows fmartly from the land, as it were from the centre, towards the fea, to all points of the compais it once. By the fame remarkable Providence in the difpoling of things, it is, that when the fun has made a great progrefs towards the tropic of Cancer, and becomes in a manner vertical, he draws after him a vaft body of clouds, which thield them from his direct beams, and diffolving into rain, cool the air, and refresh the country, thirsty with the long drought, which commonly prevails from the beginning of January to the latter end of May. The rains make the only diffinction of featons in the Weft-Indies; the trees are green the whole year round ; they have no cold; no frofts no fnows, and but rarely fome

hail :







hail; the forms of hail are, however, very violent when they happen, and the hail-ftones very great and heavy. The grand ftaple commodity of the Weft-Indies is fugar. The Portuguele were the first who cultivated it in America. The juice of the fugar cane is the most lively, excellent, and the least cloying fweet in nature. They compute that, when things are well managed, the rum and molaffes pay the charges of the plantation, and the fugars are clear gain. The quantity of rum and molaffes exported from all the Britith West-India Islands in 1789 to all parts, was accurately as follows : Rum, 9,492,177 gal. of which 1,485,461 gal. came to the United States; Molaffes, 21,192 gal. of which 1000 gal. came to the United States. The negroes in the plantations are fublifted at a very eafy rate. This is generally by allotting to each family of them a fmall portion of land, and allowing them two days in the week, Saturday and Sunday, to cultivate it; fome are fubfifted in this manner, but others find their negroes a certain portion of Indian or Guinea corn, and to fome a falt herring, or a certain portion of bacon or falt pork, a day. All the reft of the charge confifts in a cap, a fhirt, a pair of breeches, and a blanket ; and the profit of their labour yields on an average f10 or f12 annually. The price of men negroes, upon their first arrival, is from £30 to (36; women and grown boys 50s. lefs; but fuch negro families as are acquainted with the buline's of the illands, generally bring above £40 upon an average one with another; and there are inftances of a fingle negro man, expert in the bufinefs, bringing 150 guineas; and the wealth of a planter is generally computed from the number of flaves he poffeffes. In the year 1787, the Moravians or United Brethren, had the following number of converted negro flaves, independent of those who attended divine fervice. In Antigua 5,465

In St. Kitts, a new million	- 80
In Barbadoes and Jamaica abou	it 100
In St. Thomas's, St. Croix, and	1.1.1
St. John's about -	10,000
In Surrinam (or the continent)	
a hard state of the second s	1 miles

about -			- 400
Still living in the	Weft	-Indies	
and Surrinam	1997 - S.	. 2	16,045

Population of th	be Brif We	A-Indies.
A TRANSPORT	Whas.	Blacks.
Jamaica	30,00	250,000
Barbadoes	16.67	62,115
Grenada	1,00	23,926
St. Vincent	1.50	31,853
Dominica '	3/36	34,967
Antigua	2:90	37,808
Montferrat	1100	10,000
Nevis	1000	8,420
St. Chriftopher's	tooo	20,435
Virgin Ifles	1200	9,000
Bahamas	2000	2,241
Bermudas	462	4,919
Salata at 1 Mill	· ····································	Contraction of the local division of the loc

Total 455,684 There is likewife, in ach of the iflands, a number of perions of mixed blood, and native blacks of ee condition. In Jamaica, they are reconed at 10,000 ; and about the fame nuber in the other iflands taken collectivly. The following statement was mae by Mr. Dundas in the British House Commons. Im-ports from the Brith West-Indies in 1795, £8,800,000 ftd.-revenue arifing therefrom, £1,44,000-thipping employed in that trae, 664 vefiels-tonnage, 153,000-famen, 8,000. Exports from Great-Btain to the Weft-Indies, in 1794, £3:00,000, employ-ing 700 veffels-tonage, 177,000-feamen 12,000. Pronce of the illands imported and re-exposed, £3,700,000-The following account of the white inhabitants, free negros, and flaves, in the French islands is stracted from the ftatement of Monf. Nekar; but it is thought that the ngro flaves were doubled before the emmencement of the French revolution

St. Domingo in 1779 Martinico in 1776 Guadaloupe in 1776 St. Lucia in 1776 Tobago (fuppofed 7	Whis. 3050 1519 1.561 997	F. Blacks. 71055 83898 8.383 8.383 8.383	Slaves, 849,098 71,108 85,317 10,758
to be the fame as st. Lucia)	397	1,010	10,758
Cayenne (S. A.) in 1786	158	-	10,539
	61.44	12.424	A 22. 276

The French writers ate the number of fhips employed in heir Weft-India trade at 600, each omn average 300 tons-their feamen at 25,000. The produce in 1785, 160 millions of livres. The Weft-India trade thought to be worth to France about [400,000 fterl. annually. This was before the revolution. The value of the Spanish Weft-India trade is blended with that of P p

America in geneal; fee Spanifi America. The Dath Weft-India trade brings in a revoue to the King of Denmark of 13,000 dollars. The illands are defented under their respective names.

WEST LIBERX, a post town of Virginia, and the apital of Ohio co. is fituated at the lad of Short Creek, 6 miles from the Ohio. It contains above 120 house, a refleyterian church, a court-house and gol. It lies 2 miles west of the Pennfy ania line, 18 northwest of Wheeling, 5 west of Washington in Pennfylwan, and 348 west of Philadelphia.

WEST MAIN, to well thore of Hudfon's Bay in North America is fo called, at leaft that part of called James Bay. See Eaft Main.

WESTMINSTE, a township of Malfachusetts, fituatedn Worcester co. was granted to those wo did fervice in the Narraganset war, otheir heirs, in 1728, and was then flyled Narraganset, No. 2. It was incorporate by its present name in 1759; and comins 20,000 acres of land, well watered It is fituated on the height of land between the rivers Merrimack and onnecticut, having fitreams arising in te town, and running into both. It is pout 55 miles from Boston to the nort of west, and about 22 miles north from Worcester, and contains 177 dwellig-houses, and \$176 inhabitants.

WESTMINSTEI a confiderable townthip of Vermont, in Windham co. on Connecticut river opposite Walpole in New-Hampfhire. It contains 1601 inhabitants. Sexto's river enters the Connecticut in thes. E. corner of the township. Here is post-office 18 miles north of Brattlebough, 18 north-weft of Keen, in New-Iampshire, 59 north of Northampton i Masschufetts, and 329 north east of hiladelphia. WESTMINSTE, the easternmost

WESTMINSTE, the easternmost town of Fredericko. Maryland, about 18 miles E. N. H of Woodsborough, 26 north west of Saltimore, and 47 N. by E. of the city of Wathington.

WESTMORE, the weffernmost township of Effex co. fermont. Willoughby Lake lies in this township.

WESTMORETAND, a county of Virginia, bounded orth and eaft by Patowmack river, which divides it from Mary'and, foutheaft by NorthumberWES

Re

20

211

joi

ed

ba

Ne

N

ke

hi

113

fo

ed

at

at

ne

at

ri

aı

Ottabht

Puriter

21

Ð

1

0.1.0

3

ž

land, fouth-weft by Richmond, and weft by King George. It contains 7722 inhabitants, of whom 4425 are flaves. This county has the honour of having given birth to GEORGE WASHINGTON, first President of the United States. The court-house in this county is on the fouth bank of Patowmack river, 10 miles N. by E. of Richmond, 16 northweft of Kinfale, and 289 fouth weft by fouth of Philadelphia. Here is a paftoffice.

WESTMORELAND, a county of Pennfylvania, bounded north by Lycoming, and fouth by Fayette co. and abounds with iron ore and coal. It contains 15 townfhips and 16,018 inhabitants, including 128 flaves. Chief town Greentburg.

burg. WESTMORELAND, a confiderable townfhip of New Hampfhire, Chefhire co. on the eaftern bank of Connecticut river, between Chefterfield and Walpole, 120 miles from Portfmouth. It was incorporated in 1752, and contains 2,018 inhabitants.

WESTMORELAND, a townfhip of New-York, in Herkemer co. taken from Whiteftown, and incorporated in 1792. In 1796, it contained \$40 inhabitants, of whom 137 were electors. The centre of the town is 6 miles fouth of Fort Schuyler, and 36 north-weft of Cooperftown.

WESTMORELAND, a track of land in Pennfylvania, bounded east by Delaware river, weft by a line drawn due. north and fouth 15 miles weft of Wyoming on Sufquehannah river, and between the parallels of 41 and 40 degrees of north lat. was claimed by the State of Connecticut, as within the limits of their original charter, and in 1754 was purchased of the Six Nations. of Indians by the Sufquehannah and Delaware companies, and afterwards fettled. by a confiderable colony, under the jurifdiction of Connecticut. This tract. was called Weftmoreland, and annexed to the county of Litcafield in Connecticut. The Pennfylvanians difputed the claim of Connecticut to thefe. lands, and in the progress of this bufneis there was much warm contention, and fome bloodfhed. This unhappy difpute has fince been adjusted. Sea Wyoming.

WESTON, a township of Maffachuletts, in Middlefex co. 15 miles weft of Bofton.

WES

F94

Boston. It was incorporated in 1712, and contains 1,010 inhabitants.

weft

in-

Ves.

ling

ON,

tes.

ion

10

rth-

by

oft-

nn-

ng,

nds

115

in-

:ní-

ible

hire

cut

al-

uns

of

iom

92.

166,

en-

ort

erf-

and da-

due.

ly-

be-

de-

the

li-

in

ona

De-

led

the

act

ked

bn-

pt-

efe.

the-

on,

Py Sea

112-

of

1120.

It

WESTON, a township of Connesticut, Fairfield co. north of Fairfield, adjoining.

WESTON'S Islands, groups of illands

WEST POINT, a ftrong fortreiserected during the revolution, on the welt bank of Hudson's river, in the State of New-York, 6 miles above Anthony's Nofe, 7 below Fifh-Kill, 22 S. of Poughkeephe, and about 60 N. of New-York city. It is fituated in the midft of the high lands, and is strongly fortified by nature as well as art. The principal fort is fituated on a point of land, formed by a fudden bend in the river, and commands it, for a confiderable diftance, above and below. Fort Putnam is fituated a little farther back, on an eminence which overlooks the other fort, and commands a greater extent of the river. There are a number of houses and barracks on the point near the forts. On the opposite fide of the river, are the ruins of Old Fort Conflication, with fome barracks going to decay. A number of continental troops are stationed here to guard the arfenal and ftores of the United States, which are kept at this place. This fortrel's is called the Gibraltar of America, as by reafon of the rocky ridges, riling one behind another, it is incapable of being invefted by lefs than 20,000 men. The fate of America seemed to hover over this place. It was taken by the British, and afterwards retaken by ftorm, in a very gallant manner, by Gen. Wayne. Benedict Arneld, to whom the important charge of this fort was committed, defigned to have furrendered it up to the British; but Providence difappointed the treafonable defign, by the most fimple means. Major Andre, a most accomplished and gallant officer, was taken, tried, and executed as a fpy, and Arnold escaped. Thus the British exchanged one of their belt officers, for one of the work men in the American army.

WESTFORT, a flourishing township of Massachusetts, Bristol co. 70 miles southerly of Boston. It was incorporated in 1787, and contains 2,466 inhabitants.

WEST SPRINGFIELD, a township of Maffachuletts, Hampshire co. on the W. fide of Connecticut river, opposite Springfield, about 28 miles north of Hartford, and 100 W. S. W. of Bofton. In the compact part are about forty dwelling houses, and a Congregational church. The township contains 3 parishes, and 2,367 inhabitants.

WHA

WEST-STOCKBRIDGE, a township of Massachuletts, in Berkshire co. adjoining Stockbridge on the west, and has the New-York line on the northwest, and lies 150 miles from Boston. William's river, and its streams, water the township, and accommodate 3 ironworks, a fulling-mill, a grist-mill, and 2 faw mills.

WEST-TOWN, a township in Chefter co. Pennsylvania.

WETHERSFIELD. See Weathersfield.

WEYBRIDGE, a township of Vermont, in Addison county, separated from New-Haven on the N. and E. by Otter Creek. It contains 175 inhabitants. Snake Mountain lies nearly on the line between this township and that of Addison on the west.

WEYMOUTH, the Weffagufcus, or Wassagusset, of the Indians, a township of Maffachufetts, Norfolk co. incorporated in 1635. It lies 14 miles S. E. of Bofton, and employs fome finall veffels in the mackarel fishery. Fore river on the N. W. and Back river on the S. E. include near one half of the townthip. The cheefe made here is reckoned among the beft brought to Bofton market. It is faid to be one of the oldeft towns in the State : Mr. Wefton, an English merchant, having made a temporary fettlement here in fummer, 1622. It contains 232 houfes, and 1469 inhabitants.

WHALE COVE Island, in the northern part of N. America, is the most northerly of two islands lying to the S. of Brook Cobham, or Marble Island, which is in lat. 63. N. Lovegrove, the other island, has a fair opening to the west of it.

WHALE FISH Island, in the river Effequibo, on the coast of S. America, is above the Seven Brothers, or Seven Islands, and below the Three Brothers.

WHALE Island, at the mouth of M'Kenzie's river, in the North Sea or Frozen Ocean, on the north coaft of the north-weftern part of North-America. N. lat. 69. 14.

WHAPPING'S Creek, a fmall creek which empties through the eaft bank of P p 2 Hudion's

Hudfon's river, in the township of Fish-Kill, 8 miles south of Poughkeepsie, and 72 north of New-York city. Here are two mills, at which considerable business is performed.

WHARTON, a township of Fayette co. Pennsylvania.

WHATELY, a township of Massachufetts, in Hampshire co. 10 miles north of Northampton, and 105 miles from Boston. It was incorporated in 1771, and contains 736 inhabitants.

WHEELING, or Wheelin, a post-town of Virginia, fituated at the mouth of a creek on the east bank of Ohio river, to miles above Grave Creek, 18 fouthwest of West Liberty, and 61 southwest of Pittsburg. Not far from this place, a wall has been discovered fome feet under the earth, very regularly built, apparently the work of art. It is 363 miles from Philadelphia.

WHEELOCK, a township of Vermont, in Caledonia co. about 20 miles northwest of Littleron, and contains 33 inhabitants.

WHEELWRIGHT Gut, at the northweft end of the ifland of St. Chriftopher's in the Weft-Indies, has Willet's Bay and Maſshouſe Bay to the eaft, and Courpon's and Convent Bays to the fouth-weft. There is a fand before the entrance which appears to prevent fhips from going in.

WHENNUIA, one of two finall iflands in the South Pacific Ocean, near the ifland of Otaha.

WHETSTONE Fort, is on the north fide of Patapico river, and welt fide of the mouth of Baltimore harbour, in Maryland. It is opposite Goffuch Point, $2\frac{1}{2}$ miles eafterly from the Baltimore Company's iron-works, at the mouth of Gwinn's Falls.

WHIPPANY, a village of New-Jerfey, Morris co. on a branch of Paffaick river, nearly 5 miles N. E. of Morriftown.

WHIRL, or Suck, in Tenneffee river, lies in about lat. 35. N.

WHITE, a river or torrent iffuing from the mountain of fulphur in the ifland of Gaudaloupe, in the Weft-Indies. It is thus named as often affuming a white colour from the afhes and fulphur covering it. It empties into the river St. Louis.

WHITE, a river of Louisiana, which joins Arkanias river, a water of the

four

Brit

177

Kin

Yot

Sco

wef

of (

the

120

Bre

Bla

bur

Bay

ca,

abo

fou

56.

of

Por

Net

hav

Sch Th

flou

ftre

ed ally

by

nei

cou

hou

but

fep

fev

ĩs

wh

age

an

Th

bee

AI

the

ma

int

ris

fev

102

COL

Hu

lin

mi

≫In

1

1

Miffifippi, about 10 miles above the fort, which Mr. Hutchins reckons 550 computed miles from New-Orleans, and 660 from the fea. It has been navigated above 200 miles in flat bottomed boats. See Arkanfas.

WHITE, a final river of the N. W. Territory, which purfues a north-weft, and, near its mouth, a wefterly courfe, and enters Wabath river, 12 miles below the mouth of Chickafaw river.

WHITE, a river of Vermont, which falls into Connecticut river about 5 miles below Dartmouth college, between Norwich and Hartford. It is from 100 to 150 yards wide, fome diftance from its mouth. Its fource is in a fpring, which by means of Onion river, communicates with Lake Champlain. It derives its name from the whitenefs of its water.

WHITE Bay, on the E. coaft of Newfoundland Ifland, in the Machigonis river. Its N. limit is Cape d'Argent.

WHITE Cape, or Blanco, on the weft coaft of New-Mexico, is 20 leagues to the north-weft of Herradura. This cape, in lat. 10. N. bears with the ifland Canoe, at north-weft by weft and S. E. by E. and with St. Luke Ifland at N. E. by N. and fouth-weft by fouth, being about 9 leagues from each.

WHITE Deer, a township of Pennfylvania, fituated on Susquehannah river.

WHITE Ground, a place in the Creek country, 10 miles from Little Talaffee, WHITEFIELD, a township of Penn-

fylvania, in Westmoreland county.

WHITEHALL, a township of Pennfylvania, in Northampton county.

WHITEHALL, a township of New-York, Washington co. bounded foutherly by the S. bounds of the tract formerly called Skeensborough, and northerly by the north bounds of the county. In 1790, it contained 805 inhabitants. In 1796, 150 of the inhabitants were electors.

WHITE MARSH, a township of Pennfylvania, Montgomery co.

WHITE Mountains. See New-Hampfoire.

WHITEPAINE, a township of Pennfylvania, Montgomery co.

WHITE PLAINS, a township of New-York, West-Chefter co. bounded easterly by Mamaroneck river, and westerly by Bronx river. It contains 505 inhabitants, of whom 76 are electors, and 49 flaves.

49 flaves. It is remarkable for a battle fought here between the American and British forces, on the 28th of October, 1776. It is 15 miles E. by N. of Kingsbridge, 30 N. E. by N. of New-York, and 125 from Philadelphia.

nd

ed

¥.,

ft,

le,

e.

ch

ES

to

ťs

:h

i-

đ-

ts

į.

R

0

:,

y

3

e

WHITE Point, on the coaft of Nova-Scotia, is about 3 leagues to the fouthweft from Cape Canfo, and north-eaft of Green Point. There is an island off the point that fhelters Bar Haven.

WHITE Point, on the coaft of Cape Breton Ifland, is about a mile S. W. of Black Cape, near the harbour of Louifburg, and the east point of Gabarus Bay.

WHITE Point, in the illand of Jamaica, lies eaftward of White Horfe Cliffs, about 7 leagues E. of Port Royal.

WHITE'S Bay, on the coaft of Newfoundland. N. lat. 50. 17. W. long. 56. 15.

WHITE'S *River*, on the N. E. coaft of Jamaica, is near the weft limit of Port Antonio.

WHITESTOWN, in Herkemer co. New-York, on the fouth fide of Mohawk river, 4 miles weft of Old Fort Schuyler, and 100 weft of Albany. The compact part of this new and flourishing town lies on one beautiful ftreet about a mile in length, ornamented with trees. The houses are generally furnished with water, conducted by pipes laid under ground, from the neighbouring hills. At prefent the court-house, meeting-house, and schoolhouse, are combined in one building; but it is contemplated fhortly to erect feparate and handfome edifices for these feveral purposes, The foil of this town is remarkably good. Nine acres of wheat in one field, yielded, on an average, 41 bufhels of wheat, of 60lb. each, an acre. This is no uncommon crop. This town and its neighbourhood has been fettled with remarkable rapidity. All that diffrict comprehended between the Oneida Refervation, and the German Flats, and which is now divided into the townships of Whitestown, Paris, and Weftmoreland, was known, a few years fince, by the name of Whiteftown, and no longer ago than 1785, contained two families only, those of Hugh White, and Moles Foot, elquires. In 1796, there were within the fame limits, 5 parifhes, with as many fettled ministers, 3 full regiments of militia, 1

corps of light-horfe, all in uniform. In the whole, 7359 inhabitants, of whom 1190 were qualified electors.

WHITE Wood Island, or De Bois Blanc. See Michillimakkinak.

WHITING, a township of Vermont, in Addison co. separated from Leicester, on the E. by Otter Creek, and has part of Orwell on the W. It contains 250 inhabitants.

WHITTINGHAM, a township of Vermont, in the fouth-west corner of Windham co. containing 442 inhabitants.

WHITSUN Ifland, in the South Pacific Ocean, is about 4 miles long, and 3 broad; and fo furrounded by breakers that a boat cannot land. S. lat. 19-26. W. long. 137. 56. Variation of the needle in 1767, 6° E.

WIANDOTS, or Wyandots, an Indian tribe inhabiting near Fort St. Joseph, and Detroit in the N. W. Territory. Warriors, 200.

WIAPOCO, or Little Wia, is an outlet or arm of the river Oroonoko, on the weft fide. It has many branches, which are all navigable.

WICKFORD, a finall trading village in the township of North-Kingstown, Rhode-Island, and on the west fide of Narraganset Bay; 24 miles south of Providence, and 9 or 10 N. W. of Newport.

WIESPINCAN, a river of Louifiana, which empties into the Miflifippi, 22 miles above the Soutoux village.

WICOMICO, fmall river of Maryland, which rifes in Suffex county, Delaware, and empties into Fifting Bay, on the eaft fhore of Chefapeak Bay.

WIGHCOMICO, a fhort navigable river of Maryland, which is formed by Piles, and Allen's Fresh, and, running southward, empties into the Patowmac, about 35 miles from its mouth. Cob. Neck forms the north limits of its mouth.

WIGHT, Ifle of. See Ifle of Wight County.

WIGHT, Ifte of; eaft end of Long. Ifland. See Gardner's Island.

WILBRAHAM, a township of Massachusetts, in Hampshire co. 10 miles east of Springsfield, 30 north east of Hartford in Connecticut, and 89 southwest of Boston. It was incorporated in 1763; contains two parishes, and 1555 inhabitants.

WILKES, a county of the Upper dif-P p 3 trict trict of Georgia, feparated from South-Carolina, on the eaftward, by Savannah river, and contains 31,500 inhabitants, including 7,268 flaves. Tohacco is the chief produce of this county, of which it exported about 3000 hhds. in 1788. It is well watered, and is famous for a medicinal fpring, near its chief town, Washington; which fee.

WILKES, a county of Morgan diftrict, in the north-weft corner of North-Carolina. It contains 8,143 inhabitants, including 549 flaves.

WILKES, a post-town, and chief of the above county, 33 miles from Rock-ford, 45 from Morgantown, and 611 from Philadelphia.

WILKSBARRE, or Wilk/burg, a posttown of Pennfylvania, and chief town of Luzerne co. fituated on the fouth-eaft lide of the east branch of the Suiguehannah. It contains a court houle, gaol, and about 45 houfes. It is 67 miles N. E. of Bethlehem, about the fame diftance above Sunbury, and 118 N. by N. W. of Philadelphia.

WILLET'S Bay, at the north weft and of the island of St. Christopher's. Willet's Gut is at the fouth-weft coaft of the fame island.

WILLIAM, Fort, (now called the Caftle) was crected on Cattle Ifland in Bofton harbour, in the reign of king William, by Col. Roemer, a famous engi-When the British troops evacuneer. ated Bofton, in March, 1776, the fortifications were blown up, but were foon after repaired. The buildings are the governor's houfe, a magazine, gaol, barracks, and work-fhops. On this ifland, which contains about 18 acres of land, diftant 3 miles from the town of Bofton, there are a number of convicts, who are fentenced to confinement here for different periods, according to their crimes, and employed in the manufacture of nails and fhoes, and guarded by a company of between 60 and 70 foldiers. The fort, which commands the entrance into the harbour, has 50 pieces of cannon mounted, and 44 others lie difmounted.

WILLIAMS, a township in Northampton county, Pennfylvania.

WILLIAM's Sound, Prince, on the north-weft coaft of North-America. Its E. point is in lat. 60. 19. N. and long. 146. 53. W. and Cape Elizabeth which

Cook's river, is in lat. 59. 10. and long. 152. 15.

ielt

200

tant

lel f

cent

suns

abo

100

ftree

lege

is at

hou

mar

cula

3º I Th

tien

hav

exe

No

nor

Th

it v

Th

leg

Fre

has

the

is

Be

gu

an

go

the

ter

is

21)

A

PU

τo

ot

lis

in

M

la

ta

aï

th

al

0

e١

Ct

in

fe

lt

u

WILLIAMSBOROUGH, a post-town of N. Carolina, and capital of Granville. co. pleafantly fituated on a creek which. falls into the Roanoke. It carries on a brifk trade, with the back counties, and contains between 30 and 40 houles, a coust-house, gaol, and flourishing academy. It is 17 miles from Warrenton, 48 north east of Hillfborough, 56 weftnorth weft of Halifax, and 407 from Philadelphia.

WILLIAMSBURG, a co. of Virginia, between York and James's rivers, and was joined in the enumeration of inhabitants, in 1790, with York cu. Thefe together contain 5,233 inhabitants.

WILLIAMSBURG, a township of Maffachufetts, Hampfhire co, on the weft fide of Connecticut river, having Hatfield on the E. It contains a handfome Congregational church, 1 59 houfes, and 1,049 inhabitants. In the year 1760, this township was a wilderness. It lies, 7 miles from Connecticut river, 8 northweft of Northampton, and 108 weft of Bofton.

WILLIAMSBURG, a post-town of New-York, Ontario co. fituated on the E. fide of Genneffee river, near where Canaferago creek empties into that river; 30 miles fouth-weft of Canandaigua, 40 north-weft of Bath, 98 northweft of Athens or Tioga Point, and 288 N. westerly of Philadelphia.

WILLIAMSBURG, called also Jonestown, a town of Pennfylvania, Dauphine co. at the junction of Little Swatara with Swatara river. It has a German Lutheran and Calvinift church, and about 40 dwelling houses. It is 23 miles N. E. by E. of Harrifburg, and 89 north-weft of Philadelphia .- Alfo, the name of a township in Luzerne county.

WILLIAMSBURG, a village of Maryland in Talbot county, 5 miles northeaft of Esfton, and 4 north weft of King's-Town.

WILLIAMSBURG, a post-town of Virginia, lies 60 miles eastward of Richmond, fituated between two creeks, one falling into James, the other into York, The diffance of each landingriver. place is about a mile from the town, During the regal government it was propoled to unite these creek, by a canal paffing through the centre of the is its well point, and the E. point of town; but the removal of the feat of government

ille

ich

n a

ind

្ព

ca-

ma

A.

m

nd

la-

efe

of

he

d.

28,

0,

es

h.

of

of

be

Te

¥-

i-

h-

18

8-

ne

ra

in

Id

3

9

le

7.

1.

1-

Æ

14

ę

k

4

8

e £

Ŀ

overnment rendered it no longer an object of importance. It contains about 200 houses, and has about 1400 inhabitants. It is regularly laid out in parallel freets, with a pleafant fquare in the centre of about ten acres, through which runs the principal fireet eaft and weft, about a mile in length, and more than 100 feet wide. At the ends of this freet are two public buildings, the college, and capitol. Bendes thefe, there is an Epifeopal church, a prifon, a courthoufe, a magazine, now occupied as a market, and a hospital for lunatics, calculated to accommodate between 20 and go patients, in feparate rooms or cells. The houfe is neatly kept, and the patients well attended ; but convalefcents have not fufficient room for free air and exercife without making their efeape. Not far from the fquare flood the governor's house, or palace, as it was called. This was burnt during the war, while it was occupied as an American holpital. The house of the prefident of the college, occupied alfo as an hofpital by the French army, thared the fame fate. This has fince been rebuilt at the expense of the French government. In the capitol is a large marble statue, of Narbone Berkley, Lord Botetourt, a man diftinguifhed for his love of piety, literature, and good government, and formerly governor of Virginia. It was erected at the expense of the State, fome time fince the year 1771. The capitol is little better than in ruins, and this elegant statue is expoled to the rudenels of negroes and boys, and is mamefully defaced. A late act of the affembly authorites the pulling down one half of this building, to defray the charge of keeping the other half in repair. The college of William and Mary fixed here, was founded : in the time of king William and queen Mary, who granted to it 20,000 acres of land, and a penny a pound duty on certain tobaccos exported from Virginia and Maryland, which had been levied by the statute of 25 Car. 2. The affembly alfo gave it, by temporary laws, a duty on liquors imported, and fkins and furs exported. From these resources it re ceived upwards of 3000l. The buildings are of brick, fufficient for an indifferent accommodation of perhaps 100 students. By its charter it was to be under the government of 29 vifitors, who were to be its legislators, and to | handfome donation of lands. In 1790,

WIL 599 have a prefident and fix professors, who were incorporated. It was allo reprefentative in the general affembly Under this charter, a profefforthip of the Greek and Latin languages, a profeffor-fhip of mathematics, one of moral phi-lolophy, and two of divinity, were ef-tablished. To these were annexed, for a fixth professor for this, a confiderable do-nation by a Mr. Boyle of England, for the infruction of the Indians, and their convertion to Christianity. This was called the profefforthip of Brafferton. from an eftate of that name in England, purchased with the monies given. court of admiralty fits here whenever a controverfy arifes. It is 11 miles E. of York Town, 60 E. of Richmond, 48 N. W. of Norfolk, and 338 S. S. W. of

Philad	lelphia.	To the Lot Pro-
acresses.	Leaft heat here,	6º 0'
1.21	Mean heat,	60 8
e page de la	Greateft heat,	.98 0

N. lat. 37. 16. W. long. 76. 48. WILLIAMSPORT, a post-town of Maryland, Washington co. on the N. fide of Patowmack river, at the mouth of Conegocheague Creek, 8 miles S. of the Pennfylvania line, 6 fouth-weft of Hagarftown, 37 N. by E. of Winchefter,

in Virginia, 28 fouth by welt of Chamberfburg, in Pennfylvania, and 155 W. by S. of Philadelphia.

WILLIAMSON, a township of New York, Ontario co. In 1796, there were 142 of its inhabitants electors.

WILLIAMSTOWN, a township of Vermont, Orange co. on the height of land between Connecticut river and Lake Champlain, about 45 miles from the former, and 50 from the latter. It is bounded eaftward by Washington, and weltward by Northfield, and contains 146 inhabitants. Stephen's Branch, a ftream which runs N. to Onion river, rifes in this township.

WILLIAMSTOWN, a mountainous township of Massachusetts, in the northweft corner of the State, and in Berk-fhire co. containing 1769 inhabitants. It is well watered by Hoofack and Green rivers, the former of which is here 8 On these threams are 4 rods wide. grift-mills, 3 faw-mills, and a fullingmill. The main county road paffes through it. Colonel Ephraim Williams laid the foundation of an academy feveral years fince, and endowed it by a

Pp4

partly

600

partly by lottery, and partly by the liberal donation of gentlemen in the town, a brick edifice was erected, \$2 feet by 42, and four ftories high, containing 24 rooms for ftudents, a large school-room, a dining-hall, and a room for public fpeaking. In 1793, this academy was erected into a college, by an act of the legislature, by the name of Williams' College, in honour to its liberal foun-der. The languages and fciences ufually taught in the American colleges are taught here. Board, tuition, and other expenses of education are very low; and from its fituation and other circumstances, it is likely, in a fhort time, to become an institution of great utility and importance. The first public commencement was held at this college in September, 1795. In 1796, the legiflature granted a townships of land to Williams' College. There were, in 1796, 101 ftudents in the four claffes in this college, befides 30 pupils in the academy connected with the college. A company was incorporated the year above mentioned, to bring water in pipes into the town ftreet. It is 28 miles north of Lenox, and 1 50 north-wefterly of Bofton.

WILLIAMSTOWN, a post-town and the capital of Martin co. N. Carolina, is fituated on Roanoke river, and contains but few houses, befides the courthouse and gaol. It is 25 miles from Blountsville, 24 from Plymouth, 55 from Halifax, and 444 from Philadelphia.

WILLIMANTIC, a finall river of Connecticut, which runs a fouth-eaft courfe, and uniting with Natchaug river, forms the Shetucket at Windham.

WILLINBOROUGH, a township of New-Jersey, fituated in Burlington co. on Delaware river, about 14 miles from Philadelphia. It has generally a thin foil, but considerable quantities of fruits and vegetables are raised here for the Philadelphia market.

WILLINGTON, a township of Connecticut, in Tolland co. 6 miles east of Tolland, and 35 north-casterly of Hartford, and was settled in 1719. The lands are rough and hilly. The earthquake on fabbath evening, Oct. 29, 1727, was severely felt in this town.

WILLIS, a township in Chester co. Pennsylvania.

WILLIS Greek, in Maryland, falls into the Patowmack from the north at Fort Cumberland, WILLIS Mand, in the S. Atlantic Ocean, is near the north-welt end of South Georgia, and has Bird Island to the north of it. S. lat. 54. W. long. 38. 30. the

Nes

Acres

of t

in

fou

Fri

of

wid

land

yet.

Iti

bur

E.,

the

45

wei

pat

Yo

Ne

ma

boi

fou

fou

not

the

yei

C01

10

po

ab

of

Ch

and

COL

to:

the

to

ço

thu

ric

is

25

ch

in;

foi

bu

fu

pr

rie

ad

ye

â,n

of

WILLISTON, a township of Vermont, in Chittenden co. joins Burlington on the north-west. It contains 471 inhabitants.

WILLOUGHBY Bay, near the foutheast part of the island of Antigua, in the West-Indies. It is well fortified. Bridgetown lies on its north-eastern fide, in St. Philips' parish, and is defended by Fort William.

WILLOUGHEY Lake, in Vermont, in the township of Westmore. It is about 6 miles long and one broad, and sends a ftream which runs northward and empties into Lake Memphremagog, in the township of Salem. This lake furnishes fish resembling bass, of an excellent flavour, weighing from ten to thirty pounds. People travel twenty miles to this lake to procure a winter's stock of this fish.

WILLSBOROUGH, a new fettled townthip in Clinton co. New York ; bounded on the fouth by the town of Crown-Point, on the north by the fouth line of a patent, which includes the river Au Sable at its mouth, continuing weftward, to that part of the county of Montgomery, now called Herkemer county. It contained 375 inhabitants in 1790. In 1796, there were 160 of the inhabitants electors. It is a fine champaign, fertile country, inhabited by a number of industrious, thriving farmers. Its cultivation has been rapidly advancing. In this town is a remarkable Split Rock, which is a fmall point of a mountain projecting about 50 yards into the neighbouring lake. This disjointed point has, from the appearance of the opposite fides, and their exact fitnels for each other, doubtlefs been rent from the main rock, by fome violent fhock of nature. It is removed about 20 feet, and has on its point, a furface of nearly half an acre, which has fufficiency of foil, and is covered with wood. The height of the rock on each fide of the fiffure is about 12 feet. The river Boquet runs through this town a confiderable diftance, and is navigable for boats 2 miles, where there are talls and mills. This town was partly fettled before the year 1775. It commands a beautiful view of the

antie

id of

fland

ong.

lont,

1 00

nha-

uth-

, in

fied.

ide,

ded

, in

out

is a

the

hes

ent

rty

to

of

m-

d-

n-

of

14

rd

D-

It

In

18

i-

)£

ц

2

2

2

1

the lake, and lies 214 miles north of New-York city.

WILLS Cove, on the north-east fide of the ifthmus of the ifland of St. Kitts, in the Weft-Indies, to the eastward foutherly from North Friar and Little Friar Bays.

WILLS Creek, or CaicuStuck, a branch of Patowmack river, is 30 or 40 yards wide at its mouth, where Fort Cumberland ftood. It affords no navigation as yet, and runs a fhort courfe foutherly. It is 281 miles north-weft of Williamfburg, 171 from Frederick (burg, and 173 E, by N, of Alexandria.

WILLS-TOWN, an Indian village on the N. E. bank of Mutkingum river, 45 miles from its mouth, and 117 fouthwesterly from Pittsburg, by the Indian path through the Indian town.

WILMANTON, in the State of New-York, flands on Wallkill, between Newburg and New-Brunfwick.

WILMINGTON, one of the eaftern maritime diffricts of North Carolina; bounded north-eaft by Newbern diffrict, fouth-eaft by the Atlantic Ocean; fouth-weft by South Carolina; and north-weft by Fayette. It comprehends the counties of Brunfwick, New Hanoyer, Onflow, Duplin, and Bladen. It contains 26,035 inhabitants; of whom 30,056 are flaves.

WILMINGTON, a port of entry and post-town of N. Carolina, capital of the above diffrict, is fituated on the eaft fide of the eaftern branch of Cape Fear or Clarendon river; 34 miles from the fea, and 100 fouthward of Newbern. The course of the river, as it paffes by the town, is nearly from north to fouth, and the breadth 150 yards. Opposite the town are two illands extending with the courfe of the river, and dividing it into three channels : they afford the fineft rice fields in N Carolina. The town is regularly built, and contains about 250 houfes, a handfome Epifcopal church, a court-houfe, and gaol. Having fuffered much by two fires, onefourth of the town, which has been rebuilt, is of brick. Its markets are well fupplied with fifh, and all manner of provisions. A considerable trade is carried on to the Weft-India Iflands and the adjacent States. The exports for one year, ending the 30th of Sept. 1794, amounted to 133,534 dollars. Those of all the other ports of the State,

amounted only to 177,598 dollars. It is 90 miles fouth-east of Fayetteville, 192 fouth-fouth-west of Edenton, 198 north-east of Charleston, S. Carolina, and 600 fouth-fouth-west of Philadelphia. N. lat. 34, 11. W. long 78. 15.

WIL

WILMINGTON, a township of Vermont, in Windham co. contaning 645 inhabitants, who are chiefly wealthy farmers. It lies on Deerfield river, on the east fide of the Green Mountain, on the high-road from Bennington to Brattleborough, about 20 miles from each. Confiderable quantities of maple fugar are made in it; fome farmers make 1000 or 1400 pounds a featon. The Hay-flack, in the north-west corner of this township, is among the highest of the range of the Green Mountains. It has a pond near the top of it, about half a mile in length, round which deer and moofe are found.

WILMINGTON, a township of Maffachusetts, in Middlesex co. 16 miles from Boston. It was incorporated in 1730, and contains 710 inhabitants. Hops, in great quantities, are raised in this town.

WILMINGTON, a port of entry and post-town of the State of Delaware, and the most confiderable town in the State. It ftands in Newcaffle co. on the north fide of Christiana Creek, between Christiana and Brandywine creeks, which at this place are about a mile diftant from each other, but uniting below the town, they join the Delaware in one ftream, 400 yards wide at the mouth. The fcite of the principal part of the town is on the fouth-weft fide of a hill, which rifes 109 feet above the tide, 2 miles from Delaware river, and 28 fouthweft from Philadelphia. On the northeaft fide of the fame hill, on the Brandywine, there are 13 mills for grain, and about 40 neat dwelling-houfes, which form a beautiful appendage to the town-The Christiana admits veffels of 14 feet draught of water to the town; and those of 6 feet draught, 8 miles further, where the navigation ends; and the Brandywine admits those of 7 feet draught to the mills. The town is regularly laid out in fquares fimilar to Philadelphia, and contains upwards of 600 houles, moftly of brick, and 3,000 inhabitants. It has 6 places of public worthip, viz. two for Prefbyterians, one for Swedish Episcopalians, one for Friends,

Friends, one for Baptifts, and one for Methodifts. Here are two markethouses, a poor-house, which stands on the weft fide of the town, and is 120 feet by 40, built of flone, and 3 ftories high, for the reception of the paupers of Newcastle co. There is another stone building which was used as an academy, and was fupported for fome time with confiderable reputation, but by a defect in the conftitution of the feminary, or tome other caule, it has, of late, been entirely neglected as a place of tuition. There are, however, nearly 300 children in the different fchools in town. About the year 17 36, the first houses were built at this place; and the town was incorporated a few years afterwards. Its officers are two burgeffes, 6 affiftants, and two conftables, all of whom are annually chofen. For other particulars, fee Delaware. N. lat. 39. 43. 18. W. long. 75. 32.

WILMOT, a township of Nova Scotia, Annapolis co. settled from Ireland and New-England.

WILSONVILLE, a town of Pennfylvania, newly laid out on the Walenpapeck, at its junction with the Lexawaciein, 120 miles north of Philadelphia. Here are already erected 14 houfes, a faw and grift mill, and a large building for manufacturing fail cloth. The creck here falls upwards of 300 feet, fome fay 500, in the fpace of a mile, tor 17 miles above the fails the creck has a gentle current.

WILTON, 'a village of Charleston district, S. Carolina; fituated on the E. fide of Edisto river, 27 miles south-west of Charleston.

WILTON, a township of New Hampshire, Hillsborough co. S. W. of Amherst, adjoining, about 70 miles westerly of Portsmouth. It was incorporated in 1762, and contains 1105 inhabi-ents.

WIMACOMACK, a village of New-York, in Suffolk co. Long-Ifland; 6 miles welt by fouth of Smithtown, and north-e ft of Huntingdon, and 44 eafl by north of New-York city.

WINCHELSEA, an island in the S. Pacific Ocean which appears like three islands. It is about 30 miles S. by E. of Sir Charles Hardy's Island.

WINCHENDON, a post-town of Maffachuletts, in Worcefter co. 7 miles N. of Gardner, 35 north-westerly of Worcefter, 60 north-west by welt of Boston,

and 370 north-east of Philadelphia. This town(hip was formerly called *lpf-wich Canada*, until it was incorporated in 1764. It is on Miller's river, and contains 950 inhabitants. This place was visited by a dreadful tornado, on the 22st of October, 1795, which did confiderable damage.

WINCHESTER, a township of Connecticut, in Litchfield co. about 12 of 15 miles north of Litchfield.

WINCHESTER, a township of New-Hampshire, in Cheshire co. east of Hinsdale and Fort Dummer, adjoining. It is 110 miles from Portsmouth, and contains 1209 inhabitants.

WINCHESTER, the chief town of Clarke county, Kentucky.

WINCHESTER, or Fredericktown, a post-town of Virginia, and the capital of Frederick co. It is fituated near the head of Opeckon Creek, which emptics into Patowmack river; about 36 miles from the celebrated paffage of the Patowmack through the Blue Ridge. It is a handfome flourifing town, flanding upon low and broken ground, and has a number of refpectable buildings ; among which are a court houfe, gaol, a Preibyterian, an Episcopalian, a Methodift, and a new Roman Catholic church. The dwelling-houfes are about 350 in number, feveral of which are built of ftone. It is a corporation, and contains nearly 2,000 inhabitants. It was formerly fortified ; but the works are now in ruins. It is so miles E. by S. of Romney, 100 N. E. by N. of Staunton, 110 weft-north weft of Alexandria, 180 north-welt of Richmond, and 192 from Philadelphia. N. lat. 39. 17. 30. W. long. 78. 39.

WIND Gap, a pafs in the Blue Mountains in Penniylvania; about 9 miles S. W. of Penn's Fort. Although 100 feet higher than the prefent bed of the Delaware, it is thought to have been formerly part of the bed of that river. The Wind Gap is a mile broad, and the ftones on it fuch as feem to have been washed for ages by water running over them.

WINDHAM, a county in the foutheaft corner of Vermont; having the State of Maffachufetts louth, and Connecticut river eaft, which divides it from New Hampfhire. It contains 22 townthips, and 17,693 inhabitants. Chief towns, Newfane and Putney.

WINDHAM,

W eaft c State State 13 to inclus Wine w coun Shett of N It ce houf and a mile Wil Nati nort forn ford mot tow 168 Hai 25 froi hah trit mi DOI hal Sc Cr T (fi th O m pi la

lie

B

V

C2

at

li

b

a

1

а

0

é

hia.

Iøj

ted

and

ace

on

did

Dn-

or

100-

nf-

It

of

tal

:24

ch

111

of

e.

d-

rd

14

a

3.

۱.

in

of

18

14

w

h

۱.

ø

١.

ŧ

2

WINDHAM, a county in the northeast corner of Connecticut, having the State of Maffachuletts north, and the State of Rhode-Ifland east. It contains 13 townships, and 28,921 inhabitants, including 184 flayes. Chief town, Windham.

WINDHAM, the capital of the above county, and a post-town, is fituated on Shetucket river, 12 miles north by weft of Norwich, and 31 east of Hartford. It contains between 60 and 70 compact houfes, a court-houfe, gaol, an academy, and a Congregational church. It is 253 miles from Philadelphia. The river Willimantick from the north-weft, and Natchaug from the north, meet in the north-wellerly part of the township, and form the Shetucket, a pleafant river, affording plenty of fifh, particularly falmon, at fome feafons of the year. The township was fettled from Norwich, in 1686, and was incorporated in 1702.

WINDHAM, a township of New-Hampshire, Rockingham co. is about 25 miles south-welt of Exeter, and 40 from Portsmouth. It contains 663 inhabitants.

WINDHAM, a township of the Diftrict of Maine, Cumberland county 134 miles north of Boston. It was incorporated in 1762, and contains 938 inhabitants.

WINDSOR, a township of Nova-Scotia, in Hants co. near the river St. Croix, which empties into the Avon. The rivers Kenetcoot and Cocmiguen (fo called by the Indians) run through this township and empty into the Avon. On these rivers are flourishing fettlements end fertile land. Lime-ftone and plaister of Paris are found here. The lake Potawock (fo called by the Indians) lies between the head of St. Margaret's Bay and the main road from Halifax to Windior ; the great lake of Shubenaccadie lies on the east fide of this road, about 7 miles from it, and 21 from Halifax.

WINDSOR, a county of Vermont, bounded north by Orange, fouth by Windham, east by Connecticut river, and weft by Rutland and part of Addifon co. It contains 22 townships, and 15,748 inhabitants.

WINDSOR, a post-town of Vermont, and capital of the above co. is fituated on the west bank of Connectiout river, \$8 miles north by west of Charletton,

in New Hampfhire, 45 E. by S. of Rutland, 80 miles N. E. of Bennington, and 255 from Philadelphia, The townthip contains 1452 inhabitants. This, with Rutland, is alternately the feat of the State legislature.

WINDSOR, a hilly townfhip of Maffachufetts, in Berkfhire co. 20 miles north-north-weft of Lenox, and 136 weft by north of Bofton. The county road to Northampton paffes through it, alfo the road from Pittsfield to Deerfield. It gives rife to Houfatonick and Weftfield rivers, on which are four faw-mills and two corn-mills. It was incorporated in 1771, and contains 916 inhabitants. In the gore, adjoining Adams and Windfor, are 425 inhabitants.

WINDSOR, a confiderable and very pleafant town of Hartford co. Connecticut, on the weft fide of Connecticut river, about 7 miles northerly of Hartford. Here Windfor Ferry river, formed by the junction of Farmington and Poquabock rivers, empties into the Connecticut firsm the weft. Windfor Ferry river divides the townfhip into the upper and lower parifhes.

WINDSOR, Eafl. See Eaft Windfor. WINDSOR, a township of New-Jerfey, Middletex co. containing 2,838 inhabitants, including 190 flaves.

WINDSOR, a township of Pennfylvania, in York county.

WINDSOR, a post-town and the capital of Bertie co. N. Carolina; fituated on Cushai river, and contains, besides a few houses, a court-house and gaol. It is 23 miles west by south of Edenton, 18 from Plymouth, 97 from Halifax, and 481 from Philadelphia.

WINDWARD Paffage, a name given to a course from the S. E. part of the illand of Jamaica, in the Weft-Indies. and extending for 160 leagues to the N. fitte of Crooked Ifland in the Bahamas. Ships have often failed through this channel from the north part of it to the island of Cuba, or the Gulf of Mexico, notwithitanding the common opinion, on account of the current, which is against it; that they keep the Bahama fhore on board, and that they meet the wind in fummer for the most part of the channel eafterly, which, with a counter current on thore, puthes them eafily through it.

WINDWARD Point, near the eaftern extremity

extremity of the island of St. Christoher's, is the cast point of Sandy Hill Bay ; about a miles to the west-northweft of St. Anthony's Hill Point.

WINEE, or Black River, in St Carolina, rifes in Camden diffrict, and running fouth-easterly through Cheraws into Georgetown diffrict, unites with Pedee river, about 3 miles above Georgetown.

WINHALL, a township of Vermont, in Bennington co. about 25 or 30 miles N. F. of Bennington. It contains 155 inhabitants.

WINNIPISEOGEE, a lake in New-Hampfhire, and the largest collection of water in the State. It is 22 miles in longth from S. E. to N. W. and of very unequal breadth, but no where more than 8 miles. Some very long necks of land project into it; and it contains feveral iflands, large and finall, and on which rattle fnakes are common. It abounds with fifh from 6 to 20 pounds weight. The mountains which furround it, give rife to many freams which flow into it; and between it and the mounsains, are feveral leffer ponds, which communicate with it. Contiguous to this lake are the townships of Moultonborough on the N. W. Tuftonborough and Wolfborough on the N. E. Meredith and Gilmantown on the S. W. and a tract of land, called the Gore, on the S. E. From the S. E. extremity of this Jake, called Merry Meeting Bay, to the north-weft part called Senter Harbour, there is good navigation in the fummer, and generally a good road in the winter; the lake is frozen about 3 months in the year, and many fleighs and teams, from the circumjacent towns, crofs it on the ice. See Aquedochton. Winnipifeogee river conveys the waters of the lake into Pemigewasset river, through its eastern bank at New Chefter,

WINLAND, a country accidentally difcovered by Biron or Biorn, a Norman, in 1001; fuppofed to be a part of the ifland of Newfoundland. It was again vifited, and an intercourse opened between it and Greenland. In 1221, Eric, bishop of Greenland, went to Winland to recover and convert his countrymen, who had degenerated into favages. This prelate never returned to Greenland; nor was any thing more heard of Winland for feveral centuries.

WINLOCK, or Wenlock, a township of Vermont, in Effex county, weft of Minchead.

WINNEBAGO, a lake of the N. W. Territory; weft of Michigan Lake, and fouth-weft of Bay Puan, into which it fends its waters. It is about 15 miles long from east to welt, and 6 wide. It receives a large ftream from the fouth-west called Crocodile river. Fox river enters it from the weft, and by it, through Ouifconfing river, has communication with Miffifippi river, interrupted by a portage of only 3 miles. The centre of the lake lies in lat. about 43. 30. N. and long. 88. 10. W. See Ouifconfing and Fox Rivers.

WINNEBAGOES, an Indian nation inhabiting round the lake of the fame name, who can furnish 2 or 300 warriors. Their town flands on an ifland at the E. end of the lake, of about 50 acres extent, and diffant from Bay Puan 35 miles, according to the course of the river. The town contains about 50 houfes, which are ftrongly built with pallifades. The land adjacent to the lake is very fertile, abounding spontaneoully with grapes, plums, and other fruit. The people raife a great quantity of Indian corn, beans, pumpkims, fquashes, melons, and tobacco. The lake abounds with fifh, and in the autumn or fall, with geefe, ducks, and teal; and are very fat and well flavored by feeding on wild rice, which grows plentifully in these parts. Mr. Carver thinks from the refult of his inquiries of the origin, language, and cuftoms of this people, that they originally refided in fome of the provinces of Mexico, and migrated to this country about a century ago. Their language is different from any other yet discovered; and they converse with other nations in the Chippeway tongue.

WINNIPEG, or Winnepeck, a lake in Upper Canada, north-weft of Lake Superior. It lies between 50. 30. and 54. 32. N. lat. and between 95. 50, and 99. 30. W. long. It is 217 miles long, including Bafkefcoggan or Play-Green Lake, its northern arm; and is 100 miles broad from the Canadian Houfe on the E. fide to Sable river on the weft fide. It receives the waters of a number of fmall lakes in every direction, and exhibits a number of fmall ifles, The lands on its banks are faid, by Car-

٦

twe

rive

mil

ver

ver and other travellers, to be very fertile, producing vaft quantities of wild rice, and the lugar-tree in great plenty. The elimate is confiderably more temperate here than it is upon the Atlantic coaft, 10° farther fouthward.

thip

t of

w.

ike.

tich

15

1 6

om

/er.

and

has

in-

les.

but

See

ion

me 1r-

nd

50

ay

ſe

ut

th

he

2+

5,

le

d

đ

ŝ

r

•

WINNIFEG, Little, a lake which lies woft of the former, and has communisation with Lake Minitoba, on the S. which laft fends the waters of both into Winnipeg Lake, in an E. N. E. courfe. It is 30 miles long and 15 broad. Fort Dauphin is feated on a lake contiguous, on the weft, whofe waters empty into this lake. Dauphin Fort lies in lat. 51. 46. N. and long. 200. 54. W.

WINNIPEG River, runs north-weft into the lake of its name. It is the outlet of the waters of a valt chain of lakes; the chief of which are La Plue and Lake of the Woods. The lat. of the Provition Store, at the bottom of the river, is 50. 33. 12. N.

WINNSBOROUGH, a post-town, and the capital of Fairfield co. S. Carolina; fityated on a branch of Wateree Creek, which empties into the river of that name. Here are about 25 houses, a handsome court-house, a gaol, and a college called Mount Zion college, which is supported by a respectable fociety of gentlemen, and has been long incorporated. The infitution flouristics, and bids fair for usefulness. It is 30 miles north-north-west of Columbia, 130 from Charleston, and 708 from Philadelphia.

WINSLOW, a poft-town of the Diftrict of Maine, Lincoln co. fituated on Kennebeck river; 18 miles north of Harrington. Fort Halifax was built at this place in 1754, on the point of land at the confluence of Sebafticook and Kennebeck rivers. This town is 88 miles N. by E. of Portland, 211 in a like direction from Bofton, and 559 from Philadelphia. It was incorporated in 1771, and contained, in 1790, 779 inhabitants, and in 1797, about 1500.

WINTERHAM, a place in Amelia co. Virginia. Black lead is found here; but no works for its manufacture are established: those who want it go and procure it for themselves.

WINTHROP, a post-town of the District of Maine, Lincoln county, between Androscoggin and Kennebeck rivers, about 10 miles from each; 5 miles easterly of Monmouth; 10 west by fouth of Hallowel, now Harrington court-house, 57 north of Portland, 185 from Boston, and 528 from Philadelphia. The township in which it stands was incorporated in \$777, and coatains 1240 inhabitants.

WOA

WINTHROP'S Eay, on the north coaft of the island of Antigua. Maiden Island, a finall isle fouth fouth-west of Long Island is due east of the fouth-cast point of this Bay.

WINTON, a county of Orangeburg diffrict, S. Carolina.

WINTON, a post-town of North-Carolina, and capital of Hartford co. on the S. E. fide of Chowan river, a few miles below the place where Meherrin and Nottaway join their waters. It has a court-house and gaol, and a few compact house. It is 12 miles from Murfreefborough, 15 from the Bridge on Bennet's Creek, 130 S. S. E. of Peterburg, in Virginia, and 434 from Philadelphia.

WINYAW Bay, on the coaft of S. Carolina, communicates with the ocean 12 miles below Georgetown. See Georgetown, and Pedee river.

605 WISCASSET, a port of entry and post-town of the District of Maine, Lincoln co. on the weft fide of Sheepfcut river, 10 miles S. E. of New-Milford on the E. fide of Kennebeck river. 13 north-weft of Bath, 56 north-weft of Portland, 178 N. E. by N. of Bofton, 525 from Philadelphia, and 1513 from Sunbury in Georgia. It is a part of the township of Pownalborough, and is very flourishing. It contains a congregational church, and about 120 houses. Its navigation is greater in proportion to its fize and number of inhabitants than any part of Maffachufetts. A gazette is published here, and the county courts are held in it. Wifcaffet Point is 3 leagues from Crofs river. The exports for one year, ending the 30th of Sept. 1794, amounted to 23,329 dollars.

WITCHARN Bay, is within the great found in the Bermudas Islands, in the West-Indies; fituated at the E. part of the bottom or fouth part of the Sound, having two small islands at the mouth of it.

WOAHOO, one of the Sandwich Ifles, in the North Pacific Ocean, 7 leagues north-welt of Morotoi Ifland. It is high land, and contains 60,000 inhabitants : tants; and has good anchoring ground, in lat. 21.43. N. and long. 157. 51.W. WOAPANACHKY, the name of the Delaware nation, in their language.

WOBURN, a township of Mallichufetts, in Middlesex co. 10 miles north of Boston. It was incorporated in 1642 by the name of *Wooborne*, and was till then known by the name of *Charles*town Village. It contains 1727 inhabitants.

WOLCOTT, a township of Vermont, in Orleans co. south of Craftsbury, containing 32 inhabitants. La Moille river runs N. westward through it.

WOLF, a fmall boatable river of Tennefice, which runs wefterly into Miffitippi river, about 19 miles fouth of Hatchy river, and 55 from Reelfoot. It is 50 yards wide feveral miles from its mouth, which is very near the fouthweft corner of the State, in lat. 35.

WOLFBOROUGH, a township of New Hampshire, Strafford co. on the E. fide of Winnipifiogee Lake, and contains 447 inhabitants. It contains fome fine farms, and particularly that which farmerly belonged to Governor Wentworth.

WOLVES Islands lie near Campo Bello Island, on the easternmost coalt of the District of Maine. Between these the foundings are from 50 to 100 fathoms. N. lat. 44, 48. W. long. 66. 40. From Grand Mannan Island to Wolves Islands, the courte is N. E. by N. 3 lengues.

WOMELDORF, a post town of Pennfylvania, in Berks co. fituated on the well fide of a finall stream which falls into Tulpehocken Creek. It contains about 40 houses, and a German Lutheran and Calvinist church. It is 68 miles north-west of Philadelphia.

Woaro, one of the Ingraham Iflands, lefs in fize than Chriftiana. The body of it lies in lat. 9. 27. S. It bears north-welt by welt, about 20 leagues from Refolution B^{...}. It was called *Adams*, by Capt. Ingraham; and a finall ifland to the louthward of it he called *Lincola*. Capt. Roberts afterwards diffeovered them, and named them from his fhip and fcooner; the larger *Jefferfon*, and the lefter *Refolution*.

WOODERIDGE, a post town of New-Jerfey, Middlefex co. on the great road from New-York to Philadelphia, on a fream which falls into Arthur Kull,

above Amboy. It is about 3 miles Ns by welt of Amboy, 10 fouth-westerly of Elizabeth-Town, and 70 N. E. of Philadelphin. The township contains 3,5 to inhabitants, including 256 flaves. it is 3

tince]

filh an

nicati

Bourk

towns

a cou

houfe

adjoir

tants.

she c

whic

court

Yor

Kin

weft

1,02

In I

160

eleci

Car

rive

ples N.

co.

this

ed

7th

fan

toy

M

and

25

mi

Ha

N.

fai

gù

na

T an an ar an

1468

Ŀ

Ł

W

W

WOODBRIDGE, a township of Connecticut, New-Haven co. about 7 miles north-west of New-Haven city.

WOODBURY, a township of Vermont, in Caledonia co. 15 or 20 miles west north-west of Barnet.

WOODBURY, a post-town of Newjeriey, and capital of Gloucester co. fituated near a small stream, which emptics into the Delaware below Red Bank. It contains about 80 houses, a handsome brick court-house, a Quaker meetinghouse, and an academy. Several of the houses are neat and handsome. It is 9 miles fouth of Philadelphia, and 11 north-east of Swedesburg. Also, the name of a township of Pennsylvania, in Huntingdon co.

WOODBURY, a township of Connecticut, in Litchfield co. 8 miles fouth of Litchfield. It was settled in 1672.

Wood Creek, a fluggift ftream which rifes in the high lands, a little eaft of Fort Edward, on Hudfon's river; and after running 25 miles, falls into the head of Lake Champlain at Skenefborough. It has a fall at its mouth, otherwife it is navigable for batteaux for 20 miles up to Fort Anne.

WOOD Creek runs westward, and empties into Lake Oneida. See Oneida, Onondago, and Mobawk River.

WOODFORD, a county of Kentucky, on Ohio river, between Kentucky and Licking rivers. Chief town, Verfailles.

WOODFORD, a township of Vermont, east of Bennington, adjoining. It contains 60 inhabitants.

WOOD Island, on the fea-coaft of the Diffrict of Maine, 5 lengues northeaft of Cape Porpoile, and fouth-west by fouth four leagues of Richman's litand.

WOODS, Lake of the, the most northern in the United States, is fo called from the large quantities of wood growing on its banks; fuch as oak, pine, fir, fpruce, &c. This lake lies nearly east of the fouth end of Winnipeg Lake, and is fuppoied to be the fource or conductor of one branch of Bourbon river. Its length from east to welt is faid to be about 70 miles; and in fome places it is 40 miles wide. Other accounts fay. it is 36 leagues in length. The Killif. tinoe Indians encamp on its borders to fifh and hunt. This lake is the communication between the lakes Winnipeg, Bourbon, and Lake Superior.

S N

terh

. of

ains

Ves.

Con-

niles

Ver-

niles

ew.

co.

np.

nk.

ome

ng-

the

18 9

11

the

in

ec.

1 02

ich

of

ind

the

10.

er-

20

nd

la.

nd

S.

۱t,

n-

0(

h.

A

's

١.

d

t --

۰,

ß

d

r

s

e

t

X

WOODSTOCK, one of the principal towns of Windfor co. Vermont. It has a court-house and about so dwellinghoufes. It lies north-weft of Windfor, adjoining, and contains 1,605 inhabitants. Waterquechie river paffes through the centre of the town, on the banks of which ftand the meeting-houfe and court-houfe.

WOODSTOCK, a township of New-York, in Uliter co. bounded eafterly by Kingtton, Hurley and Marbletown, and wefterly by Delaware river. It contains 1,025 inhabitants, including 15 flaves. In 1796, according to the State cenfus, 160 of the inhabitants were qualified electors.

WOODSTOCE, a finall town of N. Carolina, on the E. fide of Pamplico river.

WOODSTOCK, a confiderable and pleafant township of good land, in the N. E. corner of Connecticut, Windham co. divided into 3 parifies. This townthip, which is 7 miles fquare, was granted by the general court of Maffachufetts, 7th Nov. 1683, and was fettled by 39 families from Roxbury in 1688. This town remained under the jurifdiction of Maffachufetts till about the year 1760, nce which time it has been confidered as belonging to Connecticut. It is 66 miles S. W. of Bofton, 45 N. E. of Hartford, 22 S. W. of Worcester, 33 N. W. of Providence, and about the fame diftance N. of Norwich.

WOODSTOCK, a post-town of Virginia, feat of justice and capital in Shenandoah co. It contains between 60 and 70 houfes, a court-houfe and gaol. The inhabitants are mostly Germans and their descendants. It is 12 miles from Strafburg, 49 from Rockingham. court-house, and 222 from Philadelphia.

WOODSTOWN, a polt town of New-Jerfey, Salem co. and contains about 40 or 50 houles. It is 12 miles N. by E. of Salem, 31 north by weft of Bridgetown, and 26 S. S. W. of Philadelphia.

WOODY Point, one of the limits of Hope Bay, on the north west coast of North-America, as Breaker's is the

other. It is in about lat. 50. N. and

long. 128. weft. WOOLWICH, a township of Gloucefter co. New-Jerfey.

WOOLWICH, a township of Lincoln co. District of Maine, on the E. fide o Kennebeck river, S. of Pownalborough, containing 797 inhabitants.

WOONSOKET Falls, on Blueftone river, in Smithfield township, Rhode-Ifland.

WORCESTER, a large and populous county of Maffachufetts. It contains 50 townfhips, 53 Congregational churches 510,236 acres of unimproved land, and 207,430 under cultivation, and 56,807 inhabitants. It is about so miles in length, from north to fouth, and about 40 in breadth ; bounded fouth almost equally by the States of Connecticut and Rhode Ifl.nd, and north by the State of New-Hampshive. On the east it is bounded chiefly by Middlefex co. and welt by Hampfhire co.

WORCESTER, a post-town of Maffachuletts, and capital of the above county. It is the largest inland town of New-England, and is fituated about 45 miles welt of Bolton, 52 north eaft of Springfield, and 299 north-east of Philadelphia. The public buildings in this town are two Congregational churches, a court house, and a ftrong ftone gaol. The inhabitants, upwards of 2,000 in number, have a large inland trade, and manufacture pot and pearl afh, cotton and tinen goods, befides fome other articles. The compact part of the town contains about 1 50 neat houfes, fituated in a healthy vale, principally on one ftreet. Printing, in its various branches, is, carried on very extensively in this town, by Maiah Thomas, Efq. who in the year 1791, printed two editions of the Bible, the one the large royal quarto, the first of that kind published in America ; the other a large folio, with 50 copper plates, befides feveral other books of confequence. His printing apparatus confilts of 10 printing-preffes, with types in proportion; and he is now making preparations for the printing of Bibles of various finaller kinds. His printing apparatus is reckoned the largeft in America. This townfhip, part of what was called Quinfigamond by the Indians, was incorporated in 1684; but being depopulated by Indian hoitilities, the first town-meeting was held

in

in 1722. It is proposed to open a canal between Providence, in Rhode-Island, and this town. N. lat. 42. 23. W. long. 71. 44.

WORCESTER. a township of Pennfylvania, in Montgomery county.

WORCESTER, the fouth-eafternmoft county of Maryland, having Somerfet county and Chefapeak Bay on the weft, Sinepuxent Bay on the caft, which opens to the N. Atlantic Ocean, and Accomac co. in Virginia, on the fouth. It is well watered by Pocomoke, Affatigul, and St. Martin's river. It contains 11,640 inhabitants, including 3,836 flaves. Chief town, Snowhill.

WORCESTER, a township of Vermont, in the easternmost part of Chittendon co. about 25 miles east of Burlington.

WORTHINGTON, a post-town of Massachuietts, in Hampshire co. 19 miles west by north of Northampton, 25 east by south of New Lebanon, in New-York State, 120 westerly of Boston, and 289 from Philadelphia. It was incorporated in 1768, and contains 1116 inhabitants.

WRENTHAM, the Wollomonuppouge of the Indians, a confiderable township of Norfolk co. Maffachufetts, on the poft-road from Boston to Providence, 27 miles Touth fouth-weft of Bofton, and 18 north eaft of Providence, containing 1,767 inhabitants; formerly a part of Dedham, incorporated in 1661. There is a curious cavern in this town, called Wampom's Rock, from an Indian family of that name, who lived in it for a number of years. It is about 9 feet square, and 8 feet high, leffening from the centre to about 4 feet. It is furrounded by broken rocks, and now ferves as a fhelter for cattle and fheep, as do feveral others here, formerly inhabited by Indians.

WRIGHTSBOROUGH, a finall fettlement or village on Little river, a branch of the Savannah, about 30 miles from Augusta. It was fettled by Joseph Mattock, Elq. one of the Friends, who named it after Sir James Wright, then governor of Georgia, who promoted its establishment.

WRIGHTSTOWN, in Buck's county, Pennfylvania, 4 miles north of Newtown, and 4 weft of Delaware river.

WUNALACHTIKOS, a tribe, the fecond in rank, of the Delaware nation. WYACONDA, a river of Louisianity, which falls into the Miffifippi 34 miles below Riviere du Moins.

WYALUSING, a township of Pennfylvania, Luzerne county.

WYALUXING Creek, in Luzerne co. Pennfylvania, falls into the Eaff Branch of Sulquehannah river from the northcaftward, and north-weftward of Mefhoppen Creek, which is 33 miles foutheast of Tioga Point.

WYMOA Road, in the North Pacific Ocean, a place of anchorage at Atoo? Ifland, one of the Sandwich Iflands, in lat 21. 57. north, and long. 159. 47. weft. It is at the fouth-weft finde, and about 6 miles from the weft end of the ifland. The ifland is about 10 leagues long, and 25 leagues north-weft of Woahoo Ifland.

WYONDOTTS, or Wiandats, an Indian nation refiding near Fort Detroit, in the neighbourhood of the Ottawas and Putawatimes, whole hunting grounds' are about Lake Erie. The number of warriors, 20 years ago, were, Wyondotts 250, Ottawas 400, Putawatimes 150. Another tribe of the Wyondotts live near Sandusky, among the Mohickons and Caghnawagas, who together have 300 warriors. At the treaty of Greenville, in confequence of lands ceded to the United States, the latter agreed to pay them a fum in hand, and in goods to the value of 1000 dollars a year for ever.

WYNTON, the chief town of Hertford county, Edenton district, North-Carolina.

WYOMING, a general name formerly given to a tract of country in Pennfylvania, fituated on Sufquehannah river, above Wilksbarre. In the year 1778, the fettlement which was known under this name, confifted of 8 townships, each containing 5 miles fquare, fettled from Connecticut, and originally under its jurifdiction, and produced great quantities of grain of all forts, fruit, hemp, flax, &c. inhabited by about 1000 families, who had furnished the continental army with near 1000 foldiers, befides various fupplies of provisions, &c. In the month of July, all these flourishing fettlements were reduced by the Indians and tories to a ftate of defolation and horror, almost beyond defcription. See Westmoreland. In the vicinity of Wyoming is a bed of coaly

of the c very in about 81 mil lat. 41 WY lies wi charte the bo end of line w W to be in bre way, Caroli includ are le Great line from walhe 100. publi under not i empl to ad their fome tract Chie houf mon mile the mer and offic

Х

one

Ind

Pin

Ыa

COV

nia

Ga

Th

18

14

Ha

wh

3

ouifiana; 34 miles

of Penn+

f Branch f Branch ie northof Mefes fouth-

h Pacific it Atooi ands, in 159.47. ide, and d of the leagues weft of an In-Detroit. Ottawas grounds mber of. 'ondotts 18 1 50. tts live hickons er have Greeneded to reed to n goods year for f Hert-North- . former-Pennh river, 1778, n under nchips, fettled ly und great fruit. about ed the oldiers, visions, 1 thefe ced by f defond de-In the f coaly

of

XAI

of the open burning kind, which gives a very intenfe heat. Wyoming Falls lie about 2 miles above Wilkefbarre, and 8½ miles above Nantikoke Falls. N.

lat. 41. 14. W. long. 75. 53. WYONOKE Creek, in N. Carolina, lies within or about lat. 36. 30. N. The charter of Carolina, in 1664, extended the bounds eaftward as far as the north end of Currituck Inlet, upon a ftraight line wefterly to this creek.

WYTHE, a county of Virginia, faid to be 120 miles in length, and nearly 50 in breadth; bounded north by Kanhaway, and fouth by the State of North-Carolina. Its population in 1790 was included in Montgomery county. There are lead mines in this county, on the Great Kanhaway, 25 miles from the line of North Carolina, which yield from 50 to 80lbs. pure lead from 100lbs. washed ore, but most commonly 60 to 100. Two of them are worked by the public; the beft of which is 100 yards under the hill; and although there are not more than 30 labourers generally employed, they might employ 50 or 60 to advantage. The labourers cultivate their own corn. Twenty, 25, and fometimes 60 tons of lead have been extracted from these mines in a year. Chief town, Evansham. The courthouse is on the post-road from Richmond to Danville, in Kentucky, 301 miles from the former, and 323 from the latter. It is 46 miles from Montgomery court-house, 57 from Abingdon, and 4.54 from Philadelphia. A postoffice is kept here.

х

AGUA, harbour on the S. E. coaft of the island of Cuba, and one of the finest ports in the West-Indies. It lies between the Islands of Pines, or Pinez, and Spirito Santo.

XAINTES, SANTOS, or All Saints Islands, fo named from their being difcovered on that Holy day, by the Spaniards, on the S. E. fide of the ifland of Gaudaloupe, and in its jurifdiction. The most westerly of these three isles is called Terre de Bas, or the Low Mand, and the most easterly Terre de Haut, or the High Island. The third, which lies exactly in the middle between the other two, is little other than a barren rock, and helps to form a very good harbour.

XALISCO, a province of New-Spain, and the most foutherly on the coast of Guadalajara audience. It is bounded S. and W. by the South Sea; eaft by Guadalajara Proper, and Mechoacan, and divided from Chiametlan, on the N. by a narrow flip of land belonging to Guadalajara, extending into the fea. It is not above 150 miles in extent either way. It has filver mines, and abounds with Indian wheat, but has few cattle. The oil of the Infernal Fig-tree, as the Spaniards call it, is brought from this province. It is faid to be efficacious in diffolving tumors, expelling of wind, and all cold humours, by anointing the belly, and taking a few drops of it in a glafs of wine, as also by clyfters. It is alfo faid to cure ulcers in the head, and deafness. The Indians are numerous here, and are reckoned braver and more polite than their neighbouring countrymen. The Xalifco, an ancient city, is the capital, yet the most confiderable place in it is Compostella,

XARAYES, Laguna de los, a large lake of Paraguay, in S. America, formed by the river Paraguay, in its course from north to fouth.

XERES de la Frontera, a town in the fouthernmost part of Zacatecas, a province of Guadalajara audience, in New Spain, in N. America. It is garrifoned for defending the mines against the hostile Indians.

Y

X ABAQUE, one of the Lucayos or Bahama Iflands, fituated fouth weft of Meguana Ifland. N. lat. 22. 30.

YADKIN, a confiderable river of N. Carolina, which rifes in the Alleghany Mountains, running E. about 60 miles, then turning to the S. S. E. paffes the Narrows, a few miles above Rocky river; thence directing its courfe through Montgomery and Aufon counties, enters South Carolina. It is about 400 yards broad where it paffes Salifbury, but it is reduced between 2 hills, about 25 miles to the fouthward of that town, to the width of 80 or 100 feet. For 3 miles it is narrow and rapid, but the moff Q q narrow

n na stalle

narrow and most rapid part is not above half a mile in length. In this narrow part, fhad are caught in the fpring of the year, by hoop nets, in the eddies, as fast as the strongest men are able to throw them out. Perhaps there is not in the United States a more eligible fituation for a large manufacturing town. Boats with 40 or 50 hogheads pais eafily from these Rapids to Georgetown. The late war, by which North-Carolina was greatly convulled, put a flop to feveral iron-works. At prefent there are 4 or 5 furnaces in the State that are in blaft, and a proportionable number of forges. There is one in Guilford co. one in Surry, and one in Wilkes, all on the Yadkin. From the mouth of Rocky river to the ocean, the ftream affumes the name of Great Pedee.

YAG

YAGARCHOCA, a lake of Quito, within the limits of the juridiction of San Miguel de Ibarra. It is famous for having been the fepulehre of the inhabitants of Otabalo, when taken by Huayna Capac, the rath Inca; who, inftead of rewarding their magnanimity with clemency, was irritated at the noble refiftance which they made againft his army, ordered them all to be beheaded, and their bodies to be thrown into the lake; hence its name, which fignifies a lake of blood.

YAGO, St. or St. James, an ancient town on the north fide of St. Domingo Island, founded before 1504, and the country round is reckoned as healthy as any in the island. It is fituated on the high road from La Vega to Daxavon; To leagues welt by north of the former, and 28 easterly of the latter, and about 10 from the anchoring-place of St. Yague, and nearly as far from Port de Plate. It ftands on the northern fide of the river Yaqui, in a favannah commanding the river. The town is open, and regularly laid out, and contains above 600 houfes. It is 52 leagues N. N. W. of St. Domingo city, 34 weft by north of the bottom of Samana Bay, and 22 N. W. of Cotuy. The territory of St. Yago, or Jago, contains 28,000 fouls, and is very fertile in mines. The fand of Green and Yaqui rivers is mixed with gold. Mercury is found at the head of the latter river, and copper is alfo found in this territory. The tree, guatapana, which retains its Indian name, is found here. It bears a fort of YAR

grain of pod, from which is extracted a very fine black dye.

of th

er th

fame

upon

tions

arch

Teri

whic

its m

weft

Auen

the N

100

Gau

Purc

Terr

mile

mile

river

in T

from

with

prod

41 1

and

is a

larg

pital

is it

of th

of S

Y

Y

conv

in 1

nam

the

bite

of

You

nort

the

fron

150

mac

pids

the

adm

to 1

Gre

agai

and

The

Y

Y

Y

Y

v

Y

YAGUACHE, a litutenancy of Guayaquil jurifdiction, in South-America. It lies at the mouth of the river of the fame name, which empties into that of Guayaquil on the fouth fide, and has its fource from the fkirts of the Cordilleras, fouth of the river Bamba. Within its jurifdiction are 3 towns; the chief of which is that where the cuffom-houfe is erected, and called San Jacint de Yaguache; the two others are Nauía and Antonche. It produces wood, cocoa, cattle, and cotten.

YALE College. See New Haven.

YAMACRAW, the ancient Indian name of the fpot where Savannah, in Georgia, is erected.—Alfo the name of a tribe of the Creek Indians.

YAQUE, Port St. vulgarly called Old Port, a fmall anchoring-place on the N. fide of the island of St. Domingo; fituated between Padrepin on the weft, and Macoris Point on the E.

YAQUI, Grand, or Monte Chrift River, a river of the north part of the illand of St. Domingo, which runs a W. N. W. courfe, and empties into the Bay of Monte Chrift. It might be afcended in cances or fmall boats, for 15 leagues, were it not for the limbs of trees which lodge in it. All its numerous branches are from the fouthward. See Monte Chrift.

'YARDSLEY'S *Forry*, on Delaware river, is 3 miles north-wefterly of Trenton, in New-Jerfey, and five below M'Crankey's Ferry.

YARI, a town in Amazonia, South-America, at the head of a branch of Amazon river, fouth wefterly from Macapa.

YARMOUTH, a post-town of Massachusetts, Barnstable co. on the neck of the penintula of Cape-Cod, 5 miles E. of Barnstable, 12 E. by S. of Sandwich, 110 fouth-weft of Boston, and 427 from Philadelphia. The harbour is described in the account of Barnstable; which fee. The township extends from fea to fea. It was incorporated in 1639, and contains 2,678 inhabitants.

YARMOUTH, a township of Nova-Scotia, in Queen's co. fettled by New Englanders. It lies at the head of a short bay, 8 miles south-east of Cape St. Mary.

YARUQUI, a plain 4 leagues N. E.

610

ted a

laya-

E. It

f the

at of

is its

eras,

n its

ef of

loufe

t de

1 and

icoa,

dian

ı, in

ie of

Old

the

go ;

veft,

brift

the

w.

the

af-

15

s of

ier-

urd.

are

en-

low

th-

1a-

ffa-

of

E.

oh,

DIM

red

te.

ea.

m-

1a -

ew

a

pe

E.

of

ot

12.

of the city of Quito, and 249 toifes lower than it. Near it is a village of the fame name. This fpot was pitched upon as the bafe of the whole operations for measuring the length of an arch of the meridian, by Ulloa.

YAZOO River, in Georgia Weftern Territory, confifts of 3 large branches which run a fouthern courfe, and near its mouth thefe unite and purfue a fouthweft courfe a few miles, and the confluent ftream enters the eaftern bank of the Miffifippi, by a mouth upwards of 100 yards wide; according to Mr. Gauld, in lat. 32. 37. N. and by Mr. Purcel, in 32. 38. See Georgia Weftern Territory.

YAZOO Cliffs, or Aux Cotes, lie 71 miles from the river Yazoo, and 391 miles from Loufa Chitto, or Big Black river.

YBAGUE, a city of New-Granada, in Terra Firma South-America.

YCA, or Valverde, or the Green Vale, from a valley of the fame name planted with vines, which is 6 leagues long, and produces plenty of wine. It is about 41 miles fouth-eaft of Pifco, in Peru, and is inhabited by 300 Spaniards. It is a beautiful and rich town, having a large church, 3 convents, and an hofpital. About 6 leagues from the town is its port, called Puerto Quemada.

YCAQUE, or *Icaco*, the northern point of the bay of Mancenilla, in the island of St. Domingo.

YELLOW Mountain. See Tenneffee.

YLO, a port of Peru, in Los Charcos convenient for loading and unloading, in lat. 18. S. The town of the fame name, lies about a quarter of a league to the windward of the river, and is inhabited by Indians. Frezier calls it *Hilo*.

YOHOGANY, the principal branch of Monongahela river, called alfo Youghiogeny, and Toxhiogeni, purfues a north-wefterly course, and paffes through the Laurel Mountain, about 30 miles from its mouth; is, fo far, from 300 to 1 so yards wide, and the navigation much obstructed in dry weather by rapids and thoals. In its paffage through the mountain it makes very great falls, admitting no navigation for 10 miles, to the Turkey-foot. Thence to the Great Croffing, about 20 miles, it is again navigable except in dry feafons, and at this place is 200 yards wide. The fources of this river are divided from those of the Patowmack, by the Alleghany Mountain. From the falls, where it interfects the Laurel Mountain, to Fort Cumberland, the head of the navigation to the Patowmack, is 40 miles of very mountainous road. The country on this river is uneven, but in the vallies the foil is extremely rich. Near to Pittíburg the country is well peopled, and there, as well as in Redftone, all the conforts of life are in the greateft abundance. This whole country abounds with coal, which lies almost on the furface of the ground.

YONKERS, a township of New-York, in West Chester co. bounded easterly by Bronx river, and westerly by the county of York and Hudson's river. It contains 1125 inhabitants, of whom 139 are electors, and 170 flaves.

YONKERS, a post-town of New-York, 114 miles from Philadelphia.

YOUNG FREDERICK's Island, on the N. W. coaft of N. America, divides Port Ingraham. See Port Ingraham.

YORK, a river of Virginia, which takes its rife near the Blue Ridge, and empties into the Chefapeak, a little to the S. of Mobjack Bay. At York . Town it affords the beft harbour in the State, which will admit veffels of the largest fize. The river there narrows to the width of a mile, and is contained within very high banks, clofe under which the vefiels may ride. It has 4 fathoms water at high tide, for 20 miles above York, to the mouth of Poropotank, where the river is a mile and a half wide, and the channel only 75 fathoms, pafsing under a very high bank. At the confluence of Pamunky and Mattapony it has but 3 fathoms depth, which continues up Pamunky to Cumberland, where the width is 100 yards, and up Mattapony to within 2 miles of Frazer's Ferry, where it becomes 281 fathoms deep, and holds that about 5 miles.

YORK, a river of York co. Diffrict of Maine, which runs up 7 or 8 miles, and affords a tolerable harbour for veffels under 200 tons. The rocks, however, render it fomewhat difficult and hazardous for ftrangers.

YORK, a maritime and populous co. of the Diftrict of Maine, bounded eaft and north-eaft by Cumberland, fouth by the ocean, weft by New-Hampfhire, from which it is feparated by Salmon Fall river, and north by Canada, It is Q q a well well watered by Saco, Mouforn, and other fireams, and is divided into 27 townships, and contains 28,821 inhabitants. Chief town, York.

612

YORK, a post-town of the District of Maine, in York co. 9 miles north-east of Portfmouth, in New-Hamphire, 20 fouth of Wells, 48 fouth by welt of Portland, 75 from Bofton, and 421 from Philadelphia. N. lat. 43. 16. It is a port of entry and capital of the county. The river of its name empties into York harbour at the town. It is navigable for veffels of 250 tons. About a mile from the lea is a wooden bridge acrols the river, 270 feet in length, which was erected in 1761. Before the war, 25 or go veffels were employed in the Weft-India trade, and coafting business, but their veffels were taken or deltroyed, and little marine bufinefs is now done, except that a fmall fifthery is supported. This township was settled in 1630, and called Agamenticus, from the hill of that name which is a noted land-mark for mariners. In 1640, Sir Ferdinand Gorges incorporated a great part of it by the name of Georgiana. In the year r692, the Indians took the town by furprife, and burnt most of the houses, and 150 perfons were killed or captivated. It contained, according to the cenfus of 1790, 2900 perfons. Fish of various kinds frequent the rivers and fhores of the fea contiguous. In a calm feafon, in the fummer, one may fland on the rocks of the fhore, and catch them in the fea, with a line, or even with an angling rod, and a fathom or two of line. YORK, a county of Pennfylwania, bounded east and north-east by Sufquehannah river, which feparates it from Lancafter and Dauphine counties, and fouth by the State of Maryland, It contains 19 townships, and 37,747 inhabitants.

YORK, a poft-town and capital of the above county, fituated on the eaft fide of Codorus Creek, which empties into the Suiquebannab. It contains about 500 houles, fiveral of which are of brick. The town is regularly laid out: the public buildings are a court-houfe, a flone gaol, a record-office, handfomeby built, an academy, a German Lutheran, a German Calvinift, a Prefbyterian, Roman Catholic, and Moravian church, and a Quaker meeting-houfe. It is 22 miles W. S. W. of Lancaffer, 51 N.

W: by N. of Hartford, in Manyland, 199 N.E. of Staunton, in Virginia, and 88 weft of Philadelphia.

and I

N. lat.

broad,

fore th

ed by

fon's 1

ifland

the p

the o

tween

are fc

up to

the p

into t

miles

tion

in al

hould

N.a

of H

Nelf

Seve

long Y

fora

Iflar

iflan

50.

of]

are

of t

trić

Yo

lea

-ifla

E.

55

Ma

fro

w

Y

er

no

, CO

40

St

h

tł

٦

Y

Y

Y

Yo

YORK, a county of South-Carolina, in Pinckney diffrict; bounded eaft by Catawba, river, N. by the State of N. Carolina; fouth by Cliefter co. and weft by Broad river, which divides it from Spartanburg, and is one of the moft agreeable and healthy counties in the State, and well watered by Catawba and Broad rivers, and their tributaries. It contains 6604 inhabitants, of whom 5632 are whites, and 923 flaves. Here are extensive iron-works. This county fends 3 reprefentatives and one fenator to the State legiflature.

YORK, a county of Virginia, bounded north by York river, which divides it from Gloucetter co. fouth by Warwick; eaft by Elizabeth City co. and weft by that of James City. It contains 5233 inhabitants, of whom 2760 are flaves.

YORK, or Yorktown, a port of entry and post-town of Virginia, and capital of York co. It is agreeably fituated on the fouth fide of York river, where the river is fuddenly contracted to a narrow compais, opposite to Gloucester, and a mile diftant, where there is a fort fronting that on the York fide, about 1r miles welt by fouth of Toes Point, at the mouth of the river. The banks of the river are very high, and veffels of the greatest burden may ride close under them with the greatest fafety. It contains about 60 or 70 houfes, a gaol, an Episcopal church, and a tobacco ware-houfe. In 1790, it contained 661 inhabitants, of whom 372 were flaves, Its exports, in the year 1794, amounted to feventy-one thousand five hundred and feventy-eight dollars. It will ever be famous in the American annals for the capture of Lord Cornwallis and his army, by the combined force of the United States and France, which took place on the 19th of October, 1781. It is 12 miles ealt by fouth of Williamfburgh, 21 N. W. of Hampton, 72. E. S. E. of Richmond, and 350 fouthfouth weft of Philadelphia. N. lat. 37. 22. 30. W. long. 76. 52.

YORK, a town of Upper Canada, fituated on the north weitern fide of Lake Ontario, and is defigned to be the future feat of government of that province, The public buildings are erecting. It is 40 miles N. by W. of Niagara Fort, and and 120 welt-fouth-welt of Kingston. N. lat. 43. 57. W. long. 80. 35.

YORK Bay is 9 miles long, and 4 broad, and spreads to the fouthward before the city of New-York. It is formed by the confluence of East and Hudfon's rivers, and embofoms feveral fmall iflands, of which Governor's Ifland is the principal. It communicates with the ocean through the Narroius, between Staten and Long Iflands, which are fearcely 2 miles wide. The paffage up to New-York, from Sandy Hook, the point of land that extends furtheft into the fea, is fafe, and not above 20 miles in length. The common navigation is between the east and weft banks, in about 22 feet water. The light-"house at Sandy Hook is in lat. 40. 20. N. and long. 74. 2. W.

YORK Fort, on the fouth-west shore of Hudion's Bay, at the mouth of Port Nelson river, is 160 miles westerly of Severn House. N. lat. 57. 1. 51. W. long. 92. 46. 40.

YORK Harbour lies within the elbow formed by South Head, in the Bay of Islands, Newfoundland Island.

York Island, one of the Gallipago islands, on the coast of Peru.

YORK Ifle, or Iflands, lie in S. lat. 50. 37. about 50 leagues from the coaft of Patagonia, in South America, and are inhabited. Trinity Ifle lies due E. of them, near the main land.

YORK Ledge, on the coaft of the Diftrict of Maine. From York Harbour to York Ledge, the course is S. E. two leagues.

YORK Minfler, on the 8. coast of the island Terra del Fuego, is 19 leagues at E. S. E. from Gilbert Island. S. lat. 55. 26. W. long. 70. 25.

YORK Road, or Bay, in the Straits of Magellan, in S. America, is 10 miles from Cape Crofs Tide. S. lat. 53. 39. W. long. 73. 52.

YORKTOWN, a township of New York, West-Chester co. bounded westerly by the town of Cortland, and northerly by Dutchess co. In 1790, it contained 1609 inhabitants, including 40 flaves. In 1796, according to the State confus, there were 210 of the inhabitants electors.

YOUGHIOGENY. See Yobogany.

YUCATEN, one of the 7 provinces of the audience of Mexico, in New Spain. The British had a right to cut logwood

and carry it away, by the treaty of 1783, in the tract between Rio Honde and Ballize rivers.

YUMA, Bay of. See Higuey. YUMA, a river of the illand of St. Domingo, which runs an E. S. E. and E. courfe, and empties into the W. end of the Bay of Samana. It rifes pear. Monte Chrift river. It is navigable no farther than Cotuy, 13 leagues from its mouth.

Ζ.

ZACATECAS, a province of New-Spain, bounded by New Bifcay on the N. by Panuco on the E. Mechoacan, Guadalajara, and Chiametlan, on the S. and by part of Chiametlan and Culiacan on the W. It is well inhabited, and abounds with large villages. The mines here are reckoned the richeft in America.

ZACATECAS, the capital of the above province, fituated under the tropic of Cancer, 40 leagues N. of Guadalajara, and 80 N. W. of Mexico. Its garrifon confifts of about 1000 men, and there are about 800 families of flaves, who work in the mines and other laborious work, N. lat. 23. 29. W. long. 103. 20.

ZACALLAN, a town of Mexico. See Angelos.

ZACATULA, a fmall feaport-town of the province of Mechacan, fituated at the mouth of the river of the fame name, on the coaft of the Pacific Ocean. N. lat. 17. 22. W. long. 104. 58.

ZACHEO, or Defectio, a finall island, 8 or 9 leagues to the N. E. by N. of Mona, between the island of St. Domingo, and that of Porto Rico. It is nothing more than a green mountain, 800 or 1000 yards long.

ZAMORA, a city of Peru, in South-America, 200 miles fouth of Quito, which is pretty large, and the houfes well built of timber and flone. The church and convent of Dominicans, are both elegant thructures. There are leveral gold mines in the neighbourhood of the city, but few of them are worked. S. lat. 4. 10. W. long. 77. 5.

ZAPOTECHAS, a river of New-Spain which runs north-eaftward into the gulf Q g 3 of

and lina, t by f N. weft from molt 1 the 1 and े It hom Here unty nator nded es it ick ; t by 5233 wes. ntry pital d on t the rrow nd a ont-LIE t, at cs of ls of un-It raol, acco 661 ives. nted dred ever s for 1 his the took 781. amf-. E. uth-37 -, fi-Lake fuince. lt

ort,

and

land,

ZIT

614

of Mexico. A fort of the fame name ftands on the N. W. bank of the river, about 250 miles S. E. from the city of Mexico.

ZELITO, or Ziltio, one of the forts for the protection of the harbour of Carthagena, on the N. coaft of South-America.

ZINOCHSAA, the original name of a river of New-York, which runs through Onondago, the chief town of the Six Nations.

ZITAR, a town of Terra Firma,

er ar gu à ca Lite - contrator set à - co Millator - co - à - c

Warris.

653

.U. A. A

Aberna Line

Sec. A

Better in an .

to.

518 .

. S.A. 5.

203

1.8%

THE.

¥4.7

1. 16

rich ? w

12.

ZUY

South-America, near to and fouth from the head of the gulf of Darien.

ZOAR, a plantation of Berkfluire co. Maffachufetts, containing 78 inhabitants.

ZONCOLCUCAN, mountains in Guaxaca, in New-Spain, which give rife to Papalo-apain, or Alvarad river.

ZONESHIO, the chief town of the Seneca Indians, 2 miles N. of Seneca Lake.

ZUYDT River, a name in Dutch maps given to Delaware river.

[By F

A^B Abin Acco

Alba Alex Aller

Amb

Amb

Ann

Anfc

Ave

BAL Bair Barr

Batl

Bat

Bea

Bed

Bell

Bel Ben Ben Ber Ber

Bet

TABLE

TABLE OF POST-OFFICES

1 615]

M. OF TRUE

Sections

m

:0.

Di-

to

he

ch

t

IN

THE UNITED STATES,

WITH

The DISTANCE from the Post-Office at PHILADELPHIA to every other Post-Office here mentioned.

[By permission of the Author, the following useful Table and Observations are annexed.]

, A	Miles.		Miles.	
A BBEVILLE court-house, S. C.	. 782	Bethlehem, P.	58	
Abbotftown, P.	103	Beverly, Ms.	367	
Abingdon, Va.	511	Biddeford, Me.	451	
Accomac court-house, Va.	199	Blackhorfe, Md.	IOI	
Albany, N. Y.	265	Bladenfburg, Md.	140	
Alexandria, Va.	156	Bluehill, Me.	623	
Allen's Fresh, Md.	203	Booneton, N.J.	116	
Amboy, N. J.	74	BOSTON, Ms.	347	
Amherft, N. H.	384	Bourbontown, K.	749	
Andover, Ms.	372		230	
Annapolis, Md.	1 32	Brattleborough, Vt.	311	
Anfon court houfe, N. C.	583	Brewers, Me.	745	
Avery fborough, N. C.	482	Bridgehampton, N. Y.	196	
Augusta, G.	763	Bridgetown Eaft, N. J.	74	
		Bridgetown Welt, N. J.	57	
BALTIMORE, Md.	\$02	Briftol, R. I.	306	
Bairdítown, K.	875	Briftol, P.	20	
Barnstable, Ms.	423	Brookfield, Ms.	278	
Bath, Me.	512	Brookhaven, N. Y.	161	
Bath, N. Y.	248	Brownfville, P.	345	
Bath, c. h. Va.	337	Brunfwick, Me.	500	
Beaufort, S. C.	\$36	Brunswick (New) N. J.	60	
Bedford, P.	204	Burlington, Vt.	429	
Belfaft, Me.	590	Butternutts, N. Y.	375	
Bel Air, Md.	86			
Benedict, Md.	191	Cabbin Point, Va.	329	
Bennington, Vt.	302	Cabelliburg, Va.	3 52	
Bermuda Hundred, Va,	302	Cambridge, S. C.	762	
Berwick, Me.	432	Camden, Me.	571	
Bethania, N. C.	538	Camden, S. C.	643	
	7.	Qq 4	Cangan	

	Cin.		17 2 (
	and the	N. W.	1	· ·
	. 1 6	16 1		
	Miles.		Miles.	Halifax,
Canaan, Me.	577	Drefden, Me.	540	Halifax c
Canaan, C.	257	Douty's Falls, Me.	439	Hallowell
Cantwell's Bridge, D.	52		and the second	Hallowel
Carlifle, P.	325	Eaft-Greenwich, R. I.	306	Hamburg
Carterfville, Va. Centreville, Md.	323	Eafton, P.	70	Hamptor
Centre Harbour, N. H.	98 486	Eafton, Md. Edenton, N. C.	118	Hancock
Catfkill, N. Y.	233	A DATE OF THE OWNER	446	Hanover
Caftine, Me.		Edgefield c. h. S. C.	738	Hanover
Chamberfburg, P.	157		859	Hanover
Chandler's River, Me.	697		80	Hanover
Chapel Hill, N. C.	472	Elizabeth-Town, N. C.	547	Harford
Chaptico, Md.	215	Elkton, Md.	49	Harpers
Charleftown, N. H.	341	Ephrata, P.	74	Harrifbu
Charlestown, Md.	18, 59	Exeter, N. H.	402	Harris's
CHARLESTON, S. C.	763	Palafald Mr.	Telle in	Harrodi
Charlotte c. h. Va. Charlotte, c. h. N. C.	379	Fairfield, Me.	563	HARTF
Charlottefville, Va.	617	Fairfield, C. Falmouth, Ms.	161 429	Haverhi
Chatham c. h. N. C.	3°3 584	Falmouth, Va.	429	Haverh
Chenango, N. Y.	375	Fayetteville, N. C.	507	Havre-
Cheraw c, h. S. C.	591	Fincastle, Va.	358	Hertfor Hicks's
Cherry Valley, N. Y.	336	Fifhkill, N. Y.	165	Hillfbo
Chefter, N. H.	396		53	Hingha
Chefter, P.	15	FRANFORT, K.	790	Hogtov
Chefter c. h. S. C.	736	Franklin c. h. G.	834	Holmes
Cheffer-Town, Md,	81	Frederica, D.	88	Hornto
Christiana, D.	37	Frederickfburg, Va.	208	Hudfor
Cincinnati, N. T. Claverack, N. Y.	779	Fredericktown, Md.	148	Huntin
Clemont, N. Y.	231	Freeport, Me.	493	Huntfy
Clowes, D.	108	Gallipolis, N. T.	559	to Bee
Colchefter, Va.	172	Geneva, N.Y.	457	Indian Iplwic
Columbia, Me.	688	Georgetown, C. R. Md	65	Iredell
Columbia, Va.	328	Georgetown, Ptk. Md.	148	Treach
Columbia, S. C.	678	Georgetown, S. C.	681	Johnfe
Conajohary, N. Y.	318	Georgetown, G.	873	Johnft
Concord, N. H.	420	Germanton, N. C.	528	Joneth
Concord, Ms.	368	Gettifburg, P.	119	
Cooperftown, N.ºY. Coolawatchy, S. C.	348	Gloucester, Ms. Gloucester c. h. Va.	384	Kanar
Culpepper, Va.	833	Goldfon's, Va.	328	Keen
Cumberland, Mid.	253	Goochland c. h. Va.	355 308	Killir
Cumberland c. h. Va.	330	Goldíborough, Me.	657	Kind
8 h	550	Gofhen, N. Y.	146	King Kinfa
Dagfborough, D.	\$27	Gray, Me.	489	Kiniz
Danbury, C.	171	Greene, Me.	514	KNO
Danville, K.	830	Greenfield, Ms.	391	and the second
Dedham, Ms.	321	Greenbrier c. h. Va.	410	Lanc
Dighton, Ms.	314	Greensborough, G.	841	Lanc
Dover, N. H.	426	Greensburg, P. Greensville, T.	273	Lanc
Dover, D. Downington, P.	76	Greenville, N. C.	577	Lanfi
Duck Creek, D.	33	Greenville c. h. S. C.	445 781	Laur
Duck Trap, Me.	578	Guilford, C.	201	Layt
Dumfries, Va.	182			Leba
Duplin c. h. N. C.	566	Hacketstown, N. J.	130	Leef
Durham, N. H.	426	Hagerstown, Md.	149	treer
		-	Halifax,	

.

Halifax, N. C. Halifax c. h. Va. Hallowell c. h. Me. Hallowell Hook, Me. Hamburg, N. J. Hampton, Va. Hancock, Md. Hanover, N. H. Hanover, Ms. Hanover, P. Hanover c. h. Va. Hanover-Town, Va. Harford, Md. Harpersfield, N. Y. Harrifburg, P. Harris's, Va. Harrodiburg, K. HARTFORD, C. Haverhill, N. H. Haverhill, Ms. Havre-de Grace, Md. Hertford, N. C. Hicks's Ford, Va. Hillfborough, N. C. Hingham, Ms. Hogtown, N. C. Holmes's Hole, Ms. Horntown, Va Hudson, N. Y. Huntington, Md. Huntsville, N. C. Indian-Town, N. C. Ipfwich, Ms. Iredell c. h. N. C. Johnsonsburg, N. J. Johnston, N.Y. Jonefborough, T. Kanandaigua, N. Y. Keene, N. H. Killingworth, C. Kinderhook, N. Y. Kingston, (Esopus) N. Y. Kinfale, Va. Kingfton, N. C. KNOXVILLE, T. Lancaster, Ms. Lancaster, P. Lancaster c. h. Va. Lanfingburg, N.Y. Laurens c. h. S. C.

Laytons, Va.

Lebanon, P.

Leefburg, Va.

Leefburg, N. C.

[617] Miles. Miles.

 Miles.
 384
 Leominfler, Ms.
 390

 414
 Leonard-Town, Md.
 227

 539
 Lewifburg, P.
 138

 542
 Lexington, Va.
 322

 121
 Léxington, K.
 769

 371
 Liberty, Va.
 393

 179
 Lincolnton, N. C.
 653

 377
 Litchfield, C.
 207

 375
 Little German Flats, N. Y.
 348

 106
 Londonderry, N. H.
 403

 255
 Louifburg, N. C.
 415

 300
 Louifburg, N. C.
 415

 300
 Louifville, K.
 913

 77
 LoUISVILLE, G.
 825

 289
 Lumberton, N. C.
 539

 107
 Lower Marlboro', Md.
 162

 336
 Lynchburgh, Va.
 38x

 820
 Lynn, Ms.
 36x

384 Leominster, Ms. 399 820 362 Lynn, Ms. Machias, Me. 705 Manchefter, Vt. 324 Marblehead, Ms. 372 MARIETTA, N. T. 455 Martinfburg, Va. 165 Martinforough, N. H. 350 Martiníville, Va. 478 Martiníville, N. C. 504 Mecklenburg, Va. 395 Mendon, Ms. 222 412 382 65 458 356 456 369 419 395 295 392 208 438 174 Middlebury, Vt. 227 Middletown, C. 171 49 Middletown, D. 553 93 173 95 34 514 64 758 Middletown Point, Milford, C. 492 Milford, D. 377 Millerftown, P. 592 Monmouth, Me 98 Monmouth c. h. N. J. Montgomery c. h. Md. Montgomery c. h. Va. 397 408 551 607 Montgomery c. h. N. C. 547 Moore c. h. N. C. 473 Moorefields, Va. 344 Morgantown, Va. Morganton, N. C. Morriftown, N. J. 03 661 210 244 108 192 Morrifville, P. 29 305 Mount Tizrah, N. C. 480 522 Mount Tizrah, N. C. Murfreesborough, N. C. 422 652 388 Nantucket, Ms. 385 Narraguagus, Me. 673 66 335 Nafh, c. h. N. C. 443 1015 274 Nashville, T. 755 Newark, N. J. 86 New-Bedford, Ms. 322 245 SOR Newburn, N. C. 82 Newburg, N. Y. 170 17.3 510 Newbury, Vt. 417 New

19 60806890794

2

3

ţ

9

7

8

28.

a.

	1 6	r8 .]	1.194
	Miles.		Miles
New-Brunfwick, N. J.	60	Pittfylvania c. h. Va.	448
Newbury c. h. S. C.	723	Pittifion, Me.	547
Newbury-Port, Ms.	389	Pittiton, N. J.	58
Newcaftle, Me.	535	Plumítead, P.	36
Newcastle, D.	33	Plymouth, N. H.	445
New-Germantown, N. J.	73	Plymouth, Ms.	393
New-Gloucefter, Me.	499	Plymouth, N. C.	463
New-Hartford, C.	242	Pomfret, C.	264
NEW-HAVEN, C.	183	PORTLAND, Me.	469
New-Kent c. h. Va.	308	Port-Royal, Va.	230
New Lebanon, N. Y.	293	PORTSMOUTH, N. H.	411
New London, C.	237	Portimouth, Va.	390
New-London, Va.	393	Port Tobacco, Md.	194
New-market, Va.	242	Pottigrove, P.	37
New-Milford, C.	187	Poughkeepfie, N. Y.	180
New-Milford, Me.	538	Powhatan c. h. Va.	310
Newport, R. I.	292	Prince Edward c. h. Va.	358
Newport, D.	31	Princefs-Ann, Md.	378
Newport Bridge, G.	959	Princeton, N. J.	42
Newtown, N. Y.	250	Princeton, N. C.	419
NEW-YORK city, N. Y.	-30	Prospect, Me.	602
Nixonton, N. C.	468	PROVIDENCE, R. I.	
Norfolk, Va	389		291
Northampton, Ms.	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Queen Ann's, Md.	1.141
Northampton c. h. Va.	270	Quincy, Ms.	360
	239 587	control in the second s	304
Norridgeworth, Me. Northumberland, P.		RALEIGH, N. C.	448
	124		585
North Warmouth Me	317	Randolph c. h. N. C. Reading P	
North-Yarmouth, Me.	483	Reading, P. Redbook N. V.	54
Norwalk, C.	149	Redhook, N. Y.	206
Norwich, C.	251	Rhinebeck, N. Y.	398
Nottingham, N. H.	437	Richland, N. C.	551
Nottingham, Md.	265	RICHMOND, Va.	208
Old Fast Columber M M		Richmond c. h. Va.	273
Old Fort Schuyler, N. Y.	364	Richmond c. h. N. C.	563
Old-Town, Md.	213	Ridgefield, C.	IQI
Onondaigua, N. Y.	422	Rockaway, N. J.	123
Drangeburg, S. C.	721	Rockford, N. C.	573
Orange c. h. Va.	273	Rockingham c. h. Va.	262
Orford, N. H.	395	Rockingham c. h. N. C.	536
Ouliout, N. Y.	325	Rocky Mount, Va.	433
Owega, N. Y.	284	Rome, N.Y.	376
Oxford Ac. N. Y.	395	RUTLAND, Vt.	359
		Komney, Va.	242
Painted Poft, N. Y.	230		
Paffamaquoddy, Me.	728	Sagg-Harbour, N. Y.	202
Peekskill, N. Y.	145	St. Leonard's Md.	186
Pendleton c. h. S. C.	801	St. Mary's, G.	3054
Penobicot, or Caftine, Me.	606	St. Tammany's, Va.	389
Peterborough, N. H.	366	Salem, Ms.	365
Peterfburg, P.	313	Salem, N. J.	37
Petersburg, Va.	303	Salem, N. C.	534
Petersburg, G.	836	Salifbury, Md.	163
PHILADELPHIA, P.	and the second	Salifbury, N. C.	567
Pinkneyville, S. C.	716	Sampion c. h. N. C.	543
Pifcataway, Md.	178	Sandwich, Ms.	411
Pittfburg, P.	303	Sanford, Me.	447
Pittafield, Ms.	299	Sayannah, G.	925

Sawyer's Fe Saybrook, (Scotland Ni Schenectad) Scipio, N. Sharpfburg Sheffield, M Shepherdftu Shippenfbu Shrewfburj Smithfield Smithfield Smithtowr Snowhill, Somerfet, Southamp Sparta, N . Spartan c Springfiel Springfiel Stamford Statefburg Staunten Stevenfbi Stockbri Stoningt Strafburg Stratford Suffield, Suffolk, Sullivan Sumner Suffex c Sunbury Sunbury Sweedfb Sweet S Taneyt Tappal Tarbo Taunto Thoma Tower TREN Trent Troy Unior Unior Upper Urbai

Vaffa Verg Vien Wal Sawyer's Ferry, N. C. Saybrook, C, Scotland Neck, N. C. Schenectady, N.Y. Scipio, N. Y. Sharpfburg, Md, Sheffield, Ms. Shepherdftown, Va, Shippenfburg, P. Shrewfbury, N. J. Smithfield, Va. Smithfield, N. C. Smithtown, N. Y. Snowhill, Md Somerfet, Ms. Southampton c. h. Va, Sparta, N. J. Spartan c. h. S. C. Springfield, Ms. Springfield, K. Stamford, C. Statefburg, S, C, Staunton, Va. Stevensburg, Va, Stockbridge, Ms. Stonington, C, Strafburg, Va, Stratford, C. Suffield, C. Suffolk, Va, Şullivan, Me. Sumner, S. C. Suffex c. h. N. J. Sunbury, P. Sunbury, G. Sweed(borough, N. J. Sweet Springs, Va. Taneyton, Md. Tappahannock, V Tarborough, N. C. Taunton, Ms. Thomaston, Me. Todds, Va. Tower Hill, R. I. Trenton, Me. TRENTON, N. J. Trenton, N. C. Troy, N. Y.

8

78

6

5

3

3

4

9

0

0

4

70

0

8

8

2

9

2,

ş

Ŕ

P

8

5

45

8

R.

8

3

3 E

5

35

9

L

B

ş

+ > >

1

ľ

3

1

à

Union-Town, P. Union, N. Y. Upper Marlborough, Md. Urbanna, Va.

Vaffalborough, Me. Vergennes, Vt. Vienna, Md. Waldoborough, Me. [619]

Miles.	news and the second second second	Miles.
482	Wallingford, C.	195
219	Walpole, N. H.	530
\$96	Wardfbridge, N. Y.	11.6
281	Warminster, Va.	375
461	Warren, Me.	557
181	Warren, R. I.	305
257	Warren, Va.	326
\$78	Warrenton, N. C.	390
146	Warwick, Md.	57
79	WASHINGTON city,	144
\$64	Washington, P.	325
473	Washington, K.	709 :
347	Washington, N. C.	460
1 58	Washington, G.	SIZ
311	Waterbury, Me.	456
399	Waynefborough, N. C.	498
117	Waynefborough, G.	800
746	Wells, Me.	44r
250	Wefterley, R. I.	
729	Weftfield, Ms.	
139	Weft-Liberty, Va.	348
663	Westminster, Vt.	. 329
287	Westmoreland c. h. Va.	289
200	Weathersfield, C.	218
249	Wheeling, Va.	363
251	Whiteftown, N. Y.	368
210	Wilkes, N. C.	612
169	Wikefbarre, P.	118
232	Williamfborough, N. C	
386	Williamsburg, N. Y.	288
645	Williamfburg, Va.	338
	Williamsport, Md.	155
108	Williamston, N. C.	444
122	WILMINGTON, D.	28
974	Wilmington, N. C.	600
20	Winchendon, Ms.	370
380	Winchefter, Va.	192
	Windham, C.	253
121	Windfor, Vt. Windfor, N. C.	255
263	Winnfborough, S. C.	481
420	Winflow, Me.	708
312		. 559
564 283		529
282	TTT: C C A	434 525
633		70
	TT7 11 NT T	9
30 521		223
271		26
-/-	Worcetter, Ms.	299
327	XX7	289
340	ST1	454
162		
291	77 1 77	427
-).	Yonkers, N.Y.	114
551		42 I
407	FF 1 (77) FF	350
1 50	York, P.	
54		EXPLANATION

E.	XPLANATION.
Me. for	Maine
N. H.	New-Hampfhire
Vt.	Vermont
Ms.	Maffachufetts
R. I.	Rhode-Ifland
€.	Connecticut
N.Y.	New- York
N. J.	New-Jerfey
P.	Pennfylvania
N. T.	North Weftern Territory
D.	Delaware
Md.	Maryland
Va.	Virginia
K.	Kentuky
N.C.	North-Carolina
T	Tenneffee
S. C.	South-Carolina
G.	Georgia
Ptk.	Potowmack
C. R.	Crofs Roads
c. h.	Court-Houfe
1	1

RATES of POSTAGE for Single Letters.

18 12 1		Miles.	Cts.
Any diftance	not exceeding	30	6
Over 30 and	not exceeding	60	8
Over 60	do.	100	10
Over 100	do.	150	121
Over 150	do.	200	15
Over 200	do.	250	17
Over 250	do.	350	20
Over 350	do.	450	22
Over 450			25

SHIP LETTERS received by private fhips, are rated at 4 cents each, and if they are forwarded by poft, with the addition of the ordinary rates of land poftage.

Ship Letters paffing in packet-boats or veffels provided by the United States, are rated as follow :

Single Letters at	8
Double at	16

Triple, or Packets, at 24 But at prefent there are no fuch public packets-boats.

RATES of POSTAGE of News-Papers.

Each paper carried not over } r too miles r Over 100 miles r

Cts.

But if carried to any post-office in the State in which it is printed, whatever be the diffance the rate is

MAGAZINES and PAMPHLETS are rated by the fheet.

Cts.

Cts.

Carried not over 50 miles, per freet x Over 50 and not over 100 do. 12 Any greater diftance 2

OBSERVATIONS.

When poitages are charged too high, fuch as a fingle letter charged as double, an abatement of the poitage will be made, if the letter or packet is opened in the prefence of the Poit-Master or his letter carrier, but not otherwise.

Letters must be delivered at the offices of Boston, New-York, Philadelphia and Baltimore, one hour before the time fixed for the departure of the mail, and at other offices half an hour, or they will he until the next post.

Letter-carriers are employed at large poft-towns, who deliver letters at the refidence of individuals; they are entitled to two cents for each letter or packet which they deliver, in addition to the poftage. Any perfon may, however, receive his letters at the poft-office, on giving the poft-mafter a written direction to that purpofe.

Postages of letters or packets may be paid in advance at the office where the letter is entered to be conveyed by post, or they may be fent unpaid at the writer's choice. Postages must always be paid before delivering of the letter.

Post-masters are required to be very cautious in delivering letters, there being in fome towns feveral perfons of the fame name; the directions fhould be particular in fuch cafes.

The direction should always mention the State, and generally the county in which the place is fituated; for there are places of the same name in several of the States, and in some States places of the states, and in some States places of the same name in different counties. As in Pennsylvania there are three places called Hanover; one in York county where a post-office is kept, one in Dauphin, and the other in Luzerne county.

When a letter is defined to a place where no poll-office is kept, the nearest poll office should be mentioned. If the place place is not of ed that the the letter by p fhould be ex poftage fhou the letter is

When let or Nova-Sci United State nication by paid in adv letter is en Vermont, i Maine, in When let

veyed bey paid as fa letters are post-mass ters by th

The po or other the conveyed fends or the No fta

> carrier m excepting for the ov lating to whom a conveyat When

rider, he letter, i

> The f frank th directed Prefider

place is not on apoft-road, and it is wifhed that the poft mafter thould forward the letter by private conveyance, that wifh fhould be expressed on the letter, and the postage should be paid at the office where the letter is entered.

When letters are defined for Canada or Nova-Scotia, between which and the United States there is a regular communication by poft, the poltage must be paid in advance at the office where the letter is entered, fo far as Burlington, Vermont, in one instance, and Brewers, Maine, in the other instance.

When letters are fent by post to be conveyed beyond fea, the postage must be paid as far as the post-office where the letters are intended to be shipped. The post-master there will forward such letters by the first conveyance.

The post-office does not infure money or other things fent by post; it is always conveyed at the risk of the perfon who fends or requires it to be fent.

No ftage owner, or driver, or common carrier may carry letters on a poff-road, excepting only fuch letters as may be for the owner of fuch conveyance and relating to the fame, or to the perfon to whom any package or bundle in fuch conveyance is addreffed.

When letters are delivered by a postrider, he is entitled to two cents for each letter, in addition to the postage.

FREE LETTERS.

The following perfons have a right to frank their own letters, and receive those directed to them free of poltage: The Prefident and Vice-Prefident of the

United States, Secretary of State, Secretary of the Treasury, Secretary at War, Post-Master General, Comptroller, Regifter and Auditor of the Treafury of the United States, Commiffioner of the Revenue, Purveyor, Accomptant of the War-Office, and Affiftant Poft-Mafter General; the Members of the Senate and House of Representatives of the United States, and the Secretary of the Senate and Clerk of the Houfe of Reprefentatives, during their actual at-tendance on Congress, and twenty days after the close of the feffion, when their letters do not exceed two ounces in weight, and the Deputy Post-Masters, when their letters do not exceed half an ounce in weight. No perfon may frank other letters than his own. If letters are inclosed to either of the description of officers above named for a perfon who has not the privilege of franking, he must return the letter to the post-office, marking upon the letter the place from whence it came, that the postmaster may charge postage thereon.

The diffances in the Table are taken chiefly from the information of Congress, and of Poft-Malters living on the routes a and it is prefumed that they are pretty generally accurate.

ABRAHAM BRADLEY, JUN. Clerk in the General Polt-Office, Philadelphia.

November 2, 1796.

Note. The diffances are calculated by the poft route on which the mails are ufually carried.

STATEMENT

STATEMENT OF THE CLAIMS UPON THE GEORGIA WESTERN TERRITORY.

SCIDC

1 2502 142967

when he work we had

minister of the sublicity of

f 622 1

A SUMMARY STATEMENT of the Claims of the State of Georgia, and of the United States, to the GEORGIA WESTERN TERRI-TORY; and of the Arguments adduced by the Purchafers of a part of this Territory, to invalidate thefe claims; particularly to fuch parts as are covered by their purchafes; collected and ftated with impartiality from various authentic printed manufcript documents.

[The following is referred to at the close of the article Georgia Western Territory; which fee.]

1. THE State of Georgia fay, that "the unappropriated territory," ufually confidered as within the limits of the State of Georgia, or the track of country new diffinguifhed by the name of the Georgia Weffern Territory, is their property, and that they have "not only the right of pre-emption, but also of exercifing all territorial rights." 1. Becaufe, by the 2d and 9th articles of the confederation of 1781, the territory within the limits of each of the United States is confirmed and guaranteed to each of them respectively. 2. Becaufe the boundaties of Georgia, as established by the treaty of Paris, of 1783, and by the convention of Beaufort of 1787, include this territory; and the 6th article of the Federal Confitution, by the fpirit and meaning of it, confirms these limits. And, 3dly, Becaufe the United States, by accepting a cellion from N. Carolina, of her Weffern Territory. To this claim of Georgia the purchafers accede; upon this ground the purchafers refted the validity of their claim.

But the State of Georgia now reclaims that part of her Western Territory fold according to the act of her legislature, of Jan. 7, 1795, alledging that the act authorifing the fale, is contrary to the 4th article of the Constitution of the United States; repugnant to the 16th and 17th sections of the first article of the constitution of Georgia, and was moreover obtained by means of "fraud, atrocious speculation, corruption, and collusion." Hence, by an act passed Feb. 13, 1796, the above act of Jan. 7, 1795, was "declared null and void, and the grants, rights, and claims, deduced from it, annulled, and rendered void and of no effect."⁺

In answer to the above flated claim of Georgia, it is contended by the purchafers, r. That the repealing law of Georgia is merely void, and leaves the title of the purchafers where it found it. If corruption, they fay, did exift in the legiflature which made the fale (which is however flrenuoully denied) it is very queftionable whether it can ever be alleged, as a contract cannot be repealed, like other acts of legiflation; and as the fupreme power of a State, as fuch, cannot be accountable to any other conflictud authority; for that implies a fuperior tribunal. By this, however, is not meant that the wrong done cannot be individually profecuted for corruption, though the State may be bound by the fales. If the allegation were, fay they, that the legiflature were deceived by the purchafers, the grant, like that of an individual, unfairly obtained, would be void on proof of the fraud : but for a legiflature to allege its own criminality and corruption, to avoid its own grant.

• Such are the grounds of claim alledged by Georgia to her Weftern Territory, in her Act of Jan. 7th, 1795. Other and ftronger ground feems to have been taken by the purchafers and their agents, which will be feen in the fequel of this ftatement.

+ Act of do. Feb. 13, 1796.

fame and a the grant, weigh the tion, triat by a jury. amination and void. the depofi and under It is al might be it ; yet th and livin verted ; lands, ha With against t pear to h fertion W the Unic of legifla peculiar the othe part of of unfai traventi II.] ground ferted, the pro heads" nies, al of the bmits (Thi all the alfo to much the lar ceding the be is thei quenc words nies a pleasu lands tribes diftur terati to gr objee anoth 25 () after

And

1

grant, is t

grant, is truly novel; and, in point of principle, there is no difference between the fame and a preceding legiflature. But if corruption of this kind can make void the grant, at leaft it ought to be proved; and that too in a court competent to weigh the evidence; and decide on the fact: in other words, it is a judiciary queftion, triable only in a judiciary court, and being a quefition of fact, must be tried by a jury. The legiflature, therefore, having no authority in this cafe, this examination and decifion can be confidered no otherwife than as mere usurpation, and void. And perhaps in justice to the purchasters, it ought to be added, that the depositions taken by the committee of the legiflature (though taken ex parte, and under a strong bias of party) do not contain much clear evidence of fraud.

It is also faid by the purchafers that even if there had been fraud, and that fraud might be alledged to destroy the title of the original purchafers who were privy to it; yet that innocent perfons having purchafed, utterly unacquainted with the facts, and living in remote parts of the United States, their title could never be controverted; that it was enough for them to know that a legislative act, granting the lands, had passed; and that they were ignorant of any fraudulent practices.

111

۲I.

of

i as

ity

ry;

lly

of

leir

ex-

on-

) is

ia-

in-

ral

ly,

nd

the

old

112-

ted

U -

US

16,

ls,

tle

if.

ef-

er

al.

e-

a-

nt, d :

NR

It,

a

rs

With regard to the allegation in the repealing act of Georgia, that fales were againft the confitution of the United States, and that of Georgia, it does not appear to have been treated as having any foundation; it has been called a naked affertion without any reafoning to fupport it. It has been faid that every State in the Union, having unappropriated lands, has difpored of them through the medium of legislative acts, and their validity has never been queftioned; though there is no peculiar difference in this refpect between the conflictution of Georgia and thole of the other States. In fhort, it feems to be generally agreed among the informed part of the community, that, whether Georgia had caule of complaint on account of unfairnefs in the fales, or not, the repealing law must be confiered as a "contravention of the first principles of natural juffice and policy," and void.

II. The claim of the United States deferves more particular attention. Various grounds have been taken to fupport this. It has been intimated, rather than afferted, in a Report of the Committee of the Senate of the United States, † that by the proclamation of the Britifh King, of Oct. 7, 1763, all lands lying weft of the heads of the rivers which fall into the Atlantic Ocean, were taken from the colonies, and fo remained with American Independence, and then became the property of the aggregate body politic of the United States, as they were not within the hmits of any particular States.

This, it is faid by the purchafers, is bold ground, and is oppofed not only to all the measures and opinions in Britain and America, while we were colonies, but also to the whole course of arrangements fince our independence. It proves too much to prove any thing. The argument deftroys itfelf; for if this be true, all the lands ceded to the United States by Carolina, Virginia, and every other State ceding western lands, belonged to the United States without ceffion. Some of the beft counties of Virginia now belong to them ; the Connecticut Referved Land, is theirs; the whole States of Kentucky and Tenneffee are theirs : The confeguences, fay they, are too wild to fuffer the principle to be admitted. Nor do the words of the proclamation warrant the confiruction. The Governors of the colonies are thereby only forbidden, " for the prefent, and until the King's further pleasure should be known, to grant warrants of survey, or pais patents for those lands."I And the reason is given by the Proclamation, viz. That the several tribes of Indians living under the king's protection, "fould not be molefted or diffurbed in the poffeffion of their hunting grounds." Initead of a permanent alteration of the boundaries of the colonies, a temporary prohibition to the Governors to grant those western lands, is alone to be found in the Proclamation; and the object, viz. peace with, and justice towards, the Indians, required no more. And another fact feems to put this matter paft all doubt ; the boundaries of the colonies. as expressed in the commiffions of the several Governors, were uniformly the same after the proclamation as before.

Others,

* See "The cafe of the Georgia fales on the Miffifippi, confidered" by Mr. Harper. And Mr. Hamilton's opinion on this cafe, printed at the clofe of this pamphlet. † See this printed report. ‡ See the proclamation. Others, in fupport of the claim of the United States, have faid, that the original charter of Georgia did not include the lands lying fouth of a line projected due well from the head of the most fouthern ftream of the Alatamaha river :--that this ffream is the Oakmulgee river, and that its most fouthern head is probably about lat. 33, 30. N. It is further faid, that no act of the British government ever enlarged the colony beyond its original chartered limits, except the Proclamation of 7th Oct. 2763; and that this annexes the lands between Alatamaha and St. Mary, no further weft than their heads;--therefore it is concluded that the whole weftern counting diamed by Georgia, except fo much thereof as lies north of a due weft line from the head of the Oakmulgee, never was within the colony of Georgia.

To this it is answered, by the advocates for the title of Georgia, that the charter of Carolina, granted in 1662, extended that country as far fouth as the 31ft deee of N. lat. and as far weft as the Weftern Ocean. That after the division of Carolina into two colonies, S. Carolina had the fame fouthern and weftern limits .-That the furrender of the charter by the proprietors of Carolina, only reftored the property to the crown, but did not annihilate the colony, which is evident from a royal Governor being immediately appointed, who, by his commiffion, is made " Governor of our colony of S. Carolina," without any fpecific boundaries ; which meant a tract of country bounded as under the proprietary government, or it meant nothing.-That on the 9th of June, 1732, the colony of Georgia was carved out of S. Carolina; but all lands belonging to S. Carolina, fhall continue to belong there, except that which was contained in the charter of Georgia; and of course the land lying fouth of the fouth line of Georgia, as far as the 31st degree of lat. fill belonged to S. Carofina, which is evident from common fenfe, as well as from the fact that the Governor of S. Carolina made grants of lands fouth of the colony of Georgia in 1763; which, though highly offensive to the board of trade, were at length admitted to be legitimate. It is further faid, that the State of S. Caro lina, in 1788, by folemn legiflative act, ceded to Georgia all her right to the lands in queftion, by ratifying the articles of the Convention of Beaufort, agreed upon between the States of S. Carolina and Georgia; and that the lands became thereby unqueftionably the property of Georgia.

Other answers have been made to this ground of claim by the United States; fuch as that the true intent and meaning of the Proclamation of 1763, was to annex the land in question to Georgia, and that this was confidered as the fast by the British government; and if the communication from Mr. George Chalmers, the certifying officer of the board of trade, to the Attorney-General of the United States, is to be relied on as an authority, this is true. It has also been answered, that the Oakmulgee is not the most fouthern stream of the Alatamaha, but Phenhalloway's Creek, which heads in lat. 31 mprth; fo that the whole of this land was strictly within the original chartered limits of Georgia.

Other advocates for the claim of the United States, have faid, that at leaft this claim is good from the 31ft degree of lat. as far north as a line projected due caft from the confluence of the Miflitippi and Yazoo rivers.

The foundation of this affertion is this. The board of trade, in 1764, reprefented to the king, that it was expedient to extend Weft-Florida as far northward as the above mentioned line, and advired that a proclamation might iffue for that purpole. No fuch proclamation however, was made; but feveral fubfequent commiffions to the Governors of Weft Florida, bounded the colony of Weft Florida, northward by that line; and in this flate the matter refted until the independence of the United States. Hence it is argued that this land, being a part of Weft-Florida in 1783, when the bounds of the United States were fettled by treaty with Great-Britain, could not belong to Georgia; but being within no particular State, it became the property of the United States.

To this the purcaiers have answered. That the proclamation of 7th of October, 2763, was a folemn public act, and established the output of West.

It appears by a manufcript map, in the office of the Secretary at War, taken under the authority of the United States, that Phenhalloway's Creek forks at a fmall diffance from its entrance into the Alatamaha: and that each fream runs about *thirty miles* from its head to the fork, the head of the fouthern itream being about the most northerly part of the 3st degree of latitude. Florida a inferior in why no p expedienc the comm as a temp founded to the bo of the toy confider for no re United S which ha day on v bounds, nations, Other apply to chafers a been im cognized Brita The ger blifhed, pendent the bou within been me tion of land as United allegia Span and the an equi nations withou of our Pinckn States, of an e his rep as a pi been a obtain Spain if the The acquie to bar pinci establi who h witho much and tl has be miffio Geor

Florida at the gaft degree of lat. and that the commission of a Governory being inferior in folemnity and publicity, could not abrogate it .- That the reafon why no proclamation was made, probably was, that the supposed fact on which the expediency of the alteration was predicated, was not known to exift; and that in the commiffions themfelves are words leading to a belief that it was confidered only as a temporary arrangement. The fast is, fay they, that this matter was wholly founded on a grois mifreprefentation of the Governor of Florida, who reprefented to the board of trade, and they to the king, that the 31ft degree of lat, was fourth of the town of Mobille. It is nearly certain that the British government did not confider this as a permanent alteration on the northern boundary of W. Florida; for no reason can be given why, in the peace of 1783, they should cede to the United States, without any equivalent, fo great and valuable a part of W. Florida, which had never joined in the revolution; efpecially confidering that on the fame day on which our treasy with Britsin bears date, the ceded W. Florida, without bounds, to Spain; thus on the fame day ceding the fame territory to two different nations, if it was then a part of W. Florida. the Dested

Other objections have been urged against the claim of the United States, which apply to all the grounds of claim above mentioned. It has been faid by the purchalers and their agents, that the most folemn acts of the three nations who have been immediately interested in the question, have, for a long course of years, recognized the title of Georgia, viz. Britain, Spain, and the United States.

Britain, as has been mentioned, recognized this title, by the peace of 1783. The general principle on which the boundaries of the United States were then effablifted, was, that the former thirteen colonies were to be acknowledged as Independent States by Britain ; and confequently the bounds of the colonies were to be the bounds of the States. It cannot be pretended, that the land in question was within any other colony than that of Georgia or South Carolina : and, as has been mentioned, South-Carolina has ceded all her right to Georgia by the convention of Beaufort, 1787; and it is incredible that Britain should then confider the land as part of Weft-Florida; for then, without motive or realon, the gave to the United States the belt part of a colony which had cholen to remain under her allegiance.

Spain has recognized the title of Georgia by the late treaty made between her and the United States; for if the land was, in 1783, a part of Florida, Spain had an equal right to it with the United States ; Great Britain having ceded it to both nations on the fame day. But Spain has given up all claim to the United States without any equivalent. This was done on the explicit representation on the part of our government, first by Messrs. Carmichael and Short, and afterwards by Mr. Pinckney, under express instructions from the Supreme Executive of the United States, to claim the land as a part of Georgia ; and these instructions were the refult of an elaborate inquiry by Mr. Jefferfon, then Secretary of State, as appears by his report to the Executive on the subject. Indeed, Spain never claimed the land as a part of Weft-Florida, but fet up a frivolous claim by conqueft. And it has been added, that as the ceffion of this country from Spain by the rate treaty, was obtained by a representation from the United States, that it was a part of Georgia, Spain is not in honour bound by this article of the treaty, if the fact was not for if the land did indeed belong to her own province of Weft-Florida.

The Government of the United States, it is faid, has for a long courfe of years acquiefced in, and by many public acts acknowledged the title of Georgia, fo as to bar all claim, even if the title of the United States were otherwise valid. As a principle to govern in this cafe it is flated, that in courts of equity it has been eftablished, " that the true owner of land shall be bound by a sale of a stranger who has no title, if the owner fuffer the fale to go on by an innocent purchaser, without giving notice of his title when he has it in his power; and that the cafe is much ftronger against the owner when he has given a colour of title to the feller, and thus helped to deceive the purchafer." As facts failing within this principle it has been stated, 1. That the government of the United States instructed their commiffioners for making the peace of \$783, to claim this land as belonging to Georgia, and this appears by the Journals of Congress, in the fullett manner. Rr 2. That

rged)A. furun-IOM lardearoš .---the ma lade hich eant out ong urfe lat. rom lony vere are inds pon reby tes; an-7 the the lited ered, henland this : caft preward that :omrida. ence Veftwith

inal

due

this

out

ober Veft_ er the

tate.

mits ad to : 31tt s. That attempts were made by the United States to obtain a ceffion of this land from Georgia, and a confideration offered for it, without any intimation that the United States had a claim. 3. That the convention of Beaufort, by which the conflicting claims of S. Carolina and Georgia were amicably fettled, was conducted under the aufpices of the United States; the queffion having been fubmitted to a court appointed by Congrefs to try it, according to a provision in the former confederation of the United States. 4. That in 1789, the government of the United States flated to Spain, as the ground of the claim of the American government, that this territory belonged to Georgia by virtue of her charter and the proclamation of 1763. 5. That in the negociation which preceded the late treaty between the United States and Spain, Meffirs. Carmichael and Short, American commissioners, by express infructions from the Supreme Executive of the United States, afferted the fame thing as the ground of the claim of the American government; and that even after the existing fales of this territory, and after the fame had been officially communicated by the government of Georgia to the Prefident of the United States, and by him laid before Congres, Mr. Pinckney, our late envoy to the court of Spain, who negociated the late treaty expressly declared, in his official communication, that the claim of the United States was founded on the fact, that this country was a part of Georgia, and this too purfuant to express infructions from the American Executive.

These have been urged as public acts of the American government, giving strong colour of title to Georgia. Others of acquiescence in her title by the United States have been added. Such as the filence of the general government when, in 1783, Georgia passed a legislative act, declaring her title to this country, and taking measures to settle it. Also, when in 2785, Georgia erected part of this territory into a county by the name of Bourbon, and appointed Magistrates there, and provided for the further settlement of it; and also, when, in 1789, Georgia passed an act for the falle of the now controverted lands to certain companies, who after failed of complying with the terms of payment. It has been faid, by the purchasers and their agents, That it would be indeli-

It has been faid, by the purchasers and their agents, That it would be indelicate, at leaft, for the government of the United States to hold fuch language as this : " It is true, we represented to Great-Britain that this land belonged to Georgia, and obtained a ceffion from her on this ground.—It is true, that we claimed it of Spain on the fame ground for years together, and at laft on that ground obtained a relinquifhment of her claim; but we falified, and they were cheated.— It is true, we claimed it in behalf of Georgia; but having obtained it, we will keep it ourfelves.—It is true, we declared by many public and folemn acts, that the title of Georgia was good, and thereby induced a great number of American citizens to purchase and rifk all their property in the enterprize; but we will now affert our claim, and deftroy them for being weak enough to believe us : and it is true, it has long heen fettled, that the principles of juffice forbid individuals from doing thus : but we are above the rules of inffice."

doing thus : but we are above the rules of juffice." The foregoing is as clear and impartial a view of the conflicting claims to the Georgia Weffern Territory, as the author could collect from the various documents in his poffellion. These documents do not furnish an answer to the foregoing reafoning against the claim of the United States; nothing, except what has been (alledged, having appeared on that fide of the question.

2. 57

(a) A set and a set of the set

F. G.Z. Dies, D. Oren, C. Lin, "A "A space of the weak to be provided and the second "Subsequence as a second to be second or a second seco

n nhi contra alter materia alter al altera adam kinna politication, attati ta a

6) manufar og hall

S

T is we the Un tants; and But the underflood rica to be and that

tens hi and

se ands rains

to bere seller to

barter para

and calcul increase of wealth and of courfe, The hi

to Americ number h make the was made the many that in f *evil*, it perfons p ing to A to 800,0 At the General

were not little do Suppofin years-t 1630, th

At th

-but a Americ

FACTS

627] percho ampliane do histolucio en di tras anti dan investi a do de malanti de al secondaria

FACTS AND CALCULATIONS RESPECTING THE MANTINA I WAR ANTINA

1 and

benetic serie buildende demandelse anderen

a introduction of the state of

war no in this to be

the (A dride William)

sections, manual warming (50

Artachionid . Du

金融 (

POPULATION AND TERRITORY OF THE

UNITED STATES OF AMERICA.

SECTION L.

OF THE POPULATION OF THE UNITED STATES.

T is well known that, about a century ago, the country which now composes the United States of America, contained but a few thousand civilized inhabi-

tants; and that now, the fame country contains four or five millions. But the cautes of this valt increase of numbers feem not to be equally well understood. It is believed that many perfons still suppose the population of America to be chiefly indebted for its growth to emigrations from other countries ; and that it must become stationary when they cease to take place. Some facts and calculations will be here fet down, to afcertain the ratio of the natural increase of the inhabitants of America, and to shew that the great progress of wealth and population in that country is chiefly derived from internal caules, and of courfe, lefs liable to interruption from without.

The higheft estimate that is recollected of the number of inhabitants removing to America in any one year, fuppoies the number to be 10,000 (1). If the fame number had removed every year fince the first fettlement of the country, it would make the whole about 1,600,000. But it is to be remarked that this effimate was made for a period when emigrations were unufually numerous-that during the many years of war which have taken place, they have been very few; and that in former years, when the number of emigranis/ was complained of as an evil, it was not reckoned to high (2). We may therefore suppose that 5,000 perfons per annum is a liberal allowance for the average number of perfons removing to America fince its first fettlement. This, in the year 1790, would amount to 800,000 perfons.

At the end of 1790, and beginning of 1791, there were enumerated in the General Cenfus, the number of 3.993,412 inhabitants (3). As some places were not enumerated at all, and from others no return was made, there can be little doubt but the adual number then was fomething more than 4,000,060. Supposing them to have increased, fo as to double their numbers once in twenty years-then, in the feveral preceding periods of twenty years, fince the year 1630, the numbers would ftand thus :-

At the end of 1790 4,000,000	At the end of 1690 125,000
\$770 2,000,000	
1,000,000	1650 31,250
1730 500,000	1630 15,625
1710 250,000	

-but as this laft date reaches back to the infancy of the first fettlements in North America, it can hardly be supposed that they contained fo many as 15,000 inha-

> (1) Cooper's Inform. (2) Douglas's Summary, Vol. II. p. 326. (3) See the Cenfus of 1791. R r z

bitants.

CTS

land

the

the

- f3u d to

mer

the

ern-

the

eaty

lican Dited

ernfame

nt of

IVOY 1 his

a the

prefs

rong tates

783, king

itory

pro-

d an

ailed

deli-

(e as

ed to

it we

ound

d. ---

: will

that

rican

now

it is

from

o the

nents ١

rea-

nal

bitants. It follows, therefore, that they must have doubled their numbers oftener than once in twenty years; that is, that they must have increased faster than at the rate of 5 per cent. compounding the increase with the principal at the end of every twenty years.

628 1

To determine how far this ratio of increase is justified by other facts, some pains have been taken to afcertain and compare the number of inhabitants at four different periods, viz. 1750, 1774, 1782, and 1791. The following estimate has been formed of those numbers about the year 1750.

(1) 1751, Maffachuletts contained	200,000
Connecticut,	100,000
(1) Rhode Ifland,	30,000-
New Hampfhire,	24,000.
(3) In 1756, one account fays New York contained - 100,000	
(4) Another, 96,775	A. 91250
In 1750, fuppose therefore it contained	90,000
In 1745, New Jeffey contained 61,403	
In 1750, fuppole therefore	66.000
(5) In 1760, in Penniylvania the Taxables were 31,667	
In 1793, Ditto 91,177,	

By a conjectural proportion, therefore, the number of Taxables in 1791 must have been about \$6,000. Then as \$6,000 is to 434,373 (the number of inbabitants in 1791) to is 31,667 to 1 59,945, the number of 1760, which fubftracted from the Cenfus of 1791, gives an increase of 274,428 for thirty years, of which one-third part, or 91,379 is the mean increase for ten years; but supposing the increase for the ten years previous to. 1760, to have been but 70,000, there will remain for the whole number in 1750,

Delaware .- Suppose in the fame proportion to its prefent. numbers as Pennfylvania,

(6) 1751, or 1752, in Maryland the Taxables were -Taxables are underflood to be all white men above 16 years 40,000 of age, and all black perions from 16 to 60-fay then. that to every

100 white males above 16, there are 100 ditto below ditto, and 200 white females of all ages-200 blacks from 16 to 60, and

200 of all other ages

\$ 300

1999

124.1

Sec.

(No

346,23

BRANK CONTRACTOR

(7) Total 800 of which 300 are Taxables; then, as 300 is to 800, fo is 40,000 to - 105,666 But as in those States the number of blacks is to that of whites only as 10 to 11, deduct therefore 1-22d part of tun. this number

House and an inclusion of the second s		102, 54.5
(8) 1750 in Virginia, Tytheables were Then by the fame rule as before, as 300 is to 800, fo	100,000	
100,000 10	18 266,666	mit syn i'r
Deduct in the fame proportion as for Maryland	12,141	
Sale way of as		254, 45

Carried over 969,259

(1) Doug. Sum. Vol. II. p. 180-Smith's Hift: of New York, p. 225. (2) Morfe's Geog. fays, that in 1748 Rhode Ifland contained 34, 128. (3) Smith, p. 225. (4) Morfe's Geog. (5) Coxe's View, p. 481. (6) Douglas, Vol. II. p. 363. (7) Jefferior, p. 129. (8). Jefferton's Notes, p. 122.

The

89,945

12,224

the diff A I F 1 Ŀ 1 Whic aftoni Fre 1790

ever leaft

giver it ha

and

iner l

The m

mile nin a

200 1155

About 1 Being abo the manne or in the r cent. A num, is d per cent. for the fa The ne

An ab nial Affa exceed 2

a compoi

1790, is while th cion that

bable, th

feveral §

rule for 1784, 1

Armed i

fuppofe

have ex

In 17

This

dent

1

S

Brought over The numbers of the following States must be fupplied in a great measure, from conjecture :

1710, In North Carolina, the whole number of

ener

n at d of

ains

dif-

has

,000

,000 ,000.

,000.

,000

000

945

224

194.5

\$45

,259

afe's

rfe's 129.

The

inhabitants 17 50, Suppose one-third of the increase fince 1710 South Carolina .- Suppose in the fame ratio to its

prefent numbers as North Carolina Georgia .- The fettlement of it then but lately commenced : fuppofe it had _____

About 1750 .- Total of inhabitants in the Thirteen Colonies - 1,179,259

1790 .- Whole number in the Thirteen States - 4,000,000 Being about 3.4-ro times the number of 1750. If this increase be computed in the manner of fimple intereft, it affords a ratio of 5.98, or very nearly fix per cent. or in the manner of compound intereft of between three and three and a half per cent. Any number increased in the compound ratio of three per cent. per annum, is doubled in about twenty-three years and a half, and at three and a half per cent. in about twenty years ; that is, it is equal to five per cent. fimple increase for the fame period.

The next period which will be adverted to, is the year 1774-

An able and ingenious author (1) who was very thoroughly converfant in Colo nial Affairs, fuppoles, that at that time, the whole number of Colonits could not exceed 2, 141, 307. The difference between this number and that of 1750, gives a compound increase of hardly three per cent, while the subsequent ratio, up to 1790, is more than four per cent, per annum. These different rates of increase, while they confirm the general principles here contended for, may lead to a fulpicion that Governor Pownal's calculation is too low; or what perhaps is more probable, that the foregoing effimate for 1750 is fomewhat too high.

In 1782, a return was made to Congress of the inhabitants in the feveral States ; by which there appeared to be

2,389,300

10 k

10.000

\$20.00

\$0,000

10,000

This return was then believed to be accurate, for it was made the rule for the affeffment of public burthens among the States. But in 1784, the accuracy of it was attacked by Lord Sheffield, (2) who affirmed it was too great. If it was in fact as much too great as he supposed, then the increase of numbers from that time to 1790 must have exceeded all credibility. But allowing it to have been accurate, the difference between the number of 1790 4,000,000 And this number of 1782 2,389,300

1.610.700 From this deduct for emigrants, viz. 10,000 emigrants per annum, for nine years. 90,000 Increase of ditto at five per cent. for four years and one half

20,050 110,250

Natural increase in nine years 1, 580,450 Which calculated upon the number of inhabitants returned in 1782, gives the aftonifling natural increase of 6.97, or very nearly seven per cent. per annum.

From these flatements compared with each other, it appears that in the year 2790, the actual increase of inhabitants in the United States, beyond the number ever imported, muft have been 3,200,000, or after the most liberal allowances, at least three millions. That the whole rate of increase upon the numbers at any given period has been more than five per cent, and deducting for emigrations, that it has been equal to about five per cent. for any twenty years fucceflively, or three and a half per cent. compound increase for any period that has yet elapied.

(1) Pownal's Memorial, p. 62.

Is

(1) Obfervations, &c. p. 139.

But it may be expected, that no inference as to the future population of America can be derived from these facts, because as the country becomes more thickly fettled, the increase will be flower. We have an opportunity of examining what

weight the objection poffeffes. The Eastern States are the most thickly inhabited. The greater part of the emigrations from them, have been either to other States in New England, or to the State of New York.

In 1750, New England and New York together contained

444,000 1,348,942

In 1790, Ditto Having more than trebled their numbers in 40 years, and increased, during all that period, at the rate of more than five per cent upon their original number; and in the compound ratio of nearly three per cent. And as many more perfons have emigrated from these States than have come into them from abroad, all this, and fomething more, is their natural increase.

In 1750, Maffachuletts contained thirty-two perfons, and in

1790, about fixty perfons to each fouare mile.

In 1750, Connecticut contained twenty perfons, and in

1790, about fifty perfons to the fquare mile.

14 14 1

In 1750, Rhode Ifland contained about twenty-three, and in

1790, about fifty-two inhabitants per square mile; so that befides the numerous emigrants these States have fent forth, they have more than doubled their numbers in forty years, and nearly trebled them fince they contained twenty perfons to each fquare mile.

(1) Mr. Jefferson has taken some pains to prove that the inhabitants of Virginia double their numbers once in twenty-feven years and a quarter. He also proves, by an ingenious calculation, that

(1) In 1782, the numbers in Virginia were 567,614

In 1790, the fame country (part of which made the State of Kentucky) contained - 821,287

Giving an increase of 4100, or very nearly five per cent. and doubling their numbers, not in twenty-feven years and a quarter, as Mr. Jefferson endeavoured to prove, but in lefs than twenty one years.

Virginia (exclusive of Kentucky) added about 180,000 to its numbers, between 1782 and 1790, the period when the numerous emigrations to Kentucky cauled fo great a drain upon its population.

(3) In 1780, the number of Militia, weft of Blue Ridge, in Virginia, was 11,440, which, multiplied by four, gives for the number of in-

habitants 45,760 In 1790, the fame county contained 151,235 Those counties having more than trebled their numbers in ten years.

. It is to be observed that these facts (and many more of a fimilar tendency might be adduced) are drawn from the former and least prosperous state of America, and from periods which were either absolutely those of public calamity, or,/at heit, were not those of national prosperity; yet, it is apprehended, they softciently prove that the inhabitants of the United States increase at least as fast as at the compound ratio of three and a half p.r cent.; that should foreigners ceale to remove there, it would not prevent more than one-fifteenth, or one-twentieth of this increase ; and that there are as yet no fymptoms of this rate of increase being at all diminished by the crowded population of the country. The United States must contain 18,000,000 of people to equal the average of New England, and 55,000,000 to equal the rate of population in Maffachufetts and Connecticut.

The causes of this great increase of population, so peculiar to America, might he readily and fatistactorily explained, by a review of the flate of manners, fociety, property, and government in that country .- The discuffion would, however, be too long, and is therefore foreborn,

(1) Jefferson's Notes, p. 123.

(2) Ib. p. 128. (3) Ib. 131.

Calculations

IT ap the Unit and that The t Mr. Hu computa

are con

nearly

which

portion

not fo.

whene

about

family

averag

incline Uniter

It is

Calculatio

A

Incre

Incr

Inci

Inc

Inc

Inc

In

631

of the present Number of Inhabitants in the Calculations United States. 000,004 000

그는 아이들에 집에 집에 가지 않는 것 같아요. 이 집에서 가지 않는 것 같아요. 이 것에서 가슴에 가슴에 가지 않는 것이 가지 않는 것 같아요. 이 것 같아요. 이 것 같아요. 이 것 같아요. 이 가 있는 것 같아요. 이 있는 것 이 있는 것 같아요. 이 있는 것 같아요. 이 있는 것 같아요. 이 있는 것 이 있는 것 같아요. 이 있는 것 이 없는 것 이 있는 것 같아요. 이 있는 것 이 있는 것 이 있는 것 이 있는 것 이 없는 것 이 있는 것 이 없는 것 이 않는 것 이 않는 것 이 않는 것 이 않는 것 이 없는 것 이 없는 것 이 않는 않는 것 이 않는 것 이 않는 않는 것 이 않는 않는 않는 것 이 않는 않는 않는 않는 않는 않는 않는 않는 않는 않 이 않는		
At the end of the year 1790	-	4,000,000
1791		4,140,000
Increase z year at 3½ per cent.	Ξ	4,284,900 149,971
Increase 1 year 3 f per cent.	_	4,434,871
Increase s year 31 per cent.	-	4,589,981 160,649
Increase 1 year 3 ¹ / ₂ per cent.	_	4,7 50,630 166,172
Increase 1 year 31 per cent.	_	4,916,802
1797	-	5,088,890

SECTION II.

OF THE TERRITORY OF THE UNITED STATES l

IT appears from the flatements in Sec. I. that the increase of the inhabitants of the United States, is in the compound ratio of about three and a half per cent. and that at the end of the year 1797, their number is about 5,088,890 The territory of the United States has been usually reckoned after

Mr. Hutchins, as equal to a tract of one thousand miles square. This computation, though probably too large, will be followed. a tot see man

From which, deduct for water	· · · · · · · · · · · · · · · · · · ·	8/2: 	51,000,000
And there remains of land Of this quantity it is known th	at about		589,000,000

are contained in the territory north weft of the river Ohio, and is nearly all of it uninhabited .--- Of the - 369,000,000 which remain, it is difficult to form any just estimate as to the proportion of the inhabited and appropriated parts, to those which are not fo.

It is, however, thought reasonable to suppose that, in America, whenever any part of the country has acquired a population of about twenty perfons to the fquare mile, or 150 or 200 acres to a family, that then, the land must there have acquired nearly the average price of cultivated land, and the furplus population will incline to emigrate. Affuming this as a rule, the lands in the United States, fo occupied, would in 1796 be -

Remains

V.T. St. Mitchell 1 57,337,664

inter .

Parices

121.29/28

is she at

211,662,336 a great

meckly

vhat

the r to 000 942 all er ; fons his,

the iled ned inia res, 514 187 leir

red

be-

:ky

vas

60

35 tht ca, at ffias

ale

of

ng

tes

nd

tht

6-

w.

225

Brought over -211,662,336 a great part of which is, in fact, inhabited in some degree, the remainder is owned by States and individuals, and much of it not for fale. Add for the north-weft territory.

220,000,000

Year.

End of 17 Increase

Increase

Increafe

Increase

Increase

Increase

Increafe

Increase

Increafe

Increase

Increaf

Lands of all kinds yet to be fettled 431,662,336 The increase of the population of the United States, calculated upon the principles established in Sec. I. will, if applied to the settlement of new lands, at the rate of twenty perfons to each fquare mile, or thirty-two acres each perfon, occupy the lands of the United States in the proportion, and at the periods following, viz.

632

Year.		Acres of land occu- pied by the increase.	Acres of land remain- ing unoccupied.
1796 Vear's increate		5,506,816	431,662,336
# 1 cal * mercale #797	5,088,890	66,863,712	426,155,520
1807	7,178,381	94,317,856	359,291,808
1817	10,125,814	133,044,704	264,973,952
	14,283,461	133,044,704	131,929,248
About 1834.	\$8,406,1 50	-31,929,240	000,000,000

SECTION III.

OF THE VALUE OF LANDS.

IT has usually been supposed, that the great rife which has taken place in the value of American lands, has been produced by caprice or accident, and not derived from any fixed and certain fources of profit; but it is allowed, that this rife in their value has been conftant, and very great, ever ince the first fettlement of the Colonies, and during periods which were very far from being those of public profperity. Without taking advantage, however, of the prefent favourable ftate of public affairs, it will be attempted to fnew, by facts, and calculations drawn from the former, and least prosperous state of the country, that the great increase in the value of lands is derived from fixed and neceflary caufes existing in the country, and is, in a great measure, fubject to firict-calculation.

The following calculation is founded upon these principles, viz.

aft. It is supposed to be proved in Sec. 1, that the inhabitants of the United States increase in the compound ratio of three and a half per cent.

Ed. It appears from the fame Section, that at the end of the year 1796, the number of inhabitants in the United States, is about 4,916,802.

gd. It appears from the flatements in Sec. 11. that the quantity of vacant lands in the United States is about 431,662,336 acres.

4th. Of confequence, there are, in the United States, 1139 perfons to each 100,000 acres of new lands.

sth. It is supposed that new lands, on an average, are worth one dollar per acre; and that lands inhabited at the rate of twenty perfons to the fquare mile, are worth fourteen dollars, or three guineas per stre.

The following flatement, therefore, fnews the increasing value of any 100,000 acres (taken equal to the average) upon the principle that the increase of 1139 perfons may be applied to the fettlement of it, and that as much land as they fettle, at the sate of twenty perfons to the iquare mile, is worth fourteen dollars per acre.

Year

REMANNE

[633] the State

PLEY AVE

trainth

10 46.2

562,336

Sent a Martin

200,000

562,336 he prin-, at the occupy ng, viz.

nain-d.

e in the not de-this rife ment of public sle flate i drawn increstie g in the

United

ie num-

it lands to each

er acre ; ile, are

f 1139 hey fet-lars per

Year

Year. of in tar	Number oc of inhabi- tants, o	Lands Ann. occupied by the increale of inhabi- tants. Acres. 1280	Value of 100,000 Acres cach year.		Value per Acre.		e fan terlii	
			Dollars) 100,000 16,640	Dols. 1	Crs.	l. o	s. 4	d. 6
1797 Increafe	1179 41	1312	116,640 17,056	ĩ	16	•	- 5	2
1798 Increafe	1220 42	1344	133,696 17,472	1.	33	Ô.	Ś	11
Increase 1799	1262 44	1408	151,168	1. 1. 1.	51	٥	6	93
1800 Increase	1 306 46	1472	169,472 19,136	1. A.	69	•	7	4
1801 Increase	1352 47	i 504	188,608	i	88	•	8	5
1802 Increafe	i 399 49	1 568	208,160 20,384		:08	•	9	41
1803 Increafe	1448 51	1631	228,544	• 2	28	•	10	3
1804 Increase	1499 52	1664	249,760 21,632	2	49	•	11	2
1805 Increase	1551 54	1728	271,393 22,464	2	73	•	12	.2
1806 Increase	1605 56	1792	293,856 23,296	2	93	0	13	12
	1.5	1995 T. S.	317,152	3	17	•	14	3
1807 1808 1809	1661 1719 1779	1856	341,280	3	41 66	00	15	45
1810	1841 2186	1984	392,030	35	92 35	0	17	70
1820	2596	13,120	706,110	7	06	1	11	98
1825 1830 1834	3083 3661 4255	15,584 18,784 19,008	1,152,894	11	52	23	12	10 0

I

It is not intended by this flatement to convey the idea that the rife in the value of any particular tract of land will be in the exact proportion here mentioned. In many important inflances in America it has been greater, in others perhaps lefs.

many important inflances in America it has been greater, in others perhaps lefs. But it is intended to thew, that the increase in the value of American lands is, in its nature, like that of compound interest; and that affuming the very moderate ratio of three and a half per cent, for the increase of inhabitants, the general rife in the value of property refulting therefrom, is very far above the profit of capital in any of the ordinary ways of employing it. And it is to be remembered, that thefe flatements being matters of arithmetical calculation, are not to be disproved, ex-cept by disproving fome of the premiles on which they are founded. It ought also to be remarked, that the flatement is burthened by the inclusion of all the lands in the United States, and of course, of many millions which are not now for fals, and will not begin to be fettled for many years. It is therefore

not now for fale, and will not begin to be fettled for many years. It is therefore much too moderate, if confidered with respect to the lands now in market. The loweft price at which Congress fells the lands, they offer for fale at two

dollars per acr

The altonishingly low prices of lands in America, have hitherto been occasioned by the want of capital to inveft in them. Only a few European capitalifts have lately underflood the fubject : and nobody is ignorant of the immenie advantages they have derived from it. The great increase of capital in America, together with the investments which Europeans are beginning to make in lands, will pro-bably raife their value far above the rate at which it has increased at any former period.

Such a conclusion refults, not unnaturally, from another confideration, which is this :- The price of any commodity whatever, may be raifed in two ways-either by diminishing the quantity for fale, or by increasing the demand. But the extenfion of fettlements, and the increase of wealth and population, operate at once, in both these ways, upon American lands; not only diminishing the quantity for fale, but increasing the means, and the eligibility of making further purchases and fettlements. Late

FINIS

ERNIG

4633

R. S. L. H

見い見ば

建合理学

TOT

45 281

Conserver.

からまたたわ

10 1

pes-

Bassis and

Sarah States

She 1 m.s.

2 APRIL

2040

182.00

A. B. C.

出方件工

1 4 12

NEX STREET

Children and

"Tate !

That Y

-----2:21

家里

0.2362

- horas 1333

E C

Barris and

学生学校

Ranges

96

1963

that they

Sec. 25

DE MARK

11 202 132

他, 他, 他, 他,

やわた ぎまや

5 2

1 annie

油

Carlo and a

36 Service .

1111111111

R. A. Hart Martin

3.

121

Sec.

12

DIRECTIONS TO THE BINDER

FOR PLACING THE MAPS.

ob 30

MAP of NORTH-AMERICA to front the Title. — of the NORTHERN STATES to front New-England. — of the SOUTHERN STATES to front Southern States. — of SOUTH-AMERICA to front America. — of the WEST-INDIES to front West-Indies. — of ISLANDS in the PACIFIC OCEAN to front Tierra Austral, &cc, — of GEORGIA WESTERN TERRITORY to front Georgia Western Territory,

This day is published,

RITORY, VERMON

OF

wo

her

ro-

ner

The Sixth Edition, corrected, and greatly enlarged, with a copious Index, in One large Volume 4to. Price 21. 28. in Boards, with the Maps, forming a complete Atlas, bound feparate, of

A NEW SYSTEM

MODERN GEOGRAPHY;

Geographical, Historical, and Commercial Grammar,

PRESENT STATE OF THE SEVERAL KINGDOMS OF THE WORLD.

By WILLIAM GUTHRIE, ESQ.

The Aftronomical Part

By JAMES FERGUSON, F.R.S.

Frinted for C. DILLY, in the Poultry; and G. G. and J. ROBINSON, Paternofter-row.

The prefent publication, comprehending hiftory as well as geography, the variety and magnitude of fome recent transactions, have rendered numerous alterations or additions requisite in the hiftorical part.

To make room for these important insertions, great pains have been employed in abridging diffusiveness, and lopping off redundancy; yet the new materials lately brought to light have unavoidably swelled this edition far beyond the last, and much more beyond all preceding editions.

N. B. A few copies are printed of this work on a fuperfine wove royal paper. Price 2l. 125. 6d. in boards.

The Maps, comprehending a complete Atlas, are now fold feparate. Price 155, bound.

This Day is Published, by J. STOCKDALE, Piccadilly.

In one large Volume, Quarto, containing upwards of 700 pages of close Letter-prefs, and illustrated with 25 maps, price 11, 6s. in boards.

THE

HISTORY OF AM OR. A それからちまうとう

A VIEW OF THE PRESENT SITUATION

OF THE

UNITED STATES OF AMERICA.

CONTAINING

Aftronomical Geography; Geographical Definitions; Difcovery and Ge-neral Defeription of America and the United States; of their Boundaries, Mountains, Lakes, Bays, and Rivers; Natural Hiftory, Pro-ductions, Population, Government, Agriculture, Commerce, Manu-factures, and Hiftory. A concife Account of the War, and of the im-portant Events which have fucceeded; Biographical Anecdotes of eminent Men ; with a particular Defcription of

KENTUCKY, THE WESTERN TERRITORY, VERMONT.

AND

THE TENNESSEE GOVERNMENT:

Of their Extent, Civil Divisions, Chief Towns, Climates, Soils, Trade, Character, Conftitutions, Courts of Juffice, Colleges, Academies, Religion, Iflands, Indians, Literary and Humane Societies, Springs, 'Curiolities, Hiffories, &c.

TO WHICH IS ADDED,

AN ABRIDGMENT OF THE GEOGRAPHY

OF THE BRITISH, SPANISH, FRENCH, AND DUTCH DOMINIONS

AT H VE

AMERICA AND THE WEST INDIES :

ALSO OF

EUROPE, ASIA, AND AFRICA, WITH THE NEW DISCOVERIES.

By JEDIDIAH MORSE, A.M.

The above Work is now publishing in 25 Shilling Numbers.

Alfo the Substance of the above, in one very large Volume, Octavo, price 6s. 6d. in Boards; which may be had in Six Numbers, at One Shil-ling each.

Likewife, by the fame Author, for the Instruction of Youth, in one Volume, 12mo, with Maps, price 38. 6d. bound,

ELEMENTS OF GEOGRAPHY.