

**CIHM
Microfiche
Series
(Monographs)**

**ICMH
Collection de
microfiches
(monographies)**



Canadian Institute for Historical Microreproductions / Institut canadien de microreproductions historiques

© 1997

Technical and Bibliographic Notes / Notes techniques et bibliographiques

The Institute has attempted to obtain the best original copy available for filming. Features of this copy which may be bibliographically unique, which may alter any of the images in the reproduction, or which may significantly change the usual method of filming are checked below.

- Coloured covers / Couverture de couleur
- Covers damaged / Couverture endommagée
- Covers restored and/or laminated / Couverture restaurée et/ou pelliculée
- Cover title missing / Le titre de couverture manque
- Coloured maps / Cartes géographiques en couleur
- Coloured ink (i.e. other than blue or black) / Encre de couleur (i.e. autre que bleue ou noire)
- Coloured plates and/or illustrations / Planches et/ou illustrations en couleur
- Bound with other material / Relié avec d'autres documents
- Only edition available / Seule édition disponible
- Tight binding may cause shadows or distortion along interior margin / La reliure serrée peut causer de l'ombre ou de la distorsion le long de la marge intérieure.
- Blank leaves added during restorations may appear within the text. Whenever possible, these have been omitted from filming / Il se peut que certaines pages blanches ajoutées lors d'une restauration apparaissent dans le texte, mais, lorsque cela était possible, ces pages n'ont pas été filmées.
- Additional comments / Commentaires supplémentaires:

L'Institut a microfilmé le meilleur exemplaire qu'il lui a été possible de se procurer. Les détails de cet exemplaire qui sont peut-être uniques du point de vue bibliographique, qui peuvent modifier une image reproduite, ou qui peuvent exiger une modification dans la méthode normale de filmage sont indiqués ci-dessous.

- Coloured pages / Pages de couleur
- Pages damaged / Pages endommagées
- Pages restored and/or laminated / Pages restaurées et/ou pelliculées
- Pages discoloured, stained or foxed / Pages décolorées, tachetées ou piquées
- Pages detached / Pages détachées
- Showthrough / Transparence
- Quality of print varies / Qualité inégale de l'impression
- Includes supplementary material / Comprend du matériel supplémentaire
- Pages wholly or partially obscured by errata slips, tissues, etc., have been refilmed to ensure the best possible image / Les pages totalement ou partiellement obscurcies par un feuillet d'errata, une pelure, etc., ont été filmées à nouveau de façon à obtenir la meilleure image possible.
- Opposing pages with varying colouration or discolourations are filmed twice to ensure the best possible image / Les pages s'opposant ayant des colorations variables ou des décolorations sont filmées deux fois afin d'obtenir la meilleure image possible.

This item is filmed at the reduction ratio checked below / Ce document est filmé au taux de réduction indiqué ci-dessous.

10x	12x	14x	16x	18x	20x	22x	24x	26x	28x	30x	32x
-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----

**The copy filmed here has been reproduced thanks
to the generosity of:**



National Library of Canada

**The images appearing here are the best quality
possible considering the condition and legibility
of the original copy and in keeping with the
filming contract specifications.**

**Original copies in printed paper covers are filmed
beginning with the front cover and ending on
the last page with a printed or illustrated impres-
sion, or the back cover when appropriate. All
other original copies are filmed beginning on the
first page with a printed or illustrated impres-
sion, and ending on the last page with a printed
or illustrated impression.**

**The last recorded frame on each microfiche
shall contain the symbol → (meaning "CON-
TINUED"), or the symbol ▽ (meaning "END"),
whichever applies.**

**Maps, plates, charts, etc., may be filmed at
different reduction ratios. Those too large to be
entirely included in one exposure are filmed
beginning in the upper left hand corner, left to
right and top to bottom, as many frames as
required. The following diagrams illustrate the
method:**



L'exemplaire filmé fut reproduit grâce à la générosité de:



Bibliothèque nationale du Canada

Les images suivantes ont été reproduites avec le plus grand soin, compte tenu de la condition et de la netteté de l'exemplaire filmé, et en conformité avec les conditions du contrat de filmage.

Les exemplaires origineux dont la couverture en papier est imprimée sont filmés en commençant par le premier plat et en terminent soit par la dernière page qui comporte une empreinte d'impression ou d'illustration, soit par le second plat, selon le cas. Tous les autres exemplaires origineux sont filmés en commençant par la première page qui comporte une empreinte d'impression ou d'illustration et en terminant par la dernière page qui comporte une telle empreinte.


Un des symboles suivants apparaîtra sur la dernière image de chaque microfiche, selon le cas: le symbole → signifie "A SUIVRE", le symbole ▽ signifie "FIN".

Les cartes, planches, tableaux, etc., peuvent être filmés à des taux de réduction différents. Lorsque le document est trop grand pour être reproduit en un seul cliché, il est filmé à partir de l'angle supérieur gauche, de gauche à droite, et de haut en bas, en prenant le nombre d'images nécessaire. Les diagrammes suivants illustrent la méthode.



MICROCOPY RESOLUTION TEST CHART

(ANSI and ISO TEST CHART No. 2)



APPLIED IMAGE Inc.

1653 East Main Street
Rochester, New York 14609 USA
(716) 482-0300 - Phone
(716) 288-5989 - Fax

DO YOU KNOW YOUR WEEDS?

BY
FAITH FYLES, B.A.,
Assistant Botanist.



FIG. 1.

- (a) Young plant of Canada Thistle (*Cirsium arvense* (L.) Scop.)
(b) Older plant, showing root and rootstocks with underground buds.
(c) Flower heads and escaping seeds. Drawn by F. Fyles.

As weeds and tares (darnel) have increasingly occupied the attention of agriculturists from early days, so the ground space occupied by weeds has steadily and surely increased. This is not entirely due to the extent of new land cleared and cultivated, nor is it due entirely to neglect, nor to a lack of literature on the subject of their eradication, as every agricultural pamphlet, paper, magazine and text-book has its chapter of advice on weeds.

It is knowledge of the weed itself that is wanting. No man who once recognizes a weed and its injuriousness would allow it to remain on his land undisturbed for a season. When the progressive farmer knows the weed, he will use every means at his disposal to exterminate it.

To know a weed, one must be able to recognize it in every stage of its development, to understand what harm it does and to know at what period of its growth it should be destroyed.

DOMINION EXPERIMENTAL FARMS.

J. H. GRISDALE, B.Agr.,
Director.

H. T. GÜSSOW,
Dominion Botanist.

EXHIBITION CIRCULAR No. 45.

(Revised January, 1916.)

There are two classes of weeds: those which are of definite duration, as annuals and biennials, and those of indefinite duration, as perennials. Among the annuals growing in the West are green foxtail, wild oats, wild buckwheat, redroot pigweed, tumbleweed, Russian pigweed, Russian thistle, cow cockle, purple cockle, ball mustard, false flax, hare's-ear-mustard, stinkweed, wild mustard, tumbling mustard, stickseed, dodder, great ragweed and many others. Among the biennials are squirrel-tail grass (erroneously called "foxtail" in the West), grey tansy mustard, green tansy mustard, biennial wormwood, etc. The perennials include sweet grass, couch grass, veined dock, broad-leaved pepper-grass, prairie rose, great willow herb, blue lettuce, skeleton weed, perennial sowthistle, Canada thistle, and others.

Eradication of Annuals and Biennials.

Annuals have only one means of reproduction, that is by seeds, and for this reason they yield an enormous quantity. One single plant of tumbling mustard will produce 1,500,000 seeds. Think what it means to allow one of these plants to mature its seed, to stand still until dry and be blown by the wind until its shallow foothold snaps or gives way altogether, sending the whole plant across the prairie to scatter its 1,500,000 seeds along the way! The second year there will be 1,500,000 new plants, and the third year 1,500,000 times 1,500,000! What a saving to cut one plant off before it seeds itself! What an advantage to know the plant before it flowers! Russian thistle, tumbleweed and stinkweed (French weed) are equally troublesome, and scatter their seeds in a similar manner. Land may be freed from annual weeds by any method which will kill them before they flower. The seeds already in the soil should be made to germinate, and the young seedlings destroyed by repeated cultivation.

Biennials should be treated as annuals when in the first year's growth, that is, they should be destroyed when in the form of a rosette or mat. If of the second year's growth, they should be cut off or spudded below the crown to prevent the formation of flowering shoots and seeds.

Method of Eradicating Perennials.

All perennials are capable of reproducing themselves by new shoots and roots as well as by seeds. There are two things then to be remembered in the eradication of perennials. First, they must not be allowed to seed themselves; secondly, the roots and rootstocks must be destroyed. Reproduction by means of seeds can easily be prevented by mowing the plants as soon as the flower buds appear; but the destruction of the underground growth is easy only when the weed is scarce or where digging the roots up and burning them is practical, that is, when the first patch is discovered and recognized as a pest. Thorough and persistent cultivation, which will destroy the green part of the plant, will, if repeatedly practised, starve the rootstocks to death. Shallow or deep ploughing, according to the nature of the plant, to bring the rootstocks to the surface of the soil where they may be gathered and destroyed, is most effective if properly carried out. On no account should any method be used which would result in scattering the rootstocks, and thus stimulating them to new growth.

The illustration of Canada Thistle will show the futility of cutting off the tops and leaving the rootstocks in the soil to send up new shoots. The rootstock possesses great vitality, and every inch with a bud on it is capable of producing a new plant; hence to cut the rootstocks up and leave them on the ground is worse than useless. If the plant is known in a young state as in Fig 1 (a), it may be very easily killed, but if it is allowed to live till it is six or seven weeks old, as in Fig. 1 (b), then the rootstocks must be considered. Other deep-rooted perennials with similar rootstocks are sweet grass, prairie rose, broad-leaved peppergrass, veined dock, white evening primrose,

3

poverty weed and perennial sowthistle. With all of these, deep ploughing is necessary, but shallow ploughing will do for couch grass, as its rootstocks are nearer the surface of the soil.



FIG. 2.

- (a) Broad-leaved peppergrass (*LEPIDIUM DRABA L.*) with seed pods.
- (b) Woody perennial rootstock.
- (c) Small portion of flowering branch.
- (d) Leaf from young plant.
- (e) Seed natural size and enlarged. Drawn by F. FALES.

Advent of New Weeds.

The difficulty of the weed problem would be considerably lessened if native weeds alone were to be combated, but the list of weed-immigrants is continually increasing. These new weeds are indifferently noticed until they have usurped our food-supplying land. How much more simple the weed question would be in the West if couch grass, wild oats, Russian thistle, perennial sowthistle, the (so-called) Canada thistle, and other introduced weeds had not been allowed to establish themselves. At the present time there is another new-comer, equally injurious, doing its best to gain such a footing that in another ten years or so its claims as a naturalized weed will be undisputed. This is the hoary cress or broad-leaved peppergrass (*Lepidium Draba L.*).

It was first reported in 1896 by Mr. David Macoun from Indian Head, Sask., and from Brandon, Man., by the late Dr. Fletcher in 1904 and 1905, as having been found on waste land on the side of a street. It has also been reported from Portage la Prairie, Man., and last August (1914) it was found in large patches on stubble land at Indian Head.

Unlike the other peppergrasses in Canada, it is a perennial with a deep, woody, underground rootstock, rendering it extremely difficult of eradication. The accompanying illustration will help you to recognize it more readily than a written description can do. The leaves on plants two or three years old are rather short, thick, minutely hairy and slightly toothed. On younger plants they are much longer, thinner

and more coarsely toothed. This characteristic together with the white flowers and short, broad seed pods will help you to distinguish it from other members of the mustard family. *Dig this plant up now, while it is possible to do so. Do not wait till the land is so possessed by the tough, woody rootstocks, that the plough will be turned aside much more readily by it than the couch grass.*

Send all specimens with which you are unfamiliar, or about which you want fuller information, to the Dominion Botanist, Central Experimental Farm, Ottawa.

Published by authority of Hon. MARTIN BURRELL, Minister of Agriculture, Ottawa, Ont.



